

C++ PROGRAMMING

*FROM PROBLEM ANALYSIS
TO PROGRAM DESIGN*

EDITION

5



D.S. Malik

C++ PROGRAMMING:

FROM PROBLEM ANALYSIS TO PROGRAM DESIGN

FIFTH EDITION

D.S. MALIK



 COURSE TECHNOLOGY
CENGAGE Learning™

Australia • Brazil • Japan • Korea • Mexico • Singapore • Spain • United Kingdom • United States

**C++ Programming: From Problem Analysis
to Program Design, Fifth Edition****D.S. Malik****Executive Editor:** Marie Lee**Acquisitions Editor:** Amy Jollymore**Senior Product Manager:** Alyssa Pratt**Editorial Assistant:** Zina Kresin**Content Project Manager:** Matthew
Hutchinson**Art Director:** Faith Brosnan**Print Buyer:** Julio Esperas**Cover Designer:** Roycroft Design/
www.roycroftdesign.com**Cover Photo:** © Guntmar Fritz/Masterfile**Proofreader:** Green Pen QA**Indexer:** Elizabeth Cunningham**Compositor:** Integra

© 2011 Course Technology, Cengage Learning
ALL RIGHTS RESERVED. No part of this work
covered by the copyright herein may be
reproduced, transmitted, stored or used in any
form or by any means graphic, electronic, or
mechanical, including but not limited to
photocopying, recording, scanning, digitizing,
taping, Web distribution, information
networks, or information storage and retrieval
systems, except as permitted under Section
107 or 108 of the 1976 United States Copyright
Act, without the prior written permission of
the publisher.

For product information and technology assistance, contact us at
Cengage Learning Customer & Sales Support, 1-800-354-9706
For permission to use material from this text or product, submit
all requests online at www.cengage.com/permissions

Further permissions questions can be emailed to
permissionrequest@cengage.com

Library of Congress Control Number: 2009942948

ISBN-13: 978-0-538-79808-2

ISBN-10: 0-538-79808-4

Course Technology20 Channel Center Street
Boston, MA 02210
USA

Some of the product names and company names used in this
book have been used for identification purposes only and may
be trademarks or registered trademarks of their respective
manufacturers and sellers.

Any fictional data related to persons or companies or URLs used
throughout this book is intended for instructional purposes only.
At the time this book was printed, any such data was fictional
and not belonging to any real persons or companies.

Course Technology, a part of Cengage Learning, reserves the
right to revise this publication and make changes from time to
time in its content without notice.

The programs in this book are for instructional purposes only.
They have been tested with care, but are not guaranteed
for any particular intent beyond educational purposes. The
author and the publisher do not offer any warranties or
representations, nor do they accept any liabilities with respect
to the programs.

Cengage Learning is a leading provider of customized
learning solutions with office locations around the globe,
including Singapore, the United Kingdom, Australia, Mexico,
Brazil and Japan. Locate your local office at:

www.cengage.com/global

Cengage Learning products are represented in Canada
by Nelson Education, Ltd.

To learn more about Course Technology, visit

www.cengage.com/coursetechnology

Purchase any of our products at your local college store or at
our preferred online store **www.CengageBrain.com**

TO

My Daughter

Shelly Malik

This page intentionally left blank



BRIEF CONTENTS

| | |
|----------------------------------------------------------------------------------------|-----|
| 1. An Overview of Computers and Programming Languages | 1 |
| 2. Basic Elements of C++ | 27 |
| 3. Input/Output | 117 |
| 4. Control Structures I (Selection) | 175 |
| 5. Control Structures II (Repetition) | 247 |
| 6. User-Defined Functions I | 319 |
| 7. User-Defined Functions II | 361 |
| 8. User-Defined Simple Data Types, Namespaces, and the <code>string</code> Type | 433 |
| 9. Arrays and Strings | 485 |
| 10. Applications of Arrays (Searching and Sorting) and the <code>vector</code> Type | 563 |
| 11. Records (<code>structs</code>) | 611 |
| 12. Classes and Data Abstraction | 649 |
| 13. Inheritance and Composition | 723 |
| 14. Pointers, Classes, Virtual Functions, and Abstract Classes | 793 |
| 15. Overloading and Templates | 861 |
| 16. Exception Handling | 951 |
| 17. Recursion | 991 |

| | |
|----------------------------------------------------------------------|------|
| 18. Linked Lists | 1023 |
| 19. Stacks and Queues | 1115 |
| APPENDIX A Reserved Words | 1215 |
| APPENDIX B Operator Precedence | 1217 |
| APPENDIX C Character Sets | 1219 |
| APPENDIX D Operator Overloading | 1223 |
| APPENDIX E Additional C++ Topics | 1225 |
| APPENDIX F Header Files | 1247 |
| APPENDIX G Memory Size on a System and Random Number Generator | 1257 |
| APPENDIX H Standard Template Library (STL) | 1259 |
| APPENDIX I Answers to Odd-Numbered Exercises | 1301 |
| INDEX | 1331 |



TABLE OF CONTENTS

Preface

xxvii

1

AN OVERVIEW OF COMPUTERS AND PROGRAMMING LANGUAGES

1

Introduction

2

A Brief Overview of the History of Computers

2

Elements of a Computer System

3

Hardware

4

Central Processing Unit and Main Memory

4

Input/Output Devices

5

Software

6

The Language of a Computer

6

The Evolution of Programming Languages

8

Processing a C++ Program

10

Programming with the Problem

Analysis–Coding–Execution Cycle

12

Programming Methodologies

20

Structured Programming

20

Object-Oriented Programming

20

ANSI/ISO Standard C++

22

Quick Review

22

Exercises

23

| | | |
|----------|----------------------------------------------------------|-----------|
| 2 | BASIC ELEMENTS OF C++ | 27 |
| | A C++ Program | 28 |
| | The Basics of a C++ Program | 31 |
| | Comments | 32 |
| | Special Symbols | 32 |
| | Reserved Words (Keywords) | 33 |
| | Identifiers | 33 |
| | Whitespaces | 34 |
| | Data Types | 35 |
| | Simple Data Types | 35 |
| | Floating-Point Data Types | 38 |
| | Arithmetic Operators and Operator Precedence | 39 |
| | Order of Precedence | 43 |
| | Expressions | 44 |
| | Mixed Expressions | 45 |
| | Type Conversion (Casting) | 47 |
| | string Type | 49 |
| | Input | 50 |
| | Allocating Memory with Constants and Variables | 50 |
| | Putting Data into Variables | 53 |
| | Assignment Statement | 53 |
| | Saving and Using the Value of an Expression | 56 |
| | Declaring and Initializing Variables | 57 |
| | Input (Read) Statement | 58 |
| | Variable Initialization | 61 |
| | Increment and Decrement Operators | 65 |
| | Output | 67 |
| | Preprocessor Directives | 75 |
| | namespace and Using cin and cout in a Program | 76 |
| | Using the string Data Type in a Program | 76 |
| | Creating a C++ Program | 77 |
| | Debugging: Understanding and Fixing Syntax Errors | 80 |

| | |
|--------------------------------------------|-----|
| Program Style and Form | 84 |
| Syntax | 84 |
| Use of Blanks | 85 |
| Use of Semicolons, Brackets, and Commas | 85 |
| Semantics | 85 |
| Naming Identifiers | 85 |
| Prompt Lines | 86 |
| Documentation | 87 |
| Form and Style | 87 |
| More on Assignment Statements | 89 |
| Programming Example: Convert Length | 91 |
| Programming Example: Make Change | 94 |
| Quick Review | 98 |
| Exercises | 100 |
| Programming Exercises | 109 |

3

INPUT/OUTPUT 117

| | |
|----------------------------------------------------------------------------------|-----|
| I/O Streams and Standard I/O Devices | 118 |
| <code>cin</code> and the Extraction Operator <code>>></code> | 119 |
| Using Predefined Functions in a Program | 124 |
| <code>cin</code> and the <code>get</code> Function | 127 |
| <code>cin</code> and the <code>ignore</code> Function | 128 |
| The <code>putback</code> and <code>peek</code> Functions | 130 |
| The Dot Notation between I/O Stream Variables and I/O Functions: A Precaution | 132 |
| Input Failure | 133 |
| The <code>clear</code> Function | 135 |
| Output and Formatting Output | 137 |
| <code>setprecision</code> Manipulator | 137 |
| <code>fixed</code> Manipulator | 138 |
| <code>showpoint</code> Manipulator | 139 |
| <code>setw</code> | 142 |

| | |
|----------------------------------------------------------------------------------------------|-----|
| Additional Output Formatting Tools | 144 |
| <code>setfill</code> Manipulator | 144 |
| <code>left</code> and <code>right</code> Manipulators | 146 |
| Input/Output and the <code>string</code> Type | 148 |
| Debugging: Understanding Logic Errors and Debugging with <code>cout</code> Statements | 149 |
| File Input/Output | 152 |
| Programming Example: Movie Tickets Sale and Donation to Charity | 156 |
| Programming Example: Student Grade | 162 |
| Quick Review | 165 |
| Exercises | 166 |
| Programming Exercises | 170 |

4

CONTROL STRUCTURES I(SELECTION) 175

| | |
|-----------------------------------------------------------------------------------------|-----|
| Control Structures | 176 |
| Relational Operators | 177 |
| Relational Operators and Simple Data Types | 178 |
| Comparing Characters | 179 |
| Relational Operators and the <code>string</code> Type | 180 |
| Logical (Boolean) Operators and Logical Expressions | 182 |
| Order of Precedence | 184 |
| <code>int</code> Data Type and Logical (Boolean) Expressions | 187 |
| <code>bool</code> Data Type and Logical (Boolean) Expressions | 188 |
| Selection: <code>if</code> and <code>if...else</code> | 188 |
| One-Way Selection | 189 |
| Two-Way Selection | 191 |
| Compound (Block of) Statements | 195 |
| Multiple Selections: Nested <code>if</code> | 195 |
| Comparing <code>if...else</code> Statements with a Series of <code>if</code> Statements | 198 |
| Short-Circuit Evaluation | 199 |

| | |
|--------------------------------------------------------------------|-----|
| Comparing Floating-Point Numbers for Equality: | |
| A Precaution | 200 |
| Associativity of Relational Operators: A Precaution | 201 |
| Avoiding Bugs by Avoiding Partially Understood | |
| Concepts and Techniques | 203 |
| Input Failure and the <code>if</code> Statement | 206 |
| Confusion between the Equality Operator (<code>==</code>) and | |
| the Assignment Operator (<code>=</code>) | 209 |
| Conditional Operator (<code>? :</code>) | 211 |
| Program Style and Form (Revisited): Indentation | 211 |
| Using Pseudocode to Develop, Test, and Debug a Program | 212 |
| <code>switch</code> Structures | 215 |
| Avoiding Bugs by Avoiding Partially Understood Concepts and | |
| Techniques (Revisited) | 221 |
| Terminating a Program with the <code>assert</code> Function | 223 |
| Programming Example: Cable Company Billing | 225 |
| Quick Review | 231 |
| Exercises | 232 |
| Programming Exercises | 241 |

5

CONTROL STRUCTURES II (REPETITION) 247

| | |
|----------------------------------------------------------|-----|
| Why Is Repetition Needed? | 248 |
| <code>while</code> Looping (Repetition) Structure | 249 |
| Designing <code>while</code> Loops | 251 |
| Case 1: Counter-Controlled <code>while</code> Loops | 252 |
| Case 2: Sentinel-Controlled <code>while</code> Loops | 255 |
| Case 3: Flag-Controlled <code>while</code> Loops | 259 |
| Case 4: EOF-Controlled <code>while</code> Loops | 263 |
| <code>eof</code> Function | 263 |
| More on Expressions in <code>while</code> Statements | 268 |
| Programming Example: Fibonacci Number | 269 |
| <code>for</code> Looping (Repetition) Structure | 273 |
| Programming Example: Classifying Numbers | 281 |

| | |
|--------------------------------------------------|-----|
| do...while Looping (Repetition) Structure | 284 |
| Choosing the Right Looping Structure | 289 |
| break and continue Statements | 289 |
| Nested Control Structures | 291 |
| Avoiding Bugs by Avoiding Patches | 296 |
| Debugging Loops | 299 |
| Quick Review | 300 |
| Exercises | 301 |
| Programming Exercises | 313 |

6

USER-DEFINED FUNCTIONS I 319

| | |
|---------------------------------------------|-----|
| Predefined Functions | 320 |
| User-Defined Functions | 324 |
| Value-Returning Functions | 324 |
| Syntax: Value-Returning Functions | 326 |
| Syntax: Formal Parameter List | 326 |
| Function Call | 326 |
| Syntax: Actual Parameter List | 327 |
| return Statement | 327 |
| Syntax: return Statement | 327 |
| Function Prototype | 331 |
| Syntax: Function Prototype | 332 |
| Value-Returning Functions: Some Peculiarity | 333 |
| More Examples of Value-Returning Functions | 335 |
| Flow of Execution | 340 |
| Programming Example: Largest Number | 341 |
| Programming Example: Cable Company | 343 |
| Quick Review | 349 |
| Exercises | 350 |
| Programming Exercises | 356 |

| | | |
|----------|-----------------------------------------------------------------------------------------|------------|
| 7 | USER-DEFINED FUNCTIONS II | 361 |
| | Void Functions | 362 |
| | Value Parameters | 367 |
| | Reference Variables as Parameters | 368 |
| | Value and Reference Parameters and Memory Allocation | 372 |
| | Reference Parameters and Value-Returning Functions | 382 |
| | Scope of an Identifier | 382 |
| | Global Variables, Named Constants, and Side Effects | 386 |
| | Static and Automatic Variables | 391 |
| | Debugging: Using Drivers and Stubs | 392 |
| | Function Overloading: An Introduction | 395 |
| | Functions with Default Parameters | 396 |
| | Programming Example: Classify Numbers | 399 |
| | Programming Example: Data Comparison | 404 |
| | Quick Review | 414 |
| | Exercises | 416 |
| | Programming Exercises | 424 |
| 8 | USER-DEFINED SIMPLE DATA TYPES, NAMESPACES, AND THE <code>string</code> TYPE | 433 |
| | Enumeration Type | 434 |
| | Declaring Variables | 436 |
| | Assignment | 436 |
| | Operations on Enumeration Types | 437 |
| | Relational Operators | 437 |
| | Input/Output of Enumeration Types | 438 |
| | Functions and Enumeration Types | 440 |
| | Declaring Variables When Defining the Enumeration Type | 442 |

| | |
|-------------------------------------------------------------------|-----|
| Anonymous Data Types | 442 |
| <code>typedef</code> Statement | 443 |
| Programming Example: The Game of Rock, Paper, and Scissors | 444 |
| Namespaces | 452 |
| <code>string</code> Type | 458 |
| Additional string Operations | 461 |
| Programming Example: Pig Latin Strings | 471 |
| Quick Review | 475 |
| Exercises | 477 |
| Programming Exercises | 481 |

9

ARRAYS AND STRINGS**485**

| | |
|-------------------------------------------------------|-----|
| Arrays | 487 |
| Accessing Array Components | 488 |
| Processing One-Dimensional Arrays | 491 |
| Array Index Out of Bounds | 494 |
| Array Initialization During Declaration | 495 |
| Partial Initialization of Arrays During Declaration | 496 |
| Some Restrictions on Array Processing | 496 |
| Arrays as Parameters to Functions | 497 |
| Constant Arrays as Formal Parameters | 498 |
| Base Address of an Array and Array in Computer Memory | 501 |
| Functions Cannot Return a Value of the Type Array | 503 |
| Integral Data Type and Array Indices | 506 |
| Other Ways to Declare Arrays | 507 |
| Searching an Array for a Specific Item | 507 |
| C-Strings (Character Arrays) | 510 |
| String Comparison | 512 |
| Reading and Writing Strings | 514 |
| String Input | 514 |
| String Output | 515 |

| | |
|-----------------------------------------------------------|-----|
| Specifying Input/Output Files at Execution Time | 516 |
| string Type and Input/Output Files | 516 |
| Parallel Arrays | 517 |
| Two- and Multidimensional Arrays | 518 |
| Accessing Array Components | 520 |
| Two-Dimensional Array Initialization During Declaration | 521 |
| Two-Dimensional Arrays and Enumeration Types | 521 |
| Initialization | 524 |
| Print | 525 |
| Input | 525 |
| Sum by Row | 525 |
| Sum by Column | 526 |
| Largest Element in Each Row and Each Column | 526 |
| Passing Two-Dimensional Arrays as Parameters to Functions | 527 |
| Arrays of Strings | 530 |
| Arrays of Strings and the string Type | 530 |
| Arrays of Strings and C-Strings (Character Arrays) | 530 |
| Another Way to Declare a Two-Dimensional Array | 531 |
| Multidimensional Arrays | 532 |
| Programming Example: Code Detection | 534 |
| Programming Example: Text Processing | 540 |
| Quick Review | 547 |
| Exercises | 548 |
| Programming Exercises | 558 |

10

APPLICATIONS OF ARRAYS (SEARCHING AND SORTING) AND THE `vector` TYPE

563

| | |
|------------------------|-----|
| List Processing | 564 |
| Searching | 564 |
| Bubble Sort | 565 |
| Selection Sort | 569 |
| Insertion Sort | 572 |
| Binary Search | 576 |

| | | |
|-----------|-------------------------------------------------|------------|
| | Performance of Binary Search | 580 |
| | vector Type (class) | 580 |
| | Programming Example: Election Results | 585 |
| | Quick Review | 601 |
| | Exercises | 603 |
| | Programming Exercises | 606 |
| 11 | RECORDS (structs) | 611 |
| | Records (structs) | 612 |
| | Accessing struct Members | 614 |
| | Assignment | 616 |
| | Comparison (Relational Operators) | 617 |
| | Input/Output | 618 |
| | struct Variables and Functions | 618 |
| | Arrays versus structs | 619 |
| | Arrays in structs | 620 |
| | structs in Arrays | 622 |
| | structs within a struct | 624 |
| | Programming Example: Sales Data Analysis | 628 |
| | Quick Review | 642 |
| | Exercises | 642 |
| | Programming Exercises | 645 |
| 12 | CLASSES AND DATA ABSTRACTION | 649 |
| | Classes | 650 |
| | Unified Modeling Language Class Diagrams | 654 |
| | Variable (Object) Declaration | 654 |
| | Accessing Class Members | 655 |
| | Built-in Operations on Classes | 656 |
| | Assignment Operator and Classes | 657 |
| | Class Scope | 657 |

| | |
|--------------------------------------------------------------|-----|
| Functions and Classes | 658 |
| Reference Parameters and Class Objects (Variables) | 658 |
| Implementation of Member Functions | 659 |
| Accessor and Mutator Functions | 664 |
| Order of public and private Members of a Class | 667 |
| Constructors | 669 |
| Invoking a Constructor | 671 |
| Invoking the Default Constructor | 671 |
| Invoking a Constructor with Parameters | 671 |
| Constructors and Default Parameters | 674 |
| Classes and Constructors: A Precaution | 674 |
| Arrays of Class Objects (Variables) and Constructors | 675 |
| Destructors | 677 |
| Data Abstraction, Classes, and Abstract Data Types | 678 |
| A struct Versus a class | 680 |
| Information Hiding | 681 |
| Executable Code | 685 |
| Static Members of a Class | 691 |
| Programming Example: Candy Machine | 697 |
| Quick Review | 711 |
| Exercises | 713 |
| Programming Exercises | 718 |

13

INHERITANCE AND COMPOSITION **723**

| | |
|---------------------------------------------------------------|-----|
| Inheritance | 724 |
| Redefining (Overriding) Member Functions of the Base Class | 727 |
| Constructors of Derived and Base Classes | 734 |
| Destructors in a Derived Class | 742 |
| Multiple Inclusions of a Header File | 743 |
| C++ Stream Classes | 744 |
| Protected Members of a Class | 746 |

| | |
|-------------------------------------------------------------------------------|-----|
| Inheritance as public , protected , or private | 746 |
| (Accessing protected Members in the Derived Class) | 747 |
| Composition (Aggregation) | 750 |
| Object-Oriented Design (OOD) and Object-Oriented Programming (OOP) | 755 |
| Identifying Classes, Objects, and Operations | 757 |
| Programming Example: Grade Report | 758 |
| Quick Review | 779 |
| Exercises | 780 |
| Programming Exercises | 787 |

14

POINTERS, CLASSES, VIRTUAL FUNCTIONS, AND ABSTRACT CLASSES **793**

| | |
|-------------------------------------------------|-----|
| Pointer Data Type and Pointer Variables | 794 |
| Declaring Pointer Variables | 794 |
| Address of Operator (&) | 795 |
| Dereferencing Operator (*) | 796 |
| Classes, Structs, and Pointer Variables | 800 |
| Initializing Pointer Variables | 803 |
| Dynamic Variables | 803 |
| Operator new | 804 |
| Operator delete | 805 |
| Operations on Pointer Variables | 807 |
| Dynamic Arrays | 809 |
| Functions and Pointers | 812 |
| Pointers and Function Return Values | 812 |
| Dynamic Two-Dimensional Arrays | 813 |
| Shallow versus Deep Copy and Pointers | 816 |
| Classes and Pointers: Some Peculiarities | 818 |
| Destructor | 818 |
| Assignment Operator | 820 |
| Copy Constructor | 821 |

| | |
|-----------------------------------------------------|-----|
| Inheritance, Pointers, and Virtual Functions | 828 |
| Classes and Virtual Destructors | 835 |
| Abstract Classes and Pure Virtual Functions | 835 |
| Address of Operator and Classes | 844 |
| Quick Review | 846 |
| Exercises | 849 |
| Programming Exercises | 857 |

| | | |
|-----------|---------------------------------------------------------------------|------------|
| 15 | OVERLOADING AND TEMPLATES | 861 |
| | Why Operator Overloading Is Needed | 862 |
| | Operator Overloading | 863 |
| | Syntax for Operator Functions | 864 |
| | Overloading an Operator: Some Restrictions | 864 |
| | Pointer <code>this</code> | 865 |
| | Friend Functions of Classes | 870 |
| | Operator Functions as Member Functions and Nonmember Functions | 873 |
| | Overloading Binary Operators | 876 |
| | Overloading the Stream Insertion (<<) and Extraction (>>) Operators | 882 |
| | Overloading the Assignment Operator (=) | 887 |
| | Overloading Unary Operators | 895 |
| | Operator Overloading: Member versus Nonmember | 901 |
| | Classes and Pointer Member Variables (Revisited) | 902 |
| | Operator Overloading: One Final Word | 902 |
| | Programming Example: Clock Type | 902 |
| | Programming Example: Complex Numbers | 911 |
| | Overloading the Array Index (Subscript) Operator ([]) | 916 |
| | Programming Example: Newstring | 918 |
| | Function Overloading | 924 |

| | |
|------------------------------|-----|
| Templates | 925 |
| Function Templates | 925 |
| Class Templates | 927 |
| Quick Review | 935 |
| Exercises | 937 |
| Programming Exercises | 942 |

16

EXCEPTION HANDLING 951

| | |
|---------------------------------------------|-----|
| Handling Exceptions within a Program | 952 |
| C++ Mechanisms of Exception Handling | 956 |
| try/catch Block | 956 |
| Using C++ Exception Classes | 963 |
| Creating Your Own Exception Classes | 967 |
| Rethrowing and Throwing an Exception | 973 |
| Exception-Handling Techniques | 978 |
| Terminate the Program | 978 |
| Fix the Error and Continue | 978 |
| Log the Error and Continue | 980 |
| Stack Unwinding | 980 |
| Quick Review | 984 |
| Exercises | 986 |
| Programming Exercises | 989 |

17

RECURSION 991

| | |
|----------------------------------------|------|
| Recursive Definitions | 992 |
| Direct and Indirect Recursion | 995 |
| Infinite Recursion | 995 |
| Problem Solving Using Recursion | 996 |
| Tower of Hanoi: Analysis | 1005 |
| Recursion or Iteration? | 1006 |

18

| | |
|------------------------------------------------------------------------|-------------|
| Programming Example: Converting a Number from Binary to Decimal | 1007 |
| Programming Example: Converting a Number from Decimal to Binary | 1011 |
| Quick Review | 1014 |
| Exercises | 1015 |
| Programming Exercises | 1018 |
| LINKED LISTS | 1023 |
| Linked Lists | 1024 |
| Linked Lists: Some Properties | 1025 |
| Deletion | 1031 |
| Building a Linked List | 1032 |
| Linked List as an ADT | 1037 |
| Structure of Linked List Nodes | 1038 |
| Member Variables of the <code>class linkedListType</code> | 1038 |
| Linked List Iterators | 1039 |
| Print the List | 1045 |
| Length of a List | 1045 |
| Retrieve the Data of the First Node | 1046 |
| Retrieve the Data of the Last Node | 1046 |
| Begin and End | 1046 |
| Copy the List | 1047 |
| Destructor | 1048 |
| Copy Constructor | 1048 |
| Overloading the Assignment Operator | 1049 |
| Unordered Linked Lists | 1049 |
| Search the List | 1050 |
| Insert the First Node | 1051 |
| Insert the Last Node | 1052 |
| Header File of the Unordered Linked List | 1057 |
| Ordered Linked Lists | 1058 |
| Search the List | 1059 |
| Insert a Node | 1060 |
| Insert First and Insert Last | 1064 |

| | |
|-------------------------------------------------------------------|------|
| Delete a Node | 1065 |
| Header File of the Ordered Linked List | 1066 |
| Print a Linked List in Reverse Order (Recursion Revisited) | 1069 |
| printList Reverse | 1071 |
| Doubly Linked Lists | 1072 |
| Default Constructor | 1075 |
| isEmptyList | 1075 |
| Destroy the List | 1075 |
| Initialize the List | 1076 |
| Length of the List | 1076 |
| Print the List | 1076 |
| Reverse Print the List | 1076 |
| Search the List | 1077 |
| First and Last Elements | 1077 |
| Circular Linked Lists | 1083 |
| Programming Example: Video Store | 1084 |
| Quick Review | 1104 |
| Exercises | 1104 |
| Programming Exercises | 1109 |

19

STACKS AND QUEUES**1115**

| | |
|-------------------------------------------|------|
| Stacks | 1116 |
| Stack Operations | 1118 |
| Implementation of Stacks as Arrays | 1120 |
| Initialize Stack | 1123 |
| Empty Stack | 1124 |
| Full Stack | 1124 |
| Push | 1124 |
| Return the Top Element | 1126 |
| Pop | 1126 |
| Copy Stack | 1128 |
| Constructor and Destructor | 1128 |
| Copy Constructor | 1129 |

| | |
|-----------------------------------------------------------------------------------|------|
| Overloading the Assignment Operator (=) | 1129 |
| Stack Header File | 1130 |
| Programming Example: Highest GPA | 1134 |
| Linked Implementation of Stacks | 1138 |
| Default Constructor | 1141 |
| Empty Stack and Full Stack | 1141 |
| Initialize Stack | 1142 |
| Push | 1142 |
| Return the Top Element | 1144 |
| Pop | 1144 |
| Copy Stack | 1146 |
| Constructors and Destructors | 1147 |
| Overloading the Assignment Operator (=) | 1147 |
| Stack as Derived from the | |
| class unorderedLinkedList | 1150 |
| Application of Stacks: Postfix Expressions | |
| Calculator | 1151 |
| Main Algorithm | 1154 |
| Function evaluateExpression | 1154 |
| Function evaluateOpr | 1156 |
| Function discardExp | 1158 |
| Function printResult | 1158 |
| Removing Recursion: Nonrecursive Algorithm to Print a Linked List Backward | 1161 |
| Queues | 1165 |
| Queue Operations | 1166 |
| Implementation of Queues as Arrays | 1168 |
| Linked Implementation of Queues | 1177 |
| Queue Derived from the | |
| class unorderedLinkedListType | 1182 |
| Application of Queues: Simulation | 1183 |
| Designing a Queuing System | 1184 |
| Customer | 1185 |
| Server | 1188 |

| | |
|---------------------------------------------------------------------------------------------|-----------------|
| Server List | 1191 |
| Waiting Customers Queue | 1196 |
| Main Program | 1198 |
| Quick Review | 1203 |
| Exercises | 1204 |
| Programming Exercises | 1210 |
| APPENDIX A: RESERVED WORDS | 1215 |
| APPENDIX B: OPERATOR PRECEDENCE | 1217 |
| APPENDIX C: CHARACTER SETS | 1219 |
| ASCII (American Standard Code for Information Interchange) | 1219 |
| EBCDIC (Extended Binary Coded Decimal Interchange Code) | 1220 |
| APPENDIX D: OPERATOR OVERLOADING | 1223 |
| APPENDIX E: ADDITIONAL C++ TOPICS | 1225 |
| Binary (Base 2) Representation of a Nonnegative Integer | 1225 |
| Converting a Base 10 Number to a Binary Number (Base 2) | 1225 |
| Converting a Binary Number (Base 2) to Base 10 | 1227 |
| Converting a Binary Number (Base 2) to Octal (Base 8) and Hexadecimal (Base 16) | 1228 |
| More on File Input/Output | 1230 |
| Binary Files | 1230 |
| Random File Access | 1236 |
| Naming Conventions of Header Files in ANSI/ISO Standard C++ and Standard C++ | 1244 |

| | |
|--------------------------------------------------------------------------------|-----------------|
| APPENDIX F: HEADER FILES | 1247 |
| Header File <code>cassert</code> (<code>assert.h</code>) | 1247 |
| Header File <code>cctype</code> (<code>ctype.h</code>) | 1248 |
| Header File <code>cfloating</code> (<code>float.h</code>) | 1249 |
| Header File <code>climits</code> (<code>limits.h</code>) | 1250 |
| Header File <code>cmath</code> (<code>math.h</code>) | 1252 |
| Header File <code>cstdint</code> (<code>stdint.h</code>) | 1253 |
| Header File <code>cstring</code> (<code>string.h</code>) | 1253 |
| APPENDIX G: MEMORY SIZE ON A SYSTEM AND RANDOM NUMBER GENERATOR | 1257 |
| Random Number Generator | 1258 |
| APPENDIX H: STANDARD TEMPLATE LIBRARY (STL) | 1259 |
| Components of the STL | 1259 |
| Container Types | 1260 |
| Sequence Containers | 1260 |
| Sequence Container: Vectors | 1260 |
| Member Functions Common to All Containers | 1269 |
| Member Functions Common to Sequence Containers | 1271 |
| <code>copy</code> Algorithm | 1272 |
| Sequence Container: <code>deque</code> | 1276 |
| Sequence Container: <code>list</code> | 1279 |
| Iterators | 1284 |
| IOStream Iterators | 1285 |
| Container Adapters | 1285 |
| Algorithms | 1289 |
| STL Algorithm Classification | 1289 |
| STL Algorithms | 1292 |
| Functions <code>fill</code> and <code>fill_n</code> | 1292 |
| Functions <code>find</code> and <code>find_if</code> | 1294 |

| | |
|------------------------------------------------------------------------------------|------|
| Functions <code>remove</code> and <code>replace</code> | 1295 |
| Functions <code>search</code> , <code>sort</code> , and <code>binary_search</code> | 1297 |

APPENDIX I: ANSWERS TO ODD-NUMBERED EXERCISES

1301

| | |
|-------------------|------|
| Chapter 1 | 1301 |
| Chapter 2 | 1304 |
| Chapter 3 | 1306 |
| Chapter 4 | 1307 |
| Chapter 5 | 1309 |
| Chapter 6 | 1311 |
| Chapter 7 | 1312 |
| Chapter 8 | 1313 |
| Chapter 9 | 1314 |
| Chapter 10 | 1316 |
| Chapter 11 | 1317 |
| Chapter 12 | 1318 |
| Chapter 13 | 1321 |
| Chapter 14 | 1322 |
| Chapter 15 | 1323 |
| Chapter 16 | 1324 |
| Chapter 17 | 1325 |
| Chapter 18 | 1326 |
| Chapter 19 | 1327 |

INDEX

1331



PREFACE

WELCOME TO THE FIFTH EDITION OF *C++ Programming: From Problem Analysis to Program Design*. Designed for a first Computer Science (CS1) C++ course, this text provides a breath of fresh air to you and your students. The CS1 course serves as the cornerstone of the Computer Science curriculum. My primary goal is to motivate and excite all CS1 students, regardless of their level. Motivation breeds excitement for learning. Motivation and excitement are critical factors that lead to the success of the programming student. This text is a culmination and development of my classroom notes throughout more than fifty semesters of teaching successful programming to Computer Science students.

Warning: This text can be expected to create a serious reduction in the demand for programming help during your office hours. Other side effects include significantly diminished student dependency on others while learning to program.

C++ Programming: From Problem Analysis to Program Design started as a collection of brief examples, exercises, and lengthy programming examples to supplement the books that were in use at our university. It soon turned into a collection large enough to develop into a text. *The approach taken in this book is, in fact, driven by the students' demand for clarity and readability.* The material was written and rewritten until the students felt comfortable with it. Most of the examples in this book resulted from student interaction in the classroom.

As with any profession, practice is essential. Cooking students practice their recipes. Budding violinists practice their scales. New programmers must practice solving problems and writing code. This is not a C++ cookbook. We do not simply list the C++ syntax followed by an example; we dissect the “why” behind all the concepts. The crucial question of “why?” is answered for every topic when first introduced. This technique offers a bridge to learning C++. Students must understand the “why?” in order to be motivated to learn.

Traditionally, a C++ programming neophyte needed a working knowledge of another programming language. This book assumes no prior programming experience. However, some adequate mathematics background, such as college algebra, is required.

Changes in the Fifth Edition

The fifth edition contains more than 50 new programming exercises, and more than 150 new exercises. Each of the Chapters 2 to 7 include a programming exercise which contains a solution of a problem, however, the statements are in the incorrect order. So the student is asked to rewrite the program with statements in the correct order. This will allow the students to learn how to read and debug programs written by someone else. Another major change in this edition is the inclusion of debugging sections in the chapters 2 to 7. In these sections, a program with errors is included. The program is compiled and syntax errors, if any are shown. We then show how to interpret the syntax errors and correct them. Some sections also show how to find and correct logical errors. This edition also includes various new examples, such as Examples 5-8, 7-8, 12-6, and 12-8. Various sections of Chapters 4, 5, 6, and 7 have been rewritten. Chapter 8 includes additional string functions and virtual functions section of Chapter 14 is rewritten with new examples.

Approach

The programming language C++, which evolved from C, is no longer considered an industry-only language. Numerous colleges and universities use C++ for their first programming language course. C++ is a combination of structured programming and object-oriented programming, and this book addresses both types.

This book can be easily divided into two parts: structured programming and object-oriented programming. The first 11 chapters form the structured programming part; Chapters 12 through 19 form the object-oriented part. However, only the first seven chapters are essential to move on to the object-oriented portion.

In July 1998, ANSI/ISO Standard C++ was officially approved. This book focuses on ANSI/ISO Standard C++. Even though the syntax of Standard C++ and ANSI/ISO Standard C++ is very similar, Chapter 8 discusses some of the features of ANSI/ISO Standard C++ that are not available in Standard C++.

Chapter 1 briefly reviews the history of computers and programming languages. The reader can quickly skim through this chapter and become familiar with some of the hardware components and the software parts of the computer. This chapter contains a section on processing a C++ program. This chapter also describes structured and object-oriented programming.

Chapter 2 discusses the basic elements of C++. After completing this chapter, students become familiar with the basics of C++ and are ready to write programs that are complicated enough to do some computations. Input/output is fundamental to any programming language. It is introduced early, in Chapter 3, and is covered in detail.

Chapters 4 and 5 introduce control structures to alter the sequential flow of execution. Chapters 6 and 7 study user-defined functions. It is recommended that readers with no prior programming background spend extra time on Chapters 6 and 7. Several examples are provided to help readers understand the concepts of parameter passing and the scope of an identifier.

Chapter 8 discusses the user-defined simple data type (enumeration type), the `namespace` mechanism of ANSI/ISO Standard C++, and the `string` type. The earlier versions of C did not include the enumeration type. Enumeration types have very limited use; their main purpose is to make the program readable. This book is organized such that readers can skip the section on enumeration types during the first reading without experiencing any discontinuity, and then later go through this section.

Chapter 9 discusses arrays in detail. Chapter 10 describes various searching and sorting algorithms as well as an introduction to the `vector` class. Chapter 11 introduces records (`structs`). The introduction of structs in this book is similar to C `structs`. This chapter is optional; it is not a prerequisite for any of the remaining chapters.

Chapter 12 begins the study of object-oriented programming (OOP) and introduces classes. The first half of this chapter shows how classes are defined and used in a program. The second half of the chapter introduces abstract data types (ADTs). This chapter shows how classes in C++ are a natural way to implement ADTs. Chapter 13 continues with the fundamentals of object-oriented design (OOD) and OOP and discusses inheritance and composition. It explains how classes in C++ provide a natural mechanism for OOD and how C++ supports OOP. Chapter 13 also discusses how to find the objects in a given problem.

Chapter 14 studies pointers in detail. After introducing pointers and how to use them in a program, this chapter highlights the peculiarities of classes with pointer data members and how to avoid them. Moreover, this chapter also discusses how to create and work with dynamic two-dimensional arrays. Chapter 14 also discusses abstract classes and a type of polymorphism accomplished via virtual functions.

Chapter 15 continues the study of OOD and OOP. In particular, it studies polymorphism in C++. The chapter specifically discusses two types of polymorphism—overloading and templates.

Chapter 16 discusses exception handling in detail. Chapter 17 introduces and discusses recursion. Moreover, this is a standalone chapter, so it can be studied anytime after Chapter 10.

Chapters 18 and 19 are devoted to the study of data structures. Discussed in detail are linked lists in Chapter 18 and stacks and queues in Chapter 19. The programming code developed in these chapters is generic. These chapters effectively use the fundamentals of OOD.

Appendix A lists the reserved words in C++. Appendix B shows the precedence and associativity of the C++ operators. Appendix C lists the ASCII (American Standard Code for Information Interchange) and EBCDIC (Extended Binary Coded Decimal Interchange Code) character sets. Appendix D lists the C++ operators that can be overloaded.

Appendix E has three objectives. First, we discuss how to convert a number from decimal to binary and binary to decimal. We then discuss binary and random access files in detail. Finally, we describe the naming conventions of the header files in both ANSI/ISO Standard C++ and Standard C++. Appendix F discusses some of the most widely used library routines, and includes the names of the standard C++ header files. The programs in Appendix G show how to print the memory size for the built-in data types on your system as well as how to use a random number generator. Appendix H gives an introduction to

the Standard Template Library, and Appendix I provides the answers to odd-numbered exercises in the book.

How to Use the Book

This book can be used in various ways. Figure 1 shows the dependency of the chapters.




FIGURE 1 Chapter dependency diagram

In Figure 1, dotted lines mean the preceding chapter is used in one of the sections of the chapter and is not necessarily a prerequisite for the next chapter. For example, Chapter 9 covers arrays in detail. In Chapters 11 and 12, we show the relationship between arrays and `structs` and arrays and classes, respectively. However, if Chapter 12 is studied before Chapter 9, then the section dealing with arrays in Chapter 12 can be skipped without any discontinuation. This particular section can be studied after studying chapter 9.

It is recommended that the first seven chapters be covered sequentially. After covering the first seven chapters, if the reader is interested in learning OOD and OOP early, then Chapter 12 can be studied right after Chapter 7. Chapter 8 can be studied any time after Chapter 7.

After studying the first seven chapters in sequence, some of the approaches are:

1. Study chapters in the sequence: 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19.
2. Study chapters in the sequence: 9, 12, 14, 15, 13, 17, 18, 19, 10, 16.
3. Study chapters in the sequence: 12, 9, 10, 14, 15, 13, 17, 18, 19, 16.
4. Study chapters in the sequence: 12, 9, 14, 15, 13, 17, 18, 19, 10, 16.

FEATURES OF THE BOOK

Selection: `if` and `if...else` | 205

Following the rule of pairing an `else` with an `if`, the `else` in Line 12 is paired with the `if` in Line 10. In other words, using the correct indentation, the code is:

```
if (gpa >= 2.0) //Line 9
{
    if (gpa >= 3.9) //Line 10
        cout << "Dean's Honor List." << endl; //Line 11
    else //Line 12
        cout << "The GPA is below the graduation "
            << "requirement. \nSee your "
            << "academic advisor." << endl; //Line 13
}
```

Now, we can see that the `if` statement in Line 9 is a one-way selection. Therefore, if the input number is less than 2.0, no action will take place, that is, no warning message will be printed. Now, suppose the input is 3.8. Then, the expression in Line 9 evaluates to `true`, so the expression in Line 10 is evaluated, which evaluates to `false`. This means the output statement in Line 13 executes, resulting in an unsatisfactory result.

In fact, the program should print the warning message only if the GPA is less than 2.0, and it should print the message:

Dean's Honor List.

if the GPA is greater than or equal to 3.9.

To achieve that result, the `else` in Line 12 needs to be paired with the `if` in Line 9. To pair the `else` in Line 12 with the `if` in Line 9, you need to use a compound statement, as follows:

```
if (gpa >= 2.0) //Line 9
{
    if (gpa >= 3.9) //Line 10
        cout << "Dean's Honor List." << endl; //Line 11
}
else //Line 12
    cout << "The GPA is below the graduation "
        << "requirement. \nSee your "
        << "academic advisor." << endl; //Line 13
```

The correct program is as follows:

```
//Correct GPA program.

#include <iostream> //Line 1
using namespace std; //Line 2

int main() //Line 3
{ //Line 4
    double gpa; //Line 5

    cout << "Enter the GPA: "; //Line 6
    cin >> gpa; //Line 7
    cout << endl; //Line 8
}
```

4

Four-color interior design shows accurate C++ code and related comments.

Chapter 2 defined a program as a sequence of statements whose objective is to accomplish some task. The programs you have examined so far were simple and straightforward. To process a program, the computer begins at the first executable statement and executes the statements in order until it comes to the end. In this chapter and Chapter 5, you will learn how to tell a computer that it does not have to follow a simple sequential order of statements; it can also make decisions and repeat certain statements over and over until certain conditions are met.

Control Structures

A computer can process a program in one of the following ways: in sequence; selectively, by making a choice, which is also called a branch; repetitively, by executing a statement over and over, using a structure called a loop; or by calling a function. Figure 4-1 illustrates the first three types of program flow. (In Chapter 7, we will show how function calls work.) The programming examples in Chapters 2 and 3 included simple sequential programs. With such a program, the computer starts at the beginning and follows the statements in order. No choices are made; there is no repetition. Control structures provide alternatives to sequential program execution and are used to alter the sequential flow of execution. The two most common control structures are selection and repetition. In *selection*, the program executes particular statements depending on some condition(s). In *repetition*, the program repeats particular statements a certain number of times based on some condition(s).




FIGURE 4-1 Flow of execution

More than 300 visual diagrams, both extensive and exhaustive, illustrate difficult concepts.

centimeters is fixed, because 1 inch is always equal to 2.54 centimeters. When stored in memory, this type of data needs to be protected from accidental changes during program execution. In C++, you can use a **named constant** to instruct a program to mark those memory locations in which data is fixed throughout program execution.

Named constant: A memory location whose content is not allowed to change during program execution.

To allocate memory, we use C++'s declaration statements. The syntax to declare a named constant is:

```
const dataType identifier = value;
```

In C++, `const` is a reserved word.

EXAMPLE 2-11

Consider the following C++ statements:

```
const double CONVERSION = 2.54;
const int NO_OF_STUDENTS = 20;
const char BLANK = ' ';
```

The first statement tells the compiler to allocate memory (eight bytes) to store a value of type `double`, call this memory space `CONVERSION`, and store the value 2.54 in it. Throughout a program that uses this statement, whenever the conversion formula is needed, the memory space `CONVERSION` can be accessed. The meaning of the other statements is similar.

Note that the identifier for a named constant is in uppercase letters. Even though there are no written rules, C++ programmers typically prefer to use uppercase letters to name a named constant. Moreover, if the name of a named constant is a combination of more than one word, called a *run-together word*, then the words are separated using an underscore. For example, in the preceding example, `NO_OF_STUDENTS` is a run-together word.

NOTE As noted earlier, the default type of floating-point numbers is `double`. Therefore, if you declare a named constant of type `float`, then you must specify that the value is of type `float` as follows:

```
const float CONVERSION = 2.54f;
```

Otherwise, the compiler will generate a warning message. Notice that `2.54f` says that it is a `float` value. Recall that the memory size for `float` values is four bytes; for `double` values, eight bytes. Because memory size is of little concern these days, as indicated earlier, we will mostly use the type `double` to work with floating-point values.

Numbered examples illustrate the key concepts with their relevant code. The programming code in these examples is followed by a Sample Run. An explanation then follows that describes what each line in the code does.

Notes highlight important facts about the concepts introduced in the chapter.

Programming Examples are programs featured at the end of each chapter. Programming Examples are where everything in the chapter comes together. They are highlighted with an icon in the margin like the one shown here. These examples teach problem solving skills and include the concrete stages of input, output, problem analysis and algorithm design, class design, and a program listing. All programs are designed to be methodical, consistent, and user-friendly. Each Programming Example starts with a problem analysis that is followed by the algorithm design and/or class design. Every step of the algorithm is coded in C++. In addition to helping students learn problem solving techniques, these detailed programs show the student how

to implement concepts in an actual C++ program. We strongly recommend that students study the Programming Examples carefully in order to learn C++ effectively. Students typically learn much from completely worked-out programs. Further, programming examples reduce considerably the students' need for help outside the classroom and bolster the students' self-confidence.

```
typedef int Boolean;           //Line 1
const Boolean TRUE = 1;       //Line 2
const Boolean FALSE = 0;      //Line 3
Boolean flag;                 //Line 4
```

The statement in Line 1 creates an alias, `Boolean`, for the data type `int`. The statements in Lines 2 and 3 declare the named constants `TRUE` and `FALSE` and initialize them to 1 and 0, respectively. The statement in Line 4 declares `flag` to be a variable of type `Boolean`. Because `flag` is a variable of type `Boolean`, the following statement is legal:

```
flag = TRUE;
```

PROGRAMMING EXAMPLE: The Game of Rock, Paper, and Scissors

Children often play the game of rock, paper, and scissors. This game has two players, each of whom chooses one of the three objects: rock, paper, or scissors. If player 1 chooses rock and player 2 chooses paper, player 2 wins the game because paper covers the rock. The game is played according to the following rules:

- If both players choose the same object, this play is a tie.
- If one player chooses rock and the other chooses scissors, the player choosing the rock wins this play because the rock breaks the scissors.
- If one player chooses rock and the other chooses paper, the player choosing the paper wins this play because the paper covers the rock.
- If one player chooses scissors and the other chooses paper, the player choosing the scissors wins this play because the scissors cut the paper.

Write an interactive program that allows two people to play this game.

Input This program has two types of input:

- The users' responses when asked to play the game.
- The players' choices.

Output The players' choices and the winner of each play. After the game is over, the total number of plays and the number of times that each player won should be output as well.

PROBLEM
ANALYSIS
AND
ALGORITHM
DESIGN

Two players play this game. Players enter their choices via the keyboard. Each player enters R or r for Rock, P or p for Paper, or S or s for Scissors. While the first player enters a choice, the second player looks elsewhere. Once both entries are in, if the entries are valid, the program outputs the players' choices and declares the winner of the play. The game continues until one of the players decides to quit

EXERCISES

- Mark the following statements as true or false.
 - A sequential search of a list assumes that the list elements are sorted in ascending order.
 - A binary search of a list assumes that the list is sorted.
 - A binary search is faster on ordered lists and slower on unordered lists.
 - A binary search is faster on large lists, but a sequential search is faster on small lists.
 - When you declare a `vector` object and specify its size as 10, then only 10 elements can be stored in the object.

- Consider the following list:

63 45 32 98 46 57 28 100

Using a sequential search, how many comparisons are required to determine whether the following items are in the list or not? (Recall that comparisons mean item comparisons, not index comparisons.)

- 90 b. 57 c. 63 d. 120
- Write a version of the sequential search algorithm that can be used to search a sorted list.
 - Consider the following list:

5 12 17 35 46 65 78 85 93 110 115

Using a sequential search on ordered lists, which you designed in (a), how many comparisons are required to determine whether the following items are in the list or not? (Recall that comparisons mean item comparisons, not index comparisons.)

- 35 ii. 60 iii. 78 iv. 120
- Consider the following list:

2 10 17 45 49 55 68 85 92 98 110

Using the binary search, how many comparisons are required to determine whether the following items are in the list or not? Show the values of `first`, `last`, and `middle` and the number of comparisons after each iteration of the loop.

- 15 b. 49 c. 98 d. 99
- Sort the following list using the bubble sort algorithm as discussed in this chapter. Show the list after each iteration of the outer `for` loop.

26, 45, 17, 65, 33, 55, 12, 18

Exercises further reinforce learning and ensure that students have, in fact, mastered the material.

```

{
    if (num % 5 == 0 || num % 5 == 3)
        list.insertFirst(num);
    else
        list.insertLast(num);
    cin >> num;
}

list.print();
cout << endl;

copyList = list;

copyList.deleteNode(78);
copyList.deleteNode(35);

cout << "Copy List = ";
copyList.print();
cout << endl;

```

19. Draw the UML diagram of the `class doublyLinkedList` as discussed in this chapter.
20. Draw the UML diagram of the `class videoType` of the Video Store programming example.
21. Draw the UML diagram of the `class videoListType` of the Video Store programming example.

PROGRAMMING EXERCISES

1. (**Online Address Book revisited**) Programming Exercise 6 in Chapter 13 could handle a maximum of only 500 entries. Using linked lists, redo the program to handle as many entries as required. Add the following operations to your program:
 - a. Add or delete a new entry to the address book.
 - b. Allow the user to save the data in the address book.
 2. Extend the `class linkedListType` by adding the following operations:
 - a. Find and delete the node with the smallest `info` in the list. (Delete only the first occurrence and traverse the list only once.)
 - b. Find and delete all occurrences of a given `info` from the list. (Traverse the list only once.)
- Add these as abstract functions in the `class linkedListType` and provide the definitions of these functions in the `class unorderedLinkedList`. Also, write a program to test these functions.

Programming Exercises challenge students to write C++ programs with a specified outcome.



SUPPLEMENTAL RESOURCES

The following supplemental materials are available when this book is used in a classroom setting.

All instructor teaching tools are available with this book on a single CD-ROM.

Electronic Instructor's Manual

The Instructor's Manual that accompanies this textbook includes:

- Additional instructional material to assist in class preparation, including suggestions for lecture topics.
- Solutions to all the end-of-chapter materials, including the Programming Exercises.

ExamView[®]

This textbook is accompanied by ExamView, a powerful testing software package that allows instructors to create and administer printed, computer (LAN-based), and Internet exams. ExamView includes hundreds of questions that correspond to the topics covered in this text, enabling students to generate detailed study guides that include page references for further review. These computer-based and Internet testing components allow students to take exams at their computers, and save the instructor time because each exam is graded automatically.

PowerPoint Presentations

This book comes with Microsoft PowerPoint slides for each chapter. These are included as a teaching aid for classroom presentations, either to make available to students on the network for chapter review, or to be printed for classroom distribution. Instructors can add their own slides for additional topics that they introduce to the class.

Content for Online Learning

Course Technology has partnered with today's leading distance learning solution providers and class-management platforms. To access this material, visit www.cengage.com/webtutor and search for your title. Instructor resources include the following: additional case projects, sample syllabi, PowerPoint presentations, and more. For students to access this material, they must have purchased a WebTutor PIN-code specific to this title and your campus platform. The resources for students might include (based on instructor preferences): topic reviews, review questions, practice tests, and more. For additional information, please contact your sales representative.

Source Code

The source code, in ANSI/ISO Standard C++, is available at www.course.com, and is also available on the Instructor Resources CD-ROM. The input files needed to run some of the programs are also included with the source code.

Solution Files

The solution files for all Programming Exercises, in ANSI/ISO C++, are available at www.course.com, and are also available on the Instructor Resources CD-ROM. The input files needed to run some of the Programming Exercises are also included with the solution files.



ACKNOWLEDGEMENTS

There are many people that I must thank who, one way or another, contributed to the success of this book. First, I would like to thank all the students who, during the preparation, were spontaneous in telling me if certain portions needed to be reworded for better understanding and clearer reading. Next, I would like to thank those who e-mailed numerous comments to improve upon the second edition. I am thankful to Professors S.C. Cheng, Randall Crist, and Vasant Raval for constantly supporting this project. I am also very grateful to the reviewers who reviewed earlier versions of this book and offered many critical suggestions on how to improve it.

I owe a great deal to the following reviewers who patiently read each page of every chapter of the current version and made critical comments to improve on the book: Stefano Basagni, Northeastern University; Jeff Ringenberg, University of Michigan; Colleen van Lent, University of Michigan; Tuan Vo, Mt. San Antonio College; Kerstin Voigt, California State University San Bernardino; Lan Yang, Cal Poly Pomona. The reviewers will recognize that their criticisms have not been overlooked and, in fact, made this a better book.

Next, I express thanks to Amy Jollymore, acquisition editor, for recognizing the importance and uniqueness of this project. All this would not have been possible without the careful planning of Senior Product Manager Alyssa Pratt. I extend my sincere thanks to Alyssa, as well as to Content Project Manager, Mathew Hutchinson. I also thank Tintu Thomas of Integra Software Services for assisting us in keeping the project on schedule. I would like to thank Chris Scriver and Serge Palladino of QA department of Course Technology for patiently and carefully proof reading the text, testing the code, and discovering typos and errors.

I am thankful to my parents for their blessings.

Finally, I am thankful for the support of my wife Sadhana and especially my daughter Shelly, to whom this book is dedicated. She cheered me up whenever I was overwhelmed during the writing of this book, and also made sure that the corrections were in place. Shelly always draws special joy whenever I undertake such projects.

I welcome any comments concerning the text. Comments may be forwarded to the following e-mail address: malik@creighton.edu

D. S. Malik



1 CHAPTER

AN OVERVIEW OF COMPUTERS AND PROGRAMMING LANGUAGES

IN THIS CHAPTER, YOU WILL:

- Learn about different types of computers
- Explore the hardware and software components of a computer system
- Learn about the language of a computer
- Learn about the evolution of programming languages
- Examine high-level programming languages
- Discover what a compiler is and what it does
- Examine a C++ program
- Explore how a C++ program is processed
- Learn what an algorithm is and explore problem-solving techniques
- Become aware of structured design and object-oriented design programming methodologies
- Become aware of Standard C++ and ANSI/ISO Standard C++

Introduction

Terms such as “the Internet,” which were unfamiliar just 20 years ago are now common. Students in elementary school regularly “surf” the Internet and use computers to design their classroom projects. Many people use the Internet to look for information and to communicate with others. This is all made possible by the availability of different software, also known as computer programs. Without software, a computer is useless. Software is developed by using programming languages. The programming language C++ is especially well suited for developing software to accomplish specific tasks. Our main objective is to help you learn how to write programs in the C++ programming language. Before you begin programming, it is useful to understand some of the basic terminology and different components of a computer. We begin with an overview of the history of computers.

A Brief Overview of the History of Computers

The first device known to carry out calculations was the abacus. The abacus was invented in Asia but was used in ancient Babylon, China, and throughout Europe until the late middle ages. The abacus uses a system of sliding beads in a rack for addition and subtraction. In 1642, the French philosopher and mathematician Blaise Pascal invented the calculating device called the Pascaline. It had eight movable dials on wheels and could calculate sums up to eight figures long. Both the abacus and Pascaline could perform only addition and subtraction operations. Later in the 17th century, Gottfried von Leibniz invented a device that was able to add, subtract, multiply, and divide. In 1819, Joseph Jacquard, a French weaver, discovered that the weaving instructions for his looms could be stored on cards with holes punched in them. While the cards moved through the loom in sequence, needles passed through the holes and picked up threads of the correct color and texture. A weaver could rearrange the cards and change the pattern being woven. In essence, the cards programmed a loom to produce patterns in cloth. The weaving industry may seem to have little in common with the computer industry. However, the idea of storing information by punching holes on a card proved to be of great importance in the later development of computers.

In the early and mid-1800s, Charles Babbage, an English mathematician and physical scientist, designed two calculating machines—the difference engine and the analytical engine. The difference engine could perform complex operations such as squaring numbers automatically. Babbage built a prototype of the difference engine, but the actual device was never produced. The analytical engine’s design included input device, data storage, a control unit that allowed processing instructions in any sequence, and output devices. However, the designs remained in blueprint stage. Most of Babbage’s work is known through the writings of his colleague Ada Augusta, Countess of Lovelace. Augusta is considered the first computer programmer.

At the end of the 19th century, U.S. Census officials needed help in accurately tabulating the census data. Herman Hollerith invented a calculating machine that ran on electricity and used punched cards to store data. Hollerith’s machine was immensely successful. Hollerith founded the Tabulating Machine Company, which later became the computer and technology corporation known as IBM.

The first computer-like machine was the Mark I. It was built, in 1944, jointly by IBM and Harvard University under the leadership of Howard Aiken. Punched cards were used to feed data into the machine. The Mark I was 52 feet long, weighed 50 tons, and had 750,000 parts. In 1946, the ENIAC (Electronic Numerical Integrator and Calculator) was built at the University of Pennsylvania. It contained 18,000 vacuum tubes and weighed some 30 tons.

The computers that we know today use the design rules given by John von Neumann in the late 1940s. His design included components such as an arithmetic logic unit, a control unit, memory, and input/output devices. These components are described in the next section. Von Neumann's computer design makes it possible to store the programming instructions and the data in the same memory space. In 1951, the UNIVAC (Universal Automatic Computer) was built and sold to the U.S. Census Bureau.

In 1956, the invention of transistors resulted in smaller, faster, more reliable, and more energy-efficient computers. This era also saw the emergence of the software development industry, with the introduction of FORTRAN and COBOL, two early programming languages. In the next major technological advancement, transistors were replaced by tiny integrated circuits, or "chips." Chips are smaller and cheaper than transistors and can contain thousands of circuits on a single chip. They give computers tremendous processing speed.

In 1970, the microprocessor, an entire CPU on a single chip, was invented. In 1977, Stephen Wozniak and Steven Jobs designed and built the first Apple computer in their garage. In 1981, IBM introduced its personal computer (PC). In the 1980s, clones of the IBM PC made the personal computer even more affordable. By the mid-1990s, people from many walks of life were able to afford them. Computers continue to become faster and less expensive as technology advances.

Modern-day computers are powerful, reliable, and easy to use. They can accept spoken-word instructions and imitate human reasoning through artificial intelligence. Expert systems assist doctors in making diagnoses. Mobile computing applications are growing significantly. Using handheld devices, delivery drivers can access global positioning satellites (GPS) to verify customer locations for pickups and deliveries. Cell phones permit you to check your e-mail, make airline reservations, see how stocks are performing, and access your bank accounts.

Although there are several categories of computers, such as mainframe, midsize, and micro, all computers share some basic elements, described in the next section.

Elements of a Computer System

A computer is an electronic device capable of performing commands. The basic commands that a computer performs are input (get data), output (display result), storage, and performance of arithmetic and logical operations.

In today's market, personal computers are sold with descriptions such as a Pentium 4 Processor 2.80 GHz, 1 GB RAM, 250 GB HD, VX750 19" Silver Flat CRT Color Monitor, preloaded with software such as an operating system, games, encyclopedias, and application software such as word processors or money management programs. These descriptions represent two categories: hardware and software. Items such as "Pentium 4

Processor 2.80 GHz, 1GB RAM, 250 GB HD, VX750 19" Silver Flat CRT Color Monitor” fall into the hardware category; items such as “operating system, games, encyclopedias, and application software” fall into the software category. Let’s consider the hardware first.

Hardware

Major hardware components include the central processing unit (CPU); main memory (MM), also called random access memory (RAM); input/output devices; and secondary storage. Some examples of input devices are the keyboard, mouse, and secondary storage. Examples of output devices are the screen, printer, and secondary storage. Let’s look at each of these components in greater detail.

Central Processing Unit and Main Memory

The **central processing unit** is the “brain” of the computer and the single most expensive piece of hardware in a computer. The more powerful the CPU, the faster the computer. Arithmetic and logical operations are carried out inside the CPU. Figure 1-1(a) shows some hardware components.




FIGURE 1-1 Hardware components of a computer and main memory

Main memory, or **random access memory**, is connected directly to the CPU. All programs must be loaded into main memory before they can be executed. Similarly, all data must be brought into main memory before a program can manipulate it. When the computer is turned off, everything in main memory is lost.

Main memory is an ordered sequence of cells, called **memory cells**. Each cell has a unique location in main memory, called the **address** of the cell. These addresses help you access the information stored in the cell. Figure 1-1(b) shows main memory with some data.

Today's computers come with main memory consisting of millions to billions of cells. Although Figure 1-1(b) shows data stored in cells, the content of a cell can be either a programming instruction or data. Moreover, this figure shows the data as numbers and letters. However, as explained later in this chapter, main memory stores everything as sequences of 0s and 1s. The memory addresses are also expressed as sequences of 0s and 1s.

SECONDARY STORAGE

Because programs and data must be stored in main memory before processing and because everything in main memory is lost when the computer is turned off, information stored in main memory must be transferred to some other device for permanent storage. The device that stores information permanently (unless the device becomes unusable or you change the information by rewriting it) is called **secondary storage**. To be able to transfer information from main memory to secondary storage, these components must be directly connected to each other. Examples of secondary storage are hard disks, flash drives, floppy disks, ZIP disks, CD-ROMs, and tapes.

Input/Output Devices

For a computer to perform a useful task, it must be able to take in data and programs and display the results of calculations. The devices that feed data and programs into computers are called **input devices**. The keyboard, mouse, and secondary storage are examples of input devices. The devices that the computer uses to display results are called **output devices**. A monitor, printer, and secondary storage are examples of output devices. Figure 1-2 shows some input and output devices.




FIGURE 1-2 Some input and output devices

Software

Software are programs written to perform specific tasks. For example, word processors are programs that you use to write letters, papers, and even books. All software is written in programming languages. There are two types of programs: system programs and application programs.

System programs control the computer. The system program that loads first when you turn on your PC is called the operating system. Without an operating system, the computer is useless. The **operating system** monitors the overall activity of the computer and provides services. Some of these services include memory management, input/output activities, and storage management. The operating system has a special program that organizes secondary storage so that you can conveniently access information.

Application programs perform a specific task. Word processors, spreadsheets, and games are examples of application programs. The operating system is the program that runs application programs.

The Language of a Computer

When you press **A** on your keyboard, the computer displays **A** on the screen. But what is actually stored inside the computer's main memory? What is the language of the computer? How does it store whatever you type on the keyboard?

Remember that a computer is an electronic device. Electrical signals are used inside the computer to process information. There are two types of electrical signals: analog and digital. **Analog signals** are continuous wave forms used to represent such things as sound. Audio tapes, for example, store data in analog signals. **Digital signals** represent information with a sequence of 0s and 1s. A 0 represents a low voltage, and a 1 represents a high voltage. Digital signals are more reliable carriers of information than analog signals and can be copied from one device to another with exact precision. You might have noticed that when you make a copy of an audio tape, the sound quality of the copy is not as good as the original tape. On the other hand, when you copy a CD, the copy is as good as the original. Computers use digital signals.

Because digital signals are processed inside a computer, the language of a computer, called **machine language**, is a sequence of 0s and 1s. The digit 0 or 1 is called a **binary digit**, or **bit**. Sometimes a sequence of 0s and 1s is referred to as a **binary code** or a **binary number**.

Bit: A binary digit 0 or 1.

A sequence of eight bits is called a **byte**. Moreover, 2^{10} bytes = 1024 bytes is called a **kilobyte (KB)**. Table 1-1 summarizes the terms used to describe various numbers of bytes.

TABLE 1-1 Binary Units

| Unit | Symbol | Bits/Bytes |
|-----------|--------|------------------------------------------------------------------------------------------------------------|
| Byte | | 8 bits |
| Kilobyte | KB | 2^{10} bytes = 1024 bytes |
| Megabyte | MB | $1024 \text{ KB} = 2^{10} \text{ KB} = 2^{20} \text{ bytes} = 1,048,576 \text{ bytes}$ |
| Gigabyte | GB | $1024 \text{ MB} = 2^{10} \text{ MB} = 2^{30} \text{ bytes} = 1,073,741,824 \text{ bytes}$ |
| Terabyte | TB | $1024 \text{ GB} = 2^{10} \text{ GB} = 2^{40} \text{ bytes} = 1,099,511,627,776 \text{ bytes}$ |
| Petabyte | PB | $1024 \text{ TB} = 2^{10} \text{ TB} = 2^{50} \text{ bytes} = 1,125,899,906,842,624 \text{ bytes}$ |
| Exabyte | EB | $1024 \text{ PB} = 2^{10} \text{ PB} = 2^{60} \text{ bytes} = 1,152,921,504,606,846,976 \text{ bytes}$ |
| Zettabyte | ZB | $1024 \text{ EB} = 2^{10} \text{ EB} = 2^{70} \text{ bytes} = 1,180,591,620,717,411,303,424 \text{ bytes}$ |

Every letter, number, or special symbol (such as * or {) on your keyboard is encoded as a sequence of bits, each having a unique representation. The most commonly used encoding scheme on personal computers is the *seven-bit American Standard Code for Information Interchange (ASCII)*. The ASCII data set consists of 128 characters numbered 0 through 127. That is, in the ASCII data set, the position of the first character is 0, the position of the second character is 1, and so on. In this scheme, **A** is encoded as the binary number 1000001. In fact, **A** is the 66th character in the ASCII character code, but its position is 65 because the position of the first character is 0. Furthermore, the binary number 1000001 is the binary representation of 65. The character **3** is encoded as 0110011. Note that in the ASCII character set, the position of the character **3** is 51, so the character **3** is the 52nd character in the ASCII set. It also follows that 0110011 is the binary representation of 51. For a complete list of the printable ASCII character set, refer to Appendix C.

NOTE

The number system that we use in our daily life is called the **decimal system**, or **base 10**. Because everything inside a computer is represented as a sequence of 0s and 1s, that is, binary numbers, the number system that a computer uses is called **binary**, or **base 2**. We indicated in the preceding paragraph that the number 1000001 is the binary representation of 65. Appendix E describes how to convert a number from base 10 to base 2 and vice versa.

Inside the computer, every character is represented as a sequence of *eight* bits, that is, as a byte. Now the eight-bit binary representation of 65 is **01000001**. Note that we added 0 to the left of the seven-bit representation of 65 to convert it to an eight-bit representation. Similarly, the eight-bit binary representation of 51 is **00110011**.

ASCII is a seven-bit code. Therefore, to represent each ASCII character inside the computer, you must convert the seven-bit binary representation of an ASCII character to an eight-bit binary representation. This is accomplished by adding 0 to the left of the seven-bit ASCII encoding of a character. Hence, inside the computer, the character **A** is represented as **01000001**, and the character **3** is represented as **00110011**.

There are other encoding schemes, such as EBCDIC (used by IBM) and Unicode, which is a more recent development. EBCDIC consists of 256 characters; Unicode consists of 65,536 characters. To store a character belonging to Unicode, you need two bytes.

The Evolution of Programming Languages

The most basic language of a computer, the machine language, provides program instructions in bits. Even though most computers perform the same kinds of operations, the designers of the computer may have chosen different sets of binary codes to perform the operations. Therefore, the machine language of one machine is not necessarily the same as the machine language of another machine. The only consistency among computers is that in any modern computer, all data is stored and manipulated as binary codes.

Early computers were programmed in machine language. To see how instructions are written in machine language, suppose you want to use the equation:

wages = rate • hours

to calculate weekly wages. Further, suppose that the binary code **100100** stands for load, **100110** stands for multiplication, and **100010** stands for store. In machine language, you might need the following sequence of instructions to calculate weekly wages:

```
100100 010001
100110 010010
100010 010011
```

To represent the weekly wages equation in machine language, the programmer had to remember the machine language codes for various operations. Also, to manipulate data, the programmer had to remember the locations of the data in the main memory. This need to remember specific codes made programming not only very difficult, but also error-prone.

Assembly languages were developed to make the programmer's job easier. In assembly language, an instruction is an easy-to-remember form called a **mnemonic**. Table 1-2 shows some examples of instructions in assembly language and their corresponding machine language code.

TABLE 1-2 Examples of Instructions in Assembly Language and Machine Language

| Assembly Language | Machine Language |
|-------------------|------------------|
| LOAD | 100100 |
| STOR | 100010 |
| MULT | 100110 |
| ADD | 100101 |
| SUB | 100011 |

Using assembly language instructions, you can write the equation to calculate the weekly wages as follows:

```
LOAD  rate
MULT  hours
STOR  wages
```

As you can see, it is much easier to write instructions in assembly language. However, a computer cannot execute assembly language instructions directly. The instructions first have to be translated into machine language. A program called an **assembler** translates the assembly language instructions into machine language.

Assembler: A program that translates a program written in assembly language into an equivalent program in machine language.

Moving from machine language to assembly language made programming easier, but a programmer was still forced to think in terms of individual machine instructions. The next step toward making programming easier was to devise **high-level languages** that were closer to natural languages, such as English, French, German, and Spanish. Basic, FORTRAN, COBOL, Pascal, C, C++, C#, and Java are all high-level languages. You will learn the high-level language C++ in this book.

In C++, you write the weekly wages equation as follows:

```
wages = rate * hours;
```

The instruction written in C++ is much easier to understand and is self-explanatory to a novice user who is familiar with basic arithmetic. As in the case of assembly language, however, the computer cannot directly execute instructions written in a high-level language. To run on a computer, these C++ instructions first need to be translated into machine language. A program called a **compiler** translates instructions written in high-level languages into machine code.

Compiler: A program that translates instructions written in a high-level language into the equivalent machine language.

Processing a C++ Program

In the previous sections, we discussed machine language and high-level languages and showed a C++ program. Because a computer can understand only machine language, you are ready to review the steps required to process a program written in C++.

Consider the following C++ program:

```
#include <iostream>

using namespace std;

int main()
{
    cout << "My first C++ program." << endl;

    return 0;
}
```

At this point, you need not be too concerned with the details of this program. However, if you run (execute) this program, it will display the following line on the screen:

My first C++ program.

Recall that a computer can understand only machine language. Therefore, in order to run this program successfully, the code must first be translated into machine language. In this section, we review the steps required to execute programs written in C++.

The following steps, as shown in Figure 1-3, are necessary to process a C++ program.

1. You use a text editor to create a C++ program following the rules, or *syntax*, of the high-level language. This program is called the **source code**, or **source program**. The program must be saved in a text file that has the extension **.cpp**. For example, if you saved the preceding program in the file named **FirstCPPProgram**, then its complete name is **FirstCPPProgram.cpp**.

Source program: A program written in a high-level language.

2. The C++ program given in the preceding section contains the statement **#include <iostream>**. In a C++ program, statements that begin with the symbol **#** are called preprocessor directives. These statements are processed by a program called **preprocessor**.
3. After processing preprocessor directives, the next step is to verify that the program obeys the rules of the programming language—that is, the program is syntactically correct—and translate the program into the equivalent machine language. The *compiler* checks the source program for syntax errors and, if no error is found, translates the program into the equivalent machine language. The equivalent machine language program is called an **object program**.

Object program: The machine language version of the high-level language program.

4. The programs that you write in a high-level language are developed using an integrated development environment (IDE). The IDE contains many programs that are useful in creating your program. For example, it contains the necessary code (program) to display the results of the program and several mathematical functions to make the programmer's job somewhat easier. Therefore, if certain code is already available, you can use this code rather than writing your own code. Once the program is developed and successfully compiled, you must still bring the code for the resources used from the IDE into your program to produce a final program that the computer can execute. This prewritten code (program) resides in a place called the **library**. A program called a **linker** combines the object program with the programs from libraries.

Linker: A program that combines the object program with other programs in the library and is used in the program to create the executable code.

5. You must next load the executable program into main memory for execution. A program called a **loader** accomplishes this task.

Loader: A program that loads an executable program into main memory.

6. The final step is to execute the program.

Figure 1-3 shows how a typical C++ program is processed.




FIGURE 1-3 Processing a C++ program

As a programmer, you need to be concerned only with Step 1. That is, you must learn, understand, and master the rules of the programming language to create source programs.

As noted earlier, programs are developed using an IDE. Well-known IDEs used to create programs in the high-level language C++ include Visual C++ 2008 Express and Visual Studio .NET (from Microsoft), C++ Builder (from Borland), and CodeWarrior (from Metrowerks). These IDEs contain a text editor to create the source program, a compiler to check the source program for syntax errors, a program to link the object code with the IDE resources, and a program to execute the program.

These IDEs are quite user friendly. When you compile your program, the compiler not only identifies the syntax errors, but also typically suggests how to correct them. Moreover, with just a simple command, the object code is linked with the resources used from the IDE. For example, the command that does the linking on Visual C++ 2008 Express and Visual Studio .Net is **Build** or **Rebuild**. (For further clarification regarding the use of these commands, check the documentation of these IDEs.) If the program is not yet compiled, each of these commands first compiles the program and then links and produces the executable code.

The Web site <http://msdn.microsoft.com/en-us/beginner/bb964629.aspx> contains a video that explains how to use Visual C++ 2008 Express to write C++ programs.

Programming with the Problem Analysis–Coding–Execution Cycle

Programming is a process of problem solving. Different people use different techniques to solve problems. Some techniques are nicely outlined and easy to follow. They not only solve the problem, but also give insight into how the solution was reached. These problem-solving techniques can be easily modified if the domain of the problem changes.

To be a good problem solver and a good programmer, you must follow good problem-solving techniques. One common problem-solving technique includes analyzing a problem, outlining the problem requirements, and designing steps, called an **algorithm**, to solve the problem.

Algorithm: A step-by-step problem-solving process in which a solution is arrived at in a finite amount of time.

In a programming environment, the problem-solving process requires the following three steps:

1. Analyze the problem, outline the problem and its solution requirements, and design an algorithm to solve the problem.
2. Implement the algorithm in a programming language, such as C++, and verify that the algorithm works.
3. Maintain the program by using and modifying it if the problem domain changes.

Figure 1-4 summarizes this three-step programming process.




FIGURE 1-4 Problem analysis–coding–execution cycle

To develop a program to solve a problem, you start by analyzing the problem. You then design the algorithm; write the program instructions in a high-level language, or code the program; and enter the program into a computer system.

Analyzing the problem is the first and most important step. This step requires you to do the following:

1. Thoroughly understand the problem.
2. Understand the problem requirements. Requirements can include whether the program requires interaction with the user, whether it manipulates data,

whether it produces output, and what the output looks like. If the program manipulates data, the programmer must know what the data is and how it is represented. That is, you need to look at sample data. If the program produces output, you should know how the results should be generated and formatted.

3. If the problem is complex, divide the problem into subproblems and repeat Steps 1 and 2. That is, for complex problems, you need to analyze each subproblem and understand each subproblem's requirements.

After you carefully analyze the problem, the next step is to design an algorithm to solve the problem. If you broke the problem into subproblems, you need to design an algorithm for each subproblem. Once you design an algorithm, you need to check it for correctness. You can sometimes test an algorithm's correctness by using sample data. At other times, you might need to perform some mathematical analysis to test the algorithm's correctness.

Once you have designed the algorithm and verified its correctness, the next step is to convert it into an equivalent programming code. You then use a text editor to enter the programming code or the program into a computer. Next, you must make sure that the program follows the language's syntax. To verify the correctness of the syntax, you run the code through a compiler. If the compiler generates error messages, you must identify the errors in the code, remove them, and then run the code through the compiler again. When all the syntax errors are removed, the compiler generates the equivalent machine code, the linker links the machine code with the system's resources, and the loader places the program into main memory so that it can be executed.

The final step is to execute the program. The compiler guarantees only that the program follows the language's syntax. It does not guarantee that the program will run correctly. During execution, the program might terminate abnormally due to logical errors, such as division by zero. Even if the program terminates normally, it may still generate erroneous results. Under these circumstances, you may have to reexamine the code, the algorithm, or even the problem analysis.

Your overall programming experience will be successful if you spend enough time to complete the problem analysis before attempting to write the programming instructions. Usually, you do this work on paper using a pen or pencil. Taking this careful approach to programming has a number of advantages. It is much easier to discover errors in a program that is well analyzed and well designed. Furthermore, a carefully analyzed and designed program is much easier to follow and modify. Even the most experienced programmers spend a considerable amount of time analyzing a problem and designing an algorithm.

Throughout this book, you will not only learn the rules of writing programs in C++, but you will also learn problem-solving techniques. Each chapter provides several programming examples that discuss programming problems. These programming examples teach techniques of how to analyze and solve problems, design algorithms, code the algorithms into C++, and also help you understand the concepts discussed in the chapter. To gain the full benefit of this book, we recommend that you work through the programming examples at the end of each chapter.

Next, we provide examples of various problem-analysis and algorithm-design techniques.

EXAMPLE 1-1**1**

In this example, we design an algorithm to find the perimeter and area of a rectangle.

To find the perimeter and area of a rectangle, you need to know the rectangle's length and width.

The perimeter and area of the rectangle are then given by the following formulas:

```
perimeter = 2 * (length + width)
area = length * width
```

The algorithm to find the perimeter and area of the rectangle is:

1. Get the length of the rectangle.
2. Get the width of the rectangle.
3. Find the perimeter using the following equation:

```
perimeter = 2 * (length + width)
```

4. Find the area using the following equation:

```
area = length * width
```

EXAMPLE 1-2

In this example, we design an algorithm that calculates the sales tax and the price of an item sold in a particular state.

The sales tax is calculated as follows: The state's portion of the sales tax is 4%, and the city's portion of the sales tax is 1.5%. If the item is a luxury item, such as a car more than \$50,000, then there is a 10% luxury tax.

To calculate the price of the item, we need to calculate the state's portion of the sales tax, the city's portion of the sales tax, and, if it is a luxury item, the luxury tax. Suppose **salePrice** denotes the selling price of the item, **stateSalesTax** denotes the state's sales tax, **citySalesTax** denotes the city's sales tax, **luxuryTax** denotes the luxury tax, **salesTax** denotes the total sales tax, and **amountDue** denotes the final price of the item.

To calculate the sales tax, we must know the selling price of the item and whether the item is a luxury item.

The **stateSalesTax** and **citySalesTax** can be calculated using the following formulas:

```
stateSalesTax = salePrice * 0.04
citySalesTax = salePrice * 0.015
```

Next, you can determine `luxuryTax` as follows:

```
if (item is a luxury item)
    luxuryTax = salePrice * 0.1
otherwise
    luxuryTax = 0
```

Next, you can determine `salesTax` as follows:

```
salesTax = stateSalesTax + citySalesTax + luxuryTax
```

Finally, you can calculate `amountDue` as follows:

```
amountDue = salePrice + salesTax
```

The algorithm to determine `salesTax` and `amountDue` is, therefore:

1. Get the selling price of the item.
2. Determine whether the item is a luxury item.
3. Find the state's portion of the sales tax using the formula:

```
stateSalesTax = salePrice * 0.04
```

4. Find the city's portion of the sales tax using the formula:

```
citySalesTax = salePrice * 0.015
```

5. Find the luxury tax using the following formula:

```
if (item is a luxury item)
    luxuryTax = salePrice * 0.1
otherwise
    luxuryTax = 0
```

6. Find `salesTax` using the formula:

```
salesTax = stateSalesTax + citySalesTax + luxuryTax
```

7. Find `amountDue` using the formula:

```
amountDue = salePrice + salesTax
```

EXAMPLE 1-3

In this example, we design an algorithm that calculates the monthly paycheck of a salesperson at a local department store.

Every salesperson has a base salary. The salesperson also receives a bonus at the end of each month, based on the following criteria: If the salesperson has been with the store for five years or less, the bonus is \$10 for each year that he or she has worked there. If the salesperson has been with the store for more than five years, the bonus is \$20 for each year that he or she has worked there. The salesperson can earn an additional bonus as follows: If the total sales made

by the salesperson for the month are at least \$5,000 but less than \$10,000, he or she receives a 3% commission on the sale. If the total sales made by the salesperson for the month are at least \$10,000, he or she receives a 6% commission on the sale.

To calculate a salesperson's monthly paycheck, you need to know the base salary, the number of years that the salesperson has been with the company, and the total sales made by the salesperson for that month. Suppose **baseSalary** denotes the base salary, **noOfServiceYears** denotes the number of years that the salesperson has been with the store, **bonus** denotes the bonus, **totalSales** denotes the total sales made by the salesperson for the month, and **additionalBonus** denotes the additional bonus.

You can determine the bonus as follows:

```
if (noOfServiceYears is less than or equal to five)
    bonus = 10 * noOfServiceYears
otherwise
    bonus = 20 * noOfServiceYears
```

Next, you can determine the additional bonus of the salesperson as follows:

```
if (totalSales is less than 5000)
    additionalBonus = 0
otherwise
    if (totalSales is greater than or equal to 5000 and
        totalSales is less than 10000)
        additionalBonus = totalSales * (0.03)
    otherwise
        additionalBonus = totalSales * (0.06)
```

Following the above discussion, you can now design the algorithm to calculate a salesperson's monthly paycheck:

1. Get **baseSalary**.
2. Get **noOfServiceYears**.
3. Calculate bonus using the following formula:

```
if (noOfServiceYears is less than or equal to five)
    bonus = 10 * noOfServiceYears
otherwise
    bonus = 20 * noOfServiceYears
```

4. Get **totalSales**.
5. Calculate **additionalBonus** using the following formula:

```
if (totalSales is less than 5000)
    additionalBonus = 0
otherwise
    if (totalSales is greater than or equal to 5000 and
        totalSales is less than 10000)
        additionalBonus = totalSales * (0.03)
    otherwise
        additionalBonus = totalSales * (0.06)
```

6. Calculate `payCheck` using the equation:

$$\text{payCheck} = \text{baseSalary} + \text{bonus} + \text{additionalBonus}$$

EXAMPLE 1-4

In this example, we design an algorithm to play a number-guessing game.

The objective is to randomly generate an integer greater than or equal to 0 and less than 100. Then prompt the player (user) to guess the number. If the player guesses the number correctly, output an appropriate message. Otherwise, check whether the guessed number is less than the random number. If the guessed number is less than the random number generated, output the message, “Your guess is lower than the number. Guess again!”; otherwise, output the message, “Your guess is higher than the number. Guess again!”. Then prompt the player to enter another number. The player is prompted to guess the random number until the player enters the correct number.

The first step is to generate a random number, as described above. C++ provides the means to do so, which is discussed in Chapter 5. Suppose `num` stands for the random number and `guess` stands for the number guessed by the player.

After the player enters the `guess`, you can compare the `guess` with the random number as follows:

```
if (guess is equal to num)
    Print "You guessed the correct number."
otherwise
    if guess is less than num
        Print "Your guess is lower than the number. Guess again!"
    otherwise
        Print "Your guess is higher than the number. Guess again!"
```

You can now design an algorithm as follows:

1. Generate a random number and call it `num`.
2. *Repeat* the following steps until the player has guessed the correct number:
 - a. Prompt the player to enter `guess`.
 - b.

```
if (guess is equal to num)
    Print "You guessed the correct number."
otherwise
    if guess is less than num
        Print "Your guess is lower than the number. Guess again!"
    otherwise
        Print "Your guess is higher than the number. Guess again!"
```

In Chapter 5, we use this algorithm to write a C++ program to play the guessing the number game.

EXAMPLE 1-5**1**

There are 10 students in a class. Each student has taken five tests, and each test is worth 100 points. We want to design an algorithm to calculate the grade for each student, as well as the class average. The grade is assigned as follows: If the average test score is greater than or equal to 90, the grade is **A**; if the average test score is greater than or equal to 80 and less than 90, the grade is **B**; if the average test score is greater than or equal to 70 and less than 80, the grade is **C**; if the average test score is greater than or equal to 60 and less than 70, the grade is **D**; otherwise, the grade is **F**. Note that the data consists of students' names and their test scores.

This is a problem that can be divided into subproblems as follows: There are five tests, so you design an algorithm to find the average test score. Next, you design an algorithm to determine the grade. The two subproblems are to determine the average test score and to determine the grade.

Let us first design an algorithm to determine the average test score. To find the average test score, add the five test scores and then divide the sum by 5. Therefore, the algorithm is:

1. Get the five test scores.
2. Add the five test scores. Suppose **sum** stands for the sum of the test scores.
3. Suppose **average** stands for the average test score. Then:

average = **sum** / 5;

Next, you design an algorithm to determine the grade. Suppose **grade** stands for the grade assigned to a student. The following algorithm determines the grade:

```

if average is greater than or equal to 90
    grade = A
otherwise
    if average is greater than or equal to 80 and less than 90
        grade = B
    otherwise
        if average is greater than or equal to 70 and less than 80
            grade = C
        otherwise
            if average is greater than or equal to 60 and less than 70
                grade = D
            otherwise
                grade = F

```

You can use the solutions to these subproblems to design the main algorithm as follows: (Suppose **totalAverage** stands for the sum of the averages of each student's test average.)

1. **totalAverage** = 0;
2. Repeat the following steps for each student in the class:
 - a. Get student's name.
 - b. Use the algorithm as discussed above to find the average test score.

- c. Use the algorithm as discussed above to find the grade.
 - d. Update `totalAverage` by adding the current student's average test score.
3. Determine the class average as follows:

$$\text{classAverage} = \text{totalAverage} / 10$$

A programming exercise in Chapter 7 asks you to write a C++ program to determine the average test score and grade for each student in a class.

Programming Methodologies

Two popular approaches to programming design are the structured approach and the object-oriented approach, which are outlined below.

Structured Programming

Dividing a problem into smaller subproblems is called **structured design**. Each subproblem is then analyzed, and a solution is obtained to solve the subproblem. The solutions to all of the subproblems are then combined to solve the overall problem. This process of implementing a structured design is called **structured programming**. The structured-design approach is also known as **top-down design**, **bottom-up design**, **stepwise refinement**, and **modular programming**.

Object-Oriented Programming

Object-oriented design (OOD) is a widely used programming methodology. In OOD, the first step in the problem-solving process is to identify the components called objects, which form the basis of the solution, and to determine how these objects interact with one another. For example, suppose you want to write a program that automates the video rental process for a local video store. The two main objects in this problem are the video and the customer.

After identifying the objects, the next step is to specify for each object the relevant data and possible operations to be performed on that data. For example, for a video object, the *data* might include:

- movie name
- starring actors
- producer
- production company
- number of copies in stock

Some of the *operations* on a video object might include:

- checking the name of the movie
- reducing the number of copies in stock by one after a copy is rented
- incrementing the number of copies in stock by one after a customer returns a particular video

This illustrates that each object consists of data and operations on that data. An object combines data and operations on the data into a single unit. In OOD, the final program is a collection of interacting objects. A programming language that implements OOD is called an **object-oriented programming (OOP)** language. You will learn about the many advantages of OOD in later chapters.

Because an object consists of data and operations on that data, before you can design and use objects, you need to learn how to represent data in computer memory, how to manipulate data, and how to implement operations. In Chapter 2, you will learn the basic data types of C++ and discover how to represent and manipulate data in computer memory. Chapter 3 discusses how to input data into a C++ program and output the results generated by a C++ program.

To create operations, you write algorithms and implement them in a programming language. Because a data element in a complex program usually has many operations, to separate operations from each other and to use them effectively and in a convenient manner, you use functions to implement algorithms. After a brief introduction in Chapters 2 and 3, you will learn the details of functions in Chapters 6 and 7. Certain algorithms require that a program make decisions, a process called selection. Other algorithms might require certain statements to be repeated until certain conditions are met, a process called repetition. Still other algorithms might require both selection and repetition. You will learn about selection and repetition mechanisms, called control structures, in Chapters 4 and 5. Also, in Chapter 9, using a mechanism called an array, you will learn how to manipulate data when data items are of the same type, such as items in a list of sales figures.

Finally, to work with objects, you need to know how to combine data and operations on the data into a single unit. In C++, the mechanism that allows you to combine data and operations on the data into a single unit is called a class. You will learn how classes work, how to work with classes, and how to create classes in the chapter *Classes and Data Abstraction* (later in this book).

As you can see, you need to learn quite a few things before working with the OOD methodology. To make this learning easier and more effective, this book purposely divides control structures into two chapters (4 and 5) and user-defined functions into two chapters (6 and 7).

For some problems, the structured approach to program design will be very effective. Other problems will be better addressed by OOD. For example, if a problem requires manipulating sets of numbers with mathematical functions, you might use the structured design approach and outline the steps required to obtain the solution. The C++ library supplies a wealth of functions that you can use effectively to manipulate numbers. On the other hand, if you want to write a program that would make a candy machine operational, the OOD approach is more effective. C++ was designed especially to implement OOD. Furthermore, *OOD works well and is used in conjunction with structured design.*

Both the structured design and OOD approaches require that you master the basic components of a programming language to be an effective programmer. In Chapters 2 to 9, you will learn the basic components of C++, such as data types, input/output, control structures, user-defined functions, and arrays, required by either type of programming. We illustrate how these concepts work using the structured programming approach. Starting with the chapter Classes and Data Abstraction, we use the OOD approach.

ANSI/ISO Standard C++

The programming language C++ evolved from C and was designed by Bjarne Stroustrup at Bell Laboratories in the early 1980s. From the early 1980s through the early 1990s, several C++ compilers were available. Even though the fundamental features of C++ in all compilers were mostly the same, the C++ language, referred to in this book as Standard C++, was evolving in slightly different ways in different compilers. As a consequence, C++ programs were not always portable from one compiler to another.

To address this problem, in the early 1990s, a joint committee of the American National Standard Institution (ANSI) and International Standard Organization (ISO) was established to standardize the syntax of C++. In mid-1998, ANSI/ISO C++ language standards were approved. Most of today's compilers comply with these new standards.

This book focuses on the syntax of C++ as approved by ANSI/ISO, referred to as ANSI/ISO Standard C++.

QUICK REVIEW

1. A computer is an electronic device capable of performing arithmetic and logical operations.
2. A computer system has two components: hardware and software.
3. The central processing unit (CPU) and the main memory are examples of hardware components.
4. All programs must be brought into main memory before they can be executed.
5. When the power is switched off, everything in main memory is lost.
6. Secondary storage provides permanent storage for information. Hard disks, flash drives, floppy disks, ZIP disks, CD-ROMs, and tapes are examples of secondary storage.
7. Input to the computer is done via an input device. Two common input devices are the keyboard and the mouse.
8. The computer sends its output to an output device, such as the computer screen.
9. Software are programs run by the computer.
10. The operating system monitors the overall activity of the computer and provides services.

11. The most basic language of a computer is a sequence of 0s and 1s called machine language. Every computer directly understands its own machine language.
12. A bit is a binary digit, 0 or 1.
13. A byte is a sequence of eight bits.
14. A sequence of 0s and 1s is referred to as a binary code or a binary number.
15. One kilobyte (KB) is $2^{10} = 1024$ bytes; one megabyte (MB) is $2^{20} = 1,048,576$ bytes; one gigabyte (GB) is $2^{30} = 1,073,741,824$ bytes; one terabyte (TB) is $2^{40} = 1,099,511,627,776$ bytes; one petabyte (PB) is $2^{50} = 1,125,899,906,842,624$ bytes; one exabyte (EB) is $2^{60} = 1,152,921,504,606,846,976$ bytes; and one zettabyte (ZB) is $2^{70} = 1,180,591,620,717,411,303,424$ bytes.
16. Assembly language uses easy-to-remember instructions called mnemonics.
17. Assemblers are programs that translate a program written in assembly language into machine language.
18. Compilers are programs that translate a program written in a high-level language into machine code, called object code.
19. A linker links the object code with other programs provided by the integrated development environment (IDE) and used in the program to produce executable code.
20. Typically, six steps are needed to execute a C++ program: edit, preprocess, compile, link, load, and execute.
21. A loader transfers executable code into main memory.
22. An algorithm is a step-by-step problem-solving process in which a solution is arrived at in a finite amount of time.
23. The problem-solving process has three steps: analyze the problem and design an algorithm, implement the algorithm in a programming language, and maintain the program.
24. Programs written using the structured design approach are easier to understand, easier to test and debug, and easier to modify.
25. In structured design, a problem is divided into smaller subproblems. Each subproblem is solved, and the solutions to all of the subproblems are then combined to solve the problem.
26. In object-oriented design (OOD), a program is a collection of interacting objects.
27. An object consists of data and operations on that data.
28. The ANSI/ISO Standard C++ syntax was approved in mid-1998.

EXERCISES

1. Mark the following statements as true or false.
 - a. The first device known to carry out calculations was the Pascaline.
 - b. Modern-day computers can accept spoken-word instructions but cannot imitate human reasoning.

- c. In ASCII coding, every character is coded as a sequence of 8 bits.
 - d. A compiler translates a high-level program into assembly language.
 - e. The arithmetic operations are performed inside CPU, and if an error is found, it outputs the logical errors.
 - f. A sequence of 0s and 1s is called a decimal code.
 - g. A linker links and loads the object code from main memory into the CPU for execution.
 - h. Development of a C++ program includes six steps.
 - i. A program written in a high-level programming language is called a source program.
 - j. ZB stands for zero byte.
 - k. The first step in the problem-solving process is to analyze the problem.
 - l. In object-oriented design, a program is a collection of interacting functions.
2. Name two input devices.
 3. Name two output devices.
 4. Why is secondary storage needed?
 5. What is the function of an operating system?
 6. What are the two types of programs?
 7. What are the differences between machine languages and high-level languages?
 8. What is a source program?
 9. Why do you need a compiler?
 10. What kind of errors are reported by a compiler?
 11. Why do you need to translate a program written in a high-level language into machine language?
 12. Why would you prefer to write a program in a high-level language rather than a machine language?
 13. What is linking?
 14. What are the advantages of problem analysis and algorithm design over directly writing a program in a high-level language?
 15. Design an algorithm to find the weighted average of four test scores. The four test scores and their respective weights are given in the following format:

```
testscore1 weight1
...
```

For example, sample data is as follows:

```
75 0.20
95 0.35
85 0.15
65 0.30
```

16. Design an algorithm to convert the change given in quarters, dimes, nickels, and pennies into pennies.
17. Given the radius, in inches, and price of a pizza, design an algorithm to find the price of the pizza per square inch.
18. A salesperson leaves his home every Monday and returns every Friday. He travels by company car. Each day on the road, the salesperson records the amount of gasoline put in the car. Given the starting odometer reading (that is, the odometer reading before he leaves on Monday) and the ending odometer reading (the odometer reading after he returns home on Friday), design an algorithm to find the average miles per gallon. Sample data is as follows:
68723 71289 15.75 16.30 10.95 20.65 30.00
19. To make a profit, the prices of the items sold in a furniture store are marked up by 60%. Design an algorithm to find the selling price of an item sold at the furniture store. What information do you need to find the selling price?
20. Suppose a , b , and c denote the lengths of the sides of a triangle. Then the area of the triangle can be calculated using the formula:


$$\sqrt{s(s-a)(s-b)(s-c)},$$

where $s = (1/2)(a + b + c)$. Design an algorithm that uses this formula to find the area of a triangle. What information do you need to find the area?

21. Suppose that the cost of sending an international fax is calculated as follows: Service charges \$3.00; \$.20 per page for the first 10 pages; and \$0.10 for each additional page. Design an algorithm that asks the user to enter the number of pages to be faxed. The algorithm then uses the number of pages to be faxed to calculate the amount due.
22. An ATM allows a customer to withdraw a maximum of \$500 per day. If a customer withdraws more than \$300, the service charge is 4% of the amount over \$300. If the customer does not have sufficient money in the account, the ATM informs the customer about the insufficient fund and gives the option to withdraw the money for a service charge of \$25.00. If there is no money in the account or if the account balance is negative, the ATM does not allow the customer to withdraw any money. If the amount to be withdrawn is greater than \$500, the ATM informs the customer about the maximum amount that can be withdrawn. Write an algorithm that allows the customer to enter the amount to be withdrawn. The algorithm then checks the total amount in the account, dispenses the money to the customer, and debits the account by the amount withdrawn and the service charges, if any.
23. You are given a list of students' names and their test scores. Design an algorithm that does the following:
 - a. Calculates the average test scores.
 - b. Determines and prints the names of all the students whose test scores are below the average test score.

- c. Determines the highest test score.
- d. Prints the names of all the students whose test scores are the same as the highest test score.

(You must divide this problem into subproblems as follows: The first subproblem determines the average test score. The second subproblem determines and prints the names of all the students whose test scores are below the average test score. The third subproblem determines the highest test score. The fourth subproblem prints the names of all the students whose test scores are the same as the highest test score. The main algorithm combines the solutions of the subproblems.)



CHAPTER 2

BASIC ELEMENTS OF C++

IN THIS CHAPTER, YOU WILL:

- Become familiar with the basic components of a C++ program, including functions, special symbols, and identifiers
- Explore simple data types
- Discover how to use arithmetic operators
- Examine how a program evaluates arithmetic expressions
- Learn what an assignment statement is and what it does
- Become familiar with the `string` data type
- Discover how to input data into memory using input statements
- Become familiar with the use of increment and decrement operators
- Examine ways to output results using output statements
- Learn how to use preprocessor directives and why they are necessary
- Learn how to debug syntax errors
- Explore how to properly structure a program, including using comments to document a program
- Learn how to write a C++ program

In this chapter, you will learn the basics of C++. As your objective is to learn the C++ programming language, two questions naturally arise. First, what is a computer program? Second, what is programming? A **computer program**, or a program, is a sequence of statements whose objective is to accomplish a task. **Programming** is a process of planning and creating a program. These two definitions tell the truth, but not the whole truth, about programming. It may very well take an entire book to give a good and satisfactory definition of programming. You might gain a better grasp of the nature of programming from an analogy, so let us turn to a topic about which almost everyone has some knowledge—cooking. A recipe is also a program, and everyone with some cooking experience can agree on the following:

1. It is usually easier to follow a recipe than to create one.
2. There are good recipes and there are bad recipes.
3. Some recipes are easy to follow and some are not easy to follow.
4. Some recipes produce reliable results and some do not.
5. You must have some knowledge of how to use cooking tools to follow a recipe to completion.
6. To create good new recipes, you must have much knowledge and understanding of cooking.

These same six points are also true about programming. Let us take the cooking analogy one step further. Suppose you need to teach someone how to become a chef. How would you go about it? Would you first introduce the person to good food, hoping that a taste for good food develops? Would you have the person follow recipe after recipe in the hope that some of it rubs off? Or would you first teach the use of tools and the nature of ingredients, the foods and spices, and explain how they fit together? Just as there is disagreement about how to teach cooking, there is disagreement about how to teach programming.

Learning a programming language is like learning to become a chef or learning to play a musical instrument. All three require direct interaction with the tools. You cannot become a good chef or even a poor chef just by reading recipes. Similarly, you cannot become a player by reading books about musical instruments. The same is true of programming. You must have a fundamental knowledge of the language, and you must test your programs on the computer to make sure that each program does what it is supposed to do.

A C++ Program

In this chapter, you will learn the basic elements and concepts of the C++ programming language to create C++ programs. In addition to giving examples to illustrate various concepts, we will also show C++ programs to clarify them. In this section, we provide an example of a C++ program. At this point, you need not be too concerned with the details of this program. You only need to know the effect of an *output* statement, which is introduced in this program.

Consider the C++ program in Example 2-1.

EXAMPLE 2-1

```
//*****
// This is a simple C++ program. It displays four lines
// of text, including the sum of two numbers.
//*****

#include <iostream>

using namespace std;

int main()
{
    int num;

    num = 6;

    cout << "My first C++ program." << endl;
    cout << "The sum of 2 and 3 = " << 5 << endl;
    cout << "7 + 8 = " << 7 + 8 << endl;
    cout << "Num = " << num << endl;

    return 0;
}
```

Sample Run: (When you compile and execute this program, the following four lines are displayed on the screen.)

```
My first C++ program.
The sum of 2 and 3 = 5
7 + 8 = 15
Num = 6
```

These lines are displayed by the execution of the following three statements.

```
cout << "My first C++ program." << endl;
cout << "The sum of 2 and 3 = " << 5 << endl;
cout << "7 + 8 = " << 7 + 8 << endl;
cout << "Num = " << num << endl;
```

Next, we explain how this happens. Let us first consider the following statement:

```
cout << "My first C++ program." << endl;
```

This is an example of a C++ *output* statement. It causes the computer to evaluate the *expression* after the pair of symbols << and display the result on the screen.

Usually, a C++ program contains various types of expressions such as arithmetic and strings. For example, $7 + 8$ is an arithmetic expression. Anything in double quotes is a *string*. For example, "My first C++ program." and "7 + 8 = " are strings. Typically, a string evaluates to itself. Arithmetic expressions are evaluated according to rules of arithmetic operations, which you typically learn in an algebra course. Later in this chapter, we explain how arithmetic expressions and strings are formed and evaluated.

Also note that in an output statement, `endl` *causes the insertion point to move to the beginning of the next line.* (On the screen, the insertion point is where the cursor is.) Therefore, the preceding statement causes the system to display the following line on the screen.

My first C++ program.

Let us now consider the following statement.

```
cout << "The sum of 2 and 3 = " << 5 << endl;
```

This output statement consists of two expressions. The first expression (after the first `<<`) is `"The sum of 2 and 3 = "` and the second expression (after the second `<<`) consists of the number 5. The expression `"The sum of 2 and 3 = "` is a string and evaluates to itself. (Notice the space after `=`.) The second expression, which consists of the number 5 evaluates to 5. Thus, the output of the preceding statement is:

```
The sum of 2 and 3 = 5
```

Let us now consider the following statement.

```
cout << "7 + 8 = " << 7 + 8 << endl;
```

In this output statement, the expression `"7 + 8 = "`, which is a string, evaluates to itself. Let us consider the second expression, `7 + 8`. This expression consists of the numbers 7 and 8 and the C++ arithmetic operator `+`. Therefore, the result of the expression `7 + 8` is the sum of 7 and 8, which is 15. Thus, the output of the preceding statement is:

```
7 + 8 = 15
```

Finally, consider the statement:

```
cout << "Num = " << num << endl;
```

This statement consists of the string `"Num = "`, which evaluates to itself, and the word `num`. The statement `num = 6;` assigns the value 6 to `num`. Therefore, the expression `num`, after the second `<<`, evaluates to 6. It now follows that the output of the previous statement is:

```
Num = 6
```

The last statement, that is,

```
return 0;
```

returns the value 0 to the operating system when the program terminates. We will elaborate on this statement later in this chapter.

In the next chapter, until we explain how to properly construct a C++ program, we will be using output statements such as the preceding ones to explain various concepts. After finishing Chapter 2, you should be able to write C++ programs well enough to do some computations and show results.

Before leaving this section, let us note the following about the previous C++ program. A C++ program is a collection of functions, one of which is the function `main`. Roughly

speaking, a **function** is a collection of statements, and when it is executed, it accomplishes something. The preceding program consists of the function `main`.

The first line of the program, that is,

```
#include <iostream>
```

allows us to use the (predefined object) `cout` to generate output and the (manipulator) `endl`. The second line, which is

```
using namespace std;
```

allows you to use `cout` and `endl` without the prefix `std::`. It means that if you do not include this statement, then `cout` should be used as `std::cout` and `endl` should be used as `std::endl`. We will elaborate on this later in this chapter.

The seventh line consists of the following:

```
int main()
```

This is the heading of the function `main`. The eighth line consists of a left brace. This marks the beginning of the (body) of the function `main`. The right brace (at the last line of the program) matches this left brace and marks the end of the body of the function `main`. We will explain the meaning of the other terms, such as those shown in blue, later in this book. Note that in C++, `<<` is an operator, called the *stream insertion operator*.

The Basics of a C++ Program

A C++ program is a collection of one or more subprograms, called functions. Some functions, called **predefined** or **standard** functions, are already written and are provided as part of the system. But to accomplish most tasks, programmers must learn to write their own functions.

Every C++ program has a function called `main`. Thus, if a C++ program has only one function, it must be the function `main`. Until Chapter 6, other than using some of the predefined functions, you will mainly deal with the function `main`. By the end of this chapter, you will have learned how to write the function `main`.

If you have never seen a program written in a programming language, the C++ program in Example 2-1 may look like a foreign language. To make meaningful sentences in a foreign language, you must learn its alphabet, words, and grammar. The same is true of a programming language. To write meaningful programs, you must learn the programming language's special symbols, words, and syntax rules. The **syntax rules** tell you which statements (instructions) are legal, or accepted by the programming language, and which are not. You must also learn **semantic rules**, which determine the meaning of the instructions. The programming language's rules, symbols, and special words enable you to write programs to solve problems. The syntax rules determine which instructions are valid.

Programming language: A set of rules, symbols, and special words.

In the remainder of this section, you will learn about some of the special symbols of a C++ program. Additional special symbols are introduced as other concepts are encountered in later chapters. Similarly, syntax and semantic rules are introduced and discussed throughout the book.

Comments

The program that you write should be clear not only to you, but also to the reader of your program. Part of good programming is the inclusion of comments in the program. Typically, comments can be used to identify the authors of the program, give the date when the program is written or modified, give a brief explanation of the program, and explain the meaning of key statements in a program. In the programming examples, for the programs that we write, we will not include the date when the program is written, consistent with the standard convention for writing such books.

Comments are for the reader, not for the compiler. So when a compiler compiles a program to check for the syntax errors, it completely ignores comments. Throughout this book, comments are shown in green.

The program in Example 2-1 contains the following comments:

```
// This is a C++ program. It prints the sentence:
// Welcome to C++ Programming.
```

There are two common types of comments in a C++ program—single-line comments and multiple-line comments.

Single-line comments begin with `//` and can be placed anywhere in the line. Everything encountered in that line after `//` is ignored by the compiler. For example, consider the following statement:

```
cout << "7 + 8 = " << 7 + 8 << endl;
```

You can put comments at the end of this line as follows:

```
cout << "7 + 8 = " << 7 + 8 << endl; //prints: 7 + 8 = 15
```

This comment could be meaningful for a beginning programmer.

Multiple-line comments are enclosed between `/*` and `*/`. The compiler ignores anything that appears between `/*` and `*/`. For example, the following is an example of a multiple-line comment:

```
/*
    You can include comments that can
    occupy several lines.
*/
```

Special Symbols

The smallest individual unit of a program written in any language is called a **token**. C++'s tokens are divided into special symbols, word symbols, and identifiers.

Following are some of the special symbols:

```
+      -      *      /
.      ;      ?      ,
<=     !=     ==     >=
```

The first row includes mathematical symbols for addition, subtraction, multiplication, and division. The second row consists of punctuation marks taken from English grammar. Note that the comma is also a special symbol. In C++, commas are used to separate items in a list. Semicolons are used to end a C++ statement. Note that a blank, which is not shown above, is also a special symbol. You create a blank symbol by pressing the space bar (only once) on the keyboard. The third row consists of tokens made up of two characters that are regarded as a single symbol. No character can come between the two characters in the token, not even a blank.

Reserved Words (Keywords)

A second category of tokens is word symbols. Some of the word symbols include the following:

`int`, `float`, `double`, `char`, `const`, `void`, `return`

Reserved words are also called **keywords**. The letters that make up a reserved word are always lowercase. Like the special symbols, each is considered to be a single symbol. Furthermore, word symbols cannot be redefined within any program; that is, they cannot be used for anything other than their intended use. For a complete list of reserved words, see Appendix A.

NOTE

Throughout this book, reserved words are shown in blue.

Identifiers

A third category of tokens is identifiers. Identifiers are names of things that appear in programs, such as variables, constants, and functions. All identifiers must obey C++'s rules for identifiers.

Identifier: A C++ identifier consists of letters, digits, and the underscore character (`_`) and must begin with a letter or underscore.

Some identifiers are predefined; others are defined by the user. In the C++ program in Example 2-1, `cout` is a predefined identifier and `num` is a user-defined identifier. Two predefined identifiers that you will encounter frequently are `cout` and `cin`. You have already seen the effect of `cout`. Later in this chapter, you will learn how `cin`, which is used to input data, works. Unlike reserved words, predefined identifiers can be redefined, but it would not be wise to do so.

Identifiers can be made of only letters, digits, and the underscore character; no other symbols are permitted to form an identifier.

NOTE C++ is case sensitive—uppercase and lowercase letters are considered different. Thus, the identifier **NUMBER** is not the same as the identifier **number**. Similarly, the identifiers **X** and **x** are different.

In C++, identifiers can be of any length.

EXAMPLE 2-2

The following are legal identifiers in C++:

```
first
conversion
payRate
counter1
```

Table 2-1 shows some illegal identifiers and explains why they are illegal.

TABLE 2-1 Examples of Illegal Identifiers

| Illegal Identifier | Description |
|--------------------|-------------------------------------------------------------------|
| employee Salary | There can be no space between employee and Salary . |
| Hello! | The exclamation mark cannot be used in an identifier. |
| one + two | The symbol + cannot be used in an identifier. |
| 2nd | An identifier cannot begin with a digit. |

NOTE Compiler vendors usually begin certain identifiers with an underscore (**_**). When the linker links the object program with the system resources provided by the integrated development environment (IDE), certain errors could occur. Therefore, it is advisable that you should not begin identifiers in your program with an underscore (**_**).

Whitespaces

Every C++ program contains whitespaces. Whitespaces include blanks, tabs, and newline characters. In a C++ program, whitespaces are used to separate special symbols, reserved words, and identifiers. Whitespaces are nonprintable in the sense that when they are printed on a white sheet of paper, the space between special symbols, reserved words, and identifiers is white. Proper utilization of whitespaces in a program is important. They can be used to make the program readable.

Data Types

The objective of a C++ program is to manipulate data. Different programs manipulate different data. A program designed to calculate an employee's paycheck will add, subtract, multiply, and divide numbers, and some of the numbers might represent hours worked and pay rate. Similarly, a program designed to alphabetize a class list will manipulate names. You wouldn't expect a cherry pie recipe to help you bake cookies. Similarly, you wouldn't use a program designed to perform arithmetic calculations to manipulate alphabetic characters. Furthermore, you wouldn't multiply or subtract names. Reflecting these kinds of underlying differences, C++ categorizes data into different types, and only certain operations can be performed on particular types of data. Although at first it may seem confusing, by being so type conscious, C++ has built-in checks to guard against errors.

Data type: A set of values together with a set of operations.

C++ data types fall into the following three categories and are illustrated in Figure 2-1:

1. Simple data type
2. Structured data type
3. Pointers




FIGURE 2-1 C++ data types

For the next few chapters, you will be concerned only with simple data types.

Simple Data Types

The simple data type is the fundamental data type in C++ because it becomes a building block for the structured data type, which you start learning about in Chapter 9. There are three categories of simple data:

1. **Integral**, which is a data type that deals with integers, or numbers without a decimal part
2. **Floating-point**, which is a data type that deals with decimal numbers
3. **Enumeration**, which is a user-defined data type

NOTE

The enumeration type is C++'s method for allowing programmers to create their own simple data types. This data type will be discussed in Chapter 8.

Integral data types are further classified into the following nine categories: `char`, `short`, `int`, `long`, `bool`, `unsigned char`, `unsigned short`, `unsigned int`, and `unsigned long`.

Why are there so many categories of the same data type? Every data type has a different set of values associated with it. For example, the `char` data type is used to represent integers between -128 and 127 . The `int` data type is used to represent integers between -2147483648 and 2147483647 , and the data type `short` is used to represent integers between -32768 and 32767 .

Note that the identifier `num` in Example 2-1 can be assigned any value belonging to the `int` data type.

Which data type you use depends on how big a number your program needs to deal with. In the early days of programming, computers and main memory were very expensive. Only a small amount of memory was available to execute programs and manipulate the data. As a result, programmers had to optimize the use of memory. Because writing a program and making it work is already a complicated process, not having to worry about the size of the memory makes for one less thing to think about. Thus, to effectively use memory, a programmer can look at the type of data used in a program and figure out which data type to use.

Newer programming languages have only five categories of simple data types: `integer`, `real`, `char`, `bool`, and the enumeration type. The integral data types that are used in this book are `int`, `bool`, and `char`.

Table 2-2 gives the range of possible values associated with these three data types and the size of memory allocated to manipulate these values.

TABLE 2-2 Values and Memory Allocation for Three Simple Data Types

| Data Type | Values | Storage (in bytes) |
|-------------------|------------------------------------------|--------------------|
| <code>int</code> | -2147483648 to 2147483647 | 4 |
| <code>bool</code> | <code>true</code> and <code>false</code> | 1 |
| <code>char</code> | -128 to 127 | 1 |

NOTE

Use this table only as a guide. Different compilers may allow different ranges of values. Check your compiler's documentation. To find the exact size of the integral data types on a particular system, you can run a program given in Appendix G (Memory Size of a System). Furthermore, to find the maximum and minimum values of these data types, you can run another program given in Appendix F (Header File `climits`).

int DATA TYPE

This section describes the `int` data type. This discussion also applies to other integral data types.

Integers in C++, as in mathematics, are numbers such as the following:

`-6728, -67, 0, 78, 36782, +763`

Note the following two rules from these examples:

1. Positive integers do not need a `+` sign in front of them.
2. No commas are used within an integer. Recall that in C++, commas are used to separate items in a list. So `36,782` would be interpreted as two integers: `36` and `782`.

bool DATA TYPE

The data type `bool` has only two values: `true` and `false`. Also, `true` and `false` are called the *logical (Boolean) values*. The central purpose of this data type is to manipulate logical (Boolean) expressions. Logical (Boolean) expressions will be formally defined and discussed in detail in Chapter 4. In C++, `bool`, `true`, and `false` are reserved words.

char DATA TYPE

The data type `char` is the smallest integral data type. It is mainly used to represent characters—that is, letters, digits, and special symbols. Thus, the `char` data type can represent every key on your keyboard. When using the `char` data type, you enclose each character represented within single quotation marks. Examples of values belonging to the `char` data type include the following:

`'A', 'a', '0', '*', '+', '$', '&', ' '`

Note that a blank space is a character and is written as `' '`, with a space between the single quotation marks.

The data type `char` allows only one symbol to be placed between the single quotation marks. Thus, the value `'abc'` is not of the type `char`. Furthermore, even though `'!='` and similar special symbols are considered to be one symbol, they are not regarded as possible values of the data type `char`. All the individual symbols located on the keyboard that are printable may be considered as possible values of the `char` data type.

Several different character data sets are currently in use. The most common are the American Standard Code for Information Interchange (ASCII) and Extended Binary-Coded Decimal Interchange Code (EBCDIC). The ASCII character set has 128 values. The EBCDIC character set has 256 values and was created by IBM. Both character sets are described in Appendix C.

Each of the 128 values of the ASCII character set represents a different character. For example, the value `65` represents `'A'`, and the value `43` represents `'+'`. Thus, each

character has a predefined ordering, which is called a **collating sequence**, in the set. The collating sequence is used when you compare characters. For example, the value representing 'B' is 66, so 'A' is smaller than 'B'. Similarly, '+' is smaller than 'A' because 43 is smaller than 65.

The 14th character in the ASCII character set is called the newline character and is represented as '\n'. (Note that the position of the newline character in the ASCII character set is 13 because the position of the first character is 0.) Even though the newline character is a combination of two characters, it is treated as one character. Similarly, the horizontal tab character is represented in C++ as '\t' and the null character is represented as '\0' (backslash followed by zero). Furthermore, the first 32 characters in the ASCII character set are nonprintable. (See Appendix C for a description of these characters.)

Floating-Point Data Types

To deal with decimal numbers, C++ provides the floating-point data type, which we discuss in this section. To facilitate the discussion, let us review a concept from a high school or college algebra course.

You may be familiar with scientific notation. For example:

```
43872918 = 4.3872918 * 107      {10 to the power of seven}
.0000265 = 2.65 * 10-5         {10 to the power of minus five}
47.9832 = 4.79832 * 101       {10 to the power of one}
```

To represent real numbers, C++ uses a form of scientific notation called **floating-point notation**. Table 2-3 shows how C++ might print a set of real numbers using one machine's interpretation of floating-point notation. In the C++ floating-point notation, the letter E stands for the exponent.

TABLE 2-3 Examples of Real Numbers Printed in C++ Floating-Point Notation

| Real Number | C++ Floating-Point Notation |
|-------------|-----------------------------|
| 75.924 | 7.592400E1 |
| 0.18 | 1.800000E-1 |
| 0.0000453 | 4.530000E-5 |
| -1.482 | -1.482000E0 |
| 7800.0 | 7.800000E3 |

C++ provides three data types to manipulate decimal numbers: **float**, **double**, and **long double**. As in the case of integral data types, the data types **float**, **double**, and **long double** differ in the set of values.

NOTE

On most newer compilers, the data types `double` and `long double` are the same. Therefore, only the data types `float` and `double` are described here.

float: The data type `float` is used in C++ to represent any real number between $-3.4\text{E}+38$ and $3.4\text{E}+38$. The memory allocated for a value of the `float` data type is four bytes.

double: The data type `double` is used in C++ to represent any real number between $-1.7\text{E}+308$ and $1.7\text{E}+308$. The memory allocated for a value of the `double` data type is eight bytes.

The maximum and minimum values of the data types `float` and `double` are system dependent. To find these values on a particular system, you can check your compiler's documentation or, alternatively, you can run a program given in Appendix F (Header File `cfloat`).

Other than the set of values, there is one more difference between the data types `float` and `double`. The maximum number of significant digits—that is, the number of decimal places—in `float` values is six or seven. The maximum number of significant digits in values belonging to the `double` type is 15.

NOTE

For values of the `double` type, for better precision, some compilers might give more than 15 significant digits. Check your compiler's documentation.

The maximum number of significant digits is called the **precision**. Sometimes `float` values are called **single precision**, and values of type `double` are called **double precision**. If you are dealing with decimal numbers, for the most part you need only the `float` type; if you need accuracy to more than six or seven decimal places, you can use the `double` type.

NOTE

In C++, by default, floating-point numbers are considered of type `double`. Therefore, if you use the data type `float` to manipulate floating-point numbers in a program, certain compilers might give you a warning message, such as “truncation from double to float.” To avoid such warning messages, you should use the `double` data type. For illustration purposes and to avoid such warning messages in programming examples, this book mostly uses the data type `double` to manipulate floating-point numbers.

Arithmetic Operators and Operator Precedence

One of the most important uses of a computer is its ability to calculate. You can use the standard arithmetic operators to manipulate integral and floating-point data types. There are five arithmetic operators.

Arithmetic Operators: + (addition), - (subtraction or negation), * (multiplication), / (division), % (mod, (modulus or remainder)).

You can use the operators +, -, *, and / with both integral and floating-point data types. You use % with only the integral data type to find the remainder in ordinary division. When you use / with the integral data type, it gives the quotient in ordinary division. That is, integral division truncates any fractional part; there is no rounding.

Since high school, you have been accustomed to working with arithmetic expressions such as the following:

- i. -5
- ii. 8 - 7
- iii. 3 + 4
- iv. 2 + 3 * 5
- v. 5.6 + 6.2 * 3
- vi. $x + 2 * 5 + 6 / y$

(Note that in expression (vi), x and y are unknown numbers.) Formally, an **arithmetic expression** is constructed by using arithmetic operators and numbers. The numbers appearing in the expression are called **operands**. The numbers that are used to evaluate an operator are called the operands for that operator. In expression (i), the symbol - specifies that the number 5 is negative. In this expression, - has only one operand. Operators that have only one operand are called **unary operators**.

In expression (ii), the symbol - is used to subtract 7 from 8. In this expression, - has two operands, 8 and 7. Operators that have two operands are called **binary operators**.

Unary operator: An operator that has only one operand.

Binary operator: An operator that has two operands.

In expression (iii), that is, 3 + 4, 3 and 4 are the operands for the operator +. In this expression, the operator + has two operands and is a binary operator. Now consider the following expression:

+27

In this expression, the operator + indicates that the number 27 is positive. Here, + has only one operand and so acts as a unary operator.

From the preceding discussion, it follows that - and + are both unary and binary arithmetic operators. However, as arithmetic operators, *, /, and % are binary and so must have two operands.

The following examples show how arithmetic operators—especially / and %—work with integral data types. As you can see from these examples, the operator / represents the quotient in ordinary division when used with integral data types.

EXAMPLE 2-3

| Arithmetic Expression | Result | Description |
|-----------------------|--------|----------------------------------------------------------------------------------------------------------------------------------------------------------|
| $2 + 5$ | 7 | |
| $13 + 89$ | 102 | |
| $34 - 20$ | 14 | |
| $45 - 90$ | -45 | |
| $2 * 7$ | 14 | |
| $5 / 2$ | 2 | In the division $5 / 2$, the quotient is 2 and the remainder is 1. Therefore, $5 / 2$ with the integral operands evaluates to the quotient, which is 2. |
| $14 / 7$ | 2 | |
| $34 \% 5$ | 4 | In the division $34 / 5$, the quotient is 6 and the remainder is 4. Therefore, $34 \% 5$ evaluates to the remainder, which is 4. |
| $4 \% 6$ | 4 | In the division $4 / 6$, the quotient is 0 and the remainder is 4. Therefore, $4 \% 6$ evaluates to the remainder, which is 4. |

The following C++ program evaluates the preceding expressions:

```
// This program illustrates how integral expressions are
// evaluated.

#include <iostream>

using namespace std;

int main()
{
    cout << "2 + 5 = " << 2 + 5 << endl;
    cout << "13 + 89 = " << 13 + 89 << endl;
    cout << "34 - 20 = " << 34 - 20 << endl;
    cout << "45 - 90 = " << 45 - 90 << endl;
    cout << "2 * 7 = " << 2 * 7 << endl;
    cout << "5 / 2 = " << 5 / 2 << endl;
    cout << "14 / 7 = " << 14 / 7 << endl;
    cout << "34 % 5 = " << 34 % 5 << endl;
    cout << "4 % 6 = " << 4 % 6 << endl;

    return 0;
}
```

Sample Run:

```
2 + 5 = 7
13 + 89 = 102
34 - 20 = 14
45 - 90 = -45
2 * 7 = 14
```

```

5 / 2 = 2
14 / 7 = 2
34 % 5 = 4
4 % 6 = 4

```

NOTE

You should be careful when evaluating the mod operator with negative integer operands. You might not get the answer you expect. For example, $-34 \% 5 = -4$, because in the division $-34 / 5$, the quotient is -6 and the remainder is -4 . Similarly, $34 \% -5 = 4$, because in the division $-34 / 5$, the quotient is -6 and the remainder is 4 . Also, $-34 \% -5 = -4$, because in the division $-34 / -5$, the quotient is 6 and the remainder is -4 .

The following example shows how arithmetic operators work with floating-point numbers.

EXAMPLE 2-4

The following C++ program evaluates various floating-point expressions. (The details of how the expressions are evaluated are left as an exercise for you.)

```
// This program illustrates how floating-point expressions
// are evaluated.
```

```
#include <iostream>

using namespace std;

int main()
{
    cout << "5.0 + 3.5 = " << 5.0 + 3.5 << endl;
    cout << "3.0 + 9.4 = " << 3.0 + 9.4 << endl;
    cout << "16.3 - 5.2 = " << 16.3 - 5.2 << endl;
    cout << "4.2 * 2.5 = " << 4.2 * 2.5 << endl;
    cout << "5.0 / 2.0 = " << 5.0 / 2.0 << endl;
    cout << "34.5 / 6.0 = " << 34.5 / 6.0 << endl;
    cout << "34.5 / 6.5 = " << 34.5 / 6.5 << endl;

    return 0;
}
```

Sample Run:

```

5.0 + 3.5 = 8.5
3.0 + 9.4 = 12.4
16.3 - 5.2 = 11.1
4.2 * 2.5 = 10.5
5.0 / 2.0 = 2.5
34.5 / 6.0 = 5.75
34.5 / 6.5 = 5.30769

```

Order of Precedence

When more than one arithmetic operator is used in an expression, C++ uses the operator precedence rules to evaluate the expression. According to the order of precedence rules for arithmetic operators,

\ast , $/$, $\%$

are at a higher level of precedence than:

$+$, $-$

Note that the operators \ast , $/$, and $\%$ have the same level of precedence. Similarly, the operators $+$ and $-$ have the same level of precedence.

When operators have the same level of precedence, the operations are performed from left to right. To avoid confusion, you can use parentheses to group arithmetic expressions. For example, using the order of precedence rules,

$3 \ast 7 - 6 + 2 \ast 5 / 4 + 6$

means the following:

| | |
|----------------------------------------------|---------------------------------------------------------|
| $(((3 \ast 7) - 6) + ((2 \ast 5) / 4)) + 6$ | |
| $= ((21 - 6) + (10 / 4)) + 6$ | (Evaluate \ast) |
| $= ((21 - 6) + 2) + 6$ | (Evaluate $/$. Note that this is an integer division.) |
| $= (15 + 2) + 6$ | (Evaluate $-$) |
| $= 17 + 6$ | (Evaluate first $+$) |
| $= 23$ | (Evaluate $+$) |

Note that the use of parentheses in the second example clarifies the order of precedence. You can also use parentheses to override the order of precedence rules (see Example 2-5).

EXAMPLE 2-5

In the expression:

$3 + 4 \ast 5$

\ast is evaluated before $+$. Therefore, the result of this expression is 23. On the other hand, in the expression:

$(3 + 4) \ast 5$

$+$ is evaluated before \ast and the result of this expression is 35.

Because arithmetic operators are evaluated from left to right, unless parentheses are present, the **associativity** of the arithmetic operators is said to be from left to right.

NOTE

(Character Arithmetic) Because the `char` data type is also an integral data type, C++ allows you to perform arithmetic operations on `char` data. However, you should use this ability carefully. There is a difference between the character `'8'` and the integer `8`. The integer value of `8` is `8`. The integer value of `'8'` is `56`, which is the ASCII collating sequence of the character `'8'`.

When evaluating arithmetic expressions, `8 + 7 = 15`; `'8' + '7' = 56 + 55`, which yields `111`; and `'8' + 7 = 56 + 7`, which yields `63`. Furthermore, because `'8' * '7' = 56 * 55 = 3080` and the ASCII character set has only 128 values, `'8' * '7'` is undefined in the ASCII character data set.

These examples illustrate that many things can go wrong when you are performing character arithmetic. If you must employ them, use arithmetic operations on the `char` data type with caution.

Expressions

To this point, we have discussed only arithmetic operators. In this section, we now discuss arithmetic expressions in detail. Arithmetic expressions were introduced in the last section.

If all operands (that is, numbers) in an expression are integers, the expression is called an **integral expression**. If all operands in an expression are floating-point numbers, the expression is called a **floating-point** or **decimal expression**. An integral expression yields an integral result; a floating-point expression yields a floating-point result. Looking at some examples will help clarify these definitions.

EXAMPLE 2-6

Consider the following C++ integral expressions:

```
2 + 3 * 5
3 + x - y / 7
x + 2 * (y - z) + 18
```

In these expressions, `x`, `y`, and `z` represent variables of the integer type; that is, they can hold integer values. Variables are discussed later in this chapter.

EXAMPLE 2-7

Consider the following C++ floating-point expressions:

```
12.8 * 17.5 - 34.50
x * 10.5 + y - 16.2
```

Here, `x` and `y` represent variables of the floating-point type; that is, they can hold floating-point values. Variables are discussed later in this chapter.

Evaluating an integral or a floating-point expression is straightforward. As before, when operators have the same precedence, the expression is evaluated from left to right. You can always use parentheses to group operands and operators to avoid confusion.

Mixed Expressions

An expression that has operands of different data types is called a **mixed expression**. A mixed expression contains both integers and floating-point numbers. The following expressions are examples of mixed expressions:

$2 + 3.5$

$6 / 4 + 3.9$

$5.4 * 2 - 13.6 + 18 / 2$

In the first expression, the operand $+$ has one integer operand and one floating-point operand. In the second expression, both operands for the operator $/$ are integers, the first operand of $+$ is the result of $6 / 4$, and the second operand of $+$ is a floating-point number. The third example is an even more complicated mix of integers and floating-point numbers. The obvious question is: How does C++ evaluate mixed expressions?

Two rules apply when evaluating a mixed expression:

1. When evaluating an operator in a mixed expression:
 - a. If the operator has the same types of operands (that is, either both integers or both floating-point numbers), the operator is evaluated according to the type of the operands. Integer operands thus yield an integer result; floating-point numbers yield a floating-point number.
 - b. If the operator has both types of operands (that is, one is an integer and the other is a floating-point number), then during calculation, the integer is changed to a floating-point number with the decimal part of zero and the operator is evaluated. The result is a floating-point number.
2. The entire expression is evaluated according to the precedence rules; the multiplication, division, and modulus operators are evaluated before the addition and subtraction operators. Operators having the same level of precedence are evaluated from left to right. Grouping is allowed for clarity.

From these rules, it follows that when evaluating a mixed expression, you concentrate on one operator at a time, using the rules of precedence. If the operator to be evaluated has operands of the same data type, evaluate the operator using Rule 1(a). That is, an operator with integer operands will yield an integer result, and an operator with floating-point operands will yield a floating-point result. If the operator to be evaluated has one integer operand and one floating-point operand, before evaluating this operator, convert the integer operand to a floating-point number with the decimal part of 0. The following examples show how to evaluate mixed expressions.

EXAMPLE 2-8

| Mixed Expression | Evaluation | Rule Applied |
|------------------------|--------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------|
| $3 / 2 + 5.5$ | $= 1 + 5.5$ $= 6.5$ | $3 / 2 = 1$ (integer division; Rule 1(a)) $(1 + 5.5$ $= 1.0 + 5.5$ (Rule 1(b)) $= 6.5)$ |
| $15.6 / 2 + 5$ | $= 7.8 + 5$ $= 12.8$ | $15.6 / 2$ $= 15.6 / 2.0$ (Rule 1(b)) $= 7.8$ $7.8 + 5$ $= 7.8 + 5.0$ (Rule 1(b)) $= 12.8$ |
| $4 + 5 / 2.0$ | $= 4 + 2.5$ $= 6.5$ | $5 / 2.0 = 5.0 / 2.0$ (Rule 1(b)) $= 2.5$ $4 + 2.5 = 4.0 + 2.5$ (Rule 1(b)) $= 6.5$ |
| $4 * 3 + 7 / 5 - 25.5$ | $= 12 + 7 / 5 - 25.5$ $= 12 + 1 - 25.5$ $= 13 - 25.5$ $= -12.5$ | $4 * 3 = 12$; (Rule 1(a)) $7 / 5 = 1$ (integer division; Rule 1(a)) $12 + 1 = 13$; (Rule 1(a)) $13 - 25.5 = 13.0 - 25.5$ (Rule 1(b)) $= -12.5$ |

The following C++ program evaluates the preceding expressions:

// This program illustrates how mixed expressions are evaluated.

```
#include <iostream>
using namespace std;
int main()
{
    cout << "3 / 2 + 5.5 = " << 3 / 2 + 5.5 << endl;
    cout << "15.6 / 2 + 5 = " << 15.6 / 2 + 5 << endl;
    cout << "4 + 5 / 2.0 = " << 4 + 5 / 2.0 << endl;
    cout << "4 * 3 + 7 / 5 - 25.5 = "
        << 4 * 3 + 7 / 5 - 25.5
        << endl;

    return 0;
}
```

Sample Run:

```
3 / 2 + 5.5 = 6.5
15.6 / 2 + 5 = 12.8
4 + 5 / 2.0 = 6.5
4 * 3 + 7 / 5 - 25.5 = -12.5
```

These examples illustrate that an integer is not converted to a floating-point number unless the operator to be evaluated has one integer and one floating-point operand.

Type Conversion (Casting)

In the previous section, you learned that when evaluating an arithmetic expression, if the operator has mixed operands, the integer value is changed to a floating-point value with the zero decimal part. When a value of one data type is automatically changed to another data type, an **implicit type coercion** is said to have occurred. As the examples in the preceding section illustrate, if you are not careful about data types, implicit type coercion can generate unexpected results.

To avoid implicit type coercion, C++ provides for explicit type conversion through the use of a cast operator. The **cast operator**, also called **type conversion** or **type casting**, takes the following form:

```
static_cast<dataTypeName> (expression)
```

First, the expression is evaluated. Its value is then converted to a value of the type specified by `dataTypeName`. In C++, `static_cast` is a reserved word.

When converting a floating-point (decimal) number to an integer using the cast operator, you simply drop the decimal part of the floating-point number. That is, the floating-point number is truncated. Example 2-9 shows how cast operators work. Be sure you understand why the last two expressions evaluate as they do.

EXAMPLE 2-9

| Expression | Evaluates to |
|------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------|
| <code>static_cast<int> (7.9)</code> | 7 |
| <code>static_cast<int> (3.3)</code> | 3 |
| <code>static_cast<double> (25)</code> | 25.0 |
| <code>static_cast<double> (5 + 3)</code> | = <code>static_cast<double> (8)</code> = 8.0 |
| <code>static_cast<double> (15) / 2</code> | = 15.0 / 2 (because <code>static_cast<double> (15)</code> = 15.0) = 15.0 / 2.0 = 7.5 |
| <code>static_cast<double> (15 / 2)</code> | = <code>static_cast<double> (7)</code> (because 15 / 2 = 7) = 7.0 |
| <code>static_cast<int> (7.8 +</code> <code>static_cast<double> (15) / 2)</code> | = <code>static_cast<int> (7.8 + 7.5)</code> = <code>static_cast<int> (15.3)</code> = 15 |
| <code>static_cast<int> (7.8 +</code> <code>static_cast<double> (15 / 2))</code> | = <code>static_cast<int> (7.8 + 7.0)</code> = <code>static_cast<int> (14.8)</code> = 14 |

The following C++ program evaluates the preceding expressions:

```
// This program illustrates how explicit type conversion works.

#include <iostream>
using namespace std;

int main()
{
    cout << "static_cast<int>(7.9) = "
          << static_cast<int>(7.9)
          << endl;
    cout << "static_cast<int>(3.3) = "
          << static_cast<int>(3.3)
          << endl;
    cout << "static_cast<double>(25) = "
          << static_cast<double>(25)
          << endl;
    cout << "static_cast<double>(5 + 3) = "
          << static_cast<double>(5 + 3)
          << endl;
    cout << "static_cast<double>(15) / 2 = "
          << static_cast<double>(15) / 2
          << endl;
    cout << "static_cast<double>(15 / 2) = "
          << static_cast<double>(15 / 2)
          << endl;
    cout << "static_cast<int>(7.8 + static_cast<double>(15) / 2) = "
          << static_cast<int>(7.8 + static_cast<double>(15) / 2)
          << endl;
    cout << "static_cast<int>(7.8 + static_cast<double>(15 / 2)) = "
          << static_cast<int>(7.8 + static_cast<double>(15 / 2))
          << endl;

    return 0;
}
```

Sample Run:

```
static_cast<int>(7.9) = 7
static_cast<int>(3.3) = 3
static_cast<double>(25) = 25
static_cast<double>(5 + 3) = 8
static_cast<double>(15) / 2 = 7.5
static_cast<double>(15 / 2) = 7
static_cast<int>(7.8 + static_cast<double>(15) / 2) = 15
static_cast<int>(7.8 + static_cast<double>(15 / 2)) = 14
```

Note that the value of the expression `static_cast<double>(25)` is 25.0. However, it is output as 25 rather than 25.0. This is because we have not yet discussed how to output decimal numbers with 0 decimal parts to show the decimal point and the trailing zeros. Chapter 3 explains how to output decimal numbers in a desired format. Similarly, the output of other decimal numbers with zero decimal parts is without the decimal point and the 0 decimal part.

NOTE

In C++, the cast operator can also take the form `dataType(expression)`. This form is called C-like casting. For example, `double(5) = 5.0` and `int(17.6) = 17`. However, `static_cast` is more stable than C-like casting.

2

You can also use cast operators to explicitly convert `char` data values into `int` data values and `int` data values into `char` data values. To convert `char` data values into `int` data values, you use a collating sequence. For example, in the ASCII character set, `static_cast<int>('A')` is 65 and `static_cast<int>('8')` is 56. Similarly, `static_cast<char>(65)` is 'A' and `static_cast<char>(56)` is '8'.

Earlier in this chapter, you learned how arithmetic expressions are formed and evaluated in C++. If you want to use the value of one expression in another expression, first you must save the value of the expression. There are many reasons to save the value of an expression. Some expressions are complex and may require a considerable amount of computer time to evaluate. By calculating the values once and saving them for further use, you not only save computer time and create a program that executes more quickly, you also avoid possible typographical errors. In C++, expressions are evaluated, and if the value is not saved, it is lost. That is, unless it is saved, the value of an expression cannot be used in later calculations. In the next section, you will learn how to save the value of an expression and use it in subsequent calculations.

Before leaving the discussion of data types, let us discuss one more data type—**string**.

string Type

The data type **string** is a programmer-defined data type. It is not directly available for use in a program like the simple data types discussed earlier. To use this data type, you need to access program components from the library, which will be discussed later in this chapter. The data type **string** is a feature of ANSI/ISO Standard C++.

NOTE

Prior to the ANSI/ISO C++ language standard, the standard C++ library did not provide a **string** data type. Compiler vendors often supplied their own programmer-defined **string** type, and the syntax and semantics of string operations often varied from vendor to vendor.

A **string** is a sequence of zero or more characters. Strings in C++ are enclosed in double quotation marks. A string containing no characters is called a **null** or **empty** string. The following are examples of strings. Note that `""` is the empty string.

```
"William Jacob"
"Mickey"
""
```

Every character in a string has a relative position in the string. The position of the first character is 0, the position of the second character is 1, and so on. The length of a string is the number of characters in it.

EXAMPLE 2-10

| String | Position of a Character in the String | Length of the String |
|-----------------|----------------------------------------------------------------------------------------------------------------------------------------------------|----------------------|
| "William Jacob" | Position of 'W' is 0. Position of the first 'i' is 1. Position of ' ' (the space) is 7. Position of 'J' is 8. Position of 'b' is 12. | 13 |
| "Mickey" | Position of 'M' is 0. Position of 'i' is 1. Position of 'c' is 2. Position of 'k' is 3. Position of 'e' is 4. Position of 'y' is 5. | 6 |

When determining the length of a string, you must also count any spaces in the string. For example, the length of the following string is 22.

"It is a beautiful day."

The string type is very powerful and more complex than simple data types. It provides many operations to manipulate strings. For example, it provides operations to find the length of a string, extract part of a string, and compare strings. You will learn about this data over the next few chapters.

Input

As noted earlier, the main objective of a C++ program is to perform calculations and manipulate data. Recall that data must be loaded into main memory before it can be manipulated. In this section, you will learn how to put data into the computer's memory. Storing data in the computer's memory is a two-step process:

1. Instruct the computer to allocate memory.
2. Include statements in the program to put data into the allocated memory.

Allocating Memory with Constants and Variables

When you instruct the computer to allocate memory, you tell it not only what names to use for each memory location, but also what type of data to store in those memory locations. Knowing the location of data is essential, because data stored in one memory location might be needed at several places in the program. As you saw earlier, knowing what data type you have is crucial for performing accurate calculations. It is also critical to know whether your data needs to remain fixed throughout program execution or whether it should change.

Some data must stay the same throughout a program. For example, the pay rate is usually the same for all part-time employees. A conversion formula that converts inches into

centimeters is fixed, because 1 inch is always equal to 2.54 centimeters. When stored in memory, this type of data needs to be protected from accidental changes during program execution. In C++, you can use a **named constant** to instruct a program to mark those memory locations in which data is fixed throughout program execution.

Named constant: A memory location whose content is not allowed to change during program execution.

To allocate memory, we use C++'s declaration statements. The syntax to declare a named constant is:

```
const dataType identifier = value;
```

In C++, `const` is a reserved word.

EXAMPLE 2-11

Consider the following C++ statements:

```
const double CONVERSION = 2.54;  
const int NO_OF_STUDENTS = 20;  
const char BLANK = ' ';
```

The first statement tells the compiler to allocate memory (eight bytes) to store a value of type `double`, call this memory space `CONVERSION`, and store the value 2.54 in it. Throughout a program that uses this statement, whenever the conversion formula is needed, the memory space `CONVERSION` can be accessed. The meaning of the other statements is similar.

Note that the identifier for a named constant is in uppercase letters. Even though there are no written rules, C++ programmers typically prefer to use uppercase letters to name a named constant. Moreover, if the name of a named constant is a combination of more than one word, called a *run-together word*, then the words are separated using an underscore. For example, in the preceding example, `NO_OF_STUDENTS` is a run-together word.

NOTE

As noted earlier, the default type of floating-point numbers is `double`. Therefore, if you declare a named constant of type `float`, then you must specify that the value is of type `float` as follows:

```
const float CONVERSION = 2.54f;
```

Otherwise, the compiler will generate a warning message. Notice that `2.54f` says that it is a `float` value. Recall that the memory size for `float` values is four bytes; for `double` values, eight bytes. Because memory size is of little concern these days, as indicated earlier, we will mostly use the type `double` to work with floating-point values.

Using a named constant to store fixed data, rather than using the data value itself, has one major advantage. If the fixed data changes, you do not need to edit the entire program and change the old value to the new value wherever the old value is used. Instead, you can make the change at just one place, recompile the program, and execute it using the new value throughout. In addition, by storing a value and referring to that memory location whenever the value is needed, you avoid typing the same value again and again and prevent accidental typos. If you misspell the name of the constant value's location, the computer will warn you through an error message, but it will not warn you if the value is mistyped.

In some programs, data needs to be modified during program execution. For example, after each test, the average test score and the number of tests taken changes. Similarly, after each pay increase, the employee's salary changes. This type of data must be stored in those memory cells whose contents can be modified during program execution. In C++, memory cells whose contents can be modified during program execution are called variables.

Variable: A memory location whose content may change during program execution.

The syntax for declaring one variable or multiple variables is:

```
dataType identifier, identifier, . . .;
```

EXAMPLE 2-12

Consider the following statements:

```
double amountDue;
int counter;
char ch;
int x, y;
string name;
```

The first statement tells the compiler to allocate enough memory to store a value of the type `double` and call it `amountDue`. The second and third statements have similar conventions. The fourth statement tells the compiler to allocate two different memory spaces, each large enough to store a value of the type `int`; name the first memory space `x`; and name the second memory space `y`. The fifth statement tells the compiler to allocate memory space to store a string and call it `name`.

As in the case of naming named constants, there are no written rules for naming variables. However, C++ programmers typically use lowercase letters to declare variables. If a variable name is a combination of more than one word, then the first letter of each word, except the first word, is uppercase. (For example, see the variable `amountDue` in the preceding example.)

From now on, when we say “variable,” we mean a variable memory location.

NOTE

In C++, you must declare all identifiers before you can use them. If you refer to an identifier without declaring it, the compiler will generate an error message (syntax error), indicating that the identifier is not declared. Therefore, to use either a named constant or a variable, you must first declare it.

2

Now that data types, variables, and constants have been defined and discussed, it is possible to offer a formal definition of simple data types. A data type is called **simple** if the variable or named constant of that type can store only one value at a time. For example, if **x** is an **int** variable, at a given time, only one value can be stored in **x**.

Putting Data into Variables

Now that you know how to declare variables, the next question is: How do you put data into those variables? In C++, you can place data into a variable in two ways:

1. Use C++'s assignment statement.
2. Use input (read) statements.

Assignment Statement

The assignment statement takes the following form:

```
variable = expression;
```

In an assignment statement, the value of the **expression** should match the data type of the **variable**. The expression on the right side is evaluated, and its value is assigned to the variable (and thus to a memory location) on the left side.

A variable is said to be **initialized** the first time a value is placed in the variable.

In C++, = is called the **assignment operator**.

EXAMPLE 2-13

Suppose you have the following variable declarations:

```
int num1, num2;
double sale;
char first;
string str;
```

Now consider the following assignment statements:

```
num1 = 4;
num2 = 4 * 5 - 11;
sale = 0.02 * 1000;
first = 'D';
str = "It is a sunny day.";
```

For each of these statements, the computer first evaluates the expression on the right and then stores that value in a memory location named by the identifier on the left. The first statement stores the value 4 in `num1`, the second statement stores 9 in `num2`, the third statement stores 20.00 in `sale`, and the fourth statement stores the character D in `first`. The fifth statement stores the string "It is a sunny day." in the variable `str`.

The following C++ program shows the effect of the preceding statements:

```
// This program illustrates how data in the variables are
// manipulated.
```

```
#include <iostream>
#include <string>

using namespace std;

int main()
{
    int num1, num2;
    double sale;
    char first;
    string str;

    num1 = 4;
    cout << "num1 = " << num1 << endl;

    num2 = 4 * 5 - 11;
    cout << "num2 = " << num2 << endl;

    sale = 0.02 * 1000;
    cout << "sale = " << sale << endl;

    first = 'D';
    cout << "first = " << first << endl;

    str = "It is a sunny day.";
    cout << "str = " << str << endl;

    return 0;
}
```

Sample Run:

```
num1 = 4
num2 = 9
sale = 20
first = D
str = It is a sunny day.
```

For the most part, the preceding program is straightforward. Let us take a look at the output statement:

```
cout << " num1 = " << num1 << endl;
```

This output statement consists of the string " num1 = ", the operator <<, and the variable num1. Here, first the value of the string " num1 = " is output, and then the value of the variable num1 is output. The meaning of the other output statements is similar.

A C++ statement such as:

```
num = num + 2;
```

means “evaluate whatever is in num, add 2 to it, and assign the new value to the memory location num.” The expression on the right side must be evaluated first; that value is then assigned to the memory location specified by the variable on the left side. Thus, the sequence of C++ statements:

```
num = 6;
num = num + 2;
```

and the statement:

```
num = 8;
```

both assign 8 to num. Note that if num has not been initialized, the statement num = num + 2 might give unexpected results and/or the compiler might generate a warning message indicating that the variable has not been initialized.

The statement num = 5; is read as “num becomes 5” or “num gets 5” or “num is assigned the value 5.” Reading the statement as “num equals 5” is incorrect, especially for statements such as num = num + 2;. Each time a new value is assigned to num, the old value is overwritten.

EXAMPLE 2-14

Suppose that num1, num2, and num3 are `int` variables and the following statements are executed in sequence.

1. num1 = 18;
2. num1 = num1 + 27;
3. num2 = num1;
4. num3 = num2 / 5;
5. num3 = num3 / 4;

The following table shows the values of the variables after the execution of each statement. (A ? indicates that the value is unknown. The orange color in a box shows that the value of that variable is changed.)

| | Values of the Variables | | | Explanation |
|--------------------|-------------------------|--------------------|-------------------|---------------------------------------------------------------------------------------------------------------------------|
| Before Statement 1 | <div>?</div> num1 | <div>?</div> num2 | <div>?</div> num3 | |
| After Statement 1 | <div>18</div> num1 | <div>?</div> num2 | <div>?</div> num3 | |
| After Statement 2 | <div>45</div> num1 | <div>?</div> num2 | <div>?</div> num3 | $\text{num1} + 27 = 18 + 27 = 45$. This value is assigned to num1 , which replaces the old value of num1 . |
| After Statement 3 | <div>45</div> num1 | <div>45</div> num2 | <div>?</div> num3 | Copy the value of num1 into num2 . |
| After Statement 4 | <div>45</div> num1 | <div>45</div> num2 | <div>9</div> num3 | $\text{num2} / 5 = 45 / 5 = 9$. This value is assigned to num3 . So num3 = 9. |
| After Statement 5 | <div>45</div> num1 | <div>45</div> num2 | <div>2</div> num3 | $\text{num3} / 4 = 9 / 4 = 2$. This value is assigned to num3 , which replaces the old value of num3 . |

Thus, after the execution of the statement in Line 5, **num1** = 45, **num2** = 45, and **num3** = 2.

Tracing values through a sequence, called a **walk-through**, is a valuable tool to learn and practice. Try it in the sequence above. You will learn more about how to walk through a sequence of C++ statements later in this chapter.

NOTE

Suppose that **x**, **y**, and **z** are **int** variables. The following is a legal statement in C++:

```
x = y = z;
```

In this statement, first the value of **z** is assigned to **y**, and then the new value of **y** is assigned to **x**. Because the assignment operator, **=**, is evaluated from right to left, the **associativity** of the **assignment operator** is said to be from right to left.

Saving and Using the Value of an Expression

Now that you know how to declare variables and put data into them, you can learn how to save the value of an expression. You can then use this value in a later expression without using the expression itself, thereby answering the question raised earlier in this chapter. To save the value of an expression and use it in a later expression, do the following:

1. Declare a variable of the appropriate data type. For example, if the result of the expression is an integer, declare an **int** variable.

2. Assign the value of the expression to the variable that was declared, using the assignment statement. This action saves the value of the expression into the variable.
3. Wherever the value of the expression is needed, use the variable holding the value. The following example further illustrates this concept.

EXAMPLE 2-15

Suppose that you have the following declaration:

```
int a, b, c, d;  
int x, y;
```

Further suppose that you want to evaluate the expressions $-b + (b^2 - 4ac)$ and $-b - (b^2 - 4ac)$ and assign the values of these expressions to **x** and **y**, respectively. Because the expression $b^2 - 4ac$ appears in both expressions, you can first calculate the value of this expression and save its value in **d**. You can then use the value of **d** to evaluate the expressions, as shown by the following statements:

```
d = b * b - 4 * a * c;  
x = -b + d;  
y = -b - d;
```

Earlier, you learned that if a variable is used in an expression, the expression would yield a meaningful value only if the variable has first been initialized. You also learned that after declaring a variable, you can use an assignment statement to initialize it. It is possible to initialize and declare variables at the same time. Before we discuss how to use an input (read) statement, we address this important issue.

Declaring and Initializing Variables

When a variable is declared, C++ may not automatically put a meaningful value in it. In other words, C++ may not automatically initialize variables. For example, the **int** and **double** variables may not be initialized to 0, as happens in some programming languages. This does not mean, however, that there is no value in a variable after its declaration. When a variable is declared, memory is allocated for it.

Recall from Chapter 1 that main memory is an ordered sequence of cells, and each cell is capable of storing a value. Also, recall that the machine language is a sequence of 0s and 1s, or bits. Therefore, data in a memory cell is a sequence of bits. These bits are nothing but electrical signals, so when the computer is turned on, some of the bits are 1 and some are 0. The state of these bits depends on how the system functions. However, when you instruct the computer to store a particular value in a memory cell, the bits are set according to the data being stored.

During data manipulation, the computer takes the value stored in particular cells and performs a calculation. If you declare a variable and do not store a value in it, the memory cell still has a value—usually the value of the setting of the bits from their last use—and you have no way to know what this value is.

If you only declare a variable and do not instruct the computer to put data into the variable, the value of that variable is garbage. However, the computer does not warn us, regards whatever values are in memory as legitimate, and performs calculations using those values in memory. Using a variable in an expression without initializing it produces erroneous results. To avoid these pitfalls, C++ allows you to initialize variables while they are being declared. For example, consider the following C++ statements in which variables are first declared and then initialized:

```
int first, second;
char ch;
double x;
```

```
first = 13;
second = 10;
ch = ' ';
x = 12.6;
```

You can declare and initialize these variables at the same time using the following C++ statements:

```
int first = 13, second = 10;
char ch = ' ';
double x = 12.6;
```

The first C++ statement declares two `int` variables, `first` and `second`, and stores 13 in `first` and 10 in `second`. The meaning of the other statements is similar.

In reality, not all variables are initialized during declaration. It is the nature of the program or the programmer's choice that dictates which variables should be initialized during declaration. The key point is that all variables must be initialized before they are used.

Input (Read) Statement

Previously, you learned how to put data into variables using the assignment statement. In this section, you will learn how to put data into variables from the *standard input device*, using C++'s input (or read) statements.

NOTE

In most cases, the standard input device is the keyboard.

When the computer gets the data from the keyboard, the user is said to be acting interactively.

Putting data into variables from the standard input device is accomplished via the use of `cin` and the operator `>>`. The syntax of `cin` together with `>>` is:

```
cin >> variable >> variable ...;
```

This is called an **input (read)** statement. In C++, `>>` is called the **stream extraction operator**.

NOTE

In a syntax, the shading indicates the part of the definition that is optional. Furthermore, throughout this book, the syntax is enclosed in yellow boxes.

EXAMPLE 2-16

Suppose that `miles` is a variable of type `double`. Further suppose that the input is `73.65`. Consider the following statements:

```
cin >> miles;
```

This statement causes the computer to get the input, which is `73.65`, from the standard input device and stores it in the variable `miles`. That is, after this statement executes, the value of the variable `miles` is `73.65`.

Example 2-17 further explains how to input numeric data into a program.

EXAMPLE 2-17

Suppose we have the following statements:

```
int feet;  
int inches;
```

Suppose the input is:

```
23 7
```

Next, consider the following statement:

```
cin >> feet >> inches;
```

This statement first stores the number `23` into the variable `feet` and then the number `7` into the variable `inches`. Notice that when these numbers are entered via the keyboard, they are separated with a blank. In fact, they can be separated with one or more blanks or lines or even the tab character.

The following C++ program shows the effect of the preceding input statements:

```
// This program illustrates how input statements work.

#include <iostream>

using namespace std;

int main()
{
    int feet;
    int inches;

    cout << "Enter two integers separated by spaces: ";
    cin >> feet >> inches;
    cout << endl;

    cout << "Feet = " << feet << endl;
    cout << "Inches = " << inches << endl;

    return 0;
}
```

Sample Run: In this sample run, the user input is shaded.

Enter two integers separated by spaces: 23 7

Feet = 23
Inches = 7

The C++ program in Example 2-18 illustrates how to read strings and numeric data.

EXAMPLE 2-18

```
// This program illustrates how to read strings and numeric data.

#include <iostream>
#include <string>

using namespace std;

int main()
{
    string firstName;           //Line 1
    string lastName;           //Line 2
    int age;                   //Line 3
    double weight;              //Line 4

    cout << "Enter first name, last name, age, "
         << "and weight, separated by spaces."
         << endl;               //Line 5
}
```

```

cin >> firstName >> lastName;           //Line 6
cin >> age >> weight;                     //Line 7

cout << "Name: " << firstName << " "
    << lastName << endl;                 //Line 8

cout << "Age: " << age << endl;           //Line 9
cout << "Weight: " << weight << endl;     //Line 10

return 0;                                //Line 11
}

```

2

Sample Run: In this sample run, the user input is shaded.

Enter first name, last name, age, and weight, separated by spaces.

Sheila Mann 23 120.5

Name: Sheila Mann

Age: 23

Weight: 120.5

The preceding program works as follows: The statements in Lines 1 to 4 declare the variables `firstName` and `lastName` of type `string`, `age` of type `int`, and `weight` of type `double`. The statement in Line 5 is an output statement and tells the user what to do. (Such output statements are called prompt lines.) As shown in the sample run, the input to the program is:

Sheila Mann 23 120.5

The statement in Line 6 first reads and stores the string `Sheila` into the variable `firstName` and then skips the space after `Sheila` and reads and stores the string `Mann` into the variable `lastName`. Next, the statement in Line 7 first skips the blank after `Mann` and reads and stores `23` into the variable `age` and then skips the blank after `23` and reads and stores `120.5` into the variable `weight`.

The statements in Lines 8, 9, and 10 produce the third, fourth, and fifth lines of the sample run.

NOTE

During programming execution, if more than one value is entered in a line, these values must be separated by at least one blank or tab. Alternately, one value per line can be entered.

Variable Initialization

Remember, there are two ways to initialize a variable: by using the assignment statement and by using a read statement. Consider the following declaration:

```

int feet;
int inches;

```

Consider the following two sets of code:

```
(a) feet = 35;
    inches = 6;
    cout << "Total inches = "
        << 12 * feet + inches;

(b) cout << "Enter feet: ";
    cin >> feet;
    cout << endl;
    cout << "Enter inches: ";
    cin >> inches;
    cout << endl;
    cout << "Total inches = "
        << 12 * feet + inches;
```

In (a), **feet** and **inches** are initialized using assignment statements, and in (b), these variables are initialized using input statements. However, each time the code in (a) executes, **feet** and **inches** are initialized to the same value unless you edit the source code, change the value, recompile, and run. On the other hand, in (b), each time the program runs, you are prompted to enter values for **feet** and **inches**. Therefore, a read statement is much more versatile than an assignment statement.

Sometimes it is necessary to initialize a variable by using an assignment statement. This is especially true if the variable is used only for internal calculation and not for reading and storing data.

Recall that C++ does not automatically initialize variables when they are declared. Some variables can be initialized when they are declared, whereas others must be initialized using either an assignment statement or a read statement.

NOTE

When the program is compiled, some of the newer IDEs might give warning messages if the program uses the value of a variable without first properly initializing that variable. In this case, if you ignore the warning and execute the program, the program might terminate abnormally with an error message.

NOTE

Suppose you want to store a character into a **char** variable using an input statement. During program execution, when you enter the character, you do not include the single quotes. For example, suppose that **ch** is a **char** variable. Consider the following input statement:

```
cin >> ch;
```

If you want to store **K** into **ch** using this statement, during program execution, you only enter **K**. Similarly, if you want to store a string into a **string** variable using an input statement, during program execution, you enter only the string without the double quotes.

EXAMPLE 2-19

This example further illustrates how assignment statements and input statements manipulate variables. Consider the following declarations:

```
int firstNum, secondNum;
double z;
char ch;
string name;
```

Also, suppose that the following statements execute in the order given:

1. `firstNum = 4;`
2. `secondNum = 2 * firstNum + 6;`
3. `z = (firstNum + 1) / 2.0;`
4. `ch = 'A';`
5. `cin >> secondNum;`
6. `cin >> z;`
7. `firstNum = 2 * secondNum + static_cast<int>(z);`
8. `cin >> name;`
9. `secondNum = secondNum + 1;`
10. `cin >> ch;`
11. `firstNum = firstNum + static_cast<int>(ch);`
12. `z = firstNum - z;`

In addition, suppose the input is:

8 16.3 Jenny D

This line has four values, 8, 16.3, Jenny, and D, and each value is separated from the others by a blank.

Let's now determine the values of the declared variables after the last statement executes. To explicitly show how a particular statement changes the value of a variable, the values of the variables after each statement executes are shown. (In the following figures, a question mark [?] in a box indicates that the value in the box is unknown.)

Before statement 1 executes, all variables are uninitialized, as shown in Figure 2-2.




FIGURE 2-2 Variables before statement 1 executes

Next, we show the values of the variables after the execution of each statement.

| After St. | Values of the Variables | Explanation |
|-----------|-----------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1 | <div> <div>4</div> <div>?</div> <div>?</div> <div>?</div> <div>?</div> </div> <div> firstNumsecondNumzchname </div> | Store 4 into firstNum . |
| 2 | <div> <div>4</div> <div>14</div> <div>?</div> <div>?</div> <div>?</div> </div> <div> firstNumsecondNumzchname </div> | $2 * \text{firstNum} + 6 = 2 * 4 + 6 = 14$. Store 14 into secondNum . |
| 3 | <div> <div>4</div> <div>14</div> <div>2.5</div> <div>?</div> <div>?</div> </div> <div> firstNumsecondNumzchname </div> | $(\text{firstNum} + 1) / 2.0 = (4 + 1) / 2.0 = 5 / 2.0 = 2.5$. Store 2.5 into z . |
| 4 | <div> <div>4</div> <div>14</div> <div>2.5</div> <div>A</div> <div>?</div> </div> <div> firstNumsecondNumzchname </div> | Store 'A' into ch . |
| 5 | <div> <div>4</div> <div>8</div> <div>2.5</div> <div>A</div> <div>?</div> </div> <div> firstNumsecondNumzchname </div> | Read a number from the keyboard (which is 8) and store it into secondNum . This statement replaces the old value of secondNum with this new value. |
| 6 | <div> <div>4</div> <div>8</div> <div>16.3</div> <div>A</div> <div>?</div> </div> <div> firstNumsecondNumzchname </div> | Read a number from the keyboard (which is 16.3) and store this number into z . This statement replaces the old value of z with this new value. |
| 7 | <div> <div>32</div> <div>8</div> <div>16.3</div> <div>A</div> <div>?</div> </div> <div> firstNumsecondNumzchname </div> | $2 * \text{secondNum} + \text{static_cast<int>}(z) = 2 * 8 + \text{static_cast<int>}(16.3) = 16 + 16 = 32$. Store 32 into firstNum . This statement replaces the old value of firstNum with this new value. |
| 8 | <div> <div>32</div> <div>8</div> <div>16.3</div> <div>A</div> <div>Jenny</div> </div> <div> firstNumsecondNumzchname </div> | Read the next input, Jenny , from the keyboard and store it into name . |
| 9 | <div> <div>32</div> <div>9</div> <div>16.3</div> <div>A</div> <div>Jenny</div> </div> <div> firstNumsecondNumzchname </div> | $\text{secondNum} + 1 = 8 + 1 = 9$. Store 9 into secondNum . |
| 10 | <div> <div>32</div> <div>9</div> <div>16.3</div> <div>D</div> <div>Jenny</div> </div> <div> firstNumsecondNumzchname </div> | Read the next input from the keyboard (which is D) and store it into ch . This statement replaces the old value of ch with the new value. |

| After St. | Values of the Variables | Explanation |
|-----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------|
| 11 | <div><div>100</div><div>9</div><div>16.3</div><div>D</div><div>Jenny</div></div> <div><div>firstNum</div><div>secondNum</div><div>z</div><div>ch</div><div>name</div></div> | <code>firstNum + static_cast<int>(ch) = 32 + static_cast<int>('D') = 32 + 68 = 100.</code> Store 100 into <code>firstNum</code> . |
| 12 | <div><div>100</div><div>9</div><div>83.7</div><div>D</div><div>Jenny</div></div> <div><div>firstNum</div><div>secondNum</div><div>z</div><div>ch</div><div>name</div></div> | <code>firstNum - z = 100 - 16.3 = 100.0 - 16.3 = 83.7.</code> Store 83.7 into <code>z</code> . |

NOTE

When something goes wrong in a program and the results it generates are not what you expected, you should do a walk-through of the statements that assign values to your variables. Example 2-19 illustrates how to do a walk-through of your program. This is a very effective debugging technique. The Web site accompanying this book contains a C++ program that shows the effect of the 12 statements listed at the beginning of Example 2-19. The program is named `Example 2_19.cpp`.

NOTE

If you assign the value of an expression that evaluates to a floating-point value—without using the cast operator—to a variable of type `int`, the fractional part is dropped. In this case, the compiler most likely will issue a warning message about the implicit type conversion.

Increment and Decrement Operators

Now that you know how to declare a variable and enter data into a variable, in this section, you will learn about two more operators: the **increment operators**. These operators are used frequently by C++ programmers and are useful programming tools.

Suppose `count` is an `int` variable. The statement:

```
count = count + 1;
```

increments the value of `count` by 1. To execute this assignment statement, the computer first evaluates the expression on the right, which is `count + 1`. It then assigns this value to the variable on the left, which is `count`.

As you will see in later chapters, such statements are frequently used to keep track of how many times certain things have happened. To expedite the execution of such statements, C++ provides the **increment operator**, `++`, which increases the value of a variable by 1, and the **decrement operator**, `--`, which decreases the value of a variable by 1.

Increment and decrement operators each have two forms, pre and post. The syntax of the increment operator is:

Pre-increment: `++variable`

Post-increment: `variable++`

The syntax of the decrement operator is:

Pre-decrement: `--variable`

Post-decrement: `variable--`

Let's look at some examples. The statement:

```
++count;
```

or:

```
count++;
```

increments the value of `count` by 1. Similarly, the statement:

```
--count;
```

or:

```
count--;
```

decrements the value of `count` by 1.

Because both the increment and decrement operators are built into C++, the value of the variable is quickly incremented or decremented without having to use the form of an assignment statement.

Now, both the pre- and post-increment operators increment the value of the variable by 1. Similarly, the pre- and post-decrement operators decrement the value of the variable by 1. What is the difference between the pre and post forms of these operators? The difference becomes apparent when the variable using these operators is employed in an expression.

Suppose that `x` is an `int` variable. If `++x` is used in an expression, first the value of `x` is incremented by 1, and then the new value of `x` is used to evaluate the expression. On the other hand, if `x++` is used in an expression, first the current value of `x` is used in the expression, and then the value of `x` is incremented by 1. The following example clarifies the difference between the pre- and post-increment operators.

Suppose that `x` and `y` are `int` variables. Consider the following statements:

```
x = 5;
y = ++x;
```

The first statement assigns the value 5 to `x`. To evaluate the second statement, which uses the pre-increment operator, first the value of `x` is incremented to 6, and then this value, 6, is assigned to `y`. After the second statement executes, both `x` and `y` have the value 6.

Now, consider the following statements:

```
x = 5;  
y = x++;
```

As before, the first statement assigns 5 to **x**. In the second statement, the post-increment operator is applied to **x**. To execute the second statement, first the value of **x**, which is 5, is used to evaluate the expression, and then the value of **x** is incremented to 6. Finally, the value of the expression, which is 5, is stored in **y**. After the second statement executes, the value of **x** is 6, and the value of **y** is 5.

The following example further illustrates how the pre and post forms of the increment operator work.

EXAMPLE 2-20

Suppose **a** and **b** are `int` variables and:

```
a = 5;  
b = 2 + (++a);
```

The first statement assigns 5 to **a**. To execute the second statement, first the expression `2 + (++a)` is evaluated. Because the pre-increment operator is applied to **a**, first the value of **a** is incremented to 6. Then 2 is added to 6 to get 8, which is then assigned to **b**. Therefore, after the second statement executes, **a** is 6 and **b** is 8.

On the other hand, after the execution of the following statements:

```
a = 5;  
b = 2 + (a++);
```

the value of **a** is 6 while the value of **b** is 7.

This book will most often use the increment and decrement operators with a variable in a stand-alone statement. That is, the variable using the increment or decrement operator will not be part of any expression.

Output

In the preceding sections, you have seen how to put data into the computer's memory and how to manipulate that data. We also used certain output statements to show the results on the *standard output device*. This section explains in some detail how to further use output statements to generate the desired results.

NOTE

The standard output device is usually the screen.

In C++, output on the standard output device is accomplished via the use of `cout` and the operator `<<`. The general syntax of `cout` together with `<<` is:

```
cout << expression or manipulator << expression or manipulator...;
```

This is called an **output statement**. In C++, `<<` is called the **stream insertion operator**. Generating output with `cout` follows two rules:

1. The expression is evaluated, and its value is printed at the current insertion point on the output device.
2. A manipulator is used to format the output. The simplest manipulator is `endl` (the last character is the letter `l`), which causes the insertion point to move to the beginning of the next line.

NOTE

On the screen, the insertion point is where the cursor is.

The next example illustrates how an output statement works. In an output statement, a string or an expression involving only one variable or a single value evaluates to itself.

NOTE

When an output statement outputs `char` values, it outputs only the character without the single quotes (unless the single quotes are part of the output statement).

For example, suppose `ch` is a `char` variable and `ch = 'A'`; . The statement:

```
cout << ch;
```

or:

```
cout << 'A';
```

outputs:

A

Similarly, when an output statement outputs the value of a string, it outputs only the string without the double quotes (unless you include double quotes as part of the output).

EXAMPLE 2-21

Consider the following statements. The output is shown to the right of each statement.

| Statement | Output |
|------------------------------------------------------------|--------------|
| 1 <code>cout << 29 / 4 << endl;</code> | 7 |
| 2 <code>cout << "Hello there." << endl;</code> | Hello there. |
| 3 <code>cout << 12 << endl;</code> | 12 |
| 4 <code>cout << "4 + 7" << endl;</code> | 4 + 7 |

```

5 cout << 4 + 7 << endl;           11
6 cout << 'A' << endl;             A
7 cout << "4 + 7 = " << 4 + 7 << endl; 4 + 7 = 11
8 cout << 2 + 3 * 5 << endl;        17
9 cout << "Hello \nthere." << endl;  Hello
                                   there.

```

Look at the output of statement 9. Recall that in C++, the newline character is '\n'; it causes the insertion point to move to the beginning of the next line before printing there. Therefore, when \n appears in a string in an output statement, it causes the insertion point to move to the beginning of the next line on the output device. This fact explains why **Hello** and **there.** are printed on separate lines.

NOTE

In C++, \ is called the escape character and \n is called newline escape sequence.

Recall that all variables must be properly initialized; otherwise, the value stored in them may not make much sense. Also recall that C++ does not automatically initialize variables.

If **num** is an **int** variable, then the output of the C++ statement:

```
cout << num << endl;
```

is meaningful provided that **num** has been given a value. For example, the sequence of C++ statements:

```
num = 45;
cout << num << endl;
```

will produce the output 45.

EXAMPLE 2-22

Consider the following C++ program.

```

// This program illustrates how output statements work.

#include <iostream>

using namespace std;

int main()
{
    int a, b;

    a = 65;           //Line 1
    b = 78;           //Line 2

```

```

    cout << 29 / 4 << endl;           //Line 3
    cout << 3.0 / 2 << endl;         //Line 4
    cout << "Hello there.\n";       //Line 5
    cout << 7 << endl;               //Line 6
    cout << 3 + 5 << endl;           //Line 7
    cout << "3 + 5";                 //Line 8
    cout << endl;                   //Line 9
    cout << a << endl;               //Line 10
    cout << "a" << endl;            //Line 11
    cout << (a + 5) * 6 << endl;     //Line 12
    cout << 2 * b << endl;          //Line 13

    return 0;
}

```

In the following output, the column marked “Output of Statement at” and the line numbers are not part of the output. The line numbers are shown in this column to make it easy to see which output corresponds to which statement.

| | Output of Statement at |
|--------------|------------------------|
| 7 | Line 3 |
| 1.5 | Line 4 |
| Hello there. | Line 5 |
| 7 | Line 6 |
| 8 | Line 7 |
| 3 + 5 | Line 8 |
| 65 | Line 10 |
| a | Line 11 |
| 420 | Line 12 |
| 156 | Line 13 |

For the most part, the output is straightforward. Look at the output of the statements in Lines 7, 8, 9, and 10. The statement in Line 7 outputs the result of $3 + 5$, which is 8, and moves the insertion point to the beginning of the next line. The statement in Line 8 outputs the string $3 + 5$. Note that the statement in Line 8 consists only of the string $3 + 5$. Therefore, after printing $3 + 5$, the insertion point stays positioned after 5; it does not move to the beginning of the next line.

The output statement in Line 9 contains only the manipulator `endl`, which moves the insertion point to the beginning of the next line. Therefore, when the statement in Line 10 executes, the output starts at the beginning of the line. Note that in this output, the column “Output of Statement at” does not contain Line 9. This is due to the fact that the statement in Line 9 does not produce any printable output. It simply moves the insertion point to the beginning of the next line. Next, the statement in Line 10 outputs the value of `a`, which is 65. The manipulator `endl` then moves the insertion point to the beginning of the next line.

NOTE

Outputting or accessing the value of a variable in an expression does not destroy or modify the contents of the variable.

2

Let us now take a close look at the newline character, `'\n'`. Consider the following C++ statements:

```
cout << "Hello there.";
cout << "My name is James.";
```

If these statements are executed in sequence, the output is:

```
Hello there.My name is James.
```

Now consider the following C++ statements:

```
cout << "Hello there.\n";
cout << "My name is James.";
```

The output of these C++ statements is:

```
Hello there.
My name is James.
```

When `\n` is encountered in the string, the insertion point is positioned at the beginning of the next line. Note also that `\n` may appear anywhere in the string. For example, the output of the statement:

```
cout << "Hello \nthere. \nMy name is James.";
```

is:

```
Hello
there.
My name is James.
```

Also, note that the output of the statement:

```
cout << '\n';
```

is the same as the output of the statement:

```
cout << "\n";
```

which is equivalent to the output of the statement:

```
cout << endl;
```

Thus, the output of the sequence of statements:

```
cout << "Hello there.\n";
cout << "My name is James.";
```

is equivalent to the output of the sequence of statements:

```
cout << "Hello there." << endl;
cout << "My name is James.";
```

EXAMPLE 2-23

Consider the following C++ statements:

```
cout << "Hello there.\nMy name is James.";
```

or:

```
cout << "Hello there.";  
cout << "\nMy name is James.";
```

or:

```
cout << "Hello there.";  
cout << endl << "My name is James.";
```

In each case, the output of the statements is:

```
Hello there.  
My name is James.
```

EXAMPLE 2-24

The output of the C++ statements:

```
cout << "Count...\n....1\n.....2\n.....3";
```

or:

```
cout << "Count..." << endl << "....1" << endl  
    << ".....2" << endl << ".....3";
```

is:

```
Count...  
....1  
.....2  
.....3
```

EXAMPLE 2-25

Suppose that you want to output the following sentence in one line as part of a message:

```
It is sunny, warm, and not a windy day. We can go golfing.
```

Obviously, you will use an output statement to produce this output. However, in the programming code, this statement may not fit in one line as part of the output statement. Of course, you can use multiple output statements as follows:

```
cout << "It is sunny, warm, and not a windy day. ";  
cout << "We can go golfing." << endl;
```

Note the semicolon at the end of the first statement and the identifier `cout` at the beginning of the second statement. Also, note that there is no manipulator `endl` at the end of the first statement. Here, two output statements are used to output the sentence in one line. Equivalently, you can use the following output statement to output this sentence:

```
cout << "It is sunny, warm, and not a windy day. "
      << "We can go golfing." << endl;
```

In this statement, note that there is no semicolon at the end of the first line, and the identifier `cout` does not appear at the beginning of the second line. Because there is no semicolon at the end of the first line, this output statement continues at the second line. Also, note the double quotation marks at the beginning and end of the sentences on each line. The string is broken into two strings, but both strings are part of the same output statement.

If a string appearing in an output statement is long and you want to output the string in one line, you can break the string by using either of the previous two methods. However, the following statement would be incorrect:

```
cout << "It is sunny, warm, and not a windy day.
      We can go golfing." << endl; //illegal
```

In other words, the return (or Enter) key on your keyboard cannot be part of the string. That is, in programming code, a string *cannot* be broken into more than one line by using the return (Enter) key on your keyboard.

Recall that the newline character is `\n`, which causes the insertion point to move to the beginning of the next line. There are many escape sequences in C++, which allow you to control the output. Table 2-4 lists some of the commonly used escape sequences.

TABLE 2-4 Commonly Used Escape Sequences

| | Escape Sequence | Description |
|-----------------|------------------|-----------------------------------------------------------------------|
| <code>\n</code> | Newline | Cursor moves to the beginning of the next line |
| <code>\t</code> | Tab | Cursor moves to the next tab stop |
| <code>\b</code> | Backspace | Cursor moves one space to the left |
| <code>\r</code> | Return | Cursor moves to the beginning of the current line (not the next line) |
| <code>\\</code> | Backslash | Backslash is printed |
| <code>\'</code> | Single quotation | Single quotation mark is printed |
| <code>\"</code> | Double quotation | Double quotation mark is printed |

The following example shows the effect of some of these escape sequences.

EXAMPLE 2-26

The output of the statement:

```
cout << "The newline escape sequence is \\n" << endl;
```

is:

```
The newline escape sequence is \n
```

The output of the statement:

```
cout << "The tab character is represented as '\\t'" << endl;
```

is:

```
The tab character is represented as '\t'
```

Note that the single quote can also be printed without using the escape sequence. Therefore, the preceding statement is equivalent to the following output statement:

```
cout << "The tab character is represented as '\\t'" << endl;
```

The output of the statement:

```
cout << "The string \"Sunny\" contains five characters." << endl;
```

is:

```
The string "Sunny" contains five characters.
```

NOTE

The Web site accompanying this text contains the C++ program that shows the effect of the statements in Example 2-26. The program is named `Example2_26.cpp`.

To use `cin` and `cout` in a program, you must include a certain header file. The next section explains what this header file is, how to include a header file in a program, and why you need header files in a program. Chapter 3 will provide a full explanation of `cin` and `cout`.

Preprocessor Directives

Only a small number of operations, such as arithmetic and assignment operations, are explicitly defined in C++. Many of the functions and symbols needed to run a C++ program are provided as a collection of libraries. Every library has a name and is referred to by a header file. For example, the descriptions of the functions needed to perform input/output (I/O) are contained in the header file `iostream`. Similarly, the descriptions of some very useful mathematical functions, such as power, absolute, and sine, are contained in the header file `cmath`. If you want to use I/O or math functions, you need to tell the computer where to find the necessary code. You use preprocessor directives and the names of header files to tell the computer the locations of the code provided in libraries. Preprocessor directives are processed by a program called a **preprocessor**.

Preprocessor directives are commands supplied to the preprocessor that cause the preprocessor to modify the text of a C++ program before it is compiled. All preprocessor commands begin with `#`. There are no semicolons at the end of preprocessor commands because they are not C++ statements. To use a header file in a C++ program, use the preprocessor directive `include`.

The general syntax to include a header file (provided by the IDE) in a C++ program is:

```
#include <headerFileName>
```

For example, the following statement includes the header file `iostream` in a C++ program:

```
#include <iostream>
```

Preprocessor directives to include header files are placed as the first line of a program so that the identifiers declared in those header files can be used throughout the program. (Recall that in C++, identifiers must be declared before they can be used.)

Certain header files are required to be provided as part of C++. Appendix F describes some of the commonly used header files. Individual programmers can also create their own header files, which is discussed in the chapter *Classes and Data Abstraction*, later in this book.

Note that the preprocessor commands are processed by the preprocessor before the program goes through the compiler.

From Figure 1-3 (Chapter 1), we can conclude that a C++ system has three basic components: the program development environment, the C++ language, and the C++ library. All three components are integral parts of the C++ system. The program development environment consists of the six steps shown in Figure 1-3. As you learn the C++ language throughout the book, we will discuss components of the C++ library as we need them.

namespace and Using cin and cout in a Program

Earlier, you learned that both `cin` and `cout` are predefined identifiers. In ANSI/ISO Standard C++, these identifiers are declared in the header file `iostream`, but within a `namespace`. The name of this `namespace` is `std`. (The `namespace` mechanism will be formally defined and discussed in detail in Chapter 8. For now, you need to know only how to use `cin` and `cout` and, in fact, any other identifier from the header file `iostream`.)

There are several ways you can use an identifier declared in the namespace `std`. One way to use `cin` and `cout` is to refer to them as `std::cin` and `std::cout` throughout the program.

Another option is to include the following statement in your program:

```
using namespace std;
```

This statement appears after the statement `#include <iostream>`. You can then refer to `cin` and `cout` without using the prefix `std::`. To simplify the use of `cin` and `cout`, this book uses the second form. That is, to use `cin` and `cout` in a program, the programs will contain the following two statements:

```
#include <iostream>
```

```
using namespace std;
```

In C++, `namespace` and `using` are reserved words.

The `namespace` mechanism is a feature of ANSI/ISO Standard C++. As you learn more C++ programming, you will become aware of other header files. For example, the header file `cmath` contains the specifications of many useful mathematical functions. Similarly, the header file `iomanip` contains the specifications of many useful functions and manipulators that help you format your output in a specific manner. However, just like the identifiers in the header file `iostream`, the identifiers in ANSI/ISO Standard C++ header files are declared within a `namespace`.

The name of the `namespace` in each of these header files is `std`. Therefore, whenever certain features of a header file in ANSI/ISO Standard C++ are discussed, this book will refer to the identifiers without the prefix `std::`. Moreover, to simplify the accessing of identifiers in programs, the statement `using namespace std;` will be included. Also, if a program uses multiple header files, only one `using` statement is needed. This `using` statement typically appears after all the header files.

Using the string Data Type in a Program

Recall that the `string` data type is a programmer-defined data type and is not directly available for use in a program. To use the `string` data type, you need to access its definition from the header file `string`. Therefore, to use the `string` data type in a program, you must include the following preprocessor directive:

```
#include <string>
```

Creating a C++ Program

In previous sections, you learned enough C++ concepts to write meaningful programs. You are now ready to create a complete C++ program.

A C++ program is a collection of functions, one of which is the function `main`. Therefore, if a C++ program consists of only one function, then it must be the function `main`. Moreover, a function is a set of instructions designed to accomplish a specific task. Until Chapter 6, you will deal mainly with the function `main`.

The statements to declare variables, the statements to manipulate data (such as assignments), and the statements to input and output data are placed within the function `main`. The statements to declare named constants are usually placed outside of the function `main`.

The syntax of the function `main` used throughout this book has the following form:

```
int main()
{
    statement_1
    .
    .
    .
    statement_n

    return 0;
}
```

In the syntax of the function `main`, each statement (`statement_1, ..., statement_n`) is usually either a declarative statement or an executable statement. The statement `return 0;` must be included in the function `main` and must be the last statement. If the statement `return 0;` is misplaced in the body of the function `main`, the results generated by the program may not be to your liking. The meaning of the statement `return 0;` will be discussed in Chapter 6. In C++, `return` is a reserved word.

A C++ program might use the resources provided by the IDE, such as the necessary code to input the data, which would require your program to include certain header files. You can, therefore, divide a C++ program into two parts: preprocessor directives and the program. The preprocessor directives tell the compiler which header files to include in the program. The program contains statements that accomplish meaningful results. Taken together, the preprocessor directives and the program statements constitute the C++ **source code**. Recall that to be useful, source code must be saved in a file with the file extension `.cpp`. For example, if the source code is saved in the file `firstProgram`, then the complete name of this file is `firstProgram.cpp`. The file containing the source code is called the **source code file** or **source file**.

When the program is compiled, the compiler generates the object code, which is saved in a file with the file extension `.obj`. When the object code is linked with the system resources, the executable code is produced and saved in a file with the file extension `.exe`. Typically, the name of the file containing the object code and the name of the file containing the executable code are the same as the name of the file containing the source

code. For example, if the source code is located in a file named `firstProg.cpp`, the name of the file containing the object code is `firstProg.obj`, and the name of the file containing the executable code is `firstProg.exe`.

The extensions as given in the preceding paragraph—that is, `.cpp`, `.obj`, and `.exe`—are system dependent. Moreover, some IDEs maintain programs in the form of projects. The name of the project and the name of the source file need not be the same. It is possible that the name of the executable file is the name of the project, with the extension `.exe`. To be certain, check your system or IDE documentation.

Because the programming instructions are placed in the function `main`, let us elaborate on this function.

The basic parts of the function `main` are the heading and the body. The first line of the function `main`, that is:

```
int main()
```

is called the heading of the function `main`.

The statements enclosed between the curly braces (`{` and `}`) form the body of the function `main`. The body of the function `main` contains two types of statements:

- Declaration statements
- Executable statements

Declaration statements are used to declare things, such as variables.

In C++, variables or identifiers can be declared anywhere in the program, but they must be declared before they can be used.

EXAMPLE 2-27

The following statements are examples of variable declarations:

```
int a, b, c;
double x, y;
```

Executable statements perform calculations, manipulate data, create output, accept input, and so on.

Some executable statements that you have encountered so far are the assignment, input, and output statements.

EXAMPLE 2-28

The following statements are examples of executable statements:

```
a = 4;                //assignment statement
cin >> b;             //input statement
cout << a << " " << b << endl; //output statement
```

In skeleton form, a C++ program looks like the following:

```
//comments, if needed

preprocessor directives to include header files

using statement

named constants, if necessary

int main()
{
    statement_1
    .
    .
    .
    statement_n

    return 0;
}
```

The C++ program in Example 2-29 shows where include statements, declaration statements, executable statements, and so on typically appear in the program.

EXAMPLE 2-29

```

//*****
// Author: D.S. Malik
//
// This program shows where the include statements, using
// statement, named constants, variable declarations, assignment
// statements, and input and output statements typically appear.
//*****

#include <iostream>                                //Line 1

using namespace std;                               //Line 2

const int NUMBER = 12;                             //Line 3

int main()                                          //Line 4
{                                                  //Line 5
    int firstNum;                                  //Line 6
    int secondNum;                                 //Line 7

    firstNum = 18;                                  //Line 8
    cout << "Line 9: firstNum = " << firstNum
         << endl;                                   //Line 9

    cout << "Line 10: Enter an integer: ";          //Line 10
    cin >> secondNum;                                //Line 11
    cout << endl;                                    //Line 12
}
```

```

    cout << "Line 13: secondNum = " << secondNum
        << endl;                                     //Line 13

    firstNum = firstNum + NUMBER + 2 * secondNum;      //Line 14

    cout << "Line 15: The new value of "
        << "firstNum = " << firstNum << endl;         //Line 15

    return 0;                                          //Line 16
}                                                    //Line 17

```

Sample Run: In this sample run, the user input is shaded.

Line 9: `firstNum = 18`

Line 10: Enter an integer: **15**

Line 13: `secondNum = 15`

Line 15: The new value of `firstNum = 60`

The preceding program works as follows: The statement in Line 1 includes the header file `iostream` so that program can perform input/output. The statement in Line 2 uses the `using namespace` statement so that identifiers declared in the header file `iostream`, such as `cin`, `cout`, and `endl`, can be used without using the prefix `std::`. The statement in Line 3 declares the named constant `NUMBER` and sets its value to 12. The statement in Line 4 contains the heading of the function `main`, and the left brace in Line 5 marks the beginning of the function `main`. The statements in Lines 6 and 7 declare the variables `firstNum` and `secondNum`.

The statement in Line 8 sets the value of `firstNum` to 18, and the statement in Line 9 outputs the value of `firstNum`. Next, the statement in Line 10 prompts the user to enter an integer. The statement in Line 11 reads and stores the integer into the variable `secondNum`, which is 15 in the sample run. The statement in Line 12 positions the cursor on the screen at the beginning of the next line. The statement in Line 13 outputs the value of `secondNum`. The statement in Line 14 evaluates the expression:

```
firstNum + NUMBER + 2 * secondNum
```

and assigns the value of this expression to the variable `firstNum`, which is 60 in the sample run. The statement in Line 15 outputs the new value of `firstNum`. The statement in Line 16 contains the `return` statement. The right brace in Line 17 marks the end of the function `main`.

Debugging: Understanding and Fixing Syntax Errors

The previous sections of this chapter described the basic components of a C++ program. When you type a program, typos and unintentional syntax errors are likely to occur. Therefore, when you compile a program, the compiler will identify the syntax error. In this section, we show how to identify and fix syntax errors.

Consider the following C++ program:

```

1.  #include <iostream>
2.
3.  using namespace std;
4.
5.  int main()
6.  {
7.      int num
8.
9.      num = 18;
10.
11.     tempNum = 2 * num;
12.
13.     cout << "Num = " << num << ", tempNum = " < tempNum << endl;
14.
15.     return ;
16. }
```

(Note that the numbers 1 to 16 on the left side are not part of the program. We have numbered the statements for easy references.) This program contains syntax errors. When you compile this program, the compiler produces the following errors: (This program is compiled using Visual C++ Express 2008.)

Example2_Syntax_Errors.cpp

```

c:\chapter 2 source code\example2_syntax_errors.cpp(9) : error C2146: syntax error :
missing ';' before identifier 'num'
c:\chapter 2 source code\example2_syntax_errors.cpp(11) : error C2065: 'tempNum' :
undeclared identifier
c:\chapter 2 source code\example2_syntax_errors.cpp(13) : error C2065: 'tempNum' :
undeclared identifier
c:\chapter 2 source code\example2_syntax_errors.cpp(13) : error C2563: mismatch in formal
parameter list
c:\chapter 2 source code\example2_syntax_errors.cpp(13) : error C2568: '<<' : unable to
resolve function overload
      c:\program files\microsoft visual studio 9.0\vc\include\ostream(974): could be
'std::basic_ostream<_Elem,_Traits> &std::endl(std::basic_ostream<_Elem,_Traits> &)'
      with
      [
          _Elem=wchar_t,
          _Traits=std::char_traits<wchar_t>
      ]
      c:\program files\microsoft visual studio 9.0\vc\include\ostream(966): or
'std::basic_ostream<_Elem,_Traits> &std::endl(std::basic_ostream<_Elem,_Traits> &)'
      with
      [
          _Elem=char,
          _Traits=std::char_traits<char>
      ]
]
```

```

c:\program files\microsoft visual studio 9.0\vc\include\ostream(940): or
'std::basic_ostream<_Elem,_Traits> &std::endl(std::basic_ostream<_Elem,_Traits> &)'
c:\chapter 2 source code\example2_syntax_errors.cpp(15) : error C2561: 'main' : function
must return a value

f:\cs1 c++ fifth edition\chapter 2\chapter 2 source code and prog ex\chapter 2
source code\example2_syntax_errors.cpp(5) : see declaration of 'main'
Build log was saved at "file:///c:/Documents and Settings\DM\My
Documents\Proj1\Proj1\Debug\BuildLog.htm"
Proj1 - 6 error(s), 0 warning(s)
===== Rebuild All: 0 succeeded, 1 failed, 0 skipped =====

```

First, consider the following error:

```

c:\chapter 2 source code\example2_syntax_errors.cpp(9) : error C2146:
syntax error : missing ';' before identifier 'num'

```

The expression `example2_syntax_errors.cpp(9)` indicates that there is an error in Line 9. The remaining part of this error specifies that there is a missing `;` before the identifier `num`. If we look at Line 7, we find that there is a missing semicolon at the end of the statement `int num`. Therefore, we must insert `;` at the end of the statement in Line 7.

Next, consider the second error:

```

c:\chapter 2 source code\example2_syntax_errors.cpp(11) : error C2065: 'tempNum' :
undeclared identifier

```

This error occurs in Line 11, and it specifies that the identifier `tempNum` is undeclared. When we look at the code, we find that this identifier has not been declared. So we must declare `tempNum` as an `int` variable.

The error:

```

c:\chapter 2 source code\example2_syntax_errors.cpp(13) : error C2065: 'tempNum' :
undeclared identifier

```

occurs in Line 13, and it specifies that the identifier `tempNum` is undeclared. As in the previous error, we must declare `tempNum`. Note that once we declare `tempNum` and recompile, this and the previous error will disappear.

The next error is:

```

c:\chapter 2 source code\example2_syntax_errors.cpp(13) : error C2563: mismatch
in formal parameter list

```

This error occurs in Line 13, and it indicates that some formal parameter list is mismatched. For a beginner, this error is somewhat hard to understand. (In Chapter 15, we will explain the formal parameter list of the operator `<<`.) However, as you practice, you will learn how to interpret and correct syntax errors. This error becomes clear if you look at the next error, the part of which is:

```

c:\chapter 2 source code\example2_syntax_errors.cpp(13) : error C2568: '<<' :
unable to resolve function overload

```

It tells us that this error has something to do with the operator <<. When we carefully look at the statement in Line 13, which is:

```
cout << "Num = " << num << ", tempNum = " < tempNum << endl;
```

we find that in the expression < tempNum, we have unintentionally used < in place of <<. So we must correct this error.

Let us look at the last error, which is:

```
c:\chapter 2 source code\example2_syntax_errors.cpp(15) : error C2561: 'main' :  
function must return a value  
    c:\chapter 2 source code\example2_syntax_errors.cpp(5) : see declaration  
of 'main'
```

This error occurs in Line 15. However, at this point, the explanation given, especially for a beginner, is somewhat unclear. However, if you look at the statement `return ;` in Line 15 and remember the syntax of the function `main` as well as all the programs given in this book, we find that the number 0 is missing, that is, this statement must be `return 0;`

From the errors reported by the compiler, we see that the compiler not only identifies the errors, but it also specifies the line numbers where the errors occur and the types of the errors. We can effectively use this information to fix syntax error.

After correcting all of the syntax errors, a correct program is:

```
#include <iostream>

using namespace std;

int main()
{
    int num;
    int tempNum;

    num = 18;

    tempNum = 2 * num;

    cout << "Num = " << num << ", tempNum = " << tempNum << endl;

    return 0;
}
```

The output is:

```
Num = 18, tempNum = 36
```

As you learn C++ and practice writing and executing programs, you will learn how to spot and fix syntax errors. It is possible that the list of errors reported by the compiler is longer than the program itself. This is because a syntax error in one line can cause syntax errors in subsequent lines. In situations like this, correct the syntax errors in the order they

are listed and compile your program, if necessary, after each correction. You will see how quickly the syntax errors list shrinks. The important thing is not to panic.

In the next section, we describe some simple rules that you can follow so that your program is properly structured.

Program Style and Form

In previous sections, you learned enough C++ concepts to write meaningful programs. Before beginning to write programs, however, you need to learn their proper structure, among other things. Using the proper structure for a C++ program makes it easier to understand and subsequently modify the program. There is nothing more frustrating than trying to follow and perhaps modify a program that is syntactically correct but has no structure.

In addition, every C++ program must satisfy certain rules of the language. A C++ program must contain the function `main`. It must also follow the syntax rules, which, like grammar rules, tell what is right and what is wrong and what is legal and what is illegal in the language. Other rules serve the purpose of giving precise meaning to the language; that is, they support the language's semantics.

The following sections are designed to help you learn how to use the C++ programming elements you have learned so far to create a functioning program. These sections cover the syntax; the use of blanks; the use of semicolons, brackets, and commas; semantics; naming identifiers; prompt lines; documentation, including comments; and form and style.

Syntax

The syntax rules of a language tell what is legal and what is not legal. Errors in syntax are detected during compilation. For example, consider the following C++ statements:

```
int x;           //Line 1
int y           //Line 2
double z;       //Line 3

y = w + x;      //Line 4
```

When these statements are compiled, a compilation error will occur at Line 2 because the semicolon is missing after the declaration of the variable `y`. A second compilation error will occur at Line 4 because the identifier `w` is used but has not been declared.

As discussed in Chapter 1, you enter a program into the computer by using a text editor. When the program is typed, errors are almost unavoidable. Therefore, when the program is compiled, you are most likely to see syntax errors. It is quite possible that a syntax error at a particular place might lead to syntax errors in several subsequent statements. It is very common for the omission of a single character to cause four or five error messages. However, when the first syntax error is removed and the program is recompiled, subsequent syntax errors caused by this syntax error may disappear. Therefore, you should correct syntax errors in the order in which the compiler lists them. As you become more

and:

```
const double CENTIMETERS_PER_INCH = 2.54;
double centimeters;
double inches;

centimeters = inches * CENTIMETERS_PER_INCH;
```

The identifiers in the second set of statements, such as `CENTIMETERS_PER_INCH`, are usually called **self-documenting** identifiers. As you can see, self-documenting identifiers can make comments less necessary.

Consider the self-documenting identifier `annualsale`. This identifier is called a **run-together word**. In using self-documenting identifiers, you may inadvertently include run-together words, which may lessen the clarity of your documentation. You can make run-together words easier to understand by either capitalizing the beginning of each new word or by inserting an underscore just before a new word. For example, you could use either `annualSale` or `annual_sale` to create an identifier that is more clear.

Recall that earlier in this chapter, we specified the general rules for naming named constants and variables. For example, an identifier used to name a named constant is all uppercase. If this identifier is a run-together word, then the words are separated with the underscore character.

Prompt Lines

Part of good documentation is the use of clearly written prompts so that users will know what to do when they interact with a program. There is nothing more frustrating than sitting in front of a running program and not having the foggiest notion of whether to enter something or what to enter. **Prompt lines** are executable statements that inform the user what to do. For example, consider the following C++ statements, in which `num` is an `int` variable:

```
cout << "Please enter a number between 1 and 10 and "
      << "press the return key" << endl;
cin >> num;
```

When these two statements execute in the order given, first the output statement causes the following line of text to appear on the screen:

```
Please enter a number between 1 and 10 and press the return key
```

After seeing this line, users know that they must enter a number and press the return key. If the program contained only the second statement, users would have no idea that they must enter a number, and the computer would wait forever for the input. The preceding output statement is an example of a prompt line.

In a program, whenever input is needed from users, you must include the necessary prompt lines. Furthermore, these prompt lines should include as much information as possible about what input is acceptable. For example, the preceding prompt line not

only tells the user to input a number, but also informs the user that the number should be between 1 and 10.

Documentation

The programs that you write should be clear not only to you, but also to anyone else. Therefore, you must properly document your programs. A well-documented program is easier to understand and modify, even a long time after you originally wrote it. You use comments to document programs. Comments should appear in a program to explain the purpose of the program, identify who wrote it, and explain the purpose of particular statements.

Form and Style

You might be thinking that C++ has too many rules. However, in practice, the rules give C++ a great degree of freedom. For example, consider the following two ways of declaring variables:

```
int feet, inch;
double x, y;
```

and:

```
int feet, inches; double x, y;
```

The computer would have no difficulty understanding either of these formats, but the first form is easier to read and follow. Of course, the omission of a single comma or semicolon in either format may lead to all sorts of strange error messages.

What about blank spaces? Where are they significant and where are they meaningless? Consider the following two statements:

```
int a,b,c;
```

and:

```
int    a,    b,    c;
```

Both of these declarations mean the same thing. Here, the blanks between the identifiers in the second statement are meaningless. On the other hand, consider the following statement:

```
inta,b,c;
```

This statement contains a syntax error. The lack of a blank between `int` and the identifier `a` changes the reserved word `int` and the identifier `a` into a new identifier, `inta`.

The clarity of the rules of syntax and semantics frees you to adopt formats that are pleasing to you and easier to understand.

The following example further elaborates on this.

EXAMPLE 2-30

Consider the following C++ program:

```
//An improperly formatted C++ program.

#include <iostream>
#include <string>
using namespace std;

int main()
{
int num; double height;
string name;
cout << "Enter an integer: "; cin >> num; cout << endl;
    cout<<"num: "<<num<<endl;
cout<<"Enter the first name: "; cin>>name;
    cout<<endl; cout <<"Enter the height: ";
cin>>height; cout<<endl;

cout<<"Name: "<<name<<endl;cout<<"Height: "
<<height; cout <<endl;return 0;
}
```

This program is syntactically correct; the C++ compiler would have no difficulty reading and compiling this program. However, this program is very hard to read. The program that you write should be properly indented and formatted. Note the difference when the program is reformatted:

```
//A properly formatted C++ program.

#include <iostream>
#include <string>

using namespace std;

int main()
{
    int num;
    double height;
    string name;

    cout << "Enter an integer: ";
    cin >> num;
    cout << endl;
```

```

    cout << "num: " << num << endl;

    cout << "Enter the first name: ";
    cin >> name;
    cout << endl;
    cout << "Enter the height: ";
    cin >> height;
    cout << endl;

    cout << "Name: " << name << endl;
    cout << "Height: " << height << endl;

    return 0;
}

```

As you can see, this program is easier to read. Your programs should be properly indented and formatted. To document the variables, programmers typically declare one variable per line. Also, always put a space before and after an operator. When you type your program using an IDE, typically, your program is automatically indented.

More on Assignment Statements

The assignment statements you have seen so far are called **simple assignment statements**. In certain cases, you can use special assignment statements called **compound assignment statements** to write simple assignment statements in a more concise notation.

Corresponding to the five arithmetic operators $+$, $-$, $*$, $/$, and $\%$, C++ provides five compound operators: $+=$, $-=$, $*=$, $/=$, and $\%=$, respectively. Consider the following simple assignment statement, in which x and y are `int` variables:

```
x = x * y;
```

Using the compound operator $*=$, this statement can be written as:

```
x *= y;
```

In general, using the compound operator $*=$, you can rewrite the simple assignment statement:

```
variable = variable * (expression);
```

as:

```
variable *= expression;
```

The other arithmetic compound operators have similar conventions. For example, using the compound operator `+=`, you can rewrite the simple assignment statement:

```
variable = variable + (expression);
```

as:

```
variable += expression;
```

The compound assignment statement allows you to write simple assignment statements in a concise fashion by combining an arithmetic operator with the assignment operator.

EXAMPLE 2-31

This example shows several compound assignment statements that are equivalent to simple assignment statements.

Simple Assignment Statement

```
i = i + 5;
counter = counter + 1;
sum = sum + number;
amount = amount * (interest + 1);
x = x / ( y + 5);
```

Compound Assignment Statement

```
i += 5;
counter += 1;
sum += number;
amount *= interest + 1;
x /= y + 5;
```

NOTE

Any compound assignment statement can be converted into a simple assignment statement. However, a simple assignment statement may not be (easily) converted to a compound assignment statement. For example, consider the following simple assignment statement:

```
x = x * y + z - 5;
```

To write this statement as a compound assignment statement, the variable `x` must be a common factor in the right side, which is not the case. Therefore, you cannot immediately convert this statement into a compound assignment statement. In fact, the equivalent compound assignment statement is:

```
x *= y + (z - 5) / x;
```

which is more complicated than the simple assignment statement. Furthermore, in the preceding compound statement, `x` cannot be 0. We recommend avoiding such compound expressions.

NOTE

In programming code, this book typically uses only the compound operator `+=`. So statements such as `a = a + b;` are written as `a += b;`.

PROGRAMMING EXAMPLE: Convert Length

Write a program that takes as input given lengths expressed in feet and inches. The program should then convert and output the lengths in centimeters. Assume that the given lengths in feet and inches are integers.

Input Length in feet and inches.

Output Equivalent length in centimeters.

PROBLEM ANALYSIS AND ALGORITHM DESIGN

The lengths are given in feet and inches, and you need to find the equivalent length in centimeters. One inch is equal to 2.54 centimeters. The first thing the program needs to do is convert the length given in feet and inches to all inches. Then, you can use the conversion formula, 1 inch = 2.54 centimeters, to find the equivalent length in centimeters. To convert the length from feet and inches to inches, you multiply the number of feet by 12, as 1 foot is equal to 12 inches, and add the given inches.

For example, suppose the input is 5 feet and 7 inches. You then find the total inches as follows:

```
totalInches = (12 * feet) + inches
             = 12 * 5 + 7
             = 67
```

You can then apply the conversion formula, 1 inch = 2.54 centimeters, to find the length in centimeters.

```
centimeters = totalInches * 2.54
             = 67 * 2.54
             = 170.18
```

Based on this analysis of the problem, you can design an algorithm as follows:

1. Get the length in feet and inches.
2. Convert the length into total inches.
3. Convert total inches into centimeters.
4. Output centimeters.

Variables The input for the program is two numbers: one for feet and one for inches. Thus, you need two variables: one to store feet and the other to store inches. Because the program will first convert the given length into inches, you need another variable to store the total inches. You also need a variable to store the equivalent length in centimeters. In summary, you need the following variables:

```
int feet;           //variable to hold given feet
int inches;         //variable to hold given inches
int totalInches;    //variable to hold total inches
double centimeters; //variable to hold length in centimeters
```

Named Constants To calculate the equivalent length in centimeters, you need to multiply the total inches by 2.54. Instead of using the value 2.54 directly in the program, you will declare this value as a named constant. Similarly, to find the total inches, you need to multiply the feet by 12 and add the inches. Instead of using 12 directly in the program, you will also declare this value as a named constant. Using a named constant makes it easier to modify the program later.

```
const double CENTIMETERS_PER_INCH = 2.54;
const int INCHES_PER_FOOT = 12;
```

MAIN ALGORITHM

In the preceding sections, we analyzed the problem and determined the formulas to do the calculations. We also determined the necessary variables and named constants. We can now expand the algorithm given in the section Problem Analysis and Algorithm Design to solve the problem given at the beginning of this programming example.

1. Prompt the user for the input. (Without a prompt line, the user will be staring at a blank screen and will not know what to do.)
2. Get the data.
3. Echo the input—that is, output what the program read as input. (Without this step, after the program has executed, you will not know what the input was.)
4. Find the length in inches.
5. Output the length in inches.
6. Convert the length to centimeters.
7. Output the length in centimeters.

Putting It Together Now that the problem has been analyzed and the algorithm has been designed, the next step is to translate the algorithm into C++ code. Because this is the first complete C++ program you are writing, let's review the necessary steps in sequence.

The program will begin with comments that document its purpose and functionality. As there is both input to this program (the length in feet and inches) and output (the equivalent length in centimeters), you will be using system resources for input/output. In other words, the program will use input statements to get data into the program and output statements to print the results. Because the data will be entered from the keyboard and the output will be displayed on the screen, the program must include the header file `iostream`. Thus, the first statement of the program, after the comments as described above, will be the preprocessor directive to include this header file.

This program requires two types of memory locations for data manipulation: named constants and variables. Typically, named constants hold special data, such as `CENTIMETERS_PER_INCH`. Depending on the nature of a named constant, it can be placed before the function `main` or within the function `main`. If a named constant is to be

used throughout the program, then it is typically placed before the function `main`. We will comment further on where to put named constants within a program in Chapter 7, when we discuss user-defined functions in general. Until then, usually, we will place named constants before the function `main` so that they can be used throughout the program.

This program has only one function, the function `main`, which will contain all of the programming instructions in its body. In addition, the program needs variables to manipulate data, and these variables will be declared in the body of the function `main`. The reasons for declaring variables in the body of the function `main` are explained in Chapter 7. The body of the function `main` will also contain the C++ statements that implement the algorithm. Therefore, the body of the function `main` has the following form:

```
int main()
{
    declare variables

    statements

    return 0;
}
```

To write the complete length conversion program, follow these steps:

1. Begin the program with comments for documentation.
2. Include header files, if any are used in the program.
3. Declare named constants, if any.
4. Write the definition of the function `main`.

COMPLETE PROGRAM LISTING

```

//*****
// Author: D. S. Malik
//
// Program Convert Measurements: This program converts
// measurements in feet and inches into centimeters using
// the formula that 1 inch is equal to 2.54 centimeters.
//*****

//Header file
#include <iostream>

using namespace std;

//Named constants
const double CENTIMETERS_PER_INCH = 2.54;
const int INCHES_PER_FOOT = 12;
```

```

int main ()
{
    //Declare variables
    int feet, inches;
    int totalInches;
    double centimeter;

    //Statements: Step 1 - Step 7
    cout << "Enter two integers, one for feet and "
         << "one for inches: "; //Step 1
    cin >> feet >> inches; //Step 2
    cout << endl;
    cout << "The numbers you entered are " << feet
         << " for feet and " << inches
         << " for inches. " << endl; //Step 3

    totalInches = INCHES_PER_FOOT * feet + inches; //Step 4

    cout << "The total number of inches = "
         << totalInches << endl; //Step 5

    centimeter = CENTIMETERS_PER_INCH * totalInches; //Step 6

    cout << "The number of centimeters = "
         << centimeter << endl; //Step 7

    return 0;
}

```

Sample Run: In this sample run, the user input is shaded.

Enter two integers, one for feet, one for inches: 15 7

The numbers you entered are 15 for feet and 7 for inches.

The total number of inches = 187

The number of centimeters = 474.98

PROGRAMMING EXAMPLE: Make Change

Write a program that takes as input any change expressed in cents. It should then compute the number of half-dollars, quarters, dimes, nickels, and pennies to be returned, returning as many half-dollars as possible, then quarters, dimes, nickels, and pennies, in that order. For example, 483 cents should be returned as 9 half-dollars, 1 quarter, 1 nickel, and 3 pennies.

Input Change in cents.

Output Equivalent change in half-dollars, quarters, dimes, nickels, and pennies.

PROBLEM ANALYSIS AND ALGORITHM DESIGN

Suppose the given change is **646** cents. To find the number of half-dollars, you divide **646** by **50**, the value of a half-dollar, and find the quotient, which is **12**, and the remainder, which is **46**. The quotient, **12**, is the number of half-dollars, and the remainder, **46**, is the remaining change.

Next, divide the remaining change by **25** to find the number of quarters. Since the remaining change is **46**, division by **25** gives the quotient **1**, which is the number of quarters, and a remainder of **21**, which is the remaining change. This process continues for dimes and nickels. To calculate the remainder in an integer division, you use the mod operator, `%`.

Applying this discussion to **646** cents yields the following calculations:

1. Change = **646**
2. Number of half-dollars = $646 / 50 = 12$
3. Remaining change = $646 \% 50 = 46$
4. Number of quarters = $46 / 25 = 1$
5. Remaining change = $46 \% 25 = 21$
6. Number of dimes = $21 / 10 = 2$
7. Remaining change = $21 \% 10 = 1$
8. Number of nickels = $1 / 5 = 0$
9. Number of pennies = remaining change = $1 \% 5 = 1$

This discussion translates into the following algorithm:

1. Get the change in cents.
2. Find the number of half-dollars.
3. Calculate the remaining change.
4. Find the number of quarters.
5. Calculate the remaining change.
6. Find the number of dimes.
7. Calculate the remaining change.
8. Find the number of nickels.
9. Calculate the remaining change, which is the number of pennies.

Variables From the previous discussion and algorithm, it appears that the program will need variables to hold the number of half-dollars, quarters, and so on. However, the numbers of half-dollars, quarters, and so on are not used in later calculations, so the program can simply output these values without saving each of them in a variable. The only thing that keeps changing is the change, so the program actually needs only one variable:

```
int change;
```

Named Constants To calculate the equivalent change, the program performs calculations using the values of a half-dollar, which is 50; a quarter, which is 25; a dime, which is 10; and a nickel, which is 5. Because these data are special and the program uses these values more than once, it makes sense to declare them as named constants. Using named constants also simplifies later modification of the program:

```
const int HALF_DOLLAR = 50;
const int QUARTER    = 25;
const int DIME       = 10;
const int NICKEL     = 5;
```

MAIN ALGORITHM

1. Prompt the user for input.
2. Get input.
3. Echo the input by displaying the entered change on the screen.
4. Compute and print the number of half-dollars.
5. Calculate the remaining change.
6. Compute and print the number of quarters.
7. Calculate the remaining change.
8. Compute and print the number of dimes.
9. Calculate the remaining change.
10. Compute and print the number of nickels.
11. Calculate the remaining change.
12. Print the remaining change.

COMPLETE PROGRAM LISTING

```

//*****
// Author: D. S. Malik
//
// Program Make Change: Given any amount of change expressed
// in cents, this program computes the number of half-dollars,
// quarters, dimes, nickels, and pennies to be returned,
// returning as many half-dollars as possible, then quarters,
// dimes, nickels, and pennies in that order.
//*****

//Header file
#include <iostream>

using namespace std;

//Named constants
const int HALF_DOLLAR = 50;
const int QUARTER    = 25;
const int DIME       = 10;
const int NICKEL     = 5;
```

```

int main()
{
    //Declare variable
    int change;

    //Statements: Step 1 - Step 12
    cout << "Enter change in cents: ";           //Step 1
    cin >> change;                               //Step 2
    cout << endl;

    cout << "The change you entered is " << change
        << endl;                                //Step 3

    cout << "The number of half-dollars to be returned "
        << "is " << change / HALF_DOLLAR
        << endl;                                //Step 4

    change = change % HALF_DOLLAR;              //Step 5

    cout << "The number of quarters to be returned is "
        << change / QUARTER << endl;            //Step 6

    change = change % QUARTER;                  //Step 7

    cout << "The number of dimes to be returned is "
        << change / DIME << endl;              //Step 8

    change = change % DIME;                     //Step 9

    cout << "The number of nickels to be returned is "
        << change / NICKEL << endl;            //Step 10

    change = change % NICKEL;                   //Step 11

    cout << "The number of pennies to be returned is "
        << change << endl;                     //Step 12

    return 0;
}

```

Sample Run: In this sample run, the user input is shaded.

Enter change in cents: 583

The change you entered is 583
 The number of half-dollars to be returned is 11
 The number of quarters to be returned is 1
 The number of dimes to be returned is 0
 The number of nickels to be returned is 1
 The number of pennies to be returned is 3

QUICK REVIEW

1. A C++ program is a collection of functions.
2. Every C++ program has a function called `main`.
3. A single-line comment starts with the pair of symbols `//` anywhere in the line.
4. Multiline comments are enclosed between `/*` and `*/`.
5. The compiler skips comments.
6. Reserved words cannot be used as identifiers in a program.
7. All reserved words in C++ consist of lowercase letters (see Appendix A).
8. In C++, identifiers are names of things.
9. A C++ identifier consists of letters, digits, and underscores and must begin with a letter or underscore.
10. Whitespaces include blanks, tabs, and newline characters.
11. A data type is a set of values together with a set of operations.
12. C++ data types fall into the following three categories: simple, structured, and pointers.
13. There are three categories of simple data: integral, floating-point, and enumeration.
14. Integral data types are classified into nine categories: `char`, `short`, `int`, `long`, `bool`, `unsigned char`, `unsigned short`, `unsigned int`, and `unsigned long`.
15. The values belonging to `int` data type are -2147483648 ($= -2^{31}$) to 2147483647 ($= 2^{31} - 1$).
16. The data type `bool` has only two values: `true` and `false`.
17. The most common character sets are ASCII, which has 128 values, and EBCDIC, which has 256 values.
18. The collating sequence of a character is its preset number in the character data set.
19. C++ provides three data types to manipulate decimal numbers: `float`, `double`, and `long double`.
20. The data type `float` is used in C++ to represent any real number between $-3.4E + 38$ and $3.4E + 38$. The memory allocated for a value of the `float` data type is four bytes.
21. The data type `double` is used in C++ to represent any real number between $-1.7E + 308$ and $1.7E + 308$. The memory allocated for a value of the `double` data type is eight bytes.
22. The arithmetic operators in C++ are addition (+), subtraction (-), multiplication (*), division (/), and modulus (%).

23. The modulus operator, `%`, takes only integer operands.
24. Arithmetic expressions are evaluated using the precedence rules and the associativity of the arithmetic operators.
25. All operands in an integral expression, or integer expression, are integers, and all operands in a floating-point expression are decimal numbers.
26. A mixed expression is an expression that consists of both integers and decimal numbers.
27. When evaluating an operator in an expression, an integer is converted to a floating-point number, with a decimal part of 0, only if the operator has mixed operands.
28. You can use the cast operator to explicitly convert values from one data type to another.
29. A string is a sequence of zero or more characters.
30. Strings in C++ are enclosed in double quotation marks.
31. A string containing no characters is called a null or empty string.
32. Every character in a string has a relative position in the string. The position of the first character is 0, the position of the second character is 1, and so on.
33. The length of a string is the number of characters in it.
34. During program execution, the contents of a named constant cannot be changed.
35. A named constant is declared by using the reserved word `const`.
36. A named constant is initialized when it is declared.
37. All variables must be declared before they can be used.
38. C++ does not automatically initialize variables.
39. Every variable has a name, a value, a data type, and a size.
40. When a new value is assigned to a variable, the old value is lost.
41. Only an assignment statement or an input (read) statement can change the value of a variable.
42. In C++, `>>` is called the stream extraction operator.
43. Input from the standard input device is accomplished by using `cin` and the stream extraction operator `>>`.
44. When data is input in a program, the data items, such as numbers, are usually separated by blanks, lines, or tabs.
45. In C++, `<<` is called the stream insertion operator.
46. Output of the program to the standard output device is accomplished by using `cout` and the stream insertion operator `<<`.
47. The manipulator `endl` positions the insertion point at the beginning of the next line on an output device.

48. Outputting or accessing the value of a variable in an expression does not destroy or modify the contents of the variable.
49. The character `\` is called the escape character.
50. The sequence `\n` is called the newline escape sequence.
51. All preprocessor commands start with the symbol `#`.
52. The preprocessor commands are processed by the preprocessor before the program goes through the compiler.
53. The preprocessor command `#include <iostream>` instructs the preprocessor to include the header file `iostream` in the program.
54. To use `cin` and `cout`, the program must include the header file `iostream` and either include the statement `using namespace std;` or refer to these identifiers as `std::cin` and `std::cout`.
55. All C++ statements end with a semicolon. The semicolon in C++ is called the statement terminator.
56. A C++ system has three components: environment, language, and the standard libraries.
57. Standard libraries are not part of the C++ language. They contain functions to perform operations, such as mathematical operations.
58. A file containing a C++ program usually ends with the extension `.cpp`.
59. Prompt lines are executable statements that tell the user what to do.
60. Corresponding to the five arithmetic operators `+`, `-`, `*`, `/`, and `%`, C++ provides five compound operators: `+=`, `-=`, `*=`, `/=`, and `%=`, respectively.

EXERCISES

1. Mark the following statements as true or false.
 - a. An identifier can be any sequence of digits and letters.
 - b. In C++, there is no difference between a reserved word and a pre-defined identifier.
 - c. A C++ identifier can start with a digit.
 - d. The operands of the modulus operator must be integers.
 - e. If `a = 4;` and `b = 3;`, then after the statement `a = b;` the value of `b` is still 3.
 - f. In the statement `cin >> y;`, `y` can only be an `int` or a `double` variable.
 - g. In an output statement, the newline character may be a part of the string.
 - h. The following is a legal C++ program:

```
int main()
{
    return 0;
}
```

- i. In a mixed expression, all the operands are converted to floating-point numbers.
 - j. Suppose `x = 5`. After the statement `y = x++`; executes, `y` is 5 and `x` is 6.
 - k. Suppose `a = 5`. After the statement `++a`; executes, the value of `a` is still 5 because the value of the expression is not saved in another variable.
2. Which of the following are valid C++ identifiers?
- a. `myFirstProgram` b. `MIX-UP` c. `C++Program2` d. `quiz7`
 - e. `ProgrammingLecture2` f. `1footEquals12Inches`
 - g. `Mike'sFirstAttempt` h. `Update Grade` i. `4th`
 - j. `New_Student`
3. Which of the following is a reserved word in C++?
- a. `Const` b. `include` c. `Char` d. `void` e. `int` f. `Return`
4. What is the difference between a keyword and a user-defined identifier?
5. Are the identifiers `firstName` and `FirstName` the same?
6. Evaluate the following expressions.
- a. `25 / 3` b. `20 - 12 / 4 * 2` c. `32 % 7` d. `3 - 5 % 7`
 - e. `18.0 / 4` f. `28 - 5 / 2.0` g. `17 + 5 % 2 - 3`
 - h. `15.0 + 3.0 * 2.0 / 5.0`
7. If `x = 5`, `y = 6`, `z = 4`, and `w = 3.5`, evaluate each of the following statements, if possible. If it is not possible, state the reason.
- a. `(x + z) % y` b. `(x + y) % w` c. `(y + w) % x` d. `(x + y) * w`
 - e. `(x % y) % z` f. `(y % z) % x` g. `(x * z) % y` h. `((x * y) * w) * z`

8. Given:

```
int num1, num2, newNum;
double x, y;
```

Which of the following assignments are valid? If an assignment is not valid, state the reason.

When not given, assume that each variable is declared.

- a. `num1 = 35;`
- b. `newNum = num1 - num2;`
- c. `num1 = 5; num2 = 2 + num1; num1 = num2 / 3;`
- d. `num1 * num2 = newNum;`
- e. `x = 12 * num1 - 15.3;`
- f. `num1 * 2 = newNum + num2;`
- g. `x / y = x * y;`

- h. `num2 = num1 % 2.0;`
 - i. `newNum = static_cast<int> (x) % 5;`
 - j. `x = x + y - 5;`
 - k. `newNum = num1 + static_cast<int> (4.6 / 2);`
9. Do a walk-through to find the value assigned to `e`. Assume that all variables are properly declared.
- ```

a = 3;
b = 4;
c = (a % b) * 6;
d = c / b;
e = (a + b + c + d) / 4;

```
10. Which of the following variable declarations are correct? If a variable declaration is not correct, give the reason(s) and provide the correct variable declaration.
- ```

n = 12;                //Line 1
char letter = ;        //Line 2
int one = 5, two;      //Line 3
double x, y, z;        //Line 4

```
11. Which of the following are valid C++ assignment statements? Assume that `i`, `x`, and `percent` are `double` variables.
- a. `i = i + 5;`
 - b. `x + 2 = x;`
 - c. `x = 2.5 * x;`
 - d. `percent = 10%;`
12. Write C++ statement(s) that accomplish the following.
- a. Declare `int` variables `x` and `y`. Initialize `x` to 25 and `y` to 18.
 - b. Declare and initialize an `int` variable `temp` to 10 and a `char` variable `ch` to 'A'.
 - c. Update the value of an `int` variable `x` by adding 5 to it.
 - d. Declare and initialize a `double` variable `payRate` to 12.50.
 - e. Copy the value of an `int` variable `firstNum` into an `int` variable `tempNum`.
 - f. Swap the contents of the `int` variables `x` and `y`. (Declare additional variables, if necessary.)
 - g. Suppose `x` and `y` are `double` variables. Output the contents of `x`, `y`, and the expression `x + 12 / y - 18`.
 - h. Declare a `char` variable `grade` and set the value of `grade` to 'A'.
 - i. Declare `int` variables to store four integers.
 - j. Copy the value of a `double` variable `z` to the nearest integer into an `int` variable `x`.

13. Write each of the following as a C++ expression.
- 32 times `a` plus `b`
 - The character that represents 8
 - The string that represents the name Julie Nelson.
 - $(b^2 - 4ac) / 2a$
 - $(a + b) / c(e f) - gh$
 - $(-b + (b^2 - 4ac)) / 2a$
14. Suppose `x`, `y`, `z`, and `w` are `int` variables. What value is assigned to each of these variables after the last statement executes?
- ```
x = 5; z = 3;
y = x - z;
z = 2 * y + 3;
w = x - 2 * y + z;
z = w - x;
w++;
```
15. Suppose `x`, `y`, and `z` are `int` variables and `w` and `t` are `double` variables. What value is assigned to each of these variables after the last statement executes?
- ```
x = 17;
y = 15;
x = x + y / 4;
z = x % 3 + 4;
w = 17 / 3 + 6.5;
t = x / 4.0 + 15 % 4 - 3.5;
```
16. Suppose `x`, `y`, and `z` are `int` variables and `x` = 2, `y` = 5, and `z` = 6. What is the output of each of the following statements?
- `cout << "x = " << x << ", y = " << y << ", z = " << z << endl;`
 - `cout << "x + y = " << x + y << endl;`
 - `cout << "Sum of " << x << " and " << z << " is " << x + z << endl;`
 - `cout << "z / x = " << z / x << endl;`
 - `cout << "2 times " << x << " = " << 2 * x << endl;`
17. What is the output of the following statements? Suppose `a` and `b` are `int` variables, `c` is a `double` variable, and `a` = 13, `b` = 5, and `c` = 17.5.
- `cout << a + b - c << endl;`
 - `cout << 15 / 2 + c << endl;`
 - `cout << a / static_cast<double>(b) + 2 * c << endl;`
 - `cout << 14 % 3 + 6.3 + b / a << endl;`
 - `cout << static_cast<int>(c) % 5 + a - b << endl;`
 - `cout << 13.5 / 2 + 4.0 * 3.5 + 18 << endl;`

18. Write C++ statements that accomplish the following.
 - a. Output the newline character.
 - b. Output the tab character.
 - c. Output double quotation mark.
19. Which of the following are correct C++ statements?
 - a. `cout << "Hello There!" << endl;`
 - b. `cout << "Hello";`
`<< " There!" << endl;`
 - c. `cout << "Hello"`
`<< " There!" << endl;`
 - d. `cout << 'Hello There!' << endl;`
20. Give meaningful identifiers for the following variables.
 - a. A variable to store the first name of a student.
 - b. A variable to store the discounted price of an item.
 - c. A variable to store the number of juice bottles.
 - d. A variable to store the number of miles traveled.
 - e. A variable to store the highest test score.
21. Write C++ statements to do the following.
 - a. Declare `int` variable `num1` and `num2`.
 - b. Prompt the user to input two numbers.
 - c. Input the first number in `num1` and the second number in `num2`.
 - d. Output `num1`, `num2`, and 2 times `num1` minus `num2`. Your output must identify each number and the expression.
22. The following program has syntax mistakes. Correct them. On each successive line, assume that any preceding error has been corrected.

```
#include <iostream>

const int SECRET_NUM = 11,213;
const PAY_RATE = 18.35

main()
{
    int one, two;
    double first, second;
    one = 18;
    two = 11;

    first = 25;
    second = first * three;
```

```

second = 2 * SECRET_NUM;
SECRET_NUM = SECRET_NUM + 3;
cout << first << " " << second << SECRET_NUM << endl;

paycheck = hoursWorked * PAY_RATE

cout << "Wages = " << paycheck << endl;
return 0;
}

```

23. The following program has syntax mistakes. Correct them. On each successive line, assume that any preceding error has been corrected.

```

const char = STAR = '*'
const int PRIME = 71;

int main
{
    int count, sum;
    double x;

    count = 1;
    sum = count + PRIME;
    x := 25.67;
    newNum = count * ONE + 2;
    sum + count = sum;
    x = x + sum * COUNT;
    cout << " count = " << count << ", sum = " << sum
        << ", PRIME = " << Prime << endl;
}

```

24. The following program has syntax errors. Correct them. On each successive line, assume that any preceding error has been corrected.

```

#include <iostream>

using namespace std;

int main()
{
    int temp;
    string first;

    cout << "Enter first name: ;
    cin >> first
    cout << endl;

    cout << "Enter last name: ;
    cin >> last;
    cout << endl;

    cout << "Enter today's temperature: ";
    cin >> temperature;
    cout << endl;
}

```

```
    cout << first << " " << last << today's temperature is: ";
    << temperature << endl;
```

```
    return 0;
```

```
}
```

25. What action must be taken before a variable can be used in a program?
26. Preprocessor directives begin with which of the following symbols:
a. * b. # c. \$ d. ! e. None of these.
27. Write equivalent compound statements if possible.
- a. $x = 2 * x$ b. $x = x + y - 2;$ c. $sum = sum + num;$
d. $z = z * x + 2 * z;$ e. $y = y / (x + 5);$
28. Write the following compound statements as equivalent simple statements.
- a. $x += 5 - z;$ b. $y *= 2 * x + 5 - z;$ c. $w += 2 * z + 4;$
d. $x -= z + y - t;$ e. $sum += num;$
29. Suppose a, b, and c are **int** variables and a = 5 and b = 6. What value is assigned to each variable after each statement executes? If a variable is undefined at a particular statement, report UND (undefined).

| | a | b | c |
|------------------------|---|---|---|
| a = (b++) + 3; | — | — | — |
| c = 2 * a + (++b); | — | — | — |
| b = 2 * (++c) - (a++); | — | — | — |

30. Suppose a, b, and sum are **int** variables and c is a **double** variable. What value is assigned to each variable after each statement executes? Suppose a = 3, b = 5, and c = 14.1.

| | a | b | c | sum |
|------------------|---|---|---|-----|
| sum = a + b + c; | — | — | — | — |
| c /= a; | — | — | — | — |
| b += c - a; | — | — | — | — |
| a *= 2 * b + c; | — | — | — | — |

31. What is printed by the following program? Suppose the input is:
20 15

```
#include <iostream>

using namespace std;

const int NUM = 10;
const double X = 20.5;

int main()
{
    int a, b;
    double z;
```

```

char grade;

a = 25;

cout << "a = " << a << endl;

cout << "Enter two integers: ";
cin >> a >> b;
cout << endl;

cout << "The numbers you entered are "
      << a << " and " << b << endl;

z = X + 2 * a - b;
cout << "z = " << z << endl;

grade = 'A';
cout << "Your grade is " << grade << endl;

a = 2 * NUM + z;
cout << "The value of a = " << a << endl;

return 0;
}

```

32. What is printed by the following program? Suppose the input is:

```

Miller
34
340

```

```

#include <iostream>
#include <string>

using namespace std;

const int PRIME_NUM = 11;

int main()
{
    const int SECRET = 17;

    string name;
    int id;
    int num;
    int mysteryNum;

    cout << "Enter last name: ";
    cin >> name;
    cout << endl;

    cout << "Enter a two digit number: ";
    cin >> num;
    cout << endl;

```

```

    id = 100 * num + SECRET;

    cout << "Enter a positive integer less than 1000: ";
    cin >> num;
    cout << endl;

    mysteryNum = num * PRIME_NUM - 3 * SECRET;

    cout << "Name: " << name << endl;
    cout << "Id: " << id << endl;
    cout << "Mystery number: " << mysteryNum << endl;

    return 0;
}

```

33. Rewrite the following program so that it is properly formatted.

```

#include <iostream>
#include <string>
using namespace std;
const double X = 13.45; const int Y=34;
const char BLANK= ' ';
int main()
{string firstName,lastName;int num;
double salary;
cout<<"Enter first name: "; cin>> firstName; cout<<endl;
cout<<"Enter last name: "; cin
>>lastName;cout<<endl;
    cout<<"Enter a positive integer less than 70:";
cin>>num;cout<<endl; salary=num*X;
    cout<<"Name: "<<firstName<<BLANK<<lastName<<endl;cout
<<"Wages: $"<<salary<<endl; cout<<"X = "<<X<<endl;
    cout<<"X+Y = " << X+Y << endl; return 0;
}

```

34. What type of input does the following program require, and in what order does the input need to be provided?

```

#include <iostream>

using namespace std;

int main()
{
    int age;
    double weight;
    string firstName, lastName;

    cin >> firstName >> lastName;
    cin >> age >> weight;

    return 0;
}

```

PROGRAMMING EXERCISES

1. Write a program that produces the following output:

```
*****
*   Programming Assignment 1   *
*   Computer Programming I    *
*   Author: ???               *
*   Due Date: Thursday, Jan. 24 *
*****
```

In your program, substitute ??? with your own name. If necessary, adjust the positions and the number of the stars to produce a rectangle.

2. Write a program that produces the following output:

```
CCCCCCCC      ++              ++
CC             ++              ++
CC             ++++++++      ++++++++
CC             ++++++++      ++++++++
CC             ++              ++
CCCCCCCC      ++              ++
```

3. Consider the following program segment

```
//include statement(s)
//using namespace statement

int main()
{
    //variable declaration

    //executable statements

    //return statement
}
```

- a. Write C++ statements that include the header files `iostream`.
- b. Write a C++ statement that allows you to use `cin`, `cout`, and `endl` without the prefix `std::`.
- c. Write C++ statements that declare the following variables: `num1`, `num2`, `num3`, and `average` of type `int`.
- d. Write C++ statements that store 125 into `num1`, 28 into `num2`, and -25 into `num3`.
- e. Write a C++ statement that stores the average of `num1`, `num2`, and `num3`, into `average`.
- f. Write C++ statements that output the values of `num1`, `num2`, `num3`, and `average`.
- g. Compile and run your program.

4. Repeat Exercise 3 by declaring `num1`, `num2`, and `num3`, and `average` of type `double`. Store 75.35 into `num1`, -35.56 into `num2`, and 15.76 into `num3`.
5. Consider the following C++ program in which the statements are in the incorrect order. Rearrange the statements so that it prompts the user to input the length and width of a rectangle and output the area and perimeter of the rectangle.

```
#include <iostream>
{
    int main()

        cout << "Enter the length: ";
        cin >> length;
        cout << endl;

        int length;

        area = length * width;

        return 0;

        int width;

        cin>> width;
        cout << "Enter the width: "
        cout << endl;

        cout << "Area = " << area << endl;
        cout << "Perimeter = " << perimeter << endl;

        int area;
        using namespace std;
        int perimeter;
}
```

6. Consider the following program segment:

```
//include statement(s)
//using namespace statement

int main()
{
    //variable declaration

    //executable statements

    //return statement
}
```

- a. Write C++ statements that include the header files `iostream` and `string`.
- b. Write a C++ statement that allows you to use `cin`, `cout`, and `endl` without the prefix `std::`.
- c. Write C++ statements that declare the following variables: `name` of type `string` and `studyHours` of type `double`.
- d. Write C++ statements that prompt and input a string into `name` and a `double` value into `studyHours`.
- e. Write a C++ statement that outputs the values of `name` and `studyHours` with the appropriate text. For example, if the value of `name` is "Donald" and the value of `studyHours` is 4.5, the output is:

Hello, Donald! on Saturday, you need to study 4.5 hours for the exam.

- f. Compile and run your program.
7. Write a program that prompts the user to input a decimal number and outputs the number rounded to the nearest integer.
8. Consider the following program segment:

```
//include statement(s)
//using namespace statement

int main()
{
    //variable declaration

    //executable statements

    //return statement
}
```

- a. Write C++ statements that include the header files `iostream` and `string`.
- b. Write a C++ statement that allows you to use `cin`, `cout`, and `endl` without the prefix `std::`.
- c. Write C++ statements that declare and initialize the following named constants: `SECRET` of type `int` initialized to 11 and `RATE` of type `double` initialized to 12.50.
- d. Write C++ statements that declare the following variables: `num1`, `num2`, and `newNum` of type `int`; `name` of type `string`; and `hoursWorked` and `wages` of type `double`.
- e. Write C++ statements that prompt the user to input two integers and store the first number in `num1` and the second number in `num2`.

- f. Write a C++ statement(s) that outputs the values of `num1` and `num2`, indicating which is `num1` and which is `num2`. For example, if `num1` is 8 and `num2` is 5, then the output is:

The value of `num1` = 8 and the value of `num2` = 5.

- g. Write a C++ statement that multiplies the value of `num1` by 2, adds the value of `num2` to it, and then stores the result in `newNum`. Then, write a C++ statement that outputs the value of `newNum`.
- h. Write a C++ statement that updates the value of `newNum` by adding the value of the named constant `SECRET`. Then, write a C++ statement that outputs the value of `newNum` with an appropriate message.
- i. Write C++ statements that prompt the user to enter a person's last name and then store the last name into the variable `name`.
- j. Write C++ statements that prompt the user to enter a decimal number between 0 and 70 and then store the number entered into `hoursWorked`.
- k. Write a C++ statement that multiplies the value of the named constant `RATE` with the value of `hoursWorked` and then stores the result into the variable `wages`.
- l. Write C++ statements that produce the following output:

```
Name:           //output the value of the variable name
Pay Rate: $      //output the value of the variable rate
Hours Worked:    //output the value of the variable
                 //hoursWorked
Salary: $        //output the value of the variable wages
```

For example, if the value of `name` is "Rainbow" and `hoursWorked` is 45.50, then the output is:

```
Name: Rainbow
Pay Rate: $12.50
Hours Worked: 45.50
Salary: $568.75
```

- m. Write a C++ program that tests each of the C++ statements that you wrote in parts a through l. Place the statements at the appropriate place in the previous C++ program segment. Test run your program (twice) on the following input data:
 - a. `num1 = 13, num2 = 28; name = "Jacobson"; hoursWorked = 48.30.`
 - b. `num1 = 32, num2 = 15; name = "Crawford"; hoursWorked = 58.45.`
- 9. Write a program that prompts the user to enter five test scores and then prints the average test score. (Assume that the test scores are decimal numbers.)

10. Write a program that prompts the user to input five decimal numbers. The program should then add the five decimal numbers, convert the sum to the nearest integer, and print the result.
11. Write a program that does the following:
 - a. Prompts the user to input five decimal numbers.
 - b. Prints the five decimal numbers.
 - c. Converts each decimal number to the nearest integer.
 - d. Adds the five integers.
 - e. Prints the sum and average of the five integers.
12. Write a program that prompts the capacity, in gallons, of an automobile fuel tank and the miles per gallons the automobile can be driven. The program outputs the number of miles the automobile can be driven without refueling.
13. Write a C++ program that prompts the user to input the elapsed time for an event in seconds. The program then outputs the elapsed time in hours, minutes, and seconds. (For example, if the elapsed time is 9630 seconds, then the output is 2:40:30.)
14. Write a C++ program that prompts the user to input the elapsed time for an event in hours, minutes, and seconds. The program then outputs the elapsed time in seconds.
15. To make a profit, a local store marks up the prices of its items by a certain percentage. Write a C++ program that reads the original price of the item sold, the percentage of the marked-up price, and the sales tax rate. The program then outputs the original price of the item, the percentage of the mark-up, the store's selling price of the item, the sales tax rate, the sales tax, and the final price of the item. (The final price of the item is the selling price plus the sales tax.)
16. Write a program that prompts the user to input a length expressed in centimeters. The program should then convert the length to inches (to the nearest inch) and output the length expressed in yards, feet, and inches, in that order. For example, suppose the input for centimeters is 312. To the nearest inch, 312 centimeters is equal to 123 inches. 123 inches would thus be output as:

3 yard(s), 1 foot (foot), and 3 inch(es).
17. Write a program to implement and test the algorithm that you designed for Exercise 15 of Chapter 1. (You may assume that the value of $\pi = 3.141593$. In your program, declare a named constant `PI` to store this value.)
18. A milk carton can hold 3.78 liters of milk. Each morning, a dairy farm ships cartons of milk to a local grocery store. The cost of producing one liter of milk is \$0.38, and the profit of each carton of milk is \$0.27. Write a program that does the following:

- a. Prompts the user to enter the total amount of milk produced in the morning.
 - b. Outputs the number of milk cartons needed to hold milk. (Round your answer to the nearest integer.)
 - c. Outputs the cost of producing milk.
 - d. Outputs the profit for producing milk.
19. Redo Programming Exercise 18 so that the user can also input the cost of producing one liter of milk and the profit on each carton of milk.
20. You found an exciting summer job for five weeks. It pays, say, \$15.50 per hour. Suppose that the total tax you pay on your summer job income is 14%. After paying the taxes, you spend 10% of your net income to buy new clothes and other accessories for the next school year and 1% to buy school supplies. After buying clothes and school supplies, you use 25% of the remaining money to buy savings bonds. For each dollar you spend to buy savings bonds, your parents spend \$0.50 to buy additional savings bonds for you. Write a program that prompts the user to enter the pay rate for an hour and the number of hours you worked each week. The program then outputs the following:
- a. Your income before and after taxes from your summer job.
 - b. The money you spend on clothes and other accessories.
 - c. The money you spend on school supplies.
 - d. The money you spend to buy savings bonds.
 - e. The money your parents spend to buy additional savings bonds for you.
21. A permutation of three objects, a , b , and c , is any arrangement of these objects in a row. For example, some of the permutations of these objects are abc , bca , and cab . The number of permutations of three objects is six. Suppose that these three objects are strings. Write a program that prompts the user to enter three strings. The program then outputs the six permutations of those strings.
22. Write a program that prompts the user to input a number of quarters, dimes, and nickels. The program then outputs the total value of the coins in pennies.
23. Newton's law states that the force, F , between two bodies of masses M_1 and M_2 is given by:


$$F = k \left(\frac{M_1 M_2}{d^2} \right),$$

in which k is the gravitational constant and d is the distance between the bodies. The value of k is approximately 6.67×10^{-8} dyn. cm²/g². Write a

program that prompts the user to input the masses of the bodies and the distance between the bodies. The program then outputs the force between the bodies.

24. One metric ton is approximately 2205 pounds. Write a program that prompts the user to input the amount of rice, in pounds, in a bag. The program outputs the number of bags needed to store one metric ton of rice.
25. Cindy uses the services of a brokerage firm to buy and sell stocks. The firm charges 1.5% service charges on the total amount for each transaction, buy or sell. When Cindy sells stocks, she would like to know if she gained or lost on a particular investment. Write a program that allows Cindy to input the number of shares sold, the purchase price of each share, and the selling price of each share. The program outputs the amount invested, the total service charges, amount gained or lost, and the amount received after selling the stock.

This page intentionally left blank



3 CHAPTER

INPUT/OUTPUT

IN THIS CHAPTER, YOU WILL:

- Learn what a stream is and examine input and output streams
- Explore how to read data from the standard input device
- Learn how to use predefined functions in a program
- Explore how to use the input stream functions `get`, `ignore`, `putback`, and `peek`
- Become familiar with input failure
- Learn how to write data to the standard output device
- Discover how to use manipulators in a program to format output
- Learn how to perform input and output operations with the `string` data type
- Learn how to debug logic errors
- Become familiar with file input and output

In Chapter 2, you were introduced to some of C++’s input/output (I/O) instructions, which get data into a program and print the results on the screen. You used `cin` and the extraction operator `>>` to get data from the keyboard, and `cout` and the insertion operator `<<` to send output to the screen. Because I/O operations are fundamental to any programming language, in this chapter, you will learn about C++’s I/O operations in more detail. First, you will learn about statements that extract input from the standard input device and send output to the standard output device. You will then learn how to format output using manipulators. In addition, you will learn about the limitations of the I/O operations associated with the standard input/output devices and learn how to extend these operations to other devices.

I/O Streams and Standard I/O Devices

A program performs three basic operations: it gets data, it manipulates the data, and it outputs the results. In Chapter 2, you learned how to manipulate numeric data using arithmetic operations. In later chapters, you will learn how to manipulate nonnumeric data. Because writing programs for I/O is quite complex, C++ offers extensive support for I/O operations by providing substantial prewritten I/O operations, some of which you encountered in Chapter 2. In this chapter, you will learn about various I/O operations that can greatly enhance the flexibility of your programs.

In C++, I/O is a sequence of bytes, called a stream, from the source to the destination. The bytes are usually characters, unless the program requires other types of information, such as a graphic image or digital speech. Therefore, a **stream** is a sequence of characters from the source to the destination. There are two types of streams:

Input stream: A sequence of characters from an input device to the computer.

Output stream: A sequence of characters from the computer to an output device.

Recall that the standard input device is usually the keyboard, and the standard output device is usually the screen. To receive data from the keyboard and send output to the screen, every C++ program must use the header file `iostream`. This header file contains, among other things, the definitions of two data types, `istream` (input stream) and `ostream` (output stream). The header file also contains two variable declarations, one for `cin` (pronounced “see-in”), which stands for **common input**, and one for `cout` (pronounced “see-out”), which stands for **common output**.

These variable declarations are similar to the following C++ statements:

```
istream cin;
ostream cout;
```

To use `cin` and `cout`, every C++ program must use the preprocessor directive:

```
#include <iostream>
```

NOTE

From Chapter 2, recall that you have been using the statement `using namespace std;` in addition to including the header file `iostream` to use `cin` and `cout`. Without the statement `using namespace std;`, you refer to these identifiers as `std::cin` and `std::cout`. In Chapter 8, you will learn about the meaning of the statement `using namespace std;` in detail.

3

Variables of type `istream` are called **input stream variables**; variables of type `ostream` are called **output stream variables**. A **stream variable** is either an input stream variable or an output stream variable.

Because `cin` and `cout` are already defined and have specific meanings, to avoid confusion, you should never redefine them in programs.

The variable `cin` has access to operators and functions that can be used to extract data from the standard input device. You have briefly used the extraction operator `>>` to input data from the standard input device. The next section describes in detail how the extraction operator `>>` works. In the following sections, you will learn how to use the functions `get`, `ignore`, `peek`, and `putback` to input data in a specific manner.

`cin` and the Extraction Operator `>>`

In Chapter 2, you saw how to input data from the standard input device by using `cin` and the extraction operator `>>`. Suppose `payRate` is a `double` variable. Consider the following C++ statement:

```
cin >> payRate;
```

When the computer executes this statement, it inputs the next number typed on the keyboard and stores this number in `payRate`. Therefore, if the user types 15.50, the value stored in `payRate` is 15.50.

The extraction operator `>>` is binary and thus takes two operands. The left-side operand must be an input stream variable, such as `cin`. Because the purpose of an input statement is to read and store values in a memory location and because only variables refer to memory locations, the right-side operand is a variable.

NOTE

The extraction operator `>>` is defined only for putting data into variables of simple data types. Therefore, the right-side operand of the extraction operator `>>` is a variable of the simple data type. However, C++ allows the programmer to extend the definition of the extraction operator `>>` so that data can also be put into other types of variables by using an input statement. You will learn this mechanism in the chapter entitled *Overloading and Templates*, later in this book.

The syntax of an input statement using `cin` and the extraction operator `>>` is:

```
cin >> variable >> variable...;
```

As you can see in the preceding syntax, a single input statement can read more than one data item by using the operator `>>` several times. Every occurrence of `>>` extracts the next data item from the input stream. For example, you can read both `payRate` and `hoursWorked` via a single input statement by using the following code:

```
cin >> payRate >> hoursWorked;
```

There is no difference between the preceding input statement and the following two input statements. Which form you use is a matter of convenience and style.

```
cin >> payRate;
cin >> hoursWorked;
```

How does the extraction operator `>>` work? When scanning for the next input, `>>` skips all whitespace characters. Recall that whitespace characters consist of blanks and certain nonprintable characters, such as tabs and the newline character. Thus, whether you separate the input data by lines or blanks, the extraction operator `>>` simply finds the next input data in the input stream. For example, suppose that `payRate` and `hoursWorked` are `double` variables. Consider the following input statement:

```
cin >> payRate >> hoursWorked;
```

Whether the input is:

```
15.50 48.30
```

or:

```
15.50    48.30
```

or:

```
15.50
48.30
```

the preceding input statement would store 15.50 in `payRate` and 48.30 in `hoursWorked`. Note that the first input is separated by a blank, the second input is separated by a tab, and the third input is separated by a line.

Now suppose that the input is 2. How does the extraction operator `>>` distinguish between the character 2 and the number 2? The right-side operand of the extraction operator `>>` makes this distinction. If the right-side operand is a variable of the data type `char`, the input 2 is treated as the character 2 and, in this case, the ASCII value of 2 is stored. If the right-side operand is a variable of the data type `int` or `double`, the input 2 is treated as the number 2.

Next, consider the input 25 and the statement:

```
cin >> a;
```

where `a` is a variable of some simple data type. If `a` is of the data type `char`, only the single character 2 is stored in `a`. If `a` is of the data type `int`, 25 is stored in `a`. If `a` is of the data type

double, the input 25 is converted to the decimal number 25.0. Table 3-1 summarizes this discussion by showing the valid input for a variable of the simple data type.

TABLE 3-1 Valid Input for a Variable of the Simple Data Type

| Data Type of a | Valid Input for a |
|----------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| char | One printable character except the blank |
| int | An integer, possibly preceded by a + or – sign |
| double | A decimal number, possibly preceded by a + or – sign. If the actual data input is an integer, the input is converted to a decimal number with the zero decimal part. |

3

When reading data into a **char** variable, after skipping any leading whitespace characters, the extraction operator >> finds and stores only the next character; reading stops after a single character. To read data into an **int** or **double** variable, after skipping all leading whitespace characters and reading the plus or minus sign (if any), the extraction operator >> reads the digits of the number, including the decimal point for floating-point variables, and stops when it finds a whitespace character or a character other than a digit.

EXAMPLE 3-1

Suppose you have the following variable declarations:

```
int a, b;
double z;
char ch;
```

The following statements show how the extraction operator >> works.

| Statement | Input | Value Stored in Memory |
|------------------|----------|---------------------------------------|
| 1 cin >> ch; | A | ch = 'A' |
| 2 cin >> ch; | AB | ch = 'A', 'B' is held for later input |
| 3 cin >> a; | 48 | a = 48 |
| 4 cin >> a; | 46.35 | a = 46, .35 is held for later input |
| 5 cin >> z; | 74.35 | z = 74.35 |
| 6 cin >> z; | 39 | z = 39.0 |
| 7 cin >> z >> a; | 65.78 38 | z = 65.78, a = 38 |

| Statement | Input | Value Stored in Memory |
|-------------------------------------------|------------|----------------------------------------------|
| 8 <code>cin >> a >> b;</code> | 4 60 | a = 4, b = 60 |
| 9 <code>cin >> a >> z;</code> | 46 32.4 68 | a = 46, z = 32.4, 68 is held for later input |

EXAMPLE 3-2

Suppose you have the following variable declarations:

```
int a;  
double z;  
char ch;
```

The following statements show how the extraction operator >> works.

| Statement | Input | Value Stored in Memory |
|-------------------------------------------------------|-----------------|-------------------------------|
| 1 <code>cin >> a >> ch >> z;</code> | 57 A 26.9 | a = 57, ch = 'A', z = 26.9 |
| 2 <code>cin >> a >> ch >> z;</code> | 57 A 26.9 | a = 57, ch = 'A', z = 26.9 |
| 3 <code>cin >> a >> ch >> z;</code> | 57 A 26.9 | a = 57, ch = 'A', z = 26.9 |
| 4 <code>cin >> a >> ch >> z;</code> | 57A26.9 | a = 57, ch = 'A', z = 26.9 |

Note that for statements 1 through 4, the input statement is the same; however, the data is entered differently. For statement 1, data is entered on the same line separated by blanks. For statement 2, data is entered on two lines; the first two input values are separated by two blank spaces, and the third input is on the next line. For statement 3, all three input values are separated by lines, and for statement 4, all three input values are on the same line, but there is no space between them. Note that the second input is a non-numeric character. These statements work as follows.

Statements 1, 2, and 3 are easy to follow. Let us look at statement 4.

In statement 4, first the extraction operator >> extracts 57 from the input stream and stores it in **a**. Then, the extraction operator >> extracts the character 'A' from the input stream and stores it in **ch**. Next, 26.9 is extracted and stored in **z**.

Note that statements 1, 2, and 3 illustrate that regardless of whether the input is separated by blanks or by lines, the extraction operator >> always finds the next input.

EXAMPLE 3-3

Suppose you have the following variable declarations:

```
int a, b;
double z;
char ch, ch1, ch2;
```

The following statements show how the extraction operator >> works.

| | Statement | Input | Value Stored in Memory |
|---|-----------------------------------------------------|--------------|--------------------------------------------------------------------------------------|
| 1 | <code>cin >> z >> ch >> a;</code> | 36.78B34 | <code>z = 36.78</code> , <code>ch = 'B'</code> , <code>a = 34</code> |
| 2 | <code>cin >> z >> ch >> a;</code> | 36.78 B34 | <code>z = 36.78</code> , <code>ch = 'B'</code> , <code>a = 34</code> |
| 3 | <code>cin >> a >> b >> z;</code> | 11 34 | <code>a = 11</code> , <code>b = 34</code> , computer waits for the next number |
| 4 | <code>cin >> a >> z;</code> | 78.49 | <code>a = 78</code> , <code>z = 0.49</code> |
| 5 | <code>cin >> ch >> a;</code> | 256 | <code>ch = '2'</code> , <code>a = 56</code> |
| 6 | <code>cin >> a >> ch;</code> | 256 | <code>a = 256</code> , computer waits for the input value for <code>ch</code> |
| 7 | <code>cin >> ch1 >> ch2;</code> | A B | <code>ch1 = 'A'</code> , <code>ch2 = 'B'</code> |

In statement 1, because the first right-side operand of >> is `z`, which is a `double` variable, `36.78` is extracted from the input stream, and the value `36.78` is stored in `z`. Next, `'B'` is extracted and stored in `ch`. Finally, `34` is extracted and stored in `a`. Statement 2 works similarly.

In statement 3, `11` is stored in `a`, and `34` is stored in `b`, but the input stream does not have enough input data to fill each variable. In this case, the computer waits (and waits, and waits...) for the next input to be entered. The computer does not continue to execute until the next value is entered.

In statement 4, the first right-side operand of the extraction operator >> is a variable of the type `int`, and the input is `78.49`. Now for `int` variables, after inputting the digits of the number, the reading stops at the first whitespace character or a character other than a digit. Therefore, the operator >> stores `78` into `a`. The next right-side operand of >> is the variable `z`, which is of the type `double`. Therefore, the operator >> stores the value `.49` as `0.49` into `z`.

In statement 5, the first right-side operand of the extraction operator >> is a `char` variable, so the first nonwhitespace character, `'2'`, is extracted from the input stream. The character `'2'` is stored in the variable `ch`. The next right-side operand of the extraction operator >> is an `int` variable, so the next input value, `56`, is extracted and stored in `a`.

In statement 6, the first right-side operator of the extraction operator `>>` is an `int` variable, so the first data item, `256`, is extracted from the input stream and stored in `a`. Now the computer waits for the next data item for the variable `ch`.

In statement 7, `'A'` is stored into `ch1`. The extraction operator `>>` then skips the blank, and `'B'` is stored in `ch2`.

NOTE

Recall that during program execution, when entering character data such as letters, you do not enter the single quotes around the character.

What happens if the input stream has more data items than required by the program? After the program terminates, any values left in the input stream are discarded. When you enter data for processing, the data values should correspond to the data types of the variables in the input statement. Recall that when entering a number for a `double` variable, it is not necessary for the input number to have a decimal part. If the input number is an integer and has no decimal part, it is converted to a decimal value. The computer, however, does not tolerate any other kind of mismatch. For example, entering a `char` value into an `int` or `double` variable causes serious errors, called **input failure**. Input failure is discussed later in this chapter.

The extraction operator, when scanning for the next input in the input stream, skips whitespace such as blanks and the newline character. However, there are situations when these characters must also be stored and processed. For example, if you are processing text in a line-by-line fashion, you must know where in the input stream the newline character is located. Without identifying the position of the newline character, the program would not know where one line ends and another begins. The next few sections teach you how to input data into a program using the input functions, such as `get`, `ignore`, `putback`, and `peek`. These functions are associated with the data type `istream` and are called **istream member functions**. I/O functions, such as `get`, are typically called **stream member functions** or **stream functions**.

Before you can learn about the input functions `get`, `ignore`, `putback`, `peek`, and other I/O functions that are used in this chapter, you need to first understand what a function is and how it works. You will study functions in detail and learn how to write your own in Chapters 6 and 7.

Using Predefined Functions in a Program

As noted in Chapter 2, a function, also called a subprogram, is a set of instructions. When a function executes, it accomplishes something. The function `main`, as you saw in Chapter 2, executes automatically when you run a program. Other functions execute

only when they are activated—that is, called. C++ comes with a wealth of functions, called **predefined functions**, that are already written. In this section, you will learn how to use some predefined functions that are provided as part of the C++ system. Later in this chapter, you will learn how to use stream functions to perform a specific I/O operation.

Recall from Chapter 2 that predefined functions are organized as a collection of libraries, called header files. A particular header file may contain several functions. Therefore, to use a particular function, you need to know the name of the function and a few other things, which are described shortly.

A very useful function, `pow`, called the power function, can be used to calculate x^y in a program. That is, `pow(x, y) = x^y` . For example, `pow(2.0, 3.0) = $2.0^{3.0} = 8.0$` and `pow(4.0, 0.5) = $4.0^{0.5} = \sqrt{4.0} = 2.0$` . The numbers `x` and `y` that you use in the function `pow` are called the **arguments** or **parameters** of the function `pow`. For example, in `pow(2.0, 3.0)`, the parameters are 2.0 and 3.0.

An expression such as `pow(2.0, 3.0)` is called a **function call**, which causes the code attached to the predefined function `pow` to execute and, in this case, computes $2.0^{3.0}$. The header file `cmath` contains the specification of the function `pow`.

To use a predefined function in a program, you need to know the name of the header file containing the specification of the function and include that header file in the program. In addition, you need to know the name of the function, the number of parameters the function takes, and the type of each parameter. You must also be aware of what the function is going to do. For example, to use the function `pow`, you must include the header file `cmath`. The function `pow` has two parameters, which are decimal numbers. The function calculates the first parameter to the power of the second parameter. (Appendix F describes some commonly used header files and predefined functions.)

The program in the following example illustrates how to use predefined functions in a program. More specifically, we use some math functions, from the header file `cmath`, and the `string` function `length`, from the header file `string`. Note that the function `length` determines the length of a `string`.

EXAMPLE 3-4

```
// How to use predefined functions.
#include <iostream>
#include <cmath>
#include <string>

using namespace std;

int main()
{
    double u, v;
    string str;
```

```

    cout << "Line 1: 2 to the power of 6 = "
         << static_cast<int>(pow(2.0, 6.0))
         << endl;                                     //Line 1

    u = 12.5;                                          //Line 2
    v = 3.0;                                          //Line 3
    cout << "Line 4: " << u << " to the power of "
         << v << " = " << pow(u, v) << endl;        //Line 4

    cout << "Line 5: Square root of 24 = "
         << sqrt(24.0) << endl;                       //Line 5

    u = pow(8.0, 2.5);                                //Line 6
    cout << "Line 7: u = " << u << endl;              //Line 7

    str = "Programming with C++";                     //Line 8

    cout << "Line 9: Length of str = "
         << str.length() << endl;                   //Line 9

    return 0;
}

```

Sample Run:

```

Line 1: 2 to the power of 6 = 64
Line 4: 12.5 to the power of 3 = 1953.13
Line 5: Square root of 24 = 4.89898
Line 7: u = 181.019
Line 9: Length of str = 20

```

The preceding program works as follows. The statement in Line 1 uses the function `pow` to determine and output 2^6 . The statement in Line 2 sets `u` to 12.5, and the statement in Line 3 sets `v` to 3.0. The statement in Line 4 determines and outputs u^v . The statement in Line 5 uses the function `sqrt`, of the header file `cmath`, to determine and output the square root of 24.0. The statement in Line 6 determines and assigns $8.0^{2.5}$ to `u`. The statement in Line 7 outputs the value of `u`.

The statement in Line 8 stores the string "Programming with C++" in `str`. The statement in Line 9 uses the string function `length` to determine and output the length of `str`. Note how the function `length` is used. Later in this chapter, we explain the meaning of expressions such as `str.length()`.

Because I/O is fundamental to any programming language and because writing instructions to perform a specific I/O operation is not a job for everyone, every programming language provides a set of useful functions to perform specific I/O operations. In the remainder of this chapter, you will learn how to use some of these functions in a program. As a programmer, you must pay close attention to how these functions are used so that you can get the most out of them. The first function you will learn about here is the function `get`.

cin and the get Function

As you have seen, the extraction operator skips all leading whitespace characters when scanning for the next input value. Consider the variable declarations:

```
char ch1, ch2;
int num;
```

and the input:

A 25

Now consider the following statement:

```
cin >> ch1 >> ch2 >> num;
```

When the computer executes this statement, 'A' is stored in `ch1`, the blank is skipped by the extraction operator `>>`, the character '2' is stored in `ch2`, and 5 is stored in `num`. However, what if you intended to store 'A' in `ch1`, the blank in `ch2`, and 25 in `num`? It is clear that you cannot use the extraction operator `>>` to input this data.

As stated earlier, sometimes you need to process the entire input, including whitespace characters, such as blanks and the newline character. For example, suppose you want to process the entered data on a line-by-line basis. Because the extraction operator `>>` skips the newline character and unless the program captures the newline character, the computer does not know where one line ends and the next begins.

The variable `cin` can access the stream function `get`, which is used to read character data. The `get` function inputs the very next character, including whitespace characters, from the input stream and stores it in the memory location indicated by its argument. The function `get` comes in many forms. Next, we discuss the one that is used to read a character.

The syntax of `cin`, together with the `get` function to read a character, follows:

```
cin.get(varChar);
```

In the `cin.get` statement, `varChar` is a `char` variable. `varChar`, which appears in parentheses following the function name, is called the **argument** or **parameter** of the function. The effect of the preceding statement would be to store the next input character in the variable `varChar`.

Now consider the following input again:

A 25

To store 'A' in `ch1`, the blank in `ch2`, and 25 in `num`, you can effectively use the `get` function as follows:

```
cin.get(ch1);
cin.get(ch2);
cin >> num;
```

Because this form of the `get` function has only one argument and reads only one character and you need to read two characters from the input stream, you need to call this function twice. Notice that you cannot use the `get` function to read data into the variable `num` because `num` is an `int` variable. The preceding form of the `get` function reads values of only the `char` data type.

The preceding set of `cin.get` statements is equivalent to the following statements:

```
cin >> ch1;  
cin.get(ch2);  
cin >> num;
```

NOTE

The function `get` has other forms, one of which you will study in Chapter 9. For the next few chapters, you need only the form of the function `get` introduced here.

`cin` and the `ignore` Function

When you want to process only partial data (say, within a line), you can use the stream function `ignore` to discard a portion of the input. The syntax to use the function `ignore` is:

```
cin.ignore(intExp, chExp);
```

Here, `intExp` is an integer expression yielding an integer value, and `chExp` is a `char` expression yielding a `char` value. In fact, the value of the expression `intExp` specifies the maximum number of characters to be ignored in a line.

Suppose `intExp` yields a value of, say 100. This statement says to ignore the next 100 characters or ignore the input until it encounters the character specified by `chExp`, whichever comes first. To be specific, consider the following statement:

```
cin.ignore(100, '\n');
```

When this statement executes, it ignores either the next 100 characters or all characters until the newline character is found, whichever comes first. For example, if the next 120 characters do not contain the newline character, then only the first 100 characters are discarded and the next input data is the character 101. However, if the 75th character is the newline character, then the first 75 characters are discarded and the next input data is the 76th character. Similarly, the execution of the statement:

```
cin.ignore(100, 'A');
```

results in ignoring the first 100 characters or all characters until the character 'A' is found, whichever comes first.

EXAMPLE 3-5

Consider the declaration:

```
int a, b;
```

and the input:

```
25 67 89 43 72
12 78 34
```

Now consider the following statements:

```
cin >> a;
cin.ignore(100, '\n');
cin >> b;
```

The first statement, `cin >> a;`, stores 25 in `a`. The second statement, `cin.ignore(100, '\n');`, discards all of the remaining numbers in the first line. The third statement, `cin >> b;`, stores 12 (from the next line) in `b`.

EXAMPLE 3-6

Consider the declaration:

```
char ch1, ch2;
```

and the input:

```
Hello there. My name is Mickey.
```

- a. Consider the following statements:

```
cin >> ch1;
cin.ignore(100, '.');
cin >> ch2;
```

The first statement, `cin >> ch1;`, stores 'H' in `ch1`. The second statement, `cin.ignore(100, '.');`, results in discarding all characters until . (period). The third statement, `cin >> ch2;`, stores the character 'M' (from the same line) in `ch2`. (Remember that the extraction operator `>>` skips all leading whitespace characters. Thus, the extraction operator skips the space after . [period] and stores 'M' in `ch2`.)

- b. Suppose that we have the following statement:

```
cin >> ch1;
cin.ignore(5, '.');
cin >> ch2;
```

The first statement, `cin >> ch1;`, stores 'H' in `ch1`. The second statement, `cin.ignore(5, '.');`, results in discarding the next five characters, that is, until `t`. The third statement, `cin >> ch2;`, stores the character 't' (from the same line) in `ch2`.

When the function `ignore` is used without any arguments, then it only skips the very next character. For example, the following statement will skip the very next character:

```
cin.ignore();
```

This statement is typically used to skip the newline character.

The `putback` and `peek` Functions

Suppose you are processing data that is a mixture of numbers and characters. Moreover, the numbers must be read and processed as numbers. You have also looked at many sets of sample data and cannot determine whether the next input is a character or a number. You could read the entire data set character by character and check whether a certain character is a digit. If a digit is found, you could then read the remaining digits of the number and somehow convert these characters into numbers. This programming code would be somewhat complex. Fortunately, C++ provides two very useful stream functions that can be used effectively in these types of situations.

The stream function `putback` lets you put the last character extracted from the input stream by the `get` function back into the input stream. The stream function `peek` looks into the input stream and tells you what the next character is without removing it from the input stream. By using these functions, after determining that the next input is a number, you can read it as a number. You do not have to read the digits of the number as characters and then convert these characters to that number.

The syntax to use the function `putback` is:

```
istreamVar.putback(ch);
```

Here, `istreamVar` is an input stream variable, such as `cin`, and `ch` is a `char` variable.

The `peek` function returns the next character from the input stream but does not remove the character from that stream. In other words, the function `peek` looks into the input stream and checks the identity of the next input character. Moreover, after checking the next input character in the input stream, it can store this character in a designated memory location without removing it from the input stream. That is, when you use the `peek` function, the next input character stays the same, even though you now know what it is.

The syntax to use the function `peek` is:

```
ch = istreamVar.peek();
```

Here, `istreamVar` is an input stream variable, such as `cin`, and `ch` is a `char` variable.

Notice how the function `peek` is used. First, the function `peek` is used in an assignment statement. It is not a stand-alone statement like `get`, `ignore`, and `putback`. Second, the function `peek` has empty parentheses. Until you become comfortable with using a function and learn how to write one, pay close attention to how to use a predefined function.

The following example illustrates how to use the `peek` and `putback` functions.

EXAMPLE 3-7

//Functions `peek` and `putback`

```
#include <iostream>

using namespace std;

int main()
{
    char ch;

    cout << "Line 1: Enter a string: ";           //Line 1
    cin.get(ch);                                 //Line 2
    cout << endl;                                //Line 3
    cout << "Line 4: After first cin.get(ch); "
         << "ch = " << ch << endl;               //Line 4

    cin.get(ch);                                 //Line 5
    cout << "Line 6: After second cin.get(ch); "
         << "ch = " << ch << endl;               //Line 6

    cin.putback(ch);                             //Line 7
    cin.get(ch);                                 //Line 8
    cout << "Line 9: After putback and then "
         << "cin.get(ch); ch = " << ch << endl;   //Line 9

    ch = cin.peek();                             //Line 10
    cout << "Line 11: After cin.peek(); ch = "
         << ch << endl;                           //Line 11

    cin.get(ch);                                 //Line 12
    cout << "Line 13: After cin.get(ch); ch = "
         << ch << endl;                           //Line 13

    return 0;
}
```

Sample Run: In this sample run, the user input is shaded.

Line 1: Enter a string: **abcd**

Line 4: After first `cin.get(ch)`; `ch = a`

Line 6: After second `cin.get(ch)`; `ch = b`

Line 9: After `putback` and then `cin.get(ch); ch = b`
 Line 11: After `cin.peek(); ch = c`
 Line 13: After `cin.get(ch); ch = c`

The user input, `abcd`, allows you to see the effect of the functions `get`, `putback`, and `peek` in the preceding program. The statement in Line 1 prompts the user to enter a string. In Line 2, the statement `cin.get(ch);` extracts the first character from the input stream and stores it in the variable `ch`. So after Line 2 executes, the value of `ch` is `'a'`.

The `cout` statement in Line 4 outputs the value of `ch`. The statement `cin.get(ch);` in Line 5 extracts the next character from the input stream, which is `'b'`, and stores it in `ch`. At this point, the value of `ch` is `'b'`.

The `cout` statement in Line 6 outputs the value of `ch`. The `cin.putback(ch);` statement in Line 7 puts the previous character extracted by the `get` function, which is `'b'`, back into the input stream. Therefore, the next character to be extracted from the input stream is `'b'`.

The `cin.get(ch);` statement in Line 8 extracts the next character from the input stream, which is still `'b'`, and stores it in `ch`. Now the value of `ch` is `'b'`. The `cout` statement in Line 9 outputs the value of `ch` as `'b'`.

In Line 10, the statement `ch = cin.peek();` checks the next character in the input stream, which is `'c'`, and stores it in `ch`. The value of `ch` is now `'c'`. The `cout` statement in Line 11 outputs the value of `ch`. The `cin.get(ch);` statement in Line 12 extracts the next character from the input stream and stores it in `ch`. The `cout` statement in Line 13 outputs the value of `ch`, which is still `'c'`.

Note that the statement `ch = cin.peek();` in Line 10 did not remove the character `'c'` from the input stream; it only peeked into the input stream. The output of Lines 11 and 13 demonstrates this functionality.

The Dot Notation between I/O Stream Variables and I/O Functions: A Precaution

In the preceding sections, you learned how to manipulate an input stream to get data into a program. You also learned how to use the functions `get`, `ignore`, `peek`, and `putback`. It is important that you use these functions exactly as shown. For example, to use the `get` function, you used statements such as the following:

```
cin.get(ch);
```

Omitting the dot—that is, the period between the variable `cin` and the function name `get`—results in a syntax error. For example, in the statement:

```
cin.get(ch);
```

`cin` and `get` are two separate identifiers separated by a dot. In the statement:

```
cinget(ch);
```

`cin.get` becomes a new identifier. If you used `cin.get(ch);` in a program, the compiler would try to resolve an undeclared identifier, which would generate an error. Similarly, missing parentheses, as in `cin.getch;`, result in a syntax error. Also, remember that you must use the input functions together with an input stream variable. If you try to use any of the input functions alone—that is, without the input stream variable—the compiler might generate an error message such as “undeclared identifier.” For example, the statement `get(ch);` could result in a syntax error.

As you can see, several functions are associated with an `istream` variable, each doing a specific job. Recall that the functions `get`, `ignore`, and so on are *members* of the data type `istream`. Called the **dot notation**, the dot separates the input stream variable name from the member, or function, name. In fact, in C++, the dot is an operator called the **member access operator**.

NOTE

C++ has a special name for the data types `istream` and `ostream`. The data types `istream` and `ostream` are called classes. The variables `cin` and `cout` also have special names, called objects. Therefore, `cin` is called an `istream` object, and `cout` is called an `ostream` object. In fact, stream variables are called stream objects. You will learn these concepts in the chapter entitled Inheritance and Composition later in this book.

Input Failure

Many things can go wrong during program execution. A program that is syntactically correct might produce incorrect results. For example, suppose that a part-time employee’s paycheck is calculated by using the following formula:

```
wages = payRate * hoursWorked;
```

If you accidentally type `+` in place of `*`, the calculated wages would be incorrect, even though the statement containing a `+` is syntactically correct.

What about an attempt to read invalid data? For example, what would happen if you tried to input a letter into an `int` variable? If the input data did not match the corresponding variables, the program would run into problems. For example, trying to read a letter into an `int` or `double` variable would result in an **input failure**. Consider the following statements:

```
int a, b, c;
double x;
```

If the input is:

```
W 54
```

then the statement:

```
cin >> a >> b;
```

would result in an input failure, because you are trying to input the character 'w' into the `int` variable `a`. If the input were:

```
35 67.93 48
```

then the input statement:

```
cin >> a >> x >> b;
```

would result in storing 35 in `a`, 67.93 in `x`, and 48 in `b`.

Now consider the following read statement with the previous input (the input with three values):

```
cin >> a >> b >> c;
```

This statement stores 35 in `a` and 67 in `b`. The reading stops at `.` (the decimal point). Because the next variable `c` is of the data type `int`, the computer tries to read `.` into `c`, which is an error. The input stream then enters a state called the **fail state**.

What actually happens when the input stream enters the fail state? Once an input stream enters the fail state, all further I/O statements using that stream are ignored. Unfortunately, the program quietly continues to execute with whatever values are stored in variables and produces incorrect results. The program in Example 3-8 illustrates an input failure. This program on your system may produce different results.

EXAMPLE 3-8

//Input Failure program

```
#include <iostream>
```

```
using namespace std;
```

```
int main()
```

```
{
    int a = 10;           //Line 1
    int b = 20;           //Line 2
    int c = 30;           //Line 3
    int d = 40;           //Line 4

    cout << "Line 5: Enter four integers: "; //Line 5
    cin >> a >> b >> c >> d; //Line 6
    cout << endl;          //Line 7
    cout << "Line 8: The numbers you entered are:"
         << endl;          //Line 8
    cout << "Line 9: a = " << a << ", b = " << b
         << ", c = " << c << ", d = " << d << endl; //Line 9

    return 0;
}
```

Sample Runs: In these sample runs, the user input is shaded.

Sample Run 1

Line 5: Enter four integers: 34 K 67 28

Line 8: The numbers you entered are:

Line 9: a = 34, b = 20, c = 30, d = 40

The statements in Lines 1, 2, 3, and 4 declare and initialize the variables `a`, `b`, `c`, and `d` to 10, 20, 30, and 40, respectively. The statement in Line 5 prompts the user to enter four integers; the statement in Line 6 inputs these four integers into variables `a`, `b`, `c`, and `d`.

In this sample run, the second input value is the character `'K'`. The `cin` statement tries to input this character into the variable `b`. However, because `b` is an `int` variable, the input stream enters the fail state. Note that the values of `b`, `c`, and `d` are unchanged, as shown by the output of the statement in Line 9.

Sample Run 2

Line 5: Enter four integers: 37 653.89 23 76

Line 8: The numbers you entered are:

Line 9: a = 37, b = 653, c = 30, d = 40

In this sample run, the `cin` statement in Line 6 inputs 37 into `a` and 653 into `b` and then tries to input the decimal point into `c`. Because `c` is an `int` variable, the decimal point is regarded as a character, so the input stream enters the fail state. In this sample run, the values of `c` and `d` are unchanged, as shown by the output of the statement in Line 9.

The `clear` Function

When an input stream enters the fail state, the system ignores all further I/O using that stream. You can use the stream function `clear` to restore the input stream to a working state.

The syntax to use the function `clear` is:

```
istreamVar.clear();
```

Here, `istreamVar` is an input stream variable, such as `cin`.

After using the function `clear` to return the input stream to a working state, you still need to clear the rest of the garbage from the input stream. This can be accomplished by using the function `ignore`. Example 3-9 illustrates this situation.

EXAMPLE 3-9**//Input failure and the clear function**

```

#include <iostream>

using namespace std;

int main()
{
    int a = 23;                //Line 1
    int b = 34;                //Line 2

    cout << "Line 3: Enter a number followed"
         << " by a character: ";    //Line 3
    cin >> a >> b;                //Line 4
    cout << endl << "Line 5: a = " << a
         << ", b = " << b << endl;    //Line 5

    cin.clear();                //Restore input stream; Line 6

    cin.ignore(200, '\n');      //Clear the buffer; Line 7

    cout << "Line 8: Enter two numbers: ";    //Line 8
    cin >> a >> b;                //Line 9
    cout << endl << "Line 10: a = " << a
         << ", b = " << b << endl;    //Line 10

    return 0;
}

```

Sample Run: In this sample run, the user input is shaded.

Line 3: Enter a number followed by a character: 78 d

Line 5: a = 78, b = 34

Line 8: Enter two numbers: 65 88

Line 10: a = 65, b = 88

The statements in Lines 1 and 2 declare and initialize the variables **a** and **b** to 23 and 34, respectively. The statement in Line 3 prompts the user to enter a number followed by a character; the statement in Line 4 inputs this number into the variable **a** and then tries to input the character into the variable **b**. Because **b** is an **int** variable, an attempt to input a character into **b** causes the input stream to enter the fail state. The value of **b** is unchanged, as shown by the output of the statement in Line 5.

The statement in Line 6 restores the input stream by using the function **clear**, and the statement in Line 7 ignores the rest of the input. The statement in Line 8 again prompts the user to input two numbers; the statement in Line 9 stores these two numbers into **a** and **b**. Next, the statement in Line 10 outputs the values of **a** and **b**.

Output and Formatting Output

Other than writing efficient programs, generating the desired output is one of a programmer's highest priorities. Chapter 2 briefly introduced the process involved in generating output on the standard output device. More precisely, you learned how to use the insertion operator `<<` and the manipulator `endl` to display results on the standard output device.

However, there is a lot more to output than just displaying results. Sometimes, floating-point numbers must be output in a specific way. For example, a paycheck must be printed to two decimal places, whereas the results of a scientific experiment might require the output of floating-point numbers to six, seven, or perhaps even ten decimal places. Also, you might like to align the numbers in specific columns or fill the empty space between strings and numbers with a character other than the blank. For example, in preparing the table of contents, the space between the section heading and the page number might need to be filled with dots or dashes. In this section, you will learn about various output functions and manipulators that allow you to format your output in a desired way.

Recall that the syntax of `cout` when used together with the insertion operator `<<` is:

```
cout << expression or manipulator << expression or manipulator...;
```

Here, **expression** is evaluated, its value is printed, and **manipulator** is used to format the output. The simplest manipulator that you have used so far is `endl`, which is used to move the insertion point to the beginning of the next line.

Other output manipulators that are of interest include `setprecision`, `fixed`, `showpoint`, and `setw`. The next few sections describe these manipulators.

`setprecision` Manipulator

You use the manipulator `setprecision` to control the output of floating-point numbers. Usually, the default output of floating-point numbers is scientific notation. Some integrated development environments (IDEs) might use a maximum of six decimal places for the default output of floating-point numbers. However, when an employee's paycheck is printed, the desired output is a maximum of two decimal places. To print floating-point output to two decimal places, you use the `setprecision` manipulator to set the precision to 2.

The general syntax of the `setprecision` manipulator is:

```
setprecision(n)
```

where **n** is the number of decimal places.

You use the `setprecision` manipulator with `cout` and the insertion operator. For example, the statement:

```
cout << setprecision(2);
```

formats the output of decimal numbers to two decimal places until a similar subsequent statement changes the precision. Notice that the number of decimal places, or the precision value, is passed as an argument to `setprecision`.

To use the manipulator `setprecision`, the program must include the header file `iomanip`. Thus, the following include statement is required:

```
#include <iomanip>
```

fixed Manipulator

To further control the output of floating-point numbers, you can use other manipulators. To output floating-point numbers in a fixed decimal format, you use the manipulator `fixed`. The following statement sets the output of floating-point numbers in a fixed decimal format on the standard output device:

```
cout << fixed;
```

After the preceding statement executes, all floating-point numbers are displayed in the fixed decimal format until the manipulator `fixed` is disabled. You can disable the manipulator `fixed` by using the stream member function `unsetf`. For example, to disable the manipulator `fixed` on the standard output device, you use the following statement:

```
cout.unsetf(ios::fixed);
```

After the manipulator `fixed` is disabled, the output of the floating-point numbers returns to their default settings. The manipulator `scientific` is used to output floating-point numbers in scientific format.

NOTE

On some compilers, the statements `cin >> fixed;` and `cin >> scientific;` might not work. In this case, you can use `cin.setf(ios::fixed);` in place of `cin >> fixed;` and `cin.setf(ios::scientific);` in place of `cin >> scientific;`.

The following example shows how the manipulators `scientific` and `fixed` work without using the manipulator `setprecision`.

EXAMPLE 3-10

```
//Example: scientific and fixed
```

```
#include <iostream>
```

```
using namespace std;
```

```

int main()
{
    double hours = 35.45;
    double rate = 15.00;
    double tolerance = 0.01000;

    cout << "hours = " << hours << ", rate = " << rate
        << ", pay = " << hours * rate
        << ", tolerance = " << tolerance << endl << endl;

    cout << scientific;
    cout << "Scientific notation: " << endl;
    cout << "hours = " << hours << ", rate = " << rate
        << ", pay = " << hours * rate
        << ", tolerance = " << tolerance << endl << endl;

    cout << fixed;
    cout << "Fixed decimal notation: " << endl;
    cout << "hours = " << hours << ", rate = " << rate
        << ", pay = " << hours * rate
        << ", tolerance = " << tolerance << endl << endl;

    return 0;
}

```

Sample Run:

```
hours = 35.45, rate = 15, pay = 531.75, tolerance = 0.01
```

Scientific notation:

```
hours = 3.545000e+001, rate = 1.500000e+001, pay = 5.317500e+002, tolerance = 1
.000000e-002
```

Fixed decimal notation:

```
hours = 35.450000, rate = 15.000000, pay = 531.750000, tolerance = 0.010000
```

The sample run shows that when the value of **rate** and **tolerance** are printed without setting the **scientific** or **fixed** manipulators, the trailing zeros are not shown and, in the case of **rate**, the decimal point is also not shown. After setting the manipulators, the values are printed to six decimal places. In the next section, we describe the manipulator **showpoint** to force the system to show the decimal point and trailing zeros. We will then give an example to show how to use the manipulators **setprecision**, **fixed**, and **showpoint** to get the desired output.

showpoint Manipulator

Suppose that the decimal part of a decimal number is zero. In this case, when you instruct the computer to output the decimal number in a fixed decimal format, the output may not show the decimal point and the decimal part. To force the output to show the decimal point and

trailing zeros, you use the manipulator `showpoint`. The following statement sets the output of decimal numbers with a decimal point and trailing zeros on the standard input device:

```
cout << showpoint;
```

Of course, the following statement sets the output of a floating-point number in a fixed decimal format with the decimal point and trailing zeros on the standard output device:

```
cout << fixed << showpoint;
```

The program in Example 3-11 illustrates how to use the manipulators `setprecision`, `fixed`, and `showpoint`.

EXAMPLE 3-11

//Example: setprecision, fixed, showpoint

```
#include <iostream>                                     //Line 1
#include <iomanip>                                       //Line 2

using namespace std;                                   //Line 3

const double PI = 3.14159265;                          //Line 4

int main()                                             //Line 5
{                                                     //Line 6
    double radius = 12.67;                             //Line 7
    double height = 12.00;                             //Line 8

    cout << fixed << showpoint;                        //Line 9

    cout << setprecision(2)
        << "Line 10: setprecision(2)" << endl;         //Line 10
    cout << "Line 11: radius = " << radius << endl;     //Line 11
    cout << "Line 12: height = " << height << endl;     //Line 12
    cout << "Line 13: volume = "
        << PI * radius * radius * height << endl;     //Line 13
    cout << "Line 14: PI = " << PI << endl << endl;     //Line 14

    cout << setprecision(3)
        << "Line 15: setprecision(3)" << endl;         //Line 15
    cout << "Line 16: radius = " << radius << endl;     //Line 16
    cout << "Line 17: height = " << height << endl;     //Line 17
    cout << "Line 18: volume = "
        << PI * radius * radius * height << endl;     //Line 18
    cout << "Line 19: PI = " << PI << endl << endl;     //Line 19

    cout << setprecision(4)
        << "Line 20: setprecision(4)" << endl;         //Line 20
    cout << "Line 21: radius = " << radius << endl;     //Line 21
    cout << "Line 22: height = " << height << endl;     //Line 22
```

```

cout << "Line 23: volume = "
    << PI * radius * radius * height << endl;    //Line 23
cout << "Line 24: PI = " << PI << endl << endl;    //Line 24

cout << "Line 25: "
    << setprecision(3) << radius << ", "
    << setprecision(2) << height << ", "
    << setprecision(5) << PI << endl;            //Line 25

    return 0;                                    //Line 26
}                                                  //Line 27

```

Sample Run:

```

Line 10: setprecision(2)
Line 11: radius = 12.67
Line 12: height = 12.00
Line 13: volume = 6051.80
Line 14: PI = 3.14

```

```

Line 15: setprecision(3)
Line 16: radius = 12.670
Line 17: height = 12.000
Line 18: volume = 6051.797
Line 19: PI = 3.142

```

```

Line 20: setprecision(4)
Line 21: radius = 12.6700
Line 22: height = 12.0000
Line 23: volume = 6051.7969
Line 24: PI = 3.1416

```

```

Line 25: 12.670, 12.00, 3.14159

```

In this program, the statement in Line 2 includes the header file `iomanip`, and the statement in Line 4 declares the named constant `PI` and sets the value to eight decimal places. The statements in Lines 7 and 8 declare and initialize the variables `radius` and `height` to store the radius of the base and the height of a cylinder. The statement in Line 10 sets the output of floating-point numbers in a fixed decimal format with a decimal point and trailing zeros.

The statements in Lines 11, 12, 13, and 14 output the values of `radius`, `height`, the volume, and `PI` to two decimal places.

The statements in Lines 16, 17, 18, and 19 output the values of `radius`, `height`, the volume, and `PI` to three decimal places.

The statements in Lines 21, 22, 23, and 24 output the values of `radius`, `height`, the volume, and `PI` to four decimal places.

The statement in Line 25 outputs the value of `radius` to three decimal places, the value of `height` to two decimal places, and the value of `PI` to five decimal places.

Notice how the values of **radius** are printed in Lines 11, 16, and 21. The value of **radius** printed in Line 16 contains a trailing 0. This is because the stored value of **radius** has only two decimal places; a 0 is printed at the third decimal place. In a similar manner, the value of **height** is printed in Lines 12, 17, and 22.

Also, notice how the statements in Lines 13, 18, and 23 calculate and output the volume to two, three, and four decimal places.

Note that the value of **PI** printed in Line 24 is rounded.

The statement in Line 25 first sets the output of floating-point numbers to three decimal places and then outputs the value of **radius** to three decimal places. After printing the value of **radius**, the statement in Line 25 sets the output of floating-point numbers to two decimal places and then outputs the value of **height** to two decimal places. Next, it sets the output of floating-point numbers to five decimal places and then outputs the value of **PI** to four decimal places.

If you omit the statement in Line 9 and recompile and run the program, you will see the default output of the decimal numbers. More specifically, the value of the expression that calculates the volume might be printed in the scientific notation.

setw

The manipulator **setw** is used to output the value of an expression in a specific number of columns. The value of the expression can be either a string or a number. The expression **setw(n)** outputs the value of the next expression in **n** columns. The output is right-justified. Thus, if you specify the number of columns to be 8, for example, and the output requires only four columns, the first four columns are left blank. Furthermore, if the number of columns specified is less than the number of columns required by the output, the output automatically expands to the required number of columns; the output is not truncated. For example, if **x** is an **int** variable, the following statement outputs the value of **x** in five columns on the standard output device:

```
cout << setw(5) << x << endl;
```

To use the manipulator **setw**, the program must include the header file **iomanip**. Thus, the following **include** statement is required:

```
#include <iomanip>
```

Unlike **setprecision**, which controls the output of all floating-point numbers until it is reset, **setw** controls the output of only the next expression.

EXAMPLE 3-12

```
//Example: setw
```

```
#include <iostream>
#include <iomanip>
```

```

using namespace std;

int main()
{
    int x = 19;           //Line 1
    int a = 345;          //Line 2
    double y = 76.384;    //Line 3

    cout << fixed << showpoint; //Line 4

    cout << "12345678901234567890" << endl; //Line 5

    cout << setw(5) << x << endl; //Line 6
    cout << setw(5) << a << setw(5) << "Hi"
        << setw(5) << x << endl << endl; //Line 7

    cout << setprecision(2); //Line 8
    cout << setw(6) << a << setw(6) << y
        << setw(6) << x << endl; //Line 9
    cout << setw(6) << x << setw(6) << a
        << setw(6) << y << endl << endl; //Line 10

    cout << setw(5) << a << x << endl; //Line 11
    cout << setw(2) << a << setw(4) << x << endl; //Line 12

    return 0;
}

```

Sample Run:

```

12345678901234567890
  19
345   Hi   19

  345 76.38   19
  19   345 76.38

34519
345 19

```

The statements in Lines 1, 2, and 3 declare the variables **x**, **a**, and **y** and initialize these variables to 19, 345, and 76.384, respectively. The statement in Line 4 sets the output of floating-point numbers in a fixed decimal format with a decimal point and trailing zeros. The output of the statement in Line 5 shows the column positions when the specific values are printed; it is the first line of output.

The statement in Line 6 outputs the value of **x** in five columns. Because **x** has only two digits, only two columns are needed to output its value. Therefore, the first three columns are left blank in the second line of output. The statement in Line 7 outputs the value of **a** in the first five columns, the string "Hi" in the next five columns, and then the value of **x** in the following five columns. Because the string "Hi" contains only two characters and five columns are set to output these two characters, the first three columns are left blank. See

the third line of output. The fourth line of output is blank because the manipulator `endl` appears twice in the statement in Line 7.

The statement in Line 8 sets the output of floating-point numbers to two decimal places. The statement in Line 9 outputs the values of `a` in the first six columns, `y` in the next six columns, and `x` in the following six columns, creating the fifth line of output. The output of the statement in Line 10 (which is the sixth line of output) is similar to the output of the statement in Line 9. Notice how the numbers are nicely aligned in the outputs of the statements in Lines 9 and 10. The seventh line of output is blank because the manipulator `endl` appears twice in the statement in Line 10.

The statement in Line 11 outputs first the value of `a` in five columns and then the value of `x`. Note that the manipulator `setw` in the statement in Line 11 controls only the output of `a`. Thus, after the value of `a` is printed, the value of `x` is printed at the current cursor position (see the eighth line of output).

In the `cout` statement in Line 12, only two columns are assigned to output the value of `a`. However, the value of `a` has three digits, so the output is expanded to three columns. The value of `x` is then printed in four columns. Because the value of `x` contains only two digits, only two columns are required to output the value of `x`. Therefore, because four columns are allocated to output the value of `x`, the first two columns are left blank (see the ninth line of output).

Additional Output Formatting Tools

In the previous section, you learned how to use the manipulators `setprecision`, `fixed`, and `showpoint` to control the output of floating-point numbers and how to use the manipulator `setw` to display the output in specific columns. Even though these manipulators are adequate to produce an elegant report, in some situations, you may want to do more. In this section, you will learn additional formatting tools that give you more control over your output.

`setfill` Manipulator

Recall that in the manipulator `setw`, if the number of columns specified exceeds the number of columns required by the expression, the output of the expression is right-justified and the unused columns to the left are filled with spaces. The output stream variables can use the manipulator `setfill` to fill the unused columns with a character other than a space.

The syntax to use the manipulator `setfill` is:

```
ostreamVar << setfill(ch);
```

where `ostreamVar` is an output stream variable and `ch` is a character. For example, the statement:

```
cout << setfill('#');
```

sets the fill character to '#' on the standard output device.

To use the manipulator `setfill`, the program must include the header file `iomanip`.

The program in Example 3-13 illustrates the effect of using `setfill` in a program.

EXAMPLE 3-13

```
//Example: setfill

#include <iostream>
#include <iomanip>

using namespace std;

int main()
{
    int x = 15;           //Line 1
    int y = 7634;         //Line 2

    cout << "12345678901234567890" << endl; //Line 3
    cout << setw(5) << x << setw(7) << y
        << setw(8) << "Warm" << endl;      //Line 4

    cout << setfill('*'); //Line 5
    cout << setw(5) << x << setw(7) << y
        << setw(8) << "Warm" << endl;      //Line 6

    cout << setw(5) << x << setw(7) << setfill('#')
        << y << setw(8) << "Warm" << endl;  //Line 7

    cout << setw(5) << setfill('@') << x
        << setw(7) << setfill('#') << y
        << setw(8) << setfill('^') << "Warm"
        << endl;                          //Line 8
    cout << setfill(' '); //Line 9
    cout << setw(5) << x << setw(7) << y
        << setw(8) << "Warm" << endl;      //Line 10

    return 0;
}
```

Sample Run:

```
12345678901234567890
  15   7634   Warm
***15***7634***Warm
***15###7634####Warm
@@@15###7634^^^^Warm
  15   7634   Warm
```

The statements in Lines 1 and 2 declare and initialize the variables `x` and `y` to 15 and 7634, respectively. The output of the statement in Line 3—the first line of output—shows the

column position when the subsequent statements output the values of the variables. The statement in Line 4 outputs the value of **x** in five columns, the value of **y** in seven columns, and the string **"Warm"** in eight columns. In this statement, the filling character is the blank character, as shown in the second line of output.

The statement in Line 5 sets the filling character to *****. The statement in Line 6 outputs the value of **x** in five columns, the value of **y** in seven columns, and the string **"Warm"** in eight columns. Because **x** is a two-digit number and five columns are assigned to output its value, the first three columns are unused by **x** and are, therefore, filled by the filling character *****. To print the value of **y**, seven columns are assigned; **y** is a four-digit number, however, so the filling character fills the first three columns. Similarly, to print the value of the string **"Warm"**, eight columns are assigned; the string **"Warm"** has only four characters, so the filling character fills the first four columns. See the third line of output.

The output of the statement in Line 7—the fourth line of output—is similar to the output of the statement in Line 6, except that the filling character for **y** and the string **"Warm"** is **#**. In the output of the statement in Line 8 (the fifth line of output), the filling character for **x** is **@**, the filling character for **y** is **#**, and the filling character for the string **"Warm"** is **^**. The manipulator **setfill** sets these filling characters.

The statement in Line 9 sets the filling character to blank. The statement in Line 10 outputs the values of **x**, **y**, and the string **"Warm"** using the filling character blank, as shown in the sixth line of output.

left and right Manipulators

Recall that if the number of columns specified in the **setw** manipulator exceeds the number of columns required by the next expression, the default output is right-justified. Sometimes, you might want the output to be left-justified. To left-justify the output, you use the manipulator **left**.

The syntax to set the manipulator **left** is:

```
ostreamVar << left;
```

where **ostreamVar** is an output stream variable. For example, the following statement sets the output to be left-justified on the standard output device:

```
cout << left;
```

You can disable the manipulator **left** by using the stream function **unsetf**. The syntax to disable the manipulator **left** is:

```
ostreamVar.unsetf(ios::left);
```

where `ostreamVar` is an output stream variable. Disabling the manipulator `left` returns the output to the settings of the default output format. For example, the following statement disables the manipulator `left` on the standard output device:

```
cout.unsetf(ios::left);
```

The syntax to set the manipulator `right` is:

```
ostreamVar << right;
```

where `ostreamVar` is an output stream variable. For example, the following statement sets the output to be right-justified on the standard output device:

```
cout << right;
```

NOTE

On some compilers, the statements `cin >> left;` and `cin >> right;` might not work. In this case, you can use `cin.setf(ios::left);` in place of `cin >> left;` and `cin.setf(ios::right);` in place of `cin >> right;`.

The program in Example 3-14 illustrates the effect of the manipulators `left` and `right`.

EXAMPLE 3-14

//Example: left justification

```
#include <iostream>
#include <iomanip>

using namespace std;

int main()
{
    int x = 15; //Line 1
    int y = 7634; //Line 2

    cout << left; //Line 3

    cout << "12345678901234567890" << endl; //Line 4
    cout << setw(5) << x << setw(7) << y
        << setw(8) << "Warm" << endl; //Line 5

    cout << setfill('*'); //Line 6

    cout << setw(5) << x << setw(7) << y
        << setw(8) << "Warm" << endl; //Line 7

    cout << setw(5) << x << setw(7) << setfill('#')
        << y << setw(8) << "Warm" << endl; //Line 8

    cout << setw(5) << setfill('@') << x
        << setw(7) << setfill('#') << y
```

```

        << setw(8) << setfill('^') << "Warm"
        << endl;                                     //Line 9

    cout << right;                                     //Line 10
    cout << setfill(' ');                             //Line 11

    cout << setw(5) << x << setw(7) << y
        << setw(8) << "Warm" << endl;               //Line 12

    return 0;
}

```

Sample Run:

```

12345678901234567890
15   7634   Warm
15***7634***Warm***
15***7634###Warm###
15@@@7634###Warm^^^^
    15   7634   Warm

```

The output of this program is the same as the output of Example 3-11. The only difference here is that for the statements in Lines 4 through 9, the output is left-justified. You are encouraged to do a walk-through of this program.

NOTE

This chapter discusses several stream functions and stream manipulators. To use stream functions such as `get`, `ignore`, `fill`, and `clear` in a program, the program must include the header file `iostream`.

There are two types of manipulators: those with parameters and those without parameters. Manipulators with parameters are called **parameterized stream manipulators**. For example, manipulators such as `setprecision`, `setw`, and `setfill` are parameterized. On the other hand, manipulators such as `endl`, `fixed`, `scientific`, `showpoint`, and `left` do not have parameters.

To use a parameterized stream manipulator in a program, you must include the header file `iomanip`. Manipulators without parameters are part of the `iostream` header file and, therefore, do not require inclusion of the header file `iomanip`.

Input/Output and the `string` Type

You can use an input stream variable, such as `cin`, and the extraction operator `>>` to read a string into a variable of the data type `string`. For example, if the input is the string `"Shelly"`, the following code stores this input into the `string` variable `name`:

```

string name;      //variable declaration
cin >> name;      //input statement

```

Recall that the extraction operator skips any leading whitespace characters and that reading stops at a whitespace character. As a consequence, you cannot use the extraction operator to read strings that contain blanks. For example, suppose that the variable `name` is defined as noted above. If the input is:

Alice Wonderland

then after the statement:

```
cin >> name;
```

executes, the value of the variable `name` is "Alice".

To read a string containing blanks, you can use the function `getline`.

The syntax to use the function `getline` is:

```
getline(istreamVar, strVar);
```

where `istreamVar` is an input stream variable and `strVar` is a `string` variable. The reading is delimited by the newline character `'\n'`.

The function `getline` reads until it reaches the end of the current line. The newline character is also read but not stored in the `string` variable.

Consider the following statement:

```
string myString;
```

If the input is 29 characters:

```
bbbbHello there. How are you?
```

where `b` represents a blank, after the statement:

```
getline(cin, myString);
```

the value of `myString` is:

```
myString = "    Hello there. How are you?"
```

All 29 characters, including the first four blanks, are stored into `myString`.

Similarly, you can use an output stream variable, such as `cout`, and the insertion operator `<<` to output the contents of a variable of the data type `string`.

Debugging: Understanding Logic Errors and Debugging with `cout` Statements

In the debugging section of Chapter 2, we illustrated how to understand and correct syntax errors. As we have seen, syntax errors are reported by the compiler, and the compiler not only reports syntax errors, but also gives some explanation about the errors. On the other hand, logic errors are typically not caught by the compiler except for the trivial ones such as using a variable without properly initializing it. In this section, we illustrate how to spot and

correct logic errors using `cout` statements. Suppose that we want to write a program that takes as input the temperature in Fahrenheit and outputs the equivalent temperature in Celsius. The formula to convert the temperature is: $Celsius = 5 / 9 * (Fahrenheit - 32)$. So consider the following program:

```
#include <iostream>                                //Line 1

using namespace std;                                //Line 2

int main()                                          //Line 3
{                                                  //Line 4
    int fahrenheit;                                //Line 5
    int celsius;                                    //Line 6

    cout << "Enter temperature in Fahrenheit: "; //Line 7
    cin >> fahrenheit;                             //Line 8
    cout << endl;                                   //Line 9

    celsius = 5 / 9 * (fahrenheit - 32);           //Line 10

    cout << fahrenheit << " degree F = "           //Line 11
         << celsius << " degree C. " << endl;
    return 0;                                       //Line 12
}                                                  //Line 13
```

Sample Run 1: In this sample run, the user input is shaded.

Enter temperature in Fahrenheit: 32

32 degree F = 0 degree C.

Sample Run 2: In this sample run, the user input is shaded.

Enter temperature in Fahrenheit: 110

110 degree F = 0 degree C.

The result shown in the first calculation looks correct. However, the result in the second calculation is clearly not correct even though the same formula is used, because 110 degree F = 43 degree C. It means the value of `celsius` calculated in Line 10 is incorrect. Now, the value of `celsius` is given by the expression $5 / 9 * (fahrenheit - 32)$. So we should look at this expression closely. To see the effect of this expression, we can separately print the values of the two expression $5 / 9$ and $fahrenheit - 32$. This can be accomplished by temporarily inserting an output statement as shown in the following program:

```
#include <iostream>                                //Line 1

using namespace std;                                //Line 2

int main()                                          //Line 3
{                                                  //Line 4
    int fahrenheit;                                //Line 5
    int celsius;                                    //Line 6
```

```

cout << "Enter temperature in Fahrenheit: "; //Line 7
cin >> fahrenheit;                          //Line 8
cout << endl;                               //Line 9

cout << "5 / 9 = " << 5 / 9
    << "; fahrenheit - 32 = "
    << fahrenheit - 32 << endl;             //Line 9a

celsius = 5 / 9 * (fahrenheit - 32);         //Line 10

cout << fahrenheit << " degree F = "
    << celsius << " degree C. " << endl;    //Line 11

return 0;                                   //Line 12
}                                           //Line 13

```

Sample Run: In this sample run, the user input is shaded.

Enter temperature in Fahrenheit: **110**

```

5 / 9 = 0; fahrenheit - 32 = 78
110 degree F = 0 degree C.

```

Let us look at the sample run. We see that the value of $5 / 9 = 0$ and the value of $\text{fahrenheit} - 32 = 78$. Because `fahrenheit` = 110, the value of the expression $\text{fahrenheit} - 32$ is correct. Now let us look at the expression $5 / 9$. The value of this expression is 0. Because both of the operands, 5 and 9, of the operator `/` are integers, using integer division, the value of the expression is 0. That is, the value of the expression $5 / 9 = 0$ is also calculated correctly. So by the precedence of the operators, the value of the expression $5 / 9 * (\text{fahrenheit} - 32)$ will always be 0 regardless of the value of `fahrenheit`. So the problem is in the integer division. We can replace the expression $5 / 9$ with $5.0 / 9$. In this case, the value of the expression $5.0 / 9 * (\text{fahrenheit} - 32)$ will be a decimal number. Because `fahrenheit` and `celsius` are `int` variables, we can use the cast operators to convert this value to an integer, that is, we use the following expression:

```
celsius = static_cast<int>(5.0 / 9 * (fahrenheit - 32) + 0.5);
```

(Note that in the preceding expression, we added 0.5 to round the number to the nearest integer.)

The revised program is:

```

#include <iostream>                               //Line 1

using namespace std;                             //Line 2

int main()                                       //Line 3
{                                               //Line 4
    int fahrenheit;                             //Line 5
    int celsius;                               //Line 6

```

```

    cout << "Enter temperature in Fahrenheit: ";           //Line 7
    cin >> fahrenheit;                                     //Line 8
    cout << endl;                                           //Line 9

    celsius = static_cast<int>
               (5.0 / 9 * (fahrenheit - 32) + 0.5);         //Line 10

    cout << fahrenheit << " degree F = "
         << celsius << " degree C. " << endl;             //Line 11

    return 0;                                              //Line 12
}                                                         //Line 13

```

Sample Run: In this sample run, the user input is shaded.

Enter temperature in Fahrenheit: 110

110 degree F = 43 degree C.

As we can see, using temporary `cout` statements, we were able to find the problem. After correcting the problem, the temporary `cout` statements are removed.

The temperature conversion program contained logic errors, not syntax errors. Using `cout` statements to print the values of expressions and/or variables to see the results of a calculation is an effective way to find and correct logic errors.

File Input/Output

The previous sections discussed in some detail how to get input from the keyboard (standard input device) and send output to the screen (standard output device). However, getting input from the keyboard and sending output to the screen have several limitations. Inputting data in a program from the keyboard is comfortable as long as the amount of input is very small. Sending output to the screen works well if the amount of data is small (no larger than the size of the screen) and you do not want to distribute the output in a printed format to others.

If the amount of input data is large, however, it is inefficient to type it at the keyboard each time you run a program. In addition to the inconvenience of typing large amounts of data, typing can generate errors, and unintentional typos cause erroneous results. You must have some way to get data into the program from other sources. By using alternative sources of data, you can prepare the data before running a program, and the program can access the data each time it runs.

Suppose you want to present the output of a program in a meeting. Distributing printed copies of the program output is a better approach than showing the output on a screen. For example, you might give a printed report to each member of a committee before an important meeting. Furthermore, output must sometimes be saved so that the output produced by one program can be used as an input to other programs.

This section discusses how to obtain data from other input devices, such as a disk (that is, secondary storage), and how to save the output to a disk. C++ allows a program to get

data directly from and save output directly to secondary storage. A program can use the file I/O and read data from or write data to a file. Formally, a file is defined as follows:

File: An area in secondary storage used to hold information.

The standard I/O header file, `iostream`, contains data types and variables that are used only for input from the standard input device and output to the standard output device. In addition, C++ provides a header file called `fstream`, which is used for file I/O. Among other things, the `fstream` header file contains the definitions of two data types: `ifstream`, which means input file stream and is similar to `istream`, and `ofstream`, which means output file stream and is similar to `ostream`.

The variables `cin` and `cout` are already defined and associated with the standard input/output devices. In addition, `>>`, `get`, `ignore`, `putback`, `peek`, and so on can be used with `cin`, whereas `<<`, `setfill`, and so on can be used with `cout`. These same operators and functions are also available for file I/O, but the header file `fstream` does not declare variables to use them. You must declare variables called **file stream variables**, which include `ifstream` variables for input and `ofstream` variables for output. You then use these variables together with `>>`, `<<`, or other functions for I/O. Remember that C++ does not automatically initialize user-defined variables. Once you declare the `fstream` variables, you must associate these file variables with the input/output sources.

File I/O is a five-step process:

1. Include the header file `fstream` in the program.
2. Declare file stream variables.
3. Associate the file stream variables with the input/output sources.
4. Use the file stream variables with `>>`, `<<`, or other input/output functions.
5. Close the files.

We will now describe these five steps in detail. A skeleton program then shows how the steps might appear in a program.

Step 1 requires that the header file `fstream` be included in the program. The following statement accomplishes this task:

```
#include <fstream>
```

Step 2 requires you to declare file stream variables. Consider the following statements:

```
ifstream inData;
ofstream outData;
```

The first statement declares `inData` to be an input file stream variable. The second statement declares `outData` to be an output file stream variable.

Step 3 requires you to associate file stream variables with the input/output sources. This step is called **opening the files**. The stream member function `open` is used to open files. The syntax for opening a file is:

```
fileStreamVariable.open(sourceName);
```

Here, `fileStreamVariable` is a file stream variable, and `sourceName` is the name of the input/output file.

Suppose you include the declaration from Step 2 in a program. Further suppose that the input data is stored in a file called `prog.dat`. The following statements associate `inData` with `prog.dat` and `outData` with `prog.out`. That is, the file `prog.dat` is opened for inputting data, and the file `prog.out` is opened for outputting data.

```
inData.open("prog.dat"); //open the input file; Line 1
outData.open("prog.out"); //open the output file; Line 2
```

NOTE

IDEs such as Visual Studio .Net manage programs in the form of projects. That is, first you create a project, and then you add source files to the project. The statement in Line 1 assumes that the file `prog.dat` is in the same directory (subdirectory) as your project. However, if this is in a different directory (subdirectory), then you must specify the path where the file is located, along with the name of the file. For example, suppose that the file `prog.dat` is on a flash memory in drive H. Then the statement in Line 1 should be modified as follows:

```
inData.open("h:\\prog.dat");
```

Note that there are two `\` after `h:`. Recall from Chapter 2 that in C++, `\` is the escape character. Therefore, to produce a `\` within a string, you need `\\`. (To be absolutely sure about specifying the source where the input file is stored, such as the drive `h:\\`, check your system's documentation.)

Similar conventions for the statement in Line 2.

NOTE

Suppose that a program reads data from a file. Because different computers have drives labeled differently, for simplicity, throughout the book, we assume that the file containing the data and the program reading data from the file are in the same directory (subdirectory).

NOTE

We typically use `.dat`, `.out`, or `.txt` as an extension for the input and output files and use Notepad, Wordpad, or TextPad to create and open these files. You can also use your IDE's editor, if any, to create `.txt` (text) files. (To be absolutely sure about it, check you IDE's documentation.)

Step 4 typically works as follows. You use the file stream variables with `>>`, `<<`, or other input/output functions. The syntax for using `>>` or `<<` with file stream variables is exactly the same as the syntax for using `cin` and `cout`. Instead of using `cin` and `cout`, however, you use the file stream variable names that were declared. For example, the statement:

```
inData >> payRate;
```

reads the data from the file `prog.dat` and stores it in the variable `payRate`. The statement:

```
outData << "The paycheck is: $" << pay << endl;
```

stores the output—**The paycheck is: \$565.78**—in the file `prog.out`. This statement assumes that the pay was calculated as `565.78`.

Once the I/O is complete, Step 5 requires closing the files. Closing a file means that the file stream variables are disassociated from the storage area and are freed. Once these variables are freed, they can be reused for other file I/O. Moreover, closing an output file ensures that the entire output is sent to the file; that is, the buffer is emptied. You close files by using the stream function `close`. For example, assuming the program includes the declarations listed in Steps 2 and 3, the statements for closing the files are:

```
inData.close();
outData.close();
```

NOTE

On some systems, it is not necessary to close the files. When the program terminates, the files are closed automatically. Nevertheless, it is a good practice to close the files yourself. Also, if you want to use the same file stream variable to open another file, you must close the first file opened with that file stream variable.

In skeleton form, a program that uses file I/O usually takes the following form:

```
#include <fstream>

//Add additional header files you use

using namespace std;

int main()
{
    //Declare file stream variables such as the following
    ifstream inData;
    ofstream outData;
    .
    .
    .

    //Open the files
    inData.open("prog.dat"); //open the input file
    outData.open("prog.out"); //open the output file

    //Code for data manipulation

    //Close files
    inData.close();
    outData.close();

    return 0;
}
```

Recall that Step 3 requires the file to be opened for file I/O. Opening a file associates a file stream variable declared in the program with a physical file at the source, such as a disk. In the case of an input file, the file must exist before the `open` statement executes. If the file does not exist, the `open` statement fails and the input stream enters the fail state. An output file does not have to exist before it is opened; if the output file does not exist, the computer prepares an empty file for output. If the designated output file already exists, by default, the old contents are erased when the file is opened.

NOTE

To add the output at the end of an existing file, you can use the option `ios::app` as follows. Suppose that `outData` is declared as before and you want to add the output at the end of the existing file, say, `firstProg.out`. The statement to open this file is:

```
outData.open("firstProg.out", ios::app);
```

If the file `firstProg.out` does not exist, then the system creates an empty file.

NOTE

Appendix E discusses binary and random access files.

PROGRAMMING EXAMPLE:

Movie Tickets Sale and Donation to Charity

A movie in a local theater is in great demand. To help a local charity, the theater owner has decided to donate to the charity a portion of the gross amount generated from the movie. This example designs and implements a program that prompts the user to input the movie name, adult ticket price, child ticket price, number of adult tickets sold, number of child tickets sold, and percentage of the gross amount to be donated to the charity. The output of the program is as follows.

```
--*--*--*--*--*--*--*--*--*--*--*--*--*--*--*--*--*--*--*--*--*--*--*--*
Movie Name: ..... Journey to Mars
Number of Tickets Sold: ..... 2650
Gross Amount: ..... $ 9150.00
Percentage of Gross Amount Donated: 10.00%
Amount Donated: ..... $ 915.00
Net Sale: ..... $ 8235.00
```

Note that the strings, such as "Movie Name:", in the first column are left-justified, the numbers in the right column are right-justified, and the decimal numbers are output with two decimal places.

**PROBLEM
ANALYSIS
AND
ALGORITHM
DESIGN**

Input The input to the program consists of the movie name, adult ticket price, child ticket price, number of adult tickets sold, number of child tickets sold, and percentage of the gross amount to be donated to the charity.

Output The output is as shown above.

To calculate the amount donated to the local charity and the net sale, you first need to determine the gross amount. To calculate the gross amount, you multiply the number of adult tickets sold by the price of an adult ticket, multiply the number of child tickets sold by the price of a child ticket, and then add these two numbers. That is:

```
grossAmount = adultTicketPrice * noOfAdultTicketsSold
              + childTicketPrice * noOfChildTicketsSold;
```

Next, you determine the percentage of the amount donated to the charity and then calculate the net sale amount by subtracting the amount donated from the gross amount. The formulas to calculate the amount donated and the net sale amount are given below. This analysis leads to the following algorithm:

1. Get the movie name.
2. Get the price of an adult ticket.
3. Get the price of a child ticket.
4. Get the number of adult tickets sold.
5. Get the number of child tickets sold.
6. Get the percentage of the gross amount donated to the charity.
7. Calculate the gross amount using the following formula:

```
grossAmount = adultTicketPrice * noOfAdultTicketsSold
              + childTicketPrice * noOfChildTicketsSold;
```
8. Calculate the amount donated to the charity using the following formula:

```
amountDonated = grossAmount * percentDonation / 100;
```
9. Calculate the net sale amount using the following formula:

```
netSaleAmount = grossAmount - amountDonated;
```

Variables From the preceding discussion, it follows that you need variables to store the movie name, adult ticket price, child ticket price, number of adult tickets sold, number of child tickets sold, percentage of the gross amount donated to the charity, gross amount, amount donated, and net sale amount. Therefore, the following variables are needed:

```
string movieName;
double adultTicketPrice;
double childTicketPrice;
int noOfAdultTicketsSold;
int noOfChildTicketsSold;
```


1. Declare the variables.
2. Set the output of the floating-point numbers to two decimal places in a fixed decimal format with a decimal point and trailing zeros. Include the header file `iomanip`.
3. Prompt the user to enter a movie name.
4. Input (read) the movie name. Because the name of a movie might contain more than one word (and, therefore, might contain blanks), the program uses the function `getline` to input the movie name.
5. Prompt the user to enter the price of an adult ticket.
6. Input (read) the price of an adult ticket.
7. Prompt the user to enter the price of a child ticket.
8. Input (read) the price of a child ticket.
9. Prompt the user to enter the number of adult tickets sold.
10. Input (read) the number of adult tickets sold.
11. Prompt the user to enter the number of child tickets sold.
12. Input (read) the number of child tickets sold.
13. Prompt the user to enter the percentage of the gross amount donated.
14. Input (read) the percentage of the gross amount donated.
15. Calculate the gross amount.
16. Calculate the amount donated.
17. Calculate the net sale amount.
18. Output the results.

COMPLETE PROGRAM LISTING

```
//*****
// Author: D.S. Malik
//
// Program: Movie Tickets Sale
// This program determines the money to be donated to a
// charity. It prompts the user to input the movie name, adult
// ticket price, child ticket price, number of adult tickets
// sold, number of child tickets sold, and percentage of the
// gross amount to be donated to the charity.
//*****

#include <iostream>
#include <iomanip>
#include <string>

using namespace std;
```

```

int main()
{
    //Step 1
    string movieName;
    double adultTicketPrice;
    double childTicketPrice;
    int noOfAdultTicketsSold;
    int noOfChildTicketsSold;
    double percentDonation;
    double grossAmount;
    double amountDonated;
    double netSaleAmount;

    cout << fixed << showpoint << setprecision(2); //Step 2

    cout << "Enter the movie name: "; //Step 3
    getline(cin, movieName); //Step 4
    cout << endl;

    cout << "Enter the price of an adult ticket: "; //Step 5
    cin >> adultTicketPrice; //Step 6
    cout << endl;

    cout << "Enter the price of a child ticket: "; //Step 7
    cin >> childTicketPrice; //Step 8
    cout << endl;
    cout << "Enter the number of adult tickets "
        << "sold: "; //Step 9
    cin >> noOfAdultTicketsSold; //Step 10
    cout << endl;

    cout << "Enter the number of child tickets "
        << "sold: "; //Step 11
    cin >> noOfChildTicketsSold; //Step 12
    cout << endl;

    cout << "Enter the percentage of donation: "; //Step 13
    cin >> percentDonation; //Step 14
    cout << endl << endl;

    //Step 15
    grossAmount = adultTicketPrice * noOfAdultTicketsSold +
        childTicketPrice * noOfChildTicketsSold;

    //Step 16
    amountDonated = grossAmount * percentDonation / 100;

    netSaleAmount = grossAmount - amountDonated; //Step 17

    //Step 18: Output results
    cout << "_*_*_*_*_*_*_*_*_*_*_*_*_*"
        << "_*_*_*_*_*_*_*_*_*_*_*_*_*" << endl;
}

```

```

    cout << setfill('.') << left << setw(35) << "Movie Name: "
        << right << " " << movieName << endl;
    cout << left << setw(35) << "Number of Tickets Sold: "
        << setfill(' ') << right << setw(10)
        << noOfAdultTicketsSold + noOfChildTicketsSold
        << endl;
    cout << setfill('.') << left << setw(35)
        << "Gross Amount: "
        << setfill(' ') << right << " $"
        << setw(8) << grossAmount << endl;
    cout << setfill('.') << left << setw(35)
        << "Percentage of Gross Amount Donated: "
        << setfill(' ') << right
        << setw(9) << percentDonation << '%' << endl;
    cout << setfill('.') << left << setw(35)
        << "Amount Donated: "
        << setfill(' ') << right << " $"
        << setw(8) << amountDonated << endl;
    cout << setfill('.') << left << setw(35) << "Net Sale: "
        << setfill(' ') << right << " $"
        << setw(8) << netSaleAmount << endl;

    return 0;
}

```

Sample Run: In this sample run, the user input is shaded.

Enter movie name: **Journey to Mars**

Enter the price of an adult ticket: **4.50**

Enter the price of a child ticket: **3.00**

Enter number of adult tickets sold: **800**

Enter number of child tickets sold: **1850**

Enter the percentage of donation: **10**

```

-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*
Movie Name: ..... Journey to Mars
Number of Tickets Sold: ..... 2650
Gross Amount: ..... $ 9150.00
Percentage of Gross Amount Donated: 10.00%
Amount Donated: ..... $ 915.00
Net Sale: ..... $ 8235.00

```

Note that the first six lines of output get the necessary data to generate the last six lines of the output as required.

PROGRAMMING EXAMPLE: Student Grade

Write a program that reads a student name followed by five test scores. The program should output the student name, the five test scores, and the average test score. Output the average test score with two decimal places.

The data to be read is stored in a file called `test.txt`. The output should be stored in a file called `testavg.out`.

Input A file containing the student name and the five test scores. A sample input is:

Andrew Miller 87.50 89 65.75 37 98.50

Output The student name, the five test scores, and the average of the five test scores, saved to a file.

PROBLEM ANALYSIS AND ALGORITHM DESIGN

To find the average of the five test scores, you add the five test scores and divide the sum by 5. The input data is in the following form: the student name followed by the five test scores. Therefore, you must read the student name first and then read the five test scores. This problem analysis translates into the following algorithm:

1. Read the student name and the five test scores.
2. Output the student name and the five test scores.
3. Calculate the average.
4. Output the average.

You output the average test score in the fixed decimal format with two decimal places.

Variables The program needs to read a student's first and last name and five test scores. Therefore, you need two variables to store the student name and five variables to store the five test scores.

To find the average, you must add the five test scores and then divide the sum by 5. Thus, you need a variable to store the average test score. Furthermore, because the input data is in a file, you need an `ifstream` variable to open the input file. Because the program output will be stored in a file, you need an `ofstream` variable to open the output file. The program, therefore, needs at least the following variables:

```
ifstream inFile;    //input file stream variable
ofstream outFile;   //output file stream variable

double test1, test2, test3, test4, test5; //variables to
                                         //read the five test scores
double average;     //variable to store the average test score
string firstName;   //variable to store the first name
string lastName;    //variable to store the last name
```

MAIN ALGORITHM

In the preceding sections, we analyzed the problem and determined the formulas to perform the calculations. We also determined the necessary variables and named

constants. We can now expand the previous algorithm to solve the problem given at the beginning of this programming example:

1. Declare the variables.
2. Open the input file.
3. Open the output file.
4. To output the floating-point numbers in a fixed decimal format with a decimal point and trailing zeros, set the manipulators **fixed** and **showpoint**. Also, to output the floating-point numbers with two decimal places, set the precision to two decimal places.
5. Read the student name.
6. Output the student name.
7. Read the five test scores.
8. Output the five test scores.
9. Find the average test score.
10. Output the average test score.
11. Close the input and output files.

Because this program reads data from a file and outputs data to a file, it must include the header file **fstream**. Because the program outputs the average test score to two decimal places, you need to set the precision to two decimal places. Therefore, the program uses the manipulator **setprecision**, which requires you to include the header file **iomanip**. Because **firstName** and **lastName** are **string** variables, we must include the header file **string**. The program also includes the header file **iostream** to print a message on the screen so that you will not stare at a blank screen while the program executes.

COMPLETE PROGRAM LISTING

```
//*****
// Author: D.S. Malik
//
// Program to calculate the average test score.
// Given a student's name and five test scores, this program
// calculates the average test score. The student's name, the
// five test scores, and the average test score are stored in
// the file testavg.out. The data is input from the file
// test.txt.
//*****

#include <iostream>
#include <fstream>
#include <iomanip>
#include <string>

using namespace std;
```

```

int main()
{
    //Declare variables; Step 1
    ifstream inFile;
    ofstream outFile;

    double test1, test2, test3, test4, test5;
    double average;

    string firstName;
    string lastName;

    inFile.open("test.txt"); //Step 2
    outFile.open("testavg.out"); //Step 3

    outFile << fixed << showpoint; //Step 4
    outFile << setprecision(2); //Step 4

    cout << "Processing data" << endl;

    inFile >> firstName >> lastName; //Step 5
    outFile << "Student name: " << firstName
        << " " << lastName << endl; //Step 6

    inFile >> test1 >> test2 >> test3
        >> test4 >> test5; //Step 7
    outFile << "Test scores: " << setw(6) << test1
        << setw(6) << test2 << setw(6) << test3
        << setw(6) << test4 << setw(6) << test5
        << endl; //Step 8

    average = (test1 + test2 + test3 + test4
        + test5) / 5.0; //Step 9

    outFile << "Average test score: " << setw(6)
        << average << endl; //Step 10

    inFile.close(); //Step 11
    outFile.close(); //Step 11

    return 0;
}

```

Sample Run:**Input File** (contents of the file test.txt):

Andrew Miller 87.50 89 65.75 37 98.50

Output File (contents of the file testavg.out):

Student name: Andrew Miller
 Test scores: 87.50 89.00 65.75 37.00 98.50
 Average test score: 75.55

NOTE

The preceding program uses five variables—`test1`, `test2`, `test3`, `test4`, and `test5`—to read the five test scores and then find the average test score. The Web site accompanying this book contains a modified version of this program that uses only one variable, `testScore`, to read the test scores and another variable, `sum`, to find the sum of the test scores. The program is named `Ch3_AverageTestScoreVersion2.cpp`.

QUICK REVIEW

1. A stream in C++ is an infinite sequence of characters from a source to a destination.
2. An input stream is a stream from a source to a computer.
3. An output stream is a stream from a computer to a destination.
4. `cin`, which stands for common input, is an input stream object, typically initialized to the standard input device, which is the keyboard.
5. `cout`, which stands for common output, is an output stream object, typically initialized to the standard output device, which is the screen.
6. When the binary operator `>>` is used with an input stream object, such as `cin`, it is called the stream extraction operator. The left-side operand of `>>` must be an input stream variable, such as `cin`; the right-side operand must be a variable.
7. When the binary operator `<<` is used with an output stream object, such as `cout`, it is called the stream insertion operator. The left-side operand of `<<` must be an output stream variable, such as `cout`; the right-side operand of `<<` must be an expression or a manipulator.
8. When inputting data into a variable, the operator `>>` skips all leading whitespace characters.
9. To use `cin` and `cout`, the program must include the header file `iostream`.
10. The function `get` is used to read data on a character-by-character basis and does not skip any whitespace characters.
11. The function `ignore` is used to skip data in a line.
12. The function `putback` puts the last character retrieved by the function `get` back into the input stream.
13. The function `peek` returns the next character from the input stream but does not remove the character from the input stream.
14. Attempting to read invalid data into a variable causes the input stream to enter the fail state.
15. Once an input failure has occurred, you use the function `clear` to restore the input stream to a working state.

16. The manipulator `setprecision` formats the output of floating-point numbers to a specified number of decimal places.
17. The manipulator `fixed` outputs floating-point numbers in the fixed decimal format.
18. The manipulator `showpoint` outputs floating-point numbers with a decimal point and trailing zeros.
19. The manipulator `setw` formats the output of an expression in a specific number of columns; the default output is right-justified.
20. If the number of columns specified in the argument of `setw` is less than the number of columns needed to print the value of the expression, the output is not truncated and the output of the expression expands to the required number of columns.
21. The manipulator `setfill` is used to fill the unused columns on an output device with a character other than a space.
22. If the number of columns specified in the `setw` manipulator exceeds the number of columns required by the next expression, the output is right-justified. To left-justify the output, you use the manipulator `left`.
23. To use the stream functions `get`, `ignore`, `putback`, `peek`, `clear`, and `unsetf` for standard I/O, the program must include the header file `iostream`.
24. To use the manipulators `setprecision`, `setw`, and `setfill`, the program must include the header file `iomanip`.
25. The header file `fstream` contains the definitions of `ifstream` and `ofstream`.
26. For file I/O, you must use the statement `#include <fstream>` to include the header file `fstream` in the program. You must also do the following: declare variables of type `ifstream` for file input and of type `ofstream` for file output and use open statements to open input and output files. You can use `<<`, `>>`, `get`, `ignore`, `peek`, `putback`, or `clear` with file stream variables.
27. To close a file as indicated by the `ifstream` variable `inFile`, you use the statement `inFile.close();`. To close a file as indicated by the `ofstream` variable `outFile`, you use the statement `outFile.close();`.

EXERCISES

1. Mark the following statements as true or false.
 - a. The extraction operator `>>` skips all leading whitespace characters when searching for the next data in the input stream.
 - b. In the statement `cin >> x;`, `x` must be a variable.
 - c. The statement `cin >> x >> y;` requires the input values for `x` and `y` to appear on the same line.
 - d. The statement `cin >> num;` is equivalent to the statement `num >> cin;`.

- e. You generate the newline character by pressing the Enter (return) key on the keyboard.
 - f. The function `ignore` is used to skip certain input in a line.
2. Suppose `x` and `y` are `int` variables and `ch` is a `char` variable. Consider the following input:

5 28 36

What value (if any) is assigned to `x`, `y`, and `ch` after each of the following statements executes? (Use the same input for each statement.)

- a. `cin >> x >> y >> ch;`
 - b. `cin >> ch >> x >> y;`
 - c. `cin >> x >> ch >> y;`
 - d. `cin >> x >> y;`
`cin.get(ch);`
3. Suppose `x` and `y` are `int` variables and `z` is a `double` variable. Assume the following input data:

37 86.56 32

What value (if any) is assigned to `x`, `y`, and `z` after each of the following statements executes? (Use the same input for each statement.)

- a. `cin >> x >> y >> z;`
 - b. `cin >> x >> z >> y;`
 - c. `cin >> z >> x >> y;`
4. Suppose `x` and `y` are `int` variables and `ch` is a `char` variable. Assume the following input data:

13 28 D
14 E 98
A B 56

What value (if any) is assigned to `x`, `y`, and `ch` after each of the following statements executes? (Use the same input for each statement.)

- a. `cin >> x >> y;`
`cin.ignore(50, '\n');`
`cin >> ch;`
- b. `cin >> x;`
`cin.ignore(50, '\n');`
`cin >> y;`
`cin.ignore(50, '\n');`
`cin.get(ch);`
- c. `cin >> y;`
`cin.ignore(50, '\n');`
`cin >> x >> ch;`

```
d.  cin.get(ch);
    cin.ignore(50, '\n');
    cin >> x;
    cin.ignore(50, 'E');
    cin >> y;
```

5. Given the input:

```
46 A 49
```

and the C++ code:

```
int x = 10, y = 18;
char z = '*';
cin >> x >> y >> z;
cout << x << " " << y << " " << z << endl;
```

What is the output?

6. Suppose that **x** and **y** are **int** variables, **z** is a **double** variable, and **ch** is a **char** variable. Suppose the input statement is:

```
cin >> x >> y >> ch >> z;
```

What values, if any, are stored in **x**, **y**, **z**, and **ch** if the input is:

- a. 35 62.78
 - b. 86 32A 92.6
 - c. 12 .45A 32
7. Which header file must be included to use the function **steprecision**?
8. Which header file must be included to use the function **pow**?
9. Suppose that **name** is a variable of type **string**. Write the input statement to read and store the input **Brenda Clinton** in **name**. (Assume that the input is from the standard input device.)
10. Write a C++ statement that uses the manipulator **setfill** to output a line containing 35 stars, as in the following line:
- ```

```
11. Suppose that **age** is an **int** variable and **name** is a **string** variable. What are the values of **age** and **name** after the following input statements execute:
- ```
cin >> age;
getline(cin, name);
```
- if the input is:
- a. 23 Lance Grant
 - b. 23
Lance Grant
12. Suppose that **age** is an **int** variable, **ch** is a **char** variable, and **name** is a **string** variable. What are the values of **age** and **name** after the following input statements execute:

```
cin >> age;
cin.get(ch);
getline(cin, name);
```

if the input is:

- a. 23 Lance Grant
- b. 23
Lance Grant

13. The following program is supposed to read two numbers from a file named `input.dat` and write the sum of the numbers to a file named `output.dat`. However, it fails to do so. Rewrite the program so that it accomplishes what it is intended to do. (Also, include statements to close the files.)

```
#include <iostream>
#include <fstream>
using namespace std;

int main()
{
    int num1, num2;
    ifstream infile;

    outfile.open("output.dat");
    infile >> num1 >> num2;
    outfile << "Sum = " << num1 + num2 << endl;
    return 0;
}
```

14. What may cause an input stream to enter the fail state? What happens when an input stream enters the fail state?
15. Which header file needs to be included in a program that uses the data types `ifstream` and `ofstream`?
16. Suppose that `infile` is an `ifstream` variable and `employee.dat` is a file that contains employees' information. Write the C++ statement that opens this file using the variable `infile`.
17. A program reads data from a file called `inputFile.dat` and, after doing some calculations, writes the results to a file called `outFile.dat`. Answer the following questions:
- a. After the program executes, what are the contents of the file `inputFile.dat`?
 - b. After the program executes, what are the contents of the file `outFile.dat` if this file was empty before the program executed?
 - c. After the program executes, what are the contents of the file `outFile.dat` if this file contained 100 numbers before the program executed?
 - d. What would happen if the file `outFile.dat` did not exist before the program executed?

18. Suppose that `infile` is an `ifstream` variable and it is associated with the file that contains the following data: 27306 savings 7503.35. Write the C++ statement(s) that reads and stores the first input in the `int` variable `acctNumber`, the second input in the `string` variable `accountType`, and the third input in the `double` variable `balance`.
19. Suppose that you have the following statements:
- ```
ofstream outfile;
double distance = 375;
double speed = 58;
double travelTime;
```

Write C++ statements to do the following:

- Open the file `travel.dat` using the variable `outfile`.
- Write the statement to format your output to two decimal places in fixed form.
- Write the values of the variables `day`, `distance`, and `speed` in the file `travel.dat`.
- Calculate and write the `travelTime` in the file `travel.dat`.
- Which header files are needed to process the information in (a) to (d)?

## PROGRAMMING EXERCISES

---

1. Consider the following incomplete C++ program:

```
#include <iostream>

int main()
{
 ...
}
```

- Write a statement that includes the header files `fstream`, `string`, and `iomanip` in this program.
- Write statements that declare `inFile` to be an `ifstream` variable and `outFile` to be an `ofstream` variable.
- The program will read data from the file `inData.txt` and write output to the file `outData.txt`. Write statements to open both of these files, associate `inFile` with `inData.txt`, and associate `outFile` with `outData.txt`.
- Suppose that the file `inData.txt` contains the following data:

```
10.20 5.35
15.6
Randy Gill 31
18500 3.5
A
```

The numbers in the first line represent the length and width, respectively, of a rectangle. The number in the second line represents the radius of a circle. The third line contains the first name, last name, and the age of a person. The first number in the fourth line is the savings account balance at the beginning of the month, and the second number is the interest rate per year. (Assume that  $\pi = 3.1416$ .) The fifth line contains an uppercase letter between **A** and **Y** (inclusive). Write statements so that after the program executes, the contents of the file `outData.txt` are as shown below. If necessary, declare additional variables. Your statements should be general enough so that if the content of the input file changes and the program is run again (without editing and recompiling), it outputs the appropriate results.

Rectangle:

Length = 10.20, width = 5.35, area = 54.57, parameter = 31.10

Circle:

Radius = 15.60, area = 764.54, circumference = 98.02

Name: Randy Gill, age: 31

Beginning balance = \$18500.00, interest rate = 3.50

Balance at the end of the month = \$18553.96

The character that comes after **A** in the ASCII set is **B**

- e. Write statements that close the input and output files.
  - f. Write a C++ program that tests the statements in parts a through e.
2. Consider the following program in which the statements are in the incorrect order. Rearrange the statements so that the program prompts the user to input the height and the radius of the base of a cylinder and outputs the volume and surface area of the cylinder. Format the output to two decimal places.

```
#include <iomanip>
#include <cmath>

int main()
{

 double height;

 cout << "Volume of the cylinder = "
 << PI * pow(radius, 2.0)* height << endl;

 cout << "Enter the height of the cylinder: ";
 cin >> radius;
 cout << endl;

 return 0;

 double radius;
```

```

 cout << "Surface area: "
 << 2 * radius * + 2 * PI * pow(radius, 2.0) << endl;
 cout << fixed << showpoint << setprecision(2);

 cout << "Enter the radius of the base of the cylinder: ";
 cin >> height;
 cout << endl;

```

```

#include <iostream>
const double PI = 3.14159;

```

```
using namespace std;
```

3. Write a program that prompts the user to enter the weight of a person in kilograms and outputs the equivalent weight in pounds. Output both the weights rounded to two decimal places. (Note that 1 kilogram = 2.2 pounds.) Format your output with two decimal places.
4. During each summer, John and Jessica grow vegetables in their back yard and buy seeds and fertilizer from a local nursery. The nursery carries different types of vegetable fertilizers in various bag sizes. When buying a particular fertilizer, they want to know the price of the fertilizer per pound and the cost of fertilizing per square foot. The following program prompts the user to enter the size of the fertilizer bag, in pounds, the cost of the bag, and the area, in square feet, that can be covered by the bag. The program should output the desired result. However, the program contains logic errors. Find and correct the logic errors so that the program works properly.

```
//Logic errors.
```

```

#include <iostream>
#include <iomanip>

```

```
using namespace std;
```

```
int main()
{

```

```

 double cost;
 double area;

```

```
 double bagSize;
```

```
 cout << fixed << showpoint << setprecision(2);
```

```

 cout << "Enter the amount of fertilizer, in pounds, "
 << "in one bag: ";
 cin >> bagSize;
 cout << endl;

```

```

 cout << "Enter the cost of the " << bagSize
 << " pound fertilizer bag: ";

```

```

 cin >> cost;
 cout << endl;

 cout << "Enter the area, in square feet, that can be "
 << "fertilized by one bag: ";
 cin >> area;
 cout << endl;

 cout << "The cost of the fertilizer per pound is: $"
 << bagSize / cost << endl;
 cout << "The cost of fertilizing per square foot is: $"
 << area / cost << endl;

 return 0;
}

```

5. The manager of a football stadium wants you to write a program that calculates the total ticket sales after each game. There are four types of tickets—box, sideline, premium, and general admission. After each game, data is stored in a file in the following form:

```

ticketPrice numberOfTicketsSold
...

```

Sample data are shown below:

```

250 5750
100 28000
 50 35750
 25 18750

```

The first line indicates that the ticket price is \$250 and that 5750 tickets were sold at that price. Output the number of tickets sold and the total sale amount. Format your output with two decimal places.

6. Write a program that calculates and prints the monthly paycheck for an employee. The net pay is calculated after taking the following deductions:

```

Federal Income Tax: 15%
State Tax: 3.5%
Social Security Tax: 5.75%
Medicare/Medicaid Tax: 2.75%
Pension Plan: 5%
Health Insurance: $75.00

```

Your program should prompt the user to input the gross amount and the employee name. The output will be stored in a file. Format your output to have two decimal places. A sample output follows:

```

Bill Robinson
Gross Amount: $3575.00
Federal Tax: $ 536.25
State Tax: $ 125.13

```

```

Social Security Tax: $ 205.56
Medicare/Medicaid Tax: ... $ 98.31
Pension Plan: $ 178.75
Health Insurance: $ 75.00
Net Pay: $2356.00

```

Note that the first column is left-justified, and the right column is right-justified.

7. Redo Programming Exercise 21, in Chapter 2, so that each string can store a line of text.
8. Three employees in a company are up for a special pay increase. You are given a file, say `Ch3_Ex8Data.txt`, with the following data:

```

Miller Andrew 65789.87 5
Green Sheila 75892.56 6
Sethi Amit 74900.50 6.1

```

Each input line consists of an employee's last name, first name, current salary, and percent pay increase. For example, in the first input line, the last name of the employee is **Miller**, the first name is **Andrew**, the current salary is **65789.87**, and pay increase is **5%**. Write a program that reads data from the specified file and stores the output in the file `Ch3_Ex8Output.dat`. For each employee, the data must be output in the following form: **firstName lastName updatedSalary**. Format the output of decimal numbers to two decimal places.

9. Write a program that accepts as input the mass, in grams, and density, in grams per cubic centimeters, and outputs the volume of the object using the formula:  $density = mass / volume$ . Format your output to two decimal places.
10. Interest on a credit card's unpaid balance is calculated using the average daily balance. Suppose that *netBalance* is the balance shown in the bill, *payment* is the payment made, *d1* is the number of days in the billing cycle, and *d2* is the number of days payment is made before billing cycle. Then, the average daily balance is:

$$averageDailyBalance = (netBalance * d1 - payment * d2) / d1$$

If the interest rate per month is, say, 0.0152, then the interest on the unpaid balance is:

$$interest = averageDailyBalance * 0.0152$$

Write a program that accepts as input *netBalance*, *payment*, *d1*, *d2*, and interest rate per month. The program outputs the interest. Format your output to two decimal places.



# CHAPTER 4

## CONTROL STRUCTURES I (SELECTION)

IN THIS CHAPTER, YOU WILL:

- Learn about control structures
- Examine relational and logical operators
- Explore how to form and evaluate logical (Boolean) expressions
- Discover how to use the selection control structures `if`, `if...else`, and `switch` in a program
- Learn how to avoid bugs by avoiding partially understood concepts
- Learn to use the `assert` function to terminate a program

Chapter 2 defined a program as a sequence of statements whose objective is to accomplish some task. The programs you have examined so far were simple and straightforward. To process a program, the computer begins at the first executable statement and executes the statements in order until it comes to the end. In this chapter and Chapter 5, you will learn how to tell a computer that it does not have to follow a simple sequential order of statements; it can also make decisions and repeat certain statements over and over until certain conditions are met.

## Control Structures

A computer can process a program in one of the following ways: in sequence; selectively, by making a choice, which is also called a branch; repetitively, by executing a statement over and over, using a structure called a loop; or by calling a function. Figure 4-1 illustrates the first three types of program flow. (In Chapter 7, we will show how function calls work.) The programming examples in Chapters 2 and 3 included simple sequential programs. With such a program, the computer starts at the beginning and follows the statements in order. No choices are made; there is no repetition. Control structures provide alternatives to sequential program execution and are used to alter the sequential flow of execution. The two most common control structures are selection and repetition. In *selection*, the program executes particular statements depending on some condition(s). In *repetition*, the program repeats particular statements a certain number of times based on some condition(s).




FIGURE 4-1 Flow of execution

Before you can learn about selection and repetition, you must understand the nature of conditional statements and how to use them. Consider the following three statements:

1. `if (score is greater than or equal to 90)`  
    `grade is A`
2. `if (hours worked are less than or equal to 40)`  
    `wages = rate * hours`  
    `otherwise`  
        `wages = (rate * 40) + 1.5 * (rate * (hours - 40))`
3. `if (temperature is greater than 70 degrees and it is not raining)`  
    `Go golfing!`

These statements are examples of conditional statements. You can see that certain statements are to be executed only if certain conditions are met. A condition is met if it evaluates to `true`. For example, in statement 1:

`score is greater than or equal to 90`

is `true` if the value of `score` is greater than or equal to 90; it is `false` otherwise. For example, if the value of `score` is 95, the statement evaluates to `true`. Similarly, if the value of `score` is 86, the statement evaluates to `false`.

It would be useful if the computer could recognize these types of statements to be true for appropriate values. Furthermore, in certain situations, the truth or falsity of a statement could depend on more than one condition. For example, in statement 3, both `temperature is greater than 70 degrees` and `it is not raining` must be true to recommend golfing.

As you can see, for the computer to make decisions and repeat statements, it must be able to react to conditions that exist when the program executes. The next few sections discuss how to represent and evaluate conditional statements in C++.

## Relational Operators

To make decisions, you must be able to express conditions and make comparisons. For example, the interest rate and service charges on a checking account might depend on the balance at the end of the month. If the balance is less than some minimum balance, not only is the interest rate lower, but there is also usually a service charge. Therefore, to determine the interest rate, you must be able to state the minimum balance and compare the account balance with the minimum balance (a condition). The premium on an insurance policy is also determined by stating conditions and making comparisons. For example, to determine an insurance premium, you must be able to check the smoking status of the policyholder. Nonsmokers (the condition) receive lower premiums than smokers. Both of these examples involve comparing items. Certain items are compared

for equality against a particular condition; others are compared for inequality (greater than or less than) against a particular condition.

In C++, a condition is represented by a logical (Boolean) expression. An expression that has a value of either `true` or `false` is called a **logical (Boolean) expression**. Moreover, `true` and `false` are **logical (Boolean) values**. Suppose `i` and `j` are integers. Consider the expression:

`i > j`

If this expression is a logical expression, it will have the value `true` if the value of `i` is greater than the value of `j`; otherwise, it will have the value `false`. The symbol `>` is called a relational operator. A **relational operator** allows you to make comparisons in a program.

C++ includes six relational operators that allow you to state conditions and make comparisons. Table 4-1 lists the relational operators.

**TABLE 4-1** Relational Operators in C++

| Operator           | Description              |
|--------------------|--------------------------|
| <code>==</code>    | equal to                 |
| <code>!=</code>    | not equal to             |
| <code>&lt;</code>  | less than                |
| <code>&lt;=</code> | less than or equal to    |
| <code>&gt;</code>  | greater than             |
| <code>&gt;=</code> | greater than or equal to |

**NOTE** In C++, the symbol `==`, which consists of two equal signs, is called the equality operator. Recall that the symbol `=` is called the assignment operator. Remember that the equality operator, `==`, determines whether two expressions are equal, whereas the assignment operator, `=`, assigns the value of an expression to a variable.

Each of the relational operators is a binary operator; that is, it requires two operands. Because the result of a comparison is `true` or `false`, expressions using these operators evaluate to `true` or `false`.

## Relational Operators and Simple Data Types

You can use the relational operators with all three simple data types. In the following example, the expressions use both integers and real numbers:

EXAMPLE 4-1

| Expression | Meaning                          | Value |
|------------|----------------------------------|-------|
| 8 < 15     | 8 is less than 15                | true  |
| 6 != 6     | 6 is not equal to 6              | false |
| 2.5 > 5.8  | 2.5 is greater than 5.8          | false |
| 5.9 <= 7.5 | 5.9 is less than or equal to 7.5 | true  |

Comparing Characters

For `char` values, whether an expression using relational operators evaluates to `true` or `false` depends on a machine's collating sequence. The collating sequence of some of the characters is:

| ASCII Value | Char | ASCII Value | Char | ASCII Value | Char | ASCII Value | Char |
|-------------|------|-------------|------|-------------|------|-------------|------|
| 32          | ' '  | 61          | =    | 81          | Q    | 105         | i    |
| 33          | !    | 62          | >    | 82          | R    | 106         | j    |
| 34          | "    | 65          | A    | 83          | S    | 107         | k    |
| 42          | *    | 66          | B    | 84          | T    | 108         | l    |
| 43          | +    | 67          | C    | 85          | U    | 109         | m    |
| 45          | -    | 68          | D    | 86          | V    | 110         | n    |
| 47          | /    | 69          | E    | 87          | W    | 111         | o    |
| 48          | 0    | 70          | F    | 88          | X    | 112         | p    |
| 49          | 1    | 71          | G    | 89          | Y    | 113         | q    |
| 50          | 2    | 72          | H    | 90          | Z    | 114         | r    |
| 51          | 3    | 73          | I    | 97          | a    | 115         | s    |
| 52          | 4    | 74          | J    | 98          | b    | 116         | t    |
| 53          | 5    | 75          | K    | 99          | c    | 117         | u    |
| 54          | 6    | 76          | L    | 100         | d    | 118         | v    |
| 55          | 7    | 77          | M    | 101         | e    | 119         | w    |
| 56          | 8    | 78          | N    | 102         | f    | 120         | x    |
| 57          | 9    | 79          | O    | 103         | g    | 121         | y    |
| 60          | <    | 80          | P    | 104         | h    | 122         | z    |

The ASCII character set is described in Appendix C.

Now, because 32 < 97, and the ASCII value of ' ' is 32 and the ASCII value of 'a' is 97, it follows that ' ' < 'a' is `true`. Similarly, using the previous ASCII values:

'R' > 'T' is `false`

'+' < '\*' is `false`

'A' <= 'a' is `true`

note that comparing values of different data types may produce unpredictable results. For example, the following expression compares an integer and a character:

```
8 < '5'
```

In this expression, on a particular machine, `8` would be compared with the collating sequence of `'5'`, which is 53. That is, `8` is compared with 53, which makes this particular expression evaluate to `true`.

Expressions such as `4 < 6` and `'R' > 'T'` are examples of **logical (Boolean) expressions**. When C++ evaluates a logical expression, it returns an integer value of 1 if the logical expression evaluates to `true`; it returns an integer value of 0 otherwise. In C++, any nonzero value is treated as `true`.

**NOTE** Chapter 2 introduced the data type `bool`. Recall that the data type `bool` has two values, `true` and `false`. In C++, `true` and `false` are reserved words. The identifier `true` is set to 1, and the identifier `false` is set to 0. For readability, whenever logical expressions are used, the identifiers `true` and `false` will be used here as the value of the logical expression.

## Relational Operators and the `string` Type

The relational operators can be applied to variables of type `string`. Variables of type `string` are compared character by character, starting with the first character and using the ASCII collating sequence. The character-by-character comparison continues until either a mismatch is found or the last characters have been compared and are equal. The following example shows how variables of type `string` are compared.

### EXAMPLE 4-2

Suppose that you have the statements:

```
string str1 = "Hello";
string str2 = "Hi";
string str3 = "Air";
string str4 = "Bill";
string str5 = "Big";
```

The following expressions show how string relational expressions evaluate.

| Expression                  | Value /Explanation                                                                                                                                                                                                                                                                                                                                                   |
|-----------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>str1 &lt; str2</code> | <code>true</code><br><code>str1 = "Hello"</code> and <code>str2 = "Hi"</code> . The first characters of <code>str1</code> and <code>str2</code> are the same, but the second character <code>'e'</code> of <code>str1</code> is less than the second character <code>'i'</code> of <code>str2</code> . Therefore, <code>str1 &lt; str2</code> is <code>true</code> . |

|                              |                                                                                                                                                                                                                                                                                                                                                         |
|------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>str1 &gt; "Hen"</code> | <p><b>false</b></p> <p><code>str1 = "Hello"</code>. The first two characters of <code>str1</code> and <code>"Hen"</code> are the same, but the third character <code>'l'</code> of <code>str1</code> is less than the third character <code>'n'</code> of <code>"Hen"</code>. Therefore, <code>str1 &gt; "Hen"</code> is <b>false</b>.</p>              |
| <code>str3 &lt; "An"</code>  | <p><b>true</b></p> <p><code>str3 = "Air"</code>. The first characters of <code>str3</code> and <code>"An"</code> are the same, but the second character <code>'i'</code> of <code>"Air"</code> is less than the second character <code>'n'</code> of <code>"An"</code>. Therefore, <code>str3 &lt; "An"</code> is <b>true</b>.</p>                      |
| <code>str1 == "hello"</code> | <p><b>false</b></p> <p><code>str1 = "Hello"</code>. The first character <code>'H'</code> of <code>str1</code> is less than the first character <code>'h'</code> of <code>"hello"</code> because the ASCII value of <code>'H'</code> is 72, and the ASCII value of <code>'h'</code> is 104. Therefore, <code>str1 == "hello"</code> is <b>false</b>.</p> |
| <code>str3 &lt;= str4</code> | <p><b>true</b></p> <p><code>str3 = "Air"</code> and <code>str4 = "Bill"</code>. The first character <code>'A'</code> of <code>str3</code> is less than the first character <code>'B'</code> of <code>str4</code>. Therefore, <code>str3 &lt;= str4</code> is <b>true</b>.</p>                                                                           |
| <code>str2 &gt; str4</code>  | <p><b>true</b></p> <p><code>str2 = "Hi"</code> and <code>str4 = "Bill"</code>. The first character <code>'H'</code> of <code>str2</code> is greater than the first character <code>'B'</code> of <code>str4</code>. Therefore, <code>str2 &gt; str4</code> is <b>true</b>.</p>                                                                          |

If two strings of different lengths are compared and the character-by-character comparison is equal until it reaches the last character of the shorter string, the shorter string is evaluated as less than the larger string, as shown next.

| Expression                       | Value/Explanation                                                                                                                                                                                                                                                                                                                                                                                                        |
|----------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>str4 &gt;= "Billy"</code>  | <p><b>false</b></p> <p><code>str4 = "Bill"</code>. It has four characters, and <code>"Billy"</code> has five characters. Therefore, <code>str4</code> is the shorter string. All four characters of <code>str4</code> are the same as the corresponding first four characters of <code>"Billy"</code>, and <code>"Billy"</code> is the larger string. Therefore, <code>str4 &gt;= "Billy"</code> is <b>false</b>.</p>    |
| <code>str5 &lt;= "Bigger"</code> | <p><b>true</b></p> <p><code>str5 = "Big"</code>. It has three characters, and <code>"Bigger"</code> has six characters. Therefore, <code>str5</code> is the shorter string. All three characters of <code>str5</code> are the same as the corresponding first three characters of <code>"Bigger"</code>, and <code>"Bigger"</code> is the larger string. Therefore, <code>str5 &lt;= "Bigger"</code> is <b>true</b>.</p> |

The program `Chapter4_StringComparisons.cpp` at the Web site accompanying this book shows the results of the previous expressions.

## Logical (Boolean) Operators and Logical Expressions

This section describes how to form and evaluate logical expressions that are combinations of other logical expressions. **Logical (Boolean) operators** enable you to combine logical expressions. C++ has three logical (Boolean) operators, as shown in Table 4-2.

**TABLE 4-2** Logical (Boolean) Operators in C++

| Operator | Description |
|----------|-------------|
| !        | not         |
| &&       | and         |
|          | or          |

Logical operators take only logical values as operands and yield only logical values as results. The operator `!` is unary, so it has only one operand. The operators `&&` and `||` are binary operators. Tables 4-3, 4-4, and 4-5 define these operators.

Table 4-3 defines the operator `!` (not). When you use the `!` operator, `!true` is `false` and `!false` is `true`. Putting `!` in front of a logical expression reverses the value of that logical expression.

**TABLE 4-3** The `!` (Not) Operator

| Expression                  | !(Expression)          |
|-----------------------------|------------------------|
| <code>true</code> (nonzero) | <code>false</code> (0) |
| <code>false</code> (0)      | <code>true</code> (1)  |

### EXAMPLE 4-3

| Expression                   | Value              | Explanation                                                                                                   |
|------------------------------|--------------------|---------------------------------------------------------------------------------------------------------------|
| <code>!('A' &gt; 'B')</code> | <code>true</code>  | Because <code>'A' &gt; 'B'</code> is <code>false</code> , <code>!('A' &gt; 'B')</code> is <code>true</code> . |
| <code>!(6 &lt;= 7)</code>    | <code>false</code> | Because <code>6 &lt;= 7</code> is <code>true</code> , <code>!(6 &lt;= 7)</code> is <code>false</code> .       |

Table 4-4 defines the operator `&&` (and). From this table, it follows that `Expression1 && Expression2` is **true** if and only if both `Expression1` and `Expression2` are **true**; otherwise, `Expression1 && Expression2` evaluates to **false**.

**TABLE 4-4** The `&&` (And) Operator

| Expression1           | Expression2           | Expression1 && Expression2 |
|-----------------------|-----------------------|----------------------------|
| <b>true</b> (nonzero) | <b>true</b> (nonzero) | <b>true</b> (1)            |
| <b>true</b> (nonzero) | <b>false</b> (0)      | <b>false</b> (0)           |
| <b>false</b> (0)      | <b>true</b> (nonzero) | <b>false</b> (0)           |
| <b>false</b> (0)      | <b>false</b> (0)      | <b>false</b> (0)           |

4

#### EXAMPLE 4-4

| Expression                                           | Value        | Explanation                                                                                                                                                                                    |
|------------------------------------------------------|--------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>(14 &gt;= 5) &amp;&amp; ('A' &lt; 'B')</code>  | <b>true</b>  | Because <code>(14 &gt;= 5)</code> is <b>true</b> , <code>('A' &lt; 'B')</code> is <b>true</b> , and <b>true</b> && <b>true</b> is <b>true</b> , the expression evaluates to <b>true</b> .      |
| <code>(24 &gt;= 35) &amp;&amp; ('A' &lt; 'B')</code> | <b>false</b> | Because <code>(24 &gt;= 35)</code> is <b>false</b> , <code>('A' &lt; 'B')</code> is <b>true</b> , and <b>false</b> && <b>true</b> is <b>false</b> , the expression evaluates to <b>false</b> . |

Table 4-5 defines the operator `||` (or). From this table, it follows that `Expression1 || Expression2` is **true** if and only if at least one of the expressions, `Expression1` or `Expression2`, is **true**; otherwise, `Expression1 || Expression2` evaluates to **false**.

**TABLE 4-5** The `||` (Or) Operator

| Expression1           | Expression2           | Expression1    Expression2 |
|-----------------------|-----------------------|----------------------------|
| <b>true</b> (nonzero) | <b>true</b> (nonzero) | <b>true</b> (1)            |
| <b>true</b> (nonzero) | <b>false</b> (0)      | <b>true</b> (1)            |
| <b>false</b> (0)      | <b>true</b> (nonzero) | <b>true</b> (1)            |
| <b>false</b> (0)      | <b>false</b> (0)      | <b>false</b> (0)           |

| EXAMPLE 4-5               |       |                                                                                                                    |
|---------------------------|-------|--------------------------------------------------------------------------------------------------------------------|
| Expression                | Value | Explanation                                                                                                        |
| (14 >= 5)    ('A' > 'B')  | true  | Because (14 >= 5) is true, ('A' > 'B') is false, and true    false is true, the expression evaluates to true.      |
| (24 >= 35)    ('A' > 'B') | false | Because (24 >= 35) is false, ('A' > 'B') is false, and false    false is false, the expression evaluates to false. |
| ('A' <= 'a')    (7 != 7)  | true  | Because ('A' <= 'a') is true, (7 != 7) is false, and true    false is true, the expression evaluates to true.      |

### Order of Precedence

Complex logical expressions can be difficult to evaluate. Consider the following logical expression:

11 > 5 || 6 < 15 && 7 >= 8

This logical expression yields different results, depending on whether || or && is evaluated first. If || is evaluated first, the expression evaluates to false. If && is evaluated first, the expression evaluates to true.

An expression might contain arithmetic, relational, and logical operators, as in the expression:

5 + 3 <= 9 && 2 > 3

To work with complex logical expressions, there must be some priority scheme for evaluating operators. Table 4-6 shows the order of precedence of some C++ operators,

TABLE 4-6 Precedence of Operators

| Operators                 | Precedence |
|---------------------------|------------|
| !, +, - (unary operators) | first      |
| *, /, %                   | second     |
| +, -                      | third      |
| <, <=, >=, >              | fourth     |
| ==, !=                    | fifth      |
| &&                        | sixth      |
|                           | seventh    |
| = (assignment operator)   | last       |

including the arithmetic, relational, and logical operators. (See Appendix B for the precedence of all C++ operators.)

# NOTE

In C++, `&` and `|` are also operators. The meaning of these operators is different from the meaning of `&&` and `||`. Using `&` in place of `&&` or `|` in place of `||`—as might result from a typographical error—would produce very strange results.

Using the precedence rules in an expression, relational and logical operators are evaluated from left to right. Because relational and logical operators are evaluated from left to right, the **associativity** of these operators is said to be from left to right.

Example 4-6 illustrates how logical expressions consisting of variables are evaluated.

## EXAMPLE 4-6

Suppose you have the following declarations:

```
bool found = true;
int age = 20;
double hours = 45.30;
double overTime = 15.00;
int count = 20;
char ch = 'B';
```

Consider the following expressions:

| Expression                                      | Value / Explanation                                                                                                                                                                                                                                     |
|-------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>!found</code>                             | <b>false</b><br>Because <code>found</code> is <b>true</b> , <code>!found</code> is <b>false</b> .                                                                                                                                                       |
| <code>hours &gt; 40.00</code>                   | <b>true</b><br>Because <code>hours</code> is 45.30 and <code>45.30 &gt; 40.00</code> is <b>true</b> , the expression <code>hours &gt; 40.00</code> evaluates to <b>true</b> .                                                                           |
| <code>!age</code>                               | <b>false</b><br><code>age</code> is 20, which is nonzero, so <code>age</code> is <b>true</b> . Therefore, <code>!age</code> is <b>false</b> .                                                                                                           |
| <code>!found &amp;&amp; (age &gt;= 18)</code>   | <b>false</b><br><code>!found</code> is <b>false</b> ; <code>age &gt; 18</code> is <code>20 &gt; 18</code> is <b>true</b> . Therefore, <code>!found &amp;&amp; (age &gt;= 18)</code> is <b>false &amp;&amp; true</b> , which evaluates to <b>false</b> . |
| <code>!(found &amp;&amp; (age &gt;= 18))</code> | <b>false</b><br>Now, <code>found &amp;&amp; (age &gt;= 18)</code> is <b>true &amp;&amp; true</b> , which evaluates to <b>true</b> . Therefore, <code>!(found &amp;&amp; (age &gt;= 18))</code> is <b>!true</b> , which evaluates to <b>false</b> .      |

| Expression                                                        | Value / Explanation                                                                                                                                                                                                                                                                                                                                                                                   |
|-------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>hours + overTime &lt;= 75.00</code>                         | <b>true</b><br>Because <code>hours + overTime</code> is <code>45.30 + 15.00 = 60.30</code> and <code>60.30 &lt;= 75.00</code> is <b>true</b> , it follows that <code>hours + overTime &lt;= 75.00</code> evaluates to <b>true</b> .                                                                                                                                                                   |
| <code>(count &gt;= 0) &amp;&amp;<br/>    (count &lt;= 100)</code> | <b>true</b><br>Now, <code>count</code> is 20. Because <code>20 &gt;= 0</code> is <b>true</b> , <code>count &gt;= 0</code> is <b>true</b> . Also, <code>20 &lt;= 100</code> is <b>true</b> , so <code>count &lt;= 100</code> is <b>true</b> . Therefore, <code>(count &gt;= 0) &amp;&amp; (count &lt;= 100)</code> is <b>true &amp;&amp; true</b> , which evaluates to <b>true</b> .                   |
| <code>('A' &lt;= ch &amp;&amp; ch &lt;= 'Z')</code>               | <b>true</b><br>Here, <code>ch</code> is 'B'. Because <code>'A' &lt;= 'B'</code> is <b>true</b> , <code>'A' &lt;= ch</code> evaluates to <b>true</b> . Also, because <code>'B' &lt;= 'Z'</code> is <b>true</b> , <code>ch &lt;= 'Z'</code> evaluates to <b>true</b> . Therefore, <code>('A' &lt;= ch &amp;&amp; ch &lt;= 'Z')</code> is <b>true &amp;&amp; true</b> , which evaluates to <b>true</b> . |

The following program evaluates and outputs the values of these logical expressions. Note that if a logical expression evaluates to **true**, the corresponding output is 1; if the logical expression evaluates to **false**, the corresponding output is 0, as shown in the output at the end of the program. (Recall that if the value of a logical expression is **true**, it evaluates to 1, and if the value of the logical expression is **false**, it evaluates to 0.)

#### //Chapter 4 Logical operators

```
#include <iostream>
#include <iomanip>

using namespace std;

int main()
{
 bool found = true;
 int age = 20;
 double hours = 45.30;
 double overTime = 15.00;
 int count = 20;
 char ch = 'B';

 cout << fixed << showpoint << setprecision(2);
 cout << "found = " << found << ", age = " << age
 << ", hours = " << hours << ", overTime = " << overTime
 << ", " << endl << "count = " << count
 << ", ch = " << ch << endl << endl;

 cout << "!found evaluates to " << !found << endl;
 cout << "hours > 40.00 evaluates to " << (hours > 40.00) << endl;
 cout << "!age evaluates to " << !age << endl;
 cout << "!found && (hours >= 0) evaluates to "
 << (!found && (hours >= 0)) << endl;
```

```

cout << "!(found && (hours >= 0)) evaluates to "
 << (!(found && (hours >= 0))) << endl;
cout << "hours + overTime <= 75.00 evaluates to "
 << (hours + overTime <= 75.00) << endl;
cout << "(count >= 0) && (count <= 100) evaluates to "
 << ((count >= 0) && (count <= 100)) << endl;
cout << "('A' <= ch && ch <= 'Z') evaluates to "
 << ('A' <= ch && ch <= 'Z') << endl;

return 0;
}

```

### Sample Run:

```

found = 1, age = 20, hours = 45.30, overTime = 15.00,
count = 20, ch = B

```

```

!found evaluates to 0
hours > 40.00 evaluates to 1
!age evaluates to 0
!found && (hours >= 0) evaluates to 0
!(found && (hours >= 0)) evaluates to 0
hours + overTime <= 75.00 evaluates to 1
(count >= 0) && (count <= 100) evaluates to 1
('A' <= ch && ch <= 'Z') evaluates to 1

```

You can insert parentheses into an expression to clarify its meaning. You can also use parentheses to override the precedence of operators. Using the standard order of precedence, the expression:

```
11 > 5 || 6 < 15 && 7 >= 8
```

is equivalent to:

```
11 > 5 || (6 < 15 && 7 >= 8)
```

In this expression, `11 > 5` is **true**, `6 < 15` is **true**, and `7 >= 8` is **false**. Substitute these values in the expression `11 > 5 || (6 < 15 && 7 >= 8)` to get **true || (true && false) = true || false = true**. Therefore, the expression `11 > 5 || (6 < 15 && 7 >= 8)` evaluates to **true**.

In C++, logical (Boolean) expressions can be manipulated or processed in either of two ways: by using **int** variables or by using **bool** variables. The following sections describe these methods.

## int Data Type and Logical (Boolean) Expressions

Earlier versions of C++ did not provide built-in data types that had logical (or Boolean) values **true** and **false**. Because logical expressions evaluate to either 1 or 0, the value of a logical expression was stored in a variable of the data type **int**. Therefore, you can use the **int** data type to manipulate logical (Boolean) expressions.

Recall that nonzero values are treated as **true**. Now, consider the declarations:

```
int legalAge;
int age;
```

and the assignment statement:

```
legalAge = 21;
```

If you regard **legalAge** as a logical variable, the value of **legalAge** assigned by this statement is **true**.

The assignment statement:

```
legalAge = (age >= 21);
```

assigns the value 1 to **legalAge** if the value of **age** is greater than or equal to 21. The statement assigns the value 0 if the value of **age** is less than 21.

## bool Data Type and Logical (Boolean) Expressions

More recent versions of C++ contain a built-in data type, **bool**, that has the logical (Boolean) values **true** and **false**. Therefore, you can manipulate logical (Boolean) expressions using the **bool** data type. Recall that in C++, **bool**, **true**, and **false** are reserved words. In addition, the identifier **true** has the value 1, and the identifier **false** has the value 0. Now, consider the following declaration:

```
bool legalAge;
int age;
```

The statement:

```
legalAge = true;
```

sets the value of the variable **legalAge** to **true**. The statement:

```
legalAge = (age >= 21);
```

assigns the value **true** to **legalAge** if the value of **age** is greater than or equal to 21. This statement assigns the value **false** to **legalAge** if the value of **age** is less than 21. For example, if the value of **age** is 25, the value assigned to **legalAge** is **true**—that is, 1. Similarly, if the value of **age** is 16, the value assigned to **legalAge** is **false**—that is, 0.

### NOTE

You can use either an **int** variable or a **bool** variable to store the value of a logical expression. For the purpose of clarity, this book uses **bool** variables to store the values of logical expressions.

## Selection: **if** and **if...else**

Although there are only two logical values, **true** and **false**, they turn out to be extremely useful because they permit programs to incorporate decision making that alters the processing flow. The remainder of this chapter discusses ways to incorporate decisions

into a program. In C++, there are two selections, or branch control structures: `if` statements and the `switch` structure. This section discusses how `if` and `if...else` statements can be used to create one-way selection, two-way selection, and multiple selections. The `switch` structure is discussed later in this chapter.

## One-Way Selection

A bank would like to send a notice to a customer if her or his checking account balance falls below the required minimum balance. That is, if the account balance is below the required minimum balance, it should send a notice to the customer; otherwise, it should do nothing. Similarly, if the policyholder of an insurance policy is a nonsmoker, the company would like to apply a 10% discount to the policy premium. Both of these examples involve one-way selection. In C++, one-way selections are incorporated using the `if` statement. The syntax of one-way selection is:

```
if (expression)
 statement
```

Note the elements of this syntax. It begins with the reserved word `if`, followed by an **expression** contained within parentheses, followed by a **statement**. Note that the parentheses around the **expression** are part of the syntax. The **expression** is sometimes called a **decision maker** because it decides whether to execute the **statement** that follows it. The **expression** is usually a logical expression. If the value of the **expression** is `true`, the **statement** executes. If the value is `false`, the **statement** does not execute and the computer goes on to the next statement in the program. The **statement** following the **expression** is sometimes called the **action statement**. Figure 4-2 shows the flow of execution of the `if` statement (one-way selection).




FIGURE 4-2 One-way selection

**EXAMPLE 4-7**

```
if (score >= 60)
 grade = 'P';
```

In this code, if the expression (`score >= 60`) evaluates to **true**, the assignment statement, `grade = 'P';`, executes. If the expression evaluates to **false**, the statements (if any) following the **if** structure execute. For example, if the value of `score` is 65, the value assigned to the variable `grade` is 'P'.

**EXAMPLE 4-8**

The following C++ program finds the absolute value of an integer.

```
//Program: Absolute value of an integer

#include <iostream>

using namespace std;

int main()
{
 int number, temp;

 cout << "Line 1: Enter an integer: "; //Line 1
 cin >> number; //Line 2
 cout << endl; //Line 3

 temp = number; //Line 4

 if (number < 0) //Line 5
 number = -number; //Line 6

 cout << "Line 7: The absolute value of "
 << temp << " is " << number << endl; //Line 7

 return 0;
}
```

**Sample Run:** In this sample run, the user input is shaded.

```
Line 1: Enter an integer: -6734
Line 7: The absolute value of -6734 is 6734
```

The statement in Line 1 prompts the user to enter an integer; the statement in Line 2 inputs the number into the variable `number`. The statement in Line 4 copies the value of `number` into `temp`, and the statement in Line 5 checks whether `number` is negative. If `number` is negative, the statement in Line 6 changes `number` to a positive number. The statement in Line 7 outputs the number and its absolute value. Note that because we want

to output both **number** and its absolute value, and if **number** is negative, the **if** statement changes **number** to positive, we copied the value of **number** into **temp** in Line 4.

#### EXAMPLE 4-9

Consider the following statement:

```
if score >= 60 //syntax error
 grade = 'P';
```

This statement illustrates an incorrect version of an **if** statement. The parentheses around the logical expression are missing, which is a syntax error.

Putting a semicolon after the parentheses following the **expression** in an **if** statement (that is, before the **statement**) is a semantic error. If the semicolon immediately follows the closing parenthesis, the **if** statement will operate on the empty statement.

#### EXAMPLE 4-10

Consider the following C++ statements:

```
if (score >= 60); //Line 1
 grade = 'P'; //Line 2
```

Because there is a semicolon at the end of the expression (see Line 1), the **if** statement in Line 1 terminates. The action of this **if** statement is null, and the statement in Line 2 is not part of the **if** statement in Line 1. Hence, the statement in Line 2 executes regardless of how the **if** statement evaluates.

## Two-Way Selection

There are many programming situations in which you must choose between two alternatives. For example, if a part-time employee works overtime, the paycheck is calculated using the overtime payment formula; otherwise, the paycheck is calculated using the regular formula. This is an example of two-way selection. To choose between two alternatives—that is, to implement two-way selections—C++ provides the **if...else** statement. Two-way selection uses the following syntax:

```
if (expression)
 statement1
else
 statement2
```

Take a moment to examine this syntax. It begins with the reserved word **if**, followed by a logical expression contained within parentheses, followed by a statement, followed by the reserved word **else**, followed by a second statement. Statements 1 and 2 are any valid C++ statements. In a two-way selection, if the value of the **expression** is **true**, **statement1** executes. If the value of the **expression** is **false**, **statement2** executes. Figure 4-3 shows the flow of execution of the **if...else** statement (two-way selection).




FIGURE 4-3 Two-way selection

### EXAMPLE 4-11

Consider the following statements:

```

if (hours > 40.0) //Line 1
 wages = 40.0 * rate +
 1.5 * rate * (hours - 40.0); //Line 2
else //Line 3
 wages = hours * rate; //Line 4

```

If the value of the variable **hours** is greater than 40.0, the **wages** include overtime payment. Suppose that **hours** is 50. The expression in the **if** statement, in Line 1, evaluates to **true**, so the statement in Line 2 executes. On the other hand, if **hours** is 30 or any number less than or equal to 40, the expression in the **if** statement, in Line 1, evaluates to **false**. In this case, the program skips the statement in Line 2 and executes the statement in Line 4—that is, the statement following the reserved word **else** executes.

In a two-way selection statement, putting a semicolon after the **expression** and before **statement1** creates a syntax error. If the **if** statement ends with a semicolon, **statement1** is no longer part of the **if** statement, and the **else** part of the **if...else** statement stands all by itself. There is no stand-alone **else** statement in C++. That is, it cannot be separated from the **if** statement.

**EXAMPLE 4-12**

The following statements show an example of a syntax error.

```

if (hours > 40.0); //Line 1
 wages = 40.0 * rate +
 1.5 * rate * (hours - 40.0); //Line 2
else //Line 3
 wages = hours * rate; //Line 4

```

The semicolon at the end of the **if** statement (see Line 1) ends the **if** statement, so the statement in Line 2 separates the **else** clause from the **if** statement. That is, **else** is all by itself. Because there is no stand-alone **else** statement in C++, this code generates a syntax error. As shown in Example 4-10, in a one-way selection, the semicolon at the end of an **if** statement is a logical error, whereas as shown in this example, in a two-way selection, it is a syntax error.

**4****EXAMPLE 4-13**

The following program determines an employee's weekly wages. If the hours worked exceed 40, wages include overtime payment.

```

//Program: Weekly wages

#include <iostream>
#include <iomanip>

using namespace std;

int main()

 double wages, rate, hours;

 cout << fixed << showpoint << setprecision(2); //Line 1
 cout << "Line 2: Enter working hours and rate: "; //Line 2
 cin >> hours >> rate; //Line 3

 if (hours > 40.0) //Line 4
 wages = 40.0 * rate +
 1.5 * rate * (hours - 40.0); //Line 5
 else //Line 6
 wages = hours * rate; //Line 7

 cout << endl; //Line 8
 cout << "Line 9: The wages are $" << wages
 << endl; //Line 9

 return 0;

}

```

**Sample Run:** In this sample run, the user input is shaded.

Line 2: Enter working hours and rate: 56.45 12.50

Line 9: The wages are \$808.44

The statement in Line 1 sets the output of the floating-point numbers in a fixed decimal format, with a decimal point, trailing zeros, and two decimal places. The statement in Line 2 prompts the user to input the number of hours worked and the pay rate. The statement in Line 3 inputs these values into the variables `hours` and `rate`, respectively. The statement in Line 4 checks whether the value of the variable `hours` is greater than 40.0. If `hours` is greater than 40.0, then the wages are calculated by the statement in Line 5, which includes overtime payment. Otherwise, the wages are calculated by the statement in Line 7. The statement in Line 9 outputs the wages.

Let us now consider another example of an `if` statement and examine some of the semantic errors that can occur.

#### EXAMPLE 4-14

Consider the following statements:

```
if (score >= 60) //Line 1
 cout << "Passing" << endl; //Line 2
 cout << "Failing" << endl; //Line 3
```

If the expression `(score >= 60)` evaluates to `false`, the output statement in Line 2 does not execute. So the output would be `Failing`. That is, this set of statements performs the same action as an `if...else` statement. It will execute the output statement in Line 3 rather than the output statement in Line 2. For example, if the value of `score` is 50, these statements will output the following line:

`Failing`

However, if the expression `(score >= 60)` evaluates to `true`, the program will execute both of the output statements, giving a very unsatisfactory result. For example, if the value of `score` is 70, these statements will output the following lines:

`Passing`  
`Failing`

The `if` statement controls the execution of only the statement in Line 2. The statement in Line 3 always executes.

The correct code to print `Passing` or `Failing`, depending on the value of `score`, is:

```
if (score >= 60)
 cout << "Passing" << endl;
else
 cout << "Failing" << endl;
```

## Compound (Block of) Statements

The `if` and `if...else` structures control only one statement at a time. Suppose, however, that you want to execute more than one statement if the **expression** in an `if` or `if...else` statement evaluates to `true`. To permit more complex statements, C++ provides a structure called a **compound statement** or a **block of statements**. A compound statement takes the following form:

```
{
 statement_1
 statement_2
 .
 .
 .
 statement_n
}
```

That is, a compound statement consists of a sequence of statements enclosed in curly braces, { and }. In an `if` or `if...else` structure, a compound statement functions as if it was a single statement. Thus, instead of having a simple two-way selection similar to the following code:

```
if (age >= 18)
 cout << "Eligible to vote." << endl;
else
 cout << "Not eligible to vote." << endl;
```

you could include compound statements, similar to the following code:

```
if (age >= 18)
{
 cout << "Eligible to vote." << endl;
 cout << "No longer a minor." << endl;
}
else
{
 cout << "Not eligible to vote." << endl;
 cout << "Still a minor." << endl;
}
```

The compound statement is very useful and will be used in most of the structured statements in this chapter.

## Multiple Selections: Nested `if`

In the previous sections, you learned how to implement one-way and two-way selections in a program. Some problems require the implementation of more than two alternatives. For example, suppose that if the checking account balance is more than \$50,000, the interest rate is 7%; if the balance is between \$25,000 and \$49,999.99, the interest rate is 5%; if the balance is between \$1,000 and \$24,999.99, the interest rate is 3%; otherwise,

the interest rate is 0%. This particular problem has four alternatives—that is, multiple selection paths. You can include multiple selection paths in a program by using an **if...else** structure if the action statement itself is an **if** or **if...else** statement. When one control statement is located within another, it is said to be **nested**.

Example 4-15 illustrates how to incorporate multiple selections using a nested **if...else** structure.

### EXAMPLE 4-15

Suppose that **balance** and **interestRate** are variables of type **double**. The following statements determine the **interestRate** depending on the value of the **balance**.

```
if (balance > 50000.00) //Line 1
 interestRate = 0.07; //Line 2
else //Line 3
 if (balance >= 25000.00) //Line 4
 interestRate = 0.05; //Line 5
 else //Line 6
 if (balance >= 1000.00) //Line 7
 interestRate = 0.03; //Line 8
 else //Line 9
 interestRate = 0.00; //Line 10
```

A nested **if...else** structure demands the answer to an important question: How do you know which **else** is paired with which **if**? Recall that in C++, there is no stand-alone **else** statement. Every **else** must be paired with an **if**. The rule to pair an **else** with an **if** is as follows:

**Pairing an **else** with an **if**:** In a nested **if** statement, C++ associates an **else** with the most recent incomplete **if**—that is, the most recent **if** that has not been paired with an **else**.

Using this rule, in Example 4-15, the **else** in Line 3 is paired with the **if** in Line 1. The **else** in Line 6 is paired with the **if** in Line 4, and the **else** in Line 9 is paired with the **if** in Line 7.

To avoid excessive indentation, the code in Example 4-15 can be rewritten as follows:

```
if (balance > 50000.00) //Line 1
 interestRate = 0.07; //Line 2
else if (balance >= 25000.00) //Line 3
 interestRate = 0.05; //Line 4
else if (balance >= 1000.00) //Line 5
 interestRate = 0.03; //Line 6
else //Line 7
 interestRate = 0.00; //Line 8
```

The following examples will help you to see the various ways in which you can use nested **if** structures to implement multiple selection.

**EXAMPLE 4-16**

Assume that **score** is a variable of type **int**. Based on the value of **score**, the following code outputs the grade.

```
if (score >= 90)
 cout << "The grade is A." << endl;
else if (score >= 80)
 cout << "The grade is B." << endl;
else if (score >= 70)
 cout << "The grade is C." << endl;
else if (score >= 60)
 cout << "The grade is D." << endl;
else
 cout << "The grade is F." << endl;
```

**4****EXAMPLE 4-17**

Assume that all variables are properly declared, and consider the following statements:

```
if (temperature >= 50) //Line 1
 if (temperature >= 80) //Line 2
 cout << "Good day for swimming." << endl; //Line 3
 else //Line 4
 cout << "Good day for golfing." << endl; //Line 5
else //Line 6
 cout << "Good day to play tennis." << endl; //Line 7
```

In this C++ code, the **else** in Line 4 is paired with the **if** in Line 2, and the **else** in Line 6 is paired with the **if** in Line 1. Note that the **else** in Line 4 cannot be paired with the **if** in Line 1. If you pair the **else** in Line 4 with the **if** in Line 1, the **if** in Line 2 becomes the action statement part of the **if** in Line 1, leaving the **else** in Line 6 dangling. Also, the statements in Lines 2 through 5 form the statement part of the **if** in Line 1. The indentation does not determine the pairing, but should be used to communicate the pairing.

**EXAMPLE 4-18**

Assume that all variables are properly declared, and consider the following statements:

```
if (temperature >= 70) //Line 1
 if (temperature >= 80) //Line 2
 cout << "Good day for swimming." << endl; //Line 3
 else //Line 4
 cout << "Good day for golfing." << endl; //Line 5
```

In this code, the **else** in Line 4 is paired with the **if** in Line 2. Note that for the **else** in Line 4, the most recent incomplete **if** is in Line 2. In this code, the **if** in Line 1 has no **else** and is a one-way selection. Once again, the indentation does not determine the pairing, but it communicates the pairing.

### EXAMPLE 4-19

Assume that all variables are properly declared, and consider the following statements:

```

if (gender == 'M') //Line 1
 if (age < 21) //Line 2
 policyRate = 0.05; //Line 3
 else //Line 4
 policyRate = 0.035; //Line 5
else if (gender == 'F') //Line 6
 if (age < 21) //Line 7
 policyRate = 0.04; //Line 8
 else //Line 9
 policyRate = 0.03; //Line 10

```

In this code, the **else** in Line 4 is paired with the **if** in Line 2. Note that for the **else** in Line 4, the most recent incomplete **if** is the **if** in Line 2. The **else** in Line 6 is paired with the **if** in Line 1. The **else** in Line 9 is paired with the **if** in Line 7. Once again, the indentation does not determine the pairing, but it communicates the pairing.

## Comparing **if...else** Statements with a Series of **if** Statements

Consider the following C++ program segments, all of which accomplish the same task.

```

a. if (month == 1) //Line 1
 cout << "January" << endl; //Line 2
 else if (month == 2) //Line 3
 cout << "February" << endl; //Line 4
 else if (month == 3) //Line 5
 cout << "March" << endl; //Line 6
 else if (month == 4) //Line 7
 cout << "April" << endl; //Line 8
 else if (month == 5) //Line 9
 cout << "May" << endl; //Line 10
 else if (month == 6) //Line 11
 cout << "June" << endl; //Line 12

b. if (month == 1)
 cout << "January" << endl;
 if (month == 2)
 cout << "February" << endl;
 if (month == 3)
 cout << "March" << endl;

```

```

if (month == 4)
 cout << "April" << endl;
if (month == 5)
 cout << "May" << endl;
if (month == 6)
 cout << "June" << endl;

```

Program segment (a) is written as a sequence of **if...else** statements; program segment (b) is written as a series of **if** statements. Both program segments accomplish the same thing. If **month** is 3, then both program segments output **March**. If **month** is 1, then in program segment (a), the expression in the **if** statement in Line 1 evaluates to **true**. The statement (in Line 2) associated with this **if** then executes; the rest of the structure, which is the **else** of this **if** statement, is skipped; and the remaining **if** statements are not evaluated. In program segment (b), the computer has to evaluate the expression in each **if** statement because there is no **else** statement. As a consequence, program segment (b) executes more slowly than does program segment (a).

## Short-Circuit Evaluation

Logical expressions in C++ are evaluated using a highly efficient algorithm. This algorithm is illustrated with the help of the following statements:

```

(x > y) || (x == 5) //Line 1
(a == b) && (x >= 7) //Line 2

```

In the statement in Line 1, the two operands of the operator **||** are the expressions **(x > y)** and **(x == 5)**. This expression evaluates to **true** if either the operand **(x > y)** is **true** or the operand **(x == 5)** is **true**. With short-circuit evaluation, the computer evaluates the logical expression from left to right. As soon as the value of the entire logical expression is known, the evaluation stops. For example, in statement 1, if the operand **(x > y)** evaluates to **true**, then the entire expression evaluates to **true** because **true || true** is **true** and **true || false** is **true**. Therefore, the value of the operand **(x == 5)** has no bearing on the final outcome.

Similarly, in the statement in Line 2, the two operands of the operator **&&** are **(a == b)** and **(x >= 7)**. If the operand **(a == b)** evaluates to **false**, then the entire expression evaluates to **false** because **false && true** is **false** and **false && false** is **false**.

**Short-circuit evaluation** (of a logical expression): A process in which the computer evaluates a logical expression from left to right and stops as soon as the value of the expression is known.

### EXAMPLE 4-20

Consider the following expressions:

```

(age >= 21) || (x == 5) //Line 1
(grade == 'A') && (x >= 7) //Line 2

```

For the expression in Line 1, suppose that the value of `age` is 25. Because  $(25 \geq 21)$  is `true` and the logical operator used in the expression is `||`, the expression evaluates to `true`. Due to short-circuit evaluation, the computer does not evaluate the expression  $(x == 5)$ . Similarly, for the expression in Line 2, suppose that the value of `grade` is 'B'. Because  $('B' == 'A')$  is `false` and the logical operator used in the expression is `&&`, the expression evaluates to `false`. The computer does not evaluate  $(x \geq 7)$ .

---

## Comparing Floating-Point Numbers for Equality: A Precaution

Comparison of floating-point numbers for equality may not behave as you would expect. For example, consider the following program:

```
#include <iostream>
#include <iomanip>
#include <cmath>

using namespace std;

int main()
{
 double x = 1.0;
 double y = 3.0 / 7.0 + 2.0 / 7.0 + 2.0 / 7.0;

 cout << fixed << showpoint << setprecision(17);

 cout << "3.0 / 7.0 + 2.0 / 7.0 + 2.0 / 7.0 = "
 << 3.0 / 7.0 + 2.0 / 7.0 + 2.0 / 7.0 << endl;

 cout << "x = " << x << endl;
 cout << "y = " << y << endl;

 if (x == y)
 cout << "x and y are the same." << endl;
 else
 cout << "x and y are not the same." << endl;

 if (fabs(x - y) < 0.000001)
 cout << "x and y are the same within the tolerance "
 << "0.000001." << endl;
 else
 cout << " x and y are not the same within the "
 << "tolerance 0.000001." << endl;

 return 0;
}
```

**Sample Run:**

```

3.0 / 7.0 + 2.0 / 7.0 + 2.0 / 7.0 = 0.9999999999999999
x = 1.0000000000000000
y = 0.9999999999999989
x and y are not the same.
x and y are the same within the tolerance 0.000001.

```

In this program, `x` is initialized to 1.0 and `y` is initialized to `3.0 / 7.0 + 2.0 / 7.0 + 2.0 / 7.0`. Now, due to rounding, as shown by the output, this expression evaluates to 0.9999999999999989. Therefore, the expression `(x == y)` evaluates to `false`. However, if you evaluate the expression `3.0 / 7.0 + 2.0 / 7.0 + 2.0 / 7.0` by hand using a paper and a pencil, you will get `3.0 / 7.0 + 2.0 / 7.0 + 2.0 / 7.0 = (3.0 + 2.0 + 2.0) / 7.0 = 7.0 / 7.0 = 1.0`. That is, the value of `y` should be set to 1.0.

The preceding program and its output show that you should be careful when comparing floating-point numbers for equality. One way to check whether two floating-point numbers are equal is to check whether the absolute value of their difference is less than a certain tolerance. For example, suppose the tolerance is 0.000001. Then, `x` and `y` are equal if the absolute value of `(x - y)` is less than 0.000001. To find the absolute value, you can use the function `fabs` of the header file `cmath`, as shown in the program. Therefore, the expression `fabs(x - y) < 0.000001` determines whether the absolute value of `(x - y)` is less than 0.000001.

## Associativity of Relational Operators: A Precaution

Sometimes logical expressions do not behave as you might expect, as shown by the following program, which determines if a number is between 0 and 10 (inclusive).

```

#include <iostream>

using namespace std;

int main()
{
 int num;

 cout << "Enter an integer: ";
 cin >> num;
 cout << endl;

 if (0 <= num <= 10)
 cout << num << " is within 0 and 10." << endl;
 else
 cout << num << " is not within 0 and 10." << endl;

 return 0;
}

```

**Sample Runs:** In these sample runs, the user input is shaded.

**Sample Run 1:**

Enter an integer: **5**

5 is within 0 and 10.

**Sample Run 2:**

Enter an integer: **20**

20 is within 0 and 10.

**Sample Run 3:**

Enter an integer: **-10**

-10 is within 0 and 10.

Clearly, Sample Run 1 is correct and Sample Runs 2 and 3 are incorrect. Because the **if** statement determines whether an integer is between 0 and 10, the problem is in the expression in the if statement. So, let us look at this expression, which is:

`0 <= num <= 10`

Although this statement is a legal C++ expression, you do not get the desired result. Let us evaluate this expression for certain values of **num**. Suppose that the value of **num** is 5. Then:

|                                   |                                     |                                                                                         |
|-----------------------------------|-------------------------------------|-----------------------------------------------------------------------------------------|
| <code>0 &lt;= num &lt;= 10</code> | <code>= 0 &lt;= 5 &lt;= 10</code>   |                                                                                         |
|                                   | <code>= (0 &lt;= 5) &lt;= 10</code> | (Because relational operators are evaluated from left to right)                         |
|                                   | <code>= 1 &lt;= 10</code>           | (Because <code>0 &lt;= 5</code> is <b>true</b> , <code>0 &lt;= 5</code> evaluates to 1) |
|                                   | <code>= 1   (<b>true</b>)</code>    |                                                                                         |

Now, suppose that **num** = 20. Then:

|                                   |                                      |                                                                                           |
|-----------------------------------|--------------------------------------|-------------------------------------------------------------------------------------------|
| <code>0 &lt;= num &lt;= 10</code> | <code>= 0 &lt;= 20 &lt;= 10</code>   |                                                                                           |
|                                   | <code>= (0 &lt;= 20) &lt;= 10</code> | (Because relational operators are evaluated from left to right)                           |
|                                   | <code>= 1 &lt;= 10</code>            | (Because <code>0 &lt;= 20</code> is <b>true</b> , <code>0 &lt;= 20</code> evaluates to 1) |
|                                   | <code>= 1   (<b>true</b>)</code>     |                                                                                           |

Now, you can see why the expression evaluates to **true** when **num** is 20. Similarly, if **num** is -10, the expression `0 <= num <= 10` evaluates to **true**. In fact, this expression will always evaluate to **true**, no matter what **num** is. This is due to the fact that the expression `0 <= num` evaluates to either 0 or 1, and `0 <= 10` is **true** and `1 <= 10` is **true**. So what is

wrong with the expression `0 <= num <= 10`? It is missing the logical operator `&&`. A correct way to write this expression in C++ is:

```
0 <= num && num <= 10
```

You must take care when formulating logical expressions. When creating a complex logical expression, you must use the proper logical operators.

## Avoiding Bugs by Avoiding Partially Understood Concepts and Techniques

## 4

The debugging sections in Chapters 2 and 3 illustrated how to understand and fix syntax and logic errors. In this section, we illustrate how to avoid bugs by avoiding partially understood concepts and techniques.

The programs that you have written until now should have illustrated that a small error such as omission of a semicolon at the end of a variable declaration or using a variable without properly declaring it can prevent a program from successfully compiling. Similarly, using a variable without properly initializing it can prevent a program from running correctly. Recall that the condition associated with an `if` statement must be enclosed in parentheses. Therefore, the following expression will result in a syntax error.

```
if score >= 90
```

Example 4-12 illustrates that an unintended semicolon following the condition of the following `if` statement:

```
if (hours > 40.0);
```

can prevent successful compilation or correct execution.

The approach that you take to solve a problem must use concepts and techniques correctly; otherwise, your solution will be either incorrect or deficient. If you do not understand a concept or technique completely, don't use it until your understanding is complete. The problem of using partially understood concepts and techniques can be illustrated by the following program.

Suppose that we want to write a program that analyzes students' GPA. If the GPA is greater than or equal to 3.9, the student makes the dean's honor list. If the GPA is less than 2.00, the student is sent a warning letter indicating that the GPA is below the graduation requirement. So, consider the following program:

```
//GPA program with bugs.
```

```
#include <iostream>
```

```
//Line 1
```

```
using namespace std;
```

```
//Line 2
```

```
int main()
```

```
//Line 3
```

```

{ //Line 4
 double gpa; //Line 5

 cout << "Enter the GPA: "; //Line 6
 cin >> gpa; //Line 7
 cout << endl; //Line 8

 if (gpa >= 2.0) //Line 9
 if (gpa >= 3.9) //Line 10
 cout << "Dean\'s Honor List." << endl; //Line 11
 else //Line 12
 cout << "The GPA is below the graduation "
 << "requirement. \nSee your "
 << "academic advisor." << endl; //Line 13

 return 0; //Line 14
} //Line 15

```

**Sample Runs:** In these sample runs, the user input is shaded.

**Sample Run 1:**

Enter the GPA: 3.91

Dean's Honor List.

**Sample Run 2:**

Enter the GPA: 3.8

The GPA is below the graduation requirement.  
See your academic advisor.

**Sample Run 3:**

Enter the GPA: 1.95

Let us look at these sample runs. Clearly, the output in Sample Run 1 is correct. In Sample Run 2, the input is 3.8 and the output indicates that this GPA is below the graduation requirement. However, a student with a GPA of 3.8 would graduate with some type of honor. So, the output in Sample Run 2 is incorrect. In Sample Run 3, the input is 1.95, and the output does not show any warning message. Therefore, the output in Sample Run 3 is also incorrect. It means that the `if...else` statement in Lines 9 to 13 is incorrect. Let us look at these statements, that is:

```

if (gpa >= 2.0) //Line 9
 if (gpa >= 3.9) //Line 10
 cout << "Dean\'s Honor List." << endl; //Line 11
 else //Line 12
 cout << "The GPA is below the graduation "
 << "requirement. \nSee your "
 << "academic advisor." << endl; //Line 13

```

Following the rule of pairing an `else` with an `if`, the `else` in Line 12 is paired with the `if` in Line 10. In other words, using the correct indentation, the code is:

```
if (gpa >= 2.0) //Line 9
 if (gpa >= 3.9) //Line 10
 cout << "Dean's Honor List." << endl; //Line 11
 else //Line 12
 cout << "The GPA is below the graduation "
 << "requirement. \nSee your "
 << "academic advisor." << endl; //Line 13
```

Now, we can see that the `if` statement in Line 9 is a one-way selection. Therefore, if the input number is less than 2.0, no action will take place, that is, no warning message will be printed. Now, suppose the input is 3.8. Then, the expression in Line 9 evaluates to `true`, so the expression in Line 10 is evaluated, which evaluates to `false`. This means the output statement in Line 13 executes, resulting in an unsatisfactory result.

In fact, the program should print the warning message only if the GPA is less than 2.0, and it should print the message:

Dean's Honor List.

if the GPA is greater than or equal to 3.9.

To achieve that result, the `else` in Line 12 needs to be paired with the `if` in Line 9. To pair the `else` in Line 12 with the `if` in Line 9, you need to use a compound statement, as follows:

```
if (gpa >= 2.0) //Line 9
{
 if (gpa >= 3.9) //Line 10
 cout << "Dean's Honor List." << endl; //Line 11
}
else //Line 12
 cout << "The GPA is below the graduation "
 << "requirement. \nSee your "
 << "academic advisor." << endl; //Line 13
```

The correct program is as follows:

//Correct GPA program.

```
#include <iostream> //Line 1

using namespace std; //Line 2

int main() //Line 3
{
 double gpa; //Line 4
 //Line 5

 cout << "Enter the GPA: "; //Line 6
 cin >> gpa; //Line 7
 cout << endl; //Line 8
```

```

 if (gpa >= 2.0) //Line 9
 { //Line 10
 if (gpa >= 3.9) //Line 11
 cout << "Dean\'s Honor List." << endl; //Line 12
 } //Line 13
 else //Line 14
 cout << "The GPA is below the graduation "
 << "requirement. \nSee your "
 << "academic advisor." << endl; //Line 15

 return 0; //Line 16
} //Line 17

```

**Sample Runs:** In these sample runs, the user input is shaded.

**Sample Run 1:**

Enter the GPA: 3.91

Dean's Honor List.

**Sample Run 2:**

Enter the GPA: 3.8

**Sample Run 3:**

Enter the GPA: 1.95

The GPA is below the graduation requirement.  
See your academic advisor.

In cases such as this one, the general rule is that you cannot look inside of a block (that is, inside the braces) to pair an `else` with an `if`. The `else` in Line 14 cannot be paired with the `if` in Line 11 because the `if` statement in Line 11 is enclosed within braces, and the `else` in Line 14 cannot look inside those braces. Therefore, the `else` in Line 14 is paired with the `if` in Line 9.

In this book, the C++ programming concepts and techniques are presented in a logical order. When these concepts and techniques are learned one at a time in a logical order, they are simple enough to be understood completely. Understanding a concept or technique completely before using it will save you an enormous amount of debugging time.

## Input Failure and the `if` Statement

In Chapter 3, you saw that an attempt to read invalid data causes the input stream to enter a fail state. Once an input stream enters a fail state, all subsequent input statements associated with that input stream are ignored, and the computer continues to execute the program, which produces erroneous results. You can use `if` statements to check the status of an input stream variable and, if the input stream enters the fail state, include instructions that stop program execution.

In addition to reading invalid data, other events can cause an input stream to enter the fail state. Two additional common causes of input failure are the following:

- Attempting to open an input file that does not exist
- Attempting to read beyond the end of an input file

One way to address these causes of input failure is to check the status of the input stream variable. You can check the status by using the input stream variable as the logical expression in an `if` statement. If the last input succeeded, the input stream variable evaluates to `true`; if the last input failed, it evaluates to `false`.

The statement:

```
if (cin)
 cout << "Input is OK." << endl;
```

prints:

Input is OK.

if the last input from the standard input device succeeded. Similarly, if `infile` is an `ifstream` variable, the statement:

```
if (!infile)
 cout << "Input failed." << endl;
```

prints:

Input failed.

if the last input associated with the stream variable `infile` failed.

Suppose an input stream variable tries to open a file for inputting data into a program. If the input file does not exist, you can use the value of the input stream variable, in conjunction with the `return` statement, to terminate the program.

Recall that the last statement included in the function `main` is:

```
return 0;
```

This statement returns a value of `0` to the operating system when the program terminates. A value of `0` indicates that the program terminated normally and that no error occurred during program execution. Values of type `int` other than `0` can also be returned to the operating system via the `return` statement. The return of any value other than `0`, however, indicates that something went wrong during program execution.

The `return` statement can appear anywhere in the program. Whenever a `return` statement executes, it immediately exits the function in which it appears. In the case of the function `main`, the program terminates when the `return` statement executes. You can use these properties of the `return` statement to terminate the function `main` whenever the input stream fails. This technique is especially useful when a program tries to open an input file. Consider the following statements:

```

ifstream infile;

infile.open("inputdat.dat"); //open inputdat.dat

if (!infile)
{
 cout << "Cannot open the input file. "
 << "The program terminates." << endl;
 return 1;
}

```

Suppose that the file `inputdat.dat` does not exist. The operation to open this file fails, causing the input stream to enter the fail state. As a logical expression, the file stream variable `infile` then evaluates to `false`. Because `infile` evaluates to `false`, the expression `!infile` (in the `if` statement) evaluates to `true`, and the body of the `if` statement executes. The message:

Cannot open the input file. The program terminates.

is printed on the screen, and the `return` statement terminates the program by returning a value of 1 to the operating system.

Let's now use the code that responds to input failure by including these features in the Programming Example: Student Grade from Chapter 3. Recall that this program calculates the average test score based on data from an input file and then outputs the results to another file. The following programming code is the same as the code from Chapter 3, except that it includes statements to exit the program if the input file does not exist.

```

//Program to calculate the average test score.

#include <iostream>
#include <fstream>
#include <iomanip>
#include <string>
using namespace std;

int main()
{
 ifstream inFile; //input file stream variable
 ofstream outFile; //output file stream variable

 double test1, test2, test3, test4, test5;
 double average;

 string firstName;
 string lastName;

 inFile.open("test.txt"); //open the input file

 if (!inFile)

```

```

{
 cout << "Cannot open the input file. "
 << "The program terminates." << endl;
 return 1;
}

outFile.open("testavg.out"); //open the output file

outFile << fixed << showpoint;
outFile << setprecision(2);

cout << "Processing data" << endl;

inFile >> firstName >> lastName;
outFile << "Student name: " << firstName
 << " " << lastName << endl;

inFile >> test1 >> test2 >> test3
 >> test4 >> test5;
outFile << "Test scores: " << setw(4) << test1
 << setw(4) << test2 << setw(4) << test3
 << setw(4) << test4 << setw(4) << test5
 << endl;

average = (test1 + test2 + test3 + test4 + test5) / 5.0;

outFile << "Average test score: " << setw(6)
 << average << endl;

inFile.close();
outFile.close();

return 0;
}

```

## Confusion between the Equality Operator (==) and the Assignment Operator (=)

Recall that if the decision-making expression in the **if** statement evaluates to **true**, the **statement** part of the **if** statement executes. In addition, the **expression** is usually a logical expression. However, C++ allows you to use *any* expression that can be evaluated to either **true** or **false** as an **expression** in the **if** statement. Consider the following statement:

```

if (x = 5)
 cout << "The value is five." << endl;

```

The **expression**—that is, the decision maker—in the **if** statement is **x = 5**. The expression **x = 5** is called an assignment expression because the operator **=** appears in the expression and there is no semicolon at the end.

This expression is evaluated as follows. First, the right side of the operator **=** is evaluated, which evaluates to 5. The value 5 is then assigned to **x**. Moreover, the value 5—that is, the

new value of **x**—also becomes the value of the expression in the **if** statement—that is, the value of the assignment expression. Because 5 is nonzero, the expression in the **if** statement evaluates to **true**, so the statement part of the **if** statement outputs: **The value is five.**

No matter how experienced a programmer is, almost everyone makes the mistake of using **=** in place of **==** at one time or another. One reason why these two operators are often confused is that most programming languages use **=** as an equality operator. Thus, experience with other programming languages can create confusion. Sometimes the error is merely typographical, another reason to be careful when typing code.

Despite the fact that an assignment expression can be used as an expression, using the assignment operator in place of the equality operator can cause serious problems in a program. For example, suppose that the discount on a car insurance policy is based on the insured's driving record. A driving record of 1 means that the driver is accident-free and receives a 25% discount on the policy. The statement:

```
if (drivingCode == 1)
 cout << "The discount on the policy is 25%." << endl;
```

outputs:

**The discount on the policy is 25%.**

only if the value of **drivingCode** is 1. However, the statement:

```
if (drivingCode = 1)
 cout << "The discount on the policy is 25%." << endl;
```

always outputs:

**The discount on the policy is 25%.**

because the right side of the assignment expression evaluates to 1, which is nonzero and so evaluates to **true**. Therefore, the expression in the **if** statement evaluates to **true**, outputting the following line of text: **The discount on the policy is 25%.** Also, the value 1 is assigned to the variable **drivingCode**. Suppose that before the **if** statement executes, the value of the variable **drivingCode** is 4. After the **if** statement executes, not only is the output wrong, but the new value also replaces the old driving code.

The appearance of **=** in place of **==** resembles a *silent killer*. It is not a syntax error, so the compiler does not warn you of an error. Rather, it is a logical error.

#### NOTE

Using **=** in place of **==** can cause serious problems, especially if it happens in a looping statement. Chapter 5 discusses looping structures.

The appearance of the equality operator in place of the assignment operator can also cause errors in a program. For example, suppose **x**, **y**, and **z** are **int** variables. The statement:

```
x = y + z;
```

assigns the value of the expression `y + z` to `x`. The statement:

```
x == y + z;
```

compares the value of the expression `y + z` with the value of `x`; the value of `x` remains the same, however. If somewhere else in the program you are counting on the value of `x` being `y + z`, a logic error will occur, the program output will be incorrect, and you will receive no warning of this situation from the compiler. The compiler provides feedback only about syntax errors, not logic errors. For this reason, you must use extra care when working with the equality operator and the assignment operator.

## Conditional Operator (`?:`)

### NOTE

The reader can skip this section without any discontinuation.

Certain `if...else` statements can be written in a more concise way by using C++'s conditional operator. The **conditional operator**, written as `?:`, is a **ternary operator**, which means that it takes three arguments. The syntax for using the conditional operator is:

```
expression1 ? expression2 : expression3
```

This type of statement is called a **conditional expression**. The conditional expression is evaluated as follows: If `expression1` evaluates to a nonzero integer (that is, to `true`), the result of the conditional expression is `expression2`. Otherwise, the result of the conditional expression is `expression3`.

Consider the following statements:

```
if (a >= b)
 max = a;
else
 max = b;
```

You can use the conditional operator to simplify the writing of this `if...else` statement as follows:

```
max = (a >= b) ? a : b;
```

## Program Style and Form (Revisited): Indentation

In the section “Program Style and Form” of Chapter 2, we specified some guidelines to write programs. Now that we have started discussing control structures, in this section, we give some general guidelines to properly indent your program.

As you write programs, typos and errors are unavoidable. If your program is properly indented, you can spot and fix errors quickly, as shown by several examples in this

chapter. Typically, the IDE that you use will automatically indent your program. If for some reason your IDE does not indent your program, you can indent your program yourself.

Proper indentation can show the natural grouping of statements. You should insert a blank line between statements that are naturally separate. In this book, the statements inside braces, the statements of a selection structure, and an `if` statement within an `if` statement are all indented four spaces to the right. Throughout the book, we use four spaces to indent statements, especially to show the levels of control structures within other control structures. You can also use four spaces for indentation.

There are two commonly used styles for placing braces. In this book, we place braces on a line by themselves. Also, matching left and right braces are in the same column, that is, they are the same number of spaces away from the left side of the program. This style of placing braces easily shows the grouping of the statements and also matches left and right braces. You can also follow this style to place and indent braces.

In the second style of placing braces, the left brace need not be on a line by itself. Typically, for control structures, the left brace is placed after the last right parenthesis of the (logical) expression, and the right brace is on a line by itself. This style might save some space. However, sometimes this style might not immediately show the grouping or the block of the statements.

No matter what style of indentation you use, you should be consistent within your programs, and the indentation should show the structure of the program.

## Using Pseudocode to Develop, Test, and Debug a Program

---

There are several ways to develop a program. One method involves using an informal mixture of C++ and ordinary language, called **pseudocode** or just **pseudo**. Sometimes pseudo provides a useful means to outline and refine a program before putting it into formal C++ code. When you are constructing programs that involve complex nested control structures, pseudo can help you quickly develop the correct structure of the program and avoid making common errors.

One useful program segment determines the larger of two integers. If `x` and `y` are integers, using pseudo, you can quickly write the following:

- a.   `if (x > y) then`  
      `x is larger`
- b.   `if (y > x) then`  
      `y is larger`

If the statement in (a) is **true**, then **x** is larger. If the statement in (b) is **true**, then **y** is larger. However, for this code to work in concert to determine the larger of two integers, the computer needs to evaluate both expressions:

**(x > y)      and      (y > x)**

even if the first statement is **true**. Evaluating both expressions is a waste of computer time.

Let's rewrite this pseudo as follows:

```
if (x > y) then
 x is larger
else
 y is larger
```

Here, only one condition needs to be evaluated. This code looks okay, so let's put it into C++.

```
#include <iostream>

using namespace std;

int main()
{
 if (x > y)
```

Wait...once you begin translating the pseudo into a C++ program, you should immediately notice that there is no place to store the value of **x** or **y**. The variables were not declared, which is a very common oversight, especially for new programmers. If you examine the pseudo, you will see that the program needs three variables, and you might as well make them self-documenting. Let's start the program code again:

```
#include <iostream>

using namespace std;

int main()
{
 int num1, num2, larger; //Line 1

 if (num1 > num2); //Line 2; error
 larger = num1; //Line 3
 else //Line 4
 larger = num2; //Line 5

 return 0;
}
```

Compiling this program will result in the identification of a common syntax error (in Line 2). Recall that a semicolon cannot appear after the **expression** in the

`if...else` statement. However, even if you corrected this syntax error, the program still would not give satisfactory results because it tries to use identifiers that have no values. The variables have not been initialized, which is another common error. In addition, because there are no output statements, you would not be able to see the results of the program.

Because there are so many mistakes in the program, you should try a walk-through to see whether it works at all. You should always use a wide range of values in a walk-through to evaluate the program under as many different circumstances as possible. For example, does this program work if one number is zero, if one number is negative and the other number is positive, if both numbers are negative, or if both numbers are the same? Examining the program, you can see that it does not check whether the two numbers are equal. Taking all of these points into account, you can rewrite the program as follows:

```
//Program: Compare Numbers
//This program compares two integers and outputs the largest.

#include <iostream>

using namespace std;

int main()

 int num1, num2;

 cout << "Enter any two integers: ";
 cin >> num1 >> num2;
 cout << endl;

 cout << "The two integers entered are " << num1
 << " and " << num2 << endl;

 if (num1 > num2)
 cout << "The larger number is " << num1 << endl;
 else if (num2 > num1)
 cout << "The larger number is " << num2 << endl;
 else
 cout << "Both numbers are equal." << endl;

 return 0;
}
```

**Sample Run:** In this sample run, the user input is shaded.

```
Enter any two integers: 78 90
The two integers entered are 78 and 90
The larger number is 90
```

One thing you can learn from the preceding program is that you must first develop a program using paper and pencil. Although a program that is first written on a piece of

paper is not guaranteed to run successfully on the first try, this step is still a good starting point. On paper, it is easier to spot errors and improve the program, especially with large programs.

## switch Structures


Recall that there are two selection, or branch, structures in C++. The first selection structure, which is implemented with `if` and `if...else` statements, usually requires the evaluation of a (logical) expression. The second selection structure, which does not require the evaluation of a logical expression, is called the **switch structure**. C++'s `switch` structure gives the computer the power to choose from among many alternatives.

A general syntax of the `switch` statement is:

```
switch (expression)
{
 case value1:
 statements1
 break;
 case value2:
 statements2
 break;
 .
 .
 .
 case valuen:
 statementsn
 break;
 default:
 statements
}
```

In C++, `switch`, `case`, `break`, and `default` are reserved words. In a `switch` structure, first the **expression** is evaluated. The value of the **expression** is then used to perform the actions specified in the statements that follow the reserved word `case`. Recall that in a syntax, shading indicates an optional part of the definition.

Although it need not be, the **expression** is usually an identifier. Whether it is an identifier or an expression, the value can be only integral. The **expression** is sometimes called the **selector**. Its value determines which statement is selected for execution. A particular `case` value should appear only once. One or more statements may follow a `case` label, so you do not need to use braces to turn multiple statements into a single compound statement. The `break` statement may or may not appear after each statement. Figure 4-4 shows the flow of execution of the `switch` statement.

FIGURE 4-4 `switch` statement

The `switch` statement executes according to the following rules:

1. When the value of the `expression` is matched against a `case` value (also called a label), the statements execute until either a `break` statement is found or the end of the `switch` structure is reached.
2. If the value of the `expression` does not match any of the `case` values, the statements following the `default` label execute. If the `switch` structure has no `default` label and if the value of the `expression` does not match any of the `case` values, the entire `switch` statement is skipped.
3. A `break` statement causes an immediate *exit* from the `switch` structure.

**EXAMPLE 4-21**

Consider the following statements, in which `grade` is a variable of type `char`.

```
switch (grade)
{
case 'A':
 cout << "The grade point is 4.0.";
 break;
case 'B':
 cout << "The grade point is 3.0.";
 break;
case 'C':
 cout << "The grade point is 2.0.";
 break;
case 'D':
 cout << "The grade point is 1.0.";
 break;
case 'F':
 cout << "The grade point is 0.0.";
 break;
default:
 cout << "The grade is invalid.";
}
```

In this example, the expression in the `switch` statement is a variable identifier. The variable `grade` is of type `char`, which is an integral type. The possible values of `grade` are 'A', 'B', 'C', 'D', and 'F'. Each `case` label specifies a different action to take, depending on the value of `grade`. If the value of `grade` is 'A', the output is:

The grade point is 4.0.

**EXAMPLE 4-22**

The following program illustrates the effect of the `break` statement. It asks the user to input a number between 0 and 10.

*//Program: Effect of break statements in a switch structure*

```
#include <iostream>

using namespace std;

int main()
{
 int num;

 cout << "Enter an integer between 0 and 7: "; //Line 1
 cin >> num; //Line 2
 cout << endl; //Line 3
```

```

 cout << "The number you entered is " << num
 << endl; //Line 4

 switch(num) //Line 5
 {
 case 0: //Line 6
 case 1: //Line 7
 cout << "Learning to use "; //Line 8
 case 2: //Line 9
 cout << "C++'s "; //Line 10
 case 3: //Line 11
 cout << "switch structure." << endl; //Line 12
 break; //Line 13
 case 4: //Line 14
 break; //Line 15
 case 5: //Line 16
 cout << "This program shows the effect "; //Line 17
 case 6: //Line 18
 case 7: //Line 19
 cout << "of the break statement." << endl; //Line 20
 break; //Line 21
 default: //Line 22
 cout << "The number is out of range." << endl; //Line 23
 }

 cout << "Out of the switch structure." << endl; //Line 24

 return 0; //Line 25
}

```

**Sample Runs:** These outputs were obtained by executing the preceding program several times. In each of these sample runs, the user input is shaded.

#### Sample Run 1:

```

Enter an integer between 0 and 7: 0
The number you entered is 0
Learning to use C++'s switch structure.
Out of the switch structure.

```

#### Sample Run 2:

```

Enter an integer between 0 and 7: 2
The number you entered is 2
C++'s switch structure.
Out of the switch structure.

```

#### Sample Run 3:

```

Enter an integer between 0 and 7: 4
The number you entered is 4
Out of the switch structure.

```

**Sample Run 4:**

Enter an integer between 0 and 7: **5**

The number you entered is 5

This program shows the effect of the break statement.

Out of the switch structure.

**Sample Run 5:**

Enter an integer between 0 and 7: **7**

The number you entered is 7

of the break statement.

Out of the switch structure.

**Sample Run 6:**

Enter an integer between 0 and 7: **8**

The number you entered is 8

The number is out of range.

Out of the switch structure.

A walk-through of this program, using certain values of the **switch** expression **num**, can help you understand how the **break** statement functions. If the value of **num** is 0, the value of the **switch** expression matches the **case** value 0. All statements following **case 0**: execute until a **break** statement appears.

The first **break** statement appears in Line 13, just before the **case** value of 4. Even though the value of the **switch** expression does not match any of the **case** values (that is, 1, 2, or 3), the statements following these values execute.

When the value of the **switch** expression matches a **case** value, *all* statements execute until a **break** is encountered, and the program skips all **case** labels in between. Similarly, if the value of **num** is 3, it matches the **case** value of 3, and the statements following this label execute until the **break** statement is encountered in Line 13. If the value of **num** is 4, it matches the **case** value of 4. In this situation, the action is empty because only the **break** statement, in Line 15, follows the **case** value of 4.

**EXAMPLE 4-23**

Although a **switch** structure's **case** values (labels) are limited, the **switch** statement expression can be as complex as necessary. For example, consider the following **switch** statement:

```
switch (score / 10)
{
case 0:
case 1:
case 2:
case 3:
```

```

case 4:
case 5:
 grade = 'F';
 break;
case 6:
 grade = 'D';
 break;
case 7:
 grade = 'C';
 break;
case 8:
 grade = 'B';
 break;
case 9:
case 10:
 grade = 'A';
 break;
default:
 cout << "Invalid test score." << endl;
}

```

Assume that `score` is an `int` variable with values between 0 and 100. If `score` is 75, `score / 10 = 75 / 10 = 7`, and the grade assigned is 'C'. If the value of `score` is between 0 and 59, the grade is 'F'. If `score` is between 0 and 59, then `score / 10` is 0, 1, 2, 3, 4, or 5. Each of these values corresponds to the grade 'F'.

Therefore, in this `switch` structure, the action statements of `case 0`, `case 1`, `case 2`, `case 3`, `case 4`, and `case 5` are all the same. Rather than write the statement `grade = 'F'`; followed by the `break` statement for each of the `case` values of 0, 1, 2, 3, 4, and 5, you can simplify the programming code by first specifying all of the case values (as shown in the preceding code) and then specifying the desired action statement. The `case` values of 9 and 10 follow similar conventions.

---

In addition to being a variable identifier or a complex expression, the `switch` expression can evaluate to a logical value. Consider the following statements:

```

switch (age >= 18)
{
case 1:
 cout << "Old enough to be drafted." << endl;
 cout << "Old enough to vote." << endl;
 break;
case 0:
 cout << "Not old enough to be drafted." << endl;
 cout << "Not old enough to vote." << endl;
}

```

If the value of `age` is 25, the expression `age >= 18` evaluates to 1—that is, `true`. If the `expression` evaluates to 1, the statements following the `case` label 1 execute. If the value of `age` is 14, the expression `age >= 18` evaluates to 0—that is, `false`—and the statements following the `case` label 0 execute.

You can use `true` and `false`, instead of 1 and 0, respectively, in the case labels, and rewrite the preceding `switch` statement as follows:

```
switch (age >= 18)
{
case true:
 cout << "Old enough to be drafted." << endl;
 cout << "Old enough to vote." << endl;
 break;
case false:
 cout << "Not old enough to be drafted." << endl;
 cout << "Not old enough to vote." << endl;
}
```

As you can see from the preceding examples, the `switch` statement is an elegant way to implement multiple selections. You will see the use of a `switch` statement in the programming example at the end of this chapter. Even though no fixed rules exist that can be applied to decide whether to use an `if...else` structure or a `switch` structure to implement multiple selections, the following considerations should be remembered. If multiple selections involve a range of values, you should use either an `if...else` structure or a `switch` structure, wherein you convert each range to a finite set of values.

For instance, in Example 4-23, the value of `grade` depends on the value of `score`. If `score` is between 0 and 59, `grade` is 'F'. Because `score` is an `int` variable, 60 values correspond to the grade of 'F'. If you list all 60 values as `case` values, the `switch` statement could be very long. However, dividing by 10 reduces these 60 values to only 6 values: 0, 1, 2, 3, 4, and 5.

If the range of values consists of infinitely many values and you cannot reduce them to a set containing a finite number of values, you must use the `if...else` structure. For example, if `score` happens to be a `double` variable, the number of values between 0 and 60 is infinite. However, you can use the expression `static_cast<int>(score) / 10` and still reduce this infinite number of values to just six values.

## Avoiding Bugs by Avoiding Partially Understood Concepts and Techniques (Revisited)

Earlier in this chapter, we discussed how a partial understanding of a concept or technique can lead to errors in a program. In this section, we give another example to illustrate the problem of using partially understood concepts and techniques. In Example 4-23, we illustrate how to assign a grade based on a test score between 0 and 100. Next, consider the following program that assigns a grade based on a test score.

```
//Grade program with bugs.

#include <iostream> //Line 1

using namespace std; //Line 2
```

```

int main() //Line 3
{ //Line 4
 int testScore; //Line 5

 cout << "Enter the test score: "; //Line 6
 cin >> testScore; //Line 7
 cout << endl; //Line 8

 switch (testScore / 10) //Line 9
 { //Line 10
 case 0: //Line 11
 case 1: //Line 12
 case 2: //Line 13
 case 3: //Line 14
 case 4: //Line 15
 case 5: //Line 16
 cout << "The grade is F." << endl; //Line 17
 case 6: //Line 18
 cout << "The grade is D." << endl; //Line 19
 case 7: //Line 20
 cout << "The grade is C." << endl; //Line 21
 case 8: //Line 22
 cout << "The grade is B." << endl; //Line 23
 case 9: //Line 24
 case 10: //Line 25
 cout << "The grade is A." << endl; //Line 26
 default: //Line 27
 cout << "Invalid test score." << endl; //Line 28
 } //Line 29

 return 0; //Line 30
} //Line 31

```

**Sample Runs:** In these sample runs, the user input is shaded.

**Sample Run 1:**

Enter the test score: 110

Invalid test score.

**Sample Run 2:**

Enter the test score: -70

Invalid test score.

**Sample Run 3:**

Enter the test score: 75

The grade is C.  
 The grade is B.  
 The grade is A.  
 Invalid test score.

From these sample runs, it follows that if the value of `testScore` is less than 0 or greater than 100, the program produces correct results, but if the value of `testScore` is between 0 and 100, say 75, the program produces incorrect results. Can you see why?

As in Sample Run 3, suppose that the value of `testScore` is 75. Then, `testScore % 10 = 7`, and this value matched the `case` label 7. So, as we indented, it should print **The grade is C.** However, the output is:

```
The grade is C.
The grade is B.
The grade is A.
Invalid test score.
```

But why? Clearly only at most one `cout` statement is associated with each `case` label. The problem is a result of having only a partial understanding of how the `switch` structure works. As we can see, the `switch` statement does not include any `break` statement. Therefore, after executing the statement(s) associated with the matching case label, execution continues with the statement(s) associated with the next case label, resulting in the printing of four unintended lines.

To output results correctly, the `switch` structure must include a `break` statement after each `cout` statement, except the last `cout` statement. We leave it as an exercise for you to modify this program so that it outputs correct results.

Once again, we can see that a partially understood concept can lead to serious errors in a program. Therefore, taking time to understand each concept and technique completely will save you hours of debugging time.

## Terminating a Program with the `assert` Function

Certain types of errors that are very difficult to catch can occur in a program. For example, division by zero can be difficult to catch using any of the programming techniques you have examined so far. C++ includes a predefined function, `assert`, that is useful in stopping program execution when certain elusive errors occur. In the case of division by zero, you can use the `assert` function to ensure that a program terminates with an appropriate error message indicating the type of error and the program location where the error occurred.

Consider the following statements:

```
int numerator;
int denominator;
int quotient;
double hours;
double rate;
double wages;
char ch;
```

1. `quotient = numerator / denominator;`
2. `if (hours > 0 && (0 < rate && rate <= 15.50))  
    wages = rate * hours;`
3. `if ('A' <= ch && ch <= 'Z')`

In the first statement, if the `denominator` is 0, logically you should not perform the division. During execution, however, the computer would try to perform the division. If the `denominator` is 0, the program would terminate with an error message stating that an illegal operation has occurred.

The second statement is designed to compute `wages` only if `hours` is greater than 0 and `rate` is positive and less than or equal to 15.50. The third statement is designed to execute certain statements only if `ch` is an uppercase letter.

For all of these statements (for that matter, in any situation in which certain conditions must be met), if conditions are not met, it would be useful to halt program execution with a message indicating where in the program an error occurred. You could handle these types of situations by including output and return statements in your program. However, C++ provides an effective method to halt a program if required conditions are not met through the `assert` function.

The syntax to use the `assert` function is:

```
assert(expression);
```

Here, `expression` is any logical expression. If `expression` evaluates to `true`, the next statement executes. If `expression` evaluates to `false`, the program terminates and indicates where in the program the error occurred.

The specification of the `assert` function is found in the header file `cassert`. Therefore, for a program to use the `assert` function, it must include the following statement:

```
#include <cassert>
```

A statement using the `assert` function is sometimes called an `assert` statement.

Returning to the preceding statements, you can rewrite statement 1 (`quotient = numerator / denominator;`) using the `assert` function. Because `quotient` should be calculated only if `denominator` is nonzero, you include an `assert` statement before the assignment statement as follows:

```
assert(denominator);
quotient = numerator / denominator;
```

Now, if `denominator` is 0, the `assert` statement halts the execution of the program with an error message similar to the following:

```
Assertion failed: denominator, file c:\temp\assert
function\assertfunction.cpp, line 20
```

This error message indicates that the assertion of `denominator` failed. The error message also gives the name of the file containing the source code and the line number where the assertion failed.

You can also rewrite statement 2 using an assertion statement as follows:

```
assert(hours > 0 && (0 < rate && rate <= 15.50));
if (hours > 0 && (0 < rate && rate <= 15.50))
 wages = rate * hours;
```

If the **expression** in the **assert** statement fails, the program terminates with an error message similar to the following:

```
Assertion failed: hours > 0 && (0 < rate && rate <= 15.50), file
c:\temp\assertfunction\assertfunction.cpp, line 26
```

During program development and testing, the **assert** statement is very useful for enforcing programming constraints. As you can see, the **assert** statement not only halts the program, but also identifies the expression where the assertion failed, the name of the file containing the source code, and the line number where the assertion failed.

Although **assert** statements are useful during program development, after a program has been developed and put into use, if an **assert** statement fails for some reason, an end user would have no idea what the error means. Therefore, after you have developed and tested a program, you might want to remove or disable the **assert** statements. In a very large program, it could be tedious, and perhaps impossible, to remove all of the **assert** statements that you used during development. In addition, if you plan to modify a program in the future, you might like to keep the **assert** statements. Therefore, the logical choice is to keep these statements but to disable them. You can disable **assert** statements by using the following preprocessor directive:

```
#define NDEBUG
```

This preprocessor directive **#define NDEBUG** must be placed *before* the directive **#include <cassert>**.

## PROGRAMMING EXAMPLE: Cable Company Billing

This programming example demonstrates a program that calculates a customer's bill for a local cable company. There are two types of customers: residential and business. There are two rates for calculating a cable bill: one for residential customers and one for business customers. For residential customers, the following rates apply:

- Bill processing fee: \$4.50
- Basic service fee: \$20.50
- Premium channels: \$7.50 per channel.

For business customers, the following rates apply:

- Bill processing fee: \$15.00
- Basic service fee: \$75.00 for first 10 connections, \$5.00 for each additional connection
- Premium channels: \$50.00 per channel for any number of connections

The program should ask the user for an account number (an integer) and a customer code. Assume that **R** or **r** stands for a residential customer, and **B** or **b** stands for a business customer

**Input**      The customer's account number, customer code, number of premium channels to which the user subscribes, and, in the case of business customers, number of basic service connections.

**Output**     Customer's account number and the billing amount.

#### PROBLEM ANALYSIS AND ALGORITHM DESIGN

The purpose of this program is to calculate and print the billing amount. To calculate the billing amount, you need to know the customer for whom the billing amount is calculated (whether the customer is residential or business) and the number of premium channels to which the customer subscribes. In the case of a business customer, you also need to know the number of basic service connections and the number of premium channels. Other data needed to calculate the bill, such as the bill processing fees and the cost of a premium channel, are known quantities. The program should print the billing amount to two decimal places, which is standard for monetary amounts. This problem analysis translates into the following algorithm:

1. Set the precision to two decimal places.
2. Prompt the user for the account number and customer type.
3. Based on the customer type, determine the number of premium channels and basic service connections, compute the bill, and print the bill:
  - a. If the customer type is **R** or **r**,
    - i. Prompt the user for the number of premium channels.
    - ii. Compute the bill.
    - iii. Print the bill.
  - b. If the customer type is **B** or **b**,
    - i. Prompt the user for the number of basic service connections and number of premium channels.
    - ii. Compute the bill.
    - iii. Print the bill.

**Variables** Because the program will ask the user to input the customer account number, customer code, number of premium channels, and number of basic service connections, you need variables to store all of this information. Also, because the program will calculate the billing amount, you need a variable to store the billing amount. Thus, the program needs at least the following variables to compute and print the bill:

```
int accountNumber; //variable to store the customer's
 //account number
char customerType; //variable to store the customer code
int numOfPremChannels; //variable to store the number
 //of premium channels to which the
 //customer subscribes
int numOfBasicServConn; //variable to store the
 //number of basic service connections
 //to which the customer subscribes
double amountDue; //variable to store the billing amount
```

**Named Constants** As you can see, the bill processing fees, the cost of a basic service connection, and the cost of a premium channel are fixed, and these values are needed to compute the bill. Although these values are constants in the program, the cable company can change them with little warning. To simplify the process of modifying the program later, instead of using these values directly in the program, you should declare them as named constants. Based on the problem analysis, you need to declare the following named constants:

```
//Named constants - residential customers
const double RES_BILL_PROC_FEES = 4.50;
const double RES_BASIC_SERV_COST = 20.50;
const double RES_COST_PREM_CHANNEL = 7.50;

//Named constants - business customers
const double BUS_BILL_PROC_FEES = 15.00;
const double BUS_BASIC_SERV_COST = 75.00;
const double BUS_BASIC_CONN_COST = 5.00;
const double BUS_COST_PREM_CHANNEL = 50.00;
```

**Formulas** The program uses a number of formulas to compute the billing amount. To compute the residential bill, you need to know only the number of premium channels to which the user subscribes. The following statement calculates the billing amount for a residential customer.

```
amountDue = RES_BILL_PROC_FEES + RES_BASIC_SERV_COST
 + numOfPremChannels * RES_COST_PREM_CHANNEL;
```

To compute the business bill, you need to know the number of basic service connections and the number of premium channels to which the user subscribes. If the number of basic service connections is less than or equal to 10, the cost of the

basic service connections is fixed. If the number of basic service connections exceeds 10, you must add the cost for each connection over 10. The following statement calculates the business billing amount.

```
if (numOfBasicServConn <= 10)
 amountDue = BUS_BILL_PROC_FEES + BUS_BASIC_SERV_COST
 + numOfPremChannels * BUS_COST_PREM_CHANNEL;
else
 amountDue = BUS_BILL_PROC_FEES + BUS_BASIC_SERV_COST
 + (numOfBasicServConn - 10)
 * BUS_BASIC_CONN_COST
 + numOfPremChannels * BUS_COST_PREM_CHANNEL;
```

#### MAIN ALGORITHM

Based on the preceding discussion, you can now write the main algorithm.

1. To output floating-point numbers in a fixed decimal format with a decimal point and trailing zeros, set the manipulators **fixed** and **showpoint**. Also, to output floating-point numbers with two decimal places, set the precision to two decimal places. Recall that to use these manipulators, the program must include the header file **iomanip**.
2. Prompt the user to enter the account number.
3. Get the customer account number.
4. Prompt the user to enter the customer code.
5. Get the customer code.
6. If the customer code is **r** or **R**,
  - a. Prompt the user to enter the number of premium channels.
  - b. Get the number of premium channels.
  - c. Calculate the billing amount.
  - d. Print the account number and the billing amount.
7. If the customer code is **b** or **B**,
  - a. Prompt the user to enter the number of basic service connections.
  - b. Get the number of basic service connections.
  - c. Prompt the user to enter the number of premium channels.
  - d. Get the number of premium channels.
  - e. Calculate the billing amount.
  - f. Print the account number and the billing amount.
8. If the customer code is something other than **r**, **R**, **b**, or **B**, output an error message.

For Steps 6 and 7, the program uses a **switch** statement to calculate the bill for the desired customer.

**COMPLETE PROGRAM LISTING**

```

//*****
// Author: D. S. Malik
//
// Program: Cable Company Billing
// This program calculates and prints a customer's bill for
// a local cable company. The program processes two types of
// customers: residential and business.
//*****

#include <iostream>
#include <iomanip>

using namespace std;

 //Named constants - residential customers
const double RES_BILL_PROC_FEES = 4.50;
const double RES_BASIC_SERV_COST = 20.50;
const double RES_COST_PREM_CHANNEL = 7.50;

 //Named constants - business customers
const double BUS_BILL_PROC_FEES = 15.00;
const double BUS_BASIC_SERV_COST = 75.00;
const double BUS_BASIC_CONN_COST = 5.00;
const double BUS_COST_PREM_CHANNEL = 50.00;

int main()
{
 //Variable declaration
 int accountNumber;
 char customerType;
 int numOfPremChannels;
 int numOfBasicServConn;
 double amountDue;

 cout << fixed << showpoint; //Step 1
 cout << setprecision(2); //Step 1

 cout << "This program computes a cable "
 << "bill." << endl;
 cout << "Enter account number (an integer): "; //Step 2
 cin >> accountNumber; //Step 3
 cout << endl;

 cout << "Enter customer type: "
 << "R or r (Residential), "
 << "B or b (Business): "; //Step 4
 cin >> customerType; //Step 5
 cout << endl;

```

```
switch (customerType)
{
case 'r': //Step 6
case 'R':
 cout << "Enter the number"
 << " of premium channels: "; //Step 6a
 cin >> numOfPremChannels; //Step 6b
 cout << endl;

 amountDue = RES_BILL_PROC_FEES //Step 6c
 + RES_BASIC_SERV_COST
 + numOfPremChannels *
 RES_COST_PREM_CHANNEL;

 cout << "Account number: "
 << accountNumber
 << endl; //Step 6d
 cout << "Amount due: $"
 << amountDue
 << endl; //Step 6d
 break;

case 'b': //Step 7
case 'B':
 cout << "Enter the number of basic "
 << "service connections: "; //Step 7a
 cin >> numOfBasicServConn; //Step 7b
 cout << endl;

 cout << "Enter the number"
 << " of premium channels: "; //Step 7c
 cin >> numOfPremChannels; //Step 7d
 cout << endl;

 if (numOfBasicServConn <= 10) //Step 7e
 amountDue = BUS_BILL_PROC_FEES
 + BUS_BASIC_SERV_COST
 + numOfPremChannels *
 BUS_COST_PREM_CHANNEL;

 else
 amountDue = BUS_BILL_PROC_FEES
 + BUS_BASIC_SERV_COST
 + (numOfBasicServConn - 10) *
 BUS_BASIC_CONN_COST
 + numOfPremChannels *
 BUS_COST_PREM_CHANNEL;

 cout << "Account number: "
 << accountNumber << endl; //Step 7f
 cout << "Amount due: $" << amountDue
 << endl; //Step 7f
 break;
}
```

```

 default:
 cout << "Invalid customer type." << endl; //Step 8
 }//end switch

 return 0;
}

```

**Sample Run:** In this sample run, the user input is shaded.

This program computes a cable bill.

Enter account number (an integer): 12345

Enter customer type: R or r (Residential), B or b (Business): b

Enter the number of basic service connections: 16

Enter the number of premium channels: 8

Account number: 12345

Amount due: \$520.00

## QUICK REVIEW

1. Control structures alter the normal flow of control.
2. The two most common control structures are selection and repetition.
3. Selection structures incorporate decisions in a program.
4. The relational operators are == (equality), < (less than), <= (less than or equal to), > (greater than), >= (greater than or equal to), and != (not equal to).
5. Including a space between the relational operators ==, <=, >=, and != creates a syntax error.
6. Characters are compared using a machine's collating sequence.
7. Logical expressions evaluate to 1 (or a nonzero value) or 0. The logical value 1 (or any nonzero value) is treated as **true**; the logical value 0 is treated as **false**.
8. In C++, **int** variables can be used to store the value of a logical expression.
9. In C++, **bool** variables can be used to store the value of a logical expression.
10. In C++, the logical operators are ! (not), && (and), and || (or).
11. There are two selection structures in C++.
12. One-way selection takes the following form:

```

if (expression)
 statement

```

If **expression** is **true**, the **statement** executes; otherwise, the computer executes the **statement** following the **if** statement.

13. Two-way selection takes the following form:

```
if (expression)
 statement1
else
 statement2
```

If **expression** is **true**, then **statement1** executes; otherwise, **statement2** executes.

14. The expression in an **if** or **if...else** structure is usually a logical expression.
15. Including a semicolon before the **statement** in a one-way selection creates a semantic error. In this case, the action of the **if** statement is empty.
16. Including a semicolon before **statement1** in a two-way selection creates a syntax error.
17. There is no stand-alone **else** statement in C++. Every **else** has a related **if**.
18. An **else** is paired with the most recent **if** that has not been paired with any other **else**.
19. A sequence of statements enclosed between curly braces, {and }, is called a compound statement or block of statements. A compound statement is treated as a single statement.
20. You can use the input stream variable in an **if** statement to determine the state of the input stream.
21. Using the assignment operator in place of the equality operator creates a semantic error. This can cause serious errors in the program.
22. The **switch** structure is used to handle multiway selection.
23. The execution of a **break** statement in a **switch** statement immediately exits the **switch** structure.
24. If certain conditions are not met in a program, the program can be terminated using the **assert** function.

## EXERCISES

---

1. Mark the following statements as true or false.
  - a. The result of a logical expression cannot be assigned to an **int** variable.
  - b. In a one-way selection, if a semicolon is placed after the expression in an **if** statement, the expression in the **if** statement is always **true**.
  - c. Every **if** statement must have a corresponding **else**.
  - d. The expression in the **if** statement:
 

```
if (score = 30)
 grade = 'A';
```

 always evaluates to **true**.

- e. The expression:  
`(ch >= 'A' && ch <= 'Z')`  
evaluates to **false** if either `ch < 'A'` or `ch >= 'Z'`.
- f. Suppose the input is 5. The output of the code:  

```
cin >> num;
if (num > 5)
 cout << num;
 num = 0;
else
 cout << "Num is zero" << endl;
is: Num is zero
```
- g. The expression in a **switch** statement should evaluate to a value of the simple data type.
- h. The expression `!(x > 0)` is **true** only if `x` is a negative number.
- i. In C++, both `!` and `!=` are logical operators.
- j. The order in which statements execute in a program is called the flow of control.

2. Circle the best answer.

- ```
a.  if (60 <= 12 * 5)
    cout << "Hello";
    cout << " There";
```

outputs the following:

- (i) Hello There (ii) Hello (iii) Hello (iv) There
There

- ```
b. if ('a' > 'b' || 66 > static_cast<int>('A'))
 cout << "#*#" << endl;
```

outputs the following:

- (i) # \* #      (ii) #      (iii) \*      (iv) none of these  
                          \*  
                          #

- ```
c. if (7 <= 7)
    cout << 6 - 9 * 2 / 6 << endl;
```

outputs the following:

- (i) -1 (ii) 3 (iii) 3.0 (iv) none of these

- ```
d. if (7 < 8)
{
 cout << "2 4 6 8" << endl;
 cout << "1 3 5 7" << endl;
}
```

outputs the following:

- (i) 2 4 6 8      (ii) 1 3 5 7      (iii) none of these  
1 3 5 7

```
e. if (5 < 3)
 cout << "*";
else if (7 == 8)
 cout << "&";
else
 cout << "$";
```

outputs the following:

- (i) \*      (ii) &      (iii) \$      (iv) none of these

3. Suppose that `x`, `y`, and `z` are `int` variables, and `x = 10`, `y = 15`, and `z = 20`. Determine whether the following expressions evaluate to `true` or `false`.

- `!(x > 10)`
- `x <= 5 || y < 15`
- `(x != 5) && (y != z)`
- `x >= z || (x + y >= z)`
- `(x <= y - 2) && (y >= z) || (z - 2 != 20)`

4. Suppose that `str1`, `str2`, and `str3` are `string` variables, and `str1 = "English"`, `str2 = "Computer Science"`, and `str3 = "Programming"`. Evaluate the following expressions.

- `str1 >= str2`
- `str1 != "english"`
- `str3 < str2`
- `str2 >= "Chemistry"`

5. Suppose that `x`, `y`, `z`, and `w` are `int` variables, and `x = 3`, `y = 4`, `z = 7`, and `w = 1`. What is the output of the following statements?

- `cout << "x == y: " << (x == y) << endl;`
- `cout << "x != z: " << (x != z) << endl;`
- `cout << "y == z - 3: " << (y == z - 3) << endl;`
- `cout << "!(z > w): " << !(z > w) << endl;`
- `cout << "x + y < z: " << (x + y < z) << endl;`

6. What is the output of the following C++ code?

```
x = 100;
y = 200;
if (x > 100 && y <= 200)
 cout << x << " " << y << " " << x + y << endl;
```

```
else
 cout << x << " " << y << " " << 2 * x - y << endl;
```

7. Correct the following code so that it prints the correct message.

```
if (score >= 60)
 cout << "You pass." << endl;
else;
 cout << "You fail." << endl;
```

8. Write C++ statements that output **Male** if the **gender** is 'M', **Female** if the **gender** is 'F', and **invalid gender** otherwise.

9. What is the output of the following program?

```
#include <iostream>

using namespace std;

int main()
{
 int myNum = 10;
 int yourNum = 30;

 if (yourNum % myNum == 3)
 {
 yourNum = 3;
 myNum = 1;
 }
 else if (yourNum % myNum == 2)
 {
 yourNum = 2;
 myNum = 2;
 }
 else
 {
 yourNum = 1;
 myNum = 3;
 }

 cout << myNum << " " << yourNum << endl;

 return 0;
}
```

10. a. What is the output of the program in Exercise 9, if **myNum** = 5 and **yourNum** = 12?  
 b. What is the output of the program in Exercise 9, if **myNum** = 30 and **yourNum** = 33?
11. Suppose that **sale** and **bonus** are **double** variables. Write an **if...else** statement that assigns a value to **bonus** as follows: If **sale** is greater than \$20,000, the value assigned to **bonus** is 0.10; If **sale** is greater than

\$10,000 and less than or equal to \$20,000, the value assigned to `bonus` is 0.05; otherwise, the value assigned to `bonus` is 0.

12. Suppose that `overSpeed` and `fine` are `double` variables. Assign the value to `fine` as follows: If  $0 < \text{overSpeed} \leq 5$ , the value assigned to `fine` is \$20.00; if  $5 < \text{overSpeed} \leq 10$ , the value assigned to `fine` is \$75.00; if  $10 < \text{overSpeed} \leq 15$ , the value assigned to `fine` is \$150.00; if  $\text{overSpeed} > 15$ , the value assigned to `fine` is \$150.00 plus \$20.00 per mile over 15.
13. Suppose that `score` is an `int` variable. Consider the following `if` statements:
 

```
if (score >= 90);
 cout << "Discount = 10%" << endl;
```

  - a. What is the output if the value of `score` is 95? Justify your answer.
  - b. What is the output if the value of `score` is 85? Justify your answer.
14. Suppose that `score` is an `int` variable. Consider the following `if` statements:
  - i. 

```
if (score == 70)
 cout << "Grade is C." << endl;
```
  - ii. 

```
if (score = 70)
 cout << "Grade is C." << endl;
```

Answer the following questions:

- a. What is the output in (i) and (ii) if the value of `score` is 70? What is the value of `score` after the `if` statement executes?
  - b. What is the output in (i) and (ii) if the value of `score` is 80? What is the value of `score` after the `if` statement executes?
15. Rewrite the following expressions using the conditional operator. (Assume that all variables are declared properly.)
  - a. 

```
if (x >= y)
 z = x - y;
else
 z = y - x;
```
  - b. 

```
if (hours >= 40.0)
 wages = 40 * 7.50 + 1.5 * 7.5 * (hours - 40);
else
 wages = hours * 7.50;
```
  - c. 

```
if (score >= 60)
 str = "Pass";
else
 str = "Fail";
```
16. Rewrite the following expressions using an `if...else` statement. (Assume that all variables are declared properly.)

- a. `(x < 5) ? y = 10 : y = 20;`
  - b. `(fuel >= 10) ? drive = 150 : drive = 30;`
  - c. `(booksBought >= 3) ? discount = 0.15 : discount = 0.0;`
17. Suppose that you have the following conditional expression. (Assume that all the variables are properly declared.)
- ```
(0 < backyard && backyard <= 5000) ? fertilizingCharges = 40.00
    : fertilizingCharges = 40.00 + (backyard - 5000) * 0.01;
```
- a. What is the value of `fertilizingCharges` if the value of `backyard` is 3000?
 - b. What is the value of `fertilizingCharges` if the value of `backyard` is 5000?
 - c. What is the value of `fertilizingCharges` if the value of `backyard` is 6500?
18. State whether the following are valid `switch` statements. If not, explain why. Assume that `n` and `digit` are `int` variables.
- a.

```
switch (n <= 2)
{
    case 0:
        cout << "Draw." << endl;
        break;
    case 1:
        cout << "Win." << endl;
        break;
    case 2:
        cout << "Lose." << endl;
        break;
}
```
 - b.

```
switch (digit / 4)
{
    case 0,
    case 1:
        cout << "low." << endl;
        break;
    case 1,
    case 2:
        cout << "middle." << endl;
        break;
    case 3:
        cout << "high." << endl;
}
```
 - c.

```
switch (n % 6)
{
    case 1:
    case 2:
    case 3:
```

```

    case 4:
    case 5:
        cout << n;
        break;
    case 0:
        cout << endl;
        break;
}

```

d. `switch` (`n % 10`)

```

{
    case 2:
    case 4:
    case 6:
    case 8:
        cout << "Even";
        break;
    case 1:
    case 3:
    case 5:
    case 7:
        cout << "Odd";
        break;
}

```

19. Suppose the input is 5. What is the value of `alpha` after the following C++ code executes?

```

cin >> alpha;
switch (alpha)
{
    case 1:
    case 2:
        alpha = alpha + 2;
        break;
    case 4:
        alpha++;
    case 5:
        alpha = 2 * alpha;
    case 6:
        alpha = alpha + 5;
        break;
    default:
        alpha--;
}

```

20. Suppose the input is 3. What is the value of `beta` after the following C++ code executes?

```

cin >> beta;
switch (beta)
{
    case 3:
        beta = beta + 3;
}

```

```

case 1:
    beta++;
    break;
case 5:
    beta = beta + 5;
case 4:
    beta = beta + 4;
}

```

21. Suppose the input is 6. What is the value of **a** after the following C++ code executes?

```

cin >> a;
if (a > 0)
    switch (a)
    {
        case 1:
            a = a + 3;
        case 3:
            a++;
            break;
        case 6:
            a = a + 6;
        case 8:
            a = a * 8;
            break;
        default:
            a--;
    }
else
    a = a + 2;

```

22. In the following code, correct any errors that would prevent the program from compiling or running.

```

include <iostream>

main ()
{
    int a, b;
    bool found;
    cout << "Enter two integers: ";
    cin >> a >> b;

    if a > a*b && 10 < b
        found = 2 * a > b;
    else
    {
        found = 2 * a < b;
        if found
            a = 3;
            c = 15;
            if b

```

```

        {
            b = 0;
            a = 1;
        }
    }

```

23. The following program contains errors. Correct them so that the program will run and output `w = 21`.

```

#include <iostream>

using namespace std;

const int SECRET = 5

main ()
{
    int x, y, w, z;
    z = 9;

    if z > 10
        x = 12; y = 5, w = x + y + SECRET;
    else
        x = 12; y = 4, w = x + y + SECRET;

    cout << "w = " << w << endl;
}

```

24. Write the missing statements in the following program so that it prompts the user to input two numbers. If one of the numbers is 0, the program should output a message indicating that both numbers must be nonzero. If the first number is greater than the second number, it outputs the first number divided by the second number; if the first number is less than the second number, it outputs the second number divided by the first number; otherwise, it outputs the product of the numbers.

```

#include <iostream>
using namespace std;

int main()
{
    double firstNum, secondNum;

    cout << "Enter two nonzero numbers: ";
    cin >> firstNum >> secondNum;
    cout << endl;

    //Missing statements

    return 0;
}

```

PROGRAMMING EXERCISES

1. Write a program that prompts the user to input a number. The program should then output the number and a message saying whether the number is positive, negative, or zero.
2. Write a program that prompts the user to input three numbers. The program should then output the numbers in ascending order.
3. Write a program that prompts the user to input an integer between 0 and 35. If the number is less than or equal to 9, the program should output the number; otherwise, it should output A for 10, B for 11, C for 12... and Z for 35. (*Hint:* Use the cast operator, `static_cast<char>()`, for numbers ≥ 10 .)
4. The statements in the following program are in incorrect order. Rearrange the statements so that they prompt the user to input the shape type (`rectangle`, `circle`, or `cylinder`) and the appropriate dimension of the shape. The program then outputs the following information about the shape: For a rectangle, it outputs the area and perimeter; for a circle, it outputs the area and circumference; and for a cylinder, it outputs the volume and surface area. After rearranging the statements, your program should be properly indented.

```
using namespace std;

#include <iostream>

int main()
{
    string shape;
    double height;

    #include <string>

    cout << "Enter the shape type: (rectangle, circle, cylinder) ";
    cin >> shape;
    cout << endl;

    if (shape == "rectangle")
    {
        cout << "Area of the circle = "
             << PI * pow(radius, 2.0) << endl;

        cout << "Circumference of the circle: "
             << 2 * PI * pow(radius, 2.0) << endl;

        cout << "Enter the height of the cylinder: ";
        cin >> height;
        cout << endl;

        cout << "Enter the width of the rectangle: ";
        cin >> width;
        cout << endl;
    }
}
```

```

        cout << "Perimeter of the rectangle = "
              << 2 * (length + width) << endl;
        double width;
    }

    cout << "Surface area of the cylinder: "
          << 2 * radius * + 2 * PI * pow(radius, 2.0) << endl;
    }
    else if (shape == "circle")
    {
        cout << "Enter the radius of the circle: ";
        cin >> radius;
        cout << endl;

        cout << "Volume of the cylinder = "
              << PI * pow(radius, 2.0)* height << endl;
        double length;
    }
    return 0;
    else if (shape == "cylinder")
    {
        double radius;

        cout << "Enter the length of the rectangle: ";
        cin >> length;
        cout << endl;

        #include <iomanip>

        cout << "Enter the radius of the base of the cylinder: ";
        cin >> radius;
        cout << endl;

        const double PI = 3.1416;
        cout << "Area of the rectangle = "
              << length * width << endl;
    else
        cout << "The program does not handle " << shape << endl;
        cout << fixed << showpoint << setprecision(2);

        #include <cmath>
    }
}

```

5. Write a program to implement the algorithm you designed in Exercise 21 of Chapter 1.
6. In a right triangle, the square of the length of one side is equal to the sum of the squares of the lengths of the other two sides. Write a program that prompts the user to enter the lengths of three sides of a triangle and then outputs a message indicating whether the triangle is a right triangle.

7. A box of cookies can hold 24 cookies, and a container can hold 75 boxes of cookies. Write a program that prompts the user to enter the total number of cookies, the number of cookies in a box, and the number of cookie boxes in a container. The program then outputs the number of boxes and the number of containers to ship the cookies. Note that each box must contain the specified number of cookies, and each container must contain the specified number of boxes. If the last box of cookies contains less than the number of specified cookies, you can discard it and output the number of leftover cookies. Similarly, if the last container contains less than the number of specified boxes, you can discard it and output the number of leftover boxes.
8. The roots of the quadratic equation $ax^2 + bx + c = 0$, $a \neq 0$ are given by the following formula:

$$\frac{-b \pm \sqrt{b^2 - 4ac}}{2a}$$

In this formula, the term $b^2 - 4ac$ is called the **discriminant**. If $b^2 - 4ac = 0$, then the equation has a single (repeated) root. If $b^2 - 4ac > 0$, the equation has two real roots. If $b^2 - 4ac < 0$, the equation has two complex roots. Write a program that prompts the user to input the value of a (the coefficient of x^2), b (the coefficient of x), and c (the constant term) and outputs the type of roots of the equation. Furthermore, if $b^2 - 4ac \geq 0$, the program should output the roots of the quadratic equation. (*Hint*: Use the function `pow` from the header file `cmath` to calculate the square root. Chapter 3 explains how the function `pow` is used.)

9. Write a program that mimics a calculator. The program should take as input two integers and the operation to be performed. It should then output the numbers, the operator, and the result. (For division, if the denominator is zero, output an appropriate message.) Some sample outputs follow:

```
3 + 4 = 7
13 * 5 = 65
```

10. Redo Exercise 9 to handle floating-point numbers. (Format your output to two decimal places.)
11. Redo Programming Exercise 19 of Chapter 2, taking into account that your parents buy additional savings bonds for you as follows:
 - a. If you do not spend any money to buy savings bonds, then because you had a summer job, your parents buy savings bonds for you in an amount equal to 1% of the money you save after paying taxes and buying clothes, other accessories, and school supplies.
 - b. If you spend up to 25% of your net income to buy savings bonds, your parents spend \$0.25 for each dollar you spend to buy savings bonds,

plus money equal to 1% of the money you save after paying taxes and buying clothes, other accessories, and school supplies.

- c. If you spend more than 25% of your net income to buy savings bonds, your parents spend \$0.40 for each dollar you spend to buy savings bonds, plus money equal to 2% of the money you save after paying taxes and buying clothes, other accessories, and school supplies.
12. A bank in your town updates its customers' accounts at the end of each month. The bank offers two types of accounts: savings and checking. Every customer must maintain a minimum balance. If a customer's balance falls below the minimum balance, there is a service charge of \$10.00 for savings accounts and \$25.00 for checking accounts. If the balance at the end of the month is at least the minimum balance, the account receives interest as follows:
- a. Savings accounts receive 4% interest.
 - b. Checking accounts with balances of up to \$5,000 more than the minimum balance receive 3% interest; otherwise, the interest is 5%.

Write a program that reads a customer's account number (`int` type), account type (`char`; `s` for savings, `c` for checking), minimum balance that the account should maintain, and current balance. The program should then output the account number, account type, current balance, and an appropriate message. Test your program by running it five times, using the following data:

```
46728 S 1000 2700
87324 C 1500 7689
79873 S 1000 800
89832 C 2000 3000
98322 C 1000 750
```

13. Write a program that implements the algorithm given in Example 1-3 (Chapter 1), which determines the monthly wages of a salesperson.
14. The number of lines that can be printed on a paper depends on the paper size, the point size of each character in a line, whether lines are double-spaced or single-spaced, the top and bottom margin, and the left and right margins of the paper. Assume that all characters are of the same point size, and all lines are either single-spaced or double-spaced. Note that 1 inch = 72 points. Moreover, assume that the lines are printed along the width of the paper. For example, if the length of the paper is 11 inches and width is 8.5 inches, then the maximum length of a line is 8.5 inches. Write a program that calculates the number of characters in a line and the number of lines that can be printed on a paper based on the following input from the user:
- a. The length and width, in inches, of the paper
 - b. The top, bottom, left, and right margins
 - c. The point size of a line
 - d. If the lines are double-spaced, then double the point size of each character

15. Write a program that calculates and prints the bill for a cellular telephone company. The company offers two types of service: regular and premium. Its rates vary, depending on the type of service. The rates are computed as follows:

Regular service: \$10.00 plus first 50 minutes are free. Charges for over 50 minutes are \$0.20 per minute.

Premium service: \$25.00 plus:

- a. For calls made from 6:00 a.m. to 6:00 p.m., the first 75 minutes are free; charges for more than 75 minutes are \$0.10 per minute.
- b. For calls made from 6:00 p.m. to 6:00 a.m., the first 100 minutes are free; charges for more than 100 minutes are \$0.05 per minute.

Your program should prompt the user to enter an account number, a service code (type `char`), and the number of minutes the service was used. A service code of `r` or `R` means regular service; a service code of `p` or `P` means premium service. Treat any other character as an error. Your program should output the account number, type of service, number of minutes the telephone service was used, and the amount due from the user.

For the premium service, the customer may be using the service during the day and the night. Therefore, to calculate the bill, you must ask the user to input the number of minutes the service was used during the day and the number of minutes the service was used during the night.

16. Write a program to implement the algorithm that you designed in Exercise 22 of Chapter 1. (Assume that the account balance is stored in the file `Ch4_Ex16_Data.txt`.) Your program should output account balance before and after withdrawal and service charges. Also save the account balance after withdrawal in the file `Ch4_Ex16_Output.txt`.
17. You have several pictures of different sizes that you would like to frame. A local picture-framing store offers two types of frames—regular and fancy. The frames are available in white and can be ordered in any color the customer desires. Suppose that each frame is 1 inch wide. The cost of coloring the frame is \$0.10 per inch. The cost of a regular frame is \$0.15 per inch, and the cost of a fancy frame is \$0.25 per inch. The cost of putting a cardboard paper behind the picture is \$0.02 per square inch, and the cost of putting glass on top of the picture is \$0.07 per square inch. The customer can also choose to put crowns on the corners, which costs \$0.35 per crown. Write a program that prompts the user to input the following information and then output the cost of framing the picture:
- a. The length and width, in inches, of the picture
 - b. The type of the frame
 - c. Customer's choice of color to color the frame
 - d. If the user wants to put the crowns, then the number of crowns

18. Samantha and Vikas are looking to buy a house in a new development. After looking at various models, the three models they like are colonial, split-entry, and single-story. The builder gave them the base price and the finished area in square feet of the three models. They want to know the model(s) with the least price per square foot. Write a program that accepts as input the base price and the finished area in square feet of the three models. The program outputs the model(s) with the least price per square foot.
19. One way to determine how healthy a person is by measuring the body fat of the person. The formulas to determine the body fat for female and male are as follows:

Body fat formula for women:

$$A1 = (\text{body weight} \times 0.732) + 8.987$$

$$A2 = \text{wrist measurement (at fullest point)} / 3.140$$

$$A3 = \text{waist measurement (at navel)} \times 0.157$$

$$A4 = \text{hip measurement (at fullest point)} \times 0.249$$

$$A5 = \text{forearm measurement (at fullest point)} \times 0.434$$

$$B = A1 + A2 - A3 - A4 + A5$$

$$\text{Body fat} = \text{body weight} - B$$

$$\text{Body fat percentage} = \text{body fat} \times 100 / \text{body weight}$$

Body fat formula for men:

$$A1 = (\text{body weight} \times 1.082) + 94.42$$

$$A2 = \text{wrist measurement} \times 4.15$$

$$B = A1 - A2$$

$$\text{Body fat} = \text{body weight} - B$$

$$\text{Body fat percentage} = \text{body fat} \times 100 / \text{body weight}$$

Write a program to calculate the body fat of a person.



5

CHAPTER

CONTROL STRUCTURES II (REPETITION)

IN THIS CHAPTER, YOU WILL:

- Learn about repetition (looping) control structures
- Explore how to construct and use counter-controlled, sentinel-controlled, flag-controlled, and EOF-controlled repetition structures
- Examine `break` and `continue` statements
- Discover how to form and use nested control structures
- Learn how to avoid bugs by avoiding patches
- Learn how to debug loops

In Chapter 4, you saw how decisions are incorporated in programs. In this chapter, you learn how repetitions are incorporated in programs.

Why Is Repetition Needed?

Suppose you want to add five numbers to find their average. From what you have learned so far, you could proceed as follows (assume that all variables are properly declared):

```
cin >> num1 >> num2 >> num3 >> num4 >> num5; //read five numbers
sum = num1 + num2 + num3 + num4 + num5;        //add the numbers
average = sum / 5;                             //find the average
```

But suppose you want to add and average 100, 1000, or more numbers. You would have to declare that many variables and list them again in `cin` statements and, perhaps, again in the output statements. This takes an exorbitant amount of space and time. Also, if you want to run this program again with different values or with a different number of values, you have to rewrite the program.

Suppose you want to add the following numbers:

5 3 7 9 4

Consider the following statements, in which `sum` and `num` are variables of type `int`:

1. `sum = 0;`
2. `cin >> num;`
3. `sum = sum + num;`

The first statement initializes `sum` to 0. Let us execute statements 2 and 3. Statement 2 stores 5 in `num`; statement 3 updates the value of `sum` by adding `num` to it. After statement 3, the value of `sum` is 5.

Let us repeat statements 2 and 3. After statement 2 (after the programming code reads the next number):

`num = 3`

After statement 3:

`sum = sum + num = 5 + 3 = 8`

At this point, `sum` contains the sum of the first two numbers. Let us again repeat statements 2 and 3 (a third time). After statement 2 (after the code reads the next number):

`num = 7`

After statement 3:

`sum = sum + num = 8 + 7 = 15`

Now, `sum` contains the sum of the first three numbers. If you repeat statements 2 and 3 two more times, `sum` will contain the sum of all five numbers.

If you want to add 10 numbers, you can repeat statements 2 and 3 ten times. And if you want to add 100 numbers, you can repeat statements 2 and 3 one hundred times. In either case, you do not have to declare any additional variables, as you did in the first code. You can use this C++ code to add any set of numbers, whereas the earlier code requires you to drastically change the code.

There are many other situations in which it is necessary to repeat a set of statements. For example, for each student in a class, the formula for determining the course grade is the same. C++ has three repetition, or looping, structures that let you repeat statements over and over until certain conditions are met. This chapter introduces all three looping (repetition) structures. The next section discusses the first repetition structure, called the **while** loop.

while Looping (Repetition) Structure

In the previous section, you saw that sometimes it is necessary to repeat a set of statements several times. One way to repeat a set of statements is to type the set of statements in the program over and over. For example, if you want to repeat a set of statements 100 times, you type the set of statements 100 times in the program. However, this solution of repeating a set of statements is impractical, if not impossible. Fortunately, there is a better way to repeat a set of statements. As noted earlier, C++ has three repetition, or looping, structures that allow you to repeat a set of statements until certain conditions are met. This section discusses the first looping structure, called a **while** loop.

The general form of the **while** statement is:

```
while (expression)
    statement
```

In C++, **while** is a reserved word. Of course, the **statement** can be either a simple or compound statement. The **expression** acts as a **decision maker** and is usually a logical expression. The **statement** is called the body of the loop. Note that the parentheses around the **expression** are part of the syntax. Figure 5-1 shows the flow of execution of a **while** loop.




FIGURE 5-1 **while** loop

The **expression** provides an entry condition. If it initially evaluates to **true**, the **statement** executes. The loop condition—the **expression**—is then reevaluated. If it again evaluates to **true**, the **statement** executes again. The **statement** (body of the loop) continues to execute until the **expression** is no longer **true**. A loop that continues to execute endlessly is called an **infinite loop**. To avoid an infinite loop, make sure that the loop's body contains statement(s) that assure that the exit condition—the expression in the **while** statement—will eventually be **false**.

EXAMPLE 5-1

Consider the following C++ program segment: (Assume that **i** is an **int** variable.)

```
i = 0;                                //Line 1
while (i <= 20)                       //Line 2
{
    cout << i << " ";               //Line 3
    i = i + 5;                      //Line 4
}

cout << endl;
```

Sample Run:

```
0 5 10 15 20
```

In Line 1, the variable **i** is set to 0. The **expression** in the **while** statement (in Line 2), **i <= 20**, is evaluated. Because the expression **i <= 20** evaluates to **true**, the body of the **while** loop executes next. The body of the **while** loop consists of the statements in Lines 3 and 4. The statement in Line 3 outputs the value of **i**, which is 0. The statement in Line 4 changes the value of **i** to 5. After executing the statements in Lines 3 and 4, the **expression** in the **while** loop (Line 2) is evaluated again. Because **i** is 5, the expression **i <= 20** evaluates to **true** and the body of the **while** loop executes again. This process of evaluating the **expression** and executing the body of the **while** loop continues until the **expression**, **i <= 20** (in Line 2), no longer evaluates to **true**.

The variable **i** (in Line 2, Example 5-1) in the expression is called the **loop control variable**.

Note the following from Example 5-1:

- a. Within the loop, **i** becomes 25 but is not printed because the entry condition is **false**.
- b. If you omit the statement:

```
i = i + 5;
```

from the body of the loop, you will have an infinite loop, continually printing rows of zeros.

- c. You must initialize the loop control variable `i` before you execute the loop. If the statement:

```
i = 0;
```

(in Line 1) is omitted, the loop may not execute at all. (Recall that variables in C++ are not automatically initialized.)

- d. In Example 5-1, if the two statements in the body of the loop are interchanged, it may drastically alter the result. For example, consider the following statements:

```
i = 0;

while (i <= 20)
{
    i = i + 5;
    cout << i << " ";
}

cout << endl;
```

Here, the output is:

```
5 10 15 20 25
```

Typically, this would be a semantic error because you rarely want a condition to be true for `i <= 20` and yet produce results for `i > 20`.

- e. If you put a semicolon at the end of the `while` loop, (after the logical expression), then the action of the `while` loop is empty or null. For example, the action of the following `while` loop is empty.

```
i = 0;

while (i <= 20);
{
    i = i + 5;
    cout << i << " ";
}

cout << endl;
```

The statements within the braces do not form the body of the `while` loop.

Designing while Loops

As in Example 5-1, the body of a `while` executes only when the **expression**, in the `while` statement, evaluates to `true`. Typically, the **expression** checks whether a variable(s), called the **loop control variable (LCV)**, satisfies certain conditions. For example, in Example 5-1, the **expression** in the `while` statement checks whether `i <= 20`. The LCV must be properly initialized before the `while` loop, and it should

eventually make the **expression** evaluate to **false**. We do this by updating or reinitializing the LCV in the body of the **while** loop. Therefore, typically, **while** loops are written in the following form:

```
//initialize the loop control variable(s)

while (expression) //expression tests the LCV
{
    .
    .
    .
    //update the loop control variable(s)
    .
    .
    .
}
```

For instance, in Example 5-1, the statement in Line 1 initializes the LCV **i** to 0. The expression, **i <= 20**, in Line 2, checks whether **i** is less than or equal to 20, and the statement in Line 4 updates the value of **i**.

EXAMPLE 5-2

Consider the following C++ program segment:

```
i = 20; //Line 1
while (i < 20) //Line 2
{
    cout << i << " "; //Line 3
    i = i + 5; //Line 4
}
cout << endl; //Line 5
```

It is easy to overlook the difference between this example and Example 5-1. In this example, in Line 1, **i** is set to 20. Because **i** is 20, the expression **i < 20** in the **while** statement (Line 2) evaluates to **false**. Because initially the loop entry condition, **i < 20**, is **false**, the body of the **while** loop never executes. Hence, no values are output, and the value of **i** remains 20.

The next few sections describe the various forms of **while** loops.

Case 1: Counter-Controlled **while** Loops

Suppose you know exactly how many times certain statements need to be executed. For example, suppose you know exactly how many pieces of data (or entries) need to be read. In such cases, the **while** loop assumes the form of a **counter-controlled while loop**. Suppose that a set of statements needs to be executed **N** times. You can set up a **counter**

(initialized to 0 before the **while** statement) to track how many items have been read. Before executing the body of the **while** statement, the **counter** is compared with **N**. If **counter < N**, the body of the **while** statement executes. The body of the loop continues to execute until the value of **counter >= N**. Thus, inside the body of the **while** statement, the value of **counter** increments after it reads a new item. In this case, the **while** loop might look like the following:

```
counter = 0;           //initialize the loop control variable

while (counter < N) //test the loop control variable
{
    .
    .
    .
    counter++;        //update the loop control variable
    .
    .
    .
}
```

If **N** represents the number of data items in a file, then the value of **N** can be determined several ways. The program can prompt you to specify the number of items in the file; an input statement can read the value; or you can specify the first item in the file as the number of items in the file, so that you need not remember the number of input values (items). This is useful if someone other than the programmer enters the data. Consider Example 5-3.

EXAMPLE 5-3

Suppose the input is:

```
8 9 2 3 90 38 56 8 23 89 7 2
```

Suppose you want to add these numbers and find their average. Consider the following program:

//Program: Counter-Controlled Loop

```
#include <iostream>

using namespace std;

int main()
{
    int limit;    //store the number of data items
    int number;   //variable to store the number
    int sum;      //variable to store the sum
    int counter;  //loop control variable

    cout << "Line 1: Enter the number of "
         << "integers in the list: ";           //Line 1
    cin >> limit;                               //Line 2
    cout << endl;                               //Line 3
```

```

sum = 0; //Line 4
counter = 0; //Line 5

cout << "Line 6: Enter " << limit
    << " integers." << endl; //Line 6

while (counter < limit) //Line 7
{
    cin >> number; //Line 8
    sum = sum + number; //Line 9
    counter++; //Line 10
}

cout << "Line 11: The sum of the " << limit
    << " numbers = " << sum << endl; //Line 11

if (counter != 0) //Line 12
    cout << "Line 13: The average = "
        << sum / counter << endl; //Line 13
else //Line 14
    cout << "Line 15: No input." << endl; //Line 15

return 0; //Line 16
}

```

Sample Run: In this sample run, the user input is shaded.

Line 1: Enter the number of integers in the list: 12

Line 6: Enter 12 integers.

8 9 2 3 90 38 56 8 23 89 7 2

Line 11: The sum of the 12 numbers = 335

Line 13: The average = 27

This program works as follows. The statement in Line 1 prompts the user to input the number of data items. The statement in Line 2 reads the next input line and stores it in the variable `limit`. The value of `limit` indicates the number of items in the list. The statements in Lines 4 and 5 initialize the variables `sum` and `counter` to 0. (The variable `counter` is the loop control variable.) The statement in Line 6 prompts the user to input numbers. (In this sample run, the user is prompted to enter 12 integers.) The `while` statement in Line 7 checks the value of `counter` to determine how many items have been read. If `counter` is less than `limit`, the `while` loop proceeds for the next iteration. The statement in Line 8 reads the next number and stores it in the variable `number`. The statement in Line 9 updates the value of `sum` by adding the value of `number` to the previous value, and the statement in Line 10 increments the value of `counter` by 1. The statement in Line 11 outputs the sum of the numbers; the statements in Lines 12 through 15 output the average.

Note that `sum` is initialized to 0 in Line 4 in this program. In Line 9, after reading a number at Line 8, the program adds it to the sum of all the numbers scanned before the current number. The first number read will be added to zero (because `sum` is initialized to 0), giving the correct sum of the first number. To find the average, divide `sum` by `counter`. If `counter`

is 0, then dividing by zero will terminate the program and you get an error message. Therefore, before dividing `sum` by `counter`, you must check whether or not `counter` is 0.

Notice that in this program, the statement in Line 5 initializes the LCV `counter` to 0. The expression `counter < limit` in Line 7 evaluates whether `counter` is less than `limit`. The statement in Line 10 updates the value of `counter`.

Case 2: Sentinel-Controlled while Loops

You do not always know how many pieces of data (or entries) need to be read, but you may know that the last entry is a special value, called a **sentinel**. In this case, you read the first item before the `while` statement. If this item does not equal the sentinel, the body of the `while` statement executes. The `while` loop continues to execute as long as the program has not read the sentinel. Such a `while` loop is called a **sentinel-controlled while loop**. In this case, a `while` loop might look like the following:

```
cin >> variable;           //initialize the loop control variable

while (variable != sentinel) //test the loop control variable
{
    .
    .
    .
    cin >> variable;       //update the loop control variable
    .
    .
}
```

EXAMPLE 5-4

Suppose you want to read some positive integers and average them, but you do not have a preset number of data items in mind. Suppose the number -999 marks the end of the data. You can proceed as follows.

//Program: Sentinel-Controlled Loop

```
#include <iostream>

using namespace std;

const int SENTINEL = -999;

int main()
{
    int number;           //variable to store the number
    int sum = 0;           //variable to store the sum
    int count = 0;        //variable to store the total
                          //numbers read
```

```

cout << "Line 1: Enter integers ending with "
    << SENTINEL << endl;           //Line 1
cin >> number;                      //Line 2

while (number != SENTINEL)          //Line 3
{
    sum = sum + number;              //Line 4
    count++;                        //Line 5
    cin >> number;                  //Line 6
}

cout << "Line 7: The sum of the " << count
    << " numbers is " << sum << endl; //Line 7

if (count != 0)                     //Line 8
    cout << "Line 9: The average is "
        << sum / count << endl;      //Line 9
else                                //Line 10
    cout << "Line 11: No input." << endl; //Line 11

return 0;
}

```

Sample Run: In this sample run, the user input is shaded.

```

Line 1: Enter integers ending with -999
34 23 9 45 78 0 77 8 3 5 -999
Line 7: The sum of the 10 numbers is 282
Line 9: The average is 28

```

This program works as follows. The statement in Line 1 prompts the user to enter numbers ending with -999. The statement in Line 2 reads the first number and stores it in `number`. The `while` statement in Line 3 checks whether `number` is not equal to `SENTINEL`. (The variable `number` is the loop control variable.) If `number` is not equal to `SENTINEL`, the body of the `while` loop executes. The statement in Line 4 updates the value of `sum` by adding `number` to it. The statement in Line 5 increments the value of `count` by 1; the statement in Line 6 reads and stores the next number into `number`. The statements in Lines 4 through 6 repeat until the program reads the `SENTINEL`. The statement in Line 7 outputs the sum of the numbers, and the statements in Lines 8 through 10 output the average of the numbers.

Notice that the statement in Line 2 initializes the LCV `number`. The expression `number != SENTINEL` in Line 3 checks whether the value of `number` is not equal to `SENTINEL`. The statement in Line 6 reinitializes the LCV `number`.

Next, consider another example of a sentinel-controlled `while` loop. In this example, the user is prompted to enter the value to be processed. If the user wants to stop the program, he or she can enter the sentinel.

EXAMPLE 5-5

Telephone Digits

The following program reads the letter codes A to Z and prints the corresponding telephone digit. This program uses a sentinel-controlled **while** loop. To stop the program, the user is prompted for the sentinel, which is #. This is also an example of a nested control structure, in which **if...else**, **switch**, and the **while** loop are nested.

```
//*****
// Program: Telephone Digits
// This is an example of a sentinel-controlled loop. This
// program converts uppercase letters to their corresponding
// telephone digits.
//*****

#include <iostream>

using namespace std;

int main()
{
    char letter;                                //Line 1

    cout << "Program to convert uppercase "
         << "letters to their corresponding "
         << "telephone digits." << endl;        //Line 2

    cout << "To stop the program enter #."
         << endl;                                //Line 3

    cout << "Enter a letter: ";                //Line 4
    cin >> letter;                             //Line 5
    cout << endl;                             //Line 6

    while (letter != '#')                      //Line 7
    {
        cout << "The letter you entered is: "
             << letter << endl;                //Line 8
        cout << "The corresponding telephone "
             << "digit is: ";                  //Line 9

        if (letter >= 'A' && letter <= 'Z')    //Line 10
            switch (letter)                   //Line 11
            {
                case 'A':
                case 'B':
                case 'C':
                    cout << 2 << endl;          //Line 12
                    break;                     //Line 13
            }
    }
}
```

```

        case 'D':
        case 'E':
        case 'F':
            cout << 3 << endl;           //Line 14
            break;                       //Line 15
        case 'G':
        case 'H':
        case 'I':
            cout << 4 << endl;           //Line 16
            break;                       //Line 17
        case 'J':
        case 'K':
        case 'L':
            cout << 5 << endl;           //Line 18
            break;                       //Line 19
        case 'M':
        case 'N':
        case 'O':
            cout << 6 << endl;           //Line 20
            break;                       //Line 21
        case 'P':
        case 'Q':
        case 'R':
        case 'S':
            cout << 7 << endl;           //Line 22
            break;                       //Line 23
        case 'T':
        case 'U':
        case 'V':
            cout << 8 << endl;           //Line 24
            break;                       //Line 25
        case 'W':
        case 'X':
        case 'Y':
        case 'Z':
            cout << 9 << endl;           //Line 26
    }
    else //Line 27
        cout << "Invalid input." << endl; //Line 28

    cout << "\nEnter another uppercase "
        << "letter to find its "
        << "corresponding telephone digit."
        << endl; //Line 29
    cout << "To stop the program enter #."
        << endl; //Line 30

    cout << "Enter a letter: "; //Line 31
    cin >> letter; //Line 32
    cout << endl; //Line 33
} //end while

return 0;

}

```

Sample Run: In this sample run, the user input is shaded.

Program to convert uppercase letters to their corresponding telephone digits.

To stop the program enter #.

Enter a letter: **A**

The letter you entered is: A

The corresponding telephone digit is: 2

Enter another uppercase letter to find its corresponding telephone digit.

To stop the program enter #.

Enter a letter: **D**

The letter you entered is: D

The corresponding telephone digit is: 3

Enter another uppercase letter to find its corresponding telephone digit.

To stop the program enter #.

Enter a letter: **#**

This program works as follows. The statements in Lines 2 and 3 tell the user what to do. The statement in Line 4 prompts the user to input a letter; the statement in Line 5 reads and stores that letter into the variable `letter`. The **while** loop in Line 7 checks that the letter is `#`. If the letter entered by the user is not `#`, the body of the **while** loop executes. The statement in Line 8 outputs the letter entered by the user. The **if** statement in Line 10 checks whether the letter entered by the user is uppercase. The statement part of the **if** statement is the **switch** statement (Line 11). If the letter entered by the user is uppercase, the **expression** in the **if** statement (in Line 10) evaluates to **true** and the **switch** statement executes; if the letter entered by the user is not uppercase, the **else** statement (Line 27) executes. The statements in Lines 12 through 26 determine the corresponding telephone digit.

Once the current letter is processed, the statements in Lines 29 and 30 again inform the user what to do next. The statement in Line 31 prompts the user to enter a letter; the statement in Line 32 reads and stores that letter into the variable `letter`. (Note that the statement in Line 29 is similar to the statement in Line 2 and that the statements in Lines 30 through 33 are the same as the statements in Lines 3 through 6.) After the statement in Line 33 (at the end of the **while** loop) executes, the control goes back to the top of the **while** loop and the same process begins again. When the user enters `#`, the program terminates.

Notice that in this program, the variable `letter` is the loop control variable. First, it is initialized in Line 5 by the input statement, and then it is updated in Line 32. The expression in Line 7 checks whether `letter` is `#`.

NOTE

In the program in Example 5-5, you can write the statements between Lines 10 and 28 using a **switch** structure. (See Programming Exercise 3 at the end of this chapter.)

Case 3: Flag-Controlled **while** Loops

A **flag-controlled while loop** uses a **bool** variable to control the loop. Suppose found is a **bool** variable. The flag-controlled **while** loop takes the following form:

```

found = false;           //initialize the loop control variable

while (!found)           //test the loop control variable
{
    .
    .
    .
    if (expression)
        found = true; //update the loop control variable
    .
    .
    .
}

```

The variable `found`, which is used to control the execution of the `while` loop, is called a **flag variable**.

Example 5-6 further illustrates the use of a flag-controlled `while` loop.

EXAMPLE 5-6

Number Guessing Game

The following program randomly generates an integer greater than or equal to 0 and less than 100. The program then prompts the user to guess the number. If the user guesses the number correctly, the program outputs an appropriate message. Otherwise, the program checks whether the guessed number is less than the random number. If the guessed number is less than the random number generated by the program, the program outputs the message “Your guess is lower than the number. Guess again!”; otherwise, the program outputs the message “Your guess is higher than the number. Guess again!”. The program then prompts the user to enter another number. The user is prompted to guess the random number until the user enters the correct number.

To generate a random number, you can use the function `rand` of the header file `cstdlib`. For example, the expression `rand()` returns an `int` value between 0 and 32767. Therefore, the statement:

```
cout << rand() << ", " << rand() << endl;
```

will output two numbers that appear to be random. However, each time the program is run, this statement will output the same random numbers. This is because the function `rand` uses an algorithm that produces the same sequence of random numbers each time the program is executed on the same system. To generate different random numbers each time the program is executed, you also use the function `srand` of the header file `cstdlib`. The function `srand` takes as input an `unsigned int`, which acts as the seed for the algorithm. By specifying different seed values, each time the program is executed, the function `rand` will generate a different sequence of random numbers. To specify a different seed, you can use the function `time` of the header file `ctime`, which returns the number of seconds elapsed since January 1, 1970. For example, consider the following statements:

```
srand(time(0));
num = rand() % 100;
```

The first statement sets the seed, and the second statement generates a random number greater than or equal to 0 and less than 100. Note how the function `time` is used. It is used with an argument, that is, parameter, which is 0.

The program uses the `bool` variable `isGuessed` to control the loop. The `bool` variable `isGuessed` is initialized to `false`. It is set to `true` when the user guesses the correct number.

```
//Flag-controlled while loop.
//Number guessing game.

#include <iostream>
#include <cstdlib>
#include <ctime>

using namespace std;

int main()
{
    //declare the variables
    int num;           //variable to store the random
                      //number
    int guess;         //variable to store the number
                      //guessed by the user
    bool isGuessed;    //boolean variable to control
                      //the loop

    srand(time(0));    //Line 1
    num = rand() % 100; //Line 2

    isGuessed = false; //Line 3

    while (!isGuessed) //Line 4
    {                  //Line 5
        cout << "Enter an integer greater"
              << " than or equal to 0 and "
              << "less than 100: "; //Line 6

        cin >> guess; //Line 7
        cout << endl; //Line 8

        if (guess == num) //Line 9
        {                  //Line 10
            cout << "You guessed the correct "
                  << "number." << endl; //Line 11
            isGuessed = true; //Line 12
        }                  //Line 13
        else if (guess < num) //Line 14
            cout << "Your guess is lower than the "
                  << "number.\n Guess again!"
                  << endl; //Line 15
    }
}
```

```

        else //Line 16
            cout << "Your guess is higher than "
                << "the number.\n Guess again!"
                << endl; //Line 17
    } //end while //Line 18

    return 0;
}

```

Sample Run: In this sample run, the user input is shaded.

Enter an integer greater than or equal to 0 and less than 100: 45

Your guess is higher than the number.

Guess again!

Enter an integer greater than or equal to 0 and less than 100: 20

Your guess is lower than the number.

Guess again!

Enter an integer greater than or equal to 0 and less than 100: 35

Your guess is higher than the number.

Guess again!

Enter an integer greater than or equal to 0 and less than 100: 28

Your guess is lower than the number.

Guess again!

Enter an integer greater than or equal to 0 and less than 100: 32

You guessed the correct number.

The preceding program works as follows: The statement in Line 2 creates an integer greater than or equal to 0 and less than 100 and stores this number in the variable `num`. The statement in Line 3 sets the `bool` variable `isGuessed` to `false`. The expression in the `while` loop at Line 4 evaluates the expression `!isGuessed`. If `isGuessed` is `false`, then `!isGuessed` is `true` and the body of the `while` loop executes; if `isGuessed` is `true`, then `!isGuessed` is `false`, so the `while` loop terminates.

The statement in Line 6 prompts the user to enter an integer greater than or equal to 0 and less than 100. The statement in Line 7 stores the number entered by the user in the variable `guess`. The expression in the `if` statement in Line 9 determines whether the value of `guess` is the same as `num`, that is, if the user guessed the number correctly. If the value of `guess` is the same as `num`, the statement in Line 11 outputs the message:

You guessed the correct number.

The statement in Line 12 sets the variable `isGuessed` to `true`. The control then goes back to Line 3. Because `done` is `true`, `!isGuessed` is `false` and the `while` loop terminates. If the expression in Line 9 evaluates to `false`, then the `else` statement in Line 14 determines whether the value of `guess` is less than or greater than `num` and outputs the appropriate message.

Case 4: EOF-Controlled while Loops

If the data file is frequently altered (for example, if data is frequently added or deleted), it's best not to read the data with a sentinel value. Someone might accidentally erase the sentinel value or add data past the sentinel, especially if the programmer and the data entry person are different people. Also, it can be difficult at times to select a good sentinel value. In such situations, you can use an **end-of-file (EOF)-controlled while loop**.

Until now, we have used an input stream variable, such as `cin`, and the extraction operator, `>>`, to read and store data into variables. However, the input stream variable can also return a value after reading data, as follows:

1. If the program has reached the end of the input data, the input stream variable returns the logical value `false`.
2. If the program reads any faulty data (such as a `char` value into an `int` variable), the input stream enters the fail state. Once a stream enters the fail state, any further I/O operations using that stream are considered to be null operations; that is, they have no effect. Unfortunately, the computer does not halt the program or give any error messages. It just continues executing the program, silently ignoring each additional attempt to use that stream. In this case, the input stream variable returns the value `false`.
3. In cases other than (1) and (2), the input stream variable returns the logical value `true`.

You can use the value returned by the input stream variable to determine whether the program has reached the end of the input data. Because the input stream variable returns the logical value `true` or `false`, in a `while` loop, it can be considered a logical expression.

The following is an example of an EOF-controlled `while` loop:

```
cin >> variable;      //initialize the loop control variable

while (cin)           //test the loop control variable
{
    .
    .
    .
    cin >> variable; //update the loop control variable
    .
    .
    .
}
```

Notice that here, the variable `cin` acts as the loop control variable.

eof Function

In addition to checking the value of an input stream variable, such as `cin`, to determine whether the end of the file has been reached, C++ provides a function that you can use with an input stream variable to determine the end-of-file status. This function is called

`eof`. Like the I/O functions—such as `get`, `ignore`, and `peek`, discussed in Chapter 3—the function `eof` is a member of the data type `istream`.

The syntax to use the function `eof` is:

```
istreamVar.eof()
```

in which `istreamVar` is an input stream variable, such as `cin`.

Suppose you have the declaration:

```
ifstream infile;
```

Further suppose that you opened a file using the variable `infile`. Consider the expression:

```
infile.eof()
```

This is a logical (Boolean) expression. The value of this expression is `true` if the program has read past the end of the input file, `infile`; otherwise, the value of this expression is `false`.

This method of determining the end-of-file status (that is, using the function `eof`) works best if the input is text. The earlier method of determining the end-of-file status works best if the input consists of numeric data.

Suppose you have the declaration:

```
ifstream infile;
char ch;
```

```
infile.open("inputDat.dat");
```

The following `while` loop continues to execute as long as the program has not reached the end of the file.

```
infile.get(ch);

while (!infile.eof())
{
    cout << ch;
    infile.get(ch);
}
```

As long as the program has not reached the end of the input file, the expression:

```
infile.eof()
```

is `false` and so the expression:

```
!infile.eof()
```

in the `while` statement is `true`. When the program reads past the end of the input file, the expression:

```
infile.eof()
```

becomes **true**, so the expression:

```
!infile.eof()
```

in the **while** statement becomes **false** and the loop terminates.

NOTE

In the Windows console environment, the end-of-file marker is entered using **Ctrl+z** (hold the **Ctrl** key and press **z**). In the UNIX environment, the end-of-file marker is entered using **Ctrl+d** (hold the **Ctrl** key and press **d**).

EXAMPLE 5-7

The following code uses an EOF-controlled **while** loop to find the sum of a set of numbers:

```
int sum = 0;
int num;

cin >> num;

while (cin)
{
    sum = sum + num;    //Add the number to sum
    cin >> num;        //Get the next number
}

cout << "Sum = " << sum << endl;
```

EXAMPLE 5-8

Suppose we are given a file consisting of students' names and their test scores, a number between 0 and 100 (inclusive). Each line in the file consists of a student name followed by the test score. We want a program that outputs each student's name followed by the test score followed by the grade. The program also needs to output the average test score for the class. Consider the following program:

```
// This program reads data from a file consisting of students'
// names and their test scores. The program outputs each student's
// name followed by the test score followed by the grade. The
// program also outputs the average test score for all the students.

#include <iostream>                                //Line 1
#include <fstream>                                  //Line 2
#include <string>                                    //Line 3
#include <iomanip>                                    //Line 4

using namespace std;                               //Line 5
```

```

int main() //Line 6
{ //Line 7
    //Declare variables to manipulate data
    string firstName; //Line 8
    string lastName; //Line 9
    double testScore; //Line 10
    char grade = ' '; //Line 11
    double sum = 0; //Line 12
    int count = 0; //Line 13

    //Declare stream variables
    ifstream inFile; //Line 14
    ofstream outFile; //Line 15

    //Open input file
    inFile.open("Ch5_stData.txt"); //Line 16

    if (!inFile) //Line 17
    { //Line 18
        cout << "Cannot open input file. "
              << "Program terminates!" << endl; //Line 19
        return 1; //Line 20
    } //Line 21

    //Open output file
    outFile.open("Ch5_stData.out"); //Line 22

    outFile << fixed << showpoint << setprecision(2); //Line 23

    inFile >> firstName >> lastName; //read the name Line 24
    inFile >> testScore; //read the test score Line 25

    while (inFile) //Line 26
    { //Line 27
        sum = sum + testScore; //update sum Line 28
        count++; //increment count Line 29

        //determine the grade
        switch (static_cast<int> (testScore) / 10) //Line 30
        { //Line 31
            case 0: //Line 32
            case 1: //Line 33
            case 2: //Line 34
            case 3: //Line 35
            case 4: //Line 36
            case 5: //Line 37
                grade = 'F'; //Line 38
                break; //Line 39

            case 6: //Line 40
                grade = 'D'; //Line 41
                break; //Line 42

            case 7: //Line 43
                grade = 'C'; //Line 44
                break; //Line 45

```

```

        case 8:                                //Line 46
            grade = 'B';                        //Line 47
            break;                              //Line 48

        case 9:                                //Line 49
        case 10:                               //Line 50
            grade = 'A';                        //Line 51
            break;                              //Line 52

        default:                               //Line 53
            cout << "Invalid score." << endl;  //Line 54
    } //end switch                             //Line 55

    outFile << left << setw(12) << firstName
            << setw(12) << lastName
            << right << setw(4) << testScore
            << setw(2) << grade << endl;        //Line 56

    inFile >> firstName >> lastName; //read the name Line 57
    inFile >> testScore;             //read the test score Line 58
} //end while                        //Line 59

outFile << endl;                     //Line 60

if (count != 0)                      //Line 61
    outFile << "Class Average: " << sum / count
            << endl;                 //Line 62
else                                  //Line 63
    outFile << "No data." << endl;   //Line 64

inFile.close();                      //Line 65
outFile.close();                     //Line 66

return 0;                            //Line 67
}                                    //Line 68

```

Sample Run:**Input File:**

```

Steve Gill 89
Rita Johnson 91.5
Randy Brown 85.5
Seema Arora 76.5
Samir Mann 73
Samantha McCoy 88.5

```

Output File:

| | | |
|----------|---------|---------|
| Steve | Gill | 89.00 B |
| Rita | Johnson | 91.50 A |
| Randy | Brown | 85.50 B |
| Seema | Arora | 76.50 C |
| Samir | Mann | 73.00 C |
| Samantha | McCoy | 88.50 B |

Class Average: 84.00

The preceding program works as follows. The statements in Lines 8 to 13 declare and initialize variables needed by the program. The statement in Lines 14 and 15 declares `inFile` to be an `ifstream` variable and `outFile` to be an `ofstream` variable. The statement in Line 16 opens the input file using the variable `inFile`. If the input file does not exist, the statements in Lines 17 to 21 output an appropriate message and terminate the program. The statement in Line 22 opens the output file using the variable `outFile`. The statement in Line 23 sets the output of floating-point numbers to two decimal places in a fixed form with trailing zeros.

The statements in Lines 24 and 25 and the `while` loop in Line 26 read each student's first name, last name, and test score and then output the name followed by the test score followed by the grade. Specifically, the statement in Lines 24 and 57 reads the first and last name; the statement in Lines 25 and 58 reads the test score. The statement in Line 28 updates the value of `sum`. (After reading all the data, the value of `sum` stores the sum of all the test scores.) The statement in Line 29 updates the value of `count`. (The variable `count` stores the number of students in the class.) The `switch` statement from Lines 30 to 55 determines the grade from `testScore` and stores it in the variable `grade`. The statement in Line 56 outputs a student's first name, last name, test score, and grade.

The `if...else` statement in Lines 61 to 64 outputs the class average and the statements in Lines 65 and 66 close the files.

The Programming Example: Checking Account Balance, available on the Web site accompanying this book, further illustrates how to use an EOF-controlled `while` loop in a program.

More on Expressions in `while` Statements

In the examples of the previous sections, the expression in the `while` statement is quite simple. In other words, the `while` loop is controlled by a single variable. However, there are situations when the expression in the `while` statement may be more complex.

For example, the program in Example 5-6 uses a flag-controlled `while` loop to implement the Number Guessing Game. However, the program gives as many tries as the user needs to guess the number. Suppose you want to give the user no more than five tries to guess the number. If the user does not guess the number correctly within five tries, then the program outputs the random number generated by the program as well as a message that you have lost the game. In this case, you can write the `while` loop as follows (assume that `noOfGuesses` is an `int` variable initialized to 0):

```
while ((noOfGuesses < 5) && (!isGuessed))
{
    cout << "Enter an integer greater than or equal to 0 and "
          << "less than 100: ";
    cin >> guess;
    cout << endl;
```

```

noOfGuesses++;
if (guess == num)
{
    cout << "Winner!. You guessed the correct number."
        << endl;
    isGuessed = true;
}
else if (guess < num)
    cout << "Your guess is lower than the number.\n"
        << "Guess again!" << endl;
else
    cout << "Your guess is higher than the number.\n"
        << "Guess again!" << endl;
} //end while

```

You also need the following code to be included after the `while` loop in case the user cannot guess the correct number in five tries.

```

if (!isGuessed)
    cout << "You lose! The correct number is " << num << endl;

```

Programming Exercise 16 at the end of this chapter asks you to write a complete C++ program to implement the Number Guessing Game in which the user has, at most, five tries to guess the number.

As you can see from the preceding `while` loop, the expression in a `while` statement can be complex. The main objective of a `while` loop is to repeat certain statement(s) until certain conditions are met.

PROGRAMMING EXAMPLE: Fibonacci Number

So far, you have seen several examples of loops. Recall that in C++, `while` loops are used when a certain statement(s) must be executed repeatedly until certain conditions are met. Following is a C++ program that uses a `while` loop to find a **Fibonacci number**.

Consider the following sequence of numbers:

1, 1, 2, 3, 5, 8, 13, 21, 34,

Given the first two numbers of the sequence (say, a_1 and a_2), the n th number a_n , $n \geq 3$, of this sequence is given by:

$$a_n = a_{n-1} + a_{n-2}$$

Thus:

$$a_3 = a_2 + a_1 = 1 + 1 = 2,$$

$$a_4 = a_3 + a_2 = 2 + 1 = 3,$$

and so on.

Such a sequence is called a **Fibonacci sequence**. In the preceding sequence, $a_2 = 1$ and $a_1 = 1$. However, given any first two numbers, using this process, you can determine the n th number, $a_n, n \geq 3$, of the sequence. The number determined this way is called the **n th Fibonacci number**. Suppose $a_2 = 6$ and $a_1 = 3$.

Then:

$$a_3 = a_2 + a_1 = 6 + 3 = 9; a_4 = a_3 + a_2 = 9 + 6 = 15$$

Next, we write a program that determines the n th Fibonacci number given the first two numbers.

Input The first two Fibonacci numbers and the desired Fibonacci number.

Output The n th Fibonacci number.

PROBLEM ANALYSIS AND ALGORITHM DESIGN

To find, say, the tenth Fibonacci number of a sequence, you must first find a_9 and a_8 , which requires you to find a_7 and a_6 , and so on. Therefore, to find a_{10} , you must first find $a_3, a_4, a_5, \dots, a_9$. This discussion translates into the following algorithm:

1. Get the first two Fibonacci numbers.
2. Get the desired Fibonacci number. That is, get the position, n , of the Fibonacci number in the sequence.
3. Calculate the next Fibonacci number by adding the previous two elements of the Fibonacci sequence.
4. Repeat Step 3 until the n th Fibonacci number is found.
5. Output the n th Fibonacci number.

Note that the program assumes that the first number of the Fibonacci sequence is less than or equal to the second number of the Fibonacci sequence, and both numbers are nonnegative. Moreover, the program also assumes that the user enters a valid value for the position of the desired number in the Fibonacci sequence; that is, it is a positive integer. (See Programming Exercise 12 at the end of this chapter.)

Variables Because the last two numbers must be known in order to find the current Fibonacci number, you need the following variables: two variables—say, **previous1** and **previous2** to hold the previous two numbers of the Fibonacci sequence; and one variable—say, **current**—to hold the current Fibonacci number. The number of times that Step 2 of the algorithm repeats depends on the position of the Fibonacci number you are calculating. For example, if you want to calculate the tenth Fibonacci number, you must execute Step 3 eight times. (Remember—the user gives the first two numbers of the Fibonacci sequence.) Therefore, you need a variable to store the number of times Step 3 should execute. You also need a variable to track the number of times Step 3 has executed, the loop control variable. You therefore need five variables for the data manipulation:

```
int previous1; //variable to store the first Fibonacci number
int previous2; //variable to store the second Fibonacci number
```

```

int current;    //variable to store the current
                //Fibonacci number
int counter;    //loop control variable
int nthFibonacci; //variable to store the desired
                //Fibonacci number

```

To calculate the third Fibonacci number, add the values of `previous1` and `previous2` and store the result in `current`. To calculate the fourth Fibonacci number, add the value of the second Fibonacci number (that is, `previous2`) and the value of the third Fibonacci number (that is, `current`). Thus, when the fourth Fibonacci number is calculated, you no longer need the first Fibonacci number. Instead of declaring additional variables, which could be too many, after calculating a Fibonacci number to determine the next Fibonacci number, `current` becomes `previous2` and `previous2` becomes `previous1`. Therefore, you can again use the variable `current` to store the next Fibonacci number. This process is repeated until the desired Fibonacci number is calculated. Initially, `previous1` and `previous2` are the first two elements of the sequence, supplied by the user. From the preceding discussion, it follows that you need five variables.

MAIN ALGORITHM

1. Prompt the user for the first two numbers—that is, `previous1` and `previous2`.
2. Read (input) the first two numbers into `previous1` and `previous2`.
3. Output the first two Fibonacci numbers. (Echo input.)
4. Prompt the user for the position of the desired Fibonacci number.
5. Read the position of the desired Fibonacci number into `nthFibonacci`.
6.
 - a. `if (nthFibonacci == 1)`
the desired Fibonacci number is the first Fibonacci number.
Copy the value of `previous1` into `current`.
 - b. `else if (nthFibonacci == 2)`
the desired Fibonacci number is the second Fibonacci number.
Copy the value of `previous2` into `current`.
 - c. `else` calculate the desired Fibonacci number as follows:
Because you already know the first two Fibonacci numbers of the sequence, start by determining the third Fibonacci number.
 - c.1. Initialize `counter` to 3 to keep track of the calculated Fibonacci numbers.
 - c.2. Calculate the next Fibonacci number, as follows:
`current = previous2 + previous1;`
 - c.3. Assign the value of `previous2` to `previous1`.
 - c.4. Assign the value of `current` to `previous2`.
 - c.5. Increment `counter`.

Repeat Steps c.2 through c.5 until the Fibonacci number you want is calculated.

The following **while** loop executes Steps c.2 through c.5 and determines the *n*th Fibonacci number.

```
while (counter <= nthFibonacci)
{
    current = previous2 + previous1;
    previous1 = previous2;
    previous2 = current;
    counter++;
}
```

7. Output the `nthFibonacci` number, which is `current`.

COMPLETE PROGRAM LISTING

```

//*****
// Authors: D.S. Malik
//
// Program: nth Fibonacci number
// Given the first two numbers of a Fibonacci sequence, this
// program determines and outputs the desired number of the
// Fibonacci sequence.
//*****

#include <iostream>

using namespace std;

int main()
{
    //Declare variables
    int previous1;
    int previous2;
    int current;
    int counter;
    int nthFibonacci;

    cout << "Enter the first two Fibonacci "
         << "numbers: ";
    cin >> previous1 >> previous2;
    cout << endl;
    cout << "The first two Fibonacci numbers are "
         << previous1 << " and " << previous2
         << endl;
    cout << "Enter the position of the desired "
         << "Fibonacci number: ";
    cin >> nthFibonacci;
    cout << endl;

    if (nthFibonacci == 1)
        current = previous1;

```

```

else if (nthFibonacci == 2)                //Step 6.b
    current = previous2;
else                                        //Step 6.c
{
    counter = 3;                            //Step 6.c.1

    //Steps 6.c.2 - 6.c.5
    while (counter <= nthFibonacci)
    {
        current = previous2 + previous1;    //Step 6.c.2
        previous1 = previous2;              //Step 6.c.3
        previous2 = current;                //Step 6.c.4
        counter++;                           //Step 6.c.5
    } //end while
} //end else

cout << "The Fibonacci number at position "
    << nthFibonacci << " is " << current
    << endl;                                //Step 7

return 0;
} //end main

```

Sample Runs: In these sample runs, the user input is shaded.

Sample Run 1:

```

Enter the first two Fibonacci numbers: 12 16
The first two Fibonacci numbers are 12 and 16
Enter the position of the desired Fibonacci number: 10
The Fibonacci number at position 10 is 796

```

Sample Run 2:

```

Enter the first two Fibonacci numbers: 1 1
The first two Fibonacci numbers are 1 and 1
Enter the position of the desired Fibonacci number: 15
The Fibonacci number at position 15 is 610

```

for Looping (Repetition) Structure

The **while** loop discussed in the previous section is general enough to implement most forms of repetitions. The C++ **for** looping structure discussed here is a specialized form of the **while** loop. Its primary purpose is to simplify the writing of counter-controlled loops. For this reason, the **for** loop is typically called a counted or indexed **for** loop.

The general form of the **for** statement is:

```
for (initial statement; loop condition; update statement)
    statement
```

The **initial statement**, **loop condition**, and **update statement** (called **for** loop control statements) enclosed within the parentheses control the body (**statement**) of the **for** statement. Figure 5-2 shows the flow of execution of a **for** loop.




FIGURE 5-2 **for** loop

The **for** loop executes as follows:

1. The **initial statement** executes.
2. The **loop condition** is evaluated. If the **loop condition** evaluates to **true**:
 - i. Execute the **for** loop **statement**.
 - ii. Execute the **update statement** (the third expression in the parentheses).
3. Repeat Step 2 until the **loop condition** evaluates to **false**.

The **initial statement** usually initializes a variable (called the **for** loop **control**, or **for indexed, variable**).

In C++, **for** is a reserved word.

NOTE

As the name implies, the initial statement in the **for** loop is the first statement to execute; it executes only once.

EXAMPLE 5-9

The following **for** loop prints the first 10 nonnegative integers:

```
for (i = 0; i < 10; i++)
    cout << i << " ";
cout << endl;
```

The **initial statement**, `i = 0;`, initializes the **int** variable `i` to 0. Next, the loop condition, `i < 10`, is evaluated. Because `0 < 10` is **true**, the print statement executes and outputs 0. The **update statement**, `i++`, then executes, which sets the value of `i` to 1. Once again, the loop condition is evaluated, which is still **true**, and so on. When `i` becomes 10, the loop condition evaluates to **false**, the **for** loop terminates, and the statement following the **for** loop executes.

A **for** loop can have either a simple or compound statement.

The following examples further illustrate how a **for** loop executes.

EXAMPLE 5-10

1. The following **for** loop outputs **Hello!** and a star (on separate lines) five times:

```
for (i = 1; i <= 5; i++)
{
    cout << "Hello!" << endl;
    cout << "*" << endl;
}
```

2. Consider the following **for** loop:

```
for (i = 1; i <= 5; i++)
    cout << "Hello!" << endl;
    cout << "*" << endl;
```

This loop outputs **Hello!** five times and the star only once. Note that the **for** loop controls only the first output statement because the two output statements are not made into a compound statement. Therefore, the first output statement executes five times because the **for** loop body executes five times. After the **for** loop executes, the second output statement executes only once. The indentation, which is ignored by the compiler, is nevertheless misleading.

EXAMPLE 5-11

The following **for** loop executes five empty statements:

```
for (i = 0; i < 5; i++);      //Line 1
    cout << "*" << endl;    //Line 2
```

The semicolon at the end of the **for** statement (before the output statement, Line 1) terminates the **for** loop. The action of this **for** loop is empty, that is, null.

The preceding examples show that care is required in getting a **for** loop to perform the desired action.

The following are some comments on **for** loops:

- If the **loop condition** is initially **false**, the loop body does not execute.
- The **update expression**, when executed, changes the value of the loop control variable (initialized by the initial expression), which eventually sets the value of the **loop condition** to **false**. The **for** loop body executes indefinitely if the **loop condition** is always **true**.
- C++ allows you to use fractional values for loop control variables of the **double** type (or any real data type). Because different computers can give these loop control variables different results, you should avoid using such variables.
- A semicolon at the end of the **for** statement (just before the body of the loop) is a semantic error. In this case, the action of the **for** loop is empty.
- In the **for** statement, if the **loop condition** is omitted, it is assumed to be **true**.
- In a **for** statement, you can omit all three statements—**initial statement**, **loop condition**, and **update statement**. The following is a legal **for** loop:

```
for (;;)
    cout << "Hello" << endl;
```

This is an infinite **for** loop, continuously printing the word **Hello**.

Following are more examples of **for** loops.

EXAMPLE 5-12

You can count backward using a **for** loop if the **for** loop control expressions are set correctly.

For example, consider the following **for** loop:

```
for (i = 10; i >= 1; i--)
    cout << " " << i;
cout << endl;
```

The output is:

10 9 8 7 6 5 4 3 2 1

In this **for** loop, the variable **i** is initialized to 10. After each iteration of the loop, **i** is decremented by 1. The loop continues to execute as long as **i** \geq 1.

EXAMPLE 5-13

You can increment (or decrement) the loop control variable by any fixed number. In the following **for** loop, the variable is initialized to 1; at the end of the **for** loop, **i** is incremented by 2. This **for** loop outputs the first 10 positive odd integers.

```
for (i = 1; i <= 20; i = i + 2)
    cout << " " << i;
cout << endl;
```

EXAMPLE 5-14

Suppose that **i** is an **int** variable.

1. Consider the following **for** loop:

```
for (i = 10; i <= 9; i++)
    cout << i << " ";
cout << endl;
```

In this **for** loop, the initial statement sets **i** to 10. Because initially the loop condition (**i** \leq 9) is **false**, nothing happens.

2. Consider the following **for** loop:

```
for (i = 9; i >= 10; i--)
    cout << i << " ";
cout << endl;
```

In this **for** loop, the initial statement sets **i** to 9. Because initially the loop condition (**i** \geq 10) is **false**, nothing happens.

3. Consider the following **for** loop:

```
for (i = 10; i <= 10; i++)           //Line 1
    cout << i << " ";               //Line 2
cout << endl;                        //Line 3
```

In this **for** loop, the initial statement sets **i** to 10. The loop condition (**i** \leq 10) evaluates to **true**, so the output statement in Line 2 executes, which outputs 10.

Next, the update statement increments the value of `i` by 1, so the value of `i` becomes 11. Now the loop condition evaluates to `false` and the `for` loop terminates. Note that the output statement in Line 2 executes only once.

4. Consider the following `for` loop:

```
for (i = 1; i <= 10; i++); //Line 1
    cout << i << " ";    //Line 2
cout << endl;            //Line 3
```

This `for` loop has no effect on the output statement in Line 2. The semicolon at the end of the `for` statement terminates the `for` loop; the action of the `for` loop is thus empty. The output statement is all by itself and executes only once.

5. Consider the following `for` loop:

```
for (i = 1; ; i++)
    cout << i << " ";
cout << endl;
```

In this `for` loop, because the loop condition is omitted from the `for` statement, the loop condition is always `true`. This is an infinite loop.

EXAMPLE 5-15

In this example, a `for` loop reads five numbers and finds their sum and average. Consider the following program code, in which `i`, `newNum`, `sum`, and `average` are `int` variables.

```
sum = 0;

for (i = 1; i <= 5; i++)
{
    cin >> newNum;
    sum = sum + newNum;
}

average = sum / 5;
cout << "The sum is " << sum << endl;
cout << "The average is " << average << endl;
```

In the preceding `for` loop, after reading a `newNum`, this value is added to the previously calculated (partial) `sum` of all the numbers read before the current number. The variable `sum` is initialized to 0 before the `for` loop. Thus, after the program reads the first number and adds it to the value of `sum`, the variable `sum` holds the correct `sum` of the first number.

NOTE

The syntax of the **for** loop, which is:

```
for (initial expression; logical expression; update expression)
    statement
```

is functionally equivalent to the following **while** statement:

```
initial expression
while (expression)
{
    statement
    update expression
}
```

For example, the following **for** and **while** loops are equivalent:

| | |
|----------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------|
| <pre>for (int i = 0; i < 10; i++) cout << i << " "; cout << endl;</pre> | <pre>int i = 0; while (i < 10) { cout << i << " "; i++; } cout << endl;</pre> |
|----------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------|

If the number of iterations of a loop is known or can be determined in advance, typically programmers use a **for** loop.

EXAMPLE 5-16 (FIBONACCI NUMBER PROGRAM: REVISITED)

The Programming Example: Fibonacci Number given in the previous section uses a **while** loop to determine the desired Fibonacci number. You can replace the **while** loop with an equivalent **for** loop as follows:

```
for (counter = 3; counter <= nthFibonacci; counter++)
{
    current = previous2 + previous1;
    previous1 = previous2;
    previous2 = current;
    counter++;
} //end for
```

The complete program listing of the program that uses a **for** loop to determine the desired Fibonacci number is given at the Web site accompanying this book. The program is named `Ch5_FibonacciNumberUsingAForLoop.cpp`.

In the following C++ program, we recommend that you walk through each step.

EXAMPLE 5-17

The following C++ program finds the sum of the first *n* positive integers.

//Program to determine the sum of the first n positive integers.

```
#include <iostream>

using namespace std;

int main()
{
    int counter;    //loop control variable
    int sum;        //variable to store the sum of numbers
    int n;          //variable to store the number of
                  //first positive integers to be added

    cout << "Line 1: Enter the number of positive "
          << "integers to be added: ";           //Line 1
    cin >> n;                                     //Line 2
    sum = 0;                                       //Line 3
    cout << endl;                                 //Line 4

    for (counter = 1; counter <= n; counter++)    //Line 5
        sum = sum + counter;                     //Line 6

    cout << "Line 7: The sum of the first " << n
          << " positive integers is " << sum
          << endl;                               //Line 7

    return 0;
}
```

Sample Run: In this sample run, the user input is shaded.

Line 1: Enter the number of positive integers to be added: 100

Line 7: The sum of the first 100 positive integers is 5050

The statement in Line 1 prompts the user to enter the number of positive integers to be added. The statement in Line 2 stores the number entered by the user in *n*, and the statement in Line 3 initializes *sum* to 0. The **for** loop in Line 5 executes *n* times. In the **for** loop, *counter* is initialized to 1 and is incremented by 1 after each iteration of the loop. Therefore, *counter* ranges from 1 to *n*. Each time through the loop, the value of *counter* is added to *sum*. The variable *sum* was initialized to 0, *counter* ranges from 1 to *n*, and the current value of *counter* is added to the value of *sum*. Therefore, after the **for** loop executes, *sum* contains the sum of the first *n* values, which in the sample run is 100 positive integers.

Recall that putting one control structure statement inside another is called **nesting**. The following programming example demonstrates a simple instance of nesting. It also nicely demonstrates counting.

PROGRAMMING EXAMPLE: Classifying Numbers

This program reads a given set of integers and then prints the number of odd and even integers. It also outputs the number of zeros.

The program reads 20 integers, but you can easily modify it to read any set of numbers. In fact, you can modify the program so that it first prompts the user to specify how many integers are to be read.

Input 20 integers—positive, negative, or zeros.

Output The number of zeros, even numbers, and odd numbers.

PROBLEM ANALYSIS AND ALGORITHM DESIGN

After reading a number, you need to check whether it is even or odd. Suppose the value is stored in **number**. Divide **number** by 2 and check the remainder. If the remainder is 0, **number** is even. Increment the even count and then check whether **number** is 0. If it is, increment the zero count. If the remainder is not 0, increment the odd count.

The program uses a **switch** statement to decide whether **number** is odd or even. Suppose that **number** is odd. Dividing by 2 gives the remainder 1 if **number** is positive and the remainder -1 if it is negative. If **number** is even, dividing by 2 gives the remainder 0 whether **number** is positive or negative. You can use the mod operator, **%**, to find the remainder. For example:

$6 \% 2 = 0$; $-4 \% 2 = 0$; $-7 \% 2 = -1$; $15 \% 2 = 1$

Repeat the preceding process of analyzing a number for each number in the list.

This discussion translates into the following algorithm:

1. For each number in the list:
 - a. Get the number.
 - b. Analyze the number.
 - c. Increment the appropriate count.
2. Print the results.

Variables Because you want to count the number of zeros, even numbers, and odd numbers, you need three variables of type **int**—say, **zeros**, **evens**, and **odds**—to track the counts. You also need a variable—say, **number**—to read and store the number to be analyzed and another variable—say, **counter**—to count the numbers analyzed. Therefore, you need the following variables in the program:

```

int counter;    //loop control variable
int number;    //variable to store the number read
int zeros;     //variable to store the zero count
int evens;     //variable to store the even count
int odds;      //variable to store the odd count

```

Clearly, you must initialize the variables `zeros`, `evens`, and `odds` to zero. You can initialize these variables when you declare them.

MAIN ALGORITHM

1. Initialize the variables.
2. Prompt the user to enter 20 numbers.
3. For each number in the list:
 - a. Read the number.
 - b. Output the number (echo input).
 - c. If the number is even:


```

          {
              i. Increment the even count.
              ii. If the number is zero, increment the zero count.
          }
          otherwise
              Increment the odd count.
          
```
4. Print the results.

Before writing the C++ program, let us describe Steps 1–4 in greater detail. It will be much easier for you to then write the instructions in C++.

1. Initialize the variables. You can initialize the variables `zeros`, `evens`, and `odds` when you declare them.
2. Use an output statement to prompt the user to enter 20 numbers.
3. For Step 3, you can use a `for` loop to process and analyze the 20 numbers. In pseudocode, this step is written as follows:

```

for (counter = 1; counter <= 20; counter++)
{
    read the number;
    output number;

    switch (number % 2)    // check the remainder
    {
        case 0:
            increment even count;
            if (number == 0)
                increment zero count;
            break;
    }
}

```

```

        case 1:
        case -1:
            increment odd count;
        } //end switch
    } //end for

```

4. Print the result. Output the value of the variables `zeros`, `evens`, and `odds`.

COMPLETE PROGRAM LISTING

```

//*****
// Author: D.S. Malik
//
// Program: Counts zeros, odds, and evens
// This program counts the number of odd and even numbers.
// The program also counts the number of zeros.
//*****

#include <iostream>
#include <iomanip>

using namespace std;

const int N = 20;

int main()
{
    //Declare variables
    int counter;    //loop control variable
    int number;     //variable to store the new number
    int zeros = 0;    //Step 1
    int odds = 0;     //Step 1
    int evens = 0;    //Step 1

    cout << "Please enter " << N << " integers, "
         << "positive, negative, or zeros."
         << endl;    //Step 2

    cout << "The numbers you entered are:" << endl;

    for (counter = 1; counter <= N; counter++)    //Step 3
    {
        cin >> number;    //Step 3a
        cout << number << " ";    //Step 3b

        //Step 3c
        switch (number % 2)

```

```

        {
            case 0:
                evens++;
                if (number == 0)
                    zeros++;
                break;
            case 1:
            case -1:
                odds++;
        } //end switch
    } //end for loop

    cout << endl;

    //Step 4
    cout << "There are " << evens << " evens, "
        << "which includes " << zeros << " zeros."
        << endl;
    cout << "The number of odd numbers is: " << odds
        << endl;

    return 0;
}

```

Sample Run: In this sample run, the user input is shaded.

Please enter 20 integers, positive, negative, or zeros.

The numbers you entered are:

0 0 -2 -3 -5 6 7 8 0 3 0 -23 -8 0 2 9 0 12 67 54

0 0 -2 -3 -5 6 7 8 0 3 0 -23 -8 0 2 9 0 12 67 54

There are 13 evens, which includes 6 zeros.

The number of odd numbers is: 7

We recommend that you do a walk-through of this program using the above sample input.

do...while Looping (Repetition) Structure

This section describes the third type of looping or repetition structure, called a **do...while** loop. The general form of a **do...while** statement is as follows:

```

do
    statement
while (expression);

```

Of course, **statement** can be either a simple or compound statement. If it is a compound statement, enclose it between braces. Figure 5-3 shows the flow of execution of a **do...while** loop.




FIGURE 5-3 do...while loop

In C++, **do** is a reserved word.

The **statement** executes first, and then the **expression** is evaluated. If the **expression** evaluates to **true**, the **statement** executes again. As long as the **expression** in a **do...while** statement is **true**, the **statement** executes. To avoid an infinite loop, you must, once again, make sure that the loop body contains a statement that ultimately makes the **expression** **false** and assures that it exits properly.

EXAMPLE 5-18

```

i = 0;

do
{
    cout << i << " ";
    i = i + 5;
}
while (i <= 20);
  
```

The output of this code is:

```
0 5 10 15 20
```

After 20 is output, the statement:

```
i = i + 5;
```

changes the value of **i** to 25 and so **i <= 20** becomes **false**, which halts the loop.

In a **while** and **for** loop, the loop condition is evaluated before executing the body of the loop. Therefore, **while** and **for** loops are called **pretest loops**. On the other hand, the loop condition in a **do...while** loop is evaluated after executing the body of the loop. Therefore, **do...while** loops are called **posttest loops**.

Because the **while** and **for** loops both have entry conditions, these loops may never activate. The **do...while** loop, on the other hand, has an exit condition and therefore always executes the statement at least once.

EXAMPLE 5-19

Consider the following two loops:

```
a. i = 11;
   while (i <= 10)
   {
       cout << i << " ";
       i = i + 5;
   }
   cout << endl;

b. i = 11;
   do
   {
       cout << i << " ";
       i = i + 5;
   }
   while (i <= 10);

   cout << endl;
```

In (a), the **while** loop produces nothing. In (b), the **do...while** loop outputs the number 11 and also changes the value of **i** to 16.

A **do...while** loop can be used for input validation. Suppose that a program prompts a user to enter a test score, which must be greater than or equal to 0 and less than or equal to 50. If the user enters a score less than 0 or greater than 50, the user should be prompted to re-enter the score. The following **do...while** loop can be used to accomplish this objective:

```
int score;

do
{
    cout << "Enter a score between 0 and 50: ";
    cin >> score;
    cout << endl;
}
while (score < 0 || score > 50);
```

EXAMPLE 5-20**Divisibility Test by 3 and 9**

Suppose that m and n are integers and m is nonzero. Then m is called a **divisor** of n if $n = mt$ for some integer t ; that is, when m divides n , the remainder is 0.

Let $n = a_k a_{k-1} a_{k-2} \dots a_1 a_0$ be an integer. Let $s = a_k + a_{k-1} + a_{k-2} + \dots + a_1 + a_0$ be the sum of the digits of n . It is known that n is divisible by 3 and 9 if s is divisible by 3 and 9. In other words, an integer is divisible by 3 and 9 if and only if the sum of its digits is divisible by 3 and 9.

For example, suppose $n = 27193257$. Then $s = 2 + 7 + 1 + 9 + 3 + 2 + 5 + 7 = 36$. Because 36 is divisible by both 3 and 9, it follows that 27193257 is divisible by both 3 and 9.

Next, we write a program that determines whether a positive integer is divisible by 3 and 9 by first finding the sum of its digits and then checking whether the sum is divisible by 3 and 9.

To find the sum of the digits of a positive integer, we need to extract each digit of the number. Consider the number 951372. Note that $951372 \% 10 = 2$, which is the last digit of 951372. Also note that $951372 / 10 = 95137$; that is, when the number is divided by 10, it removes the last digit. Next, we repeat this process on the number 95137. Of course, we need to add the extracted digits.

Suppose that `sum` and `num` are `int` variables and the positive integer is stored in `num`. We thus have the following algorithm to find the sum of the digits:

```
sum = 0;

do
{
    sum = sum + num % 10; //extract the last digit
                        //and add it to sum
    num = num / 10;      //remove the last digit
}
while (num > 0);
```

Using this algorithm, we can write the following program that uses a `do...while` loop to implement the preceding divisibility test algorithm.

```
//Program: Divisibility test by 3 and 9

#include <iostream>

using namespace std;

int main()
{
    int num, temp, sum;

    cout << "Enter a positive integer: ";
    cin >> num;
```

```

    cout << endl;

    temp = num;

    sum = 0;

    do
    {
        sum = sum + num % 10; //extract the last digit
                             //and add it to sum
        num = num / 10;       //remove the last digit
    }
    while (num > 0);

    cout << "The sum of the digits = " << sum << endl;

    if (sum % 3 == 0)
        cout << temp << " is divisible by 3" << endl;
    else
        cout << temp << " is not divisible by 3" << endl;

    if (sum % 9 == 0)
        cout << temp << " is divisible by 9" << endl;
    else
        cout << temp << " is not divisible by 9" << endl;
}

```

Sample Run: In these sample runs, the user input is shaded.

Sample Run 1:

Enter a positive integer: 27193257

```

The sum of the digits = 36
27193257 is divisible by 3
27193257 is divisible by 9

```

Sample Run 2:

Enter a positive integer: 609321

```

The sum of the digits = 21
609321 is divisible by 3
609321 is not divisible by 9

```

Sample Run 3:

Enter a positive integer: 161905102

```

The sum of the digits = 25
161905102 is not divisible by 3
161905102 is not divisible by 9

```

Choosing the Right Looping Structure

All three loops have their place in C++. If you know, or the program can determine in advance, the number of repetitions needed, the **for** loop is the correct choice. If you do not know, and the program cannot determine in advance the number of repetitions needed, and it could be zero, the **while** loop is the right choice. If you do not know, and the program cannot determine in advance the number of repetitions needed, and it is at least one, the **do...while** loop is the right choice.

break and continue Statements

The **break** statement, when executed in a **switch** structure, provides an immediate exit from the **switch** structure. Similarly, you can use the **break** statement in **while**, **for**, and **do...while** loops. When the **break** statement executes in a repetition structure, it immediately exits from the structure. The **break** statement is typically used for two purposes:

- To exit early from a loop.
- To skip the remainder of the **switch** structure.

After the **break** statement executes, the program continues to execute with the first statement after the structure. The use of a **break** statement in a loop can eliminate the use of certain (flag) variables. The following C++ code segment helps illustrate this idea. (Assume that all variables are properly declared.)

```
sum = 0;
isNegative = false;

cin >> num;

while (cin && !isNegative)
{
    if (num < 0)    //if num is negative, terminate the loop
                  //after this iteration
    {
        cout << "Negative number found in the data." << endl;
        isNegative = true;
    }
    else
    {
        sum = sum + num;
        cin >> num;
    }
}
```

This **while** loop is supposed to find the sum of a set of positive numbers. If the data set contains a negative number, the loop terminates with an appropriate error message. This **while** loop uses the flag variable **isNegative** to accomplish the desired result. The variable **isNegative** is initialized to **false** before the **while** loop. Before adding **num**

to `sum`, check whether `num` is negative. If `num` is negative, an error message appears on the screen and `isNegative` is set to `true`. In the next iteration, when the expression in the `while` statement is evaluated, it evaluates to `false` because `!isNegative` is `false`. (Note that because `isNegative` is `true`, `!isNegative` is `false`.)

The following `while` loop is written without using the variable `isNegative`:

```
sum = 0;
cin >> num;

while (cin)
{
    if (num < 0)    //if num is negative, terminate the loop
    {
        cout << "Negative number found in the data." << endl;
        break;
    }

    sum = sum + num;
    cin >> num;
}
```

In this form of the `while` loop, when a negative number is found, the expression in the `if` statement evaluates to `true`; after printing an appropriate message, the `break` statement terminates the loop. (After executing the `break` statement in a loop, the remaining statements in the loop are discarded.)

NOTE

The `break` statement is an effective way to avoid extra variables to control a loop and produce an elegant code. However, `break` statements must be used very sparingly within a loop. An excessive use of these statements in a loop will produce spaghetti-code (loops with many exit conditions) that can be very hard to understand and manage. You should be extra careful in using `break` statements and ensure that the use of the `break` statements makes the code more readable and not less readable. If you're not sure, don't use `break` statements.

The `continue` statement is used in `while`, `for`, and `do...while` structures. When the `continue` statement is executed in a loop, it skips the remaining statements in the loop and proceeds with the next iteration of the loop. In a `while` and `do...while` structure, the `expression` (that is, the loop-continue test) is evaluated immediately after the `continue` statement. In a `for` structure, the `update statement` is executed after the `continue` statement, and then the `loop condition` (that is, the loop-continue test) executes.

If the previous program segment encounters a negative number, the `while` loop terminates. If you want to discard the negative number and read the next number rather than terminate the loop, replace the `break` statement with the `continue` statement, as shown in the following example:

```
sum = 0;
cin >> num;
```

```

while (cin)
{
    if (num < 0)
    {
        cout << "Negative number found in the data." << endl;
        cin >> num;
        continue;
    }

    sum = sum + num;
    cin >> num;
}

```

It was stated earlier that all three loops have their place in C++ and that one loop can often replace another. The execution of a `continue` statement, however, is where the `while` and `do...while` structures differ from the `for` structure. When the `continue` statement is executed in a `while` or a `do...while` loop, the update statement may not execute. In a `for` structure, the update statement *always* executes.

5

Nested Control Structures

In this section, we give examples that illustrate how to use nested loops to achieve useful results and process data.

EXAMPLE 5-21

Suppose you want to create the following pattern:

```

*
**
***
****
*****

```

Clearly, you want to print five lines of stars. In the first line, you want to print one star, in the second line, two stars, and so on. Because five lines will be printed, start with the following `for` statement:

```
for (i = 1; i <= 5; i++)
```

The value of `i` in the first iteration is 1, in the second iteration it is 2, and so on. You can use the value of `i` as the limiting condition in another `for` loop nested within this loop to control the number of stars in a line. A little more thought produces the following code:

```

for (i = 1; i <= 5; i++)           //Line 1
{                                   //Line 2
    for (j = 1; j <= i; j++)       //Line 3
        cout << "*";              //Line 4
    cout << endl;                  //Line 5
}                                   //Line 6

```

A walk-through of this code shows that the `for` loop in Line 1 starts with `i = 1`. When `i` is 1, the inner `for` loop in Line 3 outputs one star and the insertion point moves to the next line. Then `i` becomes 2, the inner `for` loop outputs two stars, and the output statement in Line 5 moves the insertion point to the next line, and so on. This process continues until `i` becomes 6 and the loop stops.

What pattern does this code produce if you replace the `for` statement in Line 1 with the following?

```
for (i = 5; i >= 1; i--)
```

EXAMPLE 5-22

Suppose you want to create the following multiplication table:

| | | | | | | | | | |
|---|----|----|----|----|----|----|----|----|----|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 |
| 2 | 4 | 6 | 8 | 10 | 12 | 14 | 16 | 18 | 20 |
| 3 | 6 | 9 | 12 | 15 | 18 | 21 | 24 | 27 | 30 |
| 4 | 8 | 12 | 16 | 20 | 24 | 28 | 32 | 36 | 40 |
| 5 | 10 | 15 | 20 | 25 | 30 | 35 | 40 | 45 | 50 |

The multiplication table has five lines. Therefore, as in Example 5-21, we use a `for` statement to output these lines as follows:

```
for (i = 1; i <= 5; i++)
    //output a line of numbers
```

In the first line, we want to print the multiplication table of one, in the second line we want to print the multiplication table of 2, and so on. Notice that the first line starts with 1 and when this line is printed, `i` is 1. Similarly, the second line starts with 2 and when this line is printed, the value of `i` is 2, and so on. If `i` is 1, `i * 1` is 1; if `i` is 2, `i * 2` is 2; and so on. Therefore, to print a line of numbers, we can use the value of `i` as the starting number and 10 as the limiting value. That is, consider the following **for** loop:

```
for (j = 1; j <= 10; j++)
    cout << setw(3) << i * j;
```

Let us take a look at this **for** loop. Suppose **i** is 1. Then we are printing the first line of the multiplication table. Also, **j** goes from 1 to 10 and so this **for** loop outputs the numbers 1 through 10, which is the first line of the multiplication table. Similarly, if **i** is 2, we are printing the second line of the multiplication table. Also, **j** goes from 1 to 10, and so this **for** loop outputs the second line of the multiplication table, and so on.

A little more thought produces the following nested loops to output the desired grid:

```
for (i = 1; i <= 5; i++) //Line 1
{ //Line 2
    for (j = 1; j <= 10; j++) //Line 3
        cout << setw(3) << i * j; //Line 4
    cout << endl; //Line 5
} //Line 6
```

EXAMPLE 5-23

Consider the following data:

```
65 78 65 89 25 98 -999
87 34 89 99 26 78 64 34 -999
23 99 98 97 26 78 100 63 87 23 -999
62 35 78 99 12 93 19 -999
```

The number `-999` at the end of each line acts as a sentinel and therefore is not part of the data. Our objective is to find the sum of the numbers in each line and output the sum. Moreover, assume that this data is to be read from a file, say, `Exp_5_23.txt`. We assume that the input file has been opened using the input file stream variable `infile`.

This particular data set has four lines of input. So we can use a `for` loop or a counter-controlled `while` loop to process each line of data. Let us use a `while` loop to process these four lines. It follows that the `while` loop takes the following form:

```
counter = 0;                //Line 1
while (counter < 4)          //Line 2
{                            //Line 3
    //process the line      //Line 4

    //output the sum
    counter++;
}
```

Let us now concentrate on processing a line. Each line has a varying number of data items. For example, the first line has six numbers, the second line has eight numbers, and so on. Because each line ends with `-999`, we can use a sentinel-controlled `while` loop to find the sum of the numbers in each line. (Remember how a sentinel-controlled loop works.) Consider the following `while` loop:

```
sum = 0;                    //Line 4
infile >> num;              //Line 5
while (num != -999)         //Line 6
{                            //Line 7
    sum = sum + num;        //Line 8
    infile >> num;          //Line 9
}                            //Line 10
```

The statement in Line 4 initializes `sum` to 0, and the statement in Line 5 reads and stores the first number of the line into `num`. The Boolean expression `num != -999` in Line 6 checks whether the number is `-999`. If `num` is not `-999`, the statements in Lines 8 and 9 execute. The statement in Line 8 updates the value of `sum`; the statement in Line 9 reads and stores the next number into `num`. The loop continues to execute as long as `num` is not `-999`.

It now follows that the nested loop to process the data is as follows. (Assume that all variables are properly declared.)

```

counter = 0;                                //Line 1
while (counter < 4)                          //Line 2
{
    sum = 0;                                //Line 3
    infile >> num;                          //Line 4
    while (num != -999)                     //Line 5
    {
        sum = sum + num;                   //Line 6
        infile >> num;                     //Line 7
    }                                       //Line 8

    cout << "Line " << counter + 1
        << ": Sum = " << sum << endl;    //Line 9
    counter++;                             //Line 10
}                                           //Line 11

```

EXAMPLE 5-24

Suppose that we want to process data similar to the data in Example 5-23, but the input file is of an unspecified length. That is, each line contains the same data as the data in each line in Example 5-23, but we do not know the number of input lines.

Because we do not know the number of input lines, we must use an EOF-controlled **while** loop to process the data. In this case, the required code is as follows. (Assume that all variables are properly declared and the input file has been opened using the input file stream variable **infile**.)

```

counter = 0;                                //Line 1
infile >> num;                              //Line 2
while (infile)                              //Line 3
{
    sum = 0;                                //Line 4
    while (num != -999)                     //Line 5
    {
        sum = sum + num;                   //Line 6
        infile >> num;                     //Line 7
    }                                       //Line 8

    cout << "Line " << counter + 1
        << ": Sum = " << sum << endl;    //Line 9
    counter++;                             //Line 10
    infile >> num;                         //Line 11
}                                           //Line 12

```

Notice that we have again used the variable **counter**. The only reason to do so is because we want to print the line number with the sum of each line.

EXAMPLE 5-25

Consider the following data:

```
101
John Smith
65 78 65 89 25 98 -999
102
Peter Gupta
87 34 89 99 26 78 64 34 -999
103
Buddy Friend
23 99 98 97 26 78 100 63 87 23 -999
104
Doctor Miller
62 35 78 99 12 93 19 -999
...
```

The number `-999` at the end of a line acts as a sentinel and therefore is not part of the data.

Assume that this is the data of certain candidates seeking the student council's presidential seat.

For each candidate, the data is in the following form:

```
ID
Name
Votes
```

The objective is to find the total number of votes received by the candidate. We assume that the data is input from the file `Exp_5_25.txt` of unknown size. We also assume that the input file has been opened using the input file stream variable `infile`.

Because the input file is of an unspecified length, we use an EOF-controlled `while` loop. For each candidate, the first data item is the `ID` of type `int` on a line by itself; the second data item is the name, which may consist of more than one word; and the third line contains the votes received from the various departments.

To read the `ID`, we use the extraction operator `>>`; to read the name, we use the stream function `getline`. Notice that after reading the `ID`, the reading marker is after the `ID` and the character after the `ID` is the newline character. Therefore, after reading the `ID`, the reading marker is after the `ID` and before the newline character (of the line containing the `ID`).

The function `getline` reads until the end of the line. Therefore, if we read the name immediately after reading the `ID`, then what is stored in the variable `name` is the newline character (after the `ID`). It follows that to read the name, we must read and discard the newline character after the `ID`, which we can accomplish using the stream function `get`. Therefore, the statements to read the `ID` and name are as follows:

```
infile >> ID;           //read the ID
infile.get(ch);         //read the newline character after the ID
getline(infile, name);   //read the name
```

(Assume that `ch` is a variable of type `char`.) The general loop to process the data is:

```
infile >> ID;                                //Line 1
while (infile)                                //Line 2
{                                              //Line 3
    infile.get(ch);                            //Line 4
    getline(infile, name);                     //Line 5

    //process the numbers in each line        //Line 6
    //output the name and total votes
    infile >> ID;    //begin processing the next line
}
```

The code to read and sum up the voting data is:

```
sum = 0;                                     //Line 6
infile >> num;                               //Line 7; read the first number
while (num != -999)                          //Line 8
{                                              //Line 9
    sum = sum + num;                         //Line 10; update sum
    infile >> num;                           //Line 11; read the next number
}                                              //Line 12
```

We can now write the following nested loop to process data as follows:

```
infile >> ID;                                //Line 1
while (infile)                                //Line 2
{                                              //Line 3
    infile.get(ch);                            //Line 4
    getline(infile, name);                     //Line 5
    sum = 0;                                  //Line 6
    infile >> num;                             //Line 7; read the first number
    while (num != -999)                       //Line 8
    {                                          //Line 9
        sum = sum + num;                     //Line 10; update sum
        infile >> num;                       //Line 11; read the next number
    }

    cout << "Name: " << name
         << ", Votes: " << sum
         << endl;                             //Line 12

    infile >> ID;    //Line 13; begin processing the next line
}
```

Avoiding Bugs by Avoiding Patches

Debugging sections in the previous chapters illustrated how to debug syntax and logical errors, and how to avoid partially understood concepts. In this section, we illustrate how to avoid a software patch to fix a code. A software patch is a piece of code written on top of an existing piece of code and intended to fix a bug in the original code.

Suppose that the following data is in the file `Ch5_LoopWithBugsData.txt`.

```
87 78 83 94
23 89 92 70
92 78 34 56
```

The objective is to find the sum of the numbers in each line. For each line, output the numbers together with their sum. Let us consider the following program:

```
#include <iostream>
#include <fstream>

using namespace std;

int main()
{
    ifstream infile;

    int i;
    int j;
    int sum;
    int num;

    infile.open("Ch5_LoopWithBugsData.txt");

    for (i = 1; i <= 4; i++)
    {
        sum = 0;

        for (j = 1; j <= 4; j++)
        {
            infile >> num;
            cout << num << " ";
            sum = sum + num;
        }

        cout << "sum = " << sum << endl;
    }

    return 0;
}
```

Sample Run:

```
87 78 83 94 sum = 342
23 89 92 70 sum = 274
92 78 34 56 sum = 260
56 56 56 56 sum = 224
```

The sample run shows that there is a bug in the program because the file contains three lines of input and the output contains four lines. Also, the number 56 in the last line repeats four times. Clearly, there is a bug in the program and we must fix the code. Some programmers, especially some beginners, address the symptom of the problem by adding a software patch. In this case, the output should contain only three lines of output.

A beginning programmer might fix the code by adding a software patch as shown in the following modified program.

```
#include <iostream>
#include <fstream>

using namespace std;

int main()
{
    ifstream infile;

    int i;
    int j;
    int sum;
    int num;

    infile.open("Ch5_LoopWithBugsData.txt");

    for (i = 1; i <= 4; i++)
    {
        sum = 0;

        if (i != 4)
        {
            for (j = 1; j <= 4; j++)
            {
                infile >> num;
                cout << num << " ";
                sum = sum + num;
            }

            cout << "sum = " << sum << endl;
        }
    }

    return 0;
}
```

Sample Run:

```
87 78 83 94 sum = 342
23 89 92 70 sum = 274
92 78 34 56 sum = 260
```

Clearly, the program is working correctly now.

As we can see, the programmer merely observed the symptom and addressed the problem by adding a software patch. However, if you look at the code, not only does the program execute extra statements, it is also an example of a partially understood concept. It appears that the programmer does not have a good grasp of why the earlier program produced four lines rather than three. Adding a patch eliminated the symptom, but it is a poor programming practice. The programmer must resolve why the program produced four lines. Looking at the

program closely, we can see that the four lines are produced because the outer loop executes four times. The values assigned to loop control variable `i` are 1, 2, 3, and 4. This is an example of the classic “off-by-one” problem. (In an “off-by-one problem,” either the loop executes one too many or one too few times.) We can eliminate this problem by correctly setting the values of the loop control variable. For example, we can rewrite the loops as follows:

```
for (i = 1; i <= 3; i++)
{
    sum = 0;

    for (j = 1; j <= 4; j++)
    {
        infile >> num;
        cout << num << " ";
        sum = sum + num;
    }

    cout << "sum = " << sum << endl;
}
```

This code fixes the original problem without using a software patch. It also represents good programming practice. The complete modified program is available at the Web site accompanying this book and is named `Ch5_LoopWithBugsCorrectedProgram.cpp`.

Debugging Loops

As we have seen in the earlier debugging sections, no matter how careful a program is designed and coded, errors are likely to occur. If there are syntax errors, the compiler will identify them. However, if there are logical errors, we must carefully look at the code or even maybe at the design and try to find the errors. To increase the reliability of the program, errors must be discovered and fixed before the program is released to the users.

Once an algorithm is written, the next step is to verify that it works properly. If the algorithm is a simple sequential flow or contains a branch, it can be hand traced or you can use the debugger, if any, provided by the IDE. Typically, loops are harder to debug. The correctness of a loop can be verified by using loop invariants. A loop invariant is a set of statements that remains true each time the loop body is executed. Let p be a loop invariant and q be the (logical) expression in a loop statement. Then $p \ \&\& \ q$ remains true before each iteration of the loop and $p \ \&\& \ \text{not}(q)$ is true after the loop terminates. The full discussion of loop invariants is beyond the scope of the book. However, you can learn about loop invariants in the book: *Discrete Mathematical Structures: Theory and Applications*, D.S. Malik and M.K. Sen, Course Technology, 2004. Here, we give a few tips that you can use to debug a loop.

As discussed in the previous section, the most common error associated with loops is off-by-one. If a loop turns out to be an infinite loop, the error is most likely in the logical expression that controls the execution of the loop. Check the logical expression carefully and see if you have reversed an inequality, an assignment statement symbol appears in place of the equality operator, or `&&` appears in place of `||`. If the loop changes the values of

variables, you can print the values of the variables before and/or after each iteration or you can use your IDE's debugger, if any, and watch the values of variables during each iteration.

The debugging sections in this book are designed to help you understand the debugging process. However, as you will realize, debugging can be a tiresome process. If your program is very bad, do not debug. Throw it away and start over.

QUICK REVIEW

1. C++ has three looping (repetition) structures: **while**, **for**, and **do...while**.
2. The syntax of the **while** statement is:

```
while (expression)
    statement
```
3. In C++, **while** is a reserved word.
4. In the **while** statement, the parentheses around the **expression** (the decision maker) are important; they mark the beginning and end of the expression.
5. The **statement** is called the body of the loop.
6. The body of the **while** loop must contain a statement that eventually sets the expression to **false**.
7. A counter-controlled **while** loop uses a counter to control the loop.
8. In a counter-controlled **while** loop, you must initialize the counter before the loop, and the body of the loop must contain a statement that changes the value of the counter variable.
9. A sentinel is a special value that marks the end of the input data. The sentinel must be similar to, yet differ from, all the data items.
10. A sentinel-controlled **while** loop uses a sentinel to control the **while** loop. The **while** loop continues to execute until the sentinel is read.
11. An EOF-controlled **while** loop continues to execute until the program detects the end-of-file marker.
12. In the Windows console environment, the end-of-file marker is entered using **Ctrl+z** (hold the **Ctrl** key and press **z**). In the UNIX environment, the end-of-file marker is entered using **Ctrl+d** (hold the **Ctrl** key and press **d**).
13. A **for** loop simplifies the writing of a counter-controlled **while** loop.
14. In C++, **for** is a reserved word.
15. The syntax of the **for** loop is:

```
for (initialize statement; loop condition; update statement)
    statement
```

statement is called the body of the **for** loop.

16. Putting a semicolon at the end of the **for** loop (before the body of the **for** loop) is a semantic error. In this case, the action of the **for** loop is empty.
17. The syntax of the **do...while** statement is:

```
do
    statement
while (expression);
```

statement is called the body of the **do...while** loop.

18. Both **while** and **for** loops are called pretest loops. A **do...while** loop is called a posttest loop.
19. The **while** and **for** loops may not execute at all, but the **do...while** loop always executes at least once.
20. Executing a **break** statement in the body of a loop immediately terminates the loop.
21. Executing a **continue** statement in the body of a loop skips the loop's remaining statements and proceeds with the next iteration.
22. When a **continue** statement executes in a **while** or **do...while** loop, the expression update statement in the body of the loop may not execute.
23. After a **continue** statement executes in a **for** loop, the update statement is the next statement executed.

EXERCISES

1. Mark the following statements as true or false.
 - a. In a counter-controlled **while** loop, it is not necessary to initialize the loop control variable.
 - b. It is possible that the body of a **while** loop may not execute at all.
 - c. In an infinite **while** loop, the **while** expression (the decision maker) is initially false, but after the first iteration it is always true.
 - d. The **while** loop:


```
j = 0;
while (j <= 10)
    j++;
```

 terminates if $j > 10$.
 - e. A sentinel-controlled **while** loop is an event-controlled **while** loop whose termination depends on a special value.
 - f. A loop is a control structure that causes certain statements to execute over and over.
 - g. To read data from a file of an unspecified length, an EOF-controlled loop is a good choice.

h. When a **while** loop terminates, the control first goes back to the statement just before the **while** statement, and then the control goes to the statement immediately following the **while** loop.

2. What is the output of the following C++ code?

```
int count = 1;
int y = 100;
while (count < 100)
{
    y = y - 1;
    count++;
}
cout << " y = " << y << " and count = " << count << endl;
```

3. What is the output of the following C++ code?

```
int num = 5;
while (num > 5)
    num = num + 2;
cout << num << endl;
```

4. What is the output of the following C++ code?

```
int num = 1;
while (num < 10)
{
    cout << num << " ";
    num = num + 2;
}
cout << endl;
```

5. When does the following **while** loop terminate?

```
ch = 'D';
while ('A' <= ch && ch <= 'Z')
    ch = static_cast<char>(static_cast<int>(ch) + 1);
```

6. Suppose that the input is 38 35 71 14 -1. What is the output of the following code? Assume all variables are properly declared.

```
cin >> sum;
cin >> num;

for (j = 1; j <= 3; j++)
{
    cin >> num;
    sum = sum + num;
}
cout << "Sum = " << sum << endl;
```

7. Suppose that the input is 38 35 71 14 -1. What is the output of the following code? Assume all variables are properly declared.

```
cin >> sum;
cin >> num;

while (num != -1)
```

```

{
    sum = sum + num;
    cin >> num;
}
cout << "Sum = " << sum << endl;

```

8. Suppose that the input is 38 35 71 14 -1. What is the output of the following code? Assume all variables are properly declared.

```

cin >> num;
sum = num;

while (num != -1)
{
    cin >> num;
    sum = sum + num;
}
cout << "Sum = " << sum << endl;

```

9. Suppose that the input is 38 35 71 14 -1. What is the output of the following code? Assume all variables are properly declared.

```

sum = 0;
cin >> num;

while (num != -1)
{
    sum = sum + num;
    cin >> num;
}
cout << "Sum = " << sum << endl;

```

10. Correct the following code so that it finds the sum of 20 numbers.

```

sum = 0;

while (count < 20)
    cin >> num;
    sum = sum + num;
    count++;

```

11. What is the output of the following program?

```

#include <iostream>

using namespace std;

int main()
{
    int x, y, z;

    x = 4;    y = 5;
    z = y + 6;

    while (((z - x) % 4) != 0)
    {
        cout << z << " ";
        z = z + 7;
    }
}

```

```

        cout << endl;

        return 0;
    }

```

12. Suppose that the input is:

```
58 23 46 75 98 150 12 176 145 -999
```

What is the output of the following program?

```

#include <iostream>

using namespace std;

int main()
{
    int num;

    cin >> num;

    while (num != -999)
    {
        cout << num % 25 << " ";
        cin >> num;
    }

    cout << endl;

    return 0;
}

```

13. The following program is designed to input two numbers and output their sum. It asks the user if he/she would like to run the program. If the answer is Y or y, it prompts the user to enter two numbers. After adding the numbers and displaying the results, it again asks the user if he/she would like to add more numbers. However, the program fails to do so. Correct the program so that it works properly.

```

#include <iostream>
#include <iomanip>

using namespace std;

int main()
{
    char response;
    double num1;
    double num2;

    cout << "This program adds two numbers." << endl;
    cout << "Would you like to run the program: (Y/y) ";
    cin >> response;
    cout << endl;

```

```

cout << fixed << showpoint << setprecision(2);

while (response == 'Y' && response == 'y')
{
    cout << "Enter two numbers: ";
    cin >> num1 >> num2;
    cout << endl;

    cout << num1 << " + " << num2 << " = " << (num1 + num2)
        << endl;

    cout << "Would you like to add again: (Y/y) ";
    cin >> response;
    cout << endl;
}

return 0;
}

```

14. What is the output of the following program segment?

```

int count = 0;

while (count++ < 10)
    cout << "This loop can repeat statements." << endl;

```

15. What is the output of the following program segment?

```

int count = 5;

while (--count > 0)
    cout << count << " ";
cout << endl;

```

16. What is the output of the following program segment?

```

int count = 5;

while (count-- > 0)
    cout << count << " ";
cout << endl;

```

17. What is the output of the following program segment?

```

int count = 1;
while (count++ <= 5)
    cout << count * (count - 2) << " ";

cout << endl;

```

18. What type of loop, such as counter-control and sentinel-control, will you use in each of the following situations?

- a. Sum the following series: $1 + (2 / 1) + (3 / 2) + (4 / 3) + (5 / 4) + \dots + (10 / 9)$
- b. Sum the following numbers, except the last number: 17, 32, 62, 48, 58, -1
- c. A file contains an employee's salary. Update the employee's salary.

19. Consider the following **for** loop:

```
int j, s;

s = 0;
for (j = 1; j <= 10; j++)
    s = s + j * (j - 1);
```

In this **for** loop, identify the loop control variable, the initialization statement, the loop condition, the update statement, and the statement that updates the value of **s**.

20. Given that the following code is correctly inserted into a program, state its entire output as to content and form. (Assume all variables are properly declared.)

```
num = 0;
for (i = 1; i <= 4; i++)
{
    num = num + 10 * (i - 1);
    cout << num << " ";
}
cout << endl;
```

21. Given that the following code is correctly inserted into a program, state its entire output as to content and form. (Assume all variables are properly declared.)

```
j = 2;
for (i = 0; i <= 5; i++)
{
    cout << j << " ";
    j = 2 * j + 3;
}
cout << j << " " << endl;
```

22. Assume that the following code is correctly inserted into a program:

```
int s = 0;

for (i = 0; i < 5; i++)
{
    s = 2 * s + i;
    cout << s << " ";
}
cout << endl;
```

- a. What is the final value of **s**?
 - (i) 11
 - (ii) 4
 - (iii) 26
 - (iv) none of these
- b. If a semicolon is inserted after the right parenthesis in the **for** loop statement, what is the final value of **s**?
 - (i) 0
 - (ii) 1
 - (iii) 2
 - (iv) 5
 - (v) none of these
- c. If the 5 is replaced with a 0 in the **for** loop control expression, what is the final value of **s**?
 - (i) 0
 - (ii) 1
 - (iii) 2
 - (iv) none of these

23. State what output, if any, results from each of the following statements:

- a.

```
for (i = 1; i <= 1; i++)
    cout << "*";
cout << endl;
```
- b.

```
for (i = 2; i >= 1; i++)
    cout << "*";
cout << endl;
```
- c.

```
for (i = 1; i <= 1; i--)
    cout << "*";
cout << endl;
```
- d.

```
for (i = 12; i >= 9; i--)
    cout << "*";
cout << endl;
```
- e.

```
for (i = 0; i <= 5; i++)
    cout << "*";
cout << endl;
```
- f.

```
for (i = 1; i <= 5; i++)
{
    cout << "*";
    i = i + 1;
}
cout << endl;
```

24. Write a **for** statement to add all the multiples of 3 between 1 and 100.

25. What is the output of the following code? Is there a relationship between the variables **x** and **y**? If yes, state the relationship? What is the output?

```
int x = 19683;
int i;
int y = 0;

for (i = x; i >= 1; i = i / 3)
    y++;
cout << "x = " << x << ", y = " << y << endl;
```

26. Suppose that the input is 5 3 8. What is the output of the following code? Assume all variables are properly declared.

```
cin >> a >> b >> c;
for (j = 1; j < a; j++)
{
    d = b + c;
    b = c;
    c = d;
    cout << c << " ";
}
cout << endl;
```

27. What is the output of the following C++ program segment? Assume all variables are properly declared.

```

for (j = 0; j < 8; j++)
{
    cout << j * 25 << " - ";

    if (j != 7)
        cout << (j + 1) * 25 - 1 << endl;
    else
        cout << (j + 1) * 25 << endl;
}

```

28. Suppose that the input is 38 35 71 44 -1. What is the output of the following code? Assume all variables are properly declared.

```

sum = 0;
cin >> num;

for (j = 1; j <= 3; j++)
{
    cin >> num;
    sum = sum + num;
}
cout << "Sum = " << sum << endl;

```

29. Which of the following apply to the **while** loop only? To the **do...while** loop only? To both?
- It is considered a conditional loop.
 - The body of the loop executes at least once.
 - The logical expression controlling the loop is evaluated before the loop is entered.
 - The body of the loop may not execute at all.
30. The following program has more than five mistakes that prevent it from compiling and/or running. Correct all such mistakes.

```

#include <iostream>

using namespace std;
const int N = 2,137;

main ()
{
    int a, b, c, d;

    a := 3;
    b = 5;
    c = c + d;
    N = a + n;
    for (i = 3; i <= N; i++)
    {
        cout << setw(5) << i;
        i = i + 1;
    }
    return 0;
}

```

31. What is the difference between a pretest loop and a posttest loop?
32. How many times will each of the following loops execute? What is the output in each case?

a. `x = 5; y = 50;`
`do`
 `x = x + 10;`
`while (x < y);`
`cout << x << " " << y << endl;`

b. `x = 5; y = 80;`
`do`
 `x = x * 2;`
`while (x < y);`
`cout << x << " " << y << endl;`

c. `x = 5; y = 20;`
`do`
 `x = x + 2;`
`while (x >= y);`
`cout << x << " " << y << endl;`

d. `x = 5; y = 35;`
`while (x < y)`
 `x = x + 10;`
`cout << x << " " << y << endl;`

e. `x = 5; y = 30;`
`while (x <= y)`
 `x = x * 2;`
`cout << x << " " << y << endl;`

f. `x = 5; y = 30;`
`while (x > y)`
 `x = x + 2;`
`cout << x << " " << y << endl;`

33. Write an input statement validation loop that prompts the user to enter a number less than 20 or greater than 75.

34. Rewrite the following as a **for** loop.

```
int i = 0, value = 0;

while (i <= 20)
{
    if (i % 2 == 0 && i <= 10)
        value = value + i * i;
    else if (i % 2 == 0 && i > 10)
        value = value + i;
    else
        value = value - i;
    i = i + 1;
}

cout << "value = " << value << endl;
```

What is the output of this loop?

35. Write the `while` loop of Exercise 34 as a `do...while` loop.
36. The `do...while` loop in the following program is supposed to read some numbers until it reaches a sentinel (in this case, `-1`). It is supposed to add all of the numbers except for the sentinel. If the data looks like:

12 5 30 48 -1

the program does not add the numbers correctly. Correct the program so that it adds the numbers correctly.

```
#include <iostream>

using namespace std;
int main()
{
    int total = 0,
        count = 0,
        number;

    do
    {
        cin >> number;
        total = total + number;
        count++;
    }
    while (number != -1);

    cout << "The number of data read is " << count << endl;
    cout << "The sum of the numbers entered is " << total
        << endl;

    return 0;
}
```

37. Using the same data as in Exercise 36, the following loop also fails. Correct it.

```
cin >> number;
while (number != -1)
    total = total + number;
cin >> number;
cout << endl;
cout << total << endl;
```

38. Using the same data as in Exercise 36, the following loop also fails. Correct it.

```
cin >> number;
while (number != -1)
{
    cin >> number;
    total = total + number;
}
cout << endl;
cout << total << endl;
```

39. Given the following program segment:

```
for (number = 1; number <= 10; number++)
    cout << setw(3) << number;
```

write a `while` loop and a `do...while` loop that have the same output.

40. Given the following program segment:

```
j = 2;
for (i = 1; i <= 5; i++);
{
    cout << setw(4) << j;
    j = j + 5;
}
cout << endl;
```

write a **while** loop and a **do...while** loop that have the same output.

41. What is the output of the following program?

```
#include <iostream>

using namespace std;

int main()
{
    int x, y, z;
    x = 4; y = 5;
    z = y + 6;
    do
    {
        cout << z << " ";
        z = z + 7;
    }
    while ((z - x) % 4 != 0);

    cout << endl;

    return 0;
}
```

42. To learn how nested **for** loops work, do a walk-through of the following program segments and determine, in each case, the exact output.

a. **int** i, j;

```
for (i = 1; i <= 5; i++)
{
    for (j = 1; j <= 5; j++)
        cout << setw(3) << i;
    cout << endl;
}
```

b. **int** i, j;

```
for (i = 1; i <= 5; i++)
{
    for (j = (i + 1); j <= 5; j++)
        cout << setw(5) << j;
    cout << endl;
}
```

```

c.  int i, j;
    for (i = 1; i <= 5; i++)
    {
        for (j = 1; j <= i; j++)
            cout << setw(3) << j;
        cout << endl;
    }

d.  const int M = 10;
    const int N = 10;
    int i, j;

    for (i = 1; i <= M; i++)
    {
        for (j = 1; j <= N; j++)
            cout << setw(3) << M * (i - 1) + j;
        cout << endl;
    }

e.  int i, j;

    for (i = 1; i <= 9; i++)
    {
        for (j = 1; j <= (9 - i); j++)
            cout << " ";
        for (j = 1; j <= i; j++)
            cout << setw(1) << j;
        for (j = (i - 1); j >= 1; j--)
            cout << setw(1) << j;
        cout << endl;
    }

```

43. What is the output of the following program segment?

```

int count = 1;
do
    cout << count * (count - 2) << " ";
while (count++ <= 5);

cout << endl;

```

44. What is the output of the following code?

```

int num = 12;

while (num >= 0)
{
    if (num % 5 == 0)
        break;

    cout << num << " ";
    num = num - 2;
}

cout << endl;

```

45. What is the output of the following code?

```
int num = 12;

while (num >= 0)
{
    if (num % 5 == 0)
    {
        num++;
        continue;
    }

    cout << num << " ";
    num = num - 2;
}
cout << endl;
```

46. What does a **break** statement do in a loop?

PROGRAMMING EXERCISES

- Write a program that prompts the user to input an integer and then outputs both the individual digits of the number and the sum of the digits. For example, it should output the individual digits of 3456 as 3 4 5 6, output the individual digits of 8030 as 8 0 3 0, output the individual digits of 2345526 as 2 3 4 5 5 2 6, output the individual digits of 4000 as 4 0 0 0, and output the individual digits of -2345 as 2 3 4 5.

- The value of π can be approximated by using the following series:

$$\pi = 4 \left(1 - \frac{1}{3} + \frac{1}{5} - \frac{1}{7} + \cdots + \frac{1}{2n-1} + \frac{1}{2n+1} \right)$$

The following program uses this series to find the approximate value of π . However, the statements are in the incorrect order, and there is also a bug in this program. Rearrange the statements and also find and remove the bug so that this program can be used to approximate π .

```
#include <iostream>
#include <iomanip>

using namespace std;

int main()
{
    double pi = 0;
    long i;
    long n;

    cin >> n;
    cout << "Enter the value of n: ";
    cout << endl;
```

```

    if (i % 2 == 0)
        pi = pi + (1 / (2 * i + 1));
    else
        pi = pi - (1 / (2 * i + 1));

    for (i = 0; i < n; i++)
    {
        pi = 0;
        pi = 4 * pi;
    }

    cout << endl << "pi = " << pi << endl;

    return 0;
}

```

3. Rewrite the program of Example 5-5, Telephone Digits. Replace the statements from Line 10 to Line 28 so that the program uses only a **switch** structure to find the digit that corresponds to an uppercase letter.
4. The program Telephone Digits outputs only telephone digits that correspond to uppercase letters. Rewrite the program so that it processes both uppercase and lowercase letters and outputs the corresponding telephone digit. If the input is something other than an uppercase or lowercase letter, the program must output an appropriate error message.
5. To make telephone numbers easier to remember, some companies use letters to show their telephone number. For example, using letters, the telephone number 438-5626 can be shown as **GET LOAN**. In some cases, to make a telephone number meaningful, companies might use more than seven letters. For example, 225-5466 can be displayed as **CALL HOME**, which uses eight letters. Write a program that prompts the user to enter a telephone number expressed in letters and outputs the corresponding telephone number in digits. If the user enters more than seven letters, then process only the first seven letters. Also output the – (hyphen) after the third digit. Allow the user to use both uppercase and lowercase letters as well as spaces between words. Moreover, your program should process as many telephone numbers as the user wants.
6. Write a program that reads a set of integers and then finds and prints the sum of the even and odd integers.
7. Write a program that prompts the user to input a positive integer. It should then output a message indicating whether the number is a prime number. (*Note:* An even number is prime if it is 2. An odd integer is prime if it is not divisible by any odd integer less than or equal to the square root of the number.)
8. Let $n = a_k a_{k-1} a_{k-2} \dots a_1 a_0$ be an integer and $t = a_0 - a_1 + a_2 - \dots + (-1)^k a_k$. It is known that n is divisible by 11 if and only if t is divisible by 11. For example, suppose that $n = 8784204$. Then, $t = 4 - 0 + 2 - 4 + 8 - 7 + 8 = 11$. Because 11 is divisible by 11, it follows that 8784204 is divisible by 11. If $n = 54063297$, then $t = 7 - 9 + 2 - 3 + 6 - 0 + 4 - 5 = 2$. Because 2 is not

divisible by 11, 54063297 is not divisible by 11. Write a program that prompts the user to enter a positive integer and then uses this criterion to determine whether the number is divisible by 11.

9. Write a program that uses **while** loops to perform the following steps:
 - a. Prompt the user to input two integers: **firstNum** and **secondNum** (**firstNum** must be less than **secondNum**).
 - b. Output all odd numbers between **firstNum** and **secondNum**.
 - c. Output the sum of all even numbers between **firstNum** and **secondNum**.
 - d. Output the numbers and their squares between 1 and 10.
 - e. Output the sum of the square of the odd numbers between **firstNum** and **secondNum**.
 - f. Output all uppercase letters.
10. Redo Exercise 9 using **for** loops.
11. Redo Exercise 9 using **do...while** loops.
12. The program in the Programming Example: Fibonacci Number does not check whether the first number entered by the user is less than or equal to the second number and whether both the numbers are nonnegative. Also, the program does not check whether the user entered a valid value for the position of the desired number in the Fibonacci sequence. Rewrite that program so that it checks for these things.
13. The population of a town A is less than the population of town B . However, the population of town A is growing faster than the population of town B . Write a program that prompts the user to enter the population and growth rate of each town. The program outputs after how many years the population of town A will be greater than or equal to the population of town B and the populations of both the towns at that time. (A sample input is: Population of town $A = 5000$, growth rate of town $A = 4\%$, population of town $B = 8000$, and growth rate of town $B = 2\%$.)
14. Suppose that the first number of a sequence is x , in which x is an integer. Define $a_0 = x$; $a_{n+1} = a_n/2$ if a_n is even; $a_{n+1} = 3 \times a_n + 1$ if a_n is odd. Then, there exists an integer k such that $a_k = 1$. Write a program that prompts the user to input the value of x . The program output the integer k such that $a_k = 1$ and the numbers $a_0, a_1, a_2, \dots, a_k$. (For example, if $x = 75$, then $k = 14$, and the numbers $a_0, a_1, a_2, \dots, a_{14}$, respectively, are 75, 226, 113, 340, 170, 85, 256, 128, 64, 32, 16, 8, 4, 2, 1.) Test your program for the following values of x : 75, 111, 678, 732, 873, 2048, and 65535.
15. Enhance your program from Exercise 14 by outputting the position of the largest number and the largest number of the sequence $a_0, a_1, a_2, \dots, a_k$. (For example, the largest number of the sequence 75, 226, 113, 340, 170,

85, 256, 128, 64, 32, 16, 8, 4, 2, 1 is 340, and its position is 4.) Test your program for the following values of x : 75, 111, 678, 732, 873, 2048, and 65535.

16. The program in Example 5-6 implements the Number Guessing Game. However, in that program, the user is given as many tries as needed to guess the correct number. Rewrite the program so that the user has no more than five tries to guess the correct number. Your program should print an appropriate message, such as “You win!” or “You lose!”.
17. Example 5-6 implements the Number Guessing Game program. If the guessed number is not correct, the program outputs a message indicating whether the guess is low or high. Modify the program as follows: Suppose that the variables `num` and `guess` are as declared in Example 5-6 and `diff` is an `int` variable. Let `diff` = the absolute value of (`num` – `guess`). If `diff` is 0, then `guess` is correct and the program outputs a message indicating that the user guessed the correct number. Suppose `diff` is not 0. Then the program outputs the message as follows:
 - a. If `diff` is greater than or equal to 50, the program outputs the message indicating that the guess is very high (if `guess` is greater than `num`) or very low (if `guess` is less than `num`).
 - b. If `diff` is greater than or equal to 30 and less than 50, the program outputs the message indicating that the guess is high (if `guess` is greater than `num`) or low (if `guess` is less than `num`).
 - c. If `diff` is greater than or equal to 15 and less than 30, the program outputs the message indicating that the guess is moderately high (if `guess` is greater than `num`) or moderately low (if `guess` is less than `num`).
 - d. If `diff` is greater than 0 and less than 15, the program outputs the message indicating that the guess is somewhat high (if `guess` is greater than `num`) or somewhat low (if `guess` is less than `num`).

As in Programming Exercise 16, give the user no more than five tries to guess the number. (To find the absolute value of `num` – `guess`, use the expression `abs(num - guess)`. The function `abs` is from the header file `cstdlib`.)

18. A high school has 1000 students and 1000 lockers, one locker for each student. On the first day of school, the principal plays the following game: She asks the first student to go and open all the lockers. She then asks the second student to go and close all the even-numbered lockers. The third student is asked to check every third locker. If it is open, the student closes it; if it is closed, the student opens it. The fourth student is asked to check every fourth locker. If it is open, the student closes it; if it is closed, the student opens it. The remaining students continue this game. In general, the n th student checks every n th locker. If the locker is open, the student closes it; if it is closed, the student opens it. After all the students have taken their turn, some of the lockers are open and some are closed. Write a program

that prompts the user to enter the number of lockers in a school. After the game is over, the program outputs the number of lockers that are opened. Test run your program for the following inputs: 1000, 5000, 10000. Do you see any pattern developing?

(*Hint:* Consider locker number 100. This locker is visited by student numbers 1, 2, 4, 5, 10, 20, 25, 50, and 100. These are the positive divisors of 100. Similarly, locker number 30 is visited by student numbers 1, 2, 3, 5, 6, 10, 15, and 30. Notice that if the number of positive divisors of a locker number is odd, then at the end of the game, the locker is opened. If the number of positive divisors of a locker number is even, then at the end of the game, the locker is closed.)

19. When you borrow money to buy a house, a car, or for some other purpose, you repay the loan by making periodic payments over a certain period of time. Of course, the lending company will charge interest on the loan. Every periodic payment consists of the interest on the loan and the payment toward the principal amount. To be specific, suppose that you borrow \$1000 at the interest rate of 7.2% per year and the payments are monthly. Suppose that your monthly payment is \$25. Now, the interest is 7.2% per year and the payments are monthly, so the interest rate per month is $7.2/12 = 0.6\%$. The first month's interest on \$1000 is $1000 \times 0.006 = 6$. Because the payment is \$25 and interest for the first month is \$6, the payment toward the principal amount is $25 - 6 = 19$. This means after making the first payment, the loan amount is $1000 - 19 = 981$. For the second payment, the interest is calculated on \$981. So the interest for the second month is $981 \times 0.006 = 5.886$, that is, approximately \$5.89. This implies that the payment toward the principal is $25 - 5.89 = 19.11$ and the remaining balance after the second payment is $981 - 19.11 = 961.89$. This process is repeated until the loan is paid. Write a program that accepts as input the loan amount, the interest rate per year, and the monthly payment. (Enter the interest rate as a percentage. For example, if the interest rate is 7.2% per year, then enter 7.2.) The program then outputs the number of months it would take to repay the loan. (Note that if the monthly payment is less than the first month's interest, then after each payment, the loan amount will increase. In this case, the program must warn the borrower that the monthly payment is too low, and with this monthly payment, the loan amount could not be repaid.)
20. Enhance your program from Exercise 19 by first telling the user the minimum monthly payment and then prompting the user to enter the monthly payment. Your last payment might be more than the remaining loan amount and interest on it. In this case, output the loan amount before the last payment and the actual amount of the last payment. Also, output the total interest paid.
21. Write a complete program to test the code in Example 5-21.
22. Write a complete program to test the code in Example 5-22.

23. Write a complete program to test the code in Example 5-23.
24. Write a complete program to test the code in Example 5-24.
25. Write a complete program to test the code in Example 5-25.
26. **(The conical paper cup problem)** You have been given the contract for making little conical cups that come with bottled water. These cups are to be made from a circular waxed paper of 4 inches in radius by removing a sector of length x (see Figure 5-4). By closing the remaining part of the circle, a conical cup is made. Your objective is to remove the sector so that the cup is of maximum volume.




FIGURE 5-4 Conical paper cup

Write a program that prompts the user to enter the radius of the circular waxed paper. The program should then output the length of the removed sector so that the resulting cup is of maximum volume. Calculate your answer to two decimal places.

27. **(Apartment problem)** A real estate office handles, say, 50 apartment units. When the rent is, say, \$600 per month, all the units are occupied. However, for each, say, \$40 increase in rent, one unit becomes vacant. Moreover, each occupied unit requires an average of \$27 per month for maintenance. How many units should be rented to maximize the profit?

Write a program that prompts the user to enter:

- a. The rent to occupy all the units.
- b. The increase in rent that results in a vacant unit.
- c. Amount to maintain a rented unit.

The program then outputs the number of units to be rented to maximize the profit.



6 CHAPTER

USER-DEFINED FUNCTIONS I

IN THIS CHAPTER, YOU WILL:

- Learn about standard (predefined) functions and discover how to use them in a program
- Learn about user-defined functions
- Examine value-returning functions, including actual and formal parameters
- Explore how to construct and use a value-returning, user-defined function in a program

In Chapter 2, you learned that a C++ program is a collection of functions. One such function is `main`. The programs in Chapters 1 through 5 use only the function `main`; the programming instructions are packed into one function. This technique, however, is good only for short programs. For large programs, it is not practical (although it is possible) to put the entire programming instructions into one function, as you will soon discover. You must learn to break the problem into manageable pieces. This chapter first discusses the functions previously defined and then discusses user-defined functions.

Let us imagine an automobile factory. When an automobile is manufactured, it is not made from basic raw materials; it is put together from previously manufactured parts. Some parts are made by the company itself; others, by different companies.

Functions are like building blocks. They let you divide complicated programs into manageable pieces. They have other advantages, too:

- While working on one function, you can focus on just that part of the program and construct it, debug it, and perfect it.
- Different people can work on different functions simultaneously.
- If a function is needed in more than one place in a program or in different programs, you can write it once and use it many times.
- Using functions greatly enhances the program's readability because it reduces the complexity of the function `main`.

Functions are often called **modules**. They are like miniature programs; you can put them together to form a larger program. When user-defined functions are discussed, you will see that this is the case. This ability is less apparent with predefined functions because their programming code is not available to us. However, because predefined functions are already written for us, you will learn these first so that you can use them when needed.

Predefined Functions

Before formally discussing predefined functions in C++, let us review a concept from a college algebra course. In algebra, a function can be considered a rule or correspondence between values, called the function's arguments, and the unique values of the function associated with the arguments. Thus, if $f(x) = 2x + 5$, then $f(1) = 7$, $f(2) = 9$, and $f(3) = 11$, where 1, 2, and 3 are the arguments of f , and 7, 9, and 11 are the corresponding values of the function f .

In C++, the concept of a function, either predefined or user-defined, is similar to that of a function in algebra. For example, every function has a name and, depending on the values specified by the user, it does some computation. This section discusses various predefined functions.

Some of the predefined mathematical functions are `pow(x, y)`, `sqrt(x)`, and `floor(x)`.

The *power* function, `pow(x, y)`, calculates x^y ; that is, the value of `pow(x, y) = x^y` . For example, `pow(2, 3) = $2^3 = 8.0$` and `pow(2.5, 3) = $2.5^3 = 15.625$` . Because the value of `pow(x, y)` is of type `double`, we say that the function `pow` is of type `double` or that the function `pow` returns a value of type `double`. Moreover, `x` and `y` are called the parameters (or arguments) of the function `pow`. Function `pow` has two parameters.

The *square root* function, `sqrt(x)`, calculates the nonnegative square root of `x` for `x >= 0.0`. For example, `sqrt(2.25)` is `1.5`. The function `sqrt` is of type `double` and has only one parameter.

The *floor* function, `floor(x)`, calculates the largest whole number that is less than or equal to `x`. For example, `floor(48.79)` is `48.0`. The function `floor` is of type `double` and has only one parameter.

In C++, predefined functions are organized into separate libraries. For example, the header file `iostream` contains I/O functions, and the header file `cmath` contains math functions. Table 6-1 lists some of the predefined functions, the name of the header file in which each function's specification can be found, the data type of the parameters, and the function type. The function type is the data type of the final value returned by the function. (For a list of additional predefined functions, see Appendix F.)

TABLE 6-1 Predefined Functions

| Function | Header File | Purpose | Parameter(s) Type | Result |
|----------------------|----------------------------|----------------------------------------------------------------------------------------------------------|---------------------------------------------|---------------------------------------------|
| <code>abs(x)</code> | <code><cmath></code> | Returns the absolute value of its argument: <code>abs(-7) = 7</code> | <code>int</code> (<code>double</code>) | <code>int</code> (<code>double</code>) |
| <code>ceil(x)</code> | <code><cmath></code> | Returns the smallest whole number that is not less than <code>x</code> : <code>ceil(56.34) = 57.0</code> | <code>double</code> | <code>double</code> |
| <code>cos(x)</code> | <code><cmath></code> | Returns the cosine of angle: <code>x: cos(0.0) = 1.0</code> | <code>double</code> (radians) | <code>double</code> |
| <code>exp(x)</code> | <code><cmath></code> | Returns e^x , where $e = 2.718$: <code>exp(1.0) = 2.71828</code> | <code>double</code> | <code>double</code> |
| <code>fabs(x)</code> | <code><cmath></code> | Returns the absolute value of its argument: <code>fabs(-5.67) = 5.67</code> | <code>double</code> | <code>double</code> |

TABLE 6-1 Predefined Functions (continued)

| Function | Header File | Purpose | Parameter(s) Type | Result |
|-------------------------|-----------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|---------------------|
| <code>floor(x)</code> | <code><cmath></code> | Returns the largest whole number that is not greater than <code>x</code> : <code>floor(45.67) = 45.00</code> | <code>double</code> | <code>double</code> |
| <code>islower(x)</code> | <code><cctype></code> | Returns <code>true</code> if <code>x</code> is a lowercase letter; otherwise, it returns <code>false</code> ; <code>islower('h')</code> is <code>true</code> | <code>int</code> | <code>int</code> |
| <code>isupper(x)</code> | <code><cctype></code> | Returns <code>true</code> if <code>x</code> is an uppercase letter; otherwise, it returns <code>false</code> ; <code>isupper('K')</code> is <code>true</code> | <code>int</code> | <code>int</code> |
| <code>pow(x, y)</code> | <code><cmath></code> | Returns <code>x^y</code> ; if <code>x</code> is negative, <code>y</code> must be a whole number: <code>pow(0.16, 0.5) = 0.4</code> | <code>double</code> | <code>double</code> |
| <code>sqrt(x)</code> | <code><cmath></code> | Returns the nonnegative square root of <code>x</code> ; <code>x</code> must be nonnegative: <code>sqrt(4.0) = 2.0</code> | <code>double</code> | <code>double</code> |
| <code>tolower(x)</code> | <code><cctype></code> | Returns the lowercase value of <code>x</code> if <code>x</code> is uppercase; otherwise, it returns <code>x</code> | <code>int</code> | <code>int</code> |
| <code>toupper(x)</code> | <code><cctype></code> | Returns the uppercase value of <code>x</code> if <code>x</code> is lowercase; otherwise, it returns <code>x</code> | <code>int</code> | <code>int</code> |

To use predefined functions in a program, you must include the header file that contains the function's specification via the include statement. For example, to use the function `pow`, the program must include:

```
#include <cmath>
```

Example 6-1 shows you how to use some of the predefined functions.

EXAMPLE 6-1

```

//How to use predefined functions.
#include <iostream>
#include <cmath>
#include <cctype>

using namespace std;

int main()
{
    int    x;
    double u, v;

    cout << "Line 1: Uppercase a is "
          << static_cast<char>(toupper('a'))
          << endl;                                     //Line 1

    u = 4.2;                                           //Line 2
    v = 3.0;                                           //Line 3
    cout << "Line 4: " << u << " to the power of "
          << v << " = " << pow(u, v) << endl;         //Line 4

    cout << "Line 5: 5.0 to the power of 4 = "
          << pow(5.0, 4) << endl;                       //Line 5

    u = u + pow(3.0, 3);                               //Line 6
    cout << "Line 7: u = " << u << endl;               //Line 7

    x = -15;                                           //Line 8
    cout << "Line 9: Absolute value of " << x
          << " = " << abs(x) << endl;                 //Line 9

    return 0;
}

```

Sample Run:

```

Line 1: Uppercase a is A
Line 4: 4.2 to the power of 3 = 74.088
Line 5: 5.0 to the power of 4 = 625
Line 7: u = 31.2
Line 9: Absolute value of -15 = 15

```

This program works as follows. The statement in Line 1 outputs the uppercase letter that corresponds to 'a', which is A. Note that the function `toupper` returns an `int` value. Therefore, the value of the expression `toupper('a')` is 65, which is the ASCII value of 'A'. To print A rather than 65, you need to apply the `cast` operator, as shown in the statement in Line 1. In the statement in Line 4, the function `pow` is used to output u^v . In C++ terminology, it is said that the function `pow` is called with the parameters `u` and `v`. In this case, the values of `u` and `v` are passed to the function `pow`. The other statements have similar meanings. Note that the program includes the header files `cctype` and `cmath`, because it uses the functions `toupper`, `pow`, and `abs` from these header files.

User-Defined Functions

As Example 6-1 illustrates, using functions in a program greatly enhances the program's readability because it reduces the complexity of the function `main`. Also, once you write and properly debug a function, you can use it in the program (or different programs) again and again without having to rewrite the same code repeatedly. For instance, in Example 6-1, the function `pow` is used more than once.

Because C++ does not provide every function that you will ever need and designers cannot possibly know a user's specific needs, you must learn to write your own functions.

User-defined functions in C++ are classified into two categories:

- **Value-returning functions**—functions that have a return type. These functions return a value of a specific data type using the `return` statement, which we will explain shortly.
- **Void functions**—functions that do not have a return type. These functions *do not* use a `return` statement to return a value.

The remainder of this chapter discusses value-returning functions. Many of the concepts discussed in regard to value-returning functions also apply to void functions. Chapter 7 describes void functions.

Value-Returning Functions

The previous section introduced some predefined C++ functions such as `pow`, `abs`, `islower`, and `toupper`. These are examples of value-returning functions. To use these functions in your programs, you must know the name of the header file that contains the functions' specification. You need to include this header file in your program using the include statement and know the following items:

1. The name of the function
2. The number of **parameters**, if any
3. The data type of each parameter
4. The data type of the value computed (that is, the value returned) by the function, called the type of the function

Because the value returned by a value-returning function is unique, the natural thing for you to do is to use the value in one of three ways:

- Save the value for further calculation.
- Use the value in some calculation.
- Print the value.

This suggests that a value-returning function is used:

- In an assignment statement.
- As a parameter in a function call.
- In an output statement.

That is, a value-returning function is used (called) in an expression.

Before we look at the syntax of a user-defined, value-returning function, let us consider the things associated with such functions. In addition to the four properties described previously, one more thing is associated with functions (both value-returning and void):

5. The code required to accomplish the task

The first four properties form what is called the **heading** of the function (also called the **function header**); the fifth property is called the **body** of the function. Together, these five properties form what is called the **definition** of the function. For example, for the function `abs`, the heading might look like:

```
int abs(int number)
```

Similarly, the function `abs` might have the following definition:

```
int abs(int number)
{
    if (number < 0)
        number = -number;

    return number;
}
```

The variable declared in the heading of the function `abs` is called the **formal parameter** of the function `abs`. Thus, the formal parameter of `abs` is `number`.

The program in Example 6-1 contains several statements that use the function `pow`. That is, in C++ terminology, the function `pow` is called several times. Later in this chapter, we discuss what happens when a function is called.

Suppose that the heading of the function `pow` is:

```
double pow(double base, double exponent)
```

From the heading of the function `pow`, it follows that the formal parameters of `pow` are `base` and `exponent`. Consider the following statements:

```
double u = 2.5;
double v = 3.0;
double x, y;

x = pow(u, v); //Line 1
y = pow(2.0, 3.2) + 5.1; //Line 2
cout << u << " to the power of 7 = " << pow(u, 7) << endl; //Line 3
```

In Line 1, the function `pow` is called with the parameters `u` and `v`. In this case, the values of `u` and `v` are passed to the function `pow`. In fact, the value of `u` is copied into `base`, and the value of `v` is copied into `exponent`. The variables `u` and `v` that appear in the call to the function `pow` in Line 1 are called the **actual parameters** of that call. In Line 2, the function `pow` is called with the parameters `2.0` and `3.2`. In this call, the value `2.0` is copied into `base`, and `3.2` is copied into `exponent`. Moreover, in this call of the function `pow`, the actual parameters are `2.0` and `3.2`, respectively. Similarly, in Line 3, the actual parameters of the function `pow` are `u` and `7`; the value of `u` is copied into `base`, and `7.0` is copied into `exponent`.

We can now formally present two definitions:

Formal Parameter: A variable declared in the function heading.

Actual Parameter: A variable or expression listed in a call to a function.

For predefined functions, you need to be concerned only with the first four properties. Software companies do not give out the actual source code, which is the body of the function. Otherwise, software costs would be exorbitant.

Syntax: Value-Returning function

The syntax of a value-returning function is:

```
functionType functionName(formal parameter list)
{
    statements
}
```

in which statements are usually declaration statements and/or executable statements. In this syntax, `functionType` is the type of the value that the function returns. The `functionType` is also called the **data type** or the **return type** of the value-returning function. Moreover, statements enclosed between curly braces form the body of the function.

Syntax: Formal Parameter List

The syntax of the formal parameter list is:

```
dataType identifier, dataType identifier, ...
```

Function Call

The syntax to call a value-returning function is:

```
functionName(actual parameter list)
```

Syntax: Actual Parameter List

The syntax of the actual parameter list is:

```
expression or variable, expression or variable, ...
```

(In this syntax, **expression** can be a single constant value.) Thus, to call a value-returning function, you use its name, with the actual parameters (if any) in parentheses.

A function's formal parameter list *can* be empty. However, if the formal parameter list is empty, the parentheses are still needed. The function heading of the value-returning function thus takes, if the formal parameter list is empty, the following form:

```
functionType functionName()
```

If the formal parameter list of a value-returning function is empty, the actual parameter is also empty in a function call. In this case (that is, an empty formal parameter list), in a function call, the empty parentheses are still needed. Thus, a call to a value-returning function with an empty formal parameter list is:

```
functionName()
```

In a function call, the number of actual parameters, together with their data types, must match with the formal parameters in the order given. That is, actual and formal parameters have a one-to-one correspondence. (Chapter 7 discusses functions with default parameters.)

As stated previously, a value-returning function is called in an expression. The expression can be part of either an assignment statement or an output statement, or a parameter in a function call. A function call in a program causes the body of the called function to execute.

return Statement

Once a value-returning function computes the value, the function returns this value via the **return** statement. In other words, it passes this value outside the function via the **return** statement.

Syntax: return Statement

The **return** statement has the following syntax:

```
return expr;
```

in which **expr** is a variable, constant value, or expression. The **expr** is evaluated, and its value is returned. The data type of the value that **expr** computes must match the function type.

In C++, **return** is a reserved word.

When a **return** statement executes in a function, the function immediately terminates and the control goes back to the caller. Moreover, the function call statement is replaced by the value returned by the **return** statement. When a **return** statement executes in the function **main**, the program terminates.

To put the ideas in this discussion to work, let us write a function that determines the larger of two numbers. Because the function compares two numbers, it follows that this function has two parameters and that both parameters are numbers. Let us assume that the data type of these numbers is floating-point (decimal)—say, **double**. Because the larger number is of type **double**, the function's data type is also **double**. Let us name this function **larger**. The only thing you need to complete this function is the body of the function. Thus, following the syntax of a function, you can write this function as follows:

```
double larger(double x, double y)
{
    double max;

    if (x >= y)
        max = x;
    else
        max = y;

    return max;
}
```

Note that the function **larger** requires that you use an additional variable **max** (called a **local declaration**, in which **max** is a variable local to the function **larger**). Figure 6-1 describes various parts of the function **larger**.




FIGURE 6-1 Various parts of the function `larger`

Suppose that `num`, `num1`, and `num2` are `double` variables. Also suppose that `num1 = 45.75` and `num2 = 35.50`. Figure 6-2 shows various calls to the function `larger`.




FIGURE 6-2 Function calls

You can also write the definition of the function `larger` as follows:

```
double larger(double x, double y)
{
    if (x >= y)
        return x;
    else
        return y;
}
```

Because the execution of a `return` statement in a function terminates the function, the preceding function `larger` can also be written (without the word `else`) as:

```
double larger(double x, double y)
{
    if (x >= y)
        return x;

    return y;
}
```

Note that these forms of the function `larger` do not require you to declare any local variable.

NOTE

1. In the definition of the function `larger`, `x` and `y` are formal parameters.
2. The `return` statement can appear anywhere in the function. Recall that once a `return` statement executes, all subsequent statements are skipped. Thus, it's a good idea to return the value as soon as it is computed.

EXAMPLE 6-2

Now that the function `larger` is written, the following C++ code illustrates how to use it.

```
double one = 13.00;
double two = 36.53;
double maxNum;
```

Consider the following statements:

```
cout << "The larger of 5 and 6 is " << larger(5, 6)
    << endl;                                     //Line 1

cout << "The larger of " << one << " and " << two
    << " is " << larger(one, two) << endl;       //Line 2

cout << "The larger of " << one << " and 29 is "
    << larger(one, 29) << endl;                 //Line 3

maxNum = larger(38.45, 56.78);                  //Line 4
```

- The expression `larger(5, 6)` in Line 1 is a function call, and 5 and 6 are actual parameters. When the expression `larger(5, 6)` executes, 5 is copied into `x`, and 6 is copied into `y`. Therefore, the statement in Line 1 outputs the larger of 5 and 6.
- The expression `larger(one, two)` in Line 2 is a function call. Here, `one` and `two` are actual parameters. When the expression `larger(one, two)` executes, the value of `one` is copied into `x`, and the value of `two` is copied into `y`. Therefore, the statement in Line 2 outputs the larger of `one` and `two`.
- The expression `larger(one, 29)` in Line 3 is also a function call. When the expression `larger(one, 29)` executes, the value of `one` is copied into `x`, and 29 is copied into `y`. Therefore, the statement in Line 3 outputs the larger of `one` and 29.
- The expression `larger(38.45, 56.78)` in Line 4 is a function call. In this call, the actual parameters are 38.45 and 56.78. In this statement, the value returned by the function `larger` is assigned to the variable `maxNum`.

NOTE

In a function call, you specify only the actual parameter, not its data type. For example, in Example 6-2, the statements in Lines 1, 2, 3, and 4 show how to call the function `larger` with the actual parameters. However, the following statements contain incorrect calls to the function `larger` and would result in syntax errors. (Assume that all variables are properly declared.)

```
x = larger(int one, 29);           //illegal
y = larger(int one, int 29);       //illegal
cout << larger(int one, int two);   //illegal
```

Once a function is written, you can use it anywhere in the program. The function `larger` compares two numbers and returns the larger of the two. Let us now write another function that uses this function to determine the largest of three numbers. We call this function `compareThree`.

```
double compareThree(double x, double y, double z)
{
    return larger(x, larger(y, z));
}
```

In the function heading, `x`, `y`, and `z` are formal parameters.

Let us take a look at the expression:

```
larger(x, larger(y, z))
```

in the definition of the function `compareThree`. This expression has two calls to the function `larger`. The actual parameters to the outer call are `x` and `larger(y, z)`; the actual parameters to the inner call are `y` and `z`. It follows that, first, the expression `larger(y, z)` is evaluated; that is, the inner call executes first, which gives the larger of `y` and `z`. Suppose that `larger(y, z)` evaluates to, say, `t`. (Notice that `t` is either `y` or `z`.) Next, the outer call determines the larger of `x` and `t`. Finally, the `return` statement returns the largest number. It thus follows that to execute a function call, the parameters are evaluated first. For example, the actual parameter `larger(y, z)` of the outer call evaluates first.

Note that the function `larger` is much more general purpose than the function `compareThree`. Here, we are merely illustrating that once you have written a function, you can use it to write other functions. Later in this chapter, we will show how to use the function `larger` to determine the largest number from a set of numbers.

Function Prototype

Now that you have some idea of how to write and use functions in a program, the next question relates to the order in which user-defined functions should appear in a program. For example, do you place the function `larger` before or after the function `main`? Should `larger` be placed before `compareThree` or after it? Following the rule that you must declare an identifier before you can use it and knowing that the function `main` uses the identifier `larger`, logically you must place `larger` before `main`.

In reality, C++ programmers customarily place the function `main` before all other user-defined functions. However, this organization could produce a compilation error because functions are compiled in the order in which they appear in the program. For example, if the function `main` is placed before the function `larger`, the identifier `larger` is undefined when the function `main` is compiled. To work around this problem of undeclared identifiers, we place **function prototypes** before any function definition (including the definition of `main`).

Function Prototype: The function heading without the body of the function.

Syntax: Function Prototype

The general syntax of the function prototype of a value-returning function is:

```
functionType functionName(parameter list);
```

(Note that the function prototype ends with a semicolon.)

For the function `larger`, the prototype is:

```
double larger(double x, double y);
```

NOTE

When writing the function prototype, you do not have to specify the variable name in the parameter list. However, you must specify the data type of each parameter.

You can rewrite the function prototype of the function `larger` as follows:

```
double larger(double, double);
```

FINAL PROGRAM

You now know enough to write the entire program, compile it, and run it. The following program uses the functions `larger`, `compareThree`, and `main` to determine the larger/largest of two or three numbers.

```
//Program: Largest of three numbers

#include <iostream>

using namespace std;

double larger(double x, double y);
double compareThree(double x, double y, double z);

int main()
{
    double one, two;                                //Line 1

    cout << "Line 2: The larger of 5 and 10 is "
          << larger(5, 10) << endl;                  //Line 2

    cout << "Line 3: Enter two numbers: ";           //Line 3
    cin >> one >> two;                                //Line 4
    cout << endl;                                     //Line 5

    cout << "Line 6: The larger of " << one
          << " and " << two << " is "
          << larger(one, two) << endl;                //Line 6
}
```

```

        cout << "Line 7: The largest of 43.48, 34.00, "
              << "and 12.65 is "
              << compareThree(43.48, 34.00, 12.65)
              << endl;                                     //Line 7

    return 0;
}

double larger(double x, double y)
{
    double max;

    if (x >= y)
        max = x;
    else
        max = y;

    return max;
}

double compareThree (double x, double y, double z)
{
    return larger(x, larger(y, z));
}

```

Sample Run: In this sample run, the user input is shaded.

Line 2: The larger of 5 and 10 is 10

Line 3: Enter two numbers: 25.6 73.85

Line 6: The larger of 25.6 and 73.85 is 73.85

Line 7: The largest of 43.48, 34.00, and 12.65 is 43.48

NOTE

In the previous program, the function prototypes of the functions `larger` and `compareThree` appear before their function definitions. Therefore, the definition of the functions `larger` and `compareThree` can appear in any order.

Value-Returning Functions: Some Peculiarity

A value-returning function must return a value. Consider the following function, `secret`, that takes as a parameter an `int` value. If the value of the parameter, `x`, is greater than 5, it returns twice the value of `x`; otherwise, the value of `x` remains unchanged.

```

int secret(int x)
{
    if (x > 5)           //Line 1
        return 2 * x;    //Line 2
}

```

Because this is a value-returning function of type `int`, it must return a value of type `int`. Suppose the value of `x` is 10. Then the expression `x > 5` in Line 1 evaluates to `true`. So the `return` statement in Line 2 returns the value 20. Now suppose that `x` is 3. The

expression `x > 5` in Line 1 now evaluates to `false`. The `if` statement therefore fails, and the `return` statement in Line 2 *does not* execute. However, there are no more statements to be executed in the body of the function. In this case, the function returns a strange value. It thus follows that if the value of `x` is less than or equal to 5, the function does not contain any valid `return` statements to return the value of `x`.

A correct definition of the function `secret` is:

```
int secret(int x)
{
    if (x > 5)           //Line 1
        return 2 * x;    //Line 2

    return x;           //Line 3
}
```

Here, if the value of `x` is less than or equal to 5, the `return` statement in Line 3 executes, which returns the value of `x`. On the other hand, if the value of `x` is, say 10, the `return` statement in Line 2 executes, which returns the value 20 and also terminates the function.

Recall that in a value-returning function, the `return` statement returns the value. Consider the following `return` statement:

```
return x, y; //only the value of y will be returned
```

This is a legal `return` statement. You might think that this `return` statement is returning the values of `x` and `y`. However, this is not the case. Remember, a `return` statement returns only one value, even if the `return` statement contains more than one expression. If a `return` statement contains more than one expression, *only the value of the last expression is returned*. Therefore, in the case of the above `return` statement, the value of `y` is returned. The following program further illustrates this concept.

```
// This program illustrates that a value-returning function
// returns only one value, even if the return statement
// contains more than one expression.

#include <iostream>

using namespace std;

int funcRet1();
int funcRet2(int z);

int main()
{
    int num = 4;

    cout << "Line 1: The value returned by funcRet1: "
          << funcRet1() << endl;           // Line 1
```

```

        cout << "Line 2: The value returned by funcRet2: "
              << funcRet2(num) << endl;           // Line 2

    return 0;
}

int funcRet1()
{
    int x = 45;

    return 23, x; //only the value of x is returned
}

int funcRet2(int z)
{
    int a = 2;
    int b = 3;

    return 2 * a + b, z + b; //only the value of z + b is returned
}

```

Sample Run:

Line 1: The value returned by funcRet1: 45
 Line 2: The value returned by funcRet2: 7

Even though a **return** statement can contain more than one expression, a return statement in your program should contain only one expression. Having more than one expression in a **return** statement may result in redundancy, wasted code, and a confusing syntax.

More Examples of Value-Returning Functions

EXAMPLE 6-3

In this example, we write the definition of function **courseGrade**. This function takes as a parameter an **int** value specifying the score for a course and returns the grade, a value of type **char**, for the course. (We assume that the test score is a value between 0 and 100 inclusive.)

```

char courseGrade(int score)
{
    switch (score / 10)
    {
        case 0:
        case 1:
        case 2:
        case 3:

```

```

    case 4:
    case 5:
        return 'F';
    case 6:
        return 'D';
    case 7:
        return 'C';
    case 8:
        return 'B';
    case 9:
    case 10:
        return 'A';
    }
}

```

You can also write an equivalent definition of the function `courseGrade` that uses an `if...else` structure to determine the course grade.

EXAMPLE 6-4 (ROLLING A PAIR OF DICE)

In this example, we write a function that rolls a pair of dice until the sum of the numbers rolled is a specific number. We also want to know the number of times the dice are rolled to get the desired sum.

The smallest number on each die is 1, and the largest number is 6. So the smallest sum of the numbers rolled is 2, and the largest sum of the numbers rolled is 12. Suppose that we have the following declarations.

```

int die1;
int die2;
int sum;
int rollCount = 0;

```

We use the random number generator, discussed in Chapter 5, to randomly generate a number between 1 and 6. Then, the following statement randomly generates a number between 1 and 6 and stores that number into `die1`, which becomes the number rolled by `die1`.

```
die1 = rand() % 6 + 1;
```

Similarly, the following statement randomly generates a number between 1 and 6 and stores that number into `die2`, which becomes the number rolled by `die2`.

```
die2 = rand() % 6 + 1;
```

The sum of the numbers rolled by two dice is:

```
sum = die1 + die2;
```

Next, we determine whether `sum` contains the desired sum of the numbers rolled by the dice. If `sum` does not contain the desired sum, then we roll the dice again. This can be accomplished by the following `do...while` loop. (Assume that the `int` variable `num` contains the desired sum to be rolled.)

```
do
{
    die1 = rand() % 6 + 1;
    die2 = rand() % 6 + 1;
    sum = die1 + die2;
    rollCount++;
}
while (sum != num);
```

We can now write the function `rollDice` that takes as a parameter the desired sum of the numbers to be rolled and returns the number of times the dice are rolled to roll the desired sum.

```
int rollDice(int num)
{
    int die1;
    int die2;
    int sum;
    int rollCount = 0;

    srand(time(0));

    do
    {
        die1 = rand() % 6 + 1;
        die2 = rand() % 6 + 1;
        sum = die1 + die2;
        rollCount++;
    }
    while (sum != num);

    return rollCount;
}
```

The following program shows how to use the function `rollDice` in a program.

//Program: Roll dice

```
#include <iostream>
#include <cstdlib>
#include <ctime>

using namespace std;

int rollDice(int num);
```

```

int main()
{
    cout << "The number of times the dice are rolled to "
          << "get the sum 10 = " << rollDice(10) << endl;
    cout << "The number of times the dice are rolled to "
          << "get the sum 6 = " << rollDice(6) << endl;

    return 0;
}

int rollDice(int num)
{
    int die1;
    int die2;
    int sum;
    int rollCount = 0;

    srand(time(0));

    do
    {
        die1 = rand() % 6 + 1;
        die2 = rand() % 6 + 1;
        sum = die1 + die2;
        rollCount++;
    }
    while (sum != num);

    return rollCount;
}

```

Sample Run:

```

The number of times the dice are rolled to get the sum 10 = 11
The number of times the dice are rolled to get the sum 6 = 7

```

We leave it as an exercise for you to modify this program so that it allows the user to enter the desired sum of the numbers to be rolled. (See Programming Exercise 8 at the end of this chapter.)

Following is an example of a function that returns a Boolean value.

EXAMPLE 6-5 (PALINDROME NUMBER)

In this example, a function, `isNumPalindrome`, is designed that returns `true` if a nonnegative integer is a palindrome and returns `false` otherwise. A nonnegative integer

is a palindrome if it reads forward and backward in the same way. For example, the integers 5, 44, 434, 1881, and 789656987 are all palindromes.

Suppose `num` is a nonnegative integer. If `num < 10`, it is a palindrome, so the function should return `true`. Suppose `num >= 10`. To determine whether `num` is a palindrome, first compare the first and the last digits of `num`. If the first and the last digits of `num` are not the same, it is not a palindrome, so the function should return `false`. If the first and the last digits of `num` are the same, remove the first and last digits of `num` and repeat this process on the new number, which is obtained from `num` after removing the first and last digits of `num`. Repeat this process as long as the number is `>= 10`.

For example, suppose that the input is 18281. Because the first and last digits of 18281 are the same, remove the first and last digits to get the number 828. Repeat this process of comparing the first and last digits on 828. Once again, the first and last digits are the same. After removing the first and last digits of 828, the resulting number is 2, which is less than 10. Thus, 18281 is a palindrome.

To remove the first and last digits of `num`, you first need to find the highest power of 10 that divides `num` and call it `pwr`. The highest power of 10 that divides 18281 is 4, that is, `pwr = 4`. Now `18281 % 10pwr = 8281`, so the first digit is removed. Also, because `8281 / 10 = 828`, the last digit is removed. Therefore, to remove the first digit, you can use the mod operator, in which the divisor is `10pwr`. To remove the last digit, divide the number by 10. You then decrement `pwr` by 2 for the next iteration. The following algorithm implements this discussion:

1. If `num < 10`, it is a palindrome, so the function should return `true`.
2. Suppose `num` is an integer and `num >= 10`. To see if `num` is a palindrome:
 - a. Find the highest power of 10 that divides `num` and call it `pwr`. For example, the highest power of 10 that divides 434 is 2; the highest power of 10 that divides 789656987 is 8.
 - b. While `num` is greater than or equal to 10, compare the first and last digits of `num`.
 - b.1. If the first and last digits of `num` are not the same, `num` is not a palindrome. Return `false`.
 - b.2. If the first and the last digits of `num` are the same:
 - b.2.1. Remove the first and last digits of `num`.
 - b.2.2. Decrement `pwr` by 2.
 - c. Return `true`.

The following function implements this algorithm:

```
bool isNumPalindrome(int num)
{
    int pwr = 0;

    if (num < 10)                                //Step 1
        return true;
    else                                          //Step 2
    {
        while (num / static_cast<int>(pow(10.0, pwr)) >= 10) //Step 2.a
            pwr++;
        while (num >= 10)                        //Step 2.b
        {
            int tenTopwr = static_cast<int>(pow(10.0, pwr));

            if ((num / tenTopwr) != (num % 10)) //Step 2.b.1
                return false;                //Step 2.b.2
            else
            {
                num = num % tenTopwr;          //Step 2.b.2.1
                num = num / 10;                //Step 2.b.2.1
                pwr = pwr - 2;                  //Step 2.b.2.2
            }
        } //end while
        return true;
    } //end else
}
```

NOTE

In the definition of the function `isNumPalindrome`, the function `pow` from the header file `cmath` is used to find the highest power of 10 that divides the number. Therefore, make sure to include the header file `cmath` in your program.

Flow of Execution

As stated earlier, a C++ program is a collection of functions. Recall that functions can appear in any order. The only thing that you have to remember is that you must declare an identifier before you can use it. The program is compiled by the compiler sequentially from beginning to end. Thus, if the function `main` appears before any other user-defined functions, it is compiled first. However, if `main` appears at the end (or middle) of the program, all functions whose definitions (not prototypes) appear before the function `main` are compiled before the function `main`, in the order they are placed.

Function prototypes appear before any function definition, so the compiler translates these first. The compiler can then correctly translate a function call. However, when the

program executes, the first statement in the function **main** always executes first, regardless of where in the program the function **main** is placed. Other functions execute only when they are called.

A function call statement transfers control to the first statement in the body of the function. In general, after the last statement of the called function executes, control is passed back to the point immediately following the function call. A value-returning function returns a value. Therefore, after executing the value-returning function, when the control goes back to the caller, the value that the function returns replaces the function call statement. The execution continues at the point immediately following the function call.

Suppose that a program contains functions **funcA** and **funcB**, and **funcA** contains a statement that calls **funcB**. Suppose that the program calls **funcA**. When the statement that contains a call to **funcB** executes, **funcB** executes, and while **funcB** is executing, the execution of the current call of **funcA** is on hold until **funcB** is done.

PROGRAMMING EXAMPLE: Largest Number

In this programming example, the function **larger** is used to determine the largest number from a set of numbers. For the purpose of illustration, this program determines the largest number from a set of 10 numbers. You can easily enhance this program to accommodate any set of numbers.

Input A set of 10 numbers.

Output The largest of 10 numbers.

Suppose that the input data is:

15 20 7 8 28 21 43 12 35 3

Read the first number of the data set. Because this is the only number read to this point, you may assume that it is the largest number so far and call it **max**. Read the second number and call it **num**. Now compare **max** and **num** and store the larger number into **max**. Now **max** contains the larger of the first two numbers. Read the third number. Compare it with **max** and store the larger number into **max**. At this point, **max** contains the largest of the first three numbers. Read the next number, compare it with **max**, and store the larger into **max**. Repeat this process for each remaining number in the data set. Eventually, **max** will contain the largest number in the data set. This discussion translates into the following algorithm:

1. Read the first number. Because this is the only number that you have read so far, it is the largest number so far. Save it in a variable called **max**.

2. For each remaining number in the list:
 - a. Read the next number. Store it in a variable called `num`.
 - b. Compare `num` and `max`. If `max < num`, then `num` is the new largest number, so update the value of `max` by copying `num` into `max`. If `max >= num`, discard `num`; that is, do nothing.
3. Because `max` now contains the largest number, print it.

To find the larger of two numbers, the program uses the function `larger`.

COMPLETE PROGRAM LISTING

```

//*****
// Author: D.S. Malik
//
// This program finds the largest number of a set of 10
// numbers.
//*****

#include <iostream>

using namespace std;

double larger(double x, double y);

int main()
{
    double num; //variable to hold the current number
    double max; //variable to hold the larger number
    int count; //loop control variable

    cout << "Enter 10 numbers." << endl;
    cin >> num; //Step 1
    max = num; //Step 1

    for (count = 1; count < 10; count++) //Step 2
    {
        cin >> num; //Step 2a
        max = larger(max, num); //Step 2b
    }

    cout << "The largest number is " << max
         << endl; //Step 3

    return 0;
} //end main

```

```
double larger(double x, double y)
{
    if (x >= y)
        return x;
    else
        return y;
}
```

Sample Run: In this sample run, the user input is shaded.

```
Enter 10 numbers.
10 56 73 42 22 67 88 26 62 11
The largest number is 88
```

PROGRAMMING EXAMPLE: Cable Company

Chapter 4 contains a program to calculate the bill for a cable company. In that program, all of the programming instructions are packed in the function `main`. Here, we rewrite the same program using user-defined functions, further illustrating structured programming. The problem analysis phase shows how to divide a complex problem into smaller subproblems. It also shows that while solving a particular subproblem, you can focus on only that part of the problem.

Input to and output of the program are the same as before.

PROBLEM ANALYSIS AND ALGORITHM DESIGN

Because there are two types of customers, residential and business, the program contains two separate functions: one to calculate the bill for residential customers and one to calculate the bill for business customers. Both functions calculate the billing amount and then return the billing amount to the function `main`. The function `main` prints the amount due. Let us call the function that calculates the residential bill `residential` and the function that calculates the business bill `business`. The formulas to calculate the bills are the same as before.

As in Chapter 4, data such as the residential bill processing fee, the cost of residential basic service connection, and so on are special. Therefore, these are declared as named constants.

Function `residential`

To compute the residential bill, you need to know the number of premium channels to which the customer subscribes. Based on the number of premium channels, you can calculate the billing amount. After calculating the billing amount, the function returns the billing amount using the `return` statement. The following four steps describe this function:

- a. Prompt the user for the number of premium channels.
- b. Read the number of premium channels.

- c. Calculate the bill.
- d. Return the amount due.

This function contains a statement to prompt the user to enter the number of premium channels (Step a) and a statement to read the number of premium channels (Step b). Other items needed to calculate the billing amount, such as the cost of basic service connection and bill-processing fees, are defined as named constants (before the definition of the function `main`). Therefore, to calculate the billing amount, this function does not need to get any value from the function `main`. This function, therefore, has no parameters.

Local Variables (Function residential) From the previous discussion, it follows that the function `residential` requires variables to store both the number of premium channels and the billing amount. This function needs only two local variables to calculate the billing amount:

```
int noOfPChannels; //number of premium channels
double bAmount;   //billing amount
```

The definition of the function `residential` can now be written as follows:

```
double residential()
{
    int noOfPChannels; //number of premium channels
    double bAmount;    //billing amount
    cout << "Enter the number of premium "
          << "channels used: ";
    cin >> noOfPChannels;
    cout << endl;

    bAmount = RES_BILL_PROC_FEES +
              RES_BASIC_SERV_COST +
              noOfPChannels * RES_COST_PREM_CHANNEL;

    return bAmount;
}
```

Function business To compute the business bill, you need to know the number of both the basic service connections and the premium channels to which the customer subscribes. Then, based on these numbers, you can calculate the billing amount. The billing amount is then returned using the `return` statement. The following six steps describe this function:

- a. Prompt the user for the number of basic service connections.
- b. Read the number of basic service connections.
- c. Prompt the user for the number of premium channels.
- d. Read the number of premium channels.
- e. Calculate the bill.
- f. Return the amount due.

This function contains the statements to prompt the user to enter the number of basic service connections and premium channels (Steps a and c). The function also contains statements to input the number of basic service connections and premium channels (Steps b and d). Other items needed to calculate the billing amount, such as the cost of basic service connections and bill-processing fees, are defined as named constants (before the definition of the function `main`). It follows that to calculate the billing amount, this function does not need to get any values from the function `main`. Therefore, it has no parameters.

Local Variables (Function business) From the preceding discussion, it follows that the function `business` requires variables to store the number of basic service connections and premium channels, as well as the billing amount. In fact, this function needs only three local variables to calculate the billing amount:

```
int noOfBasicServiceConnections;
int noOfPChannels;           //number of premium channels
double bAmount;              //billing amount
```

The definition of the function `business` can now be written as follows:

```
double business()
{
    int noOfBasicServiceConnections;
    int noOfPChannels;           //number of premium channels
    double bAmount;              //billing amount
    cout << "Enter the number of basic "
          << "service connections: ";
    cin >> noOfBasicServiceConnections;
    cout << endl;

    cout << "Enter the number of premium "
          << "channels used: ";
    cin >> noOfPChannels;
    cout << endl;

    if (noOfBasicServiceConnections <= 10)
        bAmount = BUS_BILL_PROC_FEES + BUS_BASIC_SERV_COST +
                  noOfPChannels * BUS_COST_PREM_CHANNEL;
    else
        bAmount = BUS_BILL_PROC_FEES + BUS_BASIC_SERV_COST +
                  (noOfBasicServiceConnections - 10) *
                  BUS_BASIC_CONN_COST +
                  noOfPChannels * BUS_COST_PREM_CHANNEL;

    return bAmount;
}
```

MAIN
ALGORITHM
(Function
main)

1. To output floating-point numbers in a fixed decimal format with the decimal point and trailing zeros, set the manipulators **fixed** and **showpoint**.
2. To output floating-point numbers to two decimal places, set the precision to two decimal places.
3. Prompt the user for the account number.
4. Get the account number.
5. Prompt the user to enter the customer type.
6. Get the customer type.
7.
 - a. If the customer type is R or r:
 - i. Call the function **residential** to calculate the bill.
 - ii. Print the bill.
 - b. If the customer type is B or b:
 - i. Call the function **business** to calculate the bill.
 - ii. Print the bill.
 - c. If the customer type is other than R, r, B, or b, it is an invalid customer type.

COMPLETE PROGRAM LISTING

```

//*****
// Author: D. S. Malik
//
// Program: Cable Company Billing
// This program calculates and prints a customer's bill for
// a local cable company. The program processes two types of
// customers: residential and business.
//*****

#include <iostream>
#include <iomanip>
using namespace std;

    //Named constants - residential customers
const double RES_BILL_PROC_FEES = 4.50;
const double RES_BASIC_SERV_COST = 20.50;
const double RES_COST_PREM_CHANNEL = 7.50;

    //Named constants - business customers
const double BUS_BILL_PROC_FEES = 15.00;
const double BUS_BASIC_SERV_COST = 75.00;
const double BUS_BASIC_CONN_COST = 5.00;
const double BUS_COST_PREM_CHANNEL = 50.00;

```

```

double residential();           //Function prototype
double business();             //Function prototype

int main()
{
    //declare variables
    int accountNumber;
    char customerType;
    double amountDue;

    cout << fixed << showpoint;           //Step 1
    cout << setprecision(2);              //Step 2

    cout << "This program computes a cable bill."
        << endl;
    cout << "Enter account number: ";      //Step 3
    cin >> accountNumber;                  //Step 4
    cout << endl;

    cout << "Enter customer type: R, r "
        << "(Residential), B, b (Business): "; //Step 5
    cin >> customerType;                  //Step 6
    cout << endl;

    switch (customerType)               //Step 7
    {
        case 'r':                       //Step 7a
        case 'R':
            amountDue = residential();   //Step 7a.i
            cout << "Account number = "
                << accountNumber << endl; //Step 7a.ii
            cout << "Amount due = $"
                << amountDue << endl;    //Step 7a.ii
            break;
        case 'b':                       //Step 7b
        case 'B':
            amountDue = business();       //Step 7b.i
            cout << "Account number = "
                << accountNumber << endl; //Step 7b.ii
            cout << "Amount due = $"
                << amountDue << endl;    //Step 7b.ii
            break;
        default:
            cout << "Invalid customer type."
                << endl;                //Step 7c
    }

    return 0;
}

```

```

double residential()
{
    int noOfPChannels;    //number of premium channels
    double bAmount;       //billing amount

    cout << "Enter the number of premium "
          << "channels used: ";
    cin >> noOfPChannels;
    cout << endl;

    bAmount = RES_BILL_PROC_FEES +
              RES_BASIC_SERV_COST +
              noOfPChannels * RES_COST_PREM_CHANNEL;

    return bAmount;
}

double business()
{
    int noOfBasicServiceConnections;
    int noOfPChannels;    //number of premium channels
    double bAmount;       //billing amount

    cout << "Enter the number of basic "
          << "service connections: ";
    cin >> noOfBasicServiceConnections;
    cout << endl;
    cout << "Enter the number of premium "
          << "channels used: ";
    cin >> noOfPChannels;
    cout << endl;

    if (noOfBasicServiceConnections <= 10)
        bAmount = BUS_BILL_PROC_FEES + BUS_BASIC_SERV_COST +
                  noOfPChannels * BUS_COST_PREM_CHANNEL;
    else
        bAmount = BUS_BILL_PROC_FEES + BUS_BASIC_SERV_COST +
                  (noOfBasicServiceConnections - 10) *
                  BUS_BASIC_CONN_COST +
                  noOfPChannels * BUS_COST_PREM_CHANNEL;

    return bAmount;
}

```

Sample Run: In this sample run, the user input is shaded.

This program computes a cable bill.

Enter account number: 21341

Enter customer type: R, r (Residential), B, b (Business): B

Enter the number of basic service connections: 25

Enter the number of premium channels used: 9

Account number = 21341

Amount due = \$615.00

QUICK REVIEW

1. Functions are like miniature programs and are called modules.
2. Functions enable you to divide a program into manageable tasks.
3. The C++ system provides the standard (predefined) functions.
4. To use a standard function, you must:
 - i. Know the name of the header file that contains the function's specification,
 - ii. Include that header file in the program, and
 - iii. Know the name and type of the function and number and types of the parameters (arguments).
5. There are two types of user-defined functions: value-returning functions and void functions.
6. Variables defined in a function heading are called formal parameters.
7. Expressions, variables, or constant values used in a function call are called actual parameters.
8. In a function call, the number of actual parameters and their types must match with the formal parameters in the order given.
9. To call a function, use its name together with the actual parameter list.
10. A value-returning function returns a value. Therefore, a value-returning function is used (called) in either an expression or an output statement or as a parameter in a function call.
11. The general syntax of a user-defined function is:


```
functionType functionName(formal parameter list)
{
    statements
}
```
12. The line `functionType functionName(formal parameter list)` is called the function heading (or function header). Statements enclosed between braces (`{` and `}`) are called the body of the function.
13. The function heading and the body of the function are called the definition of the function.

14. If a function has no parameters, you still need the empty parentheses in both the function heading and the function call.
15. A value-returning function returns its value via the `return` statement.
16. A function can have more than one `return` statement. However, whenever a `return` statement executes in a function, the remaining statements are skipped and the function exits.
17. A `return` statement returns only one value.
18. A function prototype is the function heading without the body of the function; the function prototype ends with the semicolon.
19. A function prototype announces the function type, as well as the type and number of parameters, used in the function.
20. In a function prototype, the names of the variables in the formal parameter list are optional.
21. Function prototypes help the compiler correctly translate each function call.
22. In a program, function prototypes are placed before every function definition, including the definition of the function `main`.
23. When you use function prototypes, user-defined functions can appear in any order in the program.
24. When the program executes, the execution always begins with the first statement in the function `main`.
25. User-defined functions execute only when they are called.
26. A call to a function transfers control from the caller to the called function.
27. In a function call statement, you specify only the actual parameters, not their data type or the function type.
28. When a function exits, the control goes back to the caller.

EXERCISES

1. Mark the following statements as true or false.
 - a. To use a predefined function in a program, you need to know only the name of the function and how to use it.
 - b. A value-returning function returns only one value.
 - c. Parameters allow you to use different values each time the function is called.
 - d. When a `return` statement executes in a user-defined function, the function immediately exits.
 - e. A value-returning function returns only integer values.

2. Determine the value of each of the following expressions.
 - a. `static_cast<char>(toupper('b'))`
 - b. `static_cast<char>(toupper('7'))`
 - c. `static_cast<char>(toupper('K'))`
 - d. `static_cast<char>(toupper('*'))`
 - e. `static_cast<char>(tolower('D'))`
 - f. `static_cast<char>(tolower('8'))`
 - g. `static_cast<char>(tolower('h'))`
 - h. `static_cast<char>(tolower('$'))`
3. Determine the value of each of the following expressions.
 - a. `abs(-4)` b. `fabs(10.8)` c. `fabs(-2.5)` d. `pow(3.2, 2)`
 - e. `pow(2.5, 3)` f. `sqrt(25.0)` g. `sqrt(6.25)`
 - h. `pow(3.0, 4.0) / abs(-9)` i. `floor(28.95)` j. `ceil(35.2)`
4. Using the functions described in Table 6-1, write each of the following as a C++ expression. (The expression in (e) denotes the absolute value of $x + 2.5$.)
 - a. $2.0^{5.2}$ b. $\sqrt{x+y}$ c. $u^v - 3$ d. $\frac{-b + \sqrt{b^2 - 4ac}}{2a}$ e. $|x + 2.5|$
5. Consider the following function definition:

```
double func(double x, int y, string name)
{
    //function body
}
```

Which of the following is the correct function prototype of the function `func`?

- i. `double func();`
 - ii. `double func(double, int, string);`
 - iii. `double func(double x, int y, string name)`
 - iv. `func(double x, int y, string name);`
6. Consider the following program:

```
#include <iostream>
#include <cmath>

using namespace std;

int main()
{
    int num1;
    int num2;

    cout << "Enter two integers: ";
    cin >> num1 >> num2;
    cout << endl;
```

```

    if (num1 != 0 && num2 != 0)
        cout << sqrt(fabs(num1 + num2 + 0.0)) << endl;
    else if (num1 != 0)
        cout << floor(num1 + 0.0) << endl;
    else if (num2 != 0)
        cout << ceil(num2 + 0.0) << endl;
    else
        cout << 0 << endl;

    return 0;
}

```

- a. What is the output if the input is 12 4?
- b. What is the output if the input is 3 27?
- c. What is the output if the input is 25 0?
- d. What is the output if the input is 0 49?

7. Consider the following statements:

```

double num1, num2, num3;
int int1, int2, int3;
int value;

```

```

num1 = 5.0; num2 = 6.0; num3 = 3.0;
int1 = 4; int2 = 7; int3 = 8;

```

and the function prototype:

```
double cube(double a, double b, double c);
```

Which of the following statements are valid? If they are invalid, explain why.

- a. `value = cube (num1, 15.0, num3);`
 - b. `cout << cube(num1, num3, num2) << endl;`
 - c. `cout << cube(6.0, 8.0, 10.5) << endl;`
 - d. `cout << cube(num1, num3) << endl;`
 - e. `value = cube(num1, int2, num3);`
 - f. `value = cube(7, 8, 9);`
 - g. `value = cube(int1, int2, int3);`
8. Consider the following functions:

```

int secret(int x)
{
    int i, j;

    i = 2 * x;

    if (i > 10)
        j = x / 2;
}

```

```

        else
            j = x / 3;

        return j - 1;
    }

    int another(int a, int b)
    {
        int i, j;

        j = 0;

        for (i = a; i <= b; i++)
            j = j + i;

        return j;
    }

```

What is the output of each of the following program segments? Assume that `x`, `y`, and `k` are `int` variables.

- a. `x = 10;`
`cout << secret(x) << endl;`
 - b. `x = 5; y = 8;`
`cout << another(x, y) << endl;`
 - c. `x = 10; k = secret(x);`
`cout << x << " " << k << " " << another(x, k) << endl;`
 - d. `x = 5; y = 8;`
`cout << another(y, x) << endl;`
9. Consider the following function prototypes:
- ```

int test(int, char, double, int);
double two(double, double);
char three(int, int, char, double);

```

Answer the following questions.

- a. How many parameters does the function `test` have? What is the type of the function `test`?
- b. How many parameters does function `two` have? What is the type of function `two`?
- c. How many parameters does function `three` have? What is the type of function `three`?
- d. How many actual parameters are needed to call the function `test`? What is the type of each actual parameter, and in what order should you use these parameters in a call to the function `test`?
- e. Write a C++ statement that prints the value returned by the function `test` with the actual parameters 5, 5, 7.3, and 'z'.

- f. Write a C++ statement that prints the value returned by function `two` with the actual parameters 17.5 and 18.3, respectively.
- g. Write a C++ statement that prints the next character returned by function `three`. (Use your own actual parameters.)
- 10. Why do you need to include function prototypes in a program that contains user-defined functions?
- 11. Write the definition of a function that takes as input a `char` value and returns `true` if the character is uppercase; otherwise, it returns `false`.
- 12. Consider the following function:

```
int mystery(int x, double y, char ch)
{
 int u;
 if ('A' <= ch && ch <= 'R')
 return (2 * x + static_cast<int>(y));
 else
 return (static_cast<int>(2 * y) - x);
}
```

What is the output of the following C++ statements?

- a. `cout << mystery(5, 4.3, 'B') << endl;`
- b. `cout << mystery(4, 9.7, 'v') << endl;`
- c. `cout << 2 * mystery(6, 3.9, 'D') << endl;`
- 13. Consider the following function:

```
int secret(int one)
{
 int i;
 int prod = 1;

 for (i = 1; i <= 3; i++)
 prod = prod * one;
 return prod;
}
```

- a. What is the output of the following C++ statements?
  - i. `cout << secret(5) << endl;`
  - ii. `cout << 2 * secret(6) << endl;`
- b. What does the function `secret` do?
- 14. Write the definition of a function that takes as input the three numbers. The function returns `true` if the first number to the power of the second number equals the third number; otherwise, it returns `false`. (Assume that the three numbers are of type `double`.)

15. What is the output of the following C++ program?

```
#include <iostream>
#include <cmath>

using namespace std;

int main()
{
 int counter;

 for (counter = 1; counter <= 100; counter++)
 if (pow(floor(sqrt(counter + 0.0)), 2) == counter)
 cout << counter << " ";

 cout << endl;

 return 0;
}
```

16. What is the output of the following program?

```
#include <iostream>

using namespace std;

int mystery(int x, int y, int z);

int main()
{
 cout << mystery(7, 8, 3) << endl;
 cout << mystery(10, 5, 30) << endl;
 cout << mystery(9, 12, 11) << endl;
 cout << mystery(5, 5, 8) << endl;
 cout << mystery(10, 10, 10) << endl;

 return 0;
}

int mystery(int x, int y, int z)
{
 if (x <= y && x <= z)
 return (y + z - x);
 else if (y <= z && y <= x)
 return (z + x - y);
 else
 return (x + y - z);
}
```

17. Write the definition of a function that takes as input three numbers and returns the sum of the first two numbers multiplied by the third number. (Assume that the three numbers are of type `double`.)

18. Show the output of the following program:

```
#include <iostream>

using namespace std;

int mystery(int);

int main()
{
 int n;

 for (n = 1; n <= 5; n++)
 cout << mystery(n) << endl;

 return 0;
}

int mystery(int k)
{
 int x, y;

 y = k;

 for (x = 1; x <= (k - 1); x++)
 y = y * (k - x);

 return y;
}
```

## PROGRAMMING EXERCISES

---

1. Write a program that uses the function `isNumPalindrome` given in Example 6-5 (Palindrome Number). Test your program on the following numbers: 10, 34, 22, 333, 678, 67876, 44444, and 123454321.
2. Write a value-returning function, `isVowel`, that returns the value `true` if a given character is a vowel and otherwise returns `false`.
3. Write a program that prompts the user to input a sequence of characters and outputs the number of vowels. (Use the function `isVowel` written in Programming Exercise 2.)
4. Write a program that defines the named constant `PI`, `const double PI = 3.1419;`, which stores the value of  $\pi$ . The program should use `PI` and the functions listed in Table 6-1 to accomplish the following.
  - a. Output the value of  $\sqrt{\pi}$ .
  - b. Prompt the user to input the value of a `double` variable `r`, which stores the radius of a sphere. The program then outputs the following:
    - i. The value of  $4\pi r^2$ , which is the surface area of the sphere.
    - ii. The value of  $(4/3)\pi r^3$ , which is the volume of the sphere.

5. The following program is designed to find the area of a rectangle, the area of a circle, or the volume of a cylinder. However, (a) the statements are in the incorrect order; (b) the function calls are incorrect; (c) the logical expression in the `while` loop is incorrect; and (d) function definitions are incorrect. Rewrite the program so that it works correctly. Your program must be properly indented. (Note that the program is menu driven and allows the user to run the program as long as the user wishes.)

```
#include <iostream>

using namespace std;

const double PI = 3.1419;

double rectangle(double l, double w);

#include <iomanip>

int main()
{
 double radius;
 double height;

 cout << fixed << showpoint << setprecision(2) << endl;
 cout << "This program can calculate the area of a rectangle, "
 << "the area of a circle, or volume of a cylinder." << endl;
 cout << "To run the program enter: " << endl;
 cout << "1: To find the area of rectangle." << endl;
 cout << "2: To find the area of a circle." << endl;
 cout << "3: To find the volume of a cylinder." << endl;
 cout << "-1: To terminate the program." << endl;
 cin >> choice;
 cout << endl;

 int choice;

 while (choice != -1)
 {
 {
 case 1:
 cout << "Enter the radius of the base and the "
 << "height of the cylinder: ";
 cin >> radius >> height;
 cout << endl;

 cout << "Area = " << circle(length, height) << endl;
 break;

 case 3:
 double length, width;
 cout << "Enter the radius of the circle: ";
 cin >> radius;
 cout << endl;
```

```

 cout << "Area = " << rectangle(radius)
 << endl;
 break;

 case 2:
 cout << "Enter the length and the width "
 << "of the rectangle: ";
 cin >> length >> width;
 cout << endl;

 cout << "Volume = " << cylinder(radius, height)
 << endl;
 break;
 default:
 cout << "Invalid choice!" << endl;
 }
 switch (choice)
 }

double circle(double r)
double cylinder(double bR, double h);

cout << "To run the program enter: " << endl;
cout << "2: To find the area of a circle." << endl;
cout << "1: To find the area of rectangle." << endl;
cout << "3: To find the colume of a cylinder." << endl;
cout << "-1: To terminate the program." << endl;
cin >> choice;
cout << endl;

return 0;
}

double rectangle(double l, double w)
{
 return l * r;
}

double circle(double r)
{
 return PI * r * w;
}

double cylinder(double bR, double h)
{
 return PI * bR * bR * l;
}

```

6. Write a function, `reverseDigit`, that takes an integer as a parameter and returns the number with its digits reversed. For example, the value of `reverseDigit(12345)` is 54321; the value of `reverseDigit(5600)` is 65; the value of `reverseDigit(7008)` is 8007; and the value of `reverseDigit(-532)` is -235.

7. Modify the roll dice program, Example 6-4, so that it allows the user to enter the desired sum of the numbers to be rolled. Also allow the user to call the `rollDice` function as many times as the user desires.
8. The following formula gives the distance between two points,  $(x_1, y_1)$  and  $(x_2, y_2)$  in the Cartesian plane:

$$\sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2}$$

Given the center and a point on the circle, you can use this formula to find the radius of the circle. Write a program that prompts the user to enter the center and a point on the circle. The program should then output the circle's radius, diameter, circumference, and area. Your program must have at least the following functions:

- a. **distance**: This function takes as its parameters four numbers that represent two points in the plane and returns the distance between them.
- b. **radius**: This function takes as its parameters four numbers that represent the center and a point on the circle, calls the function **distance** to find the radius of the circle, and returns the circle's radius.
- c. **circumference**: This function takes as its parameter a number that represents the radius of the circle and returns the circle's circumference. (If  $r$  is the radius, the circumference is  $2\pi r$ .)
- d. **area**: This function takes as its parameter a number that represents the radius of the circle and returns the circle's area. (If  $r$  is the radius, the area is  $\pi r^2$ .)

Assume that  $\pi = 3.1416$ .

9. Rewrite the program in Programming Exercise 15 of Chapter 4 (cell phone company) so that it uses the following functions to calculate the billing amount. (In this programming exercise, do not output the number of minutes during which the service is used.)
  - a. **regularBill**: This function calculates and returns the billing amount for regular service.
  - b. **premiumBill**: This function calculates and returns the billing amount for premium service.
10. Write a program that takes as input five numbers and outputs the mean (average) and standard deviation of the numbers. If the numbers are  $x_1, x_2, x_3, x_4$ , and  $x_5$ , then the mean is  $x = (x_1 + x_2 + x_3 + x_4 + x_5)/5$  and the standard deviation is:

$$s = \sqrt{\frac{(x_1 - x)^2 + (x_2 - x)^2 + (x_3 - x)^2 + (x_4 - x)^2 + (x_5 - x)^2}{5}}$$

Your program must contain at least the following functions: a function that calculates and returns the mean and a function that calculates the standard deviation.

11. When you borrow money to buy a house, a car, or for some other purposes, then you typically repay it by making periodic payments. Suppose that the loan amount is  $L$ ,  $r$  is the interest rate per year,  $m$  is the number of payments in a year, and the loan is for  $t$  years. Suppose that  $i = (r / m)$  and  $r$  is in decimal. Then the periodic payment is:

$$R = \frac{Li}{1 - (1 + i)^{-mt}},$$

You can also calculate the unpaid loan balance after making certain payments. For example, the unpaid balance after making  $k$  payments is:

$$L' = R \left[ \frac{1 - (1 + i)^{-(mt-k)}}{i} \right],$$

where  $R$  is the periodic payment. (Note that if the payments are monthly, then  $m = 12$ .)

Write a program that prompts the user to input the values of  $L$ ,  $r$ ,  $m$ ,  $t$ , and  $k$ . The program then outputs the appropriate values. Your program must contain at least two functions, with appropriate parameters, to calculate the periodic payments and the unpaid balance after certain payments. Make the program menu driven and use a loop so that the user can repeat the program for different values.

12. During the tax season, every Friday, J&J accounting firm provides assistance to people who prepare their own tax returns. Their charges are as follows.
  - a. If a person has low income ( $\leq 25,000$ ) and the consulting time is less than or equal to 30 minutes, there are no charges; otherwise, the service charges are 40% of the regular hourly rate for the time over 30 minutes.
  - b. For others, if the consulting time is less than or equal to 20 minutes, there are no service charges; otherwise, service charges are 70% of the regular hourly rate for the time over 20 minutes.

(For example, suppose that a person has low income and spent 1 hour and 15 minutes, and the hourly rate is \$70.00. Then the billing amount is  $70.00 \times 0.40 \times (45 / 60) = \$21.00$ .)

Write a program that prompts the user to enter the hourly rate, the total consulting time, and whether the person has low income. The program should output the billing amount. Your program must contain a function that takes as input the hourly rate, the total consulting time, and a value indicating whether the person has low income. The function should return the billing amount. Your program may prompt the user to enter the consulting time in minutes.



# CHAPTER

# 7

## USER-DEFINED FUNCTIONS II

IN THIS CHAPTER, YOU WILL:

- Learn how to construct and use void functions in a program
- Discover the difference between value and reference parameters
- Explore reference parameters and value-returning functions
- Learn about the scope of an identifier
- Examine the differences between local and global identifiers
- Discover static variables
- Learn how to debug programs using drivers and stubs
- Learn function overloading
- Explore functions with default parameters

In Chapter 6, you learned how to use value-returning functions. In this chapter, you will explore user-defined functions in general and, in particular, those C++ functions that do not have a data type, called **void functions**.

## Void Functions

Void functions and value-returning functions have similar structures. Both have a heading and a body. Like value-returning functions, you can place user-defined void functions either before or after the function `main`. However, the program execution always begins with the first statement in the function `main`. If you place user-defined void functions after the function `main`, you should place the function prototype before the function `main`. A void function does not have a data type. Therefore, **functionType**—that is, the return type—in the heading part and the return statement in the body of the void functions are meaningless. However, in a void function, you can use the return statement without any value; it is typically used to exit the function early. Like value-returning functions, void functions may or may not have formal parameters.

Because void functions do not have a data type, they are not used (called) in an expression. A call to a void function is a stand-alone statement. Thus, to call a void function, you use the function name together with the actual parameters (if any) in a stand-alone statement. Before giving examples of void functions, next we give the syntax of a void function.

### FUNCTION DEFINITION

The function definition of void functions with parameters has the following syntax:

```
void functionName(formal parameter list)
{
 statements
}
```

in which **statements** are usually declaration and/or executable statements. The formal parameter list may be empty, in which case, in the function heading, the empty parentheses are still needed.

### FORMAL PARAMETER LIST

The formal parameter list has the following syntax:

```
dataType& variable, dataType& variable, ...
```

You must specify both the data type and the variable name in the formal parameter list. The symbol `&` after **dataType** has a special meaning; it is used only for certain formal parameters and is discussed later in this chapter.

## FUNCTION CALL

The function call has the following syntax:

```
functionName(actual parameter list);
```

## ACTUAL PARAMETER LIST

The actual parameter list has the following syntax:

```
expression or variable, expression or variable, ...
```

in which **expression** can consist of a single constant value. As with value-returning functions, in a function call, the number of actual parameters together with their data types must match the formal parameters in the order given. Actual and formal parameters have a one-to-one correspondence. A function call results in the execution of the body of the called function. (Functions with default parameters are discussed at the end of this chapter.)

Example 7-1 shows a void function with parameters.

### EXAMPLE 7-1

```
void funexp(int a, double b, char c, int x)
{
 .
 .
 .
}
```

The function **funexp** has four parameters.

Parameters provide a communication link between the calling function (such as **main**) and the called function. They enable functions to manipulate different data each time they are called. In general, there are two types of formal parameters: **value parameters** and **reference parameters**.

**Value parameter:** A formal parameter that receives a copy of the content of the corresponding actual parameter.

**Reference parameter:** A formal parameter that receives the location (memory address) of the corresponding actual parameter.

When you attach **&** after the **dataType** in the formal parameter list of a function, the variable following that **dataType** becomes a reference parameter.

Example 7-2 shows a void function with value and reference parameters.

### EXAMPLE 7-2

```
void expfun(int one, int& two, char three, double& four)
{
 .
 .
 .
}
```

The function `expfun` has four parameters: (1) `one`, a value parameter of type `int`; (2) `two`, a reference parameter of type `int`; (3) `three`, a value parameter of type `char`; and (4) `four`, a reference parameter of type `double`.

### EXAMPLE 7-3

We write a program to print a pattern (a triangle of stars) similar to the following:

```

 *
 * *
 * * *
 * * * *
```

The first line has one star with some blanks before the star, the second line has two stars, some blanks before the stars, and a blank between the stars, and so on. Let's write the method `printStars` that has two parameters, a parameter to specify the number of blanks before the stars in a line and a second parameter to specify the number of stars in a line. To be specific, the definition of the method `printStars` is:

```
void printStars(int blanks, int starsInLine)
{
 int count;

 //print the number of blanks before the stars in a line
 for (count = 1; count <= blanks; count++)
 cout << ' ';

 //print the number of stars with a blanks between stars
 for (count = 1; count <= starsInLine; count++)
 cout << " *";

 cout << endl;
} //end printStars
```

The first parameter, `blanks`, determines how many blanks to print preceding the star(s); the second parameter, `starsInLine`, determines how many stars to print in a line. If the value of the parameter `blanks` is 30, for instance, then the first `for` loop in the

method `printStars` executes 30 times and prints 30 blanks. Also, because you want to print a space between the stars, every iteration of the second `for` loop in the method `printStars` prints the string " \*"—a blank followed by a star.

Next, consider the following statements:

```
int numberOfLines = 15;
int numberOfBlanks = 30;

for (counter = 1; counter <= numberOfLines; counter++)
{
 printStars(numberOfBlanks, counter);
 numberOfBlanks--;
}
```

The `for` loop calls the function `printStars`. Every iteration of this `for` loop specifies the number of blanks followed by the number of stars to print in a line, using the variables `numberOfBlanks` and `counter`. Every invocation of the function `printStars` receives one fewer blank and one more star than the previous call. For example, the first iteration of the `for` loop in the method `main` specifies 30 blanks and 1 star (which are passed as the parameters `numberOfBlanks` and `counter` to the function `printStars`). The `for` loop then decrements the number of blanks by 1 by executing the statement, `numberOfBlanks--`. At the end of the `for` loop, the number of stars is incremented by 1 for the next iteration. This is done by executing the update statement `counter++` in the `for` statement, which increments the value of the variable `counter` by 1. In other words, the second call of the function `printStars` receives 29 blanks and 2 stars as parameters. Thus, the previous statements will print a triangle of stars consisting of 15 lines.

**//Program: Print a triangle of stars**

```
#include <iostream>

using namespace std;

void printStars(int blanks, int starsInLine);

int main()
{
 int noOfLines; //variable to store the number of lines
 int counter; //for loop control variable
 int noOfBlanks; //variable to store the number of blanks

 cout << "Enter the number of star lines (1 to 20) "
 << "to be printed: "; //Line 1

 cin >> noOfLines; //Line 2

 while (noOfLines < 0 || noOfLines > 20) //Line 3
 {
 cout << "Number of star lines should be "
 << "between 1 and 20" << endl; //Line 4
 }
}
```

```

 cout << "Enter the number of star lines "
 << "(1 to 20) to be printed: "; //Line 5
 cin >> noOfLines; //Line 6
 }

 cout << endl << endl; //Line 7
 noOfBlanks = 30; //Line 8

 for (counter = 1; counter <= noOfLines; counter++) //Line 9
 {
 printStars(noOfBlanks, counter); //Line 10
 noOfBlanks--; //Line 11
 }

 return 0; //Line 12
}

void printStars(int blanks, int starsInLine)
{
 int count;

 for (count = 1; count <= blanks; count++) //Line 13
 cout << ' '; //Line 14
 for (count = 1; count <= starsInLine; count++) //Line 15
 cout << " * "; //Line 16
 cout << endl;
}

```

**Sample Run:** In this sample run, the user input is shaded.

Enter the number of star lines (1 to 20) to be printed: 15

```

 *
 * *
 * * *
 * * * *
 * * * * *
 * * * * * *
* * * * * * *
 * * * * * * *
 * * * * * * *
 * * * * * * *
 * * * * * * *
 * * * * * * *
 * * * * * * *
 * * * * * * *
 * * * * * * *

```

In the function `main`, the user is first asked to specify how many lines of stars to print (Line 1). (In this program, the user is restricted to 20 lines because a triangular grid of up to 20 lines fits nicely on the screen.) Because the program is restricted to only 20 lines, the `while` loop at Lines 3 through 6 ensures that the program prints only the triangular grid of stars if the number of lines is between 1 and 20.

## Value Parameters

The previous section defined two types of parameters—value parameters and reference parameters. Example 7-3 shows a program that uses a function with parameters. Before considering more examples of void functions with parameters, let us make the following observation about value and reference parameters. When a function is called, the value of the actual parameter is copied into the corresponding formal parameter. If the formal parameter is a value parameter, then after copying the value of the actual parameter, there is no connection between the formal parameter and actual parameter; that is, the formal parameter has its own copy of the data. Therefore, during program execution, the formal parameter manipulates the data stored in its own memory space. The program in Example 7-4 further illustrates how a value parameter works.

### EXAMPLE 7-4

The following program shows how a formal parameter of a primitive data type works.

```
//Example 7-4
//Program illustrating how a value parameter works.

#include <iostream>

using namespace std;

void funcValueParam(int num);

int main()
{
 int number = 6; //Line 1

 cout << "Line 2: Before calling the function "
 << "funcValueParam, number = " << number
 << endl; //Line 2

 funcValueParam(number); //Line 3

 cout << "Line 4: After calling the function "
 << "funcValueParam, number = " << number
 << endl; //Line 4

 return 0;
}

void funcValueParam(int num)
{
 cout << "Line 5: In the function funcValueParam, "
 << "before changing, num = " << num
 << endl; //Line 5

 num = 15; //Line 6
}
```

```

 cout << "Line 7: In the function funcValueParam, "
 << "after changing, num = " << num
 << endl; //Line 7
}

```

### Sample Run:

```

Line 2: Before calling the function funcValueParam, number = 6
Line 5: In the function funcValueParam, before changing, num = 6
Line 7: In the function funcValueParam, after changing, num = 15
Line 4: After calling the function funcValueParam, number = 6

```

This program works as follows. The execution begins at the function `main`. The statement in Line 1 declares and initializes the `int` variable `number`. The statement in Line 2 outputs the value of `number` before calling the function `funcValueParam`; the statement in Line 3 calls the function `funcValueParam`. The value of the variable `number` is then passed to the formal parameter `num`. Control now transfers to the function `funcValueParam`.

The statement in Line 5 outputs the value of `num` before changing its value. The statement in Line 6 changes the value of `num` to 15; the statement in Line 7 outputs the value of `num`. After this statement executes, the function `funcValueParam` exits and control goes back to the function `main`.

The statement in Line 4 outputs the value of `number` after calling the function `funcValueParam`. The sample run shows that the value of `number` (Lines 2 and 4) remains the same even though the value of its corresponding formal parameter `num` was changed within the function `funcValueParam`.

The output shows the sequence in which the statements execute.

---

After copying data, a value parameter has no connection with the actual parameter, so a value parameter cannot pass any result back to the calling function. When the function executes, any changes made to the formal parameters do not in any way affect the actual parameters. The actual parameters have no knowledge of what is happening to the formal parameters. Thus, value parameters cannot pass information outside the function. Value parameters provide only a one-way link between actual parameters and formal parameters. Hence, functions with only value parameters have limitations.

## Reference Variables as Parameters

The program in Example 7-4 illustrates how a value parameter works. On the other hand, suppose that a formal parameter is a reference parameter. Because a reference parameter receives the address (memory location) of the actual parameter, reference parameters can pass one or more values from a function and can change the value of the actual parameter.

Reference parameters are useful in three situations:

- When the value of the actual parameter needs to be changed
- When you want to return more than one value from a function
- When passing the address would save memory space and time relative to copying a large amount of data

The first two situations are illustrated throughout this book. Chapters 9 and 12 discuss the third situation, when arrays and classes are introduced.

Recall that when you attach `&` after the **dataType** in the formal parameter list of a function, the variable following that **dataType** becomes a reference parameter.

#### NOTE

You can declare a reference (formal) parameter as a constant by using the keyword `const`. Chapters 11 and 12 discuss constant reference parameters. Until then, the reference parameters that you use will be nonconstant as defined in this chapter. From the definition of a reference parameter, it follows that a constant value or an expression cannot be passed to a nonconstant reference parameter. If a formal parameter is a nonconstant reference parameter, during a function call, its corresponding actual parameter must be a variable.

### EXAMPLE 7-5

## Calculate Grade

The following program takes a course score (a value between 0 and 100) and determines a student's course grade. This program has three functions: `main`, `getScore`, and `printGrade`, as follows:

1. `main`
  - a. Get the course score.
  - b. Print the course grade.
2. `getScore`
  - a. Prompt the user for the input.
  - b. Get the input.
  - c. Print the course score.
3. `printGrade`
  - a. Calculate the course grade.
  - b. Print the course grade.

The complete program is as follows:

```
//This program reads a course score and prints the
//associated course grade.

#include <iostream>
using namespace std;
```

```

void getScore(int& score);
void printGrade(int score);

int main()
{
 int courseScore;

 cout << "Line 1: Based on the course score, \n"
 << " this program computes the "
 << "course grade." << endl; //Line 1

 getScore(courseScore); //Line 2

 printGrade(courseScore); //Line 3

 return 0;
}

void getScore(int& score)
{
 cout << "Line 4: Enter course score: "; //Line 4
 cin >> score; //Line 5
 cout << endl << "Line 6: Course score is "
 << score << endl; //Line 6
}

void printGrade(int cScore)
{
 cout << "Line 7: Your grade for the course is "; //Line 7

 if (cScore >= 90) //Line 8
 cout << "A." << endl;
 else if (cScore >= 80)
 cout << "B." << endl;
 else if (cScore >= 70)
 cout << "C." << endl;
 else if (cScore >= 60)
 cout << "D." << endl;
 else
 cout << "F." << endl;
}

```

**Sample Run:** In this sample run, the user input is shaded.


Line 1: Based on the course score,  
         this program computes the course grade.  
 Line 4: Enter course score: 85

Line 6: Course score is 85

Line 7: Your grade for the course is B.

This program works as follows. The program starts to execute at Line 1, which prints the first line of the output (see the sample run). The statement in Line 2 calls the function `getScore` with the actual parameter `courseScore` (a variable declared in `main`). Because


the formal parameter `score` of the function `getScore` is a reference parameter, the address (that is, the memory location of the variable `courseScore`) passes to `score`. Thus, both `score` and `courseScore` refer to the same memory location, which is `courseScore` (see Figure 7-1).



**FIGURE 7-1** Variable `courseScore` and the parameter `score`


Any changes made to `score` immediately change the value of `courseScore`.

Control is then transferred to the function `getScore`, and the statement in Line 4 executes, printing the second line of output. This statement prompts the user to enter the course `score`. The statement in Line 5 reads and stores the value entered by the user (85 in the sample run) in `score`, which is actually `courseScore` (because `score` is a reference parameter). Thus, at this point, the value of the variables `score` and `courseScore` is 85 (see Figure 7-2).




**FIGURE 7-2** Variable `courseScore` and the parameter `score` after the statement in Line 5 executes

Next, the statement in Line 6 outputs the value of `score` as shown by the third line of the sample run. After Line 6 executes, control goes back to the function `main` (see Figure 7-3).



**FIGURE 7-3** Variable `courseScore` after the statement in Line 6 is executed and control goes back to `main`

The statement in Line 3 executes next. It is a function call to the function `printGrade` with the actual parameter `courseScore`. Because the formal parameter `cScore` of the function `printScore` is a value parameter, the parameter `cScore` receives the value of the corresponding actual parameter `courseScore`. Thus, the value of `cScore` is 85. After copying the value of `courseScore` into `cScore`, no communication exists between `cScore` and `courseScore` (see Figure 7-4).



**FIGURE 7-4** Variable `courseScore` and the parameter `cScore`

The program then executes the statement in Line 7, which outputs the fourth line. The `if...else` statement in Line 8 determines and outputs the grade for the course. Because the output statement in Line 7 does not contain the newline character or the manipulator `endl`, the output of the `if...else` statement is part of the fourth line of the output. After the `if...else` statement executes, control goes back to the function `main`. Because the next statement to execute in the function `main` is the last statement of the function `main`, the program terminates.

In this program, the function `main` first calls the function `getScore` to obtain the course score from the user. The function `main` then calls the function `printGrade` to calculate and print the grade based on this course score. The course score is retrieved by the function `getScore`; later, this course score is used by the function `printGrade`. Because the value retrieved by the `getScore` function is used later in the program, the function `getScore` must pass this value outside. Thus, the formal parameter that holds this value must be a reference parameter.

## Value and Reference Parameters and Memory Allocation

When a function is called, memory for its formal parameters and variables declared in the body of the function (called **local variables**) is allocated in the function data area. Recall that in the case of a value parameter, the value of the actual parameter is copied into the memory cell of its corresponding formal parameter. In the case of a reference parameter, the address of the actual parameter passes to the formal parameter. That is, the content of the formal parameter is an address. During data manipulation, the content of the formal parameter directs the computer to manipulate the data of the memory cell indicated by its content. Thus, in the case of a reference parameter, both the actual and formal parameters refer to the same memory location. Consequently, during program execution, changes made by the formal parameter permanently change the value of the actual parameter.

**NOTE**

Stream variables (for example, `ifstream` and `ofstream`) should be passed by reference to a function. After opening the input/output file or after reading and/or outputting data, the state of the input and/or output stream can then be passed outside the function.

Because parameter passing is fundamental to any programming language, Examples 7-6 and 7-7 further illustrate this concept. Each covers a different scenario.

**EXAMPLE 7-6**

The following program shows how reference and value parameters work.

**//Example 7-6: Reference and value parameters**

```
#include <iostream>

using namespace std;

void funOne(int a, int& b, char v);
void funTwo(int& x, int y, char& w);

int main()
{
 int num1, num2;
 char ch;

 num1 = 10; //Line 1
 num2 = 15; //Line 2
 ch = 'A'; //Line 3

 cout << "Line 4: Inside main: num1 = " << num1
 << ", num2 = " << num2 << ", and ch = "
 << ch << endl; //Line 4

 funOne(num1, num2, ch); //Line 5

 cout << "Line 6: After funOne: num1 = " << num1
 << ", num2 = " << num2 << ", and ch = "
 << ch << endl; //Line 6

 funTwo(num2, 25, ch); //Line 7

 cout << "Line 8: After funTwo: num1 = " << num1
 << ", num2 = " << num2 << ", and ch = "
 << ch << endl; //Line 8

 return 0;
}
```

```

void funOne(int a, int& b, char v)
{
 int one;

 one = a; //Line 9
 a++; //Line 10
 b = b * 2; //Line 11
 v = 'B'; //Line 12

 cout << "Line 13: Inside funOne: a = " << a
 << ", b = " << b << ", v = " << v
 << ", and one = " << one << endl; //Line 13
}

void funTwo(int& x, int y, char& w)
{
 x++; //Line 14
 y = y * 2; //Line 15
 w = 'G'; //Line 16

 cout << "Line 17: Inside funTwo: x = " << x
 << ", y = " << y << ", and w = " << w
 << endl; //Line 17
}

```

### Sample Run:


```

Line 4: Inside main: num1 = 10, num2 = 15, and ch = A
Line 13: Inside funOne: a = 11, b = 30, v = B, and one = 10
Line 6: After funOne: num1 = 10, num2 = 30, and ch = A
Line 17: Inside funTwo: x = 31, y = 50, and w = G
Line 8: After funTwo: num1 = 10, num2 = 31, and ch = G

```

Let us walk through this program. The values of the variables are shown before and/or after each statement executes.

Just before the statement in Line 1 executes, memory is allocated only for the variables of the function `main`; this memory is not initialized. After the statement in Line 3 executes, the variables are as shown in Figure 7-5.




**FIGURE 7-5** Values of the variables after the statement in Line 3 executes

The statement in Line 4 produces the following output:


**Line 4: Inside main: num1 = 10, num2 = 15, and ch = A**

The statement in Line 5 is a function call to the function `funOne`. Now function `funOne` has three parameters and one local variable. Memory for the parameters and the local variable of function `funOne` is allocated. Because the formal parameter `b` is a reference parameter, it receives the address (memory location) of the corresponding actual parameter, which is `num2`. The other two formal parameters are value parameters, so they copy the values of their corresponding actual parameters. Just before the statement in Line 9 executes, the variables are as shown in Figure 7-6.




**FIGURE 7-6** Values of the variables just before the statement in Line 9 executes

After the statement in Line 9, `one = a;`, executes, the variables are as shown in Figure 7-7.




**FIGURE 7-7** Values of the variables after the statement in Line 9 executes

After the statement in Line 10, `a++;`, executes, the variables are as shown in Figure 7-8.




**FIGURE 7-8** Values of the variables after the statement in Line 10 executes

After the statement in Line 11, `b = b * 2;`, executes, the variables are as shown in Figure 7-9. (Note that the variable `b` changed the value of `num2`.)



**FIGURE 7-9** Values of the variables after the statement in Line 11 executes

After the statement in Line 12, `v = 'B';`, executes, the variables are as shown in Figure 7-10.



**FIGURE 7-10** Values of the variables after the statement in Line 12 executes

The statement in Line 13 produces the following output:

**Line 13: Inside funOne: a = 11, b = 30, v = B, and one = 10**

After the statement in Line 13 executes, control goes back to Line 6 and the memory allocated for the variables of function `funOne` is deallocated. Figure 7-11 shows the values of the variables of the function `main`.




FIGURE 7-11 Values of the variables when control goes back to Line 6

Line 6 produces the following output:

**Line 6: After funOne: num1 = 10, num2 = 30, and ch = A**

The statement in Line 7 is a function call to the function `funTwo`. Now `funTwo` has three parameters: `x`, `y`, and `w`. Also, `x` and `w` are reference parameters, and `y` is a value parameter. Thus, `x` receives the address of its corresponding actual parameter, which is `num2`, and `w` receives the address of its corresponding actual parameter, which is `ch`. The variable `y` copies the value 25 into its memory cell. Figure 7-12 shows the values before the statement in Line 14 executes.




FIGURE 7-12 Values of the variables before the statement in Line 14 executes

After the statement in Line 14, `x++;`, executes, the variables are as shown in Figure 7-13. (Note that the variable `x` changed the value of `num2`.)






FIGURE 7-13 Values of the variables after the statement in Line 14 executes

After the statement in Line 15, `y = y * 2;`, executes, the variables are as shown in Figure 7-14.



**FIGURE 7-14** Values of the variables after the statement in Line 15 executes

After the statement in Line 16, `w = 'G';`, executes, the variables are as shown in Figure 7-15. (Note that the variable `w` changed the value of `ch`.)




**FIGURE 7-15** Values of the variables after the statement in Line 16 executes

Line 17 produces the following output:

**Line 17: Inside funTwo: x = 31, y = 50, and w = G**

After the statement in Line 17 executes, control goes to Line 8. The memory allocated for the variables of function **funTwo** is deallocated. The values of the variables of the function **main** are as shown in Figure 7-16.



**FIGURE 7-16** Values of the variables when control goes to Line 8

The statement in Line 8 produces the following output:

Line 8: After funTwo: num1 = 10, num2 = 31, and ch = G

After the statement in Line 8 executes, the program terminates.

### EXAMPLE 7-7

This example also shows how reference parameters manipulate actual parameters.

*//Example 7-7: Reference and value parameters.*

*//Program: Makes you think.*

```
#include <iostream>

using namespace std;

void addFirst(int& first, int& second);
void doubleFirst(int one, int two);
void squareFirst(int& ref, int val);

int main()
{
 int num = 5;

 cout << "Line 1: Inside main: num = " << num
 << endl; //Line 1

 addFirst(num, num); //Line 2
 cout << "Line 3: Inside main after addFirst:"
 << " num = " << num << endl; //Line 3

 doubleFirst(num, num); //Line 4
 cout << "Line 5: Inside main after "
 << "doubleFirst: num = " << num << endl; //Line 5

 squareFirst(num, num); //Line 6
 cout << "Line 7: Inside main after "
 << "squareFirst: num = " << num << endl; //Line 7

 return 0;
}

void addFirst(int& first, int& second)
{
 cout << "Line 8: Inside addFirst: first = "
 << first << ", second = " << second << endl; //Line 8

 first = first + 2; //Line 9

 cout << "Line 10: Inside addFirst: first = "
 << first << ", second = " << second << endl; //Line 10
```

```

 second = second * 2; //Line 11

 cout << "Line 12: Inside addFirst: first = "
 << first << ", second = " << second << endl; //Line 12
 }

 void doubleFirst(int one, int two)
 {
 cout << "Line 13: Inside doubleFirst: one = "
 << one << ", two = " << two << endl; //Line 13

 one = one * 2; //Line 14

 cout << "Line 15: Inside doubleFirst: one = "
 << one << ", two = " << two << endl; //Line 15

 two = two + 2; //Line 16

 cout << "Line 17: Inside doubleFirst: one = "
 << one << ", two = " << two << endl; //Line 17
 }

 void squareFirst(int& ref, int val)
 {
 cout << "Line 18: Inside squareFirst: ref = "
 << ref << ", val = " << val << endl; //Line 18

 ref = ref * ref; //Line 19

 cout << "Line 20: Inside squareFirst: ref = "
 << ref << ", val = " << val << endl; //Line 20

 val = val + 2; //Line 21

 cout << "Line 22: Inside squareFirst: ref = "
 << ref << ", val = " << val << endl; //Line 22
 }

```

### Sample Run:

```


Line 1: Inside main: num = 5
Line 8: Inside addFirst: first = 5, second = 5
Line 10: Inside addFirst: first = 7, second = 7
Line 12: Inside addFirst: first = 14, second = 14
Line 3: Inside main after addFirst: num = 14
Line 13: Inside doubleFirst: one = 14, two = 14
Line 15: Inside doubleFirst: one = 28, two = 14
Line 17: Inside doubleFirst: one = 28, two = 16
Line 5: Inside main after doubleFirst: num = 14
Line 18: Inside squareFirst: ref = 14, val = 14
Line 20: Inside squareFirst: ref = 196, val = 14
Line 22: Inside squareFirst: ref = 196, val = 16
Line 7: Inside main after squareFirst: num = 196

```

Both parameters of the function `addFirst` are reference parameters, and both parameters of the function `doubleFirst` are value parameters. The statement:

```
addFirst(num, num);
```

in the function `main` (Line 2) passes the reference of `num` to both formal parameters `first` and `second` of the function `addFirst`, because the corresponding actual parameters for both formal parameters are the same. That is, the variables `first` and `second` refer to the same memory location, which is `num`. Figure 7-17 illustrates this situation.




**FIGURE 7-17** Parameters of the function `addFirst`

Any changes that `first` makes to its value immediately change the value of `second` and `num`. Similarly, any changes that `second` makes to its value immediately change `first` and `num`, because all three variables refer to the same memory location. (Note that `num` was initialized to 5.)

The formal parameters of the function `doubleFirst` are value parameters. So the statement:

```
doubleFirst(num, num);
```

in the function `main` (Line 4) copies the value of `num` into `one` and `two` because the corresponding actual parameters for both formal parameters are the same. Figure 7-18 illustrates this scenario.




**FIGURE 7-18** Parameters of the function `doubleFirst`

Because both `one` and `two` are value parameters, any changes that `one` makes to its value do not affect the values of `two` and `num`. Similarly, any changes that `two` makes to its value do not affect `one` and `num`. (Note that the value of `num` before the function `doubleFirst` executes is 14.)

The formal parameter `ref` of the function `squareFirst` is a reference parameter, and the formal parameter `val` is a value parameter. The variable `ref` receives the address of its

corresponding actual parameter, which is `num`, and the variable `val` copies the value of its corresponding actual parameter, which is also `num`. Thus, both `num` and `ref` refer to the same memory location, which is `num`. Figure 7-19 illustrates this situation.



**FIGURE 7-19** Parameters of the function `squareFirst`

Any changes that `ref` makes immediately change `num`. Any changes made by `val` do not affect `num`. (Note that the value of `num` before the function `squareFirst` executes is 14.)

We recommend that you walk through the program in Example 7-8. The output shows the order in which the statements execute.

## Reference Parameters and Value-Returning Functions

In Chapter 6, in the discussion of value-returning functions, you learned how to use value parameters only. You can also use reference parameters in a value-returning function, although this approach is not recommended. By definition, a value-returning function returns a single value; this value is returned via the `return` statement. If a function needs to return more than one value, you should change it to a void function and use the appropriate reference parameters to return the values.

## Scope of an Identifier

The previous sections and Chapter 6 presented several examples of programs with user-defined functions. Identifiers are declared in a function heading, within a block, or outside a block. A question naturally arises: Are you allowed to access any identifier anywhere in the program? The answer is no. You must follow certain rules to access an identifier. The **scope** of an identifier refers to where in the program an identifier is accessible (visible). Recall that an identifier is the name of something in C++, such as a variable or function name.

This section examines the scope of an identifier. First, we define the following two terms:

**Local identifier:** Identifiers declared within a function (or block).

Local identifiers are not accessible outside of the function (block).

**Global identifier:** Identifiers declared outside of every function definition.

Also, C++ does not allow the nesting of functions. That is, you cannot include the definition of one function in the body of another function.

In general, the following rules apply when an identifier is accessed:

1. Global identifiers (such as variables) are accessible by a function or a block if:
  - a. The identifier is declared before the function definition (block),
  - b. The function name is different from the identifier,
  - c. All parameters of the function have names different than the name of the identifier, and
  - d. All local identifiers (such as local variables) have names different than the name of the identifier.
2. **(Nested Block)** An identifier declared within a block is accessible:
  - a. Only within the block from the point at which it is declared until the end of the block, and
  - b. By those blocks that are nested within that block if the nested block does not have an identifier with the same name as that of the outside block (the block that encloses the nested block).
3. The scope of a function name is similar to the scope of an identifier declared outside any block. That is, the scope of a function name is the same as the scope of a global variable.

Before considering an example to explain these scope rules, first note the scope of the identifier declared in the `for` statement. C++ allows the programmer to declare a variable in the initialization statement of the `for` statement. For example, the following `for` statement:

```
for (int count = 1; count < 10; count++)
 cout << count << endl;
```

declares the variable `count` and initializes it to 1. The scope of the variable `count` is limited to only the body of the `for` loop.

#### NOTE

This scope rule for the variable declared in a `for` statement may not apply to Standard C++. In Standard C++, the scope of the variable declared in the `initialize` statement may extend from the point at which it is declared until the end of the block that immediately surrounds the `for` statement. (To be absolutely sure, check your compiler's documentation.)

The following C++ program helps illustrate the scope rules:

```
#include <iostream>

using namespace std;

const double RATE = 10.50;
int z;
double t;
```

```

void one(int x, char y);
void two(int a, int b, char x);
void three(int one, double y, int z);

int main()
{
 int num, first;
 double x, y, z;
 char name, last;
 .
 .
 .
 return 0;
}

void one(int x, char y)
{
 .
 .
 .
}

int w;

void two(int a, int b, char x)
{
 int count;
 .
 .
 .
}

void three(int one, double y, int z)
{
 char ch;
 int a;
 .
 .
 .
 //Block four
 {
 int x;
 char a;
 .
 .
 } //end Block four
 .
 .
 .
}

```

Table 7-1 summarizes the scope (visibility) of the identifiers.

**TABLE 7-1** Scope (Visibility) of the Identifiers

| Identifier                                     | Visibility in one | Visibility in two | Visibility in three | Visibility in Block four | Visibility in main |
|------------------------------------------------|-------------------|-------------------|---------------------|--------------------------|--------------------|
| RATE (before <b>main</b> )                     | Y                 | Y                 | Y                   | Y                        | Y                  |
| z (before <b>main</b> )                        | Y                 | Y                 | N                   | N                        | N                  |
| t (before <b>main</b> )                        | Y                 | Y                 | Y                   | Y                        | Y                  |
| <b>main</b>                                    | Y                 | Y                 | Y                   | Y                        | Y                  |
| local variables of <b>main</b>                 | N                 | N                 | N                   | N                        | Y                  |
| <b>one</b> (function name)                     | Y                 | Y                 | N                   | N                        | Y                  |
| x ( <b>one</b> 's formal parameter)            | Y                 | N                 | N                   | N                        | N                  |
| y ( <b>one</b> 's formal parameter)            | Y                 | N                 | N                   | N                        | N                  |
| w (before function <b>two</b> )                | N                 | Y                 | Y                   | Y                        | N                  |
| <b>two</b> (function name)                     | Y                 | Y                 | Y                   | Y                        | Y                  |
| a ( <b>two</b> 's formal parameter)            | N                 | Y                 | N                   | N                        | N                  |
| b ( <b>two</b> 's formal parameter)            | N                 | Y                 | N                   | N                        | N                  |
| x ( <b>two</b> 's formal parameter)            | N                 | Y                 | N                   | N                        | N                  |
| local variables of <b>two</b>                  | N                 | Y                 | N                   | N                        | N                  |
| <b>three</b> (function name)                   | Y                 | Y                 | Y                   | Y                        | Y                  |
| <b>one</b> ( <b>three</b> 's formal parameter) | N                 | N                 | Y                   | Y                        | N                  |
| y ( <b>three</b> 's formal parameter)          | N                 | N                 | Y                   | Y                        | N                  |
| z ( <b>three</b> 's formal parameter)          | N                 | N                 | Y                   | Y                        | N                  |
| ch ( <b>three</b> 's local variable)           | N                 | N                 | Y                   | Y                        | N                  |
| a ( <b>three</b> 's local variable)            | N                 | N                 | Y                   | N                        | N                  |
| x (Block <b>four</b> 's local variable)        | N                 | N                 | N                   | Y                        | N                  |
| a (Block <b>four</b> 's local variable)        | N                 | N                 | N                   | Y                        | N                  |

Note that function **three** cannot call function **one**, because function **three** has a formal parameter named **one**. Similarly, the block marked **four** in function **three** cannot use the **int** variable **a**, which is declared in function **three**, because block **four** has an identifier named **a**.

Before closing this section, let us note the following about global variables:

1. Chapter 2 stated that C++ does not automatically initialize variables. However, some compilers initialize global variables to their default values. For example, if a global variable is of type **int**, **char**, or **double**, it is initialized to zero.
2. In C++, **::** is called the **scope resolution operator**. By using the scope resolution operator, a global variable declared before the definition of a function (block) can be accessed by the function (or block) even if the function (or block) has an identifier with the same name as the variable. In the preceding program, by using the scope resolution operator, the function **main** can refer to the global variable **z** as **::z**. Similarly, suppose that a global variable **t** is declared before the definition of the function—say, **funExample**. Then, **funExample** can access the variable **t** using the scope resolution operator even if **funExample** has an identifier **t**. Using the scope resolution operator, **funExample** refers to the variable **t** as **::t**. Also, in the preceding program, using the scope resolution operator, function **three** can call function **one**.
3. C++ provides a way to access a global variable declared after the definition of a function. In this case, the function must not contain any identifier with the same name as the global variable. In the preceding program, the global variable **w** is declared after the definition of function **one**. The function **one** does not contain any identifier named **w**; therefore, **w** can be accessed by function **one** only if you declare **w** as an **external variable** inside **one**. To declare **w** as an external variable inside function **one**, the function **one** must contain the following statement:

```
extern int w;
```

In C++, **extern** is a reserved word. The word **extern** in the above statement announces that **w** is a global variable declared elsewhere. Thus, when function **one** is called, no memory for **w**, as declared inside **one**, is allocated. In C++, external declaration also has another use, but it is not discussed in this book.

## Global Variables, Named Constants, and Side Effects

A C++ program can contain global variables. Using global variables, however, has side effects. If more than one function uses the same global variable and something goes wrong, it is difficult to discover what went wrong and where. Problems caused by

global variables in one area of a program might be misunderstood as problems caused in another area.

For example, consider the following program:

```
//Global variable

#include <iostream>

using namespace std;

int t;

void funOne(int& a);

int main()
{
 t = 15; //Line 1
 cout << "Line 2: In main: t = " << t << endl; //Line 2
 funOne(t); //Line 3
 cout << "Line 4: In main after funOne: "
 << " t = " << t << endl; //Line 4
 return 0; //Line 5
}

void funOne(int& a)
{
 cout << "Line 6: In funOne: a = " << a
 << " and t = " << t << endl; //Line 6
 a = a + 12; //Line 7
 cout << "Line 8: In funOne: a = " << a
 << " and t = " << t << endl; //Line 8
 t = t + 13; //Line 9
 cout << "Line 10: In funOne: a = " << a
 << " and t = " << t << endl; //Line 10
}
```

This program has a variable `t` that is declared before the definition of any function. Because none of the functions has an identifier `t`, the variable `t` is accessible anywhere in the program. Also, the program consists of a void function with a reference parameter.

In Line 3, the function `main` calls the function `funOne`, and the actual parameter passed to `funOne` is `t`. So, `a`, the formal parameter of `funOne`, receives the address of `t`. Any changes that `a` makes to its value immediately change `t`. Because `t` can be directly accessed anywhere in the program, in Line 9, the function `funOne` changes the value of `t`

by using `t` itself. Thus, you can manipulate the value of `t` by using either a reference parameter or `t` itself.

In the previous program, if the last value of `t` is incorrect, it would be difficult to determine what went wrong and in which part of the program. We strongly recommend that *you do not use global variables*; instead, use the appropriate parameters.

In the programs given in this book, we typically placed named constants before the function `main`, outside of every function definition. That is, the named constants we used are *global named constants*. Unlike global variables, global named constants have no side effects because their values cannot be changed during program execution. Moreover, placing a named constant in the beginning of the program can increase readability, even if it is used only in one function. If you need to later modify the program and change the value of a named constant, it will be easier to find if it is placed in the beginning of the program.

### EXAMPLE 7-8 (MENU-DRIVEN PROGRAM)

The following is an example of a menu-driven program. When the program executes, it gives the user a list of choices to choose from. This program further illustrates how value and reference parameters work. It converts length from feet and inches to meters and centimeters and vice versa. The program contains three functions: `showChoices`, `feetAndInchesToMetersAndCent`, and `metersAndCentTofeetAndInches`. The function `showChoices` informs the user how to use the program. The user has the choice to run the program as long as the user wishes.

```
//Menu-driven program.

#include <iostream>

using namespace std;

const double CONVERSION = 2.54;
const int INCHES_IN_FOOT = 12;
const int CENTIMETERS_IN_METER = 100;

void showChoices();

void feetAndInchesToMetersAndCent(int f, int in,
 int& mt, int& ct);
void metersAndCentTofeetAndInches(int mt, int ct,
 int& f, int& in);

int main()
{
 int feet, inches;
 int meters, centimeters;
 int choice;
```

```

do
{
 showChoices();
 cin >> choice;
 cout << endl;

 switch (choice)
 {
 case 1:
 cout << "Enter feet and inches: ";
 cin >> feet >> inches;
 cout << endl;
 feetAndInchesToMetersAndCent(feet, inches,
 meters, centimeters);

 cout << feet << " feet(foot), "
 << inches << " inch(es) = "
 << meters << " meter(s), "
 << centimeters << " centimeter(s)." << endl;
 break;

 case 2:
 cout << "Enter meters and centimeters: ";
 cin >> meters >> centimeters;
 cout << endl;
 metersAndCentToFeetAndInches(meters, centimeters,
 feet, inches);

 cout << meters << " meter(s), "
 << centimeters << " centimeter(s) = "
 << feet << " feet(foot), "
 << inches << " inch(es)."
 << endl;
 break;

 case 99:
 break;

 default:
 cout << "Invalid input." << endl;
 }
}
while (choice != 99);

return 0;
}

void showChoices()
{
 cout << "Enter--" << endl;
 cout << "1: To convert from feet and inches to meters "
 << "and centimeters." << endl;
 cout << "2: To convert from meters and centimeters to feet "
 << "and inches." << endl;
 cout << "99: To quit the program." << endl;
}

```

```

void feetAndInchesToMetersAndCent(int f, int in,
 int& mt, int& ct)
{
 int inches;

 inches = f * INCHES_IN_FOOT + in;
 ct = static_cast<int>(inches * CONVERSION);
 mt = ct / CENTIMETERS_IN_METER;
 ct = ct % CENTIMETERS_IN_METER;
}

void metersAndCentTofeetAndInches(int mt, int ct,
 int& f, int& in)
{
 int centimeters;

 centimeters = mt * CENTIMETERS_IN_METER + ct;
 in = static_cast<int>(centimeters / CONVERSION);
 f = in / INCHES_IN_FOOT;
 in = in % INCHES_IN_FOOT;
}

```

**Sample Run:** In this sample run, the user input is shaded.

Enter--

1: To convert from feet and inches to meters and centimeters.

2: To convert from meters and centimeters to feet and inches.

99: To quit the program.

2

Enter meters and centimeters: 4 25

4 meter(s), 25 centimeter(s) = 13 feet(foot), 11 inch(es).

Enter--

1: To convert from feet and inches to meters and centimeters.

2: To convert from meters and centimeters to feet and inches.

99: To quit the program.

1

Enter feet and inches: 15 8

15 feet(foot), 8 inch(es) = 4 meter(s), 77 centimeter(s).

Enter--

1: To convert from feet and inches to meters and centimeters.

2: To convert from meters and centimeters to feet and inches.

99: To quit the program.

99

The **do...while loop** in the function **main** continues to execute as long as the user has not entered 99, which allows the user to run the program as long as the user wishes. The preceding output is self explanatory.

## Static and Automatic Variables

The variables discussed so far have followed two simple rules:

1. Memory for global variables remains allocated as long as the program executes.
2. Memory for a variable declared within a block is allocated at block entry and deallocated at block exit. For example, memory for the formal parameters and local variables of a function is allocated when the function is called and deallocated when the function exits.

A variable for which memory is allocated at block entry and deallocated at block exit is called an **automatic variable**. A variable for which memory remains allocated as long as the program executes is called a **static variable**. Global variables are static variables, and by default, variables declared within a block are automatic variables. You can declare a static variable within a block by using the reserved word **static**. The syntax for declaring a static variable is:

```
static dataType identifier;
```

The statement:

```
static int x;
```

declares **x** to be a static variable of type **int**.

Static variables declared within a block are local to the block, and their scope is the same as that of any other local identifier of that block.

Most compilers initialize **static** variables to their default values. For example, **static int** variables are initialized to 0. However, it is a good practice to initialize **static** variables yourself, especially if the initial value is not the default value. In this case, **static** variables are initialized when they are declared. The statement:

```
static int x = 0;
```

declares **x** to be a static variable of type **int** and initializes **x** to 0.

### EXAMPLE 7-9

The following program shows how static and automatic variables behave.

```
//Program: Static and automatic variables

#include <iostream>

using namespace std;

void test();

int main()
{
 int count;
```

```

 for (count = 1; count <= 5; count++)
 test();

 return 0;
}

void test()
{
 static int x = 0;
 int y = 10;

 x = x + 2;
 y = y + 1;

 cout << "Inside test x = " << x << " and y = "
 << y << endl;
}

```

### Sample Run:

```

Inside test x = 2 and y = 11
Inside test x = 4 and y = 11
Inside test x = 6 and y = 11
Inside test x = 8 and y = 11
Inside test x = 10 and y = 11

```

In the function `test`, `x` is a `static` variable initialized to 0, and `y` is an automatic variable initialized to 10. The function `main` calls the function `test` five times. Memory for the variable `y` is allocated every time the function `test` is called and deallocated when the function exits. Thus, every time the function `test` is called, it prints the same value for `y`. However, because `x` is a static variable, memory for `x` remains allocated as long as the program executes. The variable `x` is initialized once to 0. The subsequent calls of the function `test` use the current value of `x`.

---

Because memory for static variables remains allocated between function calls, static variables allow you to use the value of a variable from one function call to another function call. Even though you can use global variables if you want to use certain values from one function call to another, the local scope of a static variable prevents other functions from manipulating its value.

## Debugging: Using Drivers and Stubs

In this and the previous chapters, you learned how to write functions to divide a problem into subproblems, solve each subproblem, and then combine the functions to form the complete program to get a solution of the problem. A program may contain a number of functions. In a complex program, usually, when a function is written, it is tested and debugged alone. You can write a separate program to test the function. The program that tests a function is called a **driver** program. For example, the program in Example 7-8 contains functions to convert the length from feet and inches to meters and centimeters

and vice versa. Before writing the complete program, you could write separate driver programs to make sure that each function is working properly.

Sometimes, the results calculated by one function are needed in another function. In that case, the function that depends on another function cannot be tested alone. For example, consider the following program that determines the time to fill a swimming pool.

```
#include <iostream>
#include <iomanip>

using namespace std;

const double GALLONS_IN_A_CUBIC_FOOT = 7.48;

double poolCapacity(double len, double wid, double dep);
void poolFillTime(double len, double wid, double dep,
 double fRate, int& fTime);
void print(int fTime);

int main()
{
 double length, width, depth;
 double fillRate;
 int fillTime;

 cout << fixed << showpoint << setprecision(2);

 cout << "Enter the length, width, and the depth of the "
 << "pool (in feet): ";
 cin >> length >> width >> depth;
 cout << endl;

 cout << "Enter the rate of the water (in gallons per minute): ";
 cin >> fillRate;
 cout << endl;

 poolFillTime(length, width, depth, fillRate, fillTime);
 print(fillTime);

 return 0;
}

double poolCapacity(double len, double wid, double dep)
{
 double volume;
 double poolWaterCapacity;

 volume = len * wid * dep;
 poolWaterCapacity = volume * GALLONS_IN_A_CUBIC_FOOT;

 return poolWaterCapacity;
}
```

```

void poolFillTime(double len, double wid, double dep,
 double fRate, int& fTime)
{
 double poolWaterCapacity;

 poolWaterCapacity = poolCapacity(len, wid, dep);
 fTime = static_cast<int> (poolWaterCapacity / fRate + 0.5);
}

void print(int fTime)
{
 cout << "The time to fill the pool is approximately: "
 << ftime / 60 << " hour(s) and " << ftime % 60
 << " minute(s)." << endl;
}

```

**Sample Run:** In this sample run, the user input is shaded.

Enter the length, width, and the depth of the pool (in feet): 30 15 10

Enter the rate of the water, (in gallons per minute): 100

The time to fill the pool is approximately: 5 hour(s) and 37 minute(s).

As you can see, the program contains the function `poolCapacity` to find the amount of water needed to fill the pool, the function `poolFillTime` to find the time to fill the pool, and some other functions. Now, to calculate the time to fill the pool, you must know the amount of the water needed and the rate at which the water is released in the pool. Because the results of the function `poolCapacity` are needed in the function `poolFillTime`, the function `poolFillTime` cannot be tested alone. Does this mean that we must write the functions in a specific order? Not necessarily, especially when different people are working on different parts of the program. In situations such as these, we use function stubs. A function **stub** is a function that is not fully coded. For a void function, a function stub might consist of only a function header and a set of empty braces, {}, and for a value-returning function it might contain only a return statement with a plausible return value. For example, the function stub for the function `poolCapacity` can be:

```

double poolCapacity(double len, double wid, double dep)
{
 return 1000.00;
}

```

This allows the function `poolCapacity` to be called while the program is being coded. Ultimately, the stub for function `poolCapacity` is replaced with a function that properly calculates the amount of water needed to fill the pool based on the values of the parameters. In the meantime, the function stub allows work to continue on other parts of the program that call the function `poolCapacity`.

Before we look at some programming examples, another concept about functions is worth mentioning: function overloading.

## Function Overloading: An Introduction

In a C++ program, several functions can have the same name. This is called **function overloading**, or **overloading a function name**. Before we state the rules to overloading a function, let us define the following:

Two functions are said to have **different formal parameter lists** if both functions have:

- A different number of formal parameters or
- If the number of formal parameters is the same, then the data type of the formal parameters, in the order you list them, must differ in at least one position.

For example, consider the following function headings:

```
void functionOne(int x)
void functionTwo(int x, double y)
void functionThree(double y, int x)
int functionFour(char ch, int x, double y)
int functionFive(char ch, int x, string name)
```

These functions all have different formal parameter lists.

Now consider the following function headings:

```
void functionSix(int x, double y, char ch)
void functionSeven(int one, double u, char firstCh)
```

The functions `functionSix` and `functionSeven` both have three formal parameters, and the data type of the corresponding parameters is the same. Therefore, these functions have the same formal parameter list.

To overload a function name, any two definitions of the function must have different formal parameter lists.

**Function overloading:** Creating several functions with the same name.

The **signature** of a function consists of the function name and its formal parameter list. Two functions have different signatures if they have either different names or different formal parameter lists. (Note that the signature of a function does not include the return type of the function.)

If a function's name is overloaded, then all of the functions in the set have the same name. Therefore, all of the functions in the set have different signatures if they have different formal parameter lists. Thus, the following function headings correctly overload the function `functionXYZ`:

```
void functionXYZ()
void functionXYZ(int x, double y)
void functionXYZ(double one, int y)
void functionXYZ(int x, double y, char ch)
```

Consider the following function headings to overload the function `functionABC`:

```
void functionABC(int x, double y)
int functionABC(int x, double y)
```

Both of these function headings have the same name and same formal parameter list. Therefore, these function headings to overload the function `functionABC` are incorrect. In this case, the compiler will generate a syntax error. (Notice that the return types of these function headings are different.)

If a function is overloaded, then in a call to that function, the signature—that is, the formal parameter list of the function—determines which function to execute.

**NOTE**

Some authors define the signature of a function as the formal parameter list, and some consider the entire heading of the function as its signature. However, in this book, the signature of a function consists of the function's heading and its formal parameter list. If the function's names are different, then, of course, the compiler would have no problem in identifying which function is called, and it will correctly translate the code. However, if a function's name is overloaded, then, as noted, the function's formal parameter list determines which function's body executes.

Suppose you need to write a function that determines the larger of two items. Both items can be integers, floating-point numbers, characters, or strings. You could write several functions as follows:

```
int largerInt(int x, int y);
char largerChar(char first, char second);
double largerDouble(double u, double v);
string largerString(string first, string second);
```

The function `largerInt` determines the larger of two integers; the function `largerChar` determines the larger of two characters, and so on. All of these functions perform similar operations. Instead of giving different names to these functions, you can use the same name—say, `larger`—for each function; that is, you can overload the function `larger`. Thus, you can write the previous function prototypes simply as:

```
int larger(int x, int y);
char larger(char first, char second);
double larger(double u, double v);
string larger(string first, string second);
```

If the call is `larger(5, 3)`, for example, the first function is executed. If the call is `larger('A', '9')`, the second function is executed, and so on.

Function overloading is used when you have the same action for different sets of data. Of course, for function overloading to work, you must give the definition of each function.

## Functions with Default Parameters

**NOTE**

This section is not needed until Chapter 12.

This section discusses functions with default parameters. Recall that when a function is called, the number of actual and formal parameters must be the same. C++ relaxes this condition for functions with default parameters. You specify the value of a default parameter when the function name appears for the first time, such as in the prototype. In general, the following rules apply for functions with default parameters:

- If you do not specify the value of a default parameter, the default value is used for that parameter.
- All of the default parameters must be the far-right parameters of the function.
- Suppose a function has more than one default parameter. In a function call, if a value to a default parameter is not specified, then you must omit all of the arguments to its right.
- Default values can be constants, global variables, or function calls.
- The caller has the option of specifying a value other than the default for any default parameter.
- You cannot assign a constant value as a default value to a reference parameter.

Consider the following function prototype:

```
void funcExp(int x, int y, double t, char z = 'A', int u = 67,
 char v = 'G', double w = 78.34);
```

The function `funcExp` has seven parameters. The parameters `z`, `u`, `v`, and `w` are default parameters. If no values are specified for `z`, `u`, `v`, and `w` in a call to the function `funcExp`, their default values are used.

Suppose you have the following statements:

```
int a, b;
char ch;
double d;
```

The following function calls are legal:

1. `funcExp(a, b, d);`
2. `funcExp(a, 15, 34.6, 'B', 87, ch);`
3. `funcExp(b, a, 14.56, 'D');`

In statement 1, the default values of `z`, `u`, `v`, and `w` are used. In statement 2, the default value of `z` is replaced by `'B'`, the default value of `u` is replaced by `87`, the default value of `v` is replaced by the value of `ch`, and the default value of `w` is used. In statement 3, the default value of `z` is replaced by `'D'`, and the default values of `u`, `v`, and `w` are used.

The following function calls are illegal:

1. `funcExp(a, 15, 34.6, 46.7);`
2. `funcExp(b, 25, 48.76, 'D', 4567, 78.34);`

In statement 1, because the value of `z` is omitted, all other default values must be omitted. In statement 2, because the value of `v` is omitted, the value of `w` should be omitted, too.

The following are illegal function prototypes with default parameters:

1. `void funcOne(int x, double z = 23.45, char ch, int u = 45);`
2. `int funcTwo(int length = 1, int width, int height = 1);`
3. `void funcThree(int x, int& y = 16, double z = 34);`

In statement 1, because the second parameter `z` is a default parameter, all other parameters after `z` must be default parameters. In statement 2, because the first parameter is a default parameter, all parameters must be the default parameters. In statement 3, a constant value cannot be assigned to `y` because `y` is a reference parameter.

Example 7-10 further illustrates functions with default parameters.

### EXAMPLE 7-10

```
#include <iostream>
#include <iomanip>

using namespace std;

int volume(int l = 1, int w = 1, int h = 1);
void funcOne(int& x, double y = 12.34, char z = 'B');

int main()
{
 int a = 23;
 double b = 48.78;
 char ch = 'M';

 cout << fixed << showpoint;
 cout << setprecision(2);

 cout << "Line 1: a = " << a << ", b = "
 << b << ", ch = " << ch << endl; //Line 1
 cout << "Line 2: Volume = " << volume()
 << endl; //Line 2
 cout << "Line 3: Volume = " << volume(5, 4)
 << endl; //Line 3
 cout << "Line 4: Volume = " << volume(34)
 << endl; //Line 4
 cout << "Line 5: Volume = "
 << volume(6, 4, 5) << endl; //Line 5

 funcOne(a); //Line 6
 funcOne(a, 42.68); //Line 7
 funcOne(a, 34.65, 'Q'); //Line 8

 cout << "Line 9: a = " << a << ", b = "
 << b << ", ch = " << ch << endl; //Line 9

 return 0;
}
```

```

int volume(int l, int w, int h)
{
 return l * w * h; //Line 10
}

void funcOne(int& x, double y, char z)
{
 x = 2 * x; //Line 11
 cout << "Line 12: x = " << x << ", y = "
 << y << ", z = " << z << endl; //Line 12
}

```

### Sample Run:

```

Line 1: a = 23, b = 48.78, ch = M
Line 2: Volume = 1
Line 3: Volume = 20
Line 4: Volume = 34
Line 5: Volume = 120
Line 12: x = 46, y = 12.34, z = B
Line 12: x = 92, y = 42.68, z = B
Line 12: x = 184, y = 34.65, z = Q
Line 9: a = 184, b = 48.78, ch = M

```

#### NOTE

In programs in this book, the definition of the function `main` is placed before the definition of any user-defined functions. You must, therefore, specify the default value for a parameter in the function prototype and in the function prototype only, *not* in the function definition.

## PROGRAMMING EXAMPLE: Classify Numbers

In this example, we use functions to rewrite the program that determines the number of odds and evens from a given list of integers. This program was first written in Chapter 5.

The main algorithm remains the same:

1. Initialize the variables, **zeros**, **odds**, and **evens** to 0.
2. Read a number.
3. If the number is even, increment the even count, and if the number is also zero, increment the zero count; else, increment the odd count.
4. Repeat Steps 2 and 3 for each number in the list.

The main parts of the program are: initialize the variables, read and classify the numbers, and then output the results. To simplify the function `main` and further illustrate parameter passing, the program includes:

- A function `initialize` to initialize the variables, such as `zeros`, `odds`, and `evens`.
- A function `getNumber` to get the number.
- A function `classifyNumber` to determine whether the number is odd or even (and whether it is also zero). This function also increments the appropriate count.
- A function `printResults` to print the results.

Let us now describe each of these functions.

**initialize** The function `initialize` initializes variables to their initial values. The variables that we need to initialize are `zeros`, `odds`, and `evens`. As before, their initial values are all zero. Clearly, this function has three parameters. Because the values of the formal parameters initializing these variables must be passed outside of the function, these formal parameters must be reference parameters. Essentially, this function is:

```
void initialize(int& zeroCount, int& oddCount, int& evenCount)
{
 zeroCount = 0;
 oddCount = 0;
 evenCount = 0;
}
```

**getNumber** The function `getNumber` reads a number and then passes this number to the function `main`. Because you need to pass only one number, this function has only one parameter. The formal parameter of this function must be a reference parameter because the number read is passed outside of the function. Essentially, this function is:

```
void getNumber(int& num)
{
 cin >> num;
}
```

You can also write the function `getNumber` as a value-returning function. See the note at the end of this programming example.

**classifyNumber** The function `classifyNumber` determines whether the number is odd or even, and if the number is even, it also checks whether the number is zero. It also updates the values of some of the variables, `zeros`, `odds`, and `evens`. This function needs to know the number to be analyzed; therefore, the number must be passed as a parameter. Because this function also increments the appropriate count, the variables (that is, `zeros`, `odds`, and `evens` declared in `main`) holding the counts must be passed as parameters to this function. Thus, this function has four parameters.

Because the number will only be analyzed, you need to pass only its value. Thus, the formal parameter corresponding to this variable is a value parameter. After analyzing the number, this function increments the values of some of the variables, `zeros`, `odds`, and `evens`. Therefore, the formal parameters corresponding to these variables

must be reference parameters. The algorithm to analyze the number and increment the appropriate count is the same as before. The definition of this function is:

```
void classifyNumber(int num, int& zeroCount, int& oddCount,
 int& evenCount)
{
 switch (num % 2)
 {
 case 0:
 evenCount++;
 if (num == 0)
 zeroCount++;
 break;
 case 1:
 case -1:
 oddCount++;
 } //end switch
} //end classifyNumber
```

**printResults** The function `printResults` prints the final results. To print the results (that is, the number of zeros, odds, and evens), this function must have access to the values of the variables, `zeros`, `odds`, and `evens` declared in the function `main`. Therefore, this function has three parameters. Because this function prints only the values of the variables, the formal parameters are value parameters. The definition of this function is:

```
void printResults(int zeroCount, int oddCount, int evenCount)
{
 cout << "There are " << evenCount << " evens, "
 << "which includes " << zeroCount << " zeros"
 << endl;

 cout << "The number of odd numbers is: " << oddCount
 << endl;
} //end printResults
```

We now give the main algorithm and show how the function `main` calls these functions.

#### MAIN ALGORITHM

1. Call the function `initialize` to initialize the variables.
2. Prompt the user to enter 20 numbers.
3. For each number in the list:
  - a. Call the function `getNumber` to read a number.
  - b. Output the number.
  - c. Call the function `classifyNumber` to classify the number and increment the appropriate count.
4. Call the function `printResults` to print the final results.

**COMPLETE PROGRAM LISTING**

```

//*****
// Author: D.S. Malik
//
// Program: Classify Numbers
// This program reads 20 numbers and outputs the number of
// zeros, odd, and even numbers.
//*****

#include <iostream>
#include <iomanip>

using namespace std;

const int N = 20;

//Function prototypes
void initialize(int& zeroCount, int& oddCount, int& evenCount);
void getNumber(int& num);
void classifyNumber(int num, int& zeroCount, int& oddCount,
 int& evenCount);
void printResults(int zeroCount, int oddCount, int evenCount);

int main()
{
 //Variable declaration
 int counter; //loop control variable
 int number; //variable to store the new number
 int zeros; //variable to store the number of zeros
 int odds; //variable to store the number of odd integers
 int evens; //variable to store the number of even integers

 initialize(zeros, odds, evens); //Step 1

 cout << "Please enter " << N << " integers."
 << endl; //Step 2
 cout << "The numbers you entered are: "
 << endl;

 for (counter = 1; counter <= N; counter++) //Step 3
 {
 getNumber(number); //Step 3a
 cout << number << " "; //Step 3b
 classifyNumber(number, zeros, odds, evens); //Step 3c
 } // end for loop

 cout << endl;
}

```

```

 printResults(zeros, odds, evens); //Step 4
 }
 return 0;
}

void initialize(int& zeroCount, int& oddCount, int& evenCount)
{
 zeroCount = 0;
 oddCount = 0;
 evenCount = 0;
}

void getNumber(int& num)
{
 cin >> num;
}

void classifyNumber(int num, int& zeroCount, int& oddCount,
 int& evenCount)
{
 switch (num % 2)
 {
 case 0:
 evenCount++;
 if (num == 0)
 zeroCount++;
 break;
 case 1:
 case -1:
 oddCount++;
 } //end switch
} //end classifyNumber

void printResults(int zeroCount, int oddCount, int evenCount)
{
 cout << "There are " << evenCount << " evens, "
 << "which includes " << zeroCount << " zeros"
 << endl;

 cout << "The number of odd numbers is: " << oddCount
 << endl;
} //end printResults

```

**Sample Run:** In this sample run, the user input is shaded.

```

Please enter 20 integers.
The numbers you entered are:
0 0 12 23 45 7 -2 -8 -3 -9 4 0 1 0 -7 23 -24 0 0 12
0 0 12 23 45 7 -2 -8 -3 -9 4 0 1 0 -7 23 -24 0 0 12
There are 12 evens, which includes 6 zeros
The number of odd numbers is: 8

```

**NOTE**

In the previous program, because the data is assumed to be input from the standard input device (the keyboard) and the function `getNumber` returns only one value, you can also write the function `getNumber` as a value-returning function. If written as a value-returning function, the definition of the function `getNumber` is:

```
int getNumber()
{
 int num;

 cin >> num;

 return num;
}
```

In this case, the statement (function call):

```
getNumber(number);
```

in the function `main` should be replaced by the statement:

```
number = getNumber();
```

Of course, you also need to change the function prototype.

## PROGRAMMING EXAMPLE: Data Comparison

This programming example illustrates:

- How to read data from more than one file in the same program.
- How to send output to a file.
- How to generate bar graphs.
- With the help of functions and parameter passing, how to use the same program segment on different (but similar) sets of data.
- How to use structured design to solve a problem and how to perform parameter passing.

This program is broken into two parts. First, you learn how to read data from more than one file. Second, you learn how to generate bar graphs.

Two groups of students at a local university are enrolled in certain special courses during the summer semester. The courses are offered for the first time and are taught by different teachers. At the end of the semester, both groups are given the same tests for the same courses, and their scores are recorded in separate files. The data in each file is in the following form:

```

courseNo score1, score2, ..., scoreN -999
courseNo score1, score2, ..., scoreM -999
.
.
.

```

Let us write a program that finds the average course score for each course for each group. The output is of the following form:

| Course No | Group No | Course Average |
|-----------|----------|----------------|
| CSC       | 1        | 83.71          |
|           | 2        | 80.82          |
| ENG       | 1        | 82.00          |
|           | 2        | 78.20          |
| .         | .        | .              |

Avg for group 1: 82.04

Avg for group 2: 82.01

**Input** Because the data for the two groups are recorded in separate files, the input data appears in two separate files.

**Output** As shown above.

#### PROBLEM ANALYSIS AND ALGORITHM DESIGN

Reading input data from both files is straightforward. Suppose the data is stored in the file `group1.txt` for group 1 and file `group2.txt` for group 2. After processing the data for one group, we can process the data for the second group for the same course and continue until we run out of data. Processing data for each course is similar and is a two-step process:

1. a. Sum the scores for the course.  
b. Count the number of students in the course.  
c. Divide the total score by the number of students to find the course average.
2. Output the results.

We are comparing only the averages of the corresponding courses in each group, and the data in each file is ordered according to course ID. To ensure that only the averages of the corresponding courses are compared, we compare the course IDs for each group. If the corresponding course IDs are not the same, we output an error message and terminate the program.

This discussion suggests that we should write a function, `calculateAverage`, to find the course average. We should also write another function, `printResult`, to output the data in the form given. By passing the appropriate parameters, we can use the same functions, `calculateAverage` and `printResult`, to process each course's data for both groups. (In the second part of the program, we modify the function `printResult`.)

The preceding discussion translates into the following algorithm:

1. Initialize the variables.
2. Get the course IDs for group 1 and group 2.
3. If the course IDs are different, print an error message and exit the program.
4. Calculate the course averages for group 1 and group 2.
5. Print the results in the form given above.
6. Repeat Steps 2 through 5 for each course.
7. Print the final results.

**Variables** The preceding discussion suggests that the program needs the following variables for data manipulation in the function `main`:

```

main)
string courseId1; //course ID for group 1
string courseId2; //course ID for group 2
int numberOfCourses;
double avg1; //average for a course in group 1
double avg2; //average for a course in group 2
double avgGroup1; //average group 1
double avgGroup2; //average group 2
ifstream group1; //input stream variable for group 1
ifstream group2; //input stream variable for group 2

ofstream outfile; //output stream variable

```

Next, we discuss the functions `calculateAverage` and `printResult`. Then, we will put the function `main` together.

**calculateAverage** This function calculates the average for a course. Because the input is stored in a file and the input file is opened in the function `main`, we must pass the `ifstream` variable associated with the input file to this function. Furthermore, after calculating the course average, this function must pass the course average to the function `main`. Therefore, this function has two parameters, and both parameters must be reference parameters.

To find the course average, we must first find the sum of all scores for the course and the number of students who took the course and then divide the sum by the number of students. Thus, we need a variable to find the sum of the scores, a variable to count the number of students, and a variable to read and store a score. Of course, we must initialize the variable to find the sum and the variable to count the number of students to zero.

**Local Variables** In the previous discussion of data manipulation, we identified three variables for the function `calculateAverage`:

```

calculateAverage) double totalScore = 0.0;
 int numberOfStudents = 0;
 int score;

```

The above discussion translates into the following algorithm for the function `calculateAverage`:

1. Declare and initialize variables.
2. Get the (next) course score, `score`.
3. `while` the `score` is not `-999`
  - a. Update `totalScore` by adding the course score.
  - b. Increment `numberOfStudents` by 1.
  - c. Get the (next) course score, `score`.
4. `courseAvg = totalScore / numberOfStudents;`

We are now ready to write the definition of the function `calculateAverage`.

```
void calculateAverage(istream& inp, double& courseAvg)
{
 double totalScore = 0.0;
 int numberOfStudents = 0;
 int score;

 inp >> score;
 while (score != -999)
 {
 totalScore = totalScore + score;
 numberOfStudents++;
 inp >> score;
 } //end while

 courseAvg = totalScore / numberOfStudents;
} //end calculate Average
```

`printResult` The function `printResult` prints the group's course ID, group number, and course average. The output is stored in a file. So we must pass four parameters to this function: the `ofstream` variable associated with the output file, the group number, the course ID, and the course average for the group. The `ofstream` variable must be passed by reference. Because the function uses only the values of the other variables, the remaining three parameters should be value parameters. Also, from the output, it is clear that we print the course ID only before the group number.

1. In pseudocode, the algorithm is:

```
if (group number == 1)
 print course ID
else
 print a blank
```

print group number and course average

The definition of the function `printResult` follows:

```
void printResult(ofstream& outp, string courseID, int groupNo,
 double avg)
{
 if (groupNo == 1)
 outp << " " << courseID << " ";
 else
 outp << " ";

 outp << setw(8) << groupNo << setw(17) << avg << endl;
} //end printResult
```

Now that we have designed and defined the functions `calculateAverage` and `printResult`, we can describe the algorithm for the function `main`. Before outlining the algorithm, however, we note the following: It is quite possible that in both input files, the data is ordered according to the course IDs, but one file might have fewer courses than the other. We do not discover this error until after we have processed both files and discovered that one file has unprocessed data. Make sure to check for this error before printing the final answer—that is, the averages for group 1 and group 2.

#### MAIN

#### ALGORITHM:

#### Function `main`

1. Declare the variables (local declaration).
2. Open the input files.
3. Print a message if you are unable to open a file and terminate the program.
4. Open the output file.
5. To output floating-point numbers in a fixed decimal format with the decimal point and trailing zeros, set the manipulators `fixed` and `showpoint`. Also, to output floating-point numbers to two decimal places, set the precision to two decimal places.
6. Initialize the course average for group 1 to 0.0.
7. Initialize the course average for group 2 to 0.0.
8. Initialize the number of courses to 0.
9. Print the heading.
10. Get the course ID, `courseId1`, for group 1.
11. Get the course ID, `courseId2`, for group 2.
12. For each course in group 1 and group 2,
  - a. `if (courseId1 != courseId2)`

```
{
 cout << "Data error: Course IDs do not match.\n";
 return 1;
}
```

- b. `else`
    - {
    - i. Calculate the course average for group 1 (call the function `calculateAverage` and pass the appropriate parameters).
      - ii. Calculate the course average for group 2 (call the function `calculateAverage` and pass the appropriate parameters).
      - iii. Print the results for group 1 (call the function `printResult` and pass the appropriate parameters).
      - iv. Print the results for group 2 (call the function `printResult` and pass the appropriate parameters).
      - v. Update the average for group 1.
      - vi. Update the average for group 2.
      - vii. Increment the number of courses.
    - }
  - c. Get the course ID, `courseId1`, for group 1.
  - d. Get the course ID, `courseId2`, for group 2.
13.
  - a. if `not_end_of_file` on group 1 and `end_of_file` on group 2  
print "Ran out of data for group 2 before group 1"
  - b. else if `end_of_file` on group 1 and `not_end_of_file` on group 2  
print "Ran out of data for group 1 before group 2"
  - c. else print the average of group 1 and group 2.
14. Close the input and output files.

### COMPLETE PROGRAM LISTING

```
//*****
// Author: D.S. Malik
//
// Program: Comparison of Class Averages
// This program computes and compares the class averages of
// two groups of students.
//*****

#include <iostream>
#include <iomanip>
#include <fstream>
#include <string>
using namespace std;
```

```

//Function prototypes
void calculateAverage(istream& inp, double& courseAvg);
void printResult(ofstream& outp, string courseId,
 int groupNo, double avg);

int main()
{
 //Step 1
 string courseId1; //course ID for group 1
 string courseId2; //course ID for group 2
 int numberOfCourses;
 double avg1; //average for a course in group 1
 double avg2; //average for a course in group 2
 double avgGroup1; //average group 1
 double avgGroup2; //average group 2
 ifstream group1; //input stream variable for group 1
 ifstream group2; //input stream variable for group 2
 ofstream outfile; //output stream variable

 group1.open("group1.txt"); //Step 2
 group2.open("group2.txt"); //Step 2

 if (!group1 || !group2) //Step 3
 {
 cout << "Unable to open files." << endl;
 cout << "Program terminates." << endl;
 return 1;
 }

 outfile.open("student.out"); //Step 4
 outfile << fixed << showpoint; //Step 5
 outfile << setprecision(2); //Step 5

 avgGroup1 = 0.0; //Step 6
 avgGroup2 = 0.0; //Step 7

 numberOfCourses = 0; //Step 8

 outfile << "Course No Group No "
 << "Course Average" << endl; //Step 9

 group1 >> courseId1; //Step 10
 group2 >> courseId2; //Step 11
 while (group1 && group2) //Step 12
 {
 if (courseId1 != courseId2) //Step 12a
 {
 cout << "Data error: Course IDs "
 << "do not match." << endl;

```

```

 cout << "Program terminates." << endl;
 return 1;
 }
 else //Step 12b
 {
 calculateAverage(group1, avg1); //Step 12b.i
 calculateAverage(group2, avg2); //Step 12b.ii
 printResult(outfile, courseId1,
 1, avg1); //Step 12b.iii
 printResult(outfile, courseId2,
 2, avg2); //Step 12b.iv
 avgGroup1 = avgGroup1 + avg1; //Step 12b.v
 avgGroup2 = avgGroup2 + avg2; //Step 12b.vi
 outfile << endl; //Step 12b.vii
 numberOfCourses++;
 }

 group1 >> courseId1; //Step 12c
 group2 >> courseId2; //Step 12d
} //end while

if (group1 && !group2) //Step 13a
 cout << "Ran out of data for group 2 "
 << "before group 1." << endl;
else if (!group1 && group2) //Step 13b
 cout << "Ran out of data for group 1 "
 << "before group 2." << endl;
else //Step 13c
{
 outfile << "Avg for group 1: "
 << avgGroup1 / numberOfCourses
 << endl;
 outfile << "Avg for group 2: "
 << avgGroup2 / numberOfCourses
 << endl;
}

group1.close(); //Step 14
group2.close(); //Step 14
outfile.close(); //Step 14

return 0;
}

void calculateAverage(istream& inp, double& courseAvg)
{
 double totalScore = 0.0;
 int numberOfStudents = 0;
 int score;

```

```

inp >> score;
while (score != -999)
{
 totalScore = totalScore + score;
 numberOfStudents++;
 inp >> score;
} //end while

courseAvg = totalScore / numberOfStudents;
} //end calculate Average

void printResult(ofstream& outp, string courseID, int groupNo,
 double avg)
{
 if (groupNo == 1)
 outp << " " << courseID << " ";
 else
 outp << " ";
 outp << setw(8) << groupNo << setw(17) << avg << endl;
} //end printResult

```

### Sample Run:

| Course No | Group No | Course Average |
|-----------|----------|----------------|
| CSC       | 1        | 83.71          |
|           | 2        | 80.82          |
| ENG       | 1        | 82.00          |
|           | 2        | 78.20          |
| HIS       | 1        | 77.69          |
|           | 2        | 84.15          |
| MTH       | 1        | 83.57          |
|           | 2        | 84.29          |
| PHY       | 1        | 83.22          |
|           | 2        | 82.60          |

Avg for group 1: 82.04

Avg for group 2: 82.01

### Input Data Group 1

```

CSC 80 100 70 80 72 90 89 100 83 70 90 73 85 90 -999
ENG 80 90 80 94 90 74 78 63 83 80 90 -999
HIS 90 70 80 70 90 50 89 83 90 68 90 60 80 -999
MTH 74 80 75 89 90 73 90 82 74 90 84 100 90 79 -999
PHY 100 83 93 80 63 78 88 89 75 -999

```

**Input Data Group 2**

```

CSC 90 75 90 75 80 89 100 60 80 70 80 -999
ENG 80 80 70 68 70 78 80 90 90 76 -999
HIS 100 80 80 70 90 76 88 90 90 75 90 85 80 -999
MTH 80 85 85 92 90 90 74 90 83 65 72 90 84 100 -999
PHY 90 93 73 85 68 75 67 100 87 88 -999

```

**BAR  
GRAPH**

In the business world, company executives often like to see results in some visual form, such as bar graphs. Many currently available software packages can analyze data in several forms and then display the results in a visual form, such as bar graphs or pie charts. The second part of this program aims to display the results found earlier in the form of bar graphs, as shown below:

```

Course Course Average
 ID 0 10 20 30 40 50 60 70 80 90 100
 |....|....|....|....|....|....|....|....|....|....|
CSC *****
 #####
ENG *****
 #####
 .
 .
 .
Group 1 -- ****
Group 2 -- ####

Avg for group 1: 82.04
Avg for group 2: 82.01

```

Each symbol (\* or #) in the bar graph represents two points. If a course average is less than 2, no symbol is printed.

Because the output is in the form of a bar graph, we need to modify the function `printResult`.

**Print Bars** The function `printResult` prints the course ID and the bar graph representing the average for a course. The output is stored in a file. So we must pass four parameters to this function: the `ofstream` variable associated with the output file, the group number (to print \* or #), the course ID, and the course average for the department. To print the bar graph, we can use a loop to print a symbol for each two points. If the average is 78.45, for example, we must print 39 symbols to represent this average. To find the number of symbols to print, we can use integer division as follows:

```
numberOfSymbols = static_cast<int>(average) / 2;
```

For example, `static_cast<int>(78.45) / 2 = 78 / 2 = 39`.

Following this discussion, the definition of the function `printResult` is:

```

void printResult(ofstream& outp, string courseID,
 int groupNo, double avg)
{
 int noOfSymbols;
 int count;

 if (groupNo == 1)
 outp << setw(4) << courseID << " ";
 else
 outp << " ";

 noOfSymbols = static_cast<int>(avg)/2;

 if (groupNo == 1)
 for (count = 1; count <= noOfSymbols; count++)
 outp << '*';
 else
 for (count = 1; count <= noOfSymbols; count++)
 outp << '#';
 outp << endl;
} //end printResult

```

We also include a function `printHeading` to print the first two lines of the output. The definition of this function is:

```

void printHeading(ofstream& outp)
{
 outp << "Course Course Average" << endl;
 outp << " ID 0 10 20 30 40 50 60 70"
 << " 80 90 100" << endl;
 outp << " |...|...|...|...|...|...|...|"
 << "...|...|...|" << endl;
} //end printHeading

```

Replace the function `printResult` in the preceding program, include the function `printHeading`, include the statements to output — `Group 1 -- ****` and `Group 2 -- #####` —, and rerun the program. Your program should generate a bar graph similar to bar graph shown earlier. (The complete program listing is available on the Web site accompanying this book.)

## QUICK REVIEW

1. A function that does not have a data type is called a void function.
2. A return statement without any value can be used in a void function. If a return statement is used in a void function, it is typically used to exit the function early.
3. The heading of a void function starts with the word **void**.
4. In C++, **void** is a reserved word.
5. A void function may or may not have parameters.

6. A call to a void function is a stand-alone statement.
7. To call a void function, you use the function name together with the actual parameters in a stand-alone statement.
8. There are two types of formal parameters: value parameters and reference parameters.
9. A value parameter receives a copy of its corresponding actual parameter.
10. A reference parameter receives the address (memory location) of its corresponding actual parameter.
11. The corresponding actual parameter of a value parameter is an expression, a variable, or a constant value.
12. A constant value cannot be passed to a reference parameter.
13. The corresponding actual parameter of a reference parameter must be a variable.
14. When you include `&` after the data type of a formal parameter, the formal parameter becomes a reference parameter.
15. The stream variables should be passed by reference to a function.
16. If a formal parameter needs to change the value of an actual parameter, in the function heading, you must declare this formal parameter as a reference parameter.
17. The scope of an identifier refers to those parts of the program where it is accessible.
18. Variables declared within a function (or block) are called local variables.
19. Variables declared outside of every function definition (and block) are called global variables.
20. The scope of a function name is the same as the scope of an identifier declared outside of any block.
21. See the scope rules in this chapter (section, Scope of an Identifier).
22. C++ does not allow the nesting of function definitions.
23. An automatic variable is a variable for which memory is allocated on function (or block) entry and deallocated on function (or block) exit.
24. A static variable is a variable for which memory remains allocated throughout the execution of the program.
25. By default, global variables are static variables.
26. In C++, a function can be overloaded.
27. Two functions are said to have different formal parameter lists if both functions have:
  - A different number of formal parameters or
  - If the number of formal parameters is the same, then the data type of the formal parameters, in the order you list them, must differ in at least one position.
28. The signature of a function consists of the function name and its formal parameter list. Two functions have different signatures if they have either different names or different formal parameter lists.

- 29. If a function is overloaded, then in a call to that function, the signature—that is, the formal parameter list of the function—determines which function to execute.
- 30. C++ allows functions to have default parameters.
- 31. If you do not specify the value of a default parameter, the default value is used for that parameter.
- 32. All of the default parameters must be the far-right parameters of the function.
- 33. Suppose a function has more than one default parameter. In a function call, if a value to a default parameter is not specified, then you must omit all arguments to its right.
- 34. Default values can be constants, global variables, or function calls.
- 35. The calling function has the option of specifying a value other than the default for any default parameter.
- 36. You cannot assign a constant value as a default value to a reference parameter.

## EXERCISES

---

- 1. Mark the following statements as true or false.
  - a. A function that changes the value of a reference parameter also changes the value of the actual parameter.
  - b. A variable name cannot be passed to a value parameter.
  - c. If a C++ function does not use parameters, parentheses around the empty parameter list are still required.
  - d. In C++, the names of the corresponding formal and actual parameters must be the same.
  - e. Whenever the value of a reference parameter changes, the value of the actual parameter changes.
  - f. In C++, function definitions can be nested; that is, the definition of one function can be enclosed in the body of another function.
  - g. Using global variables in a program is a better programming style than using local variables, because extra variables can be avoided.
  - h. In a program, global constants are as dangerous as global variables.
  - i. The memory for a static variable remains allocated between function calls.
- 2. Identify the following items in the programming code shown below.
  - a. Function prototype, function heading, function body, and function definitions
  - b. Function call statements, formal parameters, and actual parameters
  - c. Value parameters and reference parameters
  - d. Local variables and global variables

```

#include <iostream> //Line 1
using namespace std; //Line 2
int one; //Line 3
void hello(int&, double, char); //Line 4

int main() //Line 5
{ //Line 6
 int x; //Line 7
 double y; //Line 8
 char z; //Line 9
 .
 .
 .
 hello(x, y, z); //Line 10
 .
 .
 .
 hello(x, y - 3.5, 'S'); //Line 11
 .
 .
 .
} //Line 12

void hello(int& first, double second, char ch) //Line 13
{ //Line 14
 int num; //Line 15
 double y; //Line 16
 int u ; //Line 17
 .
 .
 .
} //Line 18

```

3. a. Explain the difference between an actual and a formal parameter.
- b. Explain the difference between a value and a reference parameter.
- c. Explain the difference between a local and a global variable.
4. What is the output of the following program?

```

#include <iostream>
using namespace std;

void func1();
void func2();

int main()
{
 int num;

 cout << "Enter 1 or 2: ";

```

```

 cin >> num;
 cout << endl;

 cout << "Take ";

 if (num == 1)
 func1();
 else if (num == 2)
 func2();
 else
 cout << "Invalid input. You must enter a 1 or 2" << endl;

 return 0;
}

void func1()
{
 cout << "Programming I." << endl;
}

void func2()
{
 cout << "Programming II." << endl;
}

```

- a. What is the output if the input is 1?
  - b. What is the output if the input is 2?
  - c. What is the output if the input is 3?
  - d. What is the output if the input is -1?
5. Write the definition of a void function that takes as input a decimal number and as output 3 times the value of the decimal number. Format your output to two decimal places.
  6. Write the definition of a void function that takes as input two decimal numbers. If the first number is nonzero, it outputs second number divided by the first number; otherwise, it outputs a message indicating that the second number cannot be divided by the first number because the first number is 0.
  7. Write the definition of a **void** function with three reference parameters of type **int**, **double**, and **string**. The function sets the values of the **int** and **double** variables to 0 and the value of the **string** variable to the empty string.
  8. Write the definition of a **void** function that takes as input two parameters of type **int**, say **sum** and **testScore**. The function updates the value of **sum** by adding the value of **testScore**. The new value of **sum** is reflected in the calling environment.
  9. What is the output of the following program?

```

#include <iostream>
using namespace std;

```

```

void find(int a, int& b, int& c,)

int main()
{
 int one, two, three;

 one = 5;
 two = 10;
 three = 15;

 find(one, two, three);
 cout << one << ", " << two << ", " << three << endl;

 find(two, one, three);
 cout << one << ", " << two << ", " << three << endl;

 find(three, two, one);
 cout << one << ", " << two << ", " << three << endl;

 find(two, three, one);
 cout << one << ", " << two << ", " << three << endl;

 return 0;
}

void find(int a, int& b, int& c)
{
 int temp;

 c = a + b;
 temp = a;
 a = b;
 b = 2 * temp;
}

```

10. What is the output of the following program?

```

#include <iostream>
using namespace std;

int x;

void summer(int&, int);
void fall(int, int&);

int main()
{
 int intNum1 = 2;
 int intNum2 = 5;
 x = 6;

 summer(intNum1, intNum2);
 cout << intNum1 << " " << intNum2 << " " << x << endl;
}

```

```

 fall(intNum1, intNum2);
 cout << intNum1 << " " << intNum2 << " " << x << endl;
 return 0;
}

void summer(int& a, int b)
{
 int intNum1;
 intNum1 = b + 12;
 a = 2 * b + 5;
 b = intNum1 + 4;
}

void fall(int u, int& v)
{
 int intNum2;
 intNum2 = x;
 v = intNum2 * 4;
 x = u - v;
}

```

11. In the following program, number the marked statements to show the order in which they will execute (the logical order of execution).

```

#include <iostream>

using namespace std;

void func(int val1, int val2);

int main()
{
 int num1, num2;
 ____ cout << "Please enter two integers." << endl;
 ____ cin >> num1 >> num2;
 ____ func (num1, num2);
 ____ cout << " The two integers are " << num1
 << ", " << num2 << endl;
 ____ return 0;
}

void func(int val1, int val2)
{
 int val3, val4;
 ____ val3 = val1 + val2;
 ____ val4 = val1 * val2;
 ____ cout << "The sum and product are " << val3
 << " and " << val4 << endl;
}

```

12. Consider the following program:

```

#include <iostream>
#include <cmath>
#include <iomanip>

```

```

using namespace std;

void traceMe(double x, double y);

int main()
{
 double one, two;

 cout << "Enter two numbers: ";
 cin >> one >> two;
 cout << endl;

 traceMe(one, two);
 traceMe(two, one);

 return 0;
}

void traceMe(double x, double y)
{
 double z;

 if (x != 0)
 z = sqrt(y) / x;
 else
 {
 cout << "Enter a nonzero number: ";
 cin >> x;
 cout << endl;
 z = floor(pow(y, x));
 }

 cout << fixed << showpoint << setprecision(2);
 cout << x << ", " << y << ", " << z << endl;
}

```

- a. What is the output if the input is 3 625?
  - b. What is the output if the input is 24 1024?
  - c. What is the output if the input is 0 196?
13. The function `traceMe` in Exercise 12 outputs the values of `x`, `y`, and `z`. Modify the definition of this function so that rather than print these values, it sends the values back to the calling environment and the calling environment prints these values.
  14. In Exercise 12, determine the scope of each identifier.
  15. What is the output of the following code fragment? (Note: `alpha` and `beta` are `int` variables.)
 

```

alpha = 5;
beta = 10;

```

```

if (beta >= 10)
{
 int alpha = 10;
 beta = beta + alpha;
 cout << alpha << ' ' << beta << endl;
}
cout << alpha << ' ' << beta << endl;

```

16. Consider the following program. What is its exact output? Show the values of the variables after each line executes, as in Example 7-6.

```

#include <iostream>

using namespace std;

void funOne(int& a);

int main()
{
 int num1, num2;

 num1 = 10; //Line 1

 num2 = 20; //Line 2

 cout << "Line 3: In main: num1 = " << num1
 << ", num2 = " << num2 << endl; //Line 3

 funOne(num1); //Line 4
 cout << "Line 5: In main after funOne: num1 = "
 << num1 << ", num2 = " << num2 << endl; //Line 5

 return 0; //Line 6
}

void funOne(int& a)
{
 int x = 12;
 int z;

 z = a + x; //Line 7

 cout << "Line 8: In funOne: a = " << a
 << ", x = " << x
 << ", and z = " << z << endl; //Line 8

 x = x + 5; //Line 9

 cout << "Line 10: In funOne: a = " << a
 << ", x = " << x
 << ", and z = " << z << endl; //Line 10

 a = a + 8; //Line 11
}

```

```

 cout << "Line 12: In funOne: a = " << a
 << ", x = " << x
 << ", and z = " << z << endl;
 }

```

//Line 12

17. What is the output of the following program?

```

#include <iostream>
using namespace std;

void tryMe(int& v);

int main()
{
 int x = 8;

 for (int count = 1; count < 5; count++)
 tryMe(x);

 return 0;
}

void tryMe(int& v)
{
 static int num = 2;

 if (v % 2 == 0)
 {
 num++;
 v = v + 3;
 }
 else
 {
 num--;
 v = v + 5;
 }
 cout << v << ", " << num << endl;
}

```

18. What is the signature of a function?

19. Consider the following function prototype:

```
void testDefaultParam(int a, int b = 7, char z = '*');
```

Which of the following function calls is correct?

- a. testDefaultParam(5);
- b. testDefaultParam(5, 8);
- c. testDefaultParam(6, '#');
- d. testDefaultParam(0, 0, '\*');

20. Consider the following function definition:

```

void defaultParam(int u, int v = 5, double z = 3.2)
{
 int a;

```

```

 u = u + static_cast<int>(2 * v + z);
 a = u + v * z;
 cout << "a = " << a << endl;
}

```

What is the output of the following function calls?

- a. `defaultParam(6);`
- b. `defaultParam(3, 4);`
- c. `defaultParam(3, 0, 2.8);`

## PROGRAMMING EXERCISES

---

1. Consider the definition of the function `main`.

```

int main()
{
 int x, y;
 char z;
 double rate, hours;
 double amount;
 .
 .
 .
}

```

The variables `x`, `y`, `z`, `rate`, and `hours` referred to in items a through f below are the variables of the function `main`. Each of the functions described must have the appropriate parameters to access these variables. Write the following definitions:

- a. Write the definition of the function `initialize` that initializes `x` and `y` to 0 and `z` to the blank character.
- b. Write the definition of the function `getHoursRate` that prompts the user to input the hours worked and rate per hour to initialize the variables `hours` and `rate` of the function `main`.
- c. Write the definition of the value-returning function `payCheck` that calculates and returns the amount to be paid to an employee based on the hours worked and rate per hour. The hours worked and rate per hour are stored in the variables `hours` and `rate`, respectively, of the function `main`. The formula for calculating the amount to be paid is as follows: For the first 40 hours, the rate is the given rate; for hours over 40, the rate is 1.5 times the given rate.
- d. Write the definition of the function `printCheck` that prints the hours worked, rate per hour, and the salary.
- e. Write the definition of the function `funcOne` that prompts the user to input a number. The function then changes the value of `x` by assigning the value of the expression 2 times the (old) value of `x` plus the value of `y` minus the value entered by the user.

- f. Write the definition of the function `nextChar` that sets the value of `z` to the next character stored in `z`.
  - g. Write the definition of a function `main` that tests each of these functions.
2. Consider the following C++ code:

```
#include <iostream>
#include <cmath>
#include <iomanip>

using namespace std;

void func1();
void func2(/*formal parameters*/);

int main()
{
 int num1, num2;
 double num3;

 int choice;

 cout << fixed << showpoint << setprecision(2);

 do
 {
 func1();
 cin >> choice;
 cout << endl;

 if (choice == 1)
 {
 func2(num1, num2, num3);
 cout << num1 << ", " << num2 << ", " << num3 << endl;
 }
 }
 while (choice != 99);

 return 0;
}

void func1()
{
 cout << "To run the program, enter 1." << endl;
 cout << "To exit the program, enter 99." << endl;
 cout << "Enter 1 or 99: ";
}

void func2(/*formal parameters*/)
{
 //Write the body of func2.
}
```

The function `func2` has three parameters of type `int`, `int`, and `double`, say `a`, `b`, and `c`, respectively. Write the definition of `func2` so that its action is as follows:

- a. Prompt the user to input two integers and store the numbers in `a` and `b`, respectively.
- b. If both of the numbers are nonzero:
  - i. If  $a \geq b$ , the value assigned to `c` is  $a$  to the power  $b$ , that is,  $a^b$ .
  - ii. If  $a < b$ , the value assigned to `c` is  $b$  to the power  $a$ , that is,  $b^a$ .
- c. If `a` is nonzero and `b` is zero, the value assigned to `c` is the square root of the absolute value of `a`.
- d. If `b` is nonzero and `a` is zero, the value assigned to `c` is the square root of the absolute value of `b`.
- e. Otherwise, the value assigned to `c` is 0.

The values of `a`, `b`, and `c` are passed back to the calling environment.

After completing the definition of the `func2` and writing its function prototype, test run your program

3. The statements in the following program are not in the correct order. Rearrange the statements so that the program outputs the total time an employee spent on the job each day. The program asks the user to enter the employee's name, the arrival time (arrival hour, arrival minute, AM or PM), and departure time (departure hour, departure minute, AM or PM). The program also allows the user to run the program as long as the user wishes. After rearranging the statements, your program must be properly indented.

```
#include <iostream>
#include <string>

using namespace std;

int main()
{
 string employeeName;
 int arrivalHr;

 int departureHr;
 int departureMin;
 bool departureAM;

 char response;
 char discard;
 char isAM;

 cout << "This program calculates the total time spent by an "
 << "employee on the job." << endl;
 cout << "To run the program, enter (y/Y): ";
 cin >> response;
 cout << endl;
```

```

cin.get(discard);

while (response == 'y' || response == 'Y')
{
 cout << "Enter employee's name: ";
 getline(cin, employeeName);
 cout << endl;

 if (isAM == 'y' || isAM == 'Y')
 arrivalAM = true;
 else
 arrivalAM = false;

 cout << "Enter departure hour: ";
 cin >> departureHr;
 cout << endl;
 cout << "Enter departure minute: ";
 cin >> departureMin;
 cout << endl;
 cout << "Enter (y/Y) if departure is before 12:00PM: ";
 cin >> isAM;
 cout << endl;

 if (isAM == 'y' || isAM == 'Y')
 departureAM = true;
 else
 departureAM = false;

 cout << employeeName << endl;
 timeOnJob(arrivalHr, arrivalMin, arrivalAM,
 departureHr, departureMin, departureAM);

 cout << "Enter arrival hour: ";
 cin >> arrivalHr;
 cout << endl;
 cout << "Enter arrival minute: ";
 cin >> arrivalMin;
 cout << endl;
 cout << "Enter (y/Y) if arrival is before 12:00PM: ";
 cin >> isAM;
 cout << endl;

 int arrivalMin;
 bool arrivalAM;
 cout << "Run program again (y/Y): ";
 cin >> response;
 cout << endl;
 cin.get(discard);
}

return 0;
}

```

```

void timeOnJob(int arvHr, int arvMin, bool arvIsAM,
 int depHr, int depMin, bool depIsAM)
{
 int arvTimeInMin;
 int depTimeInMin;
 int timeOnJobInMin;

 else if (arvIsAM == true && depIsAM == false)
 {
 arvTimeInMin = arvHr * 60 + arvMin;
 depTimeInMin = depHr * 60 + depMin;

 timeOnJobInMin = (720 - arvTimeInMin) + depTimeInMin;
 cout << "Time spent of job: "
 << timeOnJobInMin / 60 << " hour(s) and "
 << timeOnJobInMin % 60 << " minutes." << endl;
 }

 else
 if (arvTimeInMin <= depTimeInMin)
 {
 timeOnJobInMin = depTimeInMin - arvTimeInMin;
 cout << "Time spent of job: "
 << timeOnJobInMin / 60 << " hour(s) and "
 << timeOnJobInMin % 60 << " minutes." << endl;
 }
 else
 cout << "Invalid input." << endl;
 if ((arvIsAM == true && depIsAM == true)
 || (arvIsAM == false && depIsAM == false))
 {
 cout << "Invalid input." << endl;
 }

 void timeOnJob(int arvHr, int arvMin, bool arvIsAM,
 int depHr, int depMin, bool depIsAM);
}

```

4. The function `printGrade` in Example 7-5 is written as a `void` function to compute and output the course grade. The course score is passed as a parameter to the function `printGrade`. Rewrite the function `printGrade` as a value-returning function so that it computes and returns the course grade. (The course grade must be output in the function `main`.) Also, change the name of the function to `calculateGrade`.
5. In this exercise, you are to modify the Classify Numbers programming example in this chapter. As written, the program inputs the data from the standard input device (keyboard) and outputs the results on the standard output device (screen). The program can process only 20 numbers. Rewrite the program to incorporate the following requirements:

- a. Data to the program is input from a file of an unspecified length; that is, the program does not know in advance how many numbers are in the file.
  - b. Save the output of the program in a file.
  - c. Modify the function `getNumber` so that it reads a number from the input file (opened in the function `main`), outputs the number to the output file (opened in the function `main`), and sends the number read to the function `main`. Print only 10 numbers per line.
  - d. Have the program find the sum and average of the numbers.
  - e. Modify the function `printResult` so that it outputs the final results to the output file (opened in the function `main`). Other than outputting the appropriate counts, this new definition of the function `printResult` should also output the sum and average of the numbers.
6. For research purposes and to better help students, the admissions office of your local university wants to know how well female and male students perform in certain courses. You receive a file that contains female and male student GPAs for certain courses. Due to confidentiality, the letter code `f` is used for female students and `m` for male students. Every file entry consists of a letter code followed by a GPA. Each line has one entry. The number of entries in the file is unknown. Write a program that computes and outputs the average GPA for both female and male students. Format your results to two decimal places. Your program should use the following functions:
- a. Function `openFiles`: This function opens the input and output files, and sets the output of the floating-point numbers to two decimal places in a fixed decimal format with a decimal point and trailing zeros.
  - b. Function `initialize`: This function initializes variables such as `countFemale`, `countMale`, `sumFemaleGPA`, and `sumMaleGPA`.
  - c. Function `sumGrades`: This function finds the sum of the female and male students' GPAs.
  - d. Function `averageGrade`: This function finds the average GPA for female and male students.
  - e. Function `printResults`: This function outputs the relevant results.
  - f. There can be no global variables. Use the appropriate parameters to pass information in and out of functions.
7. Write a program that prints the day number of the year, given the date in the form month-day-year. For example, if the input is 1-1-2006, the day number is 1; if the input is 12-25-2006, the day number is 359. The program should check for a leap year. A year is a leap year if it is divisible by 4, but not divisible by 100. For example, 1992 and 2008 are divisible by 4, but not by 100. A year that is divisible by 100 is a leap year if it is also divisible by 400. For example, 1600 and 2000 are divisible by 400. However, 1800 is not a leap year because 1800 is not divisible by 400.

8. Write a program that reads a string and outputs the number of times each lowercase vowel appears in it. Your program must contain a function with one of its parameters as a **string** variable, and return the number of times each lowercase vowel appears in it. Also write a program to test your function. (Note that if **str** is a variable of type **string**, then **str.at(i)** returns the character at the *i*th position. The position of the first character is 0. Also, **str.length()** returns the length of the **str**, that is, the number of characters in **str**.)
9. Redo Programming Exercise 8 as follows. Write a program that reads a string and outputs the number of times each lowercase vowel appears in it. Your program must contain a function with one of its parameters as a **char** variable, and if the character is a vowel, it increments that vowel's count.
10. Write a function that takes as a parameter an integer (as a **long** value) and returns the number of odd, even, and zero digits. Also write a program to test your function.
11. The cost to become a member of a fitness center is as follows: (a) Senior citizens discount is 30%, (b) If membership is bought and paid for 12 or more months, the discount is 15%, (c) If more than five personal training sessions are bought and paid for, the discount on each session is 20%. Write a menu-driven program that determines the cost of a new membership. Your program must contain a function that displays the general information about the fitness center and its charges; a function to get all of the necessary information to determine the membership cost; and a function to determine the membership cost. Use appropriate parameters to pass information in and out of a function. (Do not use any global variables.)
12. Write a program that outputs inflation rates for two successive years and whether the inflation is increasing or decreasing. Ask the user to input the current price of an item and its price one year and two years ago. To calculate the inflation rate for a year, subtract the price of the item for that year from the price of the item one year ago and then divide the result by the price a year ago. Your program must contain at least the following functions: a function to get the input, a function to calculate the results, and a function to output the results. Use appropriate parameters to pass the information in and out of the function. Do not use any global variables.
13. Write a program to convert the time from 24-hour notation to 12-hour notation and vice versa. Your program must be menu driven, giving the user the choice of converting the time between the two notations. Furthermore, your program must contain at least the following function: a function to convert the time from 24-hour notation to 12-hour notation, a function to convert the time from 12-hour notation to 24-hour notation, a function to display the choices, function(s) to get the input, and function(s) to display the results. (For 12-hour time notation, your program must display AM or PM.)
14. **(The box problem)** You have been given a flat cardboard of area, say, 70 square inches to make an open box by cutting a square from each corner and

folding the sides (see Figure 7-20). Your objective is to determine the dimensions, that is, the length and width, and the side of the square to be cut from the corners so that the resulting box is of maximum length.




FIGURE 7-20 Cardboard box

Write a program that prompts the user to enter the area of the flat cardboard. The program then outputs the length and width of the cardboard and the length of the side of the square to be cut from the corner so that the resulting box is of maximum volume. Calculate your answer to three decimal places. Your program must contain a function that takes as input the length and width of the cardboard and returns the side of the square that should be cut to maximize the volume. The function also returns the maximum volume.

15. **(The power station problem)** A power station is on one side of a river that is one-half mile wide, and a factory is eight miles downstream on the other side of the river (see Figure 7-21). It costs \$7 per foot to run power lines over land and \$9 per foot to run them under water. Your objective is to determine the most economical path to lay the power line. That is, determine how long the power line should run under water and how long it should run over land to achieve the minimum total cost of laying the power line.




FIGURE 7-21 Power station, river, and factory

Write a program that prompts the user to enter:

- a. The width of the river
- b. The distance of the factory downstream on the other side of the river
- c. The cost of laying the power line under water
- d. The cost of laying the power line over land

The program then outputs the length of the power line that should run under water and the length that should run over land so the cost of constructing the power line is at the minimum. The program should also output the total cost of constructing the power line.

16. **(Pipe problem, requires trigonometry)** A pipe is to be carried around the right-angled corner of two intersecting corridors. Suppose that the widths of the two intersecting corridors are 5 feet and 8 feet (see Figure 7-22). Your objective is to find the length of the longest pipe, rounded to the nearest foot, that can be carried level around the right-angled corner.




FIGURE 7-22 Pipe problem

Write a program that prompts the user to input the widths of both of the hallways. The program then outputs the length of the longest pipe, rounded to the nearest foot, that can be carried level around the right-angled corner. (Note that the length of the pipe is given by  $l = AB + BC = 8 / \sin \theta + 5 / \cos \theta$ , where  $0 < \theta < \pi/2$ .)



# 8 CHAPTER

# USER-DEFINED SIMPLE DATA TYPES, NAMESPACES, AND THE `string` TYPE

IN THIS CHAPTER, YOU WILL:

- Learn how to create and manipulate your own simple data type called the enumeration type
- Become familiar with the `typedef` statement
- Learn about the `namespace` mechanism
- Explore the `string` data type and learn how to use the various `string` functions to manipulate strings

In Chapter 2, you learned that C++'s simple data type is divided into three categories: integral, floating-point, and `enum`. In subsequent chapters, you worked mainly with integral and floating-point data types. In this chapter, you will learn about the `enum` type. Moreover, the statement `using namespace std;` (discussed in Chapter 2) is used in every C++ program that uses ANSI/ISO Standard C++ style header files. The second half of this chapter examines the purpose of this statement. In fact, you will learn what the `namespace` mechanism is. You will also learn about the `string` type and many useful functions that you can use to effectively manipulate strings.

## Enumeration Type

**NOTE**

This section may be skipped without any loss of continuity.

Chapter 2 defined a data type as a set of values together with a set of operations on them. For example, the `int` data type consists of integers from -2,147,483,648 to 2,147,483,647 and the set of operations on these numbers—namely, the arithmetic operations (+, -, \*, /, and %). Because the main objective of a program is to manipulate data, the concept of a data type becomes fundamental to any programming language. By providing data types, you specify what values are legal and tell the user what kinds of operations are allowed on those values. The system thus provides you with built-in checks against errors.

The data types that you have worked with until now were mostly `int`, `bool`, `char`, and `double`. Even though these data types are sufficient to solve just about any problem, situations occur when these data types are not adequate to solve a particular problem. C++ provides a mechanism for users to create their own data types, which greatly enhances the flexibility of the programming language.

In this section, you will learn how to create your own simple data types, known as the enumeration types. In ensuing chapters, you will learn more advanced techniques to create complex data types.

To define an **enumeration type**, you need the following items:

- A name for the data type
- A set of values for the data type
- A set of operations on the values

C++ lets you define a new simple data type wherein you specify its name and values, but not the operations. Preventing users from creating their own operations helps to avoid potential system failures.

The values that you specify for the data type must be identifiers.

The syntax for enumeration type is:

```
enum typeName {value1, value2, ...};
```

in which **value1**, **value2**, ... are identifiers called **enumerators**. In C++, **enum** is a reserved word.

By listing all of the values between the braces, you also specify an ordering between the values. That is, **value1** < **value2** < **value3** <.... Thus, the enumeration type is an ordered set of values. Moreover, the default value assigned to these enumerators starts at 0. That is, the default value assigned to **value1** is 0, the default value assigned to **value2** is 1, and so on. (You can assign different values—other than the default values—for the enumerators when you define the enumeration type.) Also notice that the enumerators **value1**, **value2**, ... are *not* variables.

### EXAMPLE 8-1

The statement:

```
enum colors {BROWN, BLUE, RED, GREEN, YELLOW};
```

defines a new data type called **colors**, and the values belonging to this data type are BROWN, BLUE, RED, GREEN, and YELLOW.

8

### EXAMPLE 8-2

The statement:

```
enum standing {FRESHMAN, SOPHOMORE, JUNIOR, SENIOR};
```

defines **standing** to be an enumeration type. The values belonging to **standing** are FRESHMAN, SOPHOMORE, JUNIOR, and SENIOR.

### EXAMPLE 8-3

Consider the following statements:

```
enum grades {'A', 'B', 'C', 'D', 'F'}; //illegal enumeration type
enum places {1ST, 2ND, 3RD, 4TH}; //illegal enumeration type
```

These are illegal enumeration types because none of the values is an identifier. The following, however, are legal enumeration types:

```
enum grades {A, B, C, D, F};
enum places {FIRST, SECOND, THIRD, FOURTH};
```

---

If a value has already been used in one enumeration type, it cannot be used by any other enumeration type in the same block. The same rules apply to enumeration types declared outside of any blocks. Example 8-4 illustrates this concept.

#### EXAMPLE 8-4

Consider the following statements:

```
enum mathStudent {JOHN, BILL, CINDY, LISA, RON};
enum compStudent {SUSAN, CATHY, JOHN, WILLIAM}; //illegal
```

Suppose that these statements are in the same program in the same block. The second enumeration type, `compStudent`, is not allowed because the value `JOHN` was used in the previous enumeration type `mathStudent`.

---

## Declaring Variables

Once a data type is defined, you can declare variables of that type. The syntax for declaring variables of an `enum` type is the same as before:

```
dataType identifier, identifier,...;
```

The statement:

```
enum sports {BASKETBALL, FOOTBALL, HOCKEY, BASEBALL, SOCCER,
 VOLLEYBALL};
```

defines an enumeration type called `sports`. The statement:

```
sports popularSport, mySport;
```

declares `popularSport` and `mySport` to be variables of type `sports`.

## Assignment

Once a variable is declared, you can store values in it. Assuming the previous declaration, the statement:

```
popularSport = FOOTBALL;
```

stores `FOOTBALL` in `popularSport`. The statement:

```
mySport = popularSport;
```

copies the value of `popularSport` into `mySport`.

## Operations on Enumeration Types

No arithmetic operations are allowed on the enumeration type. So the following statements are illegal:

```
mySport = popularSport + 2; //illegal
popularSport = FOOTBALL + SOCCER; //illegal
popularSport = popularSport * 2; //illegal
```

Also, the increment and decrement operations are not allowed on enumeration types. So the following statements are illegal:

```
popularSport++; //illegal
popularSport--; //illegal
```

Suppose you want to increment the value of `popularSport` by 1. You can use the cast operator as follows:

```
popularSport = static_cast<sports>(popularSport + 1);
```

When the type name is used, the compiler assumes that the user understands what he or she is doing. Thus, the preceding statement is compiled, and during execution, it advances the value of `popularSport` to the next value in the list. Consider the following statements:

```
popularSport = FOOTBALL;
popularSport = static_cast<sports>(popularSport + 1);
```

After the second statement, the value of `popularSport` is `HOCKEY`. Similarly, the statements:

```
popularSport = FOOTBALL;
popularSport = static_cast<sports>(popularSport - 1);
```

result in storing `BASKETBALL` in `popularSport`.

## Relational Operators

Because an enumeration is an ordered set of values, the relational operators can be used with the enumeration type. Once again, suppose you have the enumeration type `sports` and the variables `popularSport` and `mySport` as defined earlier. Then:

```
FOOTBALL <= SOCCER is true
HOCKEY > BASKETBALL is true
BASEBALL < FOOTBALL is false
```

Suppose that:

```
popularSport = SOCCER;
mySport = VOLLEYBALL;
```

Then:

```
popularSport < mySport is true
```

## ENUMERATION TYPES AND LOOPS

Recall that the enumeration type is an integral type and that, using the cast operator (that is, type name), you can increment, decrement, and compare the values of the enumeration type. Therefore, you can use these enumeration types in loops. Suppose `mySport` is a variable as declared earlier. Consider the following `for` loop:

```
for (mySport = BASKETBALL; mySport <= SOCCER;
 mySport = static_cast<sports>(mySport + 1))
{
 .
 .
 .
}
```

This `for` loop has five iterations.

Using enumeration types in loops increases the readability of the program.

## Input/Output of Enumeration Types

Because input and output are defined only for built-in data types such as `int`, `char`, `double`, and so on, the enumeration type can be neither input nor output (directly). However, you can input and output enumeration indirectly. Example 8-5 illustrates this concept.

### EXAMPLE 8-5

Suppose you have the following statements:

```
enum courses {ALGEBRA, BASIC, PASCAL, CPP, PHILOSOPHY, ANALYSIS,
 CHEMISTRY, HISTORY};
courses registered;
```

The first statement defines an enumeration type, `courses`; the second declares a variable `registered` of type `courses`. You can read (that is, input) the enumeration type with the help of the `char` data type. Note that you can distinguish between some of the values in the enumeration type `courses` just by reading the first character and others by reading the first two characters. For example, you can distinguish between `ALGEBRA` and `BASIC` just by reading the first character; you can distinguish between `ALGEBRA` and `ANALYSIS` by reading the first two characters. To read these values from, say, the keyboard, you read two characters and then use a selection structure to assign the value to the variable `registered`. Thus, you need to declare two variables of type `char`.

```
char ch1, ch2;
cin >> ch1 >> ch2; //Read two characters
```

The following `switch` statement assigns the appropriate value to the variable `registered`:

```
switch (ch1)
{
case 'a':
case 'A':
 if (ch2 == 'l' || ch2 == 'L')
 registered = ALGEBRA;
 else
 registered = ANALYSIS;
 break;
case 'b':
case 'B':
 registered = BASIC;
 break;
case 'c':
case 'C':
 if (ch2 == 'h' || ch2 == 'H')
 registered = CHEMISTRY;
 else
 registered = CPP;
 break;
case 'h':
case 'H':
 registered = HISTORY;
 break;
case 'p':
case 'P':
 if (ch2 == 'a' || ch2 == 'A')
 registered = PASCAL;
 else
 registered = PHILOSOPHY;
 break;
default:
 cout << "Illegal input." << endl;
}
```

Similarly, you can output the enumeration type indirectly:

```
switch (registered)
{
case ALGEBRA:
 cout << "Algebra";
 break;
case ANALYSIS:
 cout << "Analysis";
 break;
case BASIC:
 cout << "Basic";
 break;
```

```

case CHEMISTRY:
 cout << "Chemistry";
 break;
case CPP:
 cout << "CPP";
 break;
case HISTORY:
 cout << "History";
 break;
case PASCAL:
 cout << "Pascal";
 break;
case PHILOSOPHY:
 cout << "Philosophy";
}

```

**NOTE**

If you try to output the value of an enumerator directly, the computer will output the value assigned to the enumerator. For example, suppose that `registered = ALGEBRA;`. The following statement will output the value 0 because the (default) value assigned to `ALGEBRA` is 0:

```
cout << registered << endl;
```

Similarly, the following statement will output 4:

```
cout << PHILOSOPHY << endl;
```

## Functions and Enumeration Types

You can pass the enumeration type as a parameter to functions just like any other simple data type—that is, by either value or reference. Also, just like any other simple data type, a function can return a value of the enumeration type. Using this facility, you can use functions to input and output enumeration types.

The following function inputs data from the keyboard and returns a value of the enumeration type. Assume that the enumeration type `courses` is defined as before:

```

courses readCourses()
{
 courses registered;
 char ch1, ch2;

 cout << "Enter the first two letters of the course: "
 << endl;
 cin >> ch1 >> ch2;

 switch (ch1)
 {
 case 'a':

```

```

case 'A':
 if (ch2 == 'l' || ch2 == 'L')
 registered = ALGEBRA;
 else
 registered = ANALYSIS;
 break;
case 'b':
case 'B':
 registered = BASIC;
 break;
case 'c':
case 'C':
 if (ch2 == 'h' || ch2 == 'H')
 registered = CHEMISTRY;
 else
 registered = CPP;
 break;
case 'h':
case 'H':
 registered = HISTORY;
 break;
case 'p':
case 'P':
 if (ch2 == 'a' || ch2 == 'A')
 registered = PASCAL;
 else
 registered = PHILOSOPHY;
 break;
default:
 cout << "Illegal input." << endl;
}
return registered;
} //end readCourse

```

The following function outputs an enumeration type value:

```

void printEnum(courses registered)
{
 switch (registered)
 {
 case ALGEBRA:
 cout << "Algebra";
 break;
 case ANALYSIS:
 cout << "Analysis";
 break;
 case BASIC:
 cout << "Basic";
 break;
 case CHEMISTRY:
 cout << "Chemistry";
 break;
 }
}

```

```

 case CPP:
 cout << "CPP";
 break;
 case HISTORY:
 cout << "History";
 break;
 case PASCAL:
 cout << "Pascal";
 break;
 case PHILOSOPHY:
 cout << "Philosophy";
 } //end switch
} //end printEnum

```

## Declaring Variables When Defining the Enumeration Type

In previous sections, you first defined an enumeration type and then declared variables of that type. C++ allows you to combine these two steps into one. That is, you can declare variables of an enumeration type when you define an enumeration type. For example, the statement:

```
enum grades {A, B, C, D, F} courseGrade;
```

defines an enumeration type, `grades`, and declares a variable `courseGrade` of type `grades`.

Similarly, the statement:

```
enum coins {PENNY, NICKEL, DIME, HALFDOLLAR, DOLLAR} change, usCoins;
```

defines an enumeration type, `coins`, and declares two variables, `change` and `usCoins`, of type `coins`.

## Anonymous Data Types

A data type wherein you directly specify values in the variable declaration with no type name is called an **anonymous type**. The following statement creates an anonymous type:

```
enum {BASKETBALL, FOOTBALL, BASEBALL, HOCKEY} mySport;
```

This statement specifies the values and declares a variable `mySport`, but no name is given to the data type.

Creating an anonymous type, however, has drawbacks. First, because there is no name for the type, you cannot pass an anonymous type as a parameter to a function, and a function cannot return an anonymous type value. Second, values used in one anonymous type can be used in another anonymous type, but variables of those types are treated differently. Consider the following statements:

```

enum {ENGLISH, FRENCH, SPANISH, GERMAN, RUSSIAN} languages;
enum {ENGLISH, FRENCH, SPANISH, GERMAN, RUSSIAN} foreignLanguages;

```

Even though the variables `languages` and `foreignLanguages` have the same values, the compiler treats them as variables of different types. The following statement is, therefore, illegal:

```
languages = foreignLanguages; //illegal
```

Even though these facilities are available, use them with care. To avoid confusion, first define an enumeration type and then declare the variables.

We now describe the `typedef` statement in C++.

## typedef Statement

In C++, you can create synonyms or aliases to a previously defined data type by using the `typedef` statement. The general syntax of the `typedef` statement is:

```
typedef existingTypeName newTypeName;
```

In C++, `typedef` is a reserved word. Note that the `typedef` statement does not create any new data type; it creates only an alias to an existing data type.

### EXAMPLE 8-6

The statement:

```
typedef int integer;
```

creates an alias, `integer`, for the data type `int`. Similarly, the statement:

```
typedef double real;
```

creates an alias, `real`, for the data type `double`. The statement:

```
typedef double decimal;
```

creates an alias, `decimal`, for the data type `double`.

Using the `typedef` statement, you can create your own Boolean data type, as shown in Example 8-7.

### EXAMPLE 8-7

From Chapter 4, recall that logical (Boolean) expressions in C++ evaluate to 1 or 0, which are, in fact, `int` values. As a logical value, 1 represents `true` and 0 represents `false`. Consider the following statements:

```
typedef int Boolean; //Line 1
const Boolean TRUE = 1; //Line 2
const Boolean FALSE = 0; //Line 3
Boolean flag; //Line 4
```

The statement in Line 1 creates an alias, `Boolean`, for the data type `int`. The statements in Lines 2 and 3 declare the named constants `TRUE` and `FALSE` and initialize them to 1 and 0, respectively. The statement in Line 4 declares `flag` to be a variable of type `Boolean`. Because `flag` is a variable of type `Boolean`, the following statement is legal:

```
flag = TRUE;
```

---

## PROGRAMMING EXAMPLE: The Game of Rock, Paper, and Scissors

Children often play the game of rock, paper, and scissors. This game has two players, each of whom chooses one of the three objects: rock, paper, or scissors. If player 1 chooses rock and player 2 chooses paper, player 2 wins the game because paper covers the rock. The game is played according to the following rules:

- If both players choose the same object, this play is a tie.
- If one player chooses rock and the other chooses scissors, the player choosing the rock wins this play because the rock breaks the scissors.
- If one player chooses rock and the other chooses paper, the player choosing the paper wins this play because the paper covers the rock.
- If one player chooses scissors and the other chooses paper, the player choosing the scissors wins this play because the scissors cut the paper.

Write an interactive program that allows two people to play this game.

**Input** This program has two types of input:

- The users' responses when asked to play the game.
- The players' choices.

**Output** The players' choices and the winner of each play. After the game is over, the total number of plays and the number of times that each player won should be output as well.

**PROBLEM  
ANALYSIS  
AND  
ALGORITHM  
DESIGN**

Two players play this game. Players enter their choices via the keyboard. Each player enters `R` or `r` for Rock, `P` or `p` for Paper, or `S` or `s` for Scissors. While the first player enters a choice, the second player looks elsewhere. Once both entries are in, if the entries are valid, the program outputs the players' choices and declares the winner of the play. The game continues until one of the players decides to quit

the game. After the game ends, the program outputs the total number of plays and the number of times that each player won. This discussion translates into the following algorithm:

1. Provide a brief explanation of the game and how it is played.
2. Ask the users if they want to play the game.
3. Get plays for both players.
4. If the plays are valid, output the plays and the winner.
5. Update the total game count and winner count.
6. Repeat Steps 2 through 5 while the users agree to play the game.
7. Output the number of plays and times that each player won.

We will use the enumeration type to describe the objects.

```
enum objectType {ROCK, PAPER, SCISSORS};
```

Variables  
(Function main)

It is clear that you need the following variables in the function main:

```
int gameCount; //variable to store the number of
 //games played
int winCount1; //variable to store the number of games
 //won by player 1
int winCount2; //variable to store the number of games
 //won by player 2
int gamewinner;
char response; //variable to get the user's response to
 //play the game
char selection1;
char selection2;
objectType play1; //player1's selection
objectType play2; //player2's selection
```

This program is divided into the following functions, which the ensuing sections describe in detail.

- **displayRules:** This function displays some brief information about the game and its rules.
- **validSelection:** This function checks whether a player's selection is valid. The only valid selections are R, r, P, p, S, and s.
- **retrievePlay:** Because enumeration types cannot be read directly, this function converts the entered choice (R, r, P, p, S, or s) and returns the appropriate object type.
- **gameResult:** This function outputs the players' choices and the winner of the game.

- **convertEnum:** This function is called by the function `gameResult` to output the enumeration type values.
- **winningObject:** This function determines and returns the winning object.
- **displayResults:** After the game is over, this function displays the final results.

**Function** `displayRules` This function has no parameters. It consists only of output statements to explain the game and rules of play. Essentially, this function's definition is:

```
void displayRules()
{
 cout << " Welcome to the game of Rock, Paper, "
 << "and Scissors." << endl;
 cout << " This is a game for two players. For each "
 << "game, each" << endl;
 cout << " player selects one of the objects Rock, "
 << "Paper, or Scissors." << endl;
 cout << " The rules for winning the game are: " << endl;
 cout << "1. If both players select the same object, it "
 << "is a tie." << endl;
 cout << "2. Rock breaks Scissors: So player who selects "
 << "Rock wins." << endl;
 cout << "3. Paper covers Rock: So player who selects "
 << "Paper wins." << endl;
 cout << "4. Scissors cuts Paper: So player who selects "
 << "Scissors wins." << endl << endl;
 cout << "Enter R or r to select Rock, P or p to select "
 << "Paper, and S or s to select Scissors." << endl;
}
```

**Function** `validSelection` This function checks whether a player's selection is valid.

```
if selection is 'R' or 'r' or 'S' or 's' or 'P' or 'p', then
 it is a valid selection;
otherwise the selection is invalid.
```

Let's use a `switch` statement to check for the valid selection. The definition of this function is:

```
bool validSelection(char selection)
{
 switch (selection)
 {
 case 'R':
 case 'r':
 case 'P':
 case 'p':
 case 'S':
```

```

 case 's':
 return true;
 default:
 return false;
 }
}

```

**Function retrievePlay** Because the enumeration type cannot be read directly, this function converts the entered choice (R, r, P, p, S, or s) and returns the appropriate object type. This function thus has one parameter, of type `char`. It is a value-returning function, and it returns a value of type `objectType`. In pseudocode, the algorithm of this function is:

```

if selection is 'R' or 'r'
 return ROCK;

if selection is 'P' or 'p'
 return PAPER;

if selection is 'S' or 's'
 return SCISSORS;

```

The definition of the function `retrievePlay` is:

```

objectType retrievePlay(char selection)
{
 objectType object;

 switch (selection)
 {
 case 'R':
 case 'r':
 object = ROCK;
 break;
 case 'P':
 case 'p':
 object = PAPER;
 break;
 case 'S':
 case 's':
 object = SCISSORS;
 }

 return object;
}

```

**Function gameResult** This function decides whether a game is a tie or which player is the winner. It outputs the players' selections and the winner of the game. Clearly, this function has three parameters: player 1's choice, player 2's choice, and a parameter to return the winner. In pseudocode, this function is:

- a. **if** `player1` and `player2` have the same selection, then this is a tie game.

```

b. else
{
 1. Determine the winning object. (Call function winningObject)
 2. Output each player's choice.
 3. Determine the winning player.
 4. Return the winning player via a reference parameter to the
 function main so that the function main can update the
 winning player's win count.
}

```

The definition of this function is:

```

void gameResult(objectType play1, objectType play2,
 int& winner)
{
 objectType winnerObject;

 if (play1 == play2)
 {
 winner = 0;
 cout << "Both players selected ";
 convertEnum(play1);
 cout << ". This game is a tie." << endl;
 }
 else
 {
 winnerObject = winningObject(play1, play2);

 //Output each player's choice
 cout << "Player 1 selected ";
 convertEnum(play1);
 cout << " and player 2 selected ";
 convertEnum(play2);
 cout << ". ";

 //Decide the winner
 if (play1 == winnerObject)
 winner = 1;
 else if (play2 == winnerObject)
 winner = 2;

 //Output the winner
 cout << "Player " << winner << " wins this game."
 << endl;
 }
}

```

**Function** Because enumeration types cannot be output directly, let's write the function `convertEnum` to output objects of the `enum` type `objectType`. This function has one parameter, of type `objectType`. It outputs the string that corresponds to the `objectType`. In pseudocode, this function is:

```

if object is ROCK
 output "Rock"

if object is PAPER
 output "Paper"

if object is SCISSORS
 output "Scissors"

```

The definition of the function `convertNum` is:

```

void convertEnum(objectType object)
{
 switch (object)
 {
 case ROCK:
 cout << "Rock";
 break;
 case PAPER:
 cout << "Paper";
 break;
 case SCISSORS:
 cout << "Scissors";
 }
}

```

### Function `winningObject`

To decide the winner of the game, you look at the players' selections and then at the rules of the game. For example, if one player chooses `ROCK` and another chooses `PAPER`, the player who chose `PAPER` wins. In other words, the winning object is `PAPER`. The function `winningObject`, given two objects, decides and returns the winning object. Clearly, this function has two parameters of type `objectType`, and the value returned by this function is also of type `objectType`. The definition of this function is:

```

objectType winningObject(objectType play1, objectType play2)
{
 if ((play1 == ROCK && play2 == SCISSORS)
 || (play2 == ROCK && play1 == SCISSORS))
 return ROCK;
 else if ((play1 == ROCK && play2 == PAPER)
 || (play2 == ROCK && play1 == PAPER))
 return PAPER;
 else
 return SCISSORS;
}

```

### Function `displayResults`

After the game is over, this function outputs the final results—that is, the total number of plays and the number of plays won by each player. The total number of plays is stored in the variable `gameCount`, the number of plays won by player 1 is stored in the variable `winCount1`, and the number of plays won by player 2 is stored

in the variable `winCount2`. This function has three parameters corresponding to these three variables. Essentially, the definition of this function is:

```
void displayResults(int gCount, int wCount1, int wCount2)
{
 cout << "The total number of plays: " << gCount
 << endl;
 cout << "The number of plays won by player 1: "
 << wCount1 << endl;
 cout << "The number of plays won by player 2: "
 << wCount2 << endl;
}
```

We are now ready to write the algorithm for the function `main`.

#### MAIN ALGORITHM

1. Declare the variables.
2. Initialize the variables.
3. Display the rules.
4. Prompt the users to play the game.
5. Get the users' responses to play the game.
6. **while** (response is yes)
  - {
  - a. Prompt player 1 to make a selection.
  - b. Get the play for player 1.
  - c. Prompt player 2 to make a selection.
  - d. Get the play for player 2.
  - e. If both plays are legal:
    - {
    - i. Increment the total game count.
    - ii. Declare the winner of the game.
    - iii. Increment the winner's game win count by 1.
    - }
  - f. Prompt the users to determine whether they want to play again.
  - g. Get the players' responses.
  - }
7. Output the game results.

**PROGRAM LISTING**

```

//*****
// Author: D.S. Malik
//
// Program: Rock, Paper, and Scissors
// This program plays the game of rock, paper, and scissors.
//*****

#include <iostream>

using namespace std;

enum objectType {ROCK, PAPER, SCISSORS};

 //Function prototypes
void displayRules();
objectType retrievePlay(char selection);
bool validSelection(char selection);
void convertEnum(objectType object);
objectType winningObject(objectType play1, objectType play2);
void gameResult(objectType play1, objectType play2, int& winner);
void displayResults(int gCount, int wCount1, int wCount2);

int main()
{
 //Step 1
 int gameCount; //variable to store the number of
 //games played
 int winCount1; //variable to store the number of games
 //won by player 1
 int winCount2; //variable to store the number of games
 //won by player 2
 int gamewinner;
 char response; //variable to get the user's response to
 //play the game
 char selection1;
 char selection2;
 objectType play1; //player1's selection
 objectType play2; //player2's selection

 //Initialize variables; Step 2
 gameCount = 0;
 winCount1 = 0;
 winCount2 = 0;

 displayRules(); //Step 3

 cout << "Enter Y/y to play the game: "; //Step 4
 cin >> response; //Step 5
 cout << endl;

```

```

while (response == 'Y' || response == 'y') //Step 6
{
 cout << "Player 1 enter your choice: "; //Step 6a
 cin >> selection1; //Step 6b
 cout << endl;

 cout << "Player 2 enter your choice: "; //Step 6c
 cin >> selection2; //Step 6d
 cout << endl;

 //Step 6e
 if (validSelection(selection1)
 && validSelection(selection2))
 {
 play1 = retrievePlay(selection1);
 play2 = retrievePlay(selection2);
 gameCount++; //Step 6e.i
 gameResult(play1, play2, gamewinner); //Step 6e.ii

 if (gamewinner == 1) //Step 6e.iii
 winCount1++;
 else if (gamewinner == 2)
 winCount2++;
 } //end if

 cout << "Enter Y/y to play the game: "; //Step 6f
 cin >> response; //Step 6g
 cout << endl;
} //end while

displayResults(gameCount, winCount1,
 winCount2); //Step 7

return 0;
} //end main

//Place the definitions of the functions displayRules,
//validSelection, retrievePlay, convertEnum, winningObject,
//gameResult, and displayResults as described previously here.

```

## Namespaces

In July 1998, ANSI/ISO Standard C++ was officially approved. Most recent compilers are also compatible with ANSI/ISO Standard C++. (To be absolutely sure, check your compiler's documentation.) The two standards, Standard C++ and ANSI/ISO Standard C++, are virtually the same. The ANSI/ISO Standard C++ language has some features that are not available in Standard C++, which the remainder of this chapter addresses.

In subsequent chapters, unless specified otherwise, the C++ syntax applies to both standards. First, we discuss the **namespace** mechanism of the ANSI/ISO Standard C++, which was introduced in Chapter 2.

When a header file, such as **iostream**, is included in a program, the global identifiers in the header file also become the global identifiers in the program. Therefore, if a global identifier in a program has the same name as one of the global identifiers in the header file, the compiler generates a syntax error (such as “identifier redefined”). The same problem can occur if a program uses third-party libraries. To overcome this problem, third-party vendors begin their global identifiers with a special symbol. In Chapter 2, you learned that because compiler vendors begin their global identifier names with an underscore (**\_**), to avoid linking errors, you should not begin identifier names in your program with an underscore (**\_**).

ANSI/ISO Standard C++ tries to solve this problem of overlapping global identifier names with the **namespace** mechanism.

The general syntax of the statement **namespace** is:

```
namespace namespace_name
{
 members
}
```

where **members** is usually named constants, variable declarations, functions, or another **namespace**. Note that **namespace\_name** is a C++ identifier.

In C++, **namespace** is a reserved word.

### EXAMPLE 8-8

The statement:

```
namespace globalType
{
 const int N = 10;
 const double RATE = 7.50;
 int count = 0;
 void printResult();
}
```

defines **globalType** to be a **namespace** with four members: named constants **N** and **RATE**, the variable **count**, and the function **printResult**.

The scope of a **namespace** member is local to the **namespace**. You can usually access a **namespace** member outside the **namespace** in one of two ways, as described below.

The general syntax for accessing a `namespace` member is:

```
namespace_name::identifier
```

Recall that in C++, `::` is called the scope resolution operator.

To access the member `RATE` of the `namespace` `globalType`, the following statement is required:

```
globalType::RATE
```

To access the member `printResult` (which is a function), the following statement is required:

```
globalType::printResult();
```

Thus, to access a member of a `namespace`, you use the `namespace_name`, followed by the scope resolution operator, followed by the member name.

To simplify the accessing of a `namespace` member, ANSI/ISO Standard C++ provides the use of the statement `using`. The syntax to use the statement `using` is as follows:

- a. To simplify the accessing of all `namespace` members:

```
using namespace namespace_name;
```

- b. To simplify the accessing of a specific `namespace` member:

```
using namespace_name::identifier;
```

For example, the `using` statement:

```
using namespace globalType;
```

simplifies the accessing of all members of the `namespace` `globalType`. The statement:

```
using globalType::RATE;
```

simplifies the accessing of the member `RATE` of the `namespace` `globalType`.

In C++, `using` is a reserved word.

You typically put the `using` statement after the `namespace` declaration. For the `namespace` `globalType`, for example, you usually write the code as follows:

```
namespace globalType
{
 const int N = 10;
 const double RATE = 7.50;
 int count = 0;
 void printResult();
}
using namespace globalType;
```

After the `using` statement, to access a `namespace` member, you do not have to put the `namespace_name` and the scope resolution operator before the `namespace` member. However, if a `namespace` member and a global identifier in a program have the same name, to access this `namespace` member in the program, the `namespace_name` and the scope resolution operator must precede the `namespace` member. Similarly, if a `namespace` member and an identifier in a block have the same name, to access this `namespace` member in the block, the `namespace_name` and the scope resolution operator must precede the `namespace` member.

Examples 8-9 through 8-12 help clarify the use of the `namespace` mechanism.

### EXAMPLE 8-9

Consider the following C++ code:

```
#include <iostream>

using namespace std;

.
.
.
int main()
{
 .
 .
 .
}
.
.
.
```

In this example, you can refer to the global identifiers of the header file `iostream`, such as `cin`, `cout`, and `endl`, without using the prefix `std::` before the identifier name. The obvious restriction is that the block (or function) that refers to the global identifier (of the header file `iostream`) must not contain any identifier with the same name as this global identifier.

### EXAMPLE 8-10

Consider the following C++ code:

```
#include <cmath>

int main()
{
 double x = 15.3;
 double y;
```

```

 y = std::pow(x, 2);
 .
 .
 .
}

```

This example accesses the function `pow` of the header file `cmath`.

---

### EXAMPLE 8-11

Consider the following C++ code:

```

#include <iostream>
.
.
.
int main()
{
 using namespace std;
 .
 .
 .
}
.
.
.

```

In this example, the function `main` can refer to the global identifiers of the header file `iostream` without using the prefix `std::` before the identifier name. The `using` statement appears inside the function `main`. Therefore, other functions (if any) should use the prefix `std::` before the name of the global identifier of the header file `iostream` unless the function has a similar `using` statement.

---

### EXAMPLE 8-12

Consider the following C++ code:

```

#include <iostream>

using namespace std; //Line 1

int t; //Line 2
double u; //Line 3

namespace expN
{
 int x; //Line 4
 char t; //Line 5
}

```

```

 double u; //Line 6
 void printResult(); //Line 7
}

using namespace expN;

int main()
{
 int one; //Line 8
 double t; //Line 9
 double three; //Line 10

 .
 .
 .
}

void expN::printResult() //Definition of the function printResult
{
 .
 .
 .
}

```

In this C++ program:

1. To refer to the variable `t` in Line 2 in `main`, use the *scope resolution operator*, which is `::` (that is, refer to `t` as `::t`), because the function `main` has a variable named `t` (declared in Line 9). For example, to copy the value of `x` into `t`, you can use the statement `::t = x;`.
2. To refer to the member `t` (declared in Line 5) of the `namespace expN` in `main`, use the prefix `expN::` with `t` (that is, refer to `t` as `expN::t`) because there is a global variable named `t` (declared in Line 2) and a variable named `t` in `main`.
3. To refer to the member `u` (declared in Line 6) of the `namespace expN` in `main`, use the prefix `expN::` with `u` (that is, refer to `u` as `expN::u`) because there is a global variable named `u` (declared in Line 3).
4. You can reference the member `x` (declared in Line 4) of the `namespace expN` in `main` as either `x` or `expN::x` because there is no global identifier named `x` and the function `main` does not contain any identifier named `x`.
5. The definition of a function that is a member of a `namespace`, such as `printResult`, is usually written outside the `namespace` as in the preceding program. To write the definition of the function `printResult`, the name of the function in the function heading can be either `printResult` or `expN::printResult` (because no other global identifier is named `printResult`).

**NOTE**

The identifiers in the system-provided header files, such as `iostream`, `cmath`, and `iomanip`, are defined in the `namespace std`. For this reason, to simplify the accessing of identifiers from these header files, we have been using the following statement in the programs that we write:

```
using namespace std;
```

## string Type

In Chapter 2, you were introduced to the data type `string`. Recall that prior to the ANSI/ISO C++ language standard, the Standard C++ library did not provide a `string` data type. Compiler vendors often supplied their own programmer-defined `string` type, and the syntax and semantics of string operations often varied from vendor to vendor.

The data type `string` is a programmer-defined type and is not part of the C++ language; the C++ standard library supplies it. Before using the data type `string`, the program must include the header file `string`, as follows:

```
#include <string>
```

Recall that in C++, a string is a sequence of zero or more characters, and strings are enclosed in double quotation marks.

The statement:

```
string name = "William Jacob";
```

declares `name` to be a `string` variable and initializes `name` to "William Jacob". The position of the first character, `W`, in `name` is 0; the position of the second character, `i`, is 1; and so on. That is, the position of the first character in a `string` variable starts with 0, not 1.

The variable `name` can store (just about) any size string.

Chapter 3 discussed I/O operations on the `string` type; Chapter 4 explained relational operations on the `string` type. We recommend that you revisit Chapters 3 and 4 and review the I/O and relational operations on the `string` type.

Other operators, such as the binary operator `+` (to allow the string concatenation operation) and the array index (subscript) operator `[]`, have also been defined for the data type `string`. Let's see how these operators work on the `string` data type.

Suppose you have the following declarations:

```
string str1, str2, str3;
```

The statement:

```
str1 = "Hello There";
```

stores the string "Hello There" in `str1`. The statement:

```
str2 = str1;
```

copies the value of `str1` into `str2`.

If `str1 = "Sunny"`, the statement:

```
str2 = str1 + " Day";
```

stores the string "Sunny Day" into `str2`.

Suppose `str1 = "Hello"` and `str2 = "There"`. The statement:

```
str3 = str1 + " " + str2;
```

stores "Hello There" into `str3`. This statement is equivalent to the statement:

```
str3 = str1 + ' ' + str2;
```

Also, the statement:

```
str1 = str1 + " Mickey";
```

updates the value of `str1` by appending the string " Mickey" to its old value. Therefore, the new value of `str1` is "Hello Mickey".

#### NOTE

For the operator `+` to work with the `string` data type, one of the operands of `+` must be a `string` variable. For example, the following statements will not work:

```
str1 = "Hello " + "there!"; //illegal
str2 = "Sunny Day" + '!'; //illegal
```

If `str1 = "Hello there"`, the statement:

```
str1[6] = 'T';
```

replaces the character `t` with the character `T`. Recall that the position of the first character in a `string` variable is 0. Therefore, because `t` is the seventh character in `str1`, its position is 6.

In C++, `[]` is called the **array subscript operator**.

As illustrated previously, using the array subscript operator together with the position of the character, you can access an individual character within a string.

**EXAMPLE 8-13**

The following program shows the effect of the preceding statements.

```
//Example string operations

#include <iostream>
#include <string>

using namespace std;

int main()
{
 string name = "William Jacob"; //Line 1
 string str1, str2, str3, str4; //Line 2

 cout << "Line 3: Name = " << name << endl; //Line 3

 str1 = "Hello There"; //Line 4
 cout << "Line 5: str1 = " << str1 << endl; //Line 5

 str2 = str1; //Line 6
 cout << "Line 7: str2 = " << str2 << endl; //Line 7

 str1 = "Sunny"; //Line 8
 str2 = str1 + " Day"; //Line 9
 cout << "Line 10: str2 = " << str2 << endl; //Line 10

 str1 = "Hello"; //Line 11
 str2 = "There"; //Line 12
 str3 = str1 + " " + str2; //Line 13
 cout << "Line 14: str3 = " << str3 << endl; //Line 14

 str3 = str1 + ' ' + str2; //Line 15
 cout << "Line 16: str3 = " << str3 << endl; //Line 16

 str1 = str1 + " Mickey"; //Line 17
 cout << "Line 18: str1 = " << str1 << endl; //Line 18

 str1 = "Hello there"; //Line 19
 cout << "Line 20: str1[6] = " << str1[6] //Line 20
 << endl;

 str1[6] = 'T'; //Line 21
 cout << "Line 22: str1 = " << str1 << endl; //Line 22

 //String input operations
 cout << "Line 23: Enter a string with "
 << "no blanks: "; //Line 23
 cin >> str1; //Line 24

 char ch; //Line 25
```

```
cin.get(ch); //Read the newline character; Line 26
cout << endl; //Line 27

cout << "Line 28: The string you entered = "
 << str1 << endl; //Line 28

cout << "Line 29: Enter a sentence: "; //Line 29
getline(cin, str2); //Line 30
cout << endl; //Line 31

cout << "Line 32: The sentence is: " << str2
 << endl; //Line 32

return 0;
}
```

**Sample Run:** In the following sample run, the user input is shaded.

```
Line 3: Name = William Jacob
Line 5: str1 = Hello There
Line 7: str2 = Hello There
Line 10: str2 = Sunny Day
Line 14: str3 = Hello There
Line 16: str3 = Hello There
Line 18: str1 = Hello Mickey
Line 20: str1[6] = t
Line 22: str1 = Hello There
Line 23: Enter a string with no blanks: Programming

Line 28: The string you entered = Programming
Line 29: Enter a sentence: Testing string operations

Line 32: The sentence is: Testing string operations
```

The preceding output is self-explanatory, and its unraveling is left as an exercise for you.

### Additional string Operations

The data type `string` has a data type, `string::size_type`, and a named constant, `string::npos`, defined as follows:

|                                |                                                                                                                    |
|--------------------------------|--------------------------------------------------------------------------------------------------------------------|
| <code>string::size_type</code> | An unsigned integer (data) type                                                                                    |
| <code>string::npos</code>      | The maximum value of the (data) type <code>string::size_type</code> , a number such as 4294967295 on many machines |

The data type `string` contains several other functions for string manipulation. The following table describes some these functions. In this table, we assume that `strVar` is a `string` variable and `str` is a string variable, a string constant, or a character array. (Arrays are discussed in Chapter 9.)

TABLE 8-1 Some `string` functions

| Expression                                      | Effect                                                                                                                                                                                                                                    |
|-------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>strVar.at(index)</code>                   | Returns the element at the position specified by <code>index</code> .                                                                                                                                                                     |
| <code>strVar[index]</code>                      | Returns the element at the position specified by <code>index</code> .                                                                                                                                                                     |
| <code>strVar.append(n, ch)</code>               | Appends <code>n</code> copies of <code>ch</code> to <code>strVar</code> , in which <code>ch</code> is a <code>char</code> variable or a <code>char</code> constant.                                                                       |
| <code>strVar.append(str)</code>                 | Appends <code>str</code> to <code>strVar</code> .                                                                                                                                                                                         |
| <code>strVar.clear()</code>                     | Deletes all the characters in <code>strVar</code> .                                                                                                                                                                                       |
| <code>strVar.compare(str)</code>                | Compares <code>strVar</code> and <code>str</code> . (This operation is discussed in Chapter 4.)                                                                                                                                           |
| <code>strVar.empty()</code>                     | Returns <code>true</code> if <code>strVar</code> is empty; otherwise, it returns <code>false</code> .                                                                                                                                     |
| <code>strVar.erase()</code>                     | Deletes all the characters in <code>strVar</code> .                                                                                                                                                                                       |
| <code>strVar.erase(pos, n)</code>               | Deletes <code>n</code> characters from <code>strVar</code> starting at position <code>pos</code> .                                                                                                                                        |
| <code>strVar.find(str)</code>                   | Returns the index of the first occurrence of <code>str</code> in <code>strVar</code> . If <code>str</code> is not found, the special value <code>string::npos</code> is returned.                                                         |
| <code>strVar.find(str, pos)</code>              | Returns the index of the first occurrence at or after <code>pos</code> where <code>str</code> is found in <code>strVar</code> .                                                                                                           |
| <code>strVar.find_first_of(str, pos)</code>     | Returns the index of the first occurrence of any character of <code>strVar</code> in <code>str</code> . The search starts at <code>pos</code> .                                                                                           |
| <code>strVar.find_first_not_of(str, pos)</code> | Returns the index of the first occurrence of any character of <code>str</code> not in <code>strVar</code> . The search starts at <code>pos</code> .                                                                                       |
| <code>strVar.insert(pos, n, ch);</code>         | Inserts <code>n</code> occurrences of the character <code>ch</code> at index <code>pos</code> into <code>strVar</code> ; <code>pos</code> and <code>n</code> are of type <code>string::size_type</code> ; <code>ch</code> is a character. |
| <code>strVar.insert(pos, str);</code>           | Inserts all the characters of <code>str</code> at index <code>pos</code> into <code>strVar</code> .                                                                                                                                       |
| <code>strVar.length()</code>                    | Returns a value of type <code>string::size_type</code> giving the number of characters <code>strVar</code> .                                                                                                                              |

|                                           |                                                                                                                                                                                                                                                                                         |
|-------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>strVar.replace(pos, n, str);</code> | Starting at index <code>pos</code> , replaces the next <code>n</code> characters of <code>strVar</code> with all the characters of <code>str</code> . If <code>n &gt; length</code> of <code>strVar</code> , then all the characters until the end of <code>strVar</code> are replaced. |
| <code>strVar.substr(pos, len)</code>      | Returns a string that is a substring of <code>strVar</code> starting at <code>pos</code> . The length of the substring is at most <code>len</code> characters. If <code>len</code> is too large, it means "to the end" of the string in <code>strVar</code> .                           |
| <code>strVar.size()</code>                | Returns a value of type <code>string::size_type</code> giving the number of characters <code>strVar</code> .                                                                                                                                                                            |
| <code>strVar.swap(str1);</code>           | Swaps the contents of <code>strVar</code> and <code>str1</code> . <code>str1</code> is a <code>string</code> variable.                                                                                                                                                                  |

Next, we show how some of these functions work.

**EXAMPLE 8-14 (clear, empty, erase, length, AND size FUNCTIONS)**

Consider the following statements:

```
string firstName = "Elizabeth";
string name = firstName + " Jones";
string str1 = "It is sunny.";
string str2 = "";
string str3 = "computer science";
string str4 = "C++ programming.";
string str5 = firstName + " is taking " + str4;

string::size_type len;
```

Next, we show the effect of `clear`, `empty`, `erase`, `length`, and `size` functions.

| Statement                                                    | Effect                              |
|--------------------------------------------------------------|-------------------------------------|
| <code>str3.clear();</code>                                   | <code>str3 = "";</code>             |
| <code>str1.empty();</code>                                   | Returns false;                      |
| <code>str2.empty();</code>                                   | Returns true;                       |
| <code>str4.erase(11, 4);</code>                              | <code>str4 = "C++ program.";</code> |
| <code>cout &lt;&lt; firstName.length() &lt;&lt; endl;</code> | Outputs 9                           |
| <code>cout &lt;&lt; name.length() &lt;&lt; endl;</code>      | Outputs 15                          |
| <code>cout &lt;&lt; str1.length() &lt;&lt; endl;</code>      | Outputs 12                          |
| <code>cout &lt;&lt; str5.size() &lt;&lt; endl;</code>        | Outputs 36                          |
| <code>len = name.length();</code>                            | The value of <code>len</code> is 15 |

The following program illustrates the use of the `length` function.

```
//Example: clear, empty, erase, length, and size functions

#include <iostream>
#include <string>

using namespace std;

int main()
{
 string firstName = "Elizabeth"; //Line 1
 string name = firstName + " Jones"; //Line 2
 string str1 = "It is sunny."; //Line 3
 string str2 = ""; //Line 4
 string str3 = "computer science"; //Line 5
 string str4 = "C++ programming."; //Line 6
 string str5 = firstName + " is taking " + str4; //Line 7

 string::size_type len; //Line 8

 cout << "Line 9: str3: " << str3 << endl; //Line 9
 str3.clear(); //Line 10
 cout << "Line 11: After clear, str3: " << str3 //Line 11
 << endl;

 cout << "Line 12: str1.empty(): " << str1.empty() //Line 12
 << endl;
 cout << "Line 13: str2.empty(): " << str2.empty() //Line 13
 << endl;

 cout << "Line 14: str4: " << str4 << endl; //Line 14
 str4.erase(11, 4); //Line 15
 cout << "Line 16: After erase(11, 4), str4: " //Line 16
 << str4 << endl;

 cout << "Line 17: Length of \"" << firstName << "\" = " //Line 17
 << static_cast<unsigned int>(firstName.length())
 << endl;
 cout << "Line 18: Length of \"" << name << "\" = " //Line 18
 << static_cast<unsigned int>(name.length())
 << endl;
 cout << "Line 19: Length of \"" << str1 << "\" = " //Line 19
 << static_cast<unsigned int>(str1.length())
 << endl;
 cout << "Line 20: Size of \"" << str5 << "\" = " //Line 20
 << static_cast<unsigned int>(str5.size())
 << endl;

 len = name.length(); //Line 21
 cout << "Line 22: len = " //Line 22
 << static_cast<unsigned int>(len) << endl;

 return 0; //Line 23
}
```

**Sample Run:**

```

Line 9: str3: computer science
Line 11: After clear, str3:
Line 12: str1.empty(): 0
Line 13: str2.empty(): 1
Line 14: str4: C++ programming.
Line 16: After erase(11, 4), str4: C++ program.
Line 17: Length of "Elizabeth" = 9
Line 18: Length of "Elizabeth Jones" = 15
Line 19: Length of "It is sunny." = 12
Line 20: Size of "Elizabeth is taking C++ programming." = 36
Line 22: len = 15

```

The output of this program is self-explanatory. The details are left as an exercise for you. Notice that this program uses the static cast operator to output the value returned by the function `length`. This is because the function `length` returns a value of the type `string::size_type`. Without the cast operator, some compilers might give the following warning message:

```
conversion from 'size_t' to 'unsigned int', possible loss of data
```

---

**EXAMPLE 8-15 (find FUNCTION)****8**

Suppose `str1` and `str2` are of type `string`. The following are valid calls to the function `find`:

```

str1.find(str2)
str1.find("the")
str1.find('a')
str1.find(str2 + "xyz")
str1.find(str2 + 'b')

```

Consider the following statements:

```

string sentence = "Outside it is cloudy and warm.";
string str = "cloudy";

```

```
string::size_type position;
```

Next, we show the effect of the `find` function.

| Statement                                                       | Effect                                         |
|-----------------------------------------------------------------|------------------------------------------------|
| <code>cout &lt;&lt; sentence.find("is") &lt;&lt; endl;</code>   | Outputs 11                                     |
| <code>cout &lt;&lt; sentence.find('s') &lt;&lt; endl;</code>    | Outputs 3                                      |
| <code>cout &lt;&lt; sentence.find(str) &lt;&lt; endl;</code>    | Outputs 14                                     |
| <code>cout &lt;&lt; sentence.find("the") &lt;&lt; endl;</code>  | Outputs the value of <code>string::npos</code> |
| <code>cout &lt;&lt; sentence.find('i', 6) &lt;&lt; endl;</code> | Outputs 8                                      |
| <code>position = sentence.find("warm");</code>                  | Assigns 25 to <code>position</code>            |

Note that the search is case sensitive. Therefore, the position of o (lowercase o) in the string `sentence` is 16.

The following program evaluates the previous statements.

```
//Example: find function
```

```
#include <iostream>
#include <string>

using namespace std;

int main()
{
 string sentence = "Outside it is cloudy and warm."; //Line 1
 string str = "cloudy"; //Line 2

 string::size_type position; //Line 3

 cout << "Line 4: sentence = \"" << sentence
 << "\"" << endl; //Line 4

 cout << "Line 5: The position of \"is\" in sentence = "
 << static_cast<unsigned int> (sentence.find("is"))
 << endl; //Line 5

 cout << "Line 6: The position of 's' in sentence = "
 << static_cast<unsigned int> (sentence.find('s'))
 << endl; //Line 6

 cout << "Line 7: The position of \"" << str
 << "\" in sentence = "
 << static_cast<unsigned int> (sentence.find(str))
 << endl; //Line 7

 cout << "Line 8: The position of \"the\" in sentence = "
 << static_cast<unsigned int> (sentence.find("the"))
 << endl; //Line 8

 cout << "Line 9: The first occurrence of 'i' in "
 << "sentence \n after position 6 = "
 << static_cast<unsigned int> (sentence.find('i', 6))
 << endl; //Line 9

 position = sentence.find("warm"); //Line 10
 cout << "Line 11: " << "Position = "
 << position << endl; //Line 11

 return 0; //Line 12
}
```

**Sample Run:**

```

Line 4: sentence = "Outside it is cloudy and warm."
Line 5: The position of "is" in sentence = 11
Line 6: The position of 's' in sentence = 3
Line 7: The position of "cloudy" in sentence = 14
Line 8: The position of "the" in sentence = 4294967295
Line 9: The first occurrence of 'i' in sentence
 after position 6 = 8
Line 11: Position = 25

```

The output of this program is self-explanatory. The details are left as an exercise for you. Notice that this program uses the static cast operator to output the value returned by the function `find`. This is because the function `find` returns a value of the type `string::size_type`. Without the cast operator, some compilers might give the following warning message:

```
conversion from 'size_t' to 'unsigned int', possible loss of data
```

### EXAMPLE 8-16 (insert AND replace FUNCTIONS)

Suppose that you have the following statements:

```

string firstString = "Cloudy and warm.";
string secondString = "Hello there";
string thirdString = "Henry is taking programming I.";
string str1 = " very ";
string str2 = "Lisa";

```

Next, we show the effect of `insert` and `replace` functions.

| Statement                                     | Effect                                                     |
|-----------------------------------------------|------------------------------------------------------------|
| <code>firstString.insert(10, str1);</code>    | <code>firstString = "Cloudy and very warm."</code>         |
| <code>secondString.insert(11, 5, '!');</code> | <code>secondString = "Hello there!!!!!"</code>             |
| <code>thirdString.replace(0, 5, str2);</code> | <code>thirdString = "Lisa is taking programming I."</code> |

The following program evaluates the previous statements.

```
//Example: insert and replace functions
```

```

#include <iostream>
#include <string>

using namespace std;

```

```

int main()
{
 string firstString = "Cloudy and warm."; //Line 1
 string secondString = "Hello there"; //Line 2
 string thirdString = "Henry is taking programming I."; //Line 3
 string str1 = " very "; //Line 4
 string str2 = "Lisa"; //Line 5

 cout << "Line 6: firstString = " << firstString
 << endl; //Line 6
 firstString.insert(10, str1); //Line 7
 cout << "Line 8: After insert; firstString = "
 << firstString << endl; //Line 8

 cout << "Line 9: secondString = " << secondString
 << endl; //Line 9
 secondString.insert(11, 5, '!'); //Line 10
 cout << "Line 11: After insert; secondString = "
 << secondString << endl; //Line 11

 cout << "Line 12: thirdString = " << thirdString
 << endl; //Line 12
 thirdString.replace(0, 5, str2); //Line 13
 cout << "Line 14: After replace, thirdString = "
 << thirdString << endl; //Line 14

 return 0; //Line 15
}

```

**Sample Run:**

```

Line 6: firstString = Cloudy and warm.
Line 8: After insert; firstString = Cloudy and very warm.
Line 9: secondString = Hello there
Line 11: After insert; secondString = Hello there!!!!
Line 12: thirdString = Henry is taking programming I.
Line 14: After replace, thirdString = Lisa is taking programming I.

```

The output of this program is self-explanatory. The details are left as an exercise for you.

---

**EXAMPLE 8-17 (substr FUNCTION)**

Consider the following statements:

```

string sentence;
string str;

sentence = "It is cloudy and warm.";

```

Next, we show the effect of the `substr` function.

| Statement                                                         | Effect                          |
|-------------------------------------------------------------------|---------------------------------|
| <code>cout &lt;&lt; sentence.substr(0, 5) &lt;&lt; endl;</code>   | Outputs: It is                  |
| <code>cout &lt;&lt; sentence.substr(6, 6) &lt;&lt; endl;</code>   | Outputs: cloudy                 |
| <code>cout &lt;&lt; sentence.substr(6, 16) &lt;&lt; endl;</code>  | Outputs: cloudy and warm.       |
| <code>cout &lt;&lt; sentence.substr(17, 10) &lt;&lt; endl;</code> | Outputs: warm.                  |
| <code>cout &lt;&lt; sentence.substr(3, 6) &lt;&lt; endl;</code>   | Outputs: is clo                 |
| <code>str = sentence.substr(0, 8);</code>                         | <code>str = "It is cl"</code>   |
| <code>str = sentence.substr(2, 10);</code>                        | <code>str = " is cloudy"</code> |

The following program illustrates how to use the `string` function `substr`.

**//Example: substr function**

```
#include <iostream>
#include <string>

using namespace std;

int main()
{
 string sentence; //Line 1
 string str; //Line 2

 sentence = "It is cloudy and warm."; //Line 3

 cout << "Line 4: substr(0, 5) in \""
 << sentence << "\" = \""
 << sentence.substr(0, 5) << "\"\" << endl; //Line 4

 cout << "Line 5: substr(6, 6) in \""
 << sentence << "\" = \""
 << sentence.substr(6, 6) << "\"\" << endl; //Line 5

 cout << "Line 6: substr(6, 16) in \""
 << sentence << "\" = " << endl
 << " \"" << sentence.substr(6, 16)
 << "\"\" << endl; //Line 6

 cout << "Line 7: substr(17, 10) in \""
 << sentence << "\" = \""
 << sentence.substr(17, 10) << "\"\" << endl; //Line 7

 cout << "Line 8: substr(3, 6) in \""
 << sentence << "\" = \""
 << sentence.substr(3, 6) << "\"\" << endl; //Line 8
```

```

 str = sentence.substr(0, 8); //Line 9
 cout << "Line 10: " << "str = \"" << str //Line 10
 << "\"" << endl;

 str = sentence.substr(2, 10); //Line 11
 cout << "Line 12: " << "str = \"" << str //Line 12
 << "\"" << endl;

 return 0;
}

```

**Sample Run:**

```

Line 4: substr(0, 5) in "It is cloudy and warm." = "It is"
Line 5: substr(6, 6) in "It is cloudy and warm." = "cloudy"
Line 6: substr(6, 16) in "It is cloudy and warm." =
 "cloudy and warm."
Line 7: substr(17, 10) in "It is cloudy and warm." = "warm."
Line 8: substr(3, 6) in "It is cloudy and warm." = "is clo"
Line 10: str = "It is cl"
Line 12: str = " is cloudy"

```

The output of this program is self-explanatory. The details are left as an exercise for you.

**EXAMPLE 8-18 (swap FUNCTION)**

The `swap` function is used to swap—that is, interchange—the contents of two string variables.

Suppose you have the following statements:

```

string str1 = "Warm";
string str2 = "Cold";

```

After the following statement executes, the value of `str1` is "Cold" and the value of `str2` is "Warm".

```

str1.swap(str2);

```

**NOTE**

Additional `string` functions are described in Appendix F (Header File `string`).

## PROGRAMMING EXAMPLE: Pig Latin Strings

In this programming example, we write a program that prompts the user to input a string and then outputs the string in the pig Latin form. The rules for converting a string into pig Latin form are as follows:

1. If the string begins with a vowel, add the string **"-way"** at the end of the string. For example, the pig Latin form of the string **"eye"** is **"eye-way"**.
2. If the string does not begin with a vowel, first add **"-"** at the end of the string. Then rotate the string one character at a time; that is, move the first character of the string to the end of the string until the first character of the string becomes a vowel. Then add the string **"ay"** at the end. For example, the pig Latin form of the string **"There"** is **"ere-Thay"**.
3. Strings such as **"by"** contain no vowels. In cases like this, the letter **y** can be considered a vowel. So, for this program, the vowels are **a, e, i, o, u, y, A, E, I, O, U, and Y**. Therefore, the pig Latin form of **"by"** is **"y-bay"**.
4. Strings such as **"1234"** contain no vowels. The pig Latin form of the string **"1234"** is **"1234-way"**. That is, the pig Latin form of a string that has no vowels in it is the string followed by the string **"-way"**.

**Input** Input to the program is a string.

**Output** Output of the program is the string in the pig Latin form.

### PROBLEM ANALYSIS AND ALGORITHM DESIGN

Suppose that **str** denotes a string. To convert **str** into pig Latin, check the first character, **str[0]**, of **str**. If **str[0]** is a vowel, add **"-way"** at the end of **str**—that is, **str = str + "-way"**.

Suppose that the first character of **str**, **str[0]**, is not a vowel. First, add **"-"** at the end of the string. Then, remove the first character of **str** from **str** and put it at the end of **str**. Now, the second character of **str** becomes the first character of **str**. This process of checking the first character of **str** and moving it to the end of **str** if the first character of **str** is not a vowel is repeated until either the first character of **str** is a vowel or all the characters of **str** are processed, in which case **str** does not contain any vowels.

In this program, we write a function **isVowel** to determine whether a character is a vowel, a function **rotate** to move the first character of **str** to the end of **str**, and

a function `pigLatinString` to find the pig Latin form of `str`. The previous discussion translates into the following algorithm:

1. Get `str`.
2. Find the pig Latin form of `str` by using the function `pigLatinString`.
3. Output the pig Latin form of `str`.

Before writing the main algorithm, each of these functions is described in detail.

**Function** This function takes a character as a parameter and returns `true` if the character is `isVowel` a vowel and `false` otherwise. The definition of the function `isVowel` is:

```
bool isVowel(char ch)
{
 switch (ch)
 {
 case 'A':
 case 'E':
 case 'I':
 case 'O':
 case 'U':
 case 'Y':
 case 'a':
 case 'e':
 case 'i':
 case 'o':
 case 'u':
 case 'y':
 return true;
 default:
 return false;
 }
}
```

**Function** This function takes a string as a parameter, removes the first character of the string, `rotate` and places it at the end of the string. This is done by extracting the substring, starting at position 1 (which is the second character) until the end of the string, and then adding the first character of the string. The new string is returned as the value of this function. Essentially, the definition of the function `rotate` is:

```
string rotate(string pStr)
{
 string::size_type len = pStr.length();

 string rStr;

 rStr = pStr.substr(1, len - 1) + pStr[0];

 return rStr;
}
```

**Function** `pigLatinString` This function takes a string, `pStr`, as a parameter and returns the pig Latin form of `pStr`. Suppose `pStr` denotes the string to be converted to its pig Latin form. There are three possible cases: `pStr[0]` is a vowel, `pStr` contains a vowel and the first character of `pStr` is not a vowel, or `pStr` contains no vowels. Suppose that `pStr[0]` is not a vowel. Move the first character of `pStr` to the end of `pStr`. This process is repeated until either the first character of `pStr` has become a vowel or all the characters of `pStr` are checked, in which case `pStr` does not contain any vowels. This discussion translates into the following algorithm:

1. If `pStr[0]` is a vowel, add `"-way"` at the end of `pStr`.
2. Suppose `pStr[0]` is not a vowel.
3. Move the first character of `pStr` to the end of `pStr`. The second character of `pStr` becomes the first character of `pStr`. Now `pStr` may or may not contain a vowel. We use a `bool` variable, `foundVowel`, which is set to `true` if `pStr` contains a vowel and `false` otherwise.
  - a. Suppose that `len` denotes the length of `pStr`.
  - b. Initialize `foundVowel` to `false`.
  - c. If `pStr[0]` is not a vowel, move `pStr[0]` to the end of `pStr` by calling the function `rotate`.
  - d. Repeat Step b until either the first character of `pStr` becomes a vowel or all the characters of `pStr` have been checked.
4. Convert `pStr` into the pig Latin form.
5. Return `pStr`.

The definition of the function `pigLatinString` is:

```
string pigLatinString(string pStr)
{
 string::size_type len;

 bool foundVowel;

 string::size_type counter;

 if (isVowel(pStr[0])) //Step 1
 pStr = pStr + "-way";
 else //Step 2
 {
 pStr = pStr + '-';
 pStr = rotate(pStr); //Step 3

 len = pStr.length(); //Step 3.a
 foundVowel = false; //Step 3.b
 }
}
```

```

 for (counter = 1; counter < len - 1;
 counter++) //Step 3.d
 {
 if (isVowel(pStr[0]))
 {
 foundVowel = true;
 break;
 }
 else //Step 3.c
 pStr = rotate(pStr);

 if (!foundVowel) //Step 4
 pStr = pStr.substr(1, len) + "-way";
 else
 pStr = pStr + "ay";
 }

 return pStr; //Step 5
}

```

#### MAIN ALGORITHM

1. Get the string.
2. Call the function `pigLatinString` to find the pig Latin form of the string.
3. Output the pig Latin form of the string.

#### PROGRAM LISTING

```

//*****
// Author: D.S. Malik
//
// Program: Pig Latin Strings
// This program reads a string and outputs the pig Latin form
// of the string.
//*****

#include <iostream>
#include <string>

using namespace std;

bool isVowel(char ch);
string rotate(string pStr);
string pigLatinString(string pStr);

int main()
{
 string str;

 cout << "Enter a string: ";
 cin >> str;
}

```

```

 cout << endl;

 cout << "The pig Latin form of " << str << " is: "
 << pigLatinString(str) << endl;

 return 0;
 }

 //Place the definitions of the functions isVowel, rotate, and
 //pigLatinString and as described previously here.

```

**Sample Runs:** In these sample runs, the user input is shaded.

**Sample Run 1:**

Enter a string: **eye**

The pig Latin form of eye is: eye-way

**Sample Run 2:**

Enter a string: **There**

The pig Latin form of There is: ere-Thay

**Sample Run 3:**

Enter a string: **why**

The pig Latin form of why is: y-whay

**Sample Run 4:**

Enter a string: **123456**

The pig Latin form of 123456 is: 123456-way

## QUICK REVIEW

1. An enumeration type is a set of ordered values.
2. C++'s reserved word `enum` is used to create an enumeration type.
3. The syntax of `enum` is:  

```
enum typeName {value1, value2,...};
```

in which `value1`, `value2`,... are identifiers, and `value1 < value2 < ...`
4. No arithmetic operations are allowed on the enumeration type.

5. Relational operators can be used with `enum` values.
6. Enumeration type values cannot be input or output directly.
7. Enumeration types can be passed as parameters to functions either by value or by reference.
8. A function can return a value of the enumeration type.
9. An anonymous type is one in which a variable's values are specified without any type name.
10. C++'s reserved word `typedef` is used to create synonyms or aliases to previously defined data types.
11. Anonymous types cannot be passed as parameters to functions.
12. The `namespace` mechanism is a feature of ANSI/ISO Standard C++.
13. A `namespace` member is usually a named constant, variable, function, or another `namespace`.
14. The scope of a `namespace` member is local to the `namespace`.
15. One way to access a `namespace` member outside the `namespace` is to precede the `namespace` member name with the `namespace` name and scope resolution operator.
16. In C++, `namespace` is a reserved word.
17. To use the `namespace` mechanism, the program must include the ANSI/ISO Standard C++ header files—that is, the header files without the extension `h`.
18. The `using` statement simplifies the accessing of `namespace` members.
19. In C++, `using` is a reserved word.
20. The keyword `namespace` must appear in the `using` statement.
21. When accessing a `namespace` member without the `using` statement, the `namespace` name and the scope resolution operator must precede the name of the `namespace` member.
22. To use an identifier declared in the standard header files without the `namespace` name, after including all the necessary header files, the following statement must appear in the program:  
`using namespace std;`
23. A string is a sequence of zero or more characters.
24. Strings in C++ are enclosed in double quotation marks.
25. To use the type `string`, the program must include the header file `string`. The other header files used in the program should be ANSI/ISO Standard C++ style header files.
26. The assignment operator can be used with the `string` type.
27. The operator `+` can be used to concatenate two values of the type `string`. For the operator `+` to work with the `string` data type, one of the operands of `+` must be a `string` variable.

28. Relational operators, discussed in Chapter 4, can be applied to the `string` type.
29. In a string, the position of the first character is 0, the position of the second character is 1, and so on.
30. The length of a string is the number of characters in the string.
31. In C++, `[]` is called the array subscript operator.
32. To access an individual character within a string, use the array subscript operator together with the position of the character.
33. The `string` type contains functions such as `at`, `append`, `clear`, `compare`, `erase`, `find`, `find_first_of`, `find_first_not_of`, `insert`, `length`, `replace`, `size`, `substr`, and `swap` to manipulate strings. These functions are describe in Table 8-1.

## EXERCISES

1. Mark the following statements as true or false.
  - a. The following is a valid C++ enumeration type:  

```
enum romanNumerals {I, V, X, L, C, D, M};
```
  - b. Given the declaration:  

```
enum cars {FORD, GM, TOYOTA, HONDA};
```

```
cars domesticCars = FORD;
```

the statement:  

```
domesticCars = domesticCars + 1;
```

 sets the value of `domesticCars` to `GM`.
  - c. A function can return a value of an enumeration type.
  - d. You can input the value of an enumeration type directly from a standard input device.
  - e. The only arithmetic operations allowed on the enumeration type are increment and decrement.
  - f. The values in the domain of an enumeration type are called enumerators.
  - g. The following are legal C++ statements in the same block of a C++ program:  

```
enum mathStudent {BILL, JOHN, LISA, RON, CINDY, SHELLY};
```

```
enum historyStudent {AMANDA, BOB, JACK, TOM, SUSAN};
```
  - h. The following statement creates an anonymous type:  

```
enum {A, B, C, D, F} studentGrade;
```
  - i. You can use the `namespace` mechanism with header files with the extension `h`.

- j. Suppose `str = "ABCD";`. After the statement `str[1] = 'a';`, the value of `str` is `"aBCD"`.
- k. Suppose `str = "abcd"`. After the statement:  
`str = str + "ABCD";`  
 the value of `str` is `"ABCD"`.
- 2. Write C++ statements that do the following:
  - a. Define an `enum` type, `bookType`, with the values `MATH`, `CSC`, `ENGLISH`, `HISTORY`, `PHYSICS`, and `PHILOSOPHY`.
  - b. Declare a variable `book` of type `bookType`.
  - c. Assign `MATH` to the variable `book`.
  - d. Advance `book` to the next value in the list.
  - e. Output the value of the variable `book`.
- 3. Given:

```
enum currencyType {DOLLAR, POUND, FRANK, LIRA, MARK};
currencyType currency;
```

which of the following statements are valid?

- a. `currency = DOLLAR;`
- b. `cin >> currency;`
- c. `currency = static_cast<currencyType>(currency + 1);`
- d. `for (currency = DOLLAR; currency <= MARK; currency++)`  
`cout << " ";`
- 4. Given:

```
enum cropType {WHEAT, CORN, RYE, BARLEY, OATS};
cropType crop;
```

circle the correct answer.

- a. `static_cast<int>(WHEAT)` is 0  
 (i) true (ii) false
- b. `static_cast<cropType>(static_cast<int>(WHEAT) - 1)` is `WHEAT`  
 (i) true (ii) false
- c. `RYE > WHEAT`  
 (i) true (ii) false
- d. `for (crop = wheat; crop <= oats; ++crop)`  
`cout << " ";`  
`cout << endl;`

outputs: \*\*\*\*\*

- (i) true (ii) false

5. What is wrong with the following program?

```
#include <iostream> //Line 1

int main() //Line 2
{
 cout << "Hello World! " << endl; //Line 3

 return 0; //Line 4
}
```

6. What is wrong with the following program?

```
#include <iostream.h> //Line 1

using namespace std; //Line 2

int main() //Line 3
{
 int x = 0; //Line 4
 cout << "x = " << x << endl; //Line 5
 return 0; //Line 6
}
```

7. What is wrong with the following program?

```
#include <iostream> //Line 1

namespace aaa //Line 2
{
 const int X = 0; //Line 3
 double y; //Line 4
}

using namespace std; //Line 5

int main() //Line 6
{
 y = 34.50; //Line 7
 cout << "X = " << X << ", y = " << y //Line 8
 << endl; //Line 9
 return 0;
}
```

8. What is wrong with the following program?

```
#include <iostream> //Line 1
#include <cmath> //Line 2

using std; //Line 3

int main() //Line 4
{
 return 0; //Line 5
}
```

9. Consider the following C++ code:

```
string str1;
string str2;
char ch;

cin >> str1;
str2 = str1;
cin >> ch;
str2[0] = ch;
cout << str1 << " -> " << str2 << endl;
```

Answer the following questions.

- a. What is the output if the input is `Hello J`?
  - b. What is the output if the input is `Bingo R`?
  - c. What is the output if the input is `Sunny B`?
10. Suppose that you have the following statements:

```
string str1, str2;

cin >> str1 >> str2;

if (str1 == str2)
 cout << str1 + '!' << endl;
else if (str1 > str2)
 cout << str1 + " > " + str2 << endl;
else
 cout << str1 + " < " + str2 << endl;
```

Answer the following questions.

- a. What is the output if the input is `diamond diamond`?
  - b. What is the output if the input is `diamond gold`?
  - c. What is the output if the input is `silver gold`?
11. What is the output of the following program?

```
#include <iostream>
#include <string>

using namespace std;

int main()
{
 string str1 = "Amusement Park";
 string str2 = "Going to";
 string str3 = "the";
 string str;

 cout << str2 + ' ' + str3 + ' ' + str1 << endl;
 cout << str1.length() << endl;
 cout << str1.find('P') << endl;
 cout << str1.substr(1, 5) << endl;
```

```

 str = "ABCDEFGHIJK";
 cout << str << endl;
 cout << str.length() << endl;

 str[0] = 'a';
 str[2] = 'd';

 cout << str << endl;

 return 0;
}

```

12. Consider the following statement:

```
string str = "Now is the time for the party!";
```

What is the output of the following statements? (Assume that all parts are independent of each other.)

- a. `cout << str.size() << endl;`
- b. `cout << str.substr(7, 8) << endl;`
- c. `string::size_type ind = str.find('f');`  
`string s = str.substr(ind + 4, 9);`  
`cout << s << endl;`
- d. `cout << str.insert(11, "best ") << endl;`
- e. `str.erase(16, 14);`  
`str.insert(16, "to study for the exam?");`  
`cout << str << endl;`

## PROGRAMMING EXERCISES

1.
  - a. Define an enumeration type, `triangleType`, that has the values `scalene`, `isosceles`, `equilateral`, and `noTriangle`.
  - b. Write a function, `triangleShape`, that takes as parameters three numbers, each of which represents the length of a side of the triangle. The function should return the shape of the triangle. (*Note:* In a triangle, the sum of the lengths of any two sides is greater than the length of the third side.)
  - c. Write a program that prompts the user to input the length of the sides of a triangle and outputs the shape of the triangle.
2. Redo Programming Exercise 14 of Chapter 4 (cell phone company) so that all of the named constants are defined in a `namespace`.
3. The Programming Example: Pig Latin Strings converts a string into the pig Latin form, but it processes only one word. Rewrite the program so that it can be used to process a text of an unspecified length. If a word ends with a punctuation mark, in the pig Latin form, put the punctuation at the end of the string. For example, the pig Latin form of **Hello!** is **ello-Hay!**. Assume that the text contains the following punctuation marks: `,` (comma),

- (period), ? (question mark), ; (semicolon), and : (colon). (Your program may store the output in a file.)
- 4. Write a program that prompts the user to input a string. The program then uses the function `substr` to remove all the vowels from the string. For example, if `str = "There"`, then after removing all the vowels, `str = "Thr"`. After removing all the vowels, output the string. Your program must contain a function to remove all the vowels and a function to determine whether a character is a vowel.
- 5. Write a program that can be used to calculate the federal tax. The tax is calculated as follows: For single people, the standard exemption is \$4,000; for married people, the standard exemption is \$7,000. A person can also put up to 6% of his or her gross income in a pension plan. The tax rates are as follows: If the taxable income is:
  - Between \$0 and \$15,000, the tax rate is 15%.
  - Between \$15,001 and \$40,000, the tax is \$2,250 plus 25% of the taxable income over \$15,000.
  - Over \$40,000, the tax is \$8,460 plus 35% of the taxable income over \$40,000.

Prompt the user to enter the following information:

- Marital status
- If the marital status is “married,” ask for the number of children under the age of 14
- Gross salary (If the marital status is “married” and both spouses have income, enter the combined salary.)
- Percentage of gross income contributed to a pension fund

Your program must consist of at least the following functions:

- a. Function `getData`: This function asks the user to enter the relevant data.
- b. Function `taxAmount`: This function computes and returns the tax owed.

To calculate the taxable income, subtract the sum of the standard exemption, the amount contributed to a pension plan, and the personal exemption, which is \$1,500 per person. (Note that if a married couple has two children under the age of 14, then the personal exemption is  $\$1,500 \star 4 = \$6,000$ .)

- 6. A set of integers  $a$ ,  $b$ , and  $c$  is called a **Pythagorean triple** if  $a^2 + b^2 = c^2$ . For example, the integers 3, 4, and 5 form a Pythagorean triple because  $3^2 + 4^2 = 5^2$ . To find Pythagorean triples, use the following formula. Let  $m$  and  $n$  be integers. If  $a = m^2 - n^2$ ,  $b = 2mn$ , and  $c = m^2 + n^2$ , then  $a$ ,  $b$ , and  $c$  are a Pythagorean triple. Write a program that prompts the user to enter values for  $m$  and  $n$  and then outputs the Pythagorean triple corresponding to  $m$  and  $n$ .
- 7. (**Fraction calculator**) Write a program that lets the user perform arithmetic operations on fractions. Fractions are of the form  $a/b$ , in which  $a$  and  $b$  are integers and  $b \neq 0$ . Your program must be menu driven, allowing the user to

select the operation (+, -, \*, or /) and input the numerator and denominator of each fraction. Furthermore, your program must consist of at least the following functions:

- a. Function **menu**: This function informs the user about the program's purpose, explains how to enter data, and allows the user to select the operation.
- b. Function **addFractions**: This function takes as input four integers representing the numerators and denominators of two fractions, adds the fractions, and returns the numerator and denominator of the result. (Notice that this function has a total of six parameters.)
- c. Function **subtractFractions**: This function takes as input four integers representing the numerators and denominators of two fractions, subtracts the fractions, and returns the numerator and denominator of the result. (Notice that this function has a total of six parameters.)
- d. Function **multiplyFractions**: This function takes as input four integers representing the numerators and denominators of two fractions, multiplies the fractions, and returns the numerators and denominators of the result. (Notice that this function has a total of six parameters.)
- e. Function **divideFractions**: This function takes as input four integers representing the numerators and denominators of two fractions, divides the fractions, and returns the numerator and denominator of the result. (Notice that this function has a total of six parameters.)

Some sample outputs are:

$$\begin{array}{l} 3 / 4 + 2 / 5 = 23 / 20 \\ 2 / 3 * 3 / 5 = 6 / 15 \end{array}$$

Your answer need not be in the lowest terms.

8. Write a program that reads in a line consisting of a student's name, Social Security number, user ID, and password. The program outputs the string in which all the digits of the Social Security number, and all the characters in the password are replaced by **x**. (The Social Security number is in the form 000-00-0000, and the user ID and the password do not contain any spaces.) Your program should not use the operator `[]` to access a string element. Use the appropriate functions described in Table 8-1.
9. You are given a file consisting of students' names in the following form: **lastName, firstName middleName**. (Note that a student may not have a middle name.) Write a program that converts each name to the following form: **firstName middleName lastName**. Your program must read each student's entire name in a variable and must consist of a function that takes as input a string, consists of a student's name, and returns the string consisting of the altered name. Use the string function **find** to find the index of **,**; the function **length** to find the length of the string; and the function **substr** to extract the **firstName**, **middleName**, and **lastName**.

*This page intentionally left blank*



# 9 CHAPTER

## ARRAYS AND STRINGS

IN THIS CHAPTER, YOU WILL:

- Learn about arrays
- Explore how to declare and manipulate data into arrays
- Learn about “array index out of bounds”
- Become familiar with the restrictions on array processing
- Discover how to pass an array as a parameter to a function
- Learn how to search an array
- Learn about C-strings
- Examine the use of string functions to process C-strings
- Discover how to input data into—and output data from—a C-string
- Learn about parallel arrays
- Discover how to manipulate data in a two-dimensional array
- Learn about multidimensional arrays

In previous chapters, you worked with simple data types. In Chapter 2, you learned that C++ data types fall into three categories. One of these categories is the structured data type. This chapter and the next few chapters focus on structured data types.

Recall that a data type is called **simple** if variables of that type can store only one value at a time. In contrast, in a **structured data type**, each data item is a collection of other data items. Simple data types are building blocks of structured data types. The first structured data type that we will discuss is an array. In Chapters 11 and 12, we will discuss other structured data types.

Before formally defining an array, let us consider the following problem. We want to write a C++ program that reads five numbers, finds their sum, and prints the numbers in reverse order.

In Chapter 5, you learned how to read numbers, print them, and find the sum. The difference here is that we want to print the numbers in reverse order. This means we cannot print the first four numbers until we have printed the fifth, and so on. To do this, we need to store all of the numbers before we start printing them in reverse order. From what we have learned so far, the following program accomplishes this task.

```
//Program to read five numbers, find their sum, and print the
//numbers in reverse order.
```

```
#include <iostream>

using namespace std;

int main()
{
 int item0, item1, item2, item3, item4;
 int sum;

 cout << "Enter five integers: ";
 cin >> item0 >> item1 >> item2 >> item3 >> item4;
 cout << endl;

 sum = item0 + item1 + item2 + item3 + item4;

 cout << "The sum of the numbers = " << sum << endl;
 cout << "The numbers in the reverse order are: ";
 cout << item4 << " " << item3 << " " << item2 << " "
 << item1 << " " << item0 << endl;

 return 0;
}
```

This program works fine. However, if you need to read 100 (or more) numbers and print them in reverse order, you would have to declare 100 variables and write many `cin` and `cout` statements. Thus, for large amounts of data, this type of program is not desirable.

Note the following in the previous program:

1. Five variables must be declared because the numbers are to be printed in reverse order.
2. All variables are of type `int`—that is, of the same data type.
3. The way in which these variables are declared indicates that the variables to store these numbers all have the same name—except the last character, which is a number.

Statement 1 tells you that you have to declare five variables. Statement 3 tells you that it would be convenient if you could somehow put the last character, which is a number, into a counter variable and use one `for` loop to count from 0 to 4 for reading and another `for` loop to count from 4 to 0 for printing. Finally, because all variables are of the same type, you should be able to specify how many variables must be declared—and their data type—with a simpler statement than the one we used earlier.

The data structure that lets you do all of these things in C++ is called an array.

## Arrays

An **array** is a collection of a fixed number of components all of the same data type. A **one-dimensional array** is an array in which the components are arranged in a list form. This section discusses only one-dimensional arrays. Arrays of two dimensions or more are discussed later in this chapter.

The general form for declaring a one-dimensional array is:

```
dataType arrayName[intExp];
```

in which `intExp` is any constant expression that evaluates to a positive integer. Also, `intExp` specifies the number of components in the array.

### EXAMPLE 9-1

The statement:

```
int num[5];
```

declares an array `num` of five components. Each component is of type `int`. The components are `num[0]`, `num[1]`, `num[2]`, `num[3]`, and `num[4]`. Figure 9-1 illustrates the array `num`.




FIGURE 9-1 Array num

**NOTE** To save space, we also draw an array, as shown in Figure 9-2(a) or 9-2(b).




FIGURE 9-2 Array num

## Accessing Array Components

The general form (syntax) used for accessing an array component is:

```
arrayName[indexExp]
```


in which `indexExp`, called the **index**, is any expression whose value is a nonnegative integer. The index value specifies the position of the component in the array.

In C++, `[]` is an operator called the **array subscripting operator**. Moreover, in C++, the array index starts at 0.

Consider the following statement:

```
int list[10];
```

This statement declares an array `list` of 10 components. The components are `list[0]`, `list[1]`, ..., `list[9]`. In other words, we have declared 10 variables (see Figure 9-3).




**FIGURE 9-3** Array `list`

The assignment statement:

```
list[5] = 34;
```

stores 34 in `list[5]`, which is the sixth component of the array `list` (see Figure 9-4).



**FIGURE 9-4** Array `list` after execution of the statement `list[5] = 34;`

Suppose `i` is an `int` variable. Then, the assignment statement:

```
list[3] = 63;
```

is equivalent to the assignment statements:

```
i = 3;
list[i] = 63;
```

If `i` is 4, then the assignment statement:


```
list[2 * i - 3] = 58;
```

stores 58 in `list[5]` because  $2 * i - 3$  evaluates to 5. The index expression is evaluated first, giving the position of the component in the array.

Next, consider the following statements:

```
list[3] = 10;
list[6] = 35;
list[5] = list[3] + list[6];
```

The first statement stores 10 in `list[3]`, the second statement stores 35 in `list[6]`, and the third statement adds the contents of `list[3]` and `list[6]` and stores the result in `list[5]` (see Figure 9-5).



**FIGURE 9-5** Array `list` after execution of the statements `list[3]=10;`, `list[6]=35;`, and `list[5]=list[3]+list[6];`

### EXAMPLE 9-2

You can also declare arrays as follows:

```
const int ARRAY_SIZE = 10;
int list[ARRAY_SIZE];
```

That is, you can first declare a named constant and then use the value of the named constant to declare an array and specify its size.

#### NOTE

When you declare an array, its size must be known. For example, you cannot do the following:

```
int arraySize; //Line 1

cout << "Enter the size of the array: "; //Line 2
cin >> arraySize; //Line 3
cout << endl; //Line 4

int list[arraySize]; //Line 5; not allowed
```

The statement in Line 2 asks the user to enter the size of the array when the program executes. The statement in Line 3 inputs the size of the array into `arraySize`. When the compiler compiles Line 1, the value of the variable `arraySize` is unknown. Thus, when the compiler compiles Line 5, the size of the array is unknown and the compiler will not know how much memory space to allocate for the array. In Chapter 14, you will learn how to specify the size of an array during program execution and then declare an array of that size using pointers. Arrays that are created by using pointers during program execution are called **dynamic arrays**. For now, whenever you declare an array, its size must be known.

## Processing One-Dimensional Arrays

Some of the basic operations performed on a one-dimensional array are initializing, inputting data, outputting data stored in an array, and finding the largest and/or smallest element. Moreover, if the data is numeric, some other basic operations are finding the sum and average of the elements of the array. Each of these operations requires the ability to step through the elements of the array. This is easily accomplished using a loop. For example, suppose that we have the following statements:

```
int list[100]; //list is an array of size 100
int i;
```

The following **for** loop steps through each element of the array **list**, starting at the first element of **list**:

```
for (i = 0; i < 100; i++) //Line 1
 //process list[i] //Line 2
```

If processing the list requires inputting data into **list**, the statement in Line 2 takes the form of an input statement, such as the **cin** statement. For example, the following statements read 100 numbers from the keyboard and store the numbers in **list**:

```
for (i = 0; i < 100; i++) //Line 1
 cin >> list[i]; //Line 2
```

Similarly, if processing **list** requires outputting the data, then the statement in Line 2 takes the form of an output statement. Example 9-3 further illustrates how to process one-dimensional arrays.

### EXAMPLE 9-3

This example shows how loops are used to process arrays. The following declaration is used throughout this example:

```
double sales[10];
int index;
double largestSale, sum, average;
```

The first statement declares an array **sales** of 10 components, with each component being of type **double**. The meaning of the other statements is clear.

- a. **Initializing an array:** The following loop initializes every component of the array **sales** to 0.0.

```
for (index = 0; index < 10; index++)
 sales[index] = 0.0;
```

- b. **Reading data into an array:** The following loop inputs the data into the array `sales`. For simplicity, we assume that the data is entered from the keyboard.

```
for (index = 0; index < 10; index++)
 cin >> sales[index];
```

- c. **Printing an array:** The following loop outputs the array `sales`. For simplicity, we assume that the output goes to the screen.

```
for (index = 0; index < 10; index++)
 cout << sales[index] << " ";
```

- d. **Finding the sum and average of an array:** Because the array `sales`, as its name implies, represents certain sales data, it is natural to find the total sale and average sale amounts. The following C++ code finds the sum of the elements of the array `sales` and the average sale amount:

```
sum = 0;
for (index = 0; index < 10; index++)
 sum = sum + sales[index];
```

```
average = sum / 10;
```

- e. **Largest element in the array:** We now discuss the algorithm to find the first occurrence of the largest element in an array—that is, the first array component with the largest value. However, in general, the user is more interested in determining the location of the largest element in the array. Of course, if you know the location (that is, the index of the largest element in the array), you can easily determine the value of the largest element in the array. So let us describe the algorithm to determine the index of the first occurrence of the largest element in an array—in particular, the index of the largest sale amount in the array `sales`. We will use the index of the first occurrence of the largest element in the array to find the largest sale.

We assume that `maxIndex` will contain the index of the first occurrence of the largest element in the array `sales`. The general algorithm is straightforward. Initially, we assume that the first element in the list is the largest element, so `maxIndex` is initialized to 0. We then compare the element pointed to by `maxIndex` with every subsequent element in the list. Whenever we find an element in the array larger than the element pointed to by `maxIndex`, we update `maxIndex` so that it points to the new larger element. The algorithm is as follows:

```
maxIndex = 0;
for (index = 1; index < 10; index++)
 if (sales[maxIndex] < sales[index])
 maxIndex = index;
largestSale = sales[maxIndex];
```

Let us demonstrate how this algorithm works with an example. Suppose the array `sales` is as given in Figure 9-6.

|       | [0]   | [1]  | [2]   | [3]   | [4]   | [5]   | [6]   | [7]   | [8]   | [9]   |
|-------|-------|------|-------|-------|-------|-------|-------|-------|-------|-------|
| sales | 12.50 | 8.35 | 19.60 | 25.00 | 14.00 | 39.43 | 35.90 | 98.23 | 66.65 | 35.64 |

FIGURE 9-6 Array `sales`

Here, we determine the largest element in the array `sales`. Before the `for` loop begins, `maxIndex` is initialized to 0, and the `for` loop initializes `index` to 1. In the following, we show the values of `maxIndex`, `index`, and certain array elements during each iteration of the `for` loop.

| index | maxIndex | sales<br>[maxIndex] | sales<br>[index] | sales[maxIndex] <<br>sales[index]              |
|-------|----------|---------------------|------------------|------------------------------------------------|
| 1     | 0        | 12.50               | 8.35             | 12.50 < 8.35 is <b>false</b>                   |
| 2     | 0        | 12.50               | 19.60            | 12.50 < 19.60 is <b>true</b> ;<br>maxIndex = 2 |
| 3     | 2        | 19.60               | 25.00            | 19.60 < 25.00 is <b>true</b> ;<br>maxIndex = 3 |
| 4     | 3        | 25.00               | 14.00            | 25.00 < 14.00 is <b>false</b>                  |
| 5     | 3        | 25.00               | 39.43            | 25.00 < 39.43 is <b>true</b> ;<br>maxIndex = 5 |
| 6     | 5        | 39.43               | 35.90            | 39.43 < 35.90 is <b>false</b>                  |
| 7     | 5        | 39.43               | 98.23            | 39.43 < 98.23 is <b>true</b> ;<br>maxIndex = 7 |
| 8     | 7        | 98.23               | 66.65            | 98.23 < 66.65 is <b>false</b>                  |
| 9     | 7        | 98.23               | 35.64            | 98.23 < 35.64 is <b>false</b>                  |

After the `for` loop executes, `maxIndex` = 7, giving the index of the largest element in the array `sales`. Thus, `largestSale` = `sales[maxIndex]` = 98.23.

#### NOTE

You can write an algorithm to find the smallest element in the array that is similar to the algorithm for finding the largest element in an array. (See Programming Exercise 2 at the end of this chapter.)

Now that we know how to declare and process arrays, let us rewrite the program that we discussed in the beginning of this chapter. Recall that this program reads five numbers, finds the sum, and prints the numbers in reverse order.

**EXAMPLE 9-4**

```

//Program to read five numbers, find their sum, and
//print the numbers in reverse order.

#include <iostream>

using namespace std;

int main()
{
 int item[5]; //Declare an array item of five components
 int sum;
 int counter;

 cout << "Enter five numbers: ";

 sum = 0;

 for (counter = 0; counter < 5; counter++)
 {
 cin >> item[counter];
 sum = sum + item[counter];
 }

 cout << endl;

 cout << "The sum of the numbers is: " << sum << endl;
 cout << "The numbers in reverse order are: ";

 //Print the numbers in reverse order.
 for (counter = 4; counter >= 0; counter--)
 cout << item[counter] << " ";

 cout << endl;

 return 0;
}

```

**Sample Run:** In this sample run, the user input is shaded.

Enter five numbers: 12 76 34 52 89

The sum of the numbers is: 263

The numbers in reverse order are: 89 52 34 76 12

---

## Array Index Out of Bounds

Consider the following declaration:

```

double num[10];
int i;

```

The component `num[i]` is valid, that is, `i` is a valid index if `i = 0, 1, 2, 3, 4, 5, 6, 7, 8, or 9`.

The index—say, `index`—of an array is **in bounds** if `index >= 0` and `index <= ARRAY_SIZE - 1`. If either `index < 0` or `index > ARRAY_SIZE - 1`, then we say that the index is **out of bounds**.

Unfortunately, in C++, there is no guard against out-of-bound indices. Thus, C++ does not check whether the index value is within range—that is, between 0 and `ARRAY_SIZE - 1`. If the index goes out of bounds and the program tries to access the component specified by the index, then whatever memory location is indicated by the index that location is accessed. This situation can result in altering or accessing the data of a memory location that you never intended to modify or access. Consequently, several strange things can happen if the index goes out of bounds during execution. It is solely the programmer's responsibility to make sure that the index is within bounds.

A loop such as the following can set the index out of bounds:

```
for (i = 0; i <= 10; i++)
 list[i] = 0;
```

Here, we assume that `list` is an array of 10 components. When `i` becomes 10, the loop test condition `i <= 10` evaluates to `true` and the body of the loop executes, which results in storing 0 in `list[10]`. Logically, `list[10]` does not exist.

#### NOTE

On some new compilers, if an array index goes out of bounds in a program, it is possible that the program terminates with an error message. For example, see the programs `Example_ArrayIndexOutOfBoundsA.cpp` and `Example_ArrayIndexOutOfBoundsB.cpp` at the Web site accompanying this book.

## Array Initialization During Declaration

Like any other simple variable, an array can be initialized while it is being declared. For example, the following C++ statement declares an array, `sales`, of five components and initializes these components.

```
double sales[5] = {12.25, 32.50, 16.90, 23, 45.68};
```

The values are placed between curly braces and separated by commas—here, `sales[0] = 12.25`, `sales[1] = 32.50`, `sales[2] = 16.90`, `sales[3] = 23.00`, and `sales[4] = 45.68`.

When initializing arrays as they are declared, it is not necessary to specify the size of the array. The size is determined by the number of initial values in the braces. However, you must include the brackets following the array name. The previous statement is, therefore, equivalent to:

```
double sales[] = {12.25, 32.50, 16.90, 23, 45.68};
```

Although it is not necessary to specify the size of the array if it is initialized during declaration, it is a good practice to do so.

## Partial Initialization of Arrays During Declaration

When you declare and initialize an array simultaneously, you do not need to initialize all components of the array. This procedure is called **partial initialization of an array during declaration**. However, if you partially initialize an array during declaration, you must exercise some caution. The following examples help to explain what happens when you declare and partially initialize an array.

The statement:

```
int list[10] = {0};
```

declares `list` to be an array of 10 components and initializes all of the components to 0.

The statement:

```
int list[10] = {8, 5, 12};
```

declares `list` to be an array of 10 components and initializes `list[0]` to 8, `list[1]` to 5, `list[2]` to 12, and all other components to 0. Thus, if all of the values are not specified in the initialization statement, the array components for which the values are not specified are initialized to 0. Note that, here, the size of the array in the declaration statement does matter. For example, the statement:

```
int list[] = {5, 6, 3};
```

declares `list` to be an array of **three** components and initializes `list[0]` to 5, `list[1]` to 6, and `list[2]` to 3. In contrast, the statement:

```
int list[25] = {4, 7};
```

declares `list` to be an array of 25 components. The first two components are initialized to 4 and 7, respectively, and all other components are initialized to 0.

When you partially initialize an array, then all of the elements that follow the last uninitialized elements must be uninitialized. Therefore, the following statement will result in a syntax error:

```
int list[10] = {2, 5, 6, , 8}; //illegal
```

In this initialization, because the fourth element is uninitialized, all elements that follow the fourth element must be left uninitialized.

## Some Restrictions on Array Processing

Consider the following statements:

```
int myList[5] = {0, 4, 8, 12, 16}; //Line 1
int yourList[5]; //Line 2
```

The statement in Line 1 declares and initializes the array `myList`, and the statement in Line 2 declares the array `yourList`. Note that these arrays are of the same type and have the same number of components. Suppose that you want to copy the elements of `myList` into the corresponding elements of `yourList`. The following statement is illegal:

```
yourList = myList; //illegal
```

In fact, this statement will generate a syntax error. C++ does not allow aggregate operations on an array. An **aggregate operation** on an array is any operation that manipulates the entire array as a single unit.

To copy one array into another array, you must copy it component-wise—that is, one component at a time. This can be done using a loop, such as the following:

```
for (int index = 0; index < 5; index++)
 yourList[index] = myList[index];
```

Next, suppose that you want to read data into the array `yourList`. The following statement is illegal and, in fact, would generate a syntax error.

```
cin >> yourList; //illegal
```

To read data into `yourList`, you must read one component at a time, using a loop such as the following:

```
for (int index = 0; index < 5; index++)
 cin >> yourList[index];
```

Similarly, determining whether two arrays have the same elements and printing the contents of an array must be done component-wise. Note that the following statements are illegal in the sense that they do not generate a syntax error; however, they do not give the desired results.

```
cout << yourList;

if (myList <= yourList)
.
.
.
```

We will comment on these statements in the section Base Address of an Array and Array in Computer Memory later in this chapter.

## Arrays as Parameters to Functions

Now that you have seen how to work with arrays, a question naturally arises: How are arrays passed as parameters to functions?

**By reference only:** In C++, arrays are passed by reference only.

Because arrays are passed by reference only, you *do not* use the symbol `&` when declaring an array as a formal parameter.

When declaring a one-dimensional array as a formal parameter, the size of the array is usually omitted. If you specify the size of a one-dimensional array when it is declared as a formal parameter, the size is ignored by the compiler.

### EXAMPLE 9-5

Consider the following function:

```
void funcArrayAsParam(int listOne[], double listTwo[])
{
 .
 .
 .
}
```

The function `funcArrayAsParam` has two formal parameters: (1) `listOne`, a one-dimensional array of type `int` (that is, the component type is `int`) and (2) `listTwo`, a one-dimensional array of type `double`. In this declaration, the size of both arrays is unspecified.

Sometimes, the number of elements in the array might be less than the size of the array. For example, the number of elements in an array storing student data might increase or decrease as students drop or add courses. In such situations, we want to process only the components of the array that hold actual data. To write a function to process such arrays, in addition to declaring an array as a formal parameter, we declare another formal parameter specifying the number of elements in the array, as in the following function:

```
void initialize(int list[], int listSize)
{
 int count;

 for (count = 0; count < listSize; count++)
 list[count] = 0;
}
```

The first parameter of the function `initialize` is an `int` array of any size. When the function `initialize` is called, the size of the actual array is passed as the second parameter of the function `initialize`.

## Constant Arrays as Formal Parameters

Recall that when a formal parameter is a reference parameter, then whenever the formal parameter changes, the actual parameter changes as well. However, even though an array is always passed by reference, you can still prevent the function from changing the actual parameter. You do so by using the reserved word `const` in the declaration of the formal parameter. Consider the following function:

```
void example(int x[], const int y[], int sizeX, int sizeY)
{
 .
 .
 .
}
```

Here, the function `example` can modify the array `x`, but not the array `y`. Any attempt to change `y` results in a compile-time error. It is a good programming practice to declare an array to be constant as a formal parameter if you do not want the function to modify the array.

### EXAMPLE 9-6

This example shows how to write functions for array processing and declare an array as a formal parameter.

```
//Function to initialize an int array to 0.
//The array to be initialized and its size are passed
//as parameters. The parameter listSize specifies the
//number of elements to be initialized.
void initializeArray(int list[], int listSize)
{
 int index;

 for (index = 0; index < listSize; index++)
 list[index] = 0;
}

//Function to read and store the data into an int array.
//The array to store the data and its size are passed as
//parameters. The parameter listSize specifies the number
//of elements to be read.
void fillArray(int list[], int listSize)
{
 int index;

 for (index = 0; index < listSize; index++)
 cin >> list[index];
}

//Function to print the elements of an int array.
//The array to be printed and the number of elements
//are passed as parameters. The parameter listSize
//specifies the number of elements to be printed.
void printArray(const int list[], int listSize)
{
 int index;

 for (index = 0; index < listSize; index++)
 cout << list[index] << " ";
}
```

```

//Function to find and return the sum of the
//elements of an int array. The parameter listSize
//specifies the number of elements to be added.
int sumArray(const int list[], int listSize)
{
 int index;
 int sum = 0;

 for (index = 0; index < listSize; index++)
 sum = sum + list[index];

 return sum;
}

//Function to find and return the index of the first
//largest element in an int array. The parameter listSize
//specifies the number of elements in the array.
int indexLargestElement(const int list[], int listSize)
{
 int index;
 int maxIndex = 0; //assume the first element is the largest

 for (index = 1; index < listSize; index++)
 if (list[maxIndex] < list[index])
 maxIndex = index;

 return maxIndex;
}

//Function to copy some or all of the elements of one array
//into another array. Starting at the position specified
//by src, the elements of list1 are copied into list2
//starting at the position specified by tar. The parameter
//numOfElements specifies the number of elements of list1 to
//be copied into list2. Starting at the position specified
//by tar, the list2 must have enough components to copy the
//elements of list1. The following call copies all of the
//elements of list1 into the corresponding positions in
//list2: copyArray(list1, 0, list2, 0, numOfElements);
void copyArray(int list1[], int src, int list2[],
 int tar, int numOfElements)
{
 for (int index = src; index < src + numOfElements; index++)
 {
 list2[index] = list1[tar];
 tar++;
 }
}

```

Example 9-7 will illustrate how to use some of these functions in a program.

---

## Base Address of an Array and Array in Computer Memory

The **base address** of an array is the address (that is, the memory location) of the first array component. For example, if `list` is a one-dimensional array, then the base address of `list` is the address of the component `list[0]`.

Consider the following statements:

```
int myList[5]; //Line 1
```

This statement declares `myList` to be an array of five components of type `int`. The components are `myList[0]`, `myList[1]`, `myList[2]`, `myList[3]`, and `myList[4]`. The computer allocates five memory spaces, each large enough to store an `int` value, for these components. Moreover, the five memory spaces are contiguous.

The base address of the array `myList` is the address of the component `myList[0]`. Suppose that the base address of the array `myList` is 1000. Then, the address of the component `myList[0]` is 1000. Typically, the memory allocated for an `int` variable is four bytes. Recall from Chapter 1 that main memory is an ordered sequence of cells, and each cell has a unique address. Typically, each cell is one byte. Therefore, to store a value into `myList[0]`, starting at the address 1000, the next four bytes are allocated for `myList[0]`. It follows that the starting address of `myList[1]` is 1004, the starting address of `myList[2]` is 1008, and so on (see Figure 9-7).




FIGURE 9-7 Array `myList` and the addresses of its components

Now `myList` is the name of an array. There is also a memory space associated with the identifier `myList`, and the base address of the array is stored in that memory space. Consider the following statement:

```
cout << myList << endl; //Line 2
```

Earlier, we said that this statement will not give the desired result. That is, this statement will not output the values of the *components* of `myList`. In fact, the statement outputs the value of `myList`, which is the base address of the array. This is why the statement will not generate a syntax error.

Suppose that you also have the following statement:

```
int yourList[5];
```

Then, in the statement:

```
if (myList <= yourList) //Line 3
.
.
.
```

the expression `myList <= yourList` evaluates to `true` if the base address of the array `myList` is less than the base address of the array `yourList`; and evaluates to `false` otherwise. It *does not* determine whether the elements of `myList` are less than or equal to the corresponding elements of `yourList`.

#### NOTE

The Web site accompanying this book contains the program `BaseAddressOfAnArray.cpp`, which clarifies statements such as those in Lines 2 and 3.

You might be wondering why the base address of an array is so important. The reason is that when you declare an array, the only things about the array that the computer remembers are the name of the array, its base address, the data type of each component, and (possibly) the number of components. Using the base address of the array and the index of an array component, the computer determines the address of a particular component. For example, suppose you want to access the value of `myList[3]`. Now, the base address of `myList` is 1000. Each component of `myList` is of type `int`, so it uses four bytes to store a value, and the index is 3. To access the value of `myList[3]`, the computer calculates the address  $1000 + 4 * 3 = 1000 + 12 = 1012$ . That is, this is the starting address of `myList[3]`. So, starting at 1012, the computer accesses the next four bytes.

When you pass an array as a parameter, the base address of the actual array is passed to the formal parameter. For example, suppose that you have the following function:

```

void arrayAsParameter(int list[], int size)
{
 .
 .
 .

 list[2] = 28; //Line 4

 .
 .
 .
}

```

Also, suppose that you have the following call to this function:

```
arrayAsParameter(myList, 5); //Line 5
```

In this statement, the base address of `myList` is passed to the formal parameter `list`. Therefore, the base address of `list` is 1000. The definition of the function contains the statement `list[2] = 28;`. This statement stores 28 into `list[2]`. To access `list[2]`, the computer calculates the address as follows:  $1000 + 4 * 2 = 1008$ . So, starting at the address 1008, the computer accesses the next four bytes and stores 28. Note that, in fact, 1008 is the address of `myList[2]` (see Figure 9-7). It follows that during the execution of the statement in Line 5, the statement in Line 4 stores the value 28 into `myList[2]`. It also follows that during the execution of the function call statement in Line 5, `list[index]` and `myList[index]` refer to the same memory space, where  $0 \leq \text{index}$  and  $\text{index} < 5$ .

#### NOTE

If C++ allowed arrays to be passed by value, the computer would have to allocate memory for the components of the formal parameter and copy the contents of the actual array into the corresponding formal parameter when the function is called. If the array size was large, this process would waste memory as well as the computer time needed for copying the data. That is why in C++ arrays are always passed by reference.

9

## Functions Cannot Return a Value of the Type Array

C++ does not allow functions to return a value of the type array. Note that the functions `sumArray` and `indexLargestElement` described earlier return values of type `int`.

### EXAMPLE 9-7

The following program illustrates how arrays are passed as actual parameters in a function call. (Note that this program uses the functions written in Example 9-6).

```

//Arrays as parameters to functions

#include <iostream>

```

```

using namespace std;

const int ARRAY_SIZE = 10;

void initializeArray(int x[],int sizeX);
void fillArray(int x[],int sizeX);
void printArray(const int x[],int sizeX);
int sumArray(const int x[],int sizeX);
int indexLargestElement(const int x[],int sizeX);
void copyArray(int list1[], int src, int list2[],
 int tar, int numOfElements);

int main()
{
 int listA[ARRAY_SIZE] = {0}; //Declare the array listA
 //of 10 components and
 //initialize each component
 //to 0.
 int listB[ARRAY_SIZE]; //Declare the array listB
 //of 10 components.

 cout << "Line 1: listA elements: "; //Line 1

 //Output the elements of listA using
 //the function printArray
 printArray(listA, ARRAY_SIZE); //Line 2
 cout << endl; //Line 3

 //Initialize listB using the function
 //initializeArray
 initializeArray(listB, ARRAY_SIZE); //Line 4

 cout << "Line 5: listB elements: "; //Line 5

 //Output the elements of listB
 printArray(listB, ARRAY_SIZE); //Line 6
 cout << endl << endl; //Line 7

 cout << "Line 8: Enter " << ARRAY_SIZE
 << " integers: "; //Line 8

 //Input data into listA using the
 //function fillArray
 fillArray(listA, ARRAY_SIZE); //Line 9
 cout << endl; //Line 10

 cout << "Line 11: After filling listA, "
 << "the elements are:" << endl; //Line 11

 //Output the elements of listA
 printArray(listA, ARRAY_SIZE); //Line 12
 cout << endl << endl; //Line 13
}

```

```

 //Find and output the sum of the elements
 //of listA
 cout << "Line 14: The sum of the elements of "
 << "listA is: "
 << sumArray(listA, ARRAY_SIZE) << endl
 << endl; //Line 14

 //Find and output the position of the largest
 //element in listA
 cout << "Line 15: The position of the largest "
 << "element in listA is: "
 << indexLargestElement(listA, ARRAY_SIZE)
 << endl; //Line 15

 //Find and output the largest element
 //in listA
 cout << "Line 16: The largest element in "
 << "listA is: "
 << listA[indexLargestElement(listA, ARRAY_SIZE)]
 << endl << endl; //Line 16

 //Copy the elements of listA into listB using the
 //function copyArray
 copyArray(listA, 0, listB, 0, ARRAY_SIZE); //Line 17

 cout << "Line 18: After copying the elements "
 << "of listA into listB," << endl
 << " listB elements are: "; //Line 18

 //Output the elements of listB
 printArray(listB, ARRAY_SIZE); //Line 19
 cout << endl; //Line 20

 return 0;
}

//Place the definitions of the functions initializeArray,
//fillArray, and so on here. Example 9-6 gives the definitions
//of these functions.

```

**Sample Run:** In this sample run, the user input is shaded.

```

Line 1: listA elements: 0 0 0 0 0 0 0 0 0 0
Line 5: listB elements: 0 0 0 0 0 0 0 0 0 0

```

```

Line 8: Enter 10 integers: 33 77 25 63 56 48 98 39 5 12

```

```

Line 11: After filling listA, the elements are:
33 77 25 63 56 48 98 39 5 12

```

```

Line 14: The sum of the elements of listA is: 456

```

Line 15: The position of the largest element in listA is: 6  
 Line 16: The largest element in listA is: 98

Line 18: After copying the elements of listA into listB,  
 listB elements are: 33 77 25 63 56 48 98 39 5 12

The output of this program is straightforward. First, we declare the array `listA` of 10 components and initialize each component of `listA` to 0. Then, we declare the array `listB` of 10 components. The statement in Line 2 calls the function `printArray` and outputs the values stored in `listA`. The statement in Line 9 calls the function `fillArray` to input the data into `listA`. The statement in Line 14 calls the function `sumArray` and outputs the sum of all of the elements of `listA`. Similarly, the statement in Line 16 outputs the value of the largest element in `listA`.

---

## Integral Data Type and Array Indices

### NOTE

The sections “Enumeration Type” and “`typedef` Statement” from Chapter 8 are required to understand this section.

---

Other than integers, C++ allows any integral type to be used as an array index. This feature can greatly enhance a program’s readability. Consider the following statements:

```
enum paintType {GREEN, RED, BLUE, BROWN, WHITE, ORANGE, YELLOW};
double paintSale[7];
paintType paint;
```

The following loop initializes each component of the array `paintSale` to 0:

```
for (paint = GREEN; paint <= YELLOW;
 paint = static_cast<paintType>(paint + 1))
 paintSale[paint] = 0.0;
```

The following statement updates the sale amount of `RED` paint:

```
paintSale[RED] = paintSale[RED] + 75.69;
```

As you can see, the above code is much easier to follow than the code that used integers for the index. For this reason, you should use the enumeration type for the array index or other integral data types wherever possible. Note that when using the enumeration type for array indices, use the default values of the identifiers in the enumeration type. That is, the value of the first identifier must be 0, and so on. (Recall from Chapter 8 that the default values of identifiers in an enumeration type start at 0; however, the identifiers can be set to other values.)

## Other Ways to Declare Arrays

Suppose that a class has 20 students and you need to keep track of their scores. Because the number of students can change from semester to semester, instead of specifying the size of the array while declaring it, you can declare the array as follows:

```
const int NO_OF_STUDENTS = 20;
int testScores[NO_OF_STUDENTS];
```

Other forms used to declare arrays are:

```
const int SIZE = 50; //Line 1
typedef double list[SIZE]; //Line 2

list yourList; //Line 3
list myList; //Line 4
```

The statement in Line 2 defines a data type `list`, which is an array of 50 components of type `double`. The statements in Lines 3 and 4 declare two variables, `yourList` and `myList`. Both are arrays of 50 components of type `double`. Of course, these statements are equivalent to:

```
double yourList[50];
double myList[50];
```

## Searching an Array for a Specific Item

Searching a list for a given item is one of the most common operations performed on a list. The search algorithm we describe is called the **sequential search** or **linear search**. As the name implies, you search the array sequentially, starting from the first array element. You compare `searchItem` with the elements in the array (the list) and continue the search until either you find the item or no more data is left in the `list` to compare with `searchItem`.

Consider the list of seven elements shown in Figure 9-8.

|      | [0] | [1] | [2] | [3] | [4] | [5] | [6] |
|------|-----|-----|-----|-----|-----|-----|-----|
| list | 35  | 12  | 27  | 18  | 45  | 16  | 38  |

FIGURE 9-8 List of seven elements

Suppose that you want to determine whether 27 is in the list. A sequential search works as follows: First, you compare 27 with `list[0]`, that is, compare 27 with 35. Because `list[0] ≠ 27`, you then compare 27 with `list[1]`, that is, with 12, the second item in the list. Because `list[1] ≠ 27`, you compare 27 with the next element in the list, that is, compare 27 with `list[2]`. Because `list[2] = 27`, the search stops. This search is successful.

Let us now search for 10. As before, the search starts at the first element in the list, that is, at `list[0]`. Proceeding as before, we see that, this time, the search item, which is 10, is compared with every item in the list. Eventually, no more data is left in the list to compare with the search item. This is an unsuccessful search.

It now follows that, as soon as you find an element in the list that is equal to the search item, you must stop the search and report success. (In this case, you usually also report the location in the list where the search item was found.) Otherwise, after the search item is unsuccessfully compared with every element in the list, you must stop the search and report failure.

Suppose that the name of the array containing the list elements is `list`. The previous discussion translates into the following algorithm for the sequential search:

```
found is set to false;
loc = 0;

while (loc < listLength and not found)
 if (list[loc] is equal to searchItem)
 found is set to true
 else
 increment loc

if (found)
 return loc;
else
 return -1;
```

The following function performs a sequential search on a list. To be specific, and for illustration purposes, we assume that the list elements are of type `int`.

```
int seqSearch(const int list[], int listLength, int searchItem)
{
 int loc;
 bool found = false;

 loc = 0;

 while (loc < listLength && !found)
 if (list[loc] == searchItem)
 found = true;
 else
 loc++;

 if (found)
 return loc;
 else
 return -1;
}
```

If the function `seqSearch` returns a value greater than or equal to 0, it is a successful search; otherwise, it is an unsuccessful search.

As you can see from this code, you start the search by comparing `searchItem` with the first element in the `list`. If `searchItem` is equal to the first element in the `list`, you exit the loop; otherwise, `loc` is incremented by 1 to point to the next element in the `list`. You then compare `searchItem` with the next element in the `list`, and so on.

### EXAMPLE 9-8

```
// This program illustrates how to use a sequential search in a
// program.

#include <iostream> //Line 1
using namespace std; //Line 2
const int ARRAY_SIZE = 10; //Line 3

int seqSearch(const int list[], int listLength, //Line 4
 int searchItem);

int main() //Line 5
{ //Line 6
 int intList[ARRAY_SIZE]; //Line 7
 int number; //Line 8

 cout << "Line 9: Enter " << ARRAY_SIZE //Line 9
 << " integers." << endl;

 for (int index = 0; index < ARRAY_SIZE; index++) //Line 10
 cin >> intList[index]; //Line 11

 cout << endl; //Line 12

 cout << "Line 13: Enter the number to be " //Line 13
 << "searched: "; //Line 14
 cin >> number; //Line 15
 cout << endl;

 int pos = seqSearch(intList, ARRAY_SIZE, number); //Line 16

 if (pos != -1) //Line 17
 cout << "Line 18: " << number //Line 18
 << " is found at position " << pos //Line 19
 << endl;
 else
 cout << "Line 20: " << number //Line 20
 << " is not in the list." << endl;

 return 0; //Line 21
} //Line 22

//Place the definition of the function seqSearch
//given previously here.
```

**Sample Run 1:** In this sample run, the user input is shaded.

```
Line 9: Enter 10 integers.
2 56 34 25 73 46 89 10 5 16
```

```
Line 13: Enter the number to be searched: 25
```

```
Line 18: 25 is found at position 3
```

**Sample Run 2:**

```
Line 9: Enter 10 integers.
2 56 34 25 73 46 89 10 5 16
```

```
Line 13: Enter the number to be searched: 38
```

```
Line 20: 38 is not in the list.
```

---

## C-Strings (Character Arrays)

Until now, we have avoided discussing character arrays for a simple reason: Character arrays are of special interest, and you process them differently than you process other arrays. C++ provides many (predefined) functions that you can use with character arrays.

**Character array:** An array whose components are of type `char`.

Recall that the most widely used character sets are ASCII and EBCDIC. The first character in the ASCII character set is the null character, which is nonprintable. Also, recall that in C++, the null character is represented as `'\0'`, a backslash followed by a zero.

The statement:

```
ch = '\0';
```

stores the null character in `ch`, wherein `ch` is a `char` variable.

As you will see, the null character plays an important role in processing character arrays. Because the collating sequence of the null character is 0, the null character is less than any other character in the `char` data set.

The most commonly used term for character arrays is C-strings. However, there is a subtle difference between character arrays and C-strings. Recall that a string is a sequence of zero or more characters, and strings are enclosed in double quotation marks. In C++, C-strings are null terminated; that is, the last character in a C-string is always the null character. A character array might not contain the null character, but the last character in a C-string is always the null character. As you will see, the null character should not appear anywhere in the C-string except the last position. Also, C-strings are stored in (one-dimensional) character arrays.

The following are examples of C-strings:

```
"John L. Johnson"
"Hello there."
```

From the definition of C-strings, it is clear that there is a difference between 'A' and "A". The first one is character A; the second is C-string A. Because C-strings are null terminated, "A" represents two characters: 'A' and '\0'. Similarly, the C-string "Hello" represents six characters: 'H', 'e', 'l', 'l', 'o', and '\0'. To store 'A', we need only one memory cell of type `char`; to store "A", we need two memory cells of type `char`—one for 'A' and one for '\0'. Similarly, to store the C-string "Hello" in computer memory, we need six memory cells of type `char`.

Consider the following statement:

```
char name[16];
```

This statement declares an array `name` of 16 components of type `char`. Because C-strings are null terminated and `name` has 16 components, the largest string that can be stored in `name` is of length 15. If you store a C-string of length 10 in `name`, the first 11 components of `name` are used and the last 5 are left unused.

The statement:

```
char name[16] = {'J', 'o', 'h', 'n', '\0'};
```

declares an array `name` containing 16 components of type `char` and stores the C-string "John" in it. During `char` array variable declaration, C++ allows the C-string notation to be used in the initialization statement. The above statement is, therefore, equivalent to:

```
char name[16] = "John"; //Line A
```

Recall that the size of an array can be omitted if the array is initialized during the declaration.

The statement:

```
char name[] = "John"; //Line B
```

declares a C-string variable `name` of a length large enough—in this case, 5—and stores "John" in it. There is a difference between the last two statements: Both statements store "John" in `name`, but the size of `name` in the statement in Line A is 16, and the size of `name` in the statement in Line B is 5.

Most rules that apply to other arrays also apply to character arrays. Consider the following statement:

```
char studentName[26];
```

Suppose you want to store "Lisa L. Johnson" in `studentName`. Because aggregate operations, such as assignment and comparison, are not allowed on arrays, the following statement is not legal:

```
studentName = "Lisa L. Johnson"; //illegal
```

C++ provides a set of functions that can be used for C-string manipulation. The header file `cstring` describes these functions. We often use three of these functions: `strcpy` (string copy, to copy a C-string into a C-string variable—that is, assignment); `strcmp` (string comparison, to compare C-strings); and `strlen` (string length, to find the length of a C-string). Table 9-1 summarizes these functions.

**TABLE 9-1** `strcpy`, `strcmp`, and `strlen` Functions

| Function                    | Effect                                                                                                                                                                                                             |
|-----------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>strcpy(s1, s2)</code> | Copies the string <code>s2</code> into the string variable <code>s1</code><br>The length of <code>s1</code> should be at least as large as <code>s2</code>                                                         |
| <code>strcmp(s1, s2)</code> | Returns a value $< 0$ if <code>s1</code> is less than <code>s2</code><br>Returns 0 if <code>s1</code> and <code>s2</code> are the same<br>Returns a value $> 0$ if <code>s1</code> is greater than <code>s2</code> |
| <code>strlen(s)</code>      | Returns the length of the string <code>s</code> , excluding the null character                                                                                                                                     |

To use these functions, the program must include the header file `cstring` via the `#include` statement. That is, the following statement must be included in the program:

```
#include <cstring>
```

## String Comparison

In C++, C-strings are compared character by character using the system's collating sequence. Let us assume that you use the ASCII character set.

1. The C-string "Air" is less than the C-string "Boat" because the first character of "Air" is less than the first character of "Boat".
2. The C-string "Air" is less than the C-string "An" because the first characters of both strings are the same, but the second character 'i' of "Air" is less than the second character 'n' of "An".
3. The C-string "Bill" is less than the C-string "Billy" because the first four characters of "Bill" and "Billy" are the same, but the fifth character of "Bill", which is '\0' (the null character), is less than the fifth character of "Billy", which is 'y'. (Recall that C-strings in C++ are null terminated.)
4. The C-string "Hello" is less than "hello" because the first character 'H' of the C-string "Hello" is less than the first character 'h' of the C-string "hello".

As you can see, the function `strcmp` compares its first C-string argument with its second C-string argument character by character.

### EXAMPLE 9-9

Suppose you have the following statements:

```
char studentName[21];
char myname[16];
char yourname[16];
```

The following statements show how string functions work:

| Statement                                                                                                                                | Effect                                                                                                  |
|------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------|
| <code>strcpy(myname, "John Robinson");</code>                                                                                            | <code>myname = "John Robinson"</code>                                                                   |
| <code>strlen("John Robinson");</code>                                                                                                    | Returns 13, the length of the string "John Robinson"                                                    |
| <code>int len;</code><br><code>len = strlen("Sunny Day");</code>                                                                         | Stores 9 into <code>len</code>                                                                          |
| <code>strcpy(yourname, "Lisa Miller");</code><br><code>strcpy(studentName, yourname);</code>                                             | <code>yourname = "Lisa Miller"</code><br><code>studentName = "Lisa Miller"</code>                       |
| <code>strcmp("Bill", "Lisa");</code>                                                                                                     | Returns a value $< 0$                                                                                   |
| <code>strcpy(yourname, "Kathy Brown");</code><br><code>strcpy(myname, "Mark G. Clark");</code><br><code>strcmp(myname, yourname);</code> | <code>yourname = "Kathy Brown"</code><br><code>myname = "Mark G. Clark"</code><br>Returns a value $> 0$ |

#### NOTE

In this chapter, we defined a C-string to be a sequence of zero or more characters. C-strings are enclosed in double quotation marks. We also said that C-strings are null terminated, so the C-string "Hello" has six characters even though only five are enclosed in double quotation marks. Therefore, to store the C-string "Hello" in computer memory, you must use a character array of size 6. The length of a C-string is the number of actual characters enclosed in double quotation marks; for example, the length of the C-string "Hello" is 5. Thus, in a logical sense, a C-string is a sequence of zero or more characters, but in the physical sense (that is, to store the C-string in computer memory), a C-string has at least one character. Because the length of the C-string is the actual number of characters enclosed in double quotation marks, we defined a C-string to be a sequence of zero or more characters. However, you must remember that the null character stored in computer memory at the end of the C-string plays a key role when we compare C-strings, especially C-strings such as "Bill" and "Billy".

## Reading and Writing Strings

As mentioned earlier, most rules that apply to arrays apply to C-strings as well. Aggregate operations, such as assignment and comparison, are not allowed on arrays. Even the input/output of arrays is done component-wise. However, the one place where C++ allows aggregate operations on arrays is the input and output of C-strings (that is, character arrays).

We will use the following declaration for our discussion:

```
char name[31];
```

### String Input

Because aggregate operations are allowed for C-string input, the statement:

```
cin >> name;
```

stores the next input C-string into **name**. The length of the input C-string must be less than or equal to 30. If the length of the input string is 4, the computer stores the four characters that are input and the null character '\0'. If the length of the input C-string is more than 30, then because there is no check on the array index bounds, the computer continues storing the string in whatever memory cells follow **name**. This process can cause serious problems, because data in the adjacent memory cells will be corrupted.

#### NOTE

When you input a C-string using an input device, such as the keyboard, you do not include the double quotes around it unless the double quotes are part of the string. For example, the C-string "Hello" is entered as Hello.

Recall that the extraction operator, `>>`, skips all leading whitespace characters and stops reading data into the current variable as soon as it finds the first whitespace character or invalid data. As a result, C-strings that contain blanks cannot be read using the extraction operator, `>>`. For example, if a first name and last name are separated by blanks, they cannot be read into **name**.

How do you input C-strings with blanks into a character array? Once again, the function **get** comes to our rescue. Recall that the function **get** is used to read character data. Until now, the form of the function **get** that you have used (Chapter 3) read only a single character. However, the function **get** can also be used to read strings. To read C-strings, you use the form of the function **get** that has two parameters. The first parameter is a C-string variable; the second parameter specifies how many characters to read into the string variable.

To read C-strings, the general form (syntax) of the **get** function, together with an input stream variable such as **cin**, is:

```
cin.get(str, m + 1);
```

This statement stores the next **m** characters, or all characters until the newline character '\n' is found, into **str**. The newline character is not stored in **str**. If the input C-string has fewer than **m** characters, then the reading stops at the newline character.

Consider the following statements:

```
char str[31];
cin.get(str, 31);
```

If the input is:

William T. Johnson

then "William T. Johnson" is stored in `str`. Suppose that the input is:

Hello there. My name is Mickey Blair.

Then, because `str` can store, at most, 30 characters, the C-string "Hello there. My name is Mickey" is stored in `str`.

Now, suppose that we have the statements:

```
char str1[26];
char str2[26];
char discard;
```

and the two lines of input:

Summer is warm.  
Winter will be cold.

Further, suppose that we want to store the first C-string in `str1` and the second C-string in `str2`. Both `str1` and `str2` can store C-strings that are up to 25 characters in length. Because the number of characters in the first line is 15, the reading stops at '\n'. You must read and discard the newline character at the end of the first line to store the second line into `str2`. The following sequence of statements stores the first line into `str1` and the second line into `str2`:

```
cin.get(str1, 26);
cin.get(discard);
cin.get(str2, 26);
```

To read and store a line of input, including whitespace characters, you can also use the stream function `getline`. Suppose that you have the following declaration:

```
char textLine[100];
```

The following statement will read and store the next 99 characters, or until the newline character, into `textLine`. The null character will be automatically appended as the last character of `textLine`.

```
cin.getline(textLine, 100);
```

## String Output

The output of C-strings is another place where aggregate operations on arrays are allowed. You can output C-strings by using an output stream variable, such as `cout`, together with the insertion operator, `<<`. For example, the statement:

```
cout << name;
```

outputs the contents of `name` on the screen. The insertion operator, `<<`, continues to write the contents of `name` until it finds the null character. Thus, if the length of `name` is 4, the above statement outputs only four characters. If `name` does not contain the null

character, then you will see strange output because the insertion operator continues to output data from memory adjacent to `name` until `'\0'` is found.

## Specifying Input/Output Files at Execution Time

In Chapter 3, you learned how to read data from a file. In subsequent chapters, the name of the input file was included in the `open` statement. By doing so, the program always received data from the same input file. In real-world applications, the data may actually be collected at several locations and stored in separate files. Also, for comparison purposes, someone might want to process each file separately and then store the output in separate files. To accomplish this task efficiently, the user would prefer to specify the name of the input and/or output file at execution time rather than in the programming code. C++ allows the user to do so.

Consider the following statements:

```
ifstream infile;
ofstream outfile;

char fileName[51]; //assume that the file name is at most
 //50 characters long
```

The following statements prompt and allow the user to specify the input and output files at execution time:

```
cout << "Enter the input file name: ";
cin >> fileName;

infile.open(fileName); //open the input file
.
.
.

cout << "Enter the output file name: ";
cin >> fileName;

outfile.open(fileName); //open the output file
```

The Programming Example: Code Detection, given later in this chapter, further illustrates how to specify the names of input and output files during program execution.

## string Type and Input/Output Files

In Chapter 8, we discussed the data type `string`. We now want to point out that values (that is, strings) of type `string` are not null terminated. Variables of type `string` can also be used to read and store the names of input/output files. However, the argument to the function `open` must be a null-terminated string—that is, a C-string. Therefore, if we use a variable of type `string` to read the name of an input/output file and then use this variable to open a file, the value of the variable must (first) be converted to a C-string (that is, a null-terminated string). The header file `string` contains the function `c_str`, which converts a value of type `string` to a null-terminated character array (that is, C-string). The syntax to use the function `c_str` is:

```
strVar.c_str()
```

in which `strVar` is a variable of type `string`.

The following statements illustrate how to use variables of type `string` to read the names of the input/output files during program execution and open those files:

```
ifstream infile;
string fileName;

cout << "Enter the input file name: ";
cin >> fileName;

infile.open(fileName.c_str()); //open the input file
```

Of course, you must also include the header file `string` in the program. The output file has similar conventions.

## Parallel Arrays

Two (or more) arrays are called **parallel** if their corresponding components hold related information.

Suppose you need to keep track of students' course grades, together with their ID numbers, so that their grades can be posted at the end of the semester. Further, suppose that there is a maximum of 50 students in a class and their IDs are 5 digits long. Because there may be 50 students, you need 50 variables to store the students' IDs and 50 variables to store their grades. You can declare two arrays: `studentId` of type `int` and `courseGrade` of type `char`. Each array has 50 components. Furthermore, `studentId[0]` and `courseGrade[0]` will store the ID and course grade of the first student, `studentId[1]` and `courseGrade[1]` will store the ID and course grade of the second student, and so on.

The statements:

```
int studentId[50];
char courseGrade[50];
```

declare these two arrays.

Suppose you need to input data into these arrays, and the data is provided in a file in the following form:

```
studentId courseGrade
```

For example, a sample data set is:

```
23456 A
86723 B
22356 C
92733 B
11892 D
.
.
.
```

Suppose that the input file is opened using the `ifstream` variable `infile`. Because the size of each array is 50, a maximum of 50 elements can be stored into each array. Moreover, it is possible that there may be fewer than 50 students in the class. Therefore,

while reading the data, we also count the number of students and ensure that the array indices do not go out of bounds. The following loop reads the data into the parallel arrays `studentId` and `courseGrade`:

```
int noOfStudents = 0;

infile >> studentId[noOfStudents] >> courseGrade[noOfStudents];

while (infile && noOfStudents < 50)
{
 noOfStudents++;
 infile >> studentId[noOfStudents]
 >> courseGrade[noOfStudents];
}
```

Note that, in general, when swapping values in one array, the corresponding values in parallel arrays must also be swapped.

## Two- and Multidimensional Arrays

The remainder of this chapter discusses two-dimensional arrays and ways to work with multidimensional arrays.

In the previous section, you learned how to use one-dimensional arrays to manipulate data. If the data is provided in a list form, you can use one-dimensional arrays. However, sometimes data is provided in a table form. For example, suppose that you want to track the number of cars in a particular color that are in stock at a local dealership. The dealership sells six types of cars in five different colors. Figure 9-9 shows sample data.

| inStock  | [RED] | [BROWN] | [BLACK] | [WHITE] | [GRAY] |
|----------|-------|---------|---------|---------|--------|
| [GM]     | 10    | 7       | 12      | 10      | 4      |
| [FORD]   | 18    | 11      | 15      | 17      | 10     |
| [TOYOTA] | 12    | 10      | 9       | 5       | 12     |
| [BMW]    | 16    | 6       | 13      | 8       | 3      |
| [NISSAN] | 10    | 7       | 12      | 6       | 4      |
| [VOLVO]  | 9     | 4       | 7       | 12      | 11     |

**FIGURE 9-9** Table `inStock`

You can see that the data is in a table format. The table has 30 entries, and every entry is an integer. Because the table entries are all of the same type, you can declare a one-dimensional array of 30 components of type `int`. The first five components of the one-dimensional array

can store the data of the first row of the table, the next five components of the one-dimensional array can store the data of the second row of the table, and so on. In other words, you can simulate the data given in a table format in a one-dimensional array.

If you do so, the algorithms to manipulate the data in the one-dimensional array will be somewhat complicated, because you must know where one row ends and another begins. You must also correctly compute the index of a particular element. C++ simplifies the processing of manipulating data in a table form with the use of two-dimensional arrays. This section first discusses how to declare two-dimensional arrays and then looks at ways to manipulate data in a two-dimensional array.

**Two-dimensional array:** A collection of a fixed number of components arranged in rows and columns (that is, in two dimensions), wherein all components are of the same type.

The syntax for declaring a two-dimensional array is:

```
dataType arrayName[intExp1][intExp2];
```

wherein `intExp1` and `intExp2` are constant expressions yielding positive integer values. The two expressions, `intExp1` and `intExp2`, specify the number of rows and the number of columns, respectively, in the array.

The statement:

```
double sales[10][5];
```

declares a two-dimensional array `sales` of 10 rows and 5 columns, in which every component is of type `double`. As in the case of a one-dimensional array, the rows are numbered 0 . . . 9 and the columns are numbered 0 . . . 4 (see Figure 9-10).

| sales | [0] | [1] | [2] | [3] | [4] |
|-------|-----|-----|-----|-----|-----|
| [0]   |     |     |     |     |     |
| [1]   |     |     |     |     |     |
| [2]   |     |     |     |     |     |
| [3]   |     |     |     |     |     |
| [4]   |     |     |     |     |     |
| [5]   |     |     |     |     |     |
| [6]   |     |     |     |     |     |
| [7]   |     |     |     |     |     |
| [8]   |     |     |     |     |     |
| [9]   |     |     |     |     |     |

FIGURE 9-10 Two-dimensional array `sales`

## Accessing Array Components

To access the components of a two-dimensional array, you need a pair of indices: one for the row position and one for the column position.

The syntax to access a component of a two-dimensional array is:


```
arrayName[indexExp1][indexExp2]
```

wherein `indexExp1` and `indexExp2` are expressions yielding nonnegative integer values. `indexExp1` specifies the row position; `indexExp2` specifies the column position.

The statement:

```
sales[5][3] = 25.75;
```

stores 25.75 into row number 5 and column number 3 (that is, the sixth row and the fourth column) of the array `sales` (see Figure 9-11).



| sales | [0] | [1] | [2] | [3]   | [4] |
|-------|-----|-----|-----|-------|-----|
| [0]   |     |     |     |       |     |
| [1]   |     |     |     |       |     |
| [2]   |     |     |     |       |     |
| [3]   |     |     |     |       |     |
| [4]   |     |     |     |       |     |
| [5]   |     |     |     | 25.75 |     |
| [6]   |     |     |     |       |     |
| [7]   |     |     |     |       |     |
| [8]   |     |     |     |       |     |
| [9]   |     |     |     |       |     |

**FIGURE 9-11** `sales[5][3]`

Suppose that:

```
int i = 5;
int j = 3;
```

Then, the previous statement:

```
sales[5][3] = 25.75;
```

is equivalent to:

```
sales[i][j] = 25.75;
```

So the indices can also be variables.

## Two-Dimensional Array Initialization During Declaration

Like one-dimensional arrays, two-dimensional arrays can be initialized when they are declared. The following example helps illustrate this concept. Consider the following statement:

```
int board[4][3] = {{2, 3, 1},
 {15, 25, 13},
 {20, 4, 7},
 {11, 18, 14}};
```

This statement declares `board` to be a two-dimensional array of **four** rows and **three** columns. The components of the first row are 2, 3, and 1; the components of the second row are 15, 25, and 13; the components of the third row are 20, 4, and 7; and the components of the fourth row are 11, 18, and 14, respectively. Figure 9-12 shows the array `board`.

| board | [0] | [1] | [2] |
|-------|-----|-----|-----|
| [0]   | 2   | 3   | 1   |
| [1]   | 15  | 25  | 13  |
| [2]   | 20  | 4   | 7   |
| [3]   | 11  | 18  | 14  |

FIGURE 9-12 Two-dimensional array `board`

To initialize a two-dimensional array when it is declared:

1. The elements of each row are enclosed within curly braces and separated by commas.
2. All rows are enclosed within curly braces.
3. For number arrays, if all components of a row are not specified, the unspecified components are initialized to 0. In this case, at least one of the values must be given to initialize all the components of a row.

## Two-Dimensional Arrays and Enumeration Types

### NOTE

The section “Enumeration Types” in Chapter 8 is required to understand this section.

You can also use the enumeration type for array indices. Consider the following statements:

```
const int NUMBER_OF_ROWS = 6;
const int NUMBER_OF_COLUMNS = 5;
enum carType {GM, FORD, TOYOTA, BMW, NISSAN, VOLVO};
enum colorType {RED, BROWN, BLACK, WHITE, GRAY};

int inStock[NUMBER_OF_ROWS][NUMBER_OF_COLUMNS];
```

These statements define the `carType` and `colorType` enumeration types and define `inStock` as a two-dimensional array of **six** rows and **five** columns. Suppose that each row in `inStock` corresponds to a car type, and each column in `inStock` corresponds to a color type. That is, the first row corresponds to the car type `GM`, the second row corresponds to the car type `FORD`, and so on. Similarly, the first column corresponds to the color type `RED`, the second column corresponds to the color type `BROWN`, and so on. Suppose further that each entry in `inStock` represents the number of cars of a particular type and color (see Figure 9-13).

| inStock  | [RED] | [BROWN] | [BLACK] | [WHITE] | [GRAY] |
|----------|-------|---------|---------|---------|--------|
| [GM]     |       |         |         |         |        |
| [FORD]   |       |         |         |         |        |
| [TOYOTA] |       |         |         |         |        |
| [BMW]    |       |         |         |         |        |
| [NISSAN] |       |         |         |         |        |
| [VOLVO]  |       |         |         |         |        |

**FIGURE 9-13** Two-dimensional array `inStock`

The statement:

```
inStock[1][3] = 15;
```

is equivalent to the following statement (see Figure 9-14):

```
inStock[FORD][WHITE] = 15;
```

| inStock  | [RED] | [BROWN] | [BLACK] | inStock [FORD] [WHITE] | [GRAY] |
|----------|-------|---------|---------|------------------------|--------|
| [GM]     |       |         |         |                        |        |
| [FORD]   |       |         |         | 15                     |        |
| [TOYOTA] |       |         |         |                        |        |
| [BMW]    |       |         |         |                        |        |
| [NISSAN] |       |         |         |                        |        |
| [VOLVO]  |       |         |         |                        |        |

**FIGURE 9-14** `inStock[FORD][WHITE]`

The second statement easily conveys the message—that is, set the number of **WHITE FORD** cars to 15. This example illustrates that enumeration types can be used effectively to make the program readable and easy to manage.

## PROCESSING TWO-DIMENSIONAL ARRAYS

A two-dimensional array can be processed in three ways:


1. Process the entire array.
2. Process a particular row of the array, called **row processing**.
3. Process a particular column of the array, called **column processing**.

Initializing and printing the array are examples of processing the entire two-dimensional array. Finding the largest element in a row (column) or finding the sum of a row (column) are examples of row (column) processing. We will use the following declaration for our discussion:

```
const int NUMBER_OF_ROWS = 7; //This can be set to any number.
const int NUMBER_OF_COLUMNS = 6; //This can be set to any number.

int matrix[NUMBER_OF_ROWS][NUMBER_OF_COLUMNS];
int row;
int col;
int sum;
int largest;
int temp;
```

Figure 9-15 shows the array `matrix`.



| matrix | [0] | [1] | [2] | [3] | [4] | [5] |
|--------|-----|-----|-----|-----|-----|-----|
| [0]    |     |     |     |     |     |     |
| [1]    |     |     |     |     |     |     |
| [2]    |     |     |     |     |     |     |
| [3]    |     |     |     |     |     |     |
| [4]    |     |     |     |     |     |     |
| [5]    |     |     |     |     |     |     |
| [6]    |     |     |     |     |     |     |

**FIGURE 9-15** Two-dimensional array `matrix`

Because the components of a two-dimensional array are of the same type, the components of any row or column are of the same type. This means that each row and each column of a two-dimensional array is a one-dimensional array. Therefore, when processing a particular row or column of a two-dimensional array, we use

algorithms similar to those that process one-dimensional arrays. We further explain this concept with the help of the two-dimensional array `matrix`, as declared previously.

Suppose that we want to process row number 5 of `matrix` (that is, the sixth row of `matrix`). The components of row number 5 of `matrix` are:

```
matrix[5][0], matrix[5][1], matrix[5][2], matrix[5][3], matrix[5][4],
matrix[5][5]
```

We see that in these components, the first index (the row position) is fixed at 5. The second index (the column position) ranges from 0 to 5. Therefore, we can use the following `for` loop to process row number 5:

```
for (col = 0; col < NUMBER_OF_COLUMNS; col++)
 process matrix[5][col]
```

Clearly, this `for` loop is equivalent to the following `for` loop:

```
row = 5;
for (col = 0; col < NUMBER_OF_COLUMNS; col++)
 process matrix[row][col]
```

Similarly, suppose that we want to process column number 2 of `matrix`, that is, the third column of `matrix`. The components of this column are:

```
matrix[0][2], matrix[1][2], matrix[2][2], matrix[3][2], matrix[4][2],
matrix[5][2], matrix[6][2]
```

Here, the second index (that is, the column position) is fixed at 2. The first index (that is, the row position) ranges from 0 to 6. In this case, we can use the following `for` loop to process column 2 of `matrix`:

```
for (row = 0; row < NUMBER_OF_ROWS; row++)
 process matrix[row][2]
```

Clearly, this `for` loop is equivalent to the following `for` loop:

```
col = 2;
for (row = 0; row < NUMBER_OF_ROWS; row++)
 process matrix[row][col]
```

Next, we discuss specific processing algorithms.

## Initialization

Suppose that you want to initialize row number 4, that is, the fifth row, to 0. As explained earlier, the following `for` loop does this:

```
row = 4;
for (col = 0; col < NUMBER_OF_COLUMNS; col++)
 matrix[row][col] = 0;
```

If you want to initialize the entire `matrix` to 0, you can also put the first index, that is, the row position, in a loop. By using the following nested `for` loops, we can initialize each component of `matrix` to 0:

```
for (row = 0; row < NUMBER_OF_ROWS; row++)
 for (col = 0; col < NUMBER_OF_COLUMNS; col++)
 matrix[row][col] = 0;
```

## Print

By using a nested `for` loop, you can output the components of `matrix`. The following nested `for` loops print the components of `matrix`, one row per line:

```
for (row = 0; row < NUMBER_OF_ROWS; row++)
{
 for (col = 0; col < NUMBER_OF_COLUMNS; col++)
 cout << setw(5) << matrix[row][col] << " ";

 cout << endl;
}
```

## Input

The following `for` loop inputs the data into row number 4, that is, the fifth row of `matrix`:

```
row = 4;
```

```
for (col = 0; col < NUMBER_OF_COLUMNS; col++)
 cin >> matrix[row][col];
```

As before, by putting the row number in a loop, you can input data into each component of `matrix`. The following `for` loop inputs data into each component of `matrix`:

```
for (row = 0; row < NUMBER_OF_ROWS; row++)
 for (col = 0; col < NUMBER_OF_COLUMNS; col++)
 cin >> matrix[row][col];
```

## Sum by Row

The following `for` loop finds the sum of row number 4 of `matrix`; that is, it adds the components of row number 4.

```
sum = 0;
row = 4;
for (col = 0; col < NUMBER_OF_COLUMNS; col++)
 sum = sum + matrix[row][col];
```

Once again, by putting the row number in a loop, we can find the sum of each row separately. Following is the C++ code to find the sum of each individual row:

```
//Sum of each individual row
for (row = 0; row < NUMBER_OF_ROWS; row++)
{
 sum = 0;
 for (col = 0; col < NUMBER_OF_COLUMNS; col++)
 sum = sum + matrix[row][col];

 cout << "Sum of row " << row + 1 << " = " << sum << endl;
}
```

## Sum by Column

As in the case of sum by row, the following nested `for` loop finds the sum of each individual column:

```
//Sum of each individual column
for (col = 0; col < NUMBER_OF_COLUMNS; col++)
{
 sum = 0;
 for (row = 0; row < NUMBER_OF_ROWS; row++)
 sum = sum + matrix[row][col];

 cout << "Sum of column " << col + 1 << " = " << sum
 << endl;
}
```

## Largest Element in Each Row and Each Column

As stated earlier, two other operations on a two-dimensional array are finding the largest element in each row and each column and finding the sum of both diagonals. Next, we give the C++ code to perform these operations.

The following `for` loop determines the largest element in row number 4:

```
row = 4;
largest = matrix[row][0]; //Assume that the first element of
 //the row is the largest.
for (col = 1; col < NUMBER_OF_COLUMNS; col++)
 if (largest < matrix[row][col])
 largest = matrix[row][col];
```

The following C++ code determines the largest element in each row and each column:

```
//Largest element in each row
for (row = 0; row < NUMBER_OF_ROWS; row++)
{
 largest = matrix[row][0]; //Assume that the first element
 //of the row is the largest.
 for (col = 1; col < NUMBER_OF_COLUMNS; col++)
 if (largest < matrix[row][col])
 largest = matrix[row][col];

 cout << "The largest element in row " << row + 1 << " = "
 << largest << endl;
}

//Largest element in each column
for (col = 0; col < NUMBER_OF_COLUMNS; col++)
{
 largest = matrix[0][col]; //Assume that the first element
 //of the column is the largest.
 for (row = 1; row < NUMBER_OF_ROWS; row++)
 if (largest < matrix[row][col])
 largest = matrix[row][col];

 cout << "The largest element in column " << col + 1
 << " = " << largest << endl;
}
```

## Passing Two-Dimensional Arrays as Parameters to Functions

Two-dimensional arrays can be passed as parameters to a function, and they are passed by reference. The base address (that is, the address of the first component of the actual parameter) is passed to the formal parameter. If `matrix` is the name of a two-dimensional array, then `matrix[0][0]` is the first component of `matrix`.

When storing a two-dimensional array in the computer's memory, C++ uses the **row order form**. That is, the first row is stored first, followed by the second row, followed by the third row, and so on.

In the case of a one-dimensional array, when declaring it as a formal parameter, we usually omit the size of the array. Because C++ stores two-dimensional arrays in row order form, to compute the address of a component correctly, the compiler must know where one row ends and the next row begins. Thus, when declaring a two-dimensional array as a formal parameter, you can omit the size of the first dimension, but not the second; that is, you must specify the number of columns.

Suppose we have the following declaration:

```
const int NUMBER_OF_ROWS = 6;
const int NUMBER_OF_COLUMNS = 5;
```

Consider the following definition of the function `printMatrix`:

```
void printMatrix(int matrix[] [NUMBER_OF_COLUMNS],
 int noOfRows)
{
 int row, col;

 for (row = 0; row < noOfRows; row++)
 {
 for (col = 0; col < NUMBER_OF_COLUMNS; col++)
 cout << setw(5) << matrix[row][col] << " ";

 cout << endl;
 }
}
```

This function takes as a parameter a two-dimensional array of an unspecified number of rows and five columns, and outputs the content of the two-dimensional array. During the function call, the number of columns of the actual parameter must match the number of columns of the formal parameter.

Similarly, the following function outputs the sum of the elements of each row of a two-dimensional array whose elements are of type `int`.

```
void sumRows(int matrix[] [NUMBER_OF_COLUMNS], int noOfRows)
{
 int row, col;
 int sum;

 //Sum of each individual row
 for (row = 0; row < noOfRows; row++)
```

```

 {
 sum = 0;

 for (col = 0; col < NUMBER_OF_COLUMNS; col++)
 sum = sum + matrix[row][col];

 cout << "Sum of row " << (row + 1) << " = " << sum
 << endl;
 }
}

```

The following function determines the largest element in each row:

```

void largestInRows(int matrix[][NUMBER_OF_COLUMNS],
 int noOfRows)
{
 int row, col;
 int largest;

 //Largest element in each row
 for (row = 0; row < noOfRows; row++)
 {
 largest = matrix[row][0]; //Assume that the first element
 //of the row is the largest.
 for (col = 1; col < NUMBER_OF_COLUMNS; col++)
 if (largest < matrix[row][col])
 largest = matrix[row][col];

 cout << "The largest element of row " << (row + 1)
 << " = " << largest << endl;
 }
}

```

Likewise, you can write a function to find the sum of the elements of each column, read the data into a two-dimensional array, find the largest and/or smallest element in each row or column, and so on.

Example 9-10 shows how the functions `printMatrix`, `sumRows`, and `largestInRows` are used in a program.

### EXAMPLE 9-10

The following program illustrates how two-dimensional arrays are passed as parameters to functions.

```

// Two-dimensional arrays as parameters to functions.

#include <iostream>
#include <iomanip>

using namespace std;

const int NUMBER_OF_ROWS = 6;
const int NUMBER_OF_COLUMNS = 5;

```

```

void printMatrix(int matrix[][NUMBER_OF_COLUMNS],
 int NUMBER_OF_ROWS);
void sumRows(int matrix[][NUMBER_OF_COLUMNS],
 int NUMBER_OF_ROWS);
void largestInRows(int matrix[][NUMBER_OF_COLUMNS],
 int NUMBER_OF_ROWS);

int main()
{
 int board[NUMBER_OF_ROWS][NUMBER_OF_COLUMNS]
 = {{23, 5, 6, 15, 18},
 {4, 16, 24, 67, 10},
 {12, 54, 23, 76, 11},
 {1, 12, 34, 22, 8},
 {81, 54, 32, 67, 33},
 {12, 34, 76, 78, 9}}; //Line 1

 printMatrix(board, NUMBER_OF_ROWS); //Line 2
 cout << endl; //Line 3
 sumRows(board, NUMBER_OF_ROWS); //Line 4
 cout << endl; //Line 5
 largestInRows(board, NUMBER_OF_ROWS); //Line 6

 return 0;
}

//Place the definitions of the functions printMatrix,
//sumRows, and largestInRows as described previously here.

```

### Sample Run:

|    |    |    |    |    |
|----|----|----|----|----|
| 23 | 5  | 6  | 15 | 18 |
| 4  | 16 | 24 | 67 | 10 |
| 12 | 54 | 23 | 76 | 11 |
| 1  | 12 | 34 | 22 | 8  |
| 81 | 54 | 32 | 67 | 33 |
| 12 | 34 | 76 | 78 | 9  |

```

Sum of row 1 = 67
Sum of row 2 = 121
Sum of row 3 = 176
Sum of row 4 = 77
Sum of row 5 = 267
Sum of row 6 = 209

```

```

The largest element in row 1 = 23
The largest element in row 2 = 67
The largest element in row 3 = 76
The largest element in row 4 = 34
The largest element in row 5 = 81
The largest element in row 6 = 78

```

In this program, the statement in Line 1 declares and initializes `board` to be a two-dimensional array of six rows and five columns. The statement in Line 2 uses the

function `printMatrix` to output the elements of `board` (see the first six lines of the Sample Run). The statement in Line 4 uses the function `sumRows` to calculate and print the sum of each row. The statement in Line 6 uses the function `largestInRows` to find and print the largest element in each row.

# Arrays of Strings

Suppose that you need to perform an operation, such as alphabetizing a list of names. Because every name is a string, a convenient way to store the list of names is to use an array. Strings in C++ can be manipulated using either the data type `string` or character arrays (C-strings). Also, on some compilers, the data type `string` may not be available in Standard C++ (that is, non-ANSI/ISO Standard C++). This section illustrates both ways to manipulate a list of strings.

## Arrays of Strings and the `string` Type

Processing a list of strings using the data type `string` is straightforward. Suppose that the list consists of a maximum of 100 names. You can declare an array of 100 components of type `string` as follows:

```
string list[100];
```

Basic operations, such as assignment, comparison, and input/output, can be performed on values of the `string` type. Therefore, the data in `list` can be processed just like any one-dimensional array discussed in the first part of this chapter.

## Arrays of Strings and C-Strings (Character Arrays)

Suppose that the largest string (for example, name) in your list is 15 characters long and your list has 100 strings. You can declare a two-dimensional array of characters of 100 rows and 16 columns as follows (see Figure 9-16):

```
char list[100][16];
```




FIGURE 9-16 Array `list` of strings

Now `list[j]` for each `j`,  $0 \leq j \leq 99$ , is a string of at most 15 characters in length. The following statement stores "Snow White" in `list[1]` (see Figure 9-17):

```
strcpy(list[1], "Snow White");
```




FIGURE 9-17 Array `list`, showing `list[1]`

Suppose that you want to read and store data in `list` and that there is one entry per line. The following `for` loop accomplishes this task:

```
for (j = 0; j < 100; j++)
 cin.get(list[j], 16);
```

The following `for` loop outputs the string in each row:

```
for (j = 0; j < 100; j++)
 cout << list[j] << endl;
```

You can also use other string functions (such as `strcmp` and `strlen`) and `for` loops to manipulate `list`.

#### NOTE

The data type `string` has operations such as assignment, concatenation, and relational operations defined for it. If you use Standard C++ header files and the data type `string` is available on your compiler, we recommend that you use the data type `string` to manipulate lists of strings.

## Another Way to Declare a Two-Dimensional Array

#### NOTE

This section may be skipped without any loss of continuity.

If you know the size of the tables with which the program will be working, then you can use `typedef` to first define a two-dimensional array data type and then declare variables of that type.

For example, consider the following:

```
const int NUMBER_OF_ROWS = 20;
const int NUMBER_OF_COLUMNS = 10;
```

```
typedef int tableType[NUMBER_OF_ROWS][NUMBER_OF_COLUMNS];
```

The previous statement defines a two-dimensional array data type `tableType`. Now we can declare variables of this type. So:

```
tableType matrix;
```

declares a two-dimensional array `matrix` of 20 rows and 10 columns.

You can also use this data type when declaring formal parameters, as shown in the following code:

```
void initialize(tableType table)
{
 int row;
 int col;

 for (row = 0; row < NUMBER_OF_ROWS; row++)
 for (col = 0; col < NUMBER_OF_COLUMNS; col++)
 table[row][col] = 0;
}
```

This function takes as an argument any variable of type `tableType`, which is a two-dimensional array, and initializes the array to 0.

By first defining a data type, you do not need to keep checking the exact number of columns when you declare a two-dimensional array as a variable or formal parameter, or when you pass an array as a parameter during a function call.

## Multidimensional Arrays

In this chapter, we defined an array as a collection of a fixed number of elements (called components) of the same type. A one-dimensional array is an array in which the elements are arranged in a list form; in a two-dimensional array, the elements are arranged in a table form. We can also define three-dimensional or larger arrays. In C++, there is no limit on the dimension of arrays. Following is the general definition of an array.

***n*-dimensional array:** A collection of a fixed number of elements (called components) arranged in *n* dimensions (*n* ≥ 1).

The general syntax for declaring an  $n$ -dimensional array is:

```
dataType arrayName[intExp1][intExp2] ... [intExpn];
```

where `intExp1`, `intExp2`, ..., and `intExpn` are constant expressions yielding positive integer values.

The syntax to access a component of an  $n$ -dimensional array is:

```
arrayName[indexExp1][indexExp2] ... [indexExpn]
```

where `indexExp1`, `indexExp2`, ..., and `indexExpn` are expressions yielding non-negative integer values. `indexExp $i$`  gives the position of the array component in the  $i$ th dimension.

For example, the statement:

```
double carDealers[10][5][7];
```

declares `carDealers` to be a three-dimensional array. The size of the first dimension is 10, the size of the second dimension is 5, and the size of the third dimension is 7. The first dimension ranges from 0 to 9, the second dimension ranges from 0 to 4, and the third dimension ranges from 0 to 6. The base address of the array `carDealers` is the address of the first array component—that is, the address of `carDealers[0][0][0]`. The total number of components in the array `carDealers` is  $10 * 5 * 7 = 350$ .

The statement:

```
carDealers[5][3][2] = 15564.75;
```

sets the value of the component `carDealers[5][3][2]` to 15564.75.

You can use loops to process multidimensional arrays. For example, the nested `for` loops:

```
for (i = 0; i < 10; i++)
 for (j = 0; j < 5; j++)
 for (k = 0; k < 7; k++)
 carDealers[i][j][k] = 0.0;
```

initialize the entire array to 0.0.

When declaring a multidimensional array as a formal parameter in a function, you can omit the size of the first dimension but not the other dimensions. As parameters, multidimensional arrays are passed by reference only, and a function cannot return a value of the array type. There is no check to determine whether the array indices are within bounds.

PROGRAMMING EXAMPLE: Code Detection

When a message is transmitted in secret code over a transmission channel, it is usually sent as a sequence of bits, that is, 0s and 1s. Due to noise in the transmission channel, the transmitted message may become corrupted. That is, the message received at the destination is not the same as the message transmitted; some of the bits may have been changed. There are several techniques to check the validity of the transmitted message at the destination. One technique is to transmit the same message twice. At the destination, both copies of the message are compared bit by bit. If the corresponding bits are the same, the message received is error-free.

Let’s write a program to check whether the message received at the destination is error-free. For simplicity, assume that the secret code representing the message is a sequence of digits (0 to 9) and the maximum length of the message is 250 digits. Also, the first number in the message is the length of the message. For example, if the secret code is:

7 9 2 7 8 3 5 6

then the actual message is 7 digits long, and it is transmitted twice.

The above message is transmitted as:

7 9 2 7 8 3 5 6 7 9 2 7 8 3 5 6

**Input**     A file containing the secret code and its copy

**Output**    The secret code, its copy, and a message—if the received code is error-free—in the following form:

| Code | Digit | Code | Digit | Copy |
|------|-------|------|-------|------|
|      | 9     |      | 9     |      |
|      | 2     |      | 2     |      |
|      | 7     |      | 7     |      |
|      | 8     |      | 8     |      |
|      | 3     |      | 3     |      |
|      | 5     |      | 5     |      |
|      | 6     |      | 6     |      |

Message transmitted OK.

PROBLEM  
ANALYSIS  
AND  
ALGORITHM  
DESIGN

Because we have to compare the corresponding digits of the secret code and its copy, we first read the secret code and store it in an array. Then we read the first digit of the copy and compare it with the first digit of the secret code, and so on. If any of the corresponding digits are not the same, we indicate this fact by printing a message next to the digits. Because the maximum length of the message is 250, we use an array of 250 components. The first number in the secret code, and in the copy of the secret code, indicates the length of the code. This discussion translates into the following algorithm:

1. Open the input and output files.
2. If the input file does not exist, exit the program.
3. Read the length of the secret code.
4. If the length of the secret code is greater than 250, terminate the program because the maximum length of the code in this program is 250.
5. Read and store the secret code into an array.
6. Read the length of the copy.
7. If the length of the secret code and its copy are the same, compare the codes. Otherwise, print an error message.

To simplify the function `main`, let us write a function, `readCode`, to read the secret code and another function, `compareCode`, to compare the codes.

`readCode` This function first reads the length of the secret code. If the length of the secret code is greater than 250, a `bool` variable `lenCodeOk`, which is a reference parameter, is set to `false` and the function terminates. The value of `lenCodeOk` is passed to the calling function to indicate whether the secret code was read successfully. If the length of the code is less than 250, the `readCode` function reads and stores the secret code into an array. Because the input is stored into a file and the file was opened in the function `main`, the input stream variable corresponding to the input file must be passed as a parameter to this function. Furthermore, after reading the length of the secret code and the code itself, the `readCode` function must pass these values to the function `main`. Therefore, this function has four parameters: an input file stream variable, an array to store the secret code, the length of the code, and the `bool` parameter `lenCodeOk`. The definition of the function `readCode` is as follows:

```
void readCode(ifstream& infile, int list[], int& length,
 bool& lenCodeOk)
{
 int count;

 lenCodeOk = true;

 infile >> length; //get the length of the secret code

 if (length > MAX_CODE_SIZE)
 {
 lenCodeOk = false;
 return;
 }

 //Get the secret code.
 for (count = 0; count < length; count++)
 infile >> list[count];
}
```

**compareCode** This function compares the secret code with its copy. Therefore, it must have access to the array containing the secret code and the length of the secret code. The copy of the secret code and its length are stored in the input file. Thus, the input stream variable corresponding to the input file must be passed as a parameter to this function. Also, the **compareCode** function compares the secret code with the copy and prints an appropriate message. Because the output will be stored in a file, the output stream variable corresponding to the output file must also be passed as a parameter to this function. Therefore, the function has four parameters: an input file stream variable, an output file stream variable, the array containing the secret code, and the length of the secret code. This discussion translates into the following algorithm for the function **compareCode**:

- a. Declare the variables.
- b. Set a **bool** variable **codeOk** to **true**.
- c. Read the length of the copy of the secret code.
- d. If the length of the secret code and its copy are not the same, output an appropriate error message and terminate the function.
- e. For each digit in the input file:
  - e.1. Read the next digit of the copy of the secret code.
  - e.2. Output the corresponding digits from the secret code and its copy.
  - e.3. If the corresponding digits are not the same, output an error message and set the **bool** variable **codeOk** to **false**.
- f. If the **bool** variable **codeOk** is **true**

Output a message indicating that the secret code was transmitted correctly.

else

Output an error message.

Following this algorithm, the definition of the function **compareCode** is:

```
void compareCode(ifstream& infile, ofstream& outfile,
 const int list[], int length)
{
 //Step a
 int length2;
 int digit;
 bool codeOk;
 int count;

 codeOk = true; //Step b

 infile >> length2; //Step c
```

```

if (length != length2) //Step d
{
 cout << "The original code and its copy "
 << "are not of the same length."
 << endl;
 return;
}

outfile << "Code Digit Code Digit Copy"
 << endl;

for (count = 0; count < length; count++) //Step e
{
 infile >> digit; //Step e.1
 outfile << setw(5) << list[count]
 << setw(17) << digit; //Step e.2

 if (digit != list[count]) //Step e.3
 {
 outfile << " code digits are not the same"
 << endl;
 codeOk = false;
 }
 else
 outfile << endl;
}

if (codeOk) //Step f
 outfile << "Message transmitted OK."
 << endl;
else
 outfile << "Error in transmission. "
 << "Retransmit!!" << endl;
}

```

Following is the algorithm for the function main.

#### Main Algorithm

1. Declare the variables.
2. Open the files.
3. Call the function `readCode` to read the secret code.
4. `if` (length of the secret code  $\leq$  250)
  - Call the function `compareCode` to compare the codes.
- `else`
  - Output an appropriate error message.

```

//*****
// Author: D.S. Malik
//
// Program: Check Code
// This program determines whether a code is transmitted
// correctly.
//*****

#include <iostream>
#include <fstream>
#include <iomanip>

using namespace std;

const int MAX_CODE_SIZE = 250;

void readCode(ifstream& infile, int list[],
 int& length, bool& lenCodeOk);
void compareCode(ifstream& infile, ofstream& outfile,
 const int list[], int length);

int main()
{
 //Step 1
 int codeArray[MAX_CODE_SIZE]; //array to store the secret
 //code
 int codeLength; //variable to store the
 //length of the secret code
 bool lengthCodeOk; //variable to indicate if the length
 //of the secret code is less than or
 //equal to 250

 ifstream incode; //input file stream variable
 ofstream outcode; //output file stream variable

 char inputFile[51]; //variable to store the name of the
 //input file
 char outputFile[51]; //variable to store the name of
 //the output file

 cout << "Enter the input file name: ";
 cin >> inputFile;
 cout << endl;

 //Step 2
 incode.open(inputFile);
 if (!incode)
 {
 cout << "Cannot open the input file." << endl;
 return 1;
 }
}

```

```

 cout << "Enter the output file name: ";
 cin >> outputFile;
 cout << endl;

 outcode.open(outputFile);

 readCode(incode, codeArray, codeLength,
 lengthCodeOk); //Step 3

 if (lengthCodeOk) //Step 4
 compareCode(incode, outcode, codeArray,
 codeLength);

 else
 cout << "Length of the secret code "
 << "must be <= " << MAX_CODE_SIZE
 << endl; //Step 5

 incode.close();
 outcode.close();

 return 0;
}

//Place the definitions of the functions readCode and
//compareCode, as described previously, here.

```

**Sample Run:** In this sample run, the user input is shaded.

Enter the input file name: Ch9\_SecretCodeData.txt

Enter the output file name: Ch9\_SecretCodeOut.txt

**Input File Data:** (Ch9\_SecretCodeData.txt)

7 9 2 7 8 3 5 6 7 9 2 7 8 3 5 6

**Output File Data:** (Ch9\_SecretCodeOut.txt)

| Code Digit | Code Digit Copy |
|------------|-----------------|
| 9          | 9               |
| 2          | 2               |
| 7          | 7               |
| 8          | 8               |
| 3          | 3               |
| 5          | 5               |
| 6          | 6               |

Message transmitted OK.

## PROGRAMMING EXAMPLE: Text Processing

**(Line and letter count)** Let us now write a program that reads a given text, outputs the text as is, and also prints the number of lines and the number of times each letter appears in the text. An uppercase letter and a lowercase letter are treated as being the same; that is, they are tallied together.

Because there are 26 letters, we use an array of 26 components to perform the letter count. We also need a variable to store the line count.

The text is stored in a file, which we will call `textin.txt`. The output will be stored in a file, which we will call `textout.out`.

**Input** A file containing the text to be processed.

**Output** A file containing the text, number of lines, and the number of times a letter appears in the text.

### PROBLEM ANALYSIS AND ALGORITHM DESIGN

Based on the desired output, it is clear that we must output the text as is. That is, if the text contains any whitespace characters, they must be output as well. Furthermore, we must count the number of lines in the text. Therefore, we must know where the line ends, which means that we must trap the newline character. This requirement suggests that we cannot use the extraction operator to process the input file. Because we also need to perform the letter count, we use the `get` function to read the text.

Let us first describe the variables that are necessary to develop the program. This will simplify the discussion that follows.

**Variables** We need to store the line count and the letter count. Therefore, we need a variable to store the line count and 26 variables to perform the letter count. We will use an array of 26 components to perform the letter count. We also need a variable to read and store each character in turn, because the input file is to be read character by character. Because data is to be read from an input file and output is to be saved in a file, we need an input stream variable to open the input file and an output stream variable to open the output file. These statements indicate that the function `main` needs (at least) the following variables:

```
int lineCount; //variable to store the line count
int letterCount[26]; //array to store the letter count
char ch; //variable to store a character
ifstream infile; //input file stream variable
ofstream outfile; //output file stream variable
```

In this declaration, `letterCount[0]` stores the A count, `letterCount[1]` stores the B count, and so on. Clearly, the variable `lineCount` and the array `letterCount` must be initialized to 0.

The algorithm for the program is:

1. Declare the variables.
2. Open the input and output files.
3. Initialize the variables.
4. While there is more data in the input file:
  - 4.1. For each character in a line:
    - 4.1.1. Read and write the character.
    - 4.1.2. Increment the appropriate letter count.
  - 4.2. Increment the line count.
5. Output the line count and letter counts.
6. Close the files.

To simplify the function `main`, we divide it into four functions:

- Function `initialize`
- Function `copyText`
- Function `characterCount`
- Function `writeTotal`

The following sections describe each of these functions in detail. Then, with the help of these functions, we describe the algorithm for the function `main`.

**initialize** This function initializes the variable `lineCount` and the array `letterCount` to 0. It, therefore, has two parameters: one corresponding to the variable `lineCount` and one corresponding to the array `letterCount`. Clearly, the parameter corresponding to `lineCount` must be a reference parameter. The definition of this function is:

```
void initialize(int& lc, int list[])
{
 int j;
 lc = 0;

 for (j = 0; j < 26; j++)
 list[j] = 0;
} //end initialize
```

**copyText** This function reads a line and outputs the line. After reading a character, it calls the function `characterCount` to update the letter count. Clearly, this function has four parameters: an input file stream variable, an output file stream variable, a `char` variable, and the array to update the letter count.

Note that the `copyText` function does not perform the `letter count`, but we still pass the array `letterCount` to it. We take this step because this function calls the

function `characterCount`, which needs the array `letterCount` to update the appropriate letter count. Therefore, we must pass the array `letterCount` to the `copyText` function so that it can pass the array to the function `characterCount`.

```
void copyText(ifstream& inText, ofstream& outText, char& ch,
 int list[])
{
 while (ch != '\n') //process the entire line
 {
 outText << ch; //output the character
 characterCount(ch, list); //call the function
 //character count
 inText.get(ch); //read the next character
 }
 outText << '\n'; //output the newline character
} //end copyText
```

**characterCount** This function increments the letter count. To increment the appropriate letter count, it must know what the letter is. Therefore, the `characterCount` function has two parameters: a `char` variable and the array to update the letter count. In pseudocode, this function is:

- a. Convert the letter to uppercase.
- b. Find the index of the array corresponding to this letter.
- c. If the index is valid, increment the appropriate count. At this step, we must ensure that the character is a letter. We are counting only letters, so other characters—such as commas, hyphens, and periods—are ignored.

Following this algorithm, the definition of this function is:

```
void characterCount(char ch, int list[])
{
 int index;

 ch = toupper(ch); //Step a

 index = static_cast<int>(ch)
 - static_cast<int>('A'); //Step b

 if (0 <= index && index < 26) //Step c
 list[index]++;
} //end characterCount
```

**writeTotal** This function outputs the line count and the letter count. It has three parameters: the output file stream variable, the line count, and the array to output the letter count. The definition of this function is:

```

void writeTotal(ofstream& outtext, int lc, int list[])
{
 int index;

 outtext << endl << endl;
 outtext << "The number of lines = " << lc << endl;

 for (index = 0; index < 26; index++)
 outtext << static_cast<char>(index
 + static_cast<int>('A'))
 << " count = " << list[index] << endl;
} //end writeTotal

```

We now describe the algorithm for the function `main`.

#### MAIN ALGORITHM

1. Declare the variables.
2. Open the input file.
3. If the input file does not exist, exit the program.
4. Open the output file.
5. Initialize the variables, such as `lineCount` and the array `letterCount`.
6. Read the first character.
7. While (not end of input file):
  - 7.1. Process the next line; call the function `copyText`.
  - 7.2. Increment the line count. (Increment the variable `lineCount`.)
  - 7.3. Read the next character.
8. Output the line count and letter counts. Call the function `writeTotal`.
9. Close the files.

#### COMPLETE PROGRAM LISTING

```

//*****
// Author: D.S. Malik
//
// Program: Line and Letter Count
// This programs reads a text, outputs the text as is, and also
// prints the number of lines and the number of times each
// letter appears in the text. An uppercase letter and a
// lowercase letter are treated as being the same; that is,
// they are tallied together.
//*****

```

```

#include <iostream>
#include <fstream>
#include <cctype>

using namespace std;

void initialize(int& lc, int list[]);
void copyText(ifstream& intext, ofstream& outtext, char& ch,
 int list[]);
void characterCount(char ch, int list[]);
void writeTotal(ofstream& outtext, int lc, int list[]);

int main()
{
 //Step 1: Declare variables
 int lineCount;
 int letterCount[26];
 char ch;
 ifstream infile;
 ofstream outfile;

 infile.open("textin.txt"); //Step 2

 if (!infile) //Step 3
 {
 cout << "Cannot open the input file."
 << endl;
 return 1;
 }

 outfile.open("textout.out"); //Step 4

 initialize(lineCount, letterCount); //Step 5

 infile.get(ch); //Step 6

 while (infile) //Step 7
 {
 copyText(infile, outfile, ch, letterCount); //Step 7.1
 lineCount++; //Step 7.2
 infile.get(ch); //Step 7.3
 }

 writeTotal(outfile, lineCount, letterCount); //Step 8

 infile.close(); //Step 9
 outfile.close(); //Step 9

 return 0;
}

```

```

void initialize(int& lc, int list[])
{
 int j;
 lc = 0;

 for (j = 0; j < 26; j++)
 list[j] = 0;
} //end initialize

void copyText(ifstream& intext, ofstream& outtext, char& ch,
 int list[])
{
 while (ch != '\n') //process the entire line
 {
 outtext << ch; //output the character

 characterCount(ch, list); //call the function
 //character count
 intext.get(ch); //read the next character
 }

 outtext << ch; //output the newline character
} //end copyText

void characterCount(char ch, int list[])
{
 int index;

 ch = toupper(ch); //Step a

 index = static_cast<int>(ch)
 - static_cast<int>('A'); //Step b

 if (0 <= index & index < 26) //Step c
 list[index]++;
} //end characterCount

void writeTotal(ofstream& outtext, int lc, int list[])
{
 int index;

 outtext << endl << endl;
 outtext << "The number of lines = " << lc << endl;

 for (index = 0; index < 26; index++)
 outtext << static_cast<char>(index
 + static_cast<int>('A'))
 << " count = " << list[index] << endl;
} //end writeTotal

```

**Sample Run (textout.out):**

Today we live in an era where information is processed almost at the speed of light. Through computers, the technological revolution is drastically changing the way we live and communicate with one another. Terms such as "the Internet," which were unfamiliar just a few years ago, are very common today. With the help of computers you can send letters to, and receive letters from, loved ones within seconds. You no longer need to send a résumé by mail to apply for a job; in many cases you can simply submit your job application via the Internet. You can watch how stocks perform in real time, and instantly buy and sell them. Students regularly "surf" the Internet and use computers to design their classroom projects. They also use powerful word-processing software to complete their term papers. Many people maintain and balance their checkbooks on computers.

The number of lines = 15

A count = 53  
B count = 7  
C count = 30  
D count = 19  
E count = 81  
F count = 11  
G count = 10  
H count = 29  
I count = 41  
J count = 4  
K count = 3  
L count = 31  
M count = 26  
N count = 50  
O count = 59  
P count = 21  
Q count = 0  
R count = 45  
S count = 48  
T count = 62  
U count = 24  
V count = 7  
W count = 15  
X count = 0  
Y count = 20  
Z count = 0

## QUICK REVIEW

---

1. A data type is simple if variables of that type can hold only one value at a time.
2. In a structured data type, each data item is a collection of other data items.
3. An array is a structured data type with a fixed number of components. Every component is of the same type, and components are accessed using their relative positions in the array.
4. Elements of a one-dimensional array are arranged in the form of a list.
5. There is no check on whether an array index is out of bounds.
6. In C++, an array index starts with 0.
7. An array index can be any expression that evaluates to a nonnegative integer. The value of the index must always be less than the size of the array.
8. There are no aggregate operations on arrays, except for the input/output of character arrays (C-strings).
9. Arrays can be initialized during their declaration. If there are fewer initial values than the array size, the remaining elements are initialized to 0.
10. The base address of an array is the address of the first array component. For example, if `list` is a one-dimensional array, the base address of `list` is the address of `list[0]`.
11. When declaring a one-dimensional array as a formal parameter, you usually omit the array size. If you specify the size of a one-dimensional array in the formal parameter declaration, the compiler will ignore the size.
12. In a function call statement, when passing an array as an actual parameter, you use only its name.
13. As parameters to functions, arrays are passed by reference only.
14. Because as parameters, arrays are passed by reference only, when declaring an array as a formal parameter, you do not use the symbol `&` after the data type.
15. A function cannot return a value of type array.
16. Although as parameters, arrays are passed by reference, when declaring an array as a formal parameter, using the reserved word `const` before the data type prevents the function from modifying the array.
17. Individual array components can be passed as parameters to functions.
18. The sequential search algorithm searches a list for a given item, starting with the first element in the list. It continues to compare the search item with the other elements in the list until either the item is found or the list has no more elements left to be compared with the search item.
19. In C++, a string is any sequence of characters enclosed between double quotation marks.
20. In C++, C-strings are null terminated.

21. In C++, the null character is represented as `'\0'`.
22. In the ASCII character set, the collating sequence of the null character is 0.
23. C-strings are stored in character arrays.
24. Character arrays can be initialized during declaration using string notation.
25. Input and output of C-strings is the only place where C++ allows aggregate operations.
26. The header file `cstring` contains the specifications of the functions that can be used for C-string manipulation.
27. Commonly used C-string manipulation functions include `strcpy` (string copy), `strcmp` (string comparison), and `strlen` (string length).
28. C-strings are compared character by character.
29. Because C-strings are stored in arrays, individual characters in the C-string can be accessed using the array component access notation.
30. Parallel arrays are used to hold related information.
31. In a two-dimensional array, the elements are arranged in a table form.
32. To access an element of a two-dimensional array, you need a pair of indices: one for the row position and one for the column position.
33. In a two-dimensional array, the rows are numbered 0 to `ROW_SIZE - 1` and the columns are numbered 0 to `COLUMN_SIZE - 1`.
34. If `matrix` is a two-dimensional array, then the base address of `matrix` is the address of the array component `matrix[0][0]`.
35. In row processing, a two-dimensional array is processed one row at a time.
36. In column processing, a two-dimensional array is processed one column at a time.
37. When declaring a two-dimensional array as a formal parameter, you can omit the size of the first dimension but not the second.
38. When a two-dimensional array is passed as an actual parameter, the number of columns of the actual and formal arrays must match.
39. C++ stores, in computer memory, two-dimensional arrays in a row order form.

## EXERCISES

---

1. Mark the following statements as true or false.
  - a. A `double` type is an example of a simple data type.
  - b. A one-dimensional array is an example of a structured data type.
  - c. Arrays can be passed as parameters to a function either by value or by reference.

- d. A function can return a value of type array.
- e. The size of an array is determined at compile time.
- f. The only aggregate operations allowable on `int` arrays are the increment and decrement operations.
- g. Given the declaration:
 

```
int list[10];
```

 the statement:
 

```
list[5] = list[3] + list[2];
```

 updates the content of the fifth component of the array `list`.
- h. If an array index goes out of bounds, the program always terminates in an error.
- i. In C++, some aggregate operations are allowed for strings.
- j. The declaration:
 

```
char name[16] = "John K. Miller";
```

 declares `name` to be an array of 15 characters because the string "John K. Miller" has only 14 characters.
- k. The declaration:
 

```
char str = "Sunny Day";
```

 declares `str` to be a string of an unspecified length.
- l. As parameters, two-dimensional arrays are passed either by value or by reference.

2. Consider the following declaration:

```
double salary[10];
```

In this declaration, identify the following:

- a. The array name.
  - b. The array size.
  - c. The data type of each array component.
  - d. The range of values for the index of the array.
3. Identify error(s), if any, in the following array declarations.
- a. `int list[10];`
  - b. `constint size = 100;`  
`double list[SIZE];`
  - c. `int numList[0..9];`
  - d. `string names[20];`
  - e. `scores[50] double;`

4. Determine whether the following array declarations are valid. If a declaration is invalid, explain why.

- a. `int list75;`
- b. `int size;`  
`double list[size];`
- c. `int test[-10];`
- d. `double sales[40.5];`

5. What would be a valid range for the index of an array of size 50?

6. Write C++ statements to do the following:

- a. Declare an array `alpha` of 15 components of type `int`.
- b. Output the value of the tenth component of the array `alpha`.
- c. Set the value of the fifth component of the array `alpha` to 35.
- d. Set the value of the ninth component of the array `alpha` to the sum of the sixth and thirteenth components of the array `alpha`.
- e. Set the value of the fourth component of the array `alpha` to three times the value of the eighth component minus 57.
- f. Output `alpha` so that five components per line are printed.

7. What is the output of the following program segment?

```
int temp[5];

for (int i = 0; i < 5; i++)
 temp[i] = 2 * i - 3;

for (int i = 0; i < 5; i++)
 cout << temp[i] << " ";
cout << endl;

temp[0] = temp[4];
temp[4] = temp[1];
temp[2] = temp[3] + temp[0];

for (int i = 0; i < 5; i++)
 cout << temp[i] << " ";
cout << endl;
```

8. Suppose `list` is an array of five components of type `int`. What is stored in `list` after the following C++ code executes?

```
for (int i = 0; i < 5; i++)
{
 list[i] = 2 * i + 5;
 if (i % 2 == 0)
 list[i] = list[i] - 3;
}
```

9. Suppose `list` is an array of six components of type `int`. What is stored in `list` after the following C++ code executes?

```
list[0] = 5;
for (int i = 1; i < 6; i++)
{
 list[i] = i * i + 5;
 if (i > 2)
 list[i] = 2 * list[i] - list[i - 1];
}
```

10. Correct the following code so that it correctly initializes and outputs the elements of the array.

```
myList;

int myList[10];

for (int i = 1; i <= 10; i++)
 cin >> myList;

for (int i = 1; i <= 10; i++)
 cout << myList[i] << " ";
cout << endl;
```

11. What is array index out of bounds? Does C++ check for array indices within bounds?

12. Suppose that `scores` is an array of 10 components of type `double`, and:

```
scores = {2.5, 3.9, 4.8, 6.2, 6.2, 7.4, 7.9, 8.5, 8.5, 9.9}
```

The following is supposed to ensure that the elements of `scores` are in nondecreasing order. However, there are errors in the code. Find and correct the errors.

```
for (int i = 1; i <= 10; i++)
 if (scores[i] >= scores[i + 1])
 cout << i << " and " << (i + 1)
 << " elements of scores are out of order." << endl;
```

13. Write C++ statements to define and initialize the following arrays.

- Array `heights` of 10 components of type `double`. Initialize this array to the following values: 5.2, 6.3, 5.8, 4.9, 5.2, 5.7, 6.7, 7.1, 5.10, 6.0.
- Array `weights` of 7 components of type `int`. Initialize this array to the following values: 120, 125, 137, 140, 150, 180, 210.
- Array `specialSymbols` of type `char`. Initialize this array to the following values: '\$', '#', '%', '@', '&', '!', '^'.
- Array `seasons` of 4 components of type `string`. Initialize this array to the following values: "fall", "winter", "spring", "summer".

14. Determine whether the following array declarations are valid.

- a. `int a[5] = {0, 4, 3, 2, 7};`
- b. `int b[10] = {0, 7, 3, 12};`
- c. `int c[7] = {12, 13, , 14, 16, , 8};`
- d. `double lengths[] = {12.7, 13.9, 18.75, 20.78};`
- e. `char name[8] = "Samantha";`

15. Suppose that you have the following declaration:

```
int list[10] = {8, 9, 15, 12, 80};
```

What is stored in each of the components of `list`.

16. What is the output of the following code?

```
int list[] = {6, 8, 2, 14, 13};

for (int i = 0; i < 4; i++)
 list[i] = list[i] - list[i + 1];

for (int i = 0; i < 5; i++)
 cout << i << " " << list[i] << endl;
```

17. Consider the following function heading:

```
void tryMe(int x[], int size);
```

and the declarations:

```
int list[100];
int score[50];
double gpas[50];
```

Which of the following function calls is valid?

- a. `tryMe(list, 100);`
- b. `tryMe(list, 75);`
- c. `tryMe(score, 100);`
- d. `tryMe(score, 49);`
- e. `tryMe(gpa, 50);`

18. Suppose that you have the following function definition.

```
void sum(int x, int y, int& z)
{
 z = x + y;
}
```

Consider the following declarations:

```
int list1[10], list2[10], list3[10];
int a, b, c;
```

Which of the following function calls is valid?

- a. `sum(a, b, c);`
- b. `sum(list1[0], list2[0], a);`
- c. `sum(list1, list2, c);`
- d. `for (int i = 1; i <= 10; i++)  
    sum(list1[i], list2[i], list[3]);`

19. What is the output of the following C++ code?

```
double salary[5] = {25000, 36500, 85000, 62500, 97000};
double raise = 0.03;

cout << fixed << showpoint << setprecision(2);

for (int i = 0; i < 5; i++)
 cout << (i + 1) << " " << salary[i] << " "
 << salary[i] * raise << endl;
```

20. A car dealer has 10 salespersons. Each salesperson keeps track of the number of cars sold each month and reports it to the management at the end of the month. The management keeps the data in a file and assigns a number, 1 to 10, to each salesperson. The following statement declares an array, `cars`, of 10 components of type `int` to store the number of cars sold by each salesperson.

```
int cars[10];
```

Write the code to store the number of cars sold by each salesperson in the array `cars`, output the total numbers of cars sold at the end of each month, and output the salesperson number selling the maximum number cars. (Assume that data is in the file `cars.dat`, and this file has been opened using the `ifstream` variable `inFile`.)

21. What is the output of the following program?

```
#include <iostream>

using namespace std;

int main()
{
 int count;
 int alpha[5];

 alpha[0] = 5;
 for (count = 1; count < 5; count++)
 {
 alpha[count] = 5 * count + 10;
 alpha[count - 1] = alpha[count] - 4;
 }
}
```

```

 cout << "List elements: ";
 for (count = 0; count < 5; count++)
 cout << alpha[count] << " ";
 cout << endl;

 return 0;
}

```

22. What is the output of the following program?

```

#include <iostream>

using namespace std;

int main()
{
 int j;
 int one[5];
 int two[10];

 for (j = 0; j < 5; j++)
 one[j] = 5 * j + 3;

 cout << "One contains: ";
 for (j = 0; j < 5; j++)
 cout << one[j] << " ";
 cout << endl;
 for (j = 0; j < 5; j++)
 {
 two[j] = 2 * one[j] - 1;
 two[j + 5] = one[4 - j] + two[j];
 }

 cout << "Two contains: ";
 for (j = 0; j < 10; j++)
 cout << two[j] << " ";
 cout << endl;

 return 0;
}

```

23. What is the output of the following C++ code?

```

const double PI = 3.14159;
double cylinderRadii[5] = {3.5, 7.2, 10.5, 9.8, 6.5};
double cylinderHeights[5] = {10.7, 6.5, 12.0, 10.5, 8.0};
double cylinderVolumes[5];

cout << fixed << showpoint << setprecision(2);

for (int i = 0; i < 5; i++)
 cylinderVolumes[i] = 2 * PI * cylinderRadii[i]
 * cylinderHeights[i];

for (int i = 0; i < 5; i++)
 cout << (i + 1) << " " << cylinderRadii[i] << " "
 << cylinderHeights[i] << " " << cylinderVolumes[i] << endl;

```

24. When an array is passed as an actual parameter to a function, what is actually being passed?
25. In C++, as an actual parameter, can an array be passed by value?
26. Given the declaration:

```
char string15[16];
```

mark the following statements as valid or invalid. If a statement is invalid, explain why.

- a. `strcpy(string15, "Hello there");`
- b. `strlen(string15);`
- c. `string15 = "Jacksonville";`
- d. `cin >> string15;`
- e. `cout << string15;`
- f. `if (string15 >= "Nice day")  
 cout << string15;`
- g. `string15[6] = 't';`

27. Given the declaration:

```
char str1[15];
char str2[15] = "Good day";
```

mark the following statements as valid or invalid. If a statement is invalid, explain why.

- a. `str1 = str2;`
- b. `if (str1 == str2)  
 cout << " Both strings are of the same length." << endl;`
- c. `if (strlen(str1) >= strlen(str2))  
 str1 = str2;`
- d. `if (strcmp(str1, str2) < 0)  
 cout << "str1 is less than str2." << endl;`

28. Given the declaration:

```
char name[8] = "Shelly";
```

mark the following statements as “Yes” if they output `Shelly`. Otherwise, mark the statement as “No” and explain why it does not output `Shelly`.

- a. `cout << name;`
- b. `for (int j = 0; j < 6; j++)  
 cout << name[j];`
- c. `int j = 0;  
while (name[j] != '\0')  
 cout << name[j++];`
- d. `int j = 0;  
while (j < 8)  
 cout << name[j++];`

29. Given the declaration:

```
char str1[21];
char str2[21];
```

- Write a C++ statement that stores "Sunny Day" in `str1`.
- Write a C++ statement that stores the length of `str1` into the `int` variable `length`.
- Write a C++ statement that copies the value of `name` into `str2`.
- Write C++ code that outputs `str1` if `str1` is less than or equal to `str2`, and otherwise outputs `str2`.

30. Assume the following declarations:

```
char name[21];
char yourName[21];
char studentName[31];
```

Mark the following statements as valid or invalid. If a statement is invalid, explain why.

- `cin >> name;`
  - `cout << studentName;`
  - `yourName[0] = '\0';`
  - `yourName = studentName;`
  - `if (yourName == name)
 studentName = name;`
  - `int x = strcmp(yourName, studentName);`
  - `strcpy(studentName, Name);`
  - `for (int j = 0; j < 21; j++)
 cout << name[j];`
31. Define a two-dimensional array named `temp` of three rows and four columns of type `int` such that the first row is initialized to 6, 8, 12, 9; the second row is initialized to 17, 5, 10, 6; and the third row is initialized to 14, 13, 16, 20.
32. Suppose that array `temp` is as defined in Exercise 31. Write C++ statements to accomplish the following:
- Output the contents of the first row and first column element of `temp`.
  - Output the contents of the first row and last column element of `temp`.
  - Output the contents of the last row and first column element of `temp`.
  - Output the contents of the last row and last column element of `temp`.
33. Consider the following declarations:
- ```
const int CAR_TYPES = 5;
const int COLOR_TYPES = 6;
```

```
double sales[CAR_TYPES][COLOR_TYPES];
```

- a. How many components does the array `sales` have?
 - b. What is the number of rows in the array `sales`?
 - c. What is the number of columns in the array `sales`?
 - d. To sum the sales by `CAR_TYPES`, what kind of processing is required?
 - e. To sum the sales by `COLOR_TYPES`, what kind of processing is required?
34. Write C++ statements that do the following:
- a. Declare an array `alpha` of 10 rows and 20 columns of type `int`.
 - b. Initialize the array `alpha` to 0.
 - c. Store 1 in the first row and 2 in the remaining rows.
 - d. Store 5 in the first column, and make sure that the value in each subsequent column is twice the value in the previous column.
 - e. Print the array `alpha` one row per line.
 - f. Print the array `alpha` one column per line.
35. Consider the following declaration:

```
int beta[3][3];
```

What is stored in `beta` after each of the following statements executes?

- a.

```
for (i = 0; i < 3; i++)
    for (j = 0; j < 3; j++)
        beta[i][j] = 0;
```
 - b.

```
for (i = 0; i < 3; i++)
    for (j = 0; j < 3; j++)
        beta[i][j] = i + j;
```
 - c.

```
for (i = 0; i < 3; i++)
    for (j = 0; j < 3; j++)
        beta[i][j] = i * j;
```
 - d.

```
for (i = 0; i < 3; i++)
    for (j = 0; j < 3; j++)
        beta[i][j] = 2 * (i + j) % 4;
```
36. Suppose that you have the following declarations:

```
int times[30][7];
int speed[15][7];
int trees[100][7];
int students[50][7];
```

- a. Write the definition of the function `print` that can be used to output the contents of these arrays.
- b. Write the C++ statements that call the function `print` to output the contents of the arrays `times`, `speed`, `trees`, and `students`.

PROGRAMMING EXERCISES

1. Write a C++ program that declares an array **alpha** of 50 components of type **double**. Initialize the array so that the first 25 components are equal to the square of the index variable, and the last 25 components are equal to three times the index variable. Output the array so that 10 elements per line are printed.
2. Write a C++ function, **smallestIndex**, that takes as parameters an **int** array and its size and returns the index of the first occurrence of the smallest element in the array. Also, write a program to test your function.
3. Write a C++ function, **lastLargestIndex**, that takes as parameters an **int** array and its size and returns the index of the last occurrence of the largest element in the array. Also, write a program to test your function.
4. Write a program that reads a file consisting of students' test scores in the range 0–200. It should then determine the number of students having scores in each of the following ranges: 0–24, 25–49, 50–74, 75–99, 100–124, 125–149, 150–174, and 175–200. Output the score ranges and the number of students. (Run your program with the following input data: 76, 89, 150, 135, 200, 76, 12, 100, 150, 28, 178, 189, 167, 200, 175, 150, 87, 99, 129, 149, 176, 200, 87, 35, 157, 189.)
5. Write a program that prompts the user to input a string and outputs the string in uppercase letters. (Use a character array to store the string.)
6. The history teacher at your school needs help in grading a True/False test. The students' IDs and test answers are stored in a file. The first entry in the file contains answers to the test in the form:

```
TFFTFFTTTTFFTFFTFTTT
```

Every other entry in the file is the student ID, followed by a blank, followed by the student's responses. For example, the entry:

```
ABC54301 TFFTFFTT TFFTFFTTTT
```

indicates that the student ID is **ABC54301** and the answer to question 1 is True, the answer to question 2 is False, and so on. This student did not answer question 9. The exam has 20 questions, and the class has more than 150 students. Each correct answer is awarded two points, each wrong answer gets one point deducted, and no answer gets zero points. Write a program that processes the test data. The output should be the student's ID, followed by the answers, followed by the test score, followed by the test grade. Assume the following grade scale: 90%–100%, A; 80%–89.99%, B; 70%–79.99%, C; 60%–69.99%, D; and 0%–59.99%, F.

7. Write a program that allows the user to enter the last names of five candidates in a local election and the number of votes received by each candidate. The program should then output each candidate's name, the number of votes

received, and the percentage of the total votes received by the candidate. Your program should also output the winner of the election. A sample output is:

| Candidate | Votes Received | % of Total Votes |
|-----------|----------------|------------------|
| Johnson | 5000 | 25.91 |
| Miller | 4000 | 20.73 |
| Duffy | 6000 | 31.09 |
| Robinson | 2500 | 12.95 |
| Ashtony | 1800 | 9.33 |
| Total | 19300 | |

The Winner of the Election is Duffy.

8. Consider the following function main:

```
int main()
{
    int inStock[10][4];
    int alpha[20];
    int beta[20];
    int gamma[4] = {11, 13, 15, 17};
    int delta[10] = {3, 5, 2, 6, 10, 9, 7, 11, 1, 8};

    .
    .
    .
}
```

- Write the definition of the function `setZero` that initializes any one-dimensional array of type `int` to 0.
- Write the definition of the function `inputArray` that prompts the user to input 20 numbers and stores the numbers into `alpha`.
- Write the definition of the function `doubleArray` that initializes the elements of `beta` to two times the corresponding elements in `alpha`. Make sure that you prevent the function from modifying the elements of `alpha`.
- Write the definition of the function `copyGamma` that sets the elements of the first row of `inStock` to `gamma` and the remaining rows of `inStock` to three times the previous row of `inStock`. Make sure that you prevent the function from modifying the elements of `gamma`.
- Write the definition of the function `copyAlphaBeta` that stores `alpha` into the first five rows of `inStock` and `beta` into the last five rows of `inStock`. Make sure that you prevent the function from modifying the elements of `alpha` and `beta`.
- Write the definition of the function `printArray` that prints any one-dimensional array of type `int`. Print 15 elements per line.

- g. Write the definition of the function `setInStock` that prompts the user to input the elements for the first column of `inStock`. The function should then set the elements in the remaining columns to two times the corresponding element in the previous column, minus the corresponding element in `delta`.
 - h. Write C++ statements that call each of the functions in parts a through g.
 - i. Write a C++ program that tests the function `main` and the functions discussed in parts a through g. (Add additional functions, such as printing a two-dimensional array, as needed.)
9. Write a program that uses a two-dimensional array to store the highest and lowest temperatures for each month of the year. The program should output the average high, average low, and the highest and lowest temperatures for the year. Your program must consist of the following functions:
- a. Function `getData`: This function reads and stores data in the two-dimensional array.
 - b. Function `averageHigh`: This function calculates and returns the average high temperature for the year.
 - c. Function `averageLow`: This function calculates and returns the average low temperature for the year.
 - d. Function `indexHighTemp`: This function returns the index of the highest high temperature in the array.
 - e. Function `indexLowTemp`: This function returns the index of the lowest low temperature in the array.
- (These functions must all have the appropriate parameters.)
10. Programming Exercise 8 in Chapter 6 asks you find the mean and standard deviation of five numbers. Extend this programming exercise to find the mean and standard deviation of up to 100 numbers. Suppose that the mean (average) of n numbers x_1, x_2, \dots, x_n is x . Then, the standard deviation of these numbers is:

$$s = \sqrt{\frac{(x_1 - x)^2 + (x_2 - x)^2 + \cdots + (x_i - x)^2 + \cdots + (x_n - x)^2}{n}}$$

11. **(Adding Large Integers)** In C++, the largest `int` value is 2147483647. So, an integer larger than this cannot be stored and processed as an integer. Similarly, if the sum or product of two positive integers is greater than 2147483647, the result will be incorrect. One way to store and manipulate large integers is to store each individual digit of the number in an array. Write a program that inputs two positive integers of, at most, 20 digits and outputs the sum of the numbers. If the sum of the numbers has more than 20 digits, output the sum with an appropriate message. Your program must,

at least, contain a function to read and store a number into an array and another function to output the sum of the numbers. (*Hint:* Read numbers as strings and store the digits of the number in the reverse order.)

12. Jason, Samantha, Ravi, Sheila, and Ankit are preparing for an upcoming marathon. Each day of the week, they run a certain number of miles and write them into a notebook. At the end of the week, they would like to know the number of miles run each day, the total miles for the week, and average miles run each day. Write a program to help them analyze their data. Your program must contain parallel arrays: an array to store the names of the runners and a two-dimensional array of five rows and seven columns to store the number of miles run by each runner each day. Furthermore, your program must contain at least the following functions: a function to read and store the runners' names and the numbers of miles run each day; a function to find the total miles run by each runner and the average number of miles run each day; and a function to output the results. (You may assume that the input data is stored in a file and each line of data is in the following form: `runnerName milesDay1 milesDay2 milesDay3 milesDay4 milesDay5 milesDay6 milesDay7`.)
13. Write a program to calculate students' average test scores and their grades. You may assume the following input data:

```
Johnson 85 83 77 91 76
Aniston 80 90 95 93 48
Cooper 78 81 11 90 73
Gupta 92 83 30 69 87
Blair 23 45 96 38 59
Clark 60 85 45 39 67
Kennedy 77 31 52 74 83
Bronson 93 94 89 77 97
Sunny 79 85 28 93 82
Smith 85 72 49 75 63
```

Use three arrays: a one-dimensional array to store the students' names, a (parallel) two-dimensional array to store the test scores, and a parallel one-dimensional array to store grades. Your program must contain at least the following functions: a function to read and store data into two arrays, a function to calculate the average test score and grade, and a function to output the results. Have your program also output the class average.

14. (**Airplane Seating Assignment**) Write a program that can be used to assign seats for a commercial airplane. The airplane has 13 rows, with six seats in each row. Rows 1 and 2 are first class, rows 3 through 7 are business class, and rows 8 through 13 are economy class. Your program must prompt the user to enter the following information:
 - a. Ticket type (first class, business class, or economy class)
 - b. Desired seat

Output the seating plan in the following form:

| | A | B | C | D | E | F |
|--------|---|---|---|---|---|---|
| Row 1 | * | * | X | * | X | X |
| Row 2 | * | X | * | X | * | X |
| Row 3 | * | * | X | X | * | X |
| Row 4 | X | * | X | * | X | X |
| Row 5 | * | X | * | X | * | * |
| Row 6 | * | X | * | * | * | X |
| Row 7 | X | * | * | * | X | X |
| Row 8 | * | X | * | X | X | * |
| Row 9 | X | * | X | X | * | X |
| Row 10 | * | X | * | X | X | X |
| Row 11 | * | * | X | * | X | * |
| Row 12 | * | * | X | X | * | X |
| Row 13 | * | * | * | * | X | * |

Here, * indicates that the seat is available; X indicates that the seat is occupied. Make this a menu-driven program; show the user's choices and allow the user to make the appropriate choices.



10

CHAPTER

APPLICATIONS OF ARRAYS (SEARCHING AND SORTING) AND THE `vector` TYPE

IN THIS CHAPTER, YOU WILL:

- Explore how to sort an array using the bubble sort, selection sort, and insertion sort algorithms
- Learn how to implement the binary search algorithm
- Become familiar with the `vector` type

Chapter 9 introduced arrays, a structured data type. When the data values are all of the same type, arrays are a convenient way to store and process them. You can effectively use loops for input/output, initialization, and other operations. Moreover, you can pass the entire set of values as a parameter with a single statement. The next section continues our discussion of one-dimensional arrays and shows you how to use them effectively for list processing. We then examine the `vector` type.

List Processing

A **list** is a collection of values of the same type. Because all values are of the same type, a convenient place to store a list is in an array and, particularly, in a one-dimensional array. The size of a list is the number of elements in the list. Because the size of a list can increase and decrease, the array you use to store the list should be declared as the maximum size of the list.

Basic operations performed on a list include the following:

- Search the list for a given item.
- Sort the list.
- Insert an item in the list.
- Delete an item from the list.
- Print the list.

The following sections discuss searching and sorting algorithms.

Searching

In Chapter 9, we described the sequential search algorithm. Recall that the sequential search algorithm is:

```
int seqSearch(const int list[], int listLength, int searchItem)
{
    int loc;
    bool found = false;
    loc = 0;

    while (loc < listLength && !found)
        if (list[loc] == searchItem)
            found = true;
        else
            loc++;

    if (found)
        return loc;
    else
        return -1;
}
```

Suppose that you have a list with 1000 elements. If the search item is the second item in the list, the sequential search makes two **key** (also called **item**) comparisons to determine whether the search item is in the list. Similarly, if the search item is the 900th item in the list, the sequential search makes 900 key comparisons to determine whether the search item is in the list. If the search item is not in the list, the sequential search makes 1000 key comparisons.

Therefore, if `searchItem` is always at the bottom of the list, it will take many comparisons to find it. Also, if `searchItem` is not in `list`, then we compare `searchItem` with every element in `list`. A sequential search is therefore not very efficient for large lists. In fact, it can be proved that, on average, the number of comparisons (key comparisons, not index comparisons) made by the sequential search is equal to half the size of the list. So, for a list size of 1000, on average, the sequential search makes about 500 key comparisons.

The sequential search algorithm does not assume that the list is sorted. If the list is sorted, then you can significantly improve the search algorithm as discussed in the section Binary Search of this chapter. However, first, we discuss how to sort a list.

Bubble Sort

There are many sorting algorithms. This section describes the sorting algorithm, called **bubble sort**, to sort a list.

Suppose `list[0]...list[n - 1]` is a list of `n` elements, indexed 0 to `n - 1`. We want to rearrange, that is, sort, the elements of `list` in increasing order. The bubble sort algorithm works as follows:

In a series of `n - 1` iterations, the successive elements `list[index]` and `list[index + 1]` of `list` are compared. If `list[index]` is greater than `list[index + 1]`, then the elements `list[index]` and `list[index + 1]` are swapped, that is, interchanged.

It follows that the smaller elements move toward the top (beginning), and the larger elements move toward the bottom (end) of the list.

In the first iteration, we consider `list[0]...list[n - 1]`; in the second iteration, we consider `list[0]...list[n - 2]`; in the third iteration, we consider `list[0]...list[n - 3]`, and so on. For example, consider `list[0]...list[4]`, as shown in Figure 10-1.

| list | |
|---------|----|
| list[0] | 10 |
| list[1] | 7 |
| list[2] | 19 |
| list[3] | 5 |
| list[4] | 16 |

FIGURE 10-1 List of five elements

Iteration 1: Sort `list[0]...list[4]`. Figure 10-2 shows how the elements of `list` get rearranged in the first iteration.




FIGURE 10-2 Elements of `list` during the first iteration

Notice that in the first diagram of Figure 10-2, `list[0] > list[1]`. Therefore, `list[0]` and `list[1]` are swapped. In the second diagram, `list[1]` and `list[2]` are compared. Because `list[1] < list[2]`, they do not get swapped. The third diagram of Figure 10-2 compares `list[2]` with `list[3]`; because `list[2] > list[3]`, `list[2]` is swapped with `list[3]`. Then, in the fourth diagram, we compare `list[3]` with `list[4]`. Because `list[3] > list[4]`, `list[3]` and `list[4]` are swapped.

After the first iteration, the largest element is at the last position. Therefore, in the next iteration, we consider `list[0...3]`.

Iteration 2: Sort `list[0...3]`. Figure 10-3 shows how the elements of `list` get rearranged in the second iteration.




FIGURE 10-3 Elements of `list` during the second iteration

The elements are compared and swapped as in the first iteration. Here, only the list elements `list[0]` through `list[3]` are considered. After the second iteration, the last two elements are in the right place. Therefore, in the next iteration, we consider `list[0...2]`.

Iteration 3: Sort `list[0...2]`. Figure 10-4 shows how the elements of `list` get rearranged in the third iteration.




FIGURE 10-4 Elements of `list` during the third iteration

After the third iteration, the last three elements are in the right place. Therefore, in the next iteration, we consider `list[0...1]`.

Iteration 4: Sort `list[0...1]`. Figure 10-5 shows how the elements of `list` get rearranged in the fourth iteration.




FIGURE 10-5 Elements of `list` during the fourth iteration

After the fourth iteration, `list` is sorted.

The following function implements the bubble sort algorithm:

```
void bubbleSort(int list[], int length)
{
    int temp;
    int iteration;
    int index;
    for (iteration = 1; iteration < length; iteration++)
    {
        for (index = 0; index < length - iteration; index++)
            if (list[index] > list[index + 1])
            {
                temp = list[index];
                list[index] = list[index + 1];
                list[index + 1] = temp;
            }
    }
}
```

The program in Example 10-1 illustrates how to use the bubble sort algorithm in a program.

EXAMPLE 10-1

```
//Bubble sort

#include <iostream>

using namespace std;

void bubbleSort(int list[], int length);

int main()
{
    int list[] = {2, 56, 34, 25, 73, 46, 89, 10, 5, 16}; //Line 1
    int i; //Line 2

    bubbleSort(list, 10); //Line 3

    cout << "After sorting, the list elements are:"
         << endl; //Line 4

    for (i = 0; i < 10; i++) //Line 5
        cout << list[i] << " "; //Line 6

    cout << endl; //Line 7

    return 0; //Line 8
}

//Place the definition of the function bubbleSort given
//previously here.
```

Sample Run:

```
After sorting, the list elements are:
2 5 10 16 25 34 46 56 73 89
```

The statement in Line 1 declares and initializes `list` to be an array of 10 components of type `int`. The statement in Line 3 uses the function `bubbleSort` to sort `list`. Notice that both `list` and its length (the number of elements in it, which is 10) are passed as parameters to the function `bubbleSort`. The `for` loop in Lines 5 and 6 outputs the elements of `list`.

To illustrate the bubble sort algorithm in this program, we declared and initialized the array `list`. However, you can also prompt the user to input the data during program execution.

For a list of length n , the bubble sort given previously makes exactly $\frac{n(n-1)}{2}$ key comparisons and, on average, about $\frac{n(n-1)}{4}$ item assignments. Therefore, if $n = 1000$, to sort the list, bubble sort makes about 500,000 key comparisons and about 250,000 item

assignments. The next section presents the selection sort algorithm, which reduces the number of item assignments.

NOTE

The performance of bubble sort can be improved if we stop the sorting process as soon as we find that, in an iteration, no swapping of elements takes place. In this case, the list has been sorted. See Exercise 12 and Programming Exercise 17 at the end of this chapter.

Selection Sort

This section describes another sorting algorithm called the **selection sort**.

As the name implies, in **selection sort** algorithm, we rearrange the list by selecting an element in the list and moving it to its proper position. This algorithm finds the location of the smallest element in the unsorted portion of the list and moves it to the top of the unsorted portion of the list. The first time, we locate the smallest item in the entire list. The second time, we locate the smallest item in the list starting from the second element in the list, and so on.

Suppose you have the list shown in Figure 10-6.




FIGURE 10-6 List of eight elements

Figure 10-7 shows the elements of `list` in the first iteration.




FIGURE 10-7 Elements of `list` during the first iteration

Initially, the entire list is unsorted. So, we find the smallest item in the list. The smallest item is at position 6, as shown in Figure 10-7(a). Because this is the smallest item, it must be moved to position 0. So, we swap 16 (that is, `list[0]`) with 5 (that is, `list[6]`), as shown in Figure 10-7(b). After swapping these elements, the resulting list is as shown in Figure 10-7(c).

Figure 10-8 shows the elements of `list` during the second iteration.




FIGURE 10-8 Elements of `list` during the second iteration

Now the unsorted list is `list[1]...list[7]`. So, we find the smallest element in the unsorted list. The smallest element is at position 3, as shown in Figure 10-8(a). Because the smallest element in the unsorted list is at position 3, it must be moved to position 1. So, we swap 7 (that is, `list[3]`) with 30 (that is, `list[1]`), as shown in Figure 10-8(b). After swapping `list[1]` with `list[3]`, the resulting list is as shown in Figure 10-8(c).

Now, the unsorted list is `list[2]...list[7]`. So, we repeat the preceding process of finding the (position of the) smallest element in the unsorted portion of the list and moving it to the beginning of the unsorted portion of the list. Selection sort thus involves the following steps.

In the unsorted portion of the list:

- a. Find the location of the smallest element.
- b. Move the smallest element to the beginning of the unsorted list.

Initially, the entire list (that is, `list[0]...list[length - 1]`) is the unsorted list. After executing Steps a and b once, the unsorted list is `list[1]...list[length - 1]`. After executing Steps a and b a second time, the unsorted list is `list[2]...list[length - 1]`, and so on. In this way, we can keep track of the unsorted portion of the list and repeat Steps a and b with the help of a `for` loop, as shown in the following pseudocode:

```

for (index = 0; index < length - 1; index++)
{
    a. Find the location, smallestIndex, of the smallest element in
       list[index]...list[length - 1].
    b. Swap the smallest element with list[index]. That is, swap
       list[smallestIndex] with list[index].
}

```

The first time through the loop, we locate the smallest element in `list[0]...list[length - 1]` and swap the smallest element with `list[0]`. The second time through the loop, we locate the smallest element in `list[1]...list[length - 1]` and swap the smallest element with `list[1]`, and so on.

Step a is similar to the algorithm for finding the index of the largest item in the list, as discussed in Chapter 9. (Also see Chapter 9, Programming Exercise 2.) Here, we find the index of the smallest item in the list. The general form of Step a is:

```

smallestIndex = index; //assume first element is the smallest

for (location = index + 1; location < length; location++)
    if (list[location] < list[smallestIndex])
        smallestIndex = location; //current element in the list
                                   //is smaller than the smallest so
                                   //far, so update smallestIndex

```

Step b swaps the contents of `list[smallestIndex]` with `list[index]`. The following statements accomplish this task:

```

temp = list[smallestIndex];
list[smallestIndex] = list[index];
list[index] = temp;

```

It follows that to swap the values, three item assignments are needed. The following function, `selectionSort`, implements the selection sort algorithm:

```

void selectionSort(int list[], int length)
{
    int index;
    int smallestIndex;
    int location;
    int temp;

    for (index = 0; index < length - 1; index++)
    {
        //Step a
        smallestIndex = index;

        for (location = index + 1; location < length; location++)
            if (list[location] < list[smallestIndex])
                smallestIndex = location;

        //Step b
        temp = list[smallestIndex];
        list[smallestIndex] = list[index];
        list[index] = temp;
    }
}

```

The program in Example 10-3 illustrates how to use the selection sort algorithm in a program.

EXAMPLE 10-3

```
//Selection sort

#include <iostream>

using namespace std;

void selectionSort(int list[], int length);

int main()
{
    int list[] = {2, 56, 34, 25, 73, 46, 89, 10, 5, 16}; //Line 1
    int i; //Line 2

    selectionSort(list, 10); //Line 3

    cout << "After sorting, the list elements are:"
         << endl; //Line 4
    for (i = 0; i < 10; i++) //Line 5
        cout << list[i] << " "; //Line 6

    cout << endl; //Line 7

    return 0; //Line 8
}

//Place the definition of the function selectionSort given
//previously here.
```

Sample Run:

```
After sorting, the list elements are:
2 5 10 16 25 34 46 56 73 89
```

This program works the same way as the program in Example 10-1. Here, we use the selection sort algorithm to sort the list.

For a list of length n , selection sort makes exactly $\frac{n(n-1)}{2}$ key comparisons and $3(n-1)$ item assignments. Therefore, if $n = 1000$, then to sort the list, selection sort makes about 500,000 key comparisons and about 3000 item assignments. The next section presents the insertion sort algorithm that reduces the number of comparisons.

Insertion Sort

As noted in the previous section, for a list of length 1000, both bubble sort and selection sort make approximately 500,000 key comparisons, which is quite high. This section

describes the sorting algorithm called insertion sort, which tries to improve—that is, reduce—the number of key comparisons.

The insertion sort algorithm sorts the list by moving each element to its proper place. Consider the list given in Figure 10-9.




FIGURE 10-9 list

The length of the list is 8. Moreover, the list elements `list[0]`, `list[1]`, `list[2]`, and `list[3]` are already in (ascending) order. That is, `list[0]...list[3]` is sorted (see Figure 10-10).




FIGURE 10-10 Sorted and unsorted portion of list

Next, we consider the element `list[4]`, the first element of the unsorted list. Because `list[4] < list[3]`, we need to move the element `list[4]` to its proper location. It thus follows that element `list[4]` should be moved to `list[2]` (see Figure 10-11).




FIGURE 10-11 Move `list[4]` into `list[2]`

To move `list[4]` into `list[2]`, first we copy `list[4]` into `temp`, a temporary memory space (see Figure 10-12).




FIGURE 10-12 Copy `list[4]` into `temp`

Next, we copy `list[3]` into `list[4]` and then `list[2]` into `list[3]` (see Figure 10-13).




FIGURE 10-13 `list` before copying `list[3]` into `list[4]` and then `list[2]` into `list[3]`

After copying `list[3]` into `list[4]` and `list[2]` into `list[3]`, the list is as shown in Figure 10-14.




FIGURE 10-14 `list` after copying `list[3]` into `list[4]` and then `list[2]` into `list[3]`

We now copy `temp` into `list[2]`. Figure 10-15 shows the resulting list.




FIGURE 10-15 list after copying `temp` into `list[2]`

Now `list[0]...list[4]` is sorted, and `list[5]...list[7]` is unsorted. We repeat this process on the resulting list by moving the first element of the unsorted list into the proper place in the sorted list.

From this discussion, we see that during the sorting phase, the array containing the list is divided into two sublists, sorted and unsorted. Elements in the sorted sublist are sorted; elements in the unsorted sublist are to be moved to their proper places in the sorted sublist one at a time. We use an index—say, `firstOutOfOrder`—to point to the first element in the unsorted sublist. Initially, `firstOutOfOrder` is initialized to 1.

This discussion translates into the following pseudocode:

```

for (firstOutOfOrder = 1; firstOutOfOrder < listLength;
    firstOutOfOrder++)
    if (list[firstOutOfOrder] is less than list[firstOutOfOrder - 1])
    {
        copy list[firstOutOfOrder] into temp

        initialize location to firstOutOfOrder

        do
        {
            a. copy list[location - 1] into list[location]
            b. decrement location by 1 to consider the next element
               in the sorted portion of the array
        }
        while (location > 0 && the element in the upper list at
               location - 1 is greater than temp)
    }
    copy temp into list[location]

```

The following C++ function implements the previous algorithm:

```
void insertionSort(int list[], int listLength)
```

```

{
    int firstOutOfOrder, location;
    int temp;

    for (firstOutOfOrder = 1; firstOutOfOrder < listLength;
        firstOutOfOrder++)
        if (list[firstOutOfOrder] < list[firstOutOfOrder - 1])
        {
            temp = list[firstOutOfOrder];
            location = firstOutOfOrder;

            do
            {
                list[location] = list[location - 1];
                location--;
            }
            while (location > 0 && list[location - 1] > temp);

            list[location] = temp;
        }
} //end insertionSort

```

We leave it as an exercise to write a program to test the insertion sort algorithm.

It is known that for a list of length n , on average, insertion sort makes about $\frac{n^2 + 3n - 4}{4}$ key comparisons and about $\frac{n(n-1)}{4}$ item assignments. Therefore, if $n = 1000$, to sort the list, insertion sort makes about 250,000 key comparisons and about 250,000 item assignments.

This chapter presented three sorting algorithms. In fact, these are not the only sorting algorithms. You might be wondering why there are so many different sorting algorithms. The answer is that the performance of each sorting algorithm is different. Some algorithms make more comparisons, whereas others make fewer item assignments. Also, there are algorithms that make fewer comparisons, as well as fewer item assignments. The previous sections give the average number of comparisons and item assignments for the three sorting algorithms covered in this chapter. Analysis of the number of key comparisons and item assignments allows the user to decide which algorithm to use in a particular situation.

Binary Search

A sequential search is not very efficient for large lists. It typically searches about half of the list. However, if the list is sorted, you can use another search algorithm called **binary search**. A binary search is much faster than a sequential search. In order to apply a binary search, *the list must be sorted*.

A binary search uses the “divide and conquer” technique to search the list. First, the search item is compared with the middle element of the list. If the search item is less than the middle element of the list, we restrict the search to the upper half of the list; otherwise, we search the lower half of the list.

Consider the following sorted list of `length = 12`, as shown in Figure 10-16.




FIGURE 10-16 List of length 12

Suppose that we want to determine whether 75 is in the list. Initially, the entire list is the search list (see Figure 10-17).




FIGURE 10-17 Search list, `list[0]...list[11]`

First, we compare 75 with the middle element, `list[5]` (which is 39), in the list. Since $75 \neq \text{list}[5]$ and $75 > \text{list}[5]$, next we restrict our search to `list[6]...list[11]`, as shown in Figure 10-18.




FIGURE 10-18 Search list, `list[6]...list[11]`

The above process is now repeated on `list[6]...list[11]`, which is a list of `length = 6`.

Because we frequently need to determine the middle element of the list, the binary search algorithm is usually implemented for array-based lists. To determine the middle element of

the list, we add the starting index, `first`, and the ending index, `last`, of the search list and divide by 2 to calculate its index. That is, $mid = \frac{first + last}{2}$. Initially, `first = 0` and (since array index in C++ starts at 0 and `listLength` denotes the number of elements in the list) `last = listLength - 1`. (Note that the formula for calculating the middle element works regardless of whether the list has an even or odd number of elements.)

The following C++ function implements the binary search algorithm. If the item is found in the list, its location is returned. If the search item is not in the list, `-1` is returned.

```
int binarySearch(const int list[], int listLength, int searchItem)
{
    int first = 0;
    int last = listLength - 1;
    int mid;

    bool found = false;

    while (first <= last && !found)
    {
        mid = (first + last) / 2;

        if (list[mid] == searchItem)
            found = true;
        else if (list[mid] > searchItem)
            last = mid - 1;
        else
            first = mid + 1;
    }

    if (found)
        return mid;
    else
        return -1;
} //end binarySearch
```

Note that in the binary search algorithm, two key (item) comparisons are made each time through the loop, except in the successful case—the last time through the loop—when only one key comparison is made.

Next, we walk through the binary search algorithm on the list shown in Figure 10-19.

| | [0] | [1] | [2] | [3] | [4] | [5] | [6] | [7] | [8] | [9] | [10] | [11] |
|------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|------|------|
| list | 4 | 8 | 19 | 25 | 34 | 39 | 45 | 48 | 66 | 75 | 89 | 95 |

FIGURE 10-19 Sorted list for a binary search

The size of the list in Figure 10-19 is 12, so `listLength = 12`. Suppose that the item for which we are searching is 89, so `searchItem = 89`. Before the `while` loop executes,

`first = 0`, `last = 11`, and `found = false`. In the following, we trace the execution of the `while` loop, showing the values of `first`, `last`, and `mid` and the number of key comparisons during each iteration.

| Iteration | first | last | mid | list[mid] | No. of key comparisons |
|-----------|-------|------|-----|-----------|---------------------------------|
| 1 | 0 | 11 | 5 | 39 | 2 |
| 2 | 6 | 11 | 8 | 66 | 2 |
| 3 | 9 | 11 | 10 | 89 | 1 (found is <code>true</code>) |

The item is found at location 10, and the total number of key comparisons is 5.

Next, let's search the list for 34, so `searchItem = 34`. Before the `while` loop executes, `first = 0`, `last = 11`, and `found = false`. In the following, as before, we trace the execution of the `while` loop, showing the values of `first`, `last`, and `mid` and the number of key comparisons during each iteration.

| Iteration | first | last | mid | list[mid] | No. of key comparisons |
|-----------|-------|------|-----|-----------|---------------------------------|
| 1 | 0 | 11 | 5 | 39 | 2 |
| 2 | 0 | 4 | 2 | 19 | 2 |
| 3 | 3 | 4 | 3 | 25 | 2 |
| 4 | 4 | 4 | 4 | 34 | 1 (found is <code>true</code>) |

The item is found at location 4, and the total number of key comparisons is 7.

Let's now search for 22, so `searchItem = 22`. Before the `while` loop executes, `first = 0`, `last = 11`, and `found = false`. In the following, as before, we trace the execution of the `while` loop, showing the values of `first`, `last`, and `mid` and the number of key comparisons during each iteration.

| Iteration | first | last | mid | list[mid] | No. of key comparisons |
|-----------|-------|------|------------------------------------------------------|-----------|------------------------|
| 1 | 0 | 11 | 5 | 39 | 2 |
| 2 | 0 | 4 | 2 | 19 | 2 |
| 3 | 3 | 4 | 3 | 25 | 2 |
| 4 | 3 | 2 | the loop stops (since <code>first > last</code>) | | |
| | | | unsuccessful search | | |

This is an unsuccessful search. The total number of key comparisons is 6.

From these tracings of the binary search algorithm, you can see that every time you go through the loop, you cut the size of the sublist by half. That is, the size of the sublist you search the next time through the loop is half the size of the previous sublist.

We leave it as an exercise for you to write a program to test the function `binarySearch`. See Programming Exercise 2 at the end of this chapter.

Performance of Binary Search

Suppose that L is a sorted list of size 1024, and we want to determine whether an item x is in L . From the binary search algorithm, it follows that every iteration of the `while` loop cuts the size of the search list by half. (For example, see Figures 10-17 and 10-18.) Because $1024 = 2^{10}$, the `while` loop will have, at most, 11 iterations to determine whether x is in L . Because every iteration of the `while` loop makes two item (key) comparisons, that is, x is compared twice with the elements of L , the binary search will make, at most, 22 comparisons to determine whether x is in L . On the other hand, recall that a sequential search, on average, will make 512 comparisons to determine whether x is in L .

To better understand how fast binary search is compared to sequential search, suppose that L is of size 1048576. Because $1048576 = 2^{20}$, it follows that the `while` loop in a binary search will have, at most, 21 iterations to determine whether an element is in L . Every iteration of the `while` loop makes two key (that is, item) comparisons. Therefore, to determine whether an element is in L , a binary search makes, at most, 42 item comparisons.

Note that $40 = 2 \star 20 = 2 \star \log_2 2^{20} = 2 \star \log_2(1048576)$.

In general, suppose that L is a sorted list of size n . Moreover, suppose that n is a power of 2, that is, $n = 2^m$, for some nonnegative integer m . After each iteration of the `while` loop, about half of the elements are left to search, that is, the search sublist for the next iteration is half the size of the current sublist. For example, after the *first* iteration, the search sublist is of size about $n/2 = 2^{m-1}$. It is easy to see that the maximum number of the iteration of the `while` loop is about $m + 1$. Also $m = \log_2 n$. Each iteration makes two key comparisons. Thus, the maximum number of comparisons to determine whether an element x is in L is $2(m + 1) = 2(\log_2 n + 1) = 2\log_2 n + 2$.

`vector` Type (class)

NOTE

This section may be skipped without any discontinuation.

Chapter 9 and the previous sections of this chapter described how arrays can be used to implement and process lists. One of the limitations of arrays discussed so far is that once you create an array, its size remains fixed. This means that only a fixed number of elements can be stored in an array. Also, inserting an element in the array at a specific position could require the elements of the array to be shifted. Similarly, removing an element from the array also could require shifting the elements of the array, as we typically do not leave empty positions between array positions holding some data. Typically, empty array positions are at the end.

In addition to arrays, C++ provides the **vector** type (most commonly called the **class vector**) to implement a list. A variable declared using the **vector** type is called a **vector container** (or a **vector**, a **vector object**, or simply an **object**). Unlike an array, the size of a **vector** object can grow and shrink during program execution. Therefore, you do not need to be concerned with the number of data elements.

When you declare a **vector** object, you must specify the type of the element the **vector** object stores. Table 10-1 describes various ways a **vector** object can be declared.

TABLE 10-1 Various Ways to Declare and Initialize a `vector` Object

| Statement | Effect |
|-------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>vector<elemType> vecList;</code> | Creates the empty vector object vecList without any elements. |
| <code>vector<elemType> vecList (otherVecList);</code> | Creates the vector object vecList and initializes vecList to the elements of the vector otherVecList . vecList and otherVecList are of the same type. |
| <code>vector<elemType> vecList (size);</code> | Creates the vector object vecList of size size . vecList is initialized using the default values. |
| <code>vector<elemType> vecList (n, elem);</code> | Creates the vector object vecList of size n . vecList is initialized using n copies of the element elem . |

In Table 10-1, **elemType** specifies the data type of the element to be stored in **vecList**.

EXAMPLE 10-3

- a. The following statement declares **intList** to be an empty **vector** object, and the element type is **int**.

```
vector<int> intList;
```

- b. The following statement declares **intList** to be a **vector** object of size 10, and the element type is **int**. The elements of **intList** are initialized to 0.

```
vector<int> intList(10);
```

Now that we know how to declare a `vector` object, let us discuss how to manipulate the data stored in a `vector` object. To do so, we must know the following basic operations:

- Item insertion
- Item deletion
- Stepping through the elements of a vector container

The type `vector` provides various operations to manipulate data stored in a vector object. Each of these operations is defined in the form of a function. Table 10-2 describes some of these functions and how to use them with a vector object. (Assume that `vecList` is a vector object. The name of the function is shown in **bold**.)

TABLE 10-2 Operations on a `vector` Object

| Expression | Effect |
|--------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------|
| <code>vecList.at(index)</code> | Returns the element at the position specified by <code>index</code> . |
| <code>vecList[index]</code> | Returns the element at the position specified by <code>index</code> . |
| <code>vecList.front()</code> | Returns the first element. (Does not check whether the object is empty.) |
| <code>vecList.back()</code> | Returns the last element. (Does not check whether the object is empty.) |
| <code>vecList.clear()</code> | Deletes all elements from the object. |
| <code>vecList.push_back(elem)</code> | A copy of <code>elem</code> is inserted into <code>vecList</code> at the end. |
| <code>vecList.pop_back()</code> | Delete the last element of <code>vecList</code> . |
| <code>vecList.empty()</code> | Returns <code>true</code> if the object <code>vecList</code> is empty and <code>false</code> otherwise. |
| <code>vecList.size()</code> | Returns the number of elements currently in the object <code>vecList</code> . The value returned is an <code>unsigned int</code> value. |
| <code>vecList.max_size()</code> | Returns the maximum number of elements that can be inserted into the object <code>vecList</code> . |

Table 10-2 shows that the elements in a **vector** can be processed just as they are in an array. (Recall that in C++, arrays start at location 0. Similarly, the first element in a **vector** object is at location 0.) (Note that both the function **at** and the subscripting operator **[]** return the elements at the specified position. However, if the position, that is, the index, of the specified position is out of range, the function **at** throws an exception.) (Exceptions are discussed in Chapter 16.)

EXAMPLE 10-4

Consider the following statement, which declares **intList** to be a vector of size 5 and the element to be of type **int**:

```
vector<int> intList(5);
```

You can use a loop, such as the following, to store elements into **intList**:

```
for (int j = 0; j < 5; j++)
    intList[j] = j;
```

Similarly, you can use a **for** loop to output the elements of **intList**.

Example 10-4 uses a **for** loop and the array subscripting operator, **[]**, to access the elements of **intList**. We declare **intList** to be a **vector** object of size 5. Does this mean that we can store only five elements in **intList**? The answer is no. You can, in fact, add more elements to **intList**. However, because when we declared **intList**, we specified the size to be 5, in order to add any elements past position 4, we use the function **push_back**.

Furthermore, if you initially declare a **vector** object and do not specify its size, then to add elements to the **vector** object, we use the function **push_back**. Example 10-5 explains how to use this function.

EXAMPLE 10-5

The following statement declares **intList** to be a vector container of size 0:

```
vector<int> intList;
```

To add elements into **intList**, we can use the function **push_back** as follows:

```
intList.push_back(34);
intList.push_back(55);
```

After these statements execute, the size of **intList** is 2, and:

```
intList = {34, 55}.
```

In Example 10-5, because **intList** is declared to be of size 0, we use the function **push_back** to add elements to **intList**. However, we can also use the **resize** function

to increase the size of `intList` and then use the array subscripting operator. For example, suppose that `intList` is declared as in Example 10-5. Then, the following statement sets the size of `intList` to 10:

```
intList.resize(10);
```

Similarly, the following statement increases the size of `intList` by 10:

```
intList.resize(intList.size() + 10);
```

However, at times, the `push_back` function is more convenient because it does not need to know the size of the vector; it simply adds the elements at the end.

NOTE

The name of the header file that contains the `class` `vector` is `vector`. Therefore, to use the `class` `vector`, you must include the header file `vector`, that is, include the following statement in your program:

```
#include <vector>
```

The program in Example 10-6 illustrates how to use a `vector` object in a program and how to process the elements of a `vector`.

EXAMPLE 10-6

// This program illustrates how to use a vector object.

```
#include <iostream>
#include <vector>

using namespace std;

int main()
{
    vector<int> intList;           //Line 1
    unsigned int i;               //Line 2

    intList.push_back(13);        //Line 3
    intList.push_back(75);        //Line 4
    intList.push_back(28);        //Line 5
    intList.push_back(35);        //Line 6

    cout << "Line 7: List Elements: "; //Line 7

    for (i = 0; i < intList.size(); i++) //Line 8
        cout << intList[i] << " "; //Line 9
    cout << endl; //Line 10

    for (i = 0; i < intList.size(); i++) //Line 11
        intList[i] = intList[i] * 2; //Line 12

    cout << "Line 13: List Elements: "; //Line 13
```

```

    for (i = 0; i < intList.size(); i++)           //Line 14
        cout << intList[i] << " ";               //Line 15

    cout << endl;                                  //Line 16

    return 0;
}

```

Sample Run:

```

Line 7: List Elements: 13 75 28 35
Line 13: List Elements: 26 150 56 70

```

The statement in Line 1 declares the **vector** object (or **vector** for short) `intList` of type `int`. The statement in Line 2 declares `i` to be an `unsigned int` variable. (Notice that we declare `i` to be an `unsigned int` because, in the `for` loop, we are using the expression `intList.size()`, which returns an `unsigned int` value, to determine the size of `intList`.)

The statements in Lines 3 through 6 use the operation `push_back` to insert four numbers—13, 75, 28, and 35—into `intList`. The statements in Lines 8 and 9 use a `for` loop and the array subscripting operator, `[]`, to output the elements of `intList`. In the output, see the line marked Line 7, which contains the output of Lines 7 through 10 of the program. The statements in Lines 11 and 12 use a `for` loop to double the value of each element of `intList`; the statements in Lines 14 and 15 output the elements of `intList`. In the output, see the line marked Line 13, which contains the output of Lines 13 through 16 of the program.

NOTE

The data type (`class`) `vector` is a part of C++ standard template library (STL). To learn more about STL, see Appendix H.

1
0

PROGRAMMING EXAMPLE: Election Results

The presidential election for the student council of your local university will be held soon. For reasons related to confidentiality, the chair of the election committee wants to computerize the voting. The chair is looking for someone to write a program to analyze the data and report the winner. Let us write a program to help the election committee.

The university has four major divisions, and each division has several departments. For the purpose of the election, the divisions are labeled as Region 1, Region 2, Region 3, and Region 4. Each department in each division manages its own voting process and directly reports the results to the election committee. The voting is reported in the following form:

```
candidateName  regionNumber  numberOfVotesForTheCandidate
```

The election committee wants the output in the following tabular form:

-----Election Results-----

| Candidate | Votes | | | | |
|-----------|---------|---------|---------|---------|-------|
| Name | Region1 | Region2 | Region3 | Region4 | Total |
| ----- | ----- | ----- | ----- | ----- | ----- |
| Ashley | 23 | 89 | 0 | 160 | 272 |
| Danny | 25 | 71 | 89 | 97 | 282 |
| Donald | 110 | 158 | 0 | 0 | 268 |
| . | | | | | |
| . | | | | | |
| . | | | | | |

Winner: ???, Votes Received: ???

Total votes polled: ???

The names of the candidates in the output must be in alphabetical order.

For this program, we assume that six candidates are running for student council president. This program can be modified to accommodate any number of candidates.

The data is provided in two files. One file, `candData.txt`, consists of the names of candidates. The names in the file are in no particular order. In the second file, `voteData.txt`, each line consists of voting results in the following form:

`candidateName regionNumber numberOfVotesForTheCandidate`

That is, each line in the file `voteData.txt` consists of the candidate name, region number, and the votes received by the candidate in this region. There is one entry per line. For example, the input file containing voting data looks like:

```
Mia 2 34
Mickey 1 56
Donald 2 56
Mia 1 78
Danny 4 29
Ashley 4 78
.
.
.
```

The first line indicates that **Mia** received **34** votes from region **2**.

Input Two files, one containing the candidates' names and the other containing the voting data, as described previously.

Output The election results in a tabular form, as described previously, and the winner.

PROBLEM
ANALYSIS
AND
ALGORITHM
DESIGN

From the output requirements, it is clear that the program must organize the voting data by region. The program must also calculate the total number of votes received by each candidate, as well as the total votes cast in the election. Furthermore, the names of the candidates must appear in alphabetical order.

Because the data type of a candidate’s name (which is a string) and the data type of the number of votes (which is an integer) are different, we need two separate arrays—one to hold the candidates’ names and one to hold the voting data. The array to hold the names of the candidates is a one-dimensional array, and each component of this array is a string. Instead of using a single two-dimensional array to hold the voting data, we will use a two-dimensional array to hold the next four columns of the output (that is, the votes by region data) and a one-dimensional array to hold the total votes received by each candidate. These three arrays are parallel arrays (see Figure 10-20).




FIGURE 10-20 Parallel arrays: candidatesName, votesByRegion, and totalVotes

The data in the first row of these three arrays corresponds to the candidate whose name is stored in the first row of the array `candidatesName`, and so on. In the `votesByRegion` array, column 1 corresponds to Region 1, column 2 corresponds to Region 2, and so on. Recall that in C++, an array index starts at 0. Therefore, if the name of this array in the program is `votesByRegion`, then `votesByRegion[][0]` refers to the first column and thus Region 1, and so on.

For easy reference, suppose that in the program, the name of the candidates’ names array is `candidatesName`, the name of the voting totals by region array is `votesByRegion`, and the name of the total votes array is `totalVotes`.

The first thing we must do in this program is read the candidates' names from the input file `candData.txt` into the array `candidatesName`. Once the candidates' names are stored in the array, we must sort it.

Next, we must process the voting data. Every entry in the file `voteData.txt` contains a `candidateName`, `regionNumber`, and `votesReceivedByTheCandidate`. To process each entry, we find the appropriate entry in the array `votesByRegion` and update it by adding `votesReceivedByTheCandidate` to this entry. Therefore, it follows that the array `votesByRegion` must be initialized to zero. (Processing the voting data is described in detail later in this section.)

After processing the voting data, the next step is to calculate the total votes received by each candidate. This task is accomplished by adding the votes received in each region. Therefore, we must initialize the array `totalVotes` to zero. Finally, we output the results as shown earlier.

This discussion translates into the following algorithm:

1. Read the candidates' names into the array `candidatesName`.
2. Sort the array `candidatesName`.
3. Initialize the arrays `votesByRegion` and `totalVotes`.
4. Process the voting data.
5. Calculate the total votes received by each candidate.
6. Output the results.

Because the input data is provided in two separate files, in this program, we must open two files. We open both input files in the function `main`.

To implement these six steps of the algorithm, this program consists of several functions, as described next.

Function
`getCandidatesName`

This function reads the data from the input file `candData.txt` and fills the array `candidatesName`. The input file is opened in the function `main`. We see that this function has three parameters: one corresponding to the input file, one corresponding to the array `candidatesName`, and one to pass the number of rows of the array `candidatesName`. Essentially, this function is:

```
void getCandidatesName(ifstream& inp, string cNames[],
                      int noOfRows)
{
    int i;

    for (i = 0; i < noOfRows; i++)
        inp >> cNames[i];
}
```

After a call to this function, the arrays to hold the data are as shown in Figure 10-21.




FIGURE 10-21 Arrays `candidatesName`, `votesByRegion`, and `totalVotes` after reading candidates' names

Function

sortCandidatesName

This function uses the selection sort algorithm to sort the array `candidatesName`. This function has two parameters: one corresponding to the array `candidatesName` and a second to pass the number of rows of the array `candidatesName`. Essentially, this function is:

```
void sortCandidatesName(string cNames[], int noOfRows)
{
    int i, j;
    int min;

    //selection sort
    for (i = 0; i < noOfRows - 1; i++)
    {
        min = i;

        for (j = i + 1; j < noOfRows; j++)
            if (cNames[j] < cNames[min])
                min = j;

        cNames[i].swap(cNames[min]);
    }
}
```

After a call to this function, the arrays are as shown in Figure 10-22.

| candidatesName | | votesByRegion | | | | totalVotes | |
|----------------|--------|-----------------|--|--|--|------------|--|
| | | [0] [1] [2] [3] | | | | | |
| [0] | Ashley | [0] | | | | [0] | |
| [1] | Danny | [1] | | | | [1] | |
| [2] | Donald | [2] | | | | [2] | |
| [3] | Mia | [3] | | | | [3] | |
| [4] | Mickey | [4] | | | | [4] | |
| [5] | Peter | [5] | | | | [5] | |

FIGURE 10-22 Arrays `candidatesName`, `votesByRegion`, and `totalVotes` after sorting names

Function initialize The function `initialize` initializes the arrays `votesByRegion` and `totalVotes` to zero. This function must have three parameters: one corresponding to the array `votesByRegion`, one corresponding to the array `totalVotes`, and one to pass the number of rows of the array `votesByRegion`. Note that both arrays have the same number of rows. The definition of this function is:

```
void initialize(int vbRegion[][NO_OF_REGIONS], int tVotes[],
               int noOfRows)
{
    int i, j;

    for (i = 0; i < noOfRows; i++)
        for (j = 0; j < NO_OF_REGIONS; j++)
            vbRegion[i][j] = 0;

    for (i = 0; i < noOfRows; i++)
        tVotes[i] = 0;
}
```

After a call to this function, the arrays `votesByRegion` and `totalVotes` are as shown in Figure 10-23.

| candidatesName | | votesByRegion | | | | totalVotes | |
|----------------|--------|-----------------|---|---|---|------------|---|
| | | [0] [1] [2] [3] | | | | | |
| [0] | Ashley | [0] | 0 | 0 | 0 | 0 | 0 |
| [1] | Danny | [1] | 0 | 0 | 0 | 0 | 0 |
| [2] | Donald | [2] | 0 | 0 | 0 | 0 | 0 |
| [3] | Mia | [3] | 0 | 0 | 0 | 0 | 0 |
| [4] | Mickey | [4] | 0 | 0 | 0 | 0 | 0 |
| [5] | Peter | [5] | 0 | 0 | 0 | 0 | 0 |

FIGURE 10-23 Arrays `candidatesName`, `votesByRegion`, and `totalVotes` after initializing

Process Processing the voting data is quite straightforward. Each entry in the file `voteData.txt` is in the following form:

Voting Data

`candidatesName regionNumber numberOfVotesForTheCandidate`

The general algorithm to process the voting data is shown next. For each entry in the file `voteData.txt`, we do the following:

- Get a `candidateName`, `regionNumber`, and `numberOfVotesForTheCandidate`.
- Find the row number in the array `candidatesName` that corresponds to this candidate. This gives the corresponding row number in the array `votesByRegion` for this candidate.
- Find the column in the array `votesByRegion` that corresponds to the `regionNumber`.
- Update the appropriate entry in the array `votesByRegion` by adding the `numberOfVotesForTheCandidate`.

Step b requires us to search the array `candidatesName` to find the location (that is, row number) of a particular candidate. Because the array `candidatesName` is sorted, we can use the binary search algorithm to find the row number corresponding to a particular candidate. Therefore, this program also includes a function, `binSearch`, to implement the binary search algorithm on the array `candidatesName`. We will write the definition of the function `binSearch` shortly. First, let us discuss how to update the array `votesByRegion`.

Suppose that the three arrays are as shown in Figure 10-24.

| candidatesName | | | votesByRegion | | | | totalVotes | |
|----------------|--------|-----|---------------|-----|-----|-----|------------|---|
| | | | [0] | [1] | [2] | [3] | | |
| [0] | Ashley | [0] | 0 | 0 | 50 | 0 | [0] | 0 |
| [1] | Danny | [1] | 10 | 0 | 56 | 0 | [1] | 0 |
| [2] | Donald | [2] | 76 | 13 | 0 | 0 | [2] | 0 |
| [3] | Mia | [3] | 0 | 45 | 0 | 0 | [3] | 0 |
| [4] | Mickey | [4] | 50 | 0 | 45 | 0 | [4] | 0 |
| [5] | Peter | [5] | 100 | 0 | 0 | 20 | [5] | 0 |

FIGURE 10-24 Arrays `candidatesName`, `votesByRegion`, and `totalVotes`

Further, suppose that the next entry read from the input file is:

Donald 2 35

We must locate the row in the grid that corresponds to this candidate. To find the row, we search the array `candidatesName` to find the row that corresponds to this name. `Donald` corresponds to row number 2 in the array `candidatesName` (see Figure 10-25).

| candidatesName | | | votesByRegion | | | | totalVotes | |
|----------------|--------|-----|---------------|-----|-----|-----|------------|---|
| | | | [0] | [1] | [2] | [3] | | |
| [0] | Ashley | [0] | 0 | 0 | 50 | 0 | [0] | 0 |
| [1] | Danny | [1] | 10 | 0 | 56 | 0 | [1] | 0 |
| [2] | Donald | [2] | 76 | 13 | 0 | 0 | [2] | 0 |
| [3] | Mia | [3] | 0 | 45 | 0 | 0 | [3] | 0 |
| [4] | Mickey | [4] | 50 | 0 | 45 | 0 | [4] | 0 |
| [5] | Peter | [5] | 100 | 0 | 0 | 20 | [5] | 0 |

FIGURE 10-25 Position of `Donald` and `region = 2`

To process this entry, we access row number 2 of the array `votesByRegion`. Because `Donald` received 35 votes from Region 2, we access row 2 and column 1 (that is, `votesByRegion[2][1]`) and update this entry by adding 35 to its previous value. The following statement accomplishes this task:

```
votesByRegion[2][1] = votesByRegion[2][1] + 35;
```

After processing this entry, the three arrays are as shown in Figure 10-26.

| | candidatesName | | votesByRegion | | | | | totalVotes |
|-----|----------------|-----|---------------|-----|-----|-----|-----|------------|
| | | | [0] | [1] | [2] | [3] | | |
| [0] | Ashley | [0] | 0 | 0 | 50 | 0 | [0] | 0 |
| [1] | Danny | [1] | 10 | 0 | 56 | 0 | [1] | 0 |
| [2] | Donald | [2] | 76 | 48 | 0 | 0 | [2] | 0 |
| [3] | Mia | [3] | 0 | 45 | 0 | 0 | [3] | 0 |
| [4] | Mickey | [4] | 50 | 0 | 45 | 0 | [4] | 0 |
| [5] | Peter | [5] | 100 | 0 | 0 | 20 | [5] | 0 |

FIGURE 10-26 Arrays `candidatesName`, `votesByRegion`, and `totalVotes` after processing the entry `Donald 2 35`

Next, we describe the function `binSearch` and the function `processVotes` to process the voting data.

Function `binSearch` This function implements the binary search algorithm on the array `candidatesName`. It is similar to the function `binarySearch` discussed earlier in this chapter. Its definition is:

```
int binSearch(string cNames[], int noOfRows, string name)
{
    int first, last, mid;
    bool found;
    first = 0;
    last = noOfRows - 1;
    found = false;

    while (!found && first <= last)
    {
        mid = (first + last) / 2;

        if (cNames[mid] == name)
            found = true;
        else if (cNames[mid] > name)
            last = mid - 1;
        else
            first = mid + 1;
    }
}
```

```

        if (found)
            return mid;
        else
            return -1;
    }

```

Function `processVotes` This function processes the voting data. Clearly, it must have access to the arrays `candidatesName` and `votesByRegion`, as well as to the input file, `voteData.txt`. We also need to tell this function the number of rows in each array. Thus, the function `processVotes` has four parameters: one to access the input file `voteData.txt`, one corresponding to the array `candidatesName`, one corresponding to the array `votesByRegion`, and one to pass the number of rows in each array. The definition of this function is:

```

void processVotes(ifstream& inp, string cNames[],
                 int vbRegion[][NO_OF_REGIONS],
                 int noOfRows)
{
    string candName;
    int region;
    int noOfVotes;
    int loc;

    inp >> candName >> region >> noOfVotes;

    while (inp)
    {
        loc = binSearch(cNames, noOfRows, candName);

        if (loc != -1)
            vbRegion[loc][region - 1] = vbRegion[loc][region - 1]
                                         + noOfVotes;
        inp >> candName >> region >> noOfVotes;
    }
}

```

Calculate Total Votes After processing the voting data, the next step is to calculate the total votes for each candidate. Suppose that after processing the voting data, the arrays are as shown in Figure 10-27.

(Function
`addRegionsVote`)

| candidatesName | | | votesByRegion | | | | totalVotes | |
|----------------|--------|-----|---------------|-----|-----|-----|------------|---|
| | | | [0] | [1] | [2] | [3] | | |
| [0] | Ashley | [0] | 23 | 89 | 0 | 160 | [0] | 0 |
| [1] | Danny | [1] | 25 | 71 | 89 | 97 | [1] | 0 |
| [2] | Donald | [2] | 110 | 158 | 0 | 0 | [2] | 0 |
| [3] | Mia | [3] | 134 | 112 | 156 | 0 | [3] | 0 |
| [4] | Mickey | [4] | 56 | 63 | 67 | 89 | [4] | 0 |
| [5] | Peter | [5] | 207 | 56 | 0 | 46 | [5] | 0 |

FIGURE 10-27 Arrays `candidatesName`, `votesByRegion`, and `totalVotes` after processing the voting data

After calculating the total votes received by each candidate, the three arrays are as shown in Figure 10-28.

| candidatesName | | | votesByRegion | | | | totalVotes | |
|----------------|--------|-----|---------------|-----|-----|-----|------------|-----|
| | | | [0] | [1] | [2] | [3] | | |
| [0] | Ashley | [0] | 23 | 89 | 0 | 160 | [0] | 272 |
| [1] | Danny | [1] | 25 | 71 | 89 | 97 | [1] | 282 |
| [2] | Donald | [2] | 110 | 158 | 0 | 0 | [2] | 268 |
| [3] | Mia | [3] | 134 | 112 | 156 | 0 | [3] | 402 |
| [4] | Mickey | [4] | 56 | 63 | 67 | 89 | [4] | 275 |
| [5] | Peter | [5] | 207 | 56 | 0 | 46 | [5] | 309 |

FIGURE 10-28 Arrays `candidatesName`, `votesByRegion`, and `totalVotes` after calculating total votes received by each candidate

To calculate the total votes received by each candidate, we add the contents of each row in the `votesByRegion` array and then store the sum in the corresponding row in the `totalVotes` array. This task is accomplished by the function `addRegionsVote`.

The function `addRegionsVote` calculates the number of total votes received by each candidate. This function must access the arrays `votesByRegion` and `totalVotes`. Also, we must tell this function the number of rows in each array. This function has three parameters: one corresponding to the array `votesByRegion`, one corresponding to the array `totalVotes`, and one to pass the number of rows in each array. The definition of this function is:

```

void addRegionsVote(int vbRegion[][NO_OF_REGIONS],
                   int tVotes[], int noOfRows)
{
    int i, j;

    for (i = 0; i < noOfRows; i++)
        for (j = 0; j < NO_OF_REGIONS; j++)
            tVotes[i] = tVotes[i] + vbRegion[i][j];
}

```

We now describe the remaining functions required to get the desired output.

Function `printHeading` This function outputs the first four lines of input, so it contains certain output statements. The definition of this function is:

```

void printHeading()
{
    cout << "          -----Election Results-----"
          << "-----" << endl << endl;
    cout << "Candidate                      Votes" << endl;
    cout << "Name          Region1    Region2    Region3    "
          << "Region4    Total" << endl;
    cout << "-----          -----          -----          "
          << "-----          -----" << endl;
}

```

Function `printResults` This function outputs the remaining lines of the output. Clearly, it must have access to each of the three arrays. We must also tell the function the number of rows in each array. (Note that each array has the same number of rows.) Thus, this function has four parameters. Suppose that the parameter `cName` corresponds to `candidatesName`, the parameter `vbRegion` corresponds to `votesByRegion`, and the parameter `tVotes` corresponds to `totalVotes`.

Further suppose that the variable `sumVotes` holds the total number of votes cast in the election, the variable `largestVotes` holds the largest number of votes received by a candidate, and the variable `winLoc` holds the index of the winning candidate in the array `candidatesName`. The algorithm for this function is:

- a. Initialize `sumVotes`, `largestVotes`, and `winLoc` to 0.
- b. For each row in each array:
 - i. **if** (`largestVotes < tVotes[i]`)


```

{
    largestVotes = tVotes[i];
    winLoc = i;
}

```

- ii. `sumVotes = sumVotes + tVotes[i];`
- iii. Output the data from the corresponding rows of each array.
- c. Output the final lines of output.

The definition of this function is:

```
void printResults(string cNames[],
                 int vbRegion[][NO_OF_REGIONS],
                 int tVotes[], int noOfRows)
{
    int i, j;
    int largestVotes = 0;
    int winLoc = 0;
    int sumVotes = 0;

    for (i = 0; i < noOfRows; i++)
    {
        if (largestVotes < tVotes[i])
        {
            largestVotes = tVotes[i];
            winLoc = i;
        }

        sumVotes = sumVotes + tVotes[i];

        cout << left;
        cout << setw(9) << cNames[i] << " ";
        cout << right;
        for (j = 0; j < NO_OF_REGIONS; j++)
            cout << setw(8) << vbRegion[i][j] << " ";
        cout << setw(6) << tVotes[i] << endl;
    }

    cout << endl << endl << "Winner: " << cNames[winLoc]
         << ", Votes Received: " << tVotes[winLoc]
         << endl << endl;
    cout << "Total votes polled: " << sumVotes << endl;
}
```

We now give the main algorithm.

Suppose that the variables in the function main are:

```
string candidatesName[NO_OF_CANDIDATES]; //array to store the
                                         //candidate's name
int votesByRegion[NO_OF_CANDIDATES][NO_OF_REGIONS]; //array to
                                                       //hold the voting data by region
int totalVotes[NO_OF_CANDIDATES]; //array to hold the total votes
                                   //received by each candidate

ifstream infile; //input file variable
```

Furthermore, suppose that the candidates' names are in the file `candData.txt`, and the voting data is in the file `voteData.txt`.

MAIN
ALGORITHM:
FUNCTION
main

1. Declare the variables.
2. Open the input file `candData.txt`.
3. If the input file does not exist, exit the program.
4. Read the data from the file `candData.txt` into the array `candidatesName`.
5. Sort the array `candidatesName`.
6. Close the file `candData.txt` and clear the input stream.
7. Open the input file `voteData.txt`.
8. If the input file does not exist, exit the program.
9. Initialize the arrays `votesByRegion` and `totalVotes`.
10. Process the voting data and store the results in the array `votesByRegion`.
11. Calculate the number of total votes received by each candidate and store the results in the array `totalVotes`.
12. Print the heading.
13. Print the results.

PROGRAM LISTING

```
//*****
// Author: D.S. Malik
//
// This program processes voting data for student council
// president's post. It outputs each candidate's name and the
// votes they received. The name of the winner is also printed.
//*****

#include <iostream>
#include <fstream>
#include <string>
#include <iomanip>

using namespace std;

const int NO_OF_CANDIDATES = 6;
const int NO_OF_REGIONS = 4;

void printHeading();
```

```

void initialize(int vbRegion[][NO_OF_REGIONS], int tVotes[],
               int noOfRows);

void getCandidatesName(ifstream& inp, string cNames[],
                      int noOfRows);

void sortCandidatesName(string cNames[], int noOfRows);

int binSearch(string cNames[], int noOfRows, string name);

void processVotes(ifstream& inp, string cNames[],
                 int vbRegion[][NO_OF_REGIONS],
                 int noOfRows);

void addRegionsVote(int vbRegion[][NO_OF_REGIONS],
                   int tVotes[], int noOfRows);

void printResults(string cNames[],
                 int vbRegion[][NO_OF_REGIONS],
                 int tVotes[], int noOfRows);

int main()
{
    //Declare variables; Step 1
    string candidatesName[NO_OF_CANDIDATES];
    int votesByRegion[NO_OF_CANDIDATES][NO_OF_REGIONS];
    int totalVotes[NO_OF_CANDIDATES];
    ifstream infile;

    infile.open("candData.txt"); //Step 2
    if (!infile) //Step 3
    {
        cout << "Input file (candData.txt) does "
              << "not exist." << endl;
        return 1;
    }

    getCandidatesName(infile, candidatesName,
                     NO_OF_CANDIDATES); //Step 4
    sortCandidatesName(candidatesName,
                     NO_OF_CANDIDATES); //Step 5

    infile.close(); //Step 6
    infile.clear(); //Step 6

    infile.open("voteData.txt"); //Step 7
    if (!infile) //Step 8
    {
        cout << "Input file (voteData.txt) does "
              << "not exist." << endl;
        return 1;
    }
}

```

```

        initialize(votesByRegion, totalVotes,
                   NO_OF_CANDIDATES);           //Step 9
    processVotes(infile, candidatesName,
                 votesByRegion, NO_OF_CANDIDATES); //Step 10
    addRegionsVote(votesByRegion, totalVotes,
                   NO_OF_CANDIDATES);           //Step 11
    printHeading();                             //Step 12
    printResults(candidatesName, votesByRegion,
                 totalVotes, NO_OF_CANDIDATES); //Step 13

    return 0;
}

//Place the definitions of the functions initialize,
//getCandidatesName, sortCandidatesName, binSearch,
//processVotes, addRegionsVote, printHeading, and
//printResults here.

```

Sample Run: (After placing the definitions of all the functions, as described, into the program and executing.)

-----Election Results-----

| Candidate Name | Region1 | Votes Region2 | Region3 | Region4 | Total |
|-------------------|---------|------------------|---------|---------|-------|
| ----- | ----- | ----- | ----- | ----- | ----- |
| Ashley | 23 | 89 | 0 | 160 | 272 |
| Danny | 25 | 71 | 89 | 97 | 282 |
| Donald | 110 | 158 | 0 | 0 | 268 |
| Mia | 134 | 112 | 156 | 0 | 402 |
| Mickey | 56 | 63 | 67 | 89 | 275 |
| Peter | 207 | 56 | 0 | 46 | 309 |

Winner: Mia, Votes Received: 402

Total votes polled: 1808

Input Files:

candData.txt

Mia
Mickey
Donald
Peter
Danny
Ashley

voteData.txt

```
Mia 2 34
Mickey 1 56
Donald 2 56
Mia 1 78
Danny 4 29
Ashley 4 78
Mickey 2 63
Donald 1 23
Peter 2 56
Danny 1 25
Peter 4 23
Danny 4 12
Ashley 4 82
Mickey 3 67
Donald 2 67
Mia 3 67
Ashley 1 23
Mia 1 56
Donald 2 35
Peter 1 27
Danny 2 34
Peter 4 23
Mickey 4 89
Peter 1 23
Danny 3 89
Mia 3 89
Peter 1 67
Danny 2 37
Ashley 2 89
Mia 2 78
Donald 1 87
Peter 1 90
Danny 4 56
```

NOTE

The complete listing of this program is available at the Web site accompanying this book.

QUICK REVIEW

1. A list is a set of elements of the same type.
2. The length of a list is the number of elements in the list.
3. A one-dimensional array is a convenient place to store and process lists.
4. The sequential search algorithm searches a list for a given item, starting with the first element in the list. It continues to compare the search item with

the other elements in the list until either the item is found or the list has no more elements left to be compared with the search item.

5. On average, the sequential search searches half of the list.
6. The sequential search is good only for very short lists.
7. To sort a list, say `list`, of n elements, the bubble sort algorithm works as follows: In a series of $n - 1$ iterations, the successive elements, `list[index]` and `list[index + 1]`, of `list` are compared. If `list[index]` is greater than `list[index + 1]`, then the elements `list[index]` and `list[index + 1]` are interchanged.
8. For a list of length n , bubble sort given in this chapter makes exactly $\frac{n(n-1)}{2}$ key comparisons and, on average, about $\frac{n(n-1)}{4}$ item assignments.
9. Selection sort sorts the list by finding the smallest (or equivalently largest) element in the list and moving it to the beginning (or end) of the list.
10. For a list of length n , selection sort makes exactly $\frac{n(n-1)}{2}$ key comparisons and $3(n-1)$ item assignments.
11. Insertion sort algorithm sorts the list by moving each element to its proper place.
12. For a list of length n , on average, insertion sort makes $\frac{n^2+3n-4}{4}$ key comparisons and about $\frac{n(n-1)}{4}$ item assignments.
13. Binary search is much faster than the sequential search.
14. Binary search requires that the list elements are in order—that is, the list must be sorted.
15. For a list of length 1024, to determine whether an item is in the list, the binary search algorithm requires no more than 22 key comparisons.
16. In addition to arrays, C++ provides the `vector` type (most commonly called the `class vector`) to implement a list.
17. Unlike an array, the size of a `vector` object can increase and decrease during program execution. Therefore, you do not need to be concerned with the number of data elements.
18. When you declare a `vector` object, you must specify the type of element the `vector` object stores.
19. The elements in a `vector` can be processed just as they are in an array. As in an array, the first element in a `vector` object is at location 0.
20. The following functions can be used to perform various operations on a `vector` object: `at`, `front`, `back`, `clear`, `push_back`, `pop_back`, `empty`, `size`, `resize`, and `max_size`. For a description of these functions, see Table 10-2.

EXERCISES

1. Mark the following statements as true or false.
 - a. A sequential search of a list assumes that the list elements are sorted in ascending order.
 - b. A binary search of a list assumes that the list is sorted.
 - c. A binary search is faster on ordered lists and slower on unordered lists.
 - d. A binary search is faster on large lists, but a sequential search is faster on small lists.
 - e. When you declare a **vector** object and specify its size as 10, then only 10 elements can be stored in the object.

2. Consider the following list:

63 45 32 98 46 57 28 100

Using a sequential search, how many comparisons are required to determine whether the following items are in the list or not? (Recall that comparisons mean item comparisons, not index comparisons.)

a. 90 b. 57 c. 63 d. 120

3.
 - a. Write a version of the sequential search algorithm that can be used to search a sorted list.
 - b. Consider the following list:

5 12 17 35 46 65 78 85 93 110 115

Using a sequential search on ordered lists, which you designed in (a), how many comparisons are required to determine whether the following items are in the list or not? (Recall that comparisons mean item comparisons, not index comparisons.)

i. 35 ii. 60 iii. 78 iv. 120

4. Consider the following list:

2 10 17 45 49 55 68 85 92 98 110

Using the binary search, how many comparisons are required to determine whether the following items are in the list or not? Show the values of **first**, **last**, and **middle** and the number of comparisons after each iteration of the loop.

a. 15 b. 49 c. 98 d. 99

5. Sort the following list using the bubble sort algorithm as discussed in this chapter. Show the list after each iteration of the outer **for** loop.

26, 45, 17, 65, 33, 55, 12, 18

6. Sort the following list using the selection sort algorithm as discussed in this chapter. Show the list after each iteration of the outer `for` loop.

36, 55, 17, 35, 63, 85, 12, 48, 3, 66

7. Consider the following list:

5, 18, 21, 10, 55, 20

The first three keys are in order. To move 10 to its proper position using the insertion sort as described in this chapter, exactly how many key comparisons are executed?

8. Consider the following list:

7, 28, 31, 40, 5, 20

The first four keys are in order. To move 5 to its proper position using the insertion sort as described in this chapter, exactly how many key comparisons are executed?

9. Consider the following list:

28, 18, 21, 10, 25, 30, 12, 71, 32, 58, 15

This list is to be sorted using the insertion sort algorithm as described in this chapter. Show the resulting list after six passes of the sorting phase—that is, after six iterations of the `for` loop.

10. Recall the insertion sort algorithm as discussed in this chapter. Assume the following list of keys:

18, 8, 11, 9, 15, 20, 32, 61, 22, 48, 75, 83, 35, 3

Exactly how many key comparisons are executed to sort this list using insertion sort?

11. Suppose that `L` is a list of 10,000 elements. Find the average number of comparisons made by bubble sort, selection sort, and insertion sort to sort `L`.
12. a. It was remarked in this chapter that the performance of bubble sort can be improved if we stop the sorting process as soon as we find that in an iteration, no swapping of elements takes place. Write a function that implements bubble sort algorithm using this fact.
- b. Using the algorithm that you designed in part (a), find the number of iterations that are needed to sort the list: 65, 14, 52, 43, 75, 25, 80, 90, 95.
13. Suppose that `L` is a sorted list of 4096 elements. What is the maximum number of comparisons made by binary search to determine whether an item is in `L`?
14. Suppose that the elements of a list are in descending order, and they need to be put in ascending order. Write a C++ function that takes as input an array of items in descending order and the number of elements in the array. The function rearranges the element of the array in ascending order. Your function must not incorporate any sorting algorithms, that is, no item comparisons should take place.

15. To use a `vector` object in a program, which header file must be included in the program?
16. What do the following statements do?
 - a. `vector<int> list(50);`
 - b. `vector<string> nameList;`
17. What is the output of the following C++ code?


```
vector<int> intList(5);
int i;

for (i = 0; i < 5; i++)
    intList[i] = 2 * i + 1;

for (i = 0; i < 5; i++)
    cout << intList.at(i) << " ";

cout << endl;
```
18. What is the output of the following C++ code?


```
vector<string> classList;

classList.push_back("Nisha");
classList.push_back("Tony");
classList.push_back("Bobby");
classList.push_back("Peter");

for (unsigned int i = 0; i < classList.size(); i++)
    cout << classList[i] << " ";

cout << endl;
```
19.
 - a. Write a C++ statement that declares `secretList` to be a `vector` object to store integers. (Do not specify the size of `secretList`.)
 - b. Write C++ statements to store the following values, in the order given, into `secretList`:
56, 28, 32, 96, 75
 - c. Write a `for` loop that outputs the contents of `secretList`. (Use the expression `secretList.size()` to determine the size of `secretList`.)
20. What is the output of the following C++ code?


```
vector<int> intList(10);

for (int i = 0; i < 10; i++)
    intList[i] = 2 * i + 5;

cout << intList.front() << " " << intList.back() << endl;
```

21. Suppose that you have the following C++ code:

```
vector<int> myList(5);

unsigned int length;

myList[0] = 3;
for (int i = 1; i < 4; i++)
    myList[i] = 2 * myList[i - 1] - 5;

myList.push_back(46);
myList.push_back(57);
myList.push_back(35);
```

- a. Write a C++ statement that outputs the first and the last elements of `myList`. (Do not use the array subscripting operator or the index of the elements.)
 - b. Write a C++ statement that stores the size of `myList` into `length`.
 - c. Write a `for` loop that outputs the elements of `myList`.
22. What is the difference between the size and capacity of a vector?

PROGRAMMING EXERCISES

1. Write a program to test the function `seqOrderedSearch`. Use either the function `bubbleSort` or `selectionSort` to sort the list before the search.
2. Write a program to test the function `binarySearch`. Use either the function `bubbleSort` or `selectionSort` to sort the list before the search.
3. Write a function, `remove`, that takes three parameters: an array of integers, the number of elements in the array, and an integer (say, `removeItem`). The function should find and delete the first occurrence of `removeItem` in the array. If the value does not exist or the array is empty, output an appropriate message. (Note that after deleting the element, the number of elements in the array is reduced by 1.) Assume that the array is unsorted.
4. Write a function, `removeAt`, that takes three parameters: an array of integers, the number of elements in the array, and an integer (say, `index`). The function should delete the array element indicated by `index`. If `index` is out of range or the array is empty, output an appropriate message. (Note that after deleting the element, the number of elements in the array is reduced by 1.) Assume that the array is unsorted.
5. Write a function, `removeAll`, that takes three parameters: an array of integers, the number of elements in the array, and an integer (say, `removeItem`). The function should find and delete all of the occurrences of `removeItem` in the array. If the value does not exist or the array is empty, output an appropriate message. (Note that after deleting the element, the number of elements in the array is reduced.) Assume that the array is unsorted.

6. Redo Exercises 3, 4, and 5 for a sorted array.
7. Write a function, `insertAt`, that takes four parameters: an array of integers, the number of elements in the array, an integer (say, `insertItem`), and an integer (say, `index`). The function should insert `insertItem` in the array at the position specified by `index`. If `index` is out of range, output an appropriate message. (Note that `index` must be between 0 and the number of elements in the array; that is, $0 \leq \text{index} < \text{the number of elements in the array}$.) Assume that the array is unsorted.
8. Write a version of the selection sort algorithm that can be used to sort a list of strings.
9. Write a version of the binary search algorithm that can be used to search a list of strings. (Use the selection sort that you designed in Exercise 8 to sort the list.)
10. Write a version of the sequential search algorithm that can be used to search a string `vector` object. Also, write a program to test your algorithm.
11. Write a version of the bubble sort algorithm that can be used to sort a string `vector` object. Also, write a program to test your algorithm.
12. Write a version of the selection sort algorithm that can be used to sort a string `vector` object. Also, write a program to test your algorithm.
13. Write a program to test the insertion sort algorithm as given in this chapter.
14. Write a version of the insertion sort algorithm that can be used to sort a string `vector` object. Also, write a program to test your algorithm.
15. Write a version of the binary search algorithm that can be used to search a string `vector` object. Also, write a program to test your algorithm. (Use the selection sort algorithm you developed in Programming Exercise 12 to sort the vector.)
16. Write a program that creates three identical arrays, `list1`, `list2`, and `list3` of 5000 elements. The program then sorts `list1` using bubble sort, `list2` using selection sort, and `list3` using insertion sort and outputs the number of comparisons and item assignments made by each sorting algorithm.
17. Write a program to test the function you designed in Exercise 12 to improve the performance of bubble sort.
18. Write a program to test the function you designed in Exercise 14.
19. Write a program that reads in a set of positive integers, representing test scores for a class, and outputs how many times a particular number appears in the list. You may assume that the data set has, at most, 100 numbers and that `-999` marks the end of the input data. The numbers must be output in increasing order. For example, for the data:

55 80 78 92 95 55 78 53 92 65 78 95 85 92 85 95 95

the output is:

| Test Score | Count |
|------------|-------|
| 53 | 1 |
| 55 | 2 |
| 65 | 1 |
| 78 | 3 |
| 80 | 1 |
| 85 | 2 |
| 92 | 3 |
| 95 | 4 |

20. In Programming Exercise 13 (Chapter 9), you are asked to write a program to calculate students' average test scores and their grades. Improve this programming exercise by adding a function to sort students' names so that students' data is output into ascending order according to their name.
21. Your state is in a process of creating a weekly lottery. Once a week, five distinct random integers between 1 to 40 (inclusive) are drawn. If a player guesses all of the numbers correctly, the player wins a certain amount. Write a program that does the following:
 - a. Generates five distinct random numbers between 1 and 40 (inclusive) and stores them in an array.
 - b. Sorts the array containing the lottery numbers.
 - c. Prompts the player to select five distinct integers between 1 and 40 (inclusive) and stores the numbers in an array. The player can select the numbers in any order, and the array containing the numbers need not be sorted.
 - d. Determines whether the player guessed the lottery numbers correctly. If the player guessed the lottery numbers correctly, it outputs the message "You win!"; otherwise it outputs the message "You lose!" and outputs the lottery numbers.

Your program should allow a player to play the game as many times as the player wants to play. Before each play, generate a new set of lottery numbers.

22. Redo the Election Results Programming Example (in this chapter) so that the names of the candidates and the total votes are stored in `vector` objects.
23. Write a program to keep track of a hardware store inventory. The store sells various items. For each item in the store, the following information is kept: item ID, item name, number of pieces ordered, number of pieces currently in the store, number of pieces sold, manufacturer's price for the item, and the store's selling price. At the end of each week, the store manager would like to see a report in the following form:

Friendly Hardware Store

| itemID | itemName | pOrdered | pInStore | pSold | manufPrice | sellingPrice |
|--------|---------------|----------|----------|-------|------------|--------------|
| 4444 | Circular Saw | 150 | 150 | 40 | 45.00 | 125.00 |
| 3333 | Cooking Range | 50 | 50 | 20 | 450.00 | 850.00 |
| . | | | | | | |
| . | | | | | | |
| . | | | | | | |

Total Inventory: \$#####.##

Total number of items in the store: _____

The total inventory is the total selling value of all of the items currently in the store. The total number of items is the sum of the number of pieces of all of the items in the store.

Your program must be menu driven, giving the user various choices, such as checking whether an item is in the store, selling an item, and printing the report. After inputting the data, sort it according to the items' names. Also, after an item is sold, update the appropriate counts.

Initially, the number of pieces (of an item) in the store is the same as the number of pieces ordered, and the number of pieces of an item sold is zero. Input to the program is a file consisting of data in the following form:

```

itemID
itemName
pOrdered manufPrice sellingPrice

```

Use seven parallel vectors to store the information. The program must contain at least the following functions: one to input data into the vectors, one to display the menu, one to sell an item, and one to print the report for the manager.

This page intentionally left blank



11

CHAPTER

RECORDS (structs)

IN THIS CHAPTER, YOU WILL:

- Learn about records (`structs`)
- Examine various operations on a `struct`
- Explore ways to manipulate data using a `struct`
- Learn about the relationship between a `struct` and functions
- Discover how arrays are used in a `struct`
- Learn how to create an array of `struct` items

In Chapter 9, you learned how to group values of the same type by using arrays. You also learned how to process data stored in an array and how to perform list operations, such as searching and sorting.

NOTE

This chapter may be skipped without experiencing any discontinuation.

In this chapter, you will learn how to group related values that are of different types. C++ provides another structured data type, called a **struct** (some languages use the term “record”), to group related items of different types. An array is a homogeneous data structure; a **struct** is typically a heterogeneous data structure. The treatment of a **struct** in this chapter is similar to the treatment of a **struct** in C. A **struct** in this chapter, therefore, is a C-like **struct**. Chapter 12 introduces and discusses another structured data type, called a class.

Records (structs)

Suppose that you want to write a program to process student data. A student record consists of, among other things, the student’s name, student ID, GPA, courses taken, and course grades. Thus, various components are associated with a student. However, these components are all of different types. For example, the student’s name is a string, and the GPA is a floating-point number. Because these components are of different types, you cannot use an array to group all of the items associated with a student. C++ provides a structured data type called **struct** to group items of different types. Grouping components that are related but of different types offers several advantages. For example, a single variable can pass all the components as parameters to a function.

struct: A collection of a fixed number of components in which the components are accessed by name. The components may be of different types.

The components of a **struct** are called the members of the **struct**. The general syntax of a **struct** in C++ is:

```
struct structName
{
    dataType1 identifier1;
    dataType2 identifier2;
    .
    .
    .
    dataTypeN identifierN;
};
```

In C++, **struct** is a reserved word. The members of a **struct**, even though they are enclosed in braces (that is, they form a block), are not considered to form a compound statement. Thus, a semicolon (after the right brace) is essential to end the **struct** statement. A semicolon at the end of the **struct** definition is, therefore, a part of the syntax.

The statement:

```
struct employeeType
{
    string firstName;
    string lastName;
    string address1;
    string address2;
    double salary;
    string deptID;
};
```

defines a **struct** `employeeType` with six members. The members `firstName`, `lastName`, `address1`, `address2`, and `deptID` are of type **string**, and the member `salary` is of type **double**.


Like any type definition, a **struct** is a definition, not a declaration. That is, it defines only a data type; no memory is allocated.

Once a data type is defined, you can declare variables of that type. Let us first define a **struct** type, `studentType`, and then declare variables of that type.

```
struct studentType
{
    string firstName;
    string lastName;
    char courseGrade;
    int testScore;
    int programmingScore;
    double GPA;
};

    //variable declaration
studentType newStudent;
studentType student;
```

These statements declare two **struct** variables, `newStudent` and `student`, of type `studentType`. The memory allocated is large enough to store `firstName`, `lastName`, `courseGrade`, `testScore`, `programmingScore`, and `GPA` (see Figure 11-1).

FIGURE 11-1 `structs` `newStudent` and `student`**NOTE**

You can also declare `struct` variables when you define the `struct`. For example, consider the following statements:

```
struct studentType
{
    string firstName;
    string lastName;
    char courseGrade;
    int testScore;
    int programmingScore;
    double GPA;
} tempStudent;
```

These statements define the `struct` `studentType` and also declare `tempStudent` to be a variable of type `studentType`.

Typically, in a program, a `struct` is defined before the definitions of all of the functions in the program so that the `struct` can be used throughout the program. Therefore, if you define a `struct` and also simultaneously declare a `struct` variable (as in the preceding statements), then that `struct` variable becomes a global variable and thus can be accessed anywhere in the program. Keeping in mind the side effects of global variables, you first should only define a `struct` and then declare the `struct` variables.

Accessing `struct` Members

In arrays, you access a component by using the array name together with the relative position (index) of the component. The array name and index are separated using square brackets. To access a structure member (component), you use the `struct` variable name together with the member name; these names are separated by a dot (period). The syntax for accessing a `struct` member is:

```
structVariableName.memberName
```

The `structVariableName.memberName` is just like any other variable. For example, `newStudent.courseGrade` is a variable of type `char`, `newStudent.firstName` is a string variable, and so on. As a result, you can do just about anything with `struct` members that you normally do with variables. You can, for example, use them in assignment statements or input/output (where permitted) statements.

In C++, the dot (`.`) is an operator called the **member access operator**.

Suppose you want to initialize the member GPA of `newStudent` to `0.0`. The following statement accomplishes this task:

```
newStudent.GPA = 0.0;
```

Similarly, the statements:

```
newStudent.firstName = "John";
newStudent.lastName = "Brown";
```

store "John" in the member `firstName` and "Brown" in the member `lastName` of `newStudent`.

After the preceding three assignment statements execute, `newStudent` is as shown in Figure 11-2.




FIGURE 11-2 `struct newStudent`

The statement:

```
cin >> newStudent.firstName;
```

reads the next string from the standard input device and stores it in:

```
newStudent.firstName
```

The statement:

```
cin >> newStudent.testScore >> newStudent.programmingScore;
```

reads two integer values from the keyboard and stores them in `newStudent.testScore` and `newStudent.programmingScore`, respectively.

Suppose that `score` is a variable of type `int`. The statement:

```
score = (newStudent.testScore + newStudent.programmingScore) / 2;
```

assigns the average of `newStudent.testScore` and `newStudent.programmingScore` to `score`.

The following statement determines the course grade and stores it in `newStudent.courseGrade`:

```
if (score >= 90)
    newStudent.courseGrade = 'A';
else if (score >= 80)
    newStudent.courseGrade = 'B';
else if (score >= 70)
    newStudent.courseGrade = 'C';
else if (score >= 60)
    newStudent.courseGrade = 'D';
else
    newStudent.courseGrade = 'F';
```

Assignment

We can assign the value of one `struct` variable to another `struct` variable of the same type by using an assignment statement. Suppose that `newStudent` is as shown in Figure 11-3.




FIGURE 11-3 `struct newStudent`

The statement:

```
student = newStudent;
```

copies the contents of `newStudent` into `student`. After this assignment statement executes, the values of `student` are as shown in Figure 11-4.

| | |
|------------------|----------|
| student | |
| firstName | Lisa |
| lastName | Robinson |
| courseGrade | A |
| testScore | 95 |
| programmingScore | 98 |
| GPA | 3.9 |

FIGURE 11-4 `student` after `student = newStudent`

In fact, the assignment statement:

```
student = newStudent;
```

is equivalent to the following statements:

```
student.firstName = newStudent.firstName;
student.lastName = newStudent.lastName;
student.courseGrade = newStudent.courseGrade;
student.testScore = newStudent.testScore;
student.programmingScore = newStudent.programmingScore;
student.GPA = newStudent.GPA;
```

Comparison (Relational Operators)

To compare **struct** variables, you compare them member-wise. As with an array, no aggregate relational operations are performed on a **struct**. For example, suppose that `newStudent` and `student` are declared as shown earlier. Furthermore, suppose that you want to see whether `student` and `newStudent` refer to the same student. Now `newStudent` and `student` refer to the same student if they have the same first name and the same last name. To compare the values of `student` and `newStudent`, you must compare them member-wise, as follows:

```
if (student.firstName == newStudent.firstName &&
    student.lastName == newStudent.lastName)
.
.
.
```

Although you can use an assignment statement to copy the contents of one `struct` into another `struct` of the same type, you cannot use relational operators on `struct` variables. Therefore, the following would be illegal:

```
if (student == newStudent)    //illegal
.
.
.
```

Input/Output

No aggregate input/output operations are allowed on a `struct` variable. Data in a `struct` variable must be read one member at a time. Similarly, the contents of a `struct` variable must be written one member at a time.

We have seen how to read data into a `struct` variable. Let us now see how to output a `struct` variable. The statement:

```
cout << newStudent.firstName << " " << newStudent.lastName
    << " " << newStudent.courseGrade
    << " " << newStudent.testScore
    << " " << newStudent.programmingScore
    << " " << newStudent.GPA << endl;
```

outputs the contents of the `struct` variable `newStudent`.

struct Variables and Functions

Recall that arrays are passed by reference only, and a function cannot return a value of type `array`. However:

- A `struct` variable can be passed as a parameter either by value or by reference, and
- A function can return a value of type `struct`.

The following function reads and stores a student's first name, last name, test score, programming score, and GPA. It also determines the student's course grade and stores it in the member `courseGrade`.

```
void readIn(studentType& student)
{
    int score;

    cin >> student.firstName >> student.lastName;
    cin >> student.testScore >> student.programmingScore;
    cin >> student.GPA;

    score = (newStudent.testScore + newStudent.programmingScore) / 2;

    if (score >= 90)
        student.courseGrade = 'A';
```

```
else if (score >= 80)
    student.courseGrade = 'B';
else if (score >= 70)
    student.courseGrade = 'C';
else if (score >= 60)
    student.courseGrade = 'D';
else
    student.courseGrade = 'F';
}
```

The statement:

```
readIn(newStudent);
```

calls the function `readIn`. The function `readIn` stores the appropriate information in the variable `newStudent`.

Similarly, we can write a function that will print the contents of a **struct** variable. For example, the following function outputs the contents of a **struct** variable of type `studentType` on the screen:

```
void printStudent(studentType student)
{
    cout << student.firstName << " " << student.lastName
        << " " << student.courseGrade
        << " " << student.testScore
        << " " << student.programmingScore
        << " " << student.GPA << endl;
}
```

Arrays versus **structs**

The previous discussion showed us that a **struct** and an array have similarities as well as differences. Table 11-1 summarizes this discussion.

TABLE 11-1 Arrays vs. **structs**

| Aggregate Operation | Array | struct |
|----------------------------|---------------------|--------------------------|
| Arithmetic | No | No |
| Assignment | No | Yes |
| Input/output | No (except strings) | No |
| Comparison | No | No |
| Parameter passing | By reference only | By value or by reference |
| Function returning a value | No | Yes |

Arrays in structs

A list is a set of elements of the same type. Thus, a list has two things associated with it: the values (that is, elements) and the length. Because the values and the length are both related to a list, we can define a **struct** containing both items.

```
const int ARRAY_SIZE = 1000;

struct listType
{
    int listElem[ARRAY_SIZE];    //array containing the list
    int listLength;              //length of the list
};
```

The following statement declares `intList` to be a **struct** variable of type `listType` (see Figure 11-5):

```
listType intList;
```




FIGURE 11-5 **struct** variable `intList`

The variable `intList` has two members: `listElem`, an array of 1000 components of type `int`, and `listLength`, of type `int`. Moreover, `intList.listElem` accesses the member `listElem`, and `intList.listLength` accesses the member `listLength`.

Consider the following statements:

```
intList.listLength = 0;           //Line 1
intList.listElem[0] = 12;        //Line 2
intList.listLength++;            //Line 3
intList.listElem[1] = 37;        //Line 4
intList.listLength++;            //Line 5
```

The statement in Line 1 sets the value of the member `listLength` to 0. The statement in Line 2 stores 12 in the first component of the array `listElem`. The statement in Line 3 increments the value of `listLength` by 1. The meaning of the other statements is similar. After these statements execute, `intList` is as shown in Figure 11-6.




FIGURE 11-6 `intList` after the statements in Lines 1 through 5 execute

Next, we write the sequential search algorithm to determine whether a given item is in the list. If `searchItem` is found in the list, then the function returns its location in the list; otherwise, the function returns -1.

```
int seqSearch(const listType& list, int searchItem)
{
    int loc;

    bool found = false;

    for (loc = 0; loc < list.listLength; loc++)
        if (list.listElem[loc] == searchItem)
        {
            found = true;
            break;
        }

    if (found)
        return loc;
    else
        return -1;
}
```

In this function, because `listLength` is a member of `list`, we access this by `list.listLength`. Similarly, we can access an element of `list` via `list.listElem[loc]`.

Notice that the formal parameter `list` of the function `seqSearch` is declared as a constant reference parameter. This means that `list` receives the address of the corresponding actual parameter, but `list` cannot modify the actual parameter.

Recall that when a variable is passed by value, the formal parameter copies the value of the actual parameter. Therefore, if the formal parameter modifies the data, the modification has no effect on the data of the actual parameter.

Suppose that a **struct** has several data members requiring a large amount of memory to store the data, and you need to pass a variable of that **struct** type by value. The corresponding formal parameter then receives a copy of the data of the variable. The compiler must then allocate memory for the formal parameter in order to copy the value of the actual parameter. This operation might require, in addition to a large amount of storage space, a considerable amount of computer time to copy the value of the actual parameter into the formal parameter.

On the other hand, if a variable is passed by reference, the formal parameter receives only the address of the actual parameter. Therefore, an efficient way to pass a variable as a parameter is by reference. If a variable is passed by reference, then when the formal parameter changes, the actual parameter also changes. Sometimes, however, you do not want the function to be able to change the values of the actual parameter. In C++, you can pass a variable by reference and still prevent the function from changing its value. This is done by using the keyword **const** in the formal parameter declaration, as shown in the definition of the function `seqSearch`.

Likewise, we can also rewrite the sorting, binary search, and other list-processing functions.

structs in Arrays

Suppose a company has 50 full-time employees. We need to print their monthly paychecks and keep track of how much money has been paid to each employee in the year-to-date. First, let's define an employee's record:

```
struct employeeType
{
    string firstName;
    string lastName;
    int    personID;
    string deptID;
    double yearlySalary;
    double monthlySalary;
    double yearToDatePaid;
    double monthlyBonus;
};
```

Each employee has the following members (components): first name, last name, personal ID, department ID, yearly salary, monthly salary, year-to-date paid, and monthly bonus.

Because we have 50 employees and the data type of each employee is the same, we can use an array of 50 components to process the employees' data.

```
employeeType employees[50];
```

This statement declares the array `employees` of 50 components of type `employeeType` (see Figure 11-7). Every element of `employees` is a **struct**. For example, Figure 11-7 also shows `employees[2]`.




FIGURE 11-7 Array of employees

Suppose we also have the following declaration:

```
int counter;
```

Further, suppose that every employee's initial data—first name, last name, personal ID, department ID, and yearly salary—are provided in a file. For our discussion, we assume that each employee's data is stored in a file, say, `employee.dat`. The following C++ code loads the data into the employees' array. We assume that, initially, `yearToDatePaid` is 0 and that the monthly bonus is determined each month based on performance.

```
ifstream infile; //input stream variable
                //assume that the file employee.dat has been opened
for (counter = 0; counter < 50; counter++)
{
    infile >> employees[counter].firstName
    >> employees[counter].lastName
    >> employees[counter].personID
    >> employees[counter].deptID
    >> employees[counter].yearlySalary;
    employees[counter].monthlySalary =
        employees[counter].yearlySalary / 12;
    employees[counter].yearToDatePaid = 0.0;
    employees[counter].monthlyBonus = 0.0;
}
```

Suppose that for a given month, the monthly bonuses are already stored in each employee's record, and we need to calculate the monthly paycheck and update the `yearToDatePaid` amount. The following loop computes and prints the employee's paycheck for the month:

```
double payCheck; //variable to calculate the paycheck

for (counter = 0; counter < 50; counter++)
```

```

{
    cout << employees[counter].firstName << " "
         << employees[counter].lastName << " ";

    payCheck = employees[counter].monthlySalary +
               employees[counter].monthlyBonus;

    employees[counter].yearToDatePaid =
        employees[counter].yearToDatePaid +
        payCheck;

    cout << setprecision(2) << payCheck << endl;
}

```

structs within a struct

You have seen how the **struct** and array data structures can be combined to organize information. You also saw examples wherein a member of a **struct** is an array, and the array type is a **struct**. In this section, you will learn about situations for which it is beneficial to organize data in a **struct** by using another **struct**.

Let us consider the following employee record:

```

struct employeeType
{
    string firstname;
    string middlename;
    string lastname;
    string empID;
    string address1;
    string address2;
    string city;
    string state;
    string zip;
    int hiremonth;
    int hireday;
    int hireyear;
    int quitmonth;
    int quitday;
    int quityear;
    string phone;
    string cellphone;
    string fax;
    string pager;
    string email;
    string deptID;
    double salary;
};

```

As you can see, a lot of information is packed into one **struct**. This **struct** has 22 members. Some members of this **struct** will be accessed more frequently than others, and some members are more closely related than others. Moreover, some members will

have the same underlying structure. For example, the hire date and the quit date are of the date type **int**. Let us reorganize this **struct** as follows:

```
struct nameType
{
    string first;
    string middle;
    string last;
};

struct addressType
{
    string address1;
    string address2;
    string city;
    string state;
    string zip;
};

struct dateType
{
    int month;
    int day;
    int year;
};

struct contactType
{
    string phone;
    string cellphone;
    string fax;
    string pager;
    string email;
};
```

We have separated the employee's name, address, and contact type into subcategories. Furthermore, we have defined a **struct** **dateType**. Let us rebuild the employee's record as follows:

```
struct employeeType
{
    nameType name;
    string empID;
    addressType address;
    dateType hireDate;
    dateType quitDate;
    contactType contact;
    string deptID;
    double salary;
};
```

The information in this employee's **struct** is easier to manage than the previous one. Some of this **struct** can be reused to build another **struct**. For example, suppose that you want to define a customer's record. Every customer has a first name, last name, and

middle name, as well as an address and a way to be contacted. You can, therefore, quickly put together a customer's record by using the `structs` `nameType`, `addressType`, `contactType`, and the members specific to the customer.

Next, let us declare a variable of type `employeeType` and discuss how to access its members. Consider the following statement:

```
employeeType newEmployee;
```

This statement declares `newEmployee` to be a `struct` variable of type `employeeType` (see Figure 11-8).




FIGURE 11-8 `struct` variable `newEmployee`

The statement:

```
newEmployee.salary = 45678.00;
```

sets the salary of `newEmployee` to 45678.00. The statements:

```
newEmployee.name.first = "Mary";
newEmployee.name.middle = "Beth";
newEmployee.name.last = "Simmons";
```

set the `first`, `middle`, and `last` name of `newEmployee` to "Mary", "Beth", and "Simmons", respectively. Note that `newEmployee` has a member called `name`. We access this member via `newEmployee.name`. Note also that `newEmployee.name` is a **struct** and has three members. We apply the member access criteria to access the member `first` of the **struct** `newEmployee.name`. So, `newEmployee.name.first` is the member where we store the first name.

The statement:

```
cin >> newEmployee.name.first;
```

reads and stores a string into `newEmployee.name.first`. The statement:

```
newEmployee.salary = newEmployee.salary * 1.05;
```

updates the salary of `newEmployee`.

The following statement declares `employees` to be an array of 100 components, wherein each component is of type `employeeType`:

```
employeeType employees[100];
```

The **for** loop:

```
for (int j = 0; j < 100; j++)
    cin >> employees[j].name.first >> employees[j].name.middle
        >> employees[j].name.last;
```

reads and stores the names of 100 employees in the array `employees`. Because `employees` is an array, to access a component, we use the index. For example, `employees[50]` is the 51st component of the array `employees` (recall that an array index starts with 0). Because `employees[50]` is a **struct**, we apply the member access criteria to select a particular member.

PROGRAMMING EXAMPLE: Sales Data Analysis

A company has six salespeople. Every month, they go on road trips to sell the company's product. At the end of each month, the total sales for each salesperson, together with that salesperson's ID and the month, is recorded in a file. At the end of each year, the manager of the company wants to see this report in the following tabular format:

----- Annual Sales Report -----

| ID | QT1 | QT2 | QT3 | QT4 | Total |
|-------|---------|---------|----------|---------|----------|
| 12345 | 1892.00 | 0.00 | 494.00 | 322.00 | 2708.00 |
| 32214 | 343.00 | 892.00 | 9023.00 | 0.00 | 10258.00 |
| 23422 | 1395.00 | 1901.00 | 0.00 | 0.00 | 3296.00 |
| 57373 | 893.00 | 892.00 | 8834.00 | 0.00 | 10619.00 |
| 35864 | 2882.00 | 1221.00 | 0.00 | 1223.00 | 5326.00 |
| 54654 | 893.00 | 0.00 | 392.00 | 3420.00 | 4705.00 |
| Total | 8298.00 | 4906.00 | 18743.00 | 4965.00 | |

Max Sale by SalesPerson: ID = 57373, Amount = \$10619.00

Max Sale by Quarter: Quarter = 3, Amount = \$18743.00

In this report, QT1 stands for quarter 1 (months 1 to 3), QT2 for quarter 2 (months 4 to 6), QT3 for quarter 3 (months 7 to 9), and QT4 for quarter 4 (months 10 to 12).

The salespeople's IDs are stored in one file; the sales data is stored in another file. The sales data is in the following form:

```
salesPersonID  month  saleAmount
.
.
.
```

Furthermore, the sales data is in no particular order; it is not ordered by ID.

A sample sales data is:

```
12345 1 893
32214 1 343
23422 3 903
57373 2 893
.
.
.
```

Let us write a program that produces the output in the specified format.

Input One file containing each salesperson's ID and a second file containing the sales data.

Output A file containing the annual sales report in the above format.

PROBLEM ANALYSIS AND ALGORITHM DESIGN

Based on the problem's requirements, it is clear that the main components for each salesperson are the salesperson's ID, quarterly sales amount, and total annual sales amount. Because the components are of different types, we can group them with the help of a `struct`, defined as follows:

```
struct salesPersonRec
{
    string ID;           //salesperson's ID
    double saleByQuarter[4]; //array to store the total
                           //sales for each quarter
    double totalSale;    //salesperson's yearly sales amount
};
```

Because there are six salespeople, we use an array of six components, wherein each component is of type `salesPersonRec`, defined as follows:

```
salesPersonRec salesPersonList[NO_OF_SALES_PERSON];
```

wherein the value of `NO_OF_SALES_PERSON` is 6.


Because the program requires us to find the company's total sales for each quarter, we need an array of four components to store the data. Note that this data will be used to determine the quarter in which the maximum sales were made. Therefore, the program also needs the following array:

```
double totalSaleByQuarter[4];
```

Recall that in C++, the array index starts with 0. Therefore, `totalSaleByQuarter[0]` stores data for quarter 1, `totalSaleByQuarter[1]` stores data for quarter 2, and so on.

We will refer to these variables throughout the discussion.

The array `salesPersonList` is as shown in Figure 11-9.

**FIGURE 11-9** Array `salesPersonList`

The first step of the program is to read the salespeople's IDs into the array `salesPersonList` and initialize the quarterly sales and total sales for each salesperson to 0. After this step, the array `salesPersonList` is as shown in Figure 11-10.

The diagram shows the same array `salesPersonList` after initialization. The `ID` column now contains numerical values, and the `saleByQuarter` and `totalSale` columns are filled with 0.0. The `saleByQuarter` column is divided into four sub-columns.

| | ID | saleByQuarter | | | | totalSale |
|---------------------------------|-------|---------------|-----|-----|-----|-----------|
| <code>salesPersonList[0]</code> | 12345 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| <code>salesPersonList[1]</code> | 32214 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| <code>salesPersonList[2]</code> | 23422 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| <code>salesPersonList[3]</code> | 57373 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| <code>salesPersonList[4]</code> | 35864 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| <code>salesPersonList[5]</code> | 54654 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |

FIGURE 11-10 Array `salesPersonList` after initialization

The next step is to process the sales data. Processing the sales data is quite straightforward. For each entry in the file containing the sales data:

1. Read the salesperson's ID, month, and sale amount for the month.
2. Search the array `salesPersonList` to locate the component corresponding to this salesperson.
3. Determine the quarter corresponding to the month.
4. Update the sales for the quarter by adding the sale amount for the month.

Once the sales data file is processed:

1. Calculate the total sales by salesperson.
2. Calculate the total sales by quarter.
3. Print the report.

This discussion translates into the following algorithm:

1. Initialize the array `salesPersonList`.
2. Process the sales data.
3. Calculate the total sales by quarter.
4. Calculate the total sales by salesperson.
5. Print the report.
6. Calculate and print the maximum sales by salesperson.
7. Calculate and print the maximum sales by quarter.

To reduce the complexity of the main program, let us write a separate function for each of these seven steps.

Function initialize This function reads the salesperson's ID from the input file and stores the salesperson's ID in the array `salesPersonList`. It also initializes the quarterly sales amount and the total sales amount for each salesperson to 0. The definition of this function is:

```
void initialize(ifstream& indata, salesPersonRec list[],
               int listSize)
{
    int index;
    int quarter;

    for (index = 0; index < listSize; index++)
    {
        indata >> list[index].ID; //get salesperson's ID

        for (quarter = 0; quarter < 4; quarter++)
            list[index].saleByQuarter[quarter] = 0.0;

        list[index].totalSale = 0.0;
    }
} //end initialize
```

Function `getData` This function reads the sales data from the input file and stores the appropriate information in the array `salesPersonList`. The algorithm for this function is:

1. Read the salesperson's ID, month, and sales amount for the month.
2. Search the array `salesPersonList` to locate the component corresponding to the salesperson. (Because the salespeople's IDs are not sorted, we will use a sequential search to search the array.)
3. Determine the quarter corresponding to the month.
4. Update the sales for the quarter by adding the sales amount for the month.

Suppose that the entry read is:

57373 2 350

Here, the salesperson's ID is 57373, the month is 2, and the sale amount is 350. Suppose that the array `salesPersonList` is as shown in Figure 11-11.

| salesPersonList | ID | saleByQuarter | | | totalSale | |
|--------------------|-------|---------------|--------|--------|-----------|-----|
| salesPersonList[0] | 12345 | 150.80 | 0.0 | 0.0 | 654.92 | 0.0 |
| salesPersonList[1] | 32214 | 0.0 | 439.90 | 0.0 | 0.0 | 0.0 |
| salesPersonList[2] | 23422 | 0.0 | 0.0 | 0.0 | 564.76 | 0.0 |
| salesPersonList[3] | 57373 | 354.80 | 0.0 | 0.0 | 0.0 | 0.0 |
| salesPersonList[4] | 35864 | 0.0 | 0.0 | 763.90 | 0.0 | 0.0 |
| salesPersonList[5] | 54654 | 783.45 | 0.0 | 0.0 | 563.80 | 0.0 |

FIGURE 11-11 Array `salesPersonList`

Now, ID 57373 corresponds to the array component `salesPersonList[3]`, and month 2 corresponds to quarter 1. Therefore, you add 350 to 354.80 to get the new amount, 704.80. After processing this entry, the array `salesPersonList` is as shown in Figure 11-12.

| | ID | saleByQuarter | | | | totalSale |
|--------------------|-------|---------------|--------|--------|--------|-----------|
| salesPersonList[0] | 12345 | 150.80 | 0.0 | 0.0 | 654.92 | 0.0 |
| salesPersonList[1] | 32214 | 0.0 | 439.90 | 0.0 | 0.0 | 0.0 |
| salesPersonList[2] | 23422 | 0.0 | 0.0 | 0.0 | 564.76 | 0.0 |
| salesPersonList[3] | 57373 | 704.80 | 0.0 | 0.0 | 0.0 | 0.0 |
| salesPersonList[4] | 35864 | 0.0 | 0.0 | 763.90 | 0.0 | 0.0 |
| salesPersonList[5] | 54654 | 783.45 | 0.0 | 0.0 | 563.80 | 0.0 |

FIGURE 11-12 Array `salesPersonList` after processing entry 57373 2 350

The definition of the function `getData` is:

```
void getData(ifstream& infile, salesPersonRec list[],
             int listSize)
{
    int index;
    int quarter;
    string sID;
    int month;
    double amount;

    infile >> sID;           //get salesperson's ID

    while (infile)
    {
        infile >> month >> amount; //get the sale month and
                                   //the sale amount

        for (index = 0; index < listSize; index++)
            if (sID == list[index].ID)
                break;
    }
}
```

```

        if (1 <= month && month <= 3)
            quarter = 0;
        else if (4 <= month && month <= 6)
            quarter = 1;
        else if (7 <= month && month <= 9)
            quarter = 2;
        else
            quarter = 3;

        if (index < listSize)
            list[index].saleByQuarter[quarter] += amount;
        else
            cout << "Invalid salesperson's ID." << endl;

        infile >> sID;
    } //end while
} //end getData

```

Function saleByQuarter This function finds the company's total sales for each quarter. To find the total sales for each quarter, we add the sales amount of each salesperson for that quarter. Clearly, this function must have access to the array `salesPersonList` and the array `totalSaleByQuarter`. This function also needs to know the number of rows in each array. Thus, this function has three parameters. The definition of this function is:

```

void saleByQuarter(salesPersonRec list[], int listSize,
                  double totalByQuarter[])
{
    int quarter;
    int index;

    for (quarter = 0; quarter < 4; quarter++)
        totalByQuarter[quarter] = 0.0;

    for (quarter = 0; quarter < 4; quarter++)
        for (index = 0; index < listSize; index++)
            totalByQuarter[quarter] +=
                list[index].saleByQuarter[quarter];
} //end saleByQuarter

```

Function totalSaleByPerson This function finds each salesperson's yearly sales amount. To find an employee's yearly sales amount, we add that employee's sales amount for the four quarters. Clearly, this function must have access to the array `salesPersonList`. This function also needs to know the size of the array. Thus, this function has two parameters.

The definition of this function is:

```

void totalSaleByPerson(salesPersonRec list[], int listSize)
{
    int index;
    int quarter;

```

```

    for (index = 0; index < listSize; index++)
        for (quarter = 0; quarter < 4; quarter++)
            list[index].totalSale +=
                list[index].saleByQuarter[quarter];
} //end totalSaleByPerson

```

Function `printReport` This function prints the annual report in the specified format. The algorithm in pseudocode is:

1. Print the heading—that is, the first three lines of output.
2. Print the data for each salesperson.
3. Print the last line of the table.

Note that the next two functions will produce the final two lines of output.

Clearly, the `printReport` function must have access to the array `salesPersonList` and the array `totalSaleByQuarter`. Also, because the output will be stored in a file, this function must have access to the `ofstream` variable associated with the output file. Thus, this function has four parameters: a parameter corresponding to the array `salesPersonList`, a parameter corresponding to the array `totalSaleByQuarter`, a parameter specifying the size of the array, and a parameter corresponding to the `ofstream` variable. The definition of this function is:

```

void printReport(ofstream& outfile, salesPersonRec list[],
                int listSize, double saleByQuarter[])
{
    int index;
    int quarter;

    outfile << "----- Annual Sales Report -----"
              << "-----" << endl;
    outfile << endl;
    outfile << "   ID           QT1           QT2           QT3           "
              << "QT4           Total" << endl;
    outfile << "_____ "
              << "_____ " << endl;

    for (index = 0; index < listSize; index++)
    {
        outfile << list[index].ID << "   ";

        for (quarter = 0; quarter < 4; quarter++)
            outfile << setw(10)
                      << list[index].saleByQuarter[quarter];

        outfile << setw(10) << list[index].totalSale << endl;
    }

    outfile << "Total   ";
}

```

```

        for (quarter = 0; quarter < 4; quarter++)
            outfile << setw(10)<< saleByQuarter[quarter];

        outfile << endl << endl;
    } //end printReport

```

Function `maxSaleByPerson` This function prints the name of the salesperson who produces the maximum sales amount. To identify this salesperson, we look at the sales total for each salesperson and find the largest sales amount. Because each employee's sales total is maintained in the array `salesPersonList`, this function must have access to the array `salesPersonList`. Also, because the output will be stored in a file, this function must have access to the `ofstream` variable associated with the output file. Therefore, this function has three parameters: a parameter corresponding to the array `salesPersonList`, a parameter specifying the size of this array, and a parameter corresponding to the output file.

The algorithm to find the largest sales amount is similar to the algorithm to find the largest element in an array (discussed in Chapter 9). The definition of this function is:

```

void maxSaleByPerson(ofstream& outData, salesPersonRec list[],
                    int listSize)
{
    int maxIndex = 0;
    int index;

    for (index = 1; index < listSize; index++)
        if (list[maxIndex].totalSale < list[index].totalSale)
            maxIndex = index;

    outData << "Max Sale by SalesPerson: ID = "
            << list[maxIndex].ID
            << ", Amount = $" << list[maxIndex].totalSale
            << endl;
} //end maxSaleByPerson

```

Function `maxSaleByQuarter` This function prints the quarter in which the maximum sales were made. To identify this quarter, we look at the total sales for each quarter and find the largest sales amount. Because the sales total for each quarter is in the array `totalSaleByQuarter`, this function must have access to the array `totalSaleByQuarter`. Also, because the output will be stored in a file, this function must have access to the `ofstream` variable associated with the output file. Therefore, this function has two parameters: a parameter corresponding to the array `totalSaleByQuarter` and a parameter corresponding to the output file.

The algorithm to find the largest sales amount is the same as the algorithm to find the largest element in an array (discussed in Chapter 9). The definition of this function is:

```

void maxSaleByQuarter(ofstream& outData,
                    double saleByQuarter[])

```

```

{
    int quarter;
    int maxIndex = 0;

    for (quarter = 0; quarter < 4; quarter++)
        if (saleByQuarter[maxIndex] < saleByQuarter[quarter])
            maxIndex = quarter;

    outData << "Max Sale by Quarter: Quarter = "
            << maxIndex + 1
            << ", Amount = $" << saleByQuarter[maxIndex]
            << endl;
} //end maxSaleByQuarter

```

To make the program more flexible, we will prompt the user to specify the input and output files during its execution.

We are now ready to write the algorithm for the function `main`.

Main Algorithm

1. Declare the variables.
2. Prompt the user to enter the name of the file containing the salesperson's ID data.
3. Read the name of the input file.
4. Open the input file.
5. If the input file does not exist, exit the program.
6. Initialize the array `salesPersonList`. Call the function `initialize`.
7. Close the input file containing the salesperson's ID data and clear the input stream.
8. Prompt the user to enter the name of the file containing the sales data.
9. Read the name of the input file.
10. Open the input file.
11. If the input file does not exist, exit the program.
12. Prompt the user to enter the name of the output file.
13. Read the name of the output file.
14. Open the output file.
15. To output floating-point numbers in a fixed decimal format with the decimal point and trailing zeroes, set the manipulators `fixed` and `showpoint`. Also, to output floating-point numbers to two decimal places, set the precision to two decimal places.

16. Process the sales data. Call the function `getData`.
17. Calculate the total sales by quarter. Call the function `saleByQuarter`.
18. Calculate the total sales for each salesperson. Call the function `totalSaleByPerson`.
19. Print the report in a tabular format. Call the function `printReport`.
20. Find and print the salesperson who produces the maximum sales for the year. Call the function `maxSaleByPerson`.
21. Find and print the quarter that produces the maximum sales for the year. Call the function `maxSaleByQuarter`.
22. Close the files.

PROGRAM LISTING

```
//*****
// Author: D.S. Malik
//
// Program: Sales Data Analysis
// This program processes sales data for a company. For each
// salesperson, it outputs the ID, the total sales by each
// quarter, and the total sales for the year. It also outputs
// the salesperson's ID generating the maximum sale for the
// year and the sales amount. The quarter generating the
// maximum sale and the sales amount is also output.
//*****

#include <iostream>
#include <fstream>
#include <iomanip>
#include <string>

using namespace std;

const int NO_OF_SALES_PERSON = 6;

struct salesPersonRec
{
    string ID;           //salesperson's ID
    double saleByQuarter[ 4]; //array to store the total
                           //sales for each quarter
    double totalSale;    //salesperson's yearly sales amount
};

void initialize(ifstream& indata, salesPersonRec list[],
               int listSize);
```

```

void getData(istream& infile, salesPersonRec list[],
             int listSize);
void saleByQuarter(salesPersonRec list[], int listSize,
                  double totalByQuarter[]);
void totalSaleByPerson(salesPersonRec list[], int listSize);
void printReport(ofstream& outfile, salesPersonRec list[],
                 int listSize, double saleByQuarter[]);
void maxSaleByPerson(ofstream& outfile, salesPersonRec list[],
                    int listSize);
void maxSaleByQuarter(ofstream& outfile, double saleByQuarter[]);

int main()
{
    //Step 1
    ifstream infile;    //input file stream variable
    ofstream outfile;   //output file stream variable

    string inputFile;   //variable to hold the input file name
    string outputFile;  //variable to hold the output file name

    double totalSaleByQuarter[4]; //array to hold the
                                   //sale by quarter

    salesPersonRec salesPersonList[NO_OF_SALES_PERSON]; //array
                                                         //to hold the salesperson's data

    cout << "Enter the salesPerson ID file name: "; //Step 2
    cin >> inputFile;                               //Step 3
    cout << endl;

    infile.open(inputFile.c_str());                  //Step 4

    if (!infile)                                     //Step 5
    {
        cout << "Cannot open the input file."
              << endl;
        return 1;
    }

    initialize(infile, salesPersonList,
               NO_OF_SALES_PERSON);                  //Step 6

    infile.close();                                  //Step 7
    infile.clear();                                  //Step 7

    cout << "Enter the sales data file name: ";      //Step 8
    cin >> inputFile;                                //Step 9
    cout << endl;

    infile.open(inputFile.c_str());                  //Step 10

```

```

    if (!infile)                                     //Step 11
    {
        cout << "Cannot open the input file."
              << endl;
        return 1;
    }

    cout << "Enter the output file name: ";           //Step 12
    cin >> outputFile;                                //Step 13
    cout << endl;

    outfile.open(outputFile.c_str());                 //Step 14
    outfile << fixed << showpoint
              << setprecision(2);                     //Step 15

    getData(infile, salesPersonList,                  //Step 16
             NO_OF_SALES_PERSON);
    saleByQuarter(salesPersonList,
                  NO_OF_SALES_PERSON,
                  totalSaleByQuarter);                //Step 17
    totalSaleByPerson(salesPersonList,
                      NO_OF_SALES_PERSON);            //Step 18

    printReport(outfile, salesPersonList,              //Step 19
                 NO_OF_SALES_PERSON,
                 totalSaleByQuarter);
    maxSaleByPerson(outfile, salesPersonList,          //Step 20
                     NO_OF_SALES_PERSON);
    maxSaleByQuarter(outfile, totalSaleByQuarter);    //Step 21

    infile.close();                                   //Step 22
    outfile.close();                                  //Step 22

    return 0;
}

//Place the definitions of the functions initialize,
//getData, saleByQuarter, totalSaleByPerson,
//printReport, maxSaleByPerson, and maxSaleByQuarter here.

```

Sample Run: In this sample run, the user input is shaded.

Enter the salesPerson ID file name: Ch11_SalesManID.txt

Enter the sales data file name: Ch11_SalesData.txt

Enter the output file name: Ch11_SalesDataAnalysis.txt

Input File: Salespeople's IDs

```
12345
32214
23422
57373
35864
54654
```

Input File: Salespeople's Data

```
12345 1 893
32214 1 343
23422 3 903
57373 2 893
35864 5 329
54654 9 392
12345 2 999
32214 4 892
23422 4 895
23422 2 492
57373 6 892
35864 10 1223
54654 11 3420
12345 12 322
35864 5 892
54654 3 893
12345 8 494
32214 8 9023
23422 6 223
23422 4 783
57373 8 8834
35864 3 2882
```

Sample Run:

```
----- Annual Sales Report -----
```

| ID | QT1 | QT2 | QT3 | QT4 | Total |
|-------|---------|---------|----------|---------|----------|
| 12345 | 1892.00 | 0.00 | 494.00 | 322.00 | 2708.00 |
| 32214 | 343.00 | 892.00 | 9023.00 | 0.00 | 10258.00 |
| 23422 | 1395.00 | 1901.00 | 0.00 | 0.00 | 3296.00 |
| 57373 | 893.00 | 892.00 | 8834.00 | 0.00 | 10619.00 |
| 35864 | 2882.00 | 1221.00 | 0.00 | 1223.00 | 5326.00 |
| 54654 | 893.00 | 0.00 | 392.00 | 3420.00 | 4705.00 |
| Total | 8298.00 | 4906.00 | 18743.00 | 4965.00 | |

```
Max Sale by SalesPerson: ID = 57373, Amount = $10619.00
```

```
Max Sale by Quarter: Quarter = 3, Amount = $18743.00
```

QUICK REVIEW

1. A **struct** is a collection of a fixed number of components.
2. Components of a **struct** can be of different types.
3. The syntax to define a **struct** is:


```
struct structName
{
    dataType1 identifier1;
    dataType2 identifier2;
    .
    .
    .
    dataTypeN identifierN;
};
```
4. In C++, **struct** is a reserved word.
5. In C++, **struct** is a definition; no memory is allocated. Memory is allocated for the **struct** variables only when you declare them.
6. Components of a **struct** are called members of the **struct**.
7. Components of a **struct** are accessed by name.
8. In C++, the dot (.) operator is called the member access operator.
9. Members of a **struct** are accessed by using the dot (.) operator. For example, if **employeeType** is a **struct**, **employee** is a variable of type **employeeType**, and **name** is a member of **employee**, then the expression **employee.name** accesses the member **name**. That is, **employee.name** is a variable and can be manipulated like other variables.
10. The only built-in operations on a **struct** are the assignment and member access operations.
11. Neither arithmetic nor relational operations are allowed on **struct**(s).
12. As a parameter to a function, a **struct** can be passed either by value or by reference.
13. A function can return a value of type **struct**.
14. A **struct** can be a member of another **struct**.

EXERCISES

1. Mark the following statements as true or false.
 - a. All members of a **struct** must be of different types.
 - b. A function cannot return a value of type **struct**.
 - c. A member of a **struct** can be another **struct**.
 - d. The only allowable operations on a **struct** are assignment and member selection.

- e. An array can be a member of a **struct**.
- f. In C++, some aggregate operations are allowed on a **struct**.
- g. Because a **struct** has a finite number of components, relational operations are allowed on a **struct**.
2. Define a **struct**, **checkingAccount**, to store the following data about a checking account: account holder's name (**string**), account number (**int**), balance (**double**), and the interest rate (**double**).
3. Assume the definition of Exercise 2. Declare a **checkingAccount** variable and write C++ statements to store the following information: account holder's name—**Jason Miller**, account number—**17328910**, balance—**24476.38**, interest rate—**2.5%**.
4. Define a **struct**, **movieType**, to store the following data about a movie: movie name (**string**), movie director (**string**), producer (**string**), the year movie was released (**int**), and number of copies in stock.
5. Assume the definition of Exercise 4. Declare a variable of type **movieType** to store the following data: movie name—**Summer Vacation**, director—**Tom Blair**, producer—**Rajiv Merchant**, year the movie released—**2005**, the number of copies in stock—**34**.
6. Consider the following statements:

```

struct nameType      struct dateType      struct personalInfoType
{
    string first;
    string last;
};

    int month;
    int day;
    int year;
};

    nameType name;
    int pID;
    dateType dob;
};

personalInfoType person;
personalInfoType classList[100];
nameType student;

```

Mark the following statements as valid or invalid. If a statement is invalid, explain why.

- a. `person.name.first = "William";`
- b. `cout << person.name << endl;`
- c. `classList[1] = person;`
- d. `classList[20].pID = 000011100;`
- e. `person = classList[20];`
- f. `student = person.name;`
- g. `cin >> student;`
- h. `for (int j = 0; j < 100; j++)`
`classList[j].pID = 00000000;`
- i. `classList.dob.day = 1;`
- j. `student = name;`

7. Consider the following statements (`nameType` is as defined in Exercise 6):

```
struct employeeType
{
    nameType name;
    int performanceRating;
    int pID;
    string dept;
    double salary;
};
employeeType employees[100];
employeeType newEmployee;
```

Mark the following statements as valid or invalid. If a statement is invalid, explain why.

- a. `newEmployee.name = "John Smith";`
 - b. `cout << newEmployee.name;`
 - c. `employees[35] = newEmployee;`
 - d. `if (employees[45].pID == 555334444)`
`employees[45].performanceRating = 1;`
 - e. `employees.salary = 0;`
8. Assume the declarations of Exercises 6 and 7. Write C++ statements that do the following:

- a. Store the following information in `newEmployee`:
`name: Mickey Doe`
`pID: 111111111`
`performanceRating: 2`
`dept: ACCT`
`salary: 34567.78`
- b. In the array `employees`, initialize each `performanceRating` to 0.
- c. Copy the information of the 20th component of the array `employees` into `newEmployee`.
- d. Update the salary of the 50th employee in the array `employees` by adding 5735.87 to its previous value.

9. Assume that you have the following definition of a `struct`.

```
struct partsType
{
    string partName;
    int partNum;
    double price;
    int quantitiesInStock;
};
```

Declare an array, `inventory`, of 100 components of type `partsType`.

10. Assume the definition of Exercise 9.
 - a. Write a C++ code to initialize each component of `inventory` as follows: `partName` to null string, `partNum` to -1, `price` to 0.0, and `quantitiesInStock` to 0.
 - b. Write a C++ code that uses a loop to output the data stored in `inventory`. Assume that the variable `length` indicates the number of elements in `inventory`.
11. Assume the definition and declaration of Exercise 9. Write the definition of a void function that can be used to input data in a variable of type `partsType`. Also write a C++ code that uses your function to input data in `inventory`.
12. Suppose that you have the following definitions:

```

struct timeType          struct tourType
{
    int hr;
    double min;
    int sec;
};
                        {
                            string cityName;
                            int distance;
                            timeType travelTime;
                        };
  
```

- a. Declare the variable `destination` of type `tourType`.
- b. Write C++ statements to store the following data in `destination`: `cityName`—Chicago, `distance`—550 miles, `travelTime`—9 hours and 30 minutes.
- c. Write the definition of a function to output the data stored in a variable of type `tourType`.
- d. Write the definition of a value-returning function that inputs data into a variable of type `tourType`.
- e. Write the definition of `void` function with a reference parameter of type `tourType` to input data in a variable of type `tourType`.

PROGRAMMING EXERCISES

1. Assume the definition of Exercise 4, which defines the `struct movieType`. Write a program that declares a variable of type `movieType`, prompts the user to input data about a movie, and outputs the movie data.
2. Write a program that reads students' names followed by their test scores. The program should output each student's name followed by the test scores and the relevant grade. It should also find and print the highest test score and the name of the students having the highest test score.

Student data should be stored in a **struct** variable of type **studentType**, which has four components: **studentFName** and **studentLName** of type **string**, **testScore** of type **int** (**testScore** is between 0 and 100), and **grade** of type **char**. Suppose that the class has 20 students. Use an array of 20 components of type **studentType**.

Your program must contain at least the following functions:

- a. A function to read the students' data into the array.
- b. A function to assign the relevant grade to each student.
- c. A function to find the highest test score.
- d. A function to print the names of the students having the highest test score.

Your program must output each student's name in this form: last name followed by a comma, followed by a space, followed by the first name; the name must be left justified. Moreover, other than declaring the variables and opening the input and output files, the function **main** should only be a collection of function calls.

3. Define a **struct**, **menuItemType**, with two components: **menuItem** of type **string** and **menuPrice** of type **double**.
4. Write a program to help a local restaurant automate its breakfast billing system. The program should do the following:
 - a. Show the customer the different breakfast items offered by the restaurant.
 - b. Allow the customer to select more than one item from the menu.
 - c. Calculate and print the bill.

Assume that the restaurant offers the following breakfast items (the price of each item is shown to the right of the item):

| | |
|---------------|--------|
| Plain Egg | \$1.45 |
| Bacon and Egg | \$2.45 |
| Muffin | \$0.99 |
| French Toast | \$1.99 |
| Fruit Basket | \$2.49 |
| Cereal | \$0.69 |
| Coffee | \$0.50 |
| Tea | \$0.75 |

Use an array, **menuList**, of the **struct** **menuItemType**, as defined in Programming Exercise 2. Your program must contain at least the following functions:

- Function **getData**: This function loads the data into the array **menuList**.
- Function **showMenu**: This function shows the different items offered by the restaurant and tells the user how to select the items.

- Function `printCheck`: This function calculates and prints the check. (Note that the billing amount should include a 5% tax.)
A sample output is:

```
Welcome to Johnny's Restaurant
Bacon and Egg      $2.45
Muffin             $0.99
Coffee             $0.50
Tax                $0.20
Amount Due         $4.14
```

Format your output with two decimal places. The name of each item in the output must be left justified. You may assume that the user selects only one item of a particular type.

5. Redo Exercise 4 so that the customer can select multiple items of a particular type. A sample output in this case is:

```
Welcome to Johnny's Restaurant
1 Bacon and Egg    $2.45
2 Muffin           $1.98
1 Coffee           $0.50
Tax                $0.25
Amount Due         $5.18
```

6. Write a program whose main function is merely a collection of variable declarations and function calls. This program reads a text and outputs the letters, together with their counts, as explained below in the function `printResult`. (There can be no global variables! All information must be passed in and out of the functions. Use a structure to store the information.) Your program must consist of at least the following functions:
 - Function `openFile`: Opens the input and output files. You must pass the file streams as parameters (by reference, of course). If the file does not exist, the program should print an appropriate message and exit. The program must ask the user for the names of the input and output files.
 - Function `count`: Counts every occurrence of capital letters `A-Z` and small letters `a-z` in the text file opened in the function `openFile`. This information must go into an array of structures. The array must be passed as a parameter, and the file identifier must also be passed as a parameter.
 - Function `printResult`: Prints the number of capital letters and small letters, as well as the percentage of capital letters for every letter `A-Z` and the percentage of small letters for every letter `a-z`. The percentages should look like this: “25%”. This information must come from an array of structures, and this array must be passed as a parameter.

7. Write a program that declares a `struct` to store the data of a baseball player (player's name, number of home runs, and number of hits). Declare an array of 10 components to store the data of 10 baseball players. Your program must contain a function to input data and a function to output data. Add functions to search the array to find the index of a specific player, and update the data of a player. (You may assume that input data is stored in a file.) Before the program terminates, give the user the option to save data in a file. Your program should be menu driven, giving the user various choices.



12

CHAPTER

CLASSES AND DATA ABSTRACTION

IN THIS CHAPTER, YOU WILL:

- Learn about classes
- Learn about `private`, `protected`, and `public` members of a class
- Explore how classes are implemented
- Examine constructors and destructors
- Learn about the abstract data type (ADT)
- Explore how classes are used to implement ADTs
- Learn about information hiding
- Explore how information hiding is implemented in C++
- Learn about the `static` members of a class

In Chapter 11, you learned how to group data items that are of different types by using a **struct**. The definition of a **struct** given in Chapter 11 is similar to the definition of a C-**struct**. However, the members of a C++ **struct** can be data items as well as functions. C++ provides another structured data type, called a **class**, which is specifically designed to group data and functions. This chapter first introduces classes and explains how to use them and then discusses the similarities and differences between a **struct** and a **class**.

NOTE

Chapter 11 is not a prerequisite for this chapter. In fact, a **struct** and a **class** have similar capabilities, as discussed in the section “A **struct** versus a **class**” in this chapter.

Classes

Chapter 1 introduced the problem-solving methodology called **object-oriented design (OOD)**. In OOD, the first step is to identify the components, called **objects**. An object combines data and the operations on that data in a single unit. In C++, the mechanism that allows you to combine data and the operations on that data in a single unit is called a class. Now that you know how to store and manipulate data in computer memory and how to construct your own functions, you are ready to learn how objects are constructed. This and subsequent chapters develop and implement programs using OOD. This chapter first explains how to define a class and use it in a program.

A **class** is a collection of a fixed number of components. The components of a class are called the **members** of the class.

The general syntax for defining a class is:

```
class classIdentifier
{
    classMembersList
};
```

in which **classMembersList** consists of variable declarations and/or functions. That is, a member of a class can be either a variable (to store data) or a function.

- If a member of a class is a variable, you declare it just like any other variable. Also, in the definition of the class, you cannot initialize a variable when you declare it.
- If a member of a class is a function, you typically use the function prototype to declare that member.
- If a member of a class is a function, it can (directly) access any member of the class—member variables and member functions. That is, when you write the definition of a member function, you can directly access any member variable of the class without passing it as a parameter. The only obvious condition is that you must declare an identifier before you can use it.

In C++, `class` is a reserved word, and it defines only a data type; no memory is allocated. It announces the declaration of a class. Moreover, note the semicolon (;) after the right brace. The semicolon is part of the syntax. A missing semicolon, therefore, will result in a syntax error.

The members of a `class` are classified into three categories: `private`, `public`, and `protected`. This chapter mainly discusses the first two types, `private` and `public`.

In C++, `private`, `protected`, and `public` are reserved words and are called member access specifiers.

Following are some facts about `public` and `private` members of a class:

- By default, all members of a class are `private`.
- If a member of a class is `private`, you cannot access it outside of the class. (Example 12-1 illustrates this concept.)
- A `public` member is accessible outside of the `class`. (Example 12-1 illustrates this concept.)
- To make a member of a class `public`, you use the member access specifier `public` with a colon, `::`.

Suppose that we want to define a class to implement the time of day in a program. Because a clock gives the time of day, let us call this `class` `clockType`. Furthermore, to represent time in computer memory, we use three `int` variables: one to represent the hours, one to represent the minutes, and one to represent the seconds.

Suppose these three variables are:

```
int hr;
int min;
int sec;
```

We also want to perform the following operations on the time:

1. Set the time.
2. Retrieve the time.
3. Print the time.
4. Increment the time by one second.
5. Increment the time by one minute.
6. Increment the time by one hour.
7. Compare the two times for equality.

To implement these seven operations, we will write seven functions—`setTime`, `getTime`, `printTime`, `incrementSeconds`, `incrementMinutes`, `incrementHours`, and `equalTime`.

From this discussion, it is clear that the `class` `clockType` has 10 members: three member variables and seven member functions.

Some members of the `class clockType` will be `private`; others will be `public`. Deciding which member to make `public` and which to make `private` depends on the nature of the member. The general rule is that any member that needs to be accessed outside of the class is declared `public`; any member that should not be accessed directly by the user should be declared `private`. For example, the user should be able to set the time and print the time. Therefore, the members that set the time and print the time should be declared `public`.

Similarly, the members to increment the time and compare the time for equality should be declared `public`. On the other hand, to prevent the *direct* manipulation of the member variables `hr`, `min`, and `sec`, we will declare them `private`. Furthermore, note that if the user has direct access to the member variables, member functions such as `setTime` are not needed. The second part of this chapter (beginning with the section “Information Hiding”) explains why some members need to be `public` and others should be `private`.

The following statements define the `class clockType`:

```
class clockType
{
public:
    void setTime(int, int, int);
    void getTime(int&, int&, int&) const;
    void printTime() const;
    void incrementSeconds();
    void incrementMinutes();
    void incrementHours();
    bool equalTime(const clockType&) const;

private:
    int hr;
    int min;
    int sec;
};
```

In this definition:

- The `class clockType` has seven member functions: `setTime`, `getTime`, `printTime`, `incrementSeconds`, `incrementMinutes`, `incrementHours`, and `equalTime`. It has three member variables: `hr`, `min`, and `sec`.
- The three member variables—`hr`, `min`, and `sec`—are `private` to the class and cannot be accessed outside of the class. (Example 12-1 illustrates this concept.)
- The seven member functions—`setTime`, `getTime`, `printTime`, `incrementSeconds`, `incrementMinutes`, `incrementHours`, and `equalTime`—can directly access the member variables (`hr`, `min`, and `sec`). In other words, when we write the definitions of these functions,

we do not pass these member variables as parameters to the member functions.

- In the function `equalTime`, the formal parameter is a constant reference parameter. That is, in a call to the function `equalTime`, the formal parameter receives the address of the actual parameter, but the formal parameter cannot modify the value of the actual parameter. You could have declared the formal parameter as a value parameter, but that would require the formal parameter to copy the value of the actual parameter, which could result in poor performance. (See the section “Reference Parameters and Class Objects (Variables)” in this chapter for an explanation.)
- The word `const` at the end of the member functions `getTime`, `printTime`, and `equalTime` specifies that these functions cannot modify the member variables of a variable of type `clockType`.

NOTE

The `private` and `public` members can appear in any order. If you want, you can declare the `private` members first and then declare the `public` ones. The section “Order of `public` and `private` Members of a Class” in this chapter discusses this issue.

NOTE

In the definition of the `class clockType`, all member variables are `private` and all member functions are `public`. However, a member function can also be `private`. For example, if a member function is used only to implement other member functions of the class and the user does not need to access this function, you make it `private`. Similarly, a member variable of a class can also be `public`.

Note that we have not yet written the definitions of the member functions of the class. You will learn how to write them shortly.

The function `setTime` sets the three member variables—`hr`, `min`, and `sec`—to a given value. The given values are passed as parameters to the function `setTime`. The function `printTime` prints the time, that is, the values of `hr`, `min`, and `sec`. The function `incrementSeconds` increments the time by one second, the function `incrementMinutes` increments the time by one minute, the function `incrementHours` increments the time by one hour, and the function `equalTime` compares two times for equality.

Note that the function `equalTime` has only one parameter, although you need two things to make a comparison. We will explain this point with the help of an example in the section “Implementation of Member Functions,” later in this chapter.

Unified Modeling Language Class Diagrams

A class and its members can be described graphically using a notation known as the **Unified Modeling Language** (UML) notation. For example, Figure 12-1 shows the UML class diagram of the `clockType` class.




FIGURE 12-1 UML class diagram of the `clockType` class

The top box contains the name of the class. The middle box contains the member variables and their data types. The last box contains the member function name, parameter list, and the return type of the function. A + (plus) sign in front of a member name indicates that this member is a **public** member; a - (minus) sign indicates that this is a **private** member. The symbol # before the member name indicates that the member is a **protected** member.

Variable (Object) Declaration

Once a class is defined, you can declare variables of that type. In C++ terminology, a class variable is called a **class object** or **class instance**. To help you become familiar with this terminology, from now on we will use the term class object, or simply **object**, for a class variable.

The syntax for declaring a class object is the same as that for declaring any other variable. The following statements declare two objects of type `clockType`:

```
clockType myClock;
clockType yourClock;
```

Each object has 10 members: seven member functions and three member variables. Each object has separate memory allocated for `hr`, `min`, and `sec`.

In actuality, memory is allocated only for the member variables of each class object. The C++ compiler generates only one physical copy of a member function of a class, and each class object executes the same copy of the member function. Therefore, whenever we draw the

figure of a class object, we will show only the member variables. As an example, Figure 12-2 shows the objects `myClock` and `yourClock` with values in their member variables.




FIGURE 12-2 Objects `myClock` and `yourClock`

Accessing Class Members

Once an object of a class is declared, it can access the members of the class. The general syntax for an object to access a member of a class is:

```
classObjectName.memberName
```

The class members that a class object can access depend on where the object is declared.

- If the object is declared in the definition of a member function of the class, then the object can access both the **public** and **private** members. (We will elaborate on this when we write the definition of the member function `equalTime` of the **class** `clockType` in the section “Implementation of Member Functions,” later in this chapter.)
- If the object is declared elsewhere (for example, in a user’s program), then the object can access *only* the **public** members of the class.

Recall that in C++, the dot, `.` (period), is an operator called the **member access operator**.

Example 12-1 illustrates how to access the members of a class.

EXAMPLE 12-1

Suppose we have the following declaration (say, in a user’s program):

```
clockType myClock;
clockType yourClock;
```

Consider the following statements:

```
myClock.setTime(5, 2, 30);
myClock.printTime();
yourClock.setTime(x, y, z);    //assume x, y, and z are
                                //variables of type int
```

```

if (myClock.equalTime(yourClock))
.
.
.

```

These statements are legal; that is, they are syntactically correct.

In the first statement, `myClock.setTime(5, 2, 30);`, the member function `setTime` is executed. The values 5, 2, and 30 are passed as parameters to the function `setTime`, and the function uses these values to set the values of the three member variables `hr`, `min`, and `sec` of `myClock` to 5, 2, and 30, respectively. Similarly, the second statement executes the member function `printTime` and outputs the contents of the three member variables of `myClock`. In the third statement, the values of the variables `x`, `y`, and `z` are used to set the values of the three member variables of `yourClock`.

In the fourth statement, the member function `equalTime` executes and compares the three member variables of `myClock` to the corresponding member variables of `yourClock`. Because in this statement `equalTime` is a member of the object `myClock`, it has direct access to the three member variables of `myClock`. So it needs one more object, which in this case is `yourClock`, to compare. This explains why the function `equalTime` has only one parameter.

The objects `myClock` and `yourClock` can access only **public** members of the class. Thus, the following statements are illegal because `hr` and `min` are declared as **private** members of the **class** `clockType` and, therefore, cannot be accessed by the objects `myClock` and `yourClock`:

```

myClock.hr = 10;           //illegal
myClock.min = yourClock.min; //illegal

```

Built-in Operations on Classes

Most of C++'s built-in operations do not apply to classes. You cannot use arithmetic operators to perform arithmetic operations on class objects (unless they are overloaded; see Chapter 15). For example, you cannot use the operator `+` to add two class objects of, say, type `clockType`. Also, you cannot use relational operators to compare two class objects for equality (unless they are overloaded; see Chapter 15).

The two built-in operations that are valid for class objects are member access (`.`) and assignment (`=`). You have seen how to access an individual member of a class by using the name of the class object, then a dot, and then the member name. (For example, if `myClock` is a `clockType` object, in the statement `myClock.incrementSeconds();`, `myClock` accesses the member `incrementSeconds`.)

We now show how an assignment statement works with the help of an example.

Assignment Operator and Classes

Suppose that `myClock` and `yourClock` are `clockType` objects, as defined previously. Furthermore, suppose that the values of `myClock` and `yourClock` are as shown in Figure 12-3(a).




FIGURE 12-3 `myClock` and `yourClock` before and after executing the statement `myClock = yourClock;`

The statement:

```
myClock = yourClock;           //Line 1
```

copies the value of `yourClock` into `myClock`. That is,

- the value of `yourClock.hr` is copied into `myClock.hr`,
- the value of `yourClock.min` is copied into `myClock.min`, and
- the value of `yourClock.sec` is copied into `myClock.sec`.

In other words, the values of the three member variables of `yourClock` are copied into the corresponding member variables of `myClock`. Therefore, an assignment statement performs a member-wise copy. After the statement in Line 1 executes, the values of `myClock` and `yourClock` are as shown in Figure 12-3(b).

Class Scope

A **class** object can be either automatic (that is, created each time the control reaches its declaration and destroyed when the control exits the surrounding block) or static (that is, created once, when the control reaches its declaration, and destroyed when the program terminates). Also, you can declare an array of **class** objects. A **class** object has the same scope as other variables. A member of a **class** has the same scope as a member of a **struct**. That is, a member of a **class** is local to the **class**. You access a **class** member outside of the **class** by using the **class** object name and the member access operator (`.`).

Functions and Classes

The following rules describe the relationship between functions and classes:

- Class objects can be passed as parameters to functions and returned as function values.
- As parameters to functions, class objects can be passed either by value or by reference.
- If a class object is passed by value, the contents of the member variables of the actual parameter are copied into the corresponding member variables of the formal parameter.

Reference Parameters and Class Objects (Variables)

Recall that when a variable is passed by value, the formal parameter copies the value of the actual parameter. That is, memory space to copy the value of the actual parameter is allocated for the formal parameter. As a parameter, a class object can be passed by value.

Suppose that a class has several member variables requiring a large amount of memory to store data, and you need to pass a variable by value. The corresponding formal parameter then receives a copy of the data of the variable. That is, the compiler must allocate memory for the formal parameter, so as to copy the value of the member variables of the actual parameter. This operation might require, in addition to a large amount of storage space, a considerable amount of computer time to copy the value of the actual parameter into the formal parameter.

On the other hand, if a variable is passed by reference, the formal parameter receives only the address of the actual parameter. Therefore, an efficient way to pass a variable as a parameter is by reference. If a variable is passed by reference, then when the formal parameter changes, the actual parameter also changes. Sometimes, however, you do not want the function to be able to change the values of the member variables. In C++, you can pass a variable by reference and still prevent the function from changing its value by using the keyword `const` in the formal parameter declaration. As an example, consider the following function definition:

```
void testTime(const clockType& otherClock)
{
    clockType dClock;
    .
    .
    .
}
```

The function `testTime` contains a reference parameter, `otherClock`. The parameter `otherClock` is declared using the keyword `const`. Thus, in a call to the function `testTime`, the formal parameter `otherClock` receives the address of the actual parameter, but `otherClock` cannot modify the contents of the actual parameter. For example, after the following statement executes, the value of `myClock` will not be altered:

```
testTime(myClock);
```

Generally, if you want to declare a class object as a value parameter, you declare it as a reference parameter using the keyword `const`, as described previously.

Recall that if a formal parameter is a value parameter, within the function definition, you can change the value of the formal parameter. That is, you can use an assignment statement to change the value of the formal parameter (which, of course, would have no effect on the actual parameter). However, if a formal parameter is a constant reference parameter, you cannot use an assignment statement to change its value within the function, nor can you use any other function to change its value. Therefore, within the definition of the function `testTime`, you cannot alter the value of `otherClock`. For example, the following would be illegal in the definition of the function `testTime`:

```
otherClock.setTime(5, 34, 56); //illegal
otherClock = dClock;           //illegal
```

Implementation of Member Functions

When we defined the `class clockType`, we included only the function prototype for the member functions. For these functions to work properly, we must write the related algorithms. One way to implement these functions is to provide the function definition rather than the function prototype in the class itself. Unfortunately, the class definition would then be very long and difficult to comprehend. Another reason for providing function prototypes instead of function definitions relates to information hiding; that is, we want to hide the details of the operations on the data. We will discuss this issue later in this chapter, in the section “Information Hiding.”

Next, let us write the definitions of the member functions of the `class clockType`. That is, we will write the definitions of the functions `setTime`, `getTime`, `printTime`, `incrementSeconds`, `equalTime`, and so on. Because the identifiers `setTime`, `printTime`, and so forth are local to the class, we cannot reference them (directly) outside of the class. In order to reference these identifiers, we use the **scope resolution operator**, `::` (double colon). In the function definition’s heading, the name of the function is the name of the class, followed by the scope resolution operator, followed by the function name. For example, the definition of the function `setTime` is as follows:

```
void clockType::setTime(int hours, int minutes, int seconds)
{
    if (0 <= hours && hours < 24)
        hr = hours;
    else
        hr = 0;

    if (0 <= minutes && minutes < 60)
        min = minutes;
    else
        min = 0;
```

```

    if (0 <= seconds && seconds < 60)
        sec = seconds;
    else
        sec = 0;
}

```

Note that the definition of the function `setTime` checks for the valid values of `hours`, `minutes`, and `seconds`. If these values are out of range, the member variables `hr`, `min`, and `sec` are initialized to 0. Let us now explain how the member function `setTime` works when accessed by an object of type `clockType`.

The member function `setTime` is a `void` function and has three parameters. Therefore:

- A call to this function is a stand-alone statement.
- We must use three parameters in a call to this function.

Furthermore, recall that because `setTime` is a member of the `class clockType`, it can directly access the member variables `hr`, `min`, and `sec`, as shown in the definition of `setTime`.

Suppose that `myClock` is an object of type `clockType` (as declared previously). The object `myClock` has three member variables, as shown in Figure 12-4(a).




FIGURE 12-4 `myClock` before and after executing the statement `myClock.setTime(3, 48, 52);`

Consider the following statement:

```
myClock.setTime(3, 48, 52);
```

In the statement `myClock.setTime(3, 48, 52);`, `setTime` is accessed by the object `myClock`. Therefore, the three variables—`hr`, `min`, and `sec`—referred to in the body of the function `setTime` are the three member variables of `myClock`. Thus, the values 3, 48, and 52, which are passed as parameters in the preceding statement, are assigned to the three member variables of `myClock` by the function `setTime` (see the body of the function `setTime`). After the previous statement executes, the object `myClock` is as shown in Figure 12-4(b).

Next, let us give the definitions of the other member functions of the `class` `clockType`. The definitions of these functions are simple and easy to follow:

```
void clockType::getTime(int& hours, int& minutes,
                       int& seconds) const
{
    hours = hr;
    minutes = min;
    seconds = sec;
}

void clockType::printTime() const
{
    if (hr < 10)
        cout << "0";
    cout << hr << ":";

    if (min < 10)
        cout << "0";
    cout << min << ":";

    if (sec < 10)
        cout << "0";
    cout << sec;
}

void clockType::incrementHours()
{
    hr++;
    if (hr > 23)
        hr = 0;
}

void clockType::incrementMinutes()
{
    min++;
    if (min > 59)
    {
        min = 0;
        incrementHours(); //increment hours
    }
}

void clockType::incrementSeconds()
{
    sec++;

    if (sec > 59)
    {
        sec = 0;
        incrementMinutes(); //increment minutes
    }
}
```

From the definitions of the functions `incrementMinutes` and `incrementSeconds`, it is clear that a member function of a class can call other member functions of the class.

The function `equalTime` has the following definition:

```
bool clockType::equalTime(const clockType& otherClock) const
{
    return (hr == otherClock.hr
           && min == otherClock.min
           && sec == otherClock.sec);
}
```

Let us see how the member function `equalTime` works.

Suppose that `myClock` and `yourClock` are objects of type `clockType`, as declared previously. Further suppose that we have `myClock` and `yourClock`, as shown in Figure 12-5.




FIGURE 12-5 Objects `myClock` and `yourClock`

Consider the following statement:

```
if (myClock.equalTime(yourClock))
{
    .
    .
    .
}
```

In the expression:

```
myClock.equalTime(yourClock)
```

the object `myClock` accesses the member function `equalTime`. Because `otherClock` is a reference parameter, the address of the actual parameter `yourClock` is passed to the formal parameter `otherClock`, as shown in Figure 12-6.




FIGURE 12-6 Object `myClock` and parameter `otherClock`

The member variables `hr`, `min`, and `sec` of `otherClock` have the values 14, 25, and 54, respectively. In other words, when the body of the function `equalTime` executes, the value of `otherClock.hr` is 14, the value of `otherClock.min` is 25, and the value of `otherClock.sec` is 54. The function `equalTime` is a member of `myClock`. When the function `equalTime` executes, the variables `hr`, `min`, and `sec` in the body of the function `equalTime` are the member variables of the object `myClock`. Therefore, the member `hr` of `myClock` is compared with `otherClock.hr`, the member `min` of `myClock` is compared with `otherClock.min`, and the member `sec` of `myClock` is compared with `otherClock.sec`.

Once again, from the definition of the function `equalTime`, it is clear why it has only one parameter.

Let us again take a look at the definition of the function `equalTime`. Notice that within the definition of this function, the object `otherClock` accesses the member variables `hr`, `min`, and `sec`. However, these member variables are **private**. So is there any violation? The answer is no. The function `equalTime` is a member of the **class** `clockType`, and `hr`, `min`, and `sec` are the member variables. Moreover, `otherClock` is an object of type `clockType`. Therefore, the object `otherClock` can access its **private** member variables within the definition of the function `equalTime`.

The same is true for any member function of a class. In general, when you write the definition of a member function, say, `dummyFunction`, of a **class**, say, `dummyClass`, and the function uses an object, `dummyObject` of the **class** `dummyClass`, then within the definition of `dummyFunction`, the object `dummyObject` can access its **private** member variables (in fact, any **private** member of the class).

Once a class is properly defined and implemented, it can be used in a program. A program or software that uses and manipulates the objects of a class is called a **client** of that class.

When you declare objects of the **class** `clockType`, every object has its own copy of the member variables `hr`, `min`, and `sec`. In object-oriented terminology, variables such as `hr`, `min`, and `sec` are called **instance variables** of the class because every object has its own instance of the data.

Accessor and Mutator Functions

Let us look at the member functions of the `class clockType`. The function `setTime` sets the values of the member variables to the values specified by the user. In other words, it alters or modifies the values of the member variables. Similarly, the functions `incrementSeconds`, `incrementMinutes`, and `incrementHours` also modify the member variables. On the other hand, functions such as `getTime`, `printTime`, and `equalTime` only *access* the values of the member variables. They *do not* modify the member variables. We can, therefore, categorize the member functions of the `class clockType` into two categories: member functions that modify the member variables and member functions that only access, and do not modify, the member variables.

This is typically true for any class. That is, every class has member functions that only access and do not modify the member variables, called accessor functions, and member functions that modify the member variables, called mutator functions.

Accessor function: A member function of a class that only accesses (that is, does not modify) the value(s) of the member variable(s).

Mutator function: A member function of a class that modifies the value(s) of the member variable(s).

Because an accessor function only accesses the values of the member variables, as a safeguard, we typically include the reserved word `const` at the end of the headings of these functions. Moreover, a constant member function of a class cannot modify the member variables of that class. For example, see the headings of the member functions `getTime`, `printTime`, and `equalTime` of the `class clockType`.

A member function of a class is called a **constant function** if its heading contains the reserved word `const` at the end. For example, the member functions `getTime`, `printTime`, and `equalTime` of the `class clockType` are constant functions. A constant member function of a class cannot modify the member variables of that class, so these are accessor functions. One thing that should be remembered about constant member functions is that a constant member function of a class can *only* call other constant member functions of that class. Therefore, you should be careful when you make a member function constant.

Example 12-2 shows how to use the `class clockType` in a program. Note that we have combined the definition of the class, the definition of the member functions, and the main function to create a complete program. Later in this chapter, you will learn how to separate the definition of the `class clockType`, the definitions of the member functions, and the main program, using three files.

EXAMPLE 12-2

```
//The program listing of the program that defines
//and uses the class clockType
```

```

#include <iostream>
using namespace std;

class clockType
{
public:
    void setTime(int, int, int);
    void getTime(int&, int&, int&) const;
    void printTime() const;
    void incrementSeconds();
    void incrementMinutes();
    void incrementHours();
    bool equalTime(const clockType&) const;

private:
    int hr;
    int min;
    int sec;
};

int main()
{
    clockType myClock;
    clockType yourClock;

    int hours;
    int minutes;
    int seconds;

    //Set the time of myClock
    myClock.setTime(5, 4, 30); //Line 1

    cout << "Line 2: myClock: "; //Line 2
    myClock.printTime(); //print the time of myClock Line 3
    cout << endl; //Line 4

    cout << "Line 5: yourClock: "; //Line 5
    yourClock.printTime(); //print the time of yourClock Line 6
    cout << endl; //Line 7

    //Set the time of yourClock
    yourClock.setTime(5, 45, 16); //Line 8

    cout << "Line 9: After setting, yourClock: "; //Line 9
    yourClock.printTime(); //print the time of yourClock Line 10
    cout << endl; //Line 11

    //Compare myClock and yourClock
    if (myClock.equalTime(yourClock)) //Line 12
        cout << "Line 13: Both times are equal."
            << endl; //Line 13
}

```

```

else //Line 14
    cout << "Line 15: The two times are not equal."
        << endl; //Line 15

cout << "Line 16: Enter the hours, minutes, and "
    << "seconds: "; //Line 16
cin >> hours >> minutes >> seconds; //Line 17
cout << endl; //Line 18

    //Set the time of myClock using the value of the
    //variables hours, minutes, and seconds
myClock.setTime(hours, minutes, seconds); //Line 19

cout << "Line 20: New myClock: "; //Line 20
myClock.printTime(); //print the time of myClock Line 21
cout << endl; //Line 22

    //Increment the time of myClock by one second
myClock.incrementSeconds(); //Line 23

cout << "Line 24: After incrementing myClock by "
    << "one second, myClock: "; //Line 24
myClock.printTime(); //print the time of myClock Line 25
cout << endl; //Line 26

    //Retrieve the hours, minutes, and seconds of the
    //object myClock
myClock.getTime(hours, minutes, seconds); //Line 27

    //Output the value of hours, minutes, and seconds
cout << "Line 28: hours = " << hours
    << ", minutes = " << minutes
    << ", seconds = " << seconds << endl; //Line 28

return 0;
} //end main

void clockType::setTime(int hours, int minutes, int seconds)
{
    if (0 <= hours && hours < 24)
        hr = hours;
    else
        hr = 0;

    if (0 <= minutes && minutes < 60)
        min = minutes;
    else
        min = 0;

    if (0 <= seconds && seconds < 60)
        sec = seconds;
    else
        sec = 0;
}

```

```
//Place the definitions of the remaining functions, getTime,
//incrementHours, incrementMinutes, incrementSeconds, printTime,
//and equalTime, of the class clockType, as described
//previously here.
```

Sample Run: In this sample run, the user input is shaded.

```
Line 2: myClock: 05:04:30
Line 5: yourClock: 0-858993460:0-858993460:0-858993460
Line 9: After setting, yourClock: 05:45:16
Line 15: The two times are not equal.
Line 16: Enter the hours, minutes, and seconds: 5 23 59

Line 20: New myClock: 05:23:59
Line 24: After incrementing myClock by one second, myClock: 05:24:00
Line 28: hours = 5, minutes = 24, seconds = 0
```

The value of `yourClock`, as printed in the second line of the output (Line 5), is machine dependent you might get different values.

Order of `public` and `private` Members of a Class

C++ has no fixed order in which you declare `public` and `private` members; you can declare them in any order. The only thing you need to remember is that, by default, all members of a class are `private`. You must use the member access specifier `public` to make a member available for `public` access. If you decide to declare the `private` members after the `public` members (as is done in the case of `clockType`), you must use the member access specifier `private` to begin the declaration of the `private` members.

We can declare the `class clockType` in one of three ways, as shown in Examples 12-3 through 12-5.

EXAMPLE 12-3

This declaration is the same as before. For the sake of completeness, we include the class definition:

```
class clockType
{
public:
    void setTime(int, int, int);
    void getTime(int&, int&, int&) const;
    void printTime() const;
    void incrementSeconds();
    void incrementMinutes();
    void incrementHours();
    bool equalTime(const clockType&) const;
```

```
private:
    int hr;
    int min;
    int sec;
};
```

EXAMPLE 12-4

```
class clockType
{
private:
    int hr;
    int min;
    int sec;

public:
    void setTime(int, int, int);
    void getTime(int&, int&, int&) const;
    void printTime() const;
    void incrementSeconds();
    void incrementMinutes();
    void incrementHours();
    bool equalTime(const clockType&) const;
};
```

EXAMPLE 12-5

```
class clockType
{
    int hr;
    int min;
    int sec;

public:
    void setTime(int, int, int);
    void getTime(int&, int&, int&) const;
    void printTime() const;
    void incrementSeconds();
    void incrementMinutes();
    void incrementHours();
    bool equalTime(const clockType&) const;
};
```

In Example 12-5, because the identifiers `hr`, `min`, and `sec` do not follow any member access specifier, they are **private**.

It is a common practice to list all of the **public** members first and then the **private** members. This way, you can focus your attention on the **public** members.

Constructors

In the program in Example 12-2, when we printed the value of `yourClock` without calling the function `setTime`, the output was some strange numbers (see the output of Line 5 in the sample run). This is due to the fact that C++ does not automatically initialize the variables. Because the **private** members of a class cannot be accessed outside of the class (in our case, the member variables), if the user forgets to initialize these variables by calling the function `setTime`, the program will produce erroneous results.

To guarantee that the member variables of a class are initialized, you use constructors. There are two types of constructors: with parameters and without parameters. The constructor without parameters is called the **default constructor**.

Constructors have the following properties:

- The name of a constructor is the same as the name of the class.
- A constructor, even though it is a function, has no type. That is, it is neither a value-returning function nor a **void** function.
- A class can have more than one constructor. However, all constructors of a class have the same name.
- If a class has more than one constructor, the constructors must have different formal parameter lists. That is, either they have a different number of formal parameters or, if the number of formal parameters is the same, then the data type of the formal parameters, in the order you list, must differ in at least one position.
- Constructors execute automatically when a class object enters its scope. Because they have no types, they cannot be called like other functions.
- Which constructor executes depends on the types of values passed to the class object when the class object is declared.

Let us extend the definition of the **class** `clockType` by including two constructors:

```
class clockType
{
public:
    void setTime(int, int, int);
    void getTime(int&, int&, int&) const;
    void printTime() const;
    void incrementSeconds();
```

```

    void incrementMinutes();
    void incrementHours();
    bool equalTime(const clockType&) const;
    clockType(int, int, int); //constructor with parameters
    clockType(); //default constructor

private:
    int hr;
    int min;
    int sec;
};

```

This definition of the `class clockType` includes two constructors: one with three parameters and one without any parameters. Let us now write the definitions of these constructors:

```

clockType::clockType(int hours, int minutes, int seconds)
{
    if (0 <= hours && hours < 24)
        hr = hours;
    else
        hr = 0;

    if (0 <= minutes && minutes < 60)
        min = minutes;
    else
        min = 0;

    if (0 <= seconds && seconds < 60)
        sec = seconds;
    else
        sec = 0;
}

clockType::clockType() //default constructor
{
    hr = 0;
    min = 0;
    sec = 0;
}

```

From the definitions of these constructors, it follows that the default constructor sets the three member variables—`hr`, `min`, and `sec`—to 0. Also, the constructor with parameters sets the member variables to whatever values are assigned to the formal parameters. Moreover, we can write the definition of the constructor with parameters by calling the function `setTime`, as follows:

```

clockType::clockType(int hours, int minutes, int seconds)
{
    setTime(hours, minutes, seconds);
}

```

Invoking a Constructor

Recall that when a class object is declared, a constructor is automatically executed. Because a class might have more than one constructor, including the default constructor, next we discuss how to invoke a specific constructor.

Invoking the Default Constructor

Suppose that a class contains the default constructor. The syntax to invoke the default constructor is:

```
className classObjectName;
```

For example, the statement:

```
clockType yourClock;
```

declares `yourClock` to be an object of type `clockType`. In this case, the default constructor executes, and the member variables of `yourClock` are initialized to 0.

NOTE

If you declare an object and want the default constructor to be executed, the empty parentheses after the object name are not required in the object declaration statement. In fact, if you accidentally include the empty parentheses, the compiler generates a syntax error message. For example, the following statement to declare the object `yourClock` is illegal:

```
clockType yourClock(); //illegal object declaration
```

Invoking a Constructor with Parameters

Suppose a class contains constructors with parameters. The syntax to invoke a constructor with a parameter is:

```
className classObjectName(argument1, argument2, ...);
```

in which `argument1`, `argument2`, and so on are either a variable or an expression.

Note the following:

- The number of arguments and their type should match the formal parameters (in the order given) of one of the constructors.
- If the type of the arguments does not match the formal parameters of any constructor (in the order given), C++ uses type conversion and looks for the best match. For example, an integer value might be converted to a floating-point value with a zero decimal part. Any ambiguity will result in a compile-time error.

Consider the statement:

```
clockType myClock(5, 12, 40);
```

This statement declares an object `myClock` of type `clockType`. Here, we are passing three values of type `int`, which matches the type of the formal parameters of the constructor with a parameter. Therefore, the constructor with parameters of the `class clockType` executes, and the three member variables of the object `myClock` are set to 5, 12, and 40.

Example 12-6 further illustrates how constructors are executed.

EXAMPLE 12-6

Consider the following class definition:

```
class inventory
{
public:
    inventory();                //Line 1
    inventory(string);          //Line 2
    inventory(string, int, double); //Line 3
    inventory(string, int, double, int); //Line 4

    //Add additional functions

private:
    string name;
    int itemNum;
    double price;
    int unitsInStock;
};
```

This class has four constructors and four member variables. Suppose that the definitions of the constructors are as follows:

```
inventory::inventory() //default constructor
{
    name = "";
    itemNum = -1;
    price = 0.0;
    unitsInStock = 0;
}

inventory::inventory(string n)
{
    name = n;
    itemNum = -1;
    price = 0.0;
    unitsInStock = 0;
}

inventory::inventory(string n, int iNum, double cost)
{
    name = n;
    itemNum = iNum;
    price = cost;
    unitsInStock = 0;
}
```

```
inventory::inventory(string n, int iNum, double cost, int inStock)
{
    name = n;
    itemNum = iNum;
    price = cost;
    unitsInStock = inStock;
}
```

Consider the following declarations:

```
inventory item1;
inventory item2("Dryer");
inventory item3("Washer", 2345, 278.95);
inventory item4("Toaster", 8231, 34.49, 200);
```

For `item1`, the default constructor in Line 1 executes because no value is passed to this variable. For `item2`, the constructor in Line 2 executes because only one parameter, which is of type `string`, is passed, and it matches with the constructor in Line 2. For `item3`, the constructor in Line 3 executes because three parameters are passed to `item3`, and they match with the constructor in Line 3. Similarly, for `item4`, the constructor in Line 4 executes (see Figure 12-7).




FIGURE 12-7 Effect of constructors on objects

NOTE

If the values passed to a class object do not match the parameters of any constructor and if no type conversion is possible, a compile-time error will be generated.

Constructors and Default Parameters

A constructor can also have default parameters. In such cases, the rules for declaring formal parameters are the same as those for declaring default formal parameters in a function. Moreover, actual parameters to a constructor with default parameters are passed according to the rules for functions with default parameters. (Chapter 7 discusses functions with default parameters.) Using the rules for defining default parameters, in the definition of the `class clockType`, you can replace both constructors using the following statement. (Recall that in the function prototype, the name of a formal parameter is optional.)

```
clockType clockType(int = 0, int = 0, int = 0);    //Line 1
```

In the implementation file, the definition of this constructor is the same as the definition of the constructor with parameters.

If you replace the constructors of the `class clockType` with the constructor in Line 1 (the constructor with the default parameters), then you can declare `clockType` objects with zero, one, two, or three arguments, as follows:

```
clockType clock1;                //Line 2
clockType clock2(5);             //Line 3
clockType clock3(12, 30);        //Line 4
clockType clock4(7, 34, 18);     //Line 5
```

The member variables of `clock1` are initialized to 0. The member variable `hr` of `clock2` is initialized to 5, and the member variables `min` and `sec` of `clock2` are initialized to 0. The member variable `hr` of `clock3` is initialized to 12, the member variable `min` of `clock3` is initialized to 30, and the member variable `sec` of `clock3` is initialized to 0. The member variable `hr` of `clock4` is initialized to 7, the member variable `min` of `clock4` is initialized to 34, and the member variable `sec` of `clock4` is initialized to 18.

Using these conventions, we can say that a constructor that has no parameters, or has all default parameters, is called the **default constructor**.

Classes and Constructors: A Precaution

As discussed in the preceding section, constructors provide guaranteed initialization of the object's member variables. Typically, the default constructor is used to initialize the member variables to some default values, and this constructor has no parameters. A constructor with parameters is used to initialize the member variables to some specific values.

We have seen that if a class has no constructor(s), then the object created is uninitialized because C++ does not automatically initialize variables when they are declared. In reality, if a class has no constructor(s), then C++ automatically provides the default constructor. However, this default constructor does not do anything. The object declared is still uninitialized.

The important things to remember about classes and constructors are the following:

- If a class has no constructor(s), C++ *automatically provides* the default constructor. However, the object declared is still uninitialized.

- On the other hand, suppose a `class`, say, `dummyClass`, includes constructor(s) with parameter(s) and does not include the default constructor. In this case, C++ *does not* provide the default constructor for the `class` `dummyClass`. Therefore, when an object of the `class` `dummyClass` is declared, we must include the appropriate arguments in its declaration.

The following code further explains this. Consider the definition of the following class:

```
class dummyClass
{
public:
    void print() const;

    dummyClass(int dX, int dY);

private:
    int x;
    int y;
};
```

The `class` `dummyClass` *does not* have the default constructor. It has a constructor with parameters. Given this definition of the `class` `dummyClass`, the following object declaration is legal:

```
dummyClass myObject(10, 25); //object declaration is legal
```

However, because the `class` `dummyClass` does not contain the default constructor, the following declaration is incorrect and would generate a syntax error:

```
dummyClass dummyObject; //incorrect object declaration
```

Therefore, to avoid such pitfalls, if a class has constructor(s), the class should also include the default constructor.

Arrays of Class Objects (Variables) and Constructors

If a class has constructors and you declare an array of that class's objects, the class should have the default constructor. The default constructor is typically used to initialize each (array) class object.


For example, if you declare an array of 100 class objects, then it is impractical (if not impossible) to specify different constructors for each component. (We will further clarify this at the end of this section.)

Suppose that you have 100 employees who are paid on an hourly basis, and you need to keep track of their arrival and departure times. You can declare two arrays—`arrivalTimeEmp` and `departureTimeEmp`—of 100 components each, wherein each component is an object of type `clockType`.

Consider the following statement:


```
clockType arrivalTimeEmp[100]; //Line 1
```

The statement in Line 1 creates the array of objects `arrivalTimeEmp[0]`, `arrivalTimeEmp[1]`, ..., `arrivalTimeEmp[99]`, as shown in Figure 12-8.

FIGURE 12-8 Array `arrivalTimeEmp`

You can now use the functions of the `class clockType` to manipulate the time for each employee. For example, the following statement sets the arrival time, that is, `hr`, `min`, and `sec`, of the 50th employee to 8, 5, and 10, respectively (see Figure 12-9).

```
arrivalTimeEmp[49].setTime(8, 5, 10);           //Line 2
```

FIGURE 12-9 Array `arrivalTimeEmp` after setting the time of employee 49

To output the arrival time of each employee, you can use a loop, such as the following:

```
for (int j = 0; j < 100; j++)           //Line 3
{
    cout << "Employee " << (j + 1)
        << " arrival time: ";
    arrivalTimeEmp[j].printTime();       //Line 4
    cout << endl;
}
```

The statement in Line 4 outputs the arrival time of an employee in the form `hr:min:sec`.

To keep track of the departure time of each employee, you can use the array `departureTimeEmp`.

Similarly, you can use arrays to manage a list of names or other objects.

NOTE

Before leaving our discussion of arrays of class objects, we would like to point out the following: The beginning of this section stated that if you declare an array of class objects and the class has constructor(s), then the class should have the default constructor. The compiler uses the default constructor to initialize the array of objects. If the array size is large, then it is impractical to specify a different constructor with parameters for each object. For a small-sized array, we can manage to specify a different constructor with parameters.

For example, the following statement declares `clocks` to be an array of two components. The member variables of the first component are initialized to 8, 35, and 42, respectively. The member variables of the second component are initialized to 6, 52, and 39, respectively.

```
clockType clocks[2] = {clockType(8, 35, 42), clockType(6, 52, 39)};
```

In fact, the expression `clockType(8, 35, 42)` creates an anonymous object of the `class clockType`; initializes its member variables to 8, 35, and 42, respectively; and then uses a member-wise copy to initialize the object `clock[0]`.

Consider the following statement, which creates the object `myClock` and initializes its member variables to 10, 45, and 38, respectively. This is how we have been creating and initializing objects. In fact, the statement:

```
clockType myClock(10, 45, 38);
```

is equivalent to the statement:

```
clockType myClock = clockType(10, 45, 38);
```

However, the first statement is more efficient. It does not first require that an anonymous object be created and then member-wise copied in order to initialize `myClock`.

The main point that we are stressing here, and that we discussed in the preceding section, is the following: To avoid any pitfalls, if a class has constructor(s), it should also have the default constructor.

Destructors

Like constructors, destructors are also functions. Moreover, like constructors, a destructor does not have a type. That is, it is neither a value-returning function nor a void function. However, a class can have only one destructor, and the destructor has no parameters. The name of a destructor is the *tilde* character (`~`), followed by the name of the class. For example, the name of the destructor for the `class clockType` is:

```
~clockType();
```

The destructor automatically executes when the class object goes out of scope. The use of destructors is discussed in subsequent chapters.

Data Abstraction, Classes, and Abstract Data Types

For the car that we drive, most of us want to know how to start the car and drive it. Most people are not concerned with the complexity of how the engine works. By separating the design details of a car's engine from its use, the manufacturer helps the driver focus on how to drive the car. Our daily life has other similar examples. For the most part, we are concerned only with how to use certain items, rather than with how they work.

Separating the design details (that is, how the car's engine works) from its use is called **abstraction**. In other words, abstraction focuses on what the engine does and not on how it works. Thus, abstraction is the process of separating the logical properties from the implementation details. Driving the car is a logical property; the construction of the engine constitutes the implementation details. We have an abstract view of what the engine does but are not interested in the engine's actual implementation.

Abstraction can also be applied to data. Earlier sections of this chapter defined a data type `clockType`. The data type `clockType` has three member variables and the following basic operations:

1. Set the time.
2. Return the time.
3. Print the time.
4. Increment the time by one second.
5. Increment the time by one minute.
6. Increment the time by one hour.
7. Compare two times to see whether they are equal.

The actual implementation of the operations, that is, the definitions of the member functions of the class `clockType`, was postponed.

Data abstraction is defined as a process of separating the logical properties of the data from its implementation. The definition of `clockType` and its basic operations are the logical properties; the storing of `clockType` objects in the computer and the algorithms to perform these operations are the implementation details of `clockType`.

Abstract data type (ADT): A data type that separates the logical properties from the implementation details.

Like any other data type, an ADT has three things associated with it: the name of the ADT, called the **type name**; the set of values belonging to the ADT, called the **domain**; and the set of **operations** on the data. Following these conventions, we can define the `clockType` ADT as follows:

```

dataTypeName
    clockType
domain
    Each clockType value is a time of day in the form of hours,
    minutes, and seconds.
operations
    Set the time.
    Return the time.
    Print the time.
    Increment the time by one second.
    Increment the time by one minute.
    Increment the time by one hour.
    Compare the two times to see whether they are equal.

```

EXAMPLE 12-7

A list is defined as a set of values of the same type. Because all values in a list are of the same type, a convenient way to represent and process a list is to use an array. You can define a list as an ADT as follows:

```

dataTypeName
    listType
domain
    Every listType value is an array of, say, 1000 numbers
operations
    Check to see whether the list is empty.
    Check to see whether the list is full.
    Search the list for a given item.
    Delete an item from the list.
    Insert an item in the list.
    Sort the list.
    Destroy the list.
    Print the list.

```

The next obvious question is how to implement an ADT in a program. To implement an ADT, you must represent the data and write algorithms to perform the operations.

The previous section used classes to group data and functions together. Furthermore, our definition of a class consisted only of the specifications of the operations; functions to implement the operations were written separately. Thus, we see that classes are a convenient way to implement an ADT. In fact, in C++, classes were specifically designed to handle ADTs.

Next, we define the `class` `listType` to implement a list as an ADT. Typically in a list, not only do we store the elements, but we also keep track of the number of elements in the list. Therefore, our `class` `listType` has two member variables: one to store the elements and another to keep track of the number of elements in the list. The following `class`, `listType`, defines the list as an ADT.

```
class listType
{
public:
    bool isEmptyList() const;
    bool isFullList() const;
    int search(int searchItem) const;
    void insert(int newElement);
    void remove(int removeElement);
    void destroyList();
    void printList() const;
    listType(); //constructor

private:
    int list[1000];
    int length;
};
```

Figure 12-10 shows the UML class diagram of the `class` `listType`.




FIGURE 12-10 UML class diagram of the `class` `listType`

A `struct` Versus a `class`

Chapter 11 defined a `struct` as a fixed collection of components, wherein the components can be of different types. This definition of components in a `struct` included only member variables. However, a C++ `struct` is very similar to a C++ `class`. As with a

`class`, members of a `struct` can also be functions, including constructors and a destructor. The only difference between a `struct` and a `class` is that, by default, all members of a `struct` are `public`, and all members of a `class` are `private`. You can use the member access specifier `private` in a `struct` to make a member `private`.

In C, the definition of a `struct` is similar to the definition of a `struct` in C++, as given in Chapter 11. Because C++ evolved from C, the standard C-`structs` are perfectly acceptable in C++. However, the definition of a `struct` in C++ was expanded to include member functions and constructors and destructors. In the future, because a `class` is a syntactically separate entity, specially designed to handle an ADT, the definition of a `class` may evolve in a completely different way than the definition of a C-like `struct`.

Both C++ `classes` and `structs` have the same capabilities. However, most programmers restrict their use of structures to adhere to their C-like structure form and thus do not use them to include member functions. In other words, if all of the member variables of a `class` are `public` and the `class` has no member functions, you typically use a `struct` to group these members. This is, in fact, how it is done in this book.

Information Hiding

The previous section defined the `class` `clockType` to implement the time in a program. We then wrote a program that used the `class` `clockType`. In fact, we combined the `class` `clockType` with the function definitions to implement the operations and the function `main` so as to complete the program. That is, the specification and implementation details of the `class` `clockType` were directly incorporated into the program.

Is it a good practice to include the specification and implementation details of a class in the program? Definitely not. There are several reasons for not doing so. Suppose the definition of the class and the definitions of the member functions are directly included in the user's program. The user then has direct access to the definition of the class and the definitions of the member functions. Therefore, the user can modify the operations in any way the user pleases. The user can also modify the member variables of an object in any way the user pleases. Thus, in this sense, the `private` member variables of an object are no longer `private` to the object.

If several programmers use the same object in a project and if they have direct access to the internal parts of the object, there is no guarantee that every programmer will use the same object in exactly the same way. Thus, we must hide the implementation details. The user should know only what the object does, not how it does it. Hiding the implementation details frees the user from having to fit this extra piece of code in the program. Also, by hiding the details, we can ensure that an object will be used in exactly the same way throughout the project. Furthermore, once an object has been written, debugged, and tested properly, it becomes (and remains) error-free.

This section discusses how to hide the implementation details of an object. For illustration purposes, we will use the `class clockType`.

To implement `clockType` in a program, the user must declare objects of type `clockType` and know which operations are allowed and what the operations do. So, the user must have access to the specification details. Because the user is not concerned with the implementation details, we must put those details in a separate file called an **implementation file**. Also, because the specification details can be too long, we must free the user from having to include them directly in the program. However, the user must be able to look at the specification details so that he or she can correctly call the functions, and so forth. We must, therefore, put the specification details in a separate file. The file that contains the specification details is called the **header file** (or **interface file**).

The implementation file contains the definitions of the functions to implement the operations of an object. This file contains, among other things (such as the preprocessor directives), the C++ statements. Because a C++ program can have only one function, `main`, the implementation file does not contain the function `main`. Only the user program contains the function `main`. Because the implementation file does not contain the function `main`, we cannot produce the executable code from this file. In fact, we produce what is called the object code from the implementation file. The user then links the object code produced by the implementation file with the object code of the program that uses the class to create the final executable code.

Finally, the header file has an extension `h`, whereas the implementation file has an extension `cpp`. Suppose that the specification details of the `class clockType` are in a file called `clockType`. The complete name of this file should then be `clockType.h`. If the implementation details of the `class clockType` are in a file—say, `clockTypeImp`—the name of this file must be `clockTypeImp.cpp`.

The file `clockTypeImp.cpp` contains only the definitions of the functions, not the definition of the class. Thus, to resolve the problem of an undeclared identifier (such as the function names and variable names), we include the header file `clockType.h` in the file `clockTypeImp.cpp` with the help of the `include` statement. The following `include` statement is required by any program that uses the `class clockType`, as well as by the implementation file that defines the operations for the `class clockType`:

```
#include "clockType.h"
```

Note that the header file `clockType.h` is enclosed in double quotation marks, not angular brackets. The header file `clockType.h` is called the user-defined header file. Typically, all user-defined header files are enclosed in double quotation marks, whereas the system-provided header files (such as `iostream`) are enclosed between angular brackets.

The implementation contains the definitions of the functions, and these definitions are hidden from the user because the user is typically provided *only* the object code.

However, the user of the class should be aware of what a particular function does and how to use it. Therefore, in the specification file with the function prototypes, we include comments that briefly describe the function and specify any preconditions and/or postconditions.

Precondition: A statement specifying the condition(s) that must be true before the function is called.

Postcondition: A statement specifying what is true after the function call is completed.

Following are the specification and implementation files for the `class` `clockType`:

`//clockType.h, the specification file for the class clockType`

```
class clockType
{
public:
    void setTime(int hours, int minutes, int seconds);
        //Function to set the time.
        //The time is set according to the parameters.
        //Postcondition: hr = hours; min = minutes;
        //                sec = seconds;
        //                The function checks whether the
        //                values of hours, minutes, and seconds
        //                are valid. If a value is invalid, the
        //                default value 0 is assigned.

    void getTime(int& hours, int& minutes, int& seconds) const;
        //Function to return the time.
        //Postcondition: hours = hr; minutes = min;
        //                seconds = sec;

    void printTime() const;
        //Function to print the time.
        //Postcondition: The time is printed in the form
        //                hh:mm:ss.

    void incrementSeconds();
        //Function to increment the time by one second.
        //Postcondition: The time is incremented by one second.
        //                If the before-increment time is
        //                23:59:59, the time is reset to 00:00:00.

    void incrementMinutes();
        //Function to increment the time by one minute.
        //Postcondition: The time is incremented by one minute.
        //                If the before-increment time is
        //                23:59:53, the time is reset to 00:00:53.

    void incrementHours();
        //Function to increment the time by one hour.
        //Postcondition: The time is incremented by one hour.
```

```

        //                If the before-increment time is
        //                23:45:53, the time is reset to 00:45:53.

bool equalTime(const clockType& otherClock) const;
    //Function to compare the two times.
    //Postcondition: Returns true if this time is equal to
    //                otherClock; otherwise, returns false.

clockType(int hours, int minutes, int seconds);
    //Constructor with parameters.
    //The time is set according to the parameters.
    //Postcondition: hr = hours; min = minutes;
    //                sec = seconds;
    //                The constructor checks whether the
    //                values of hours, minutes, and seconds
    //                are valid. If a value is invalid, the
    //                default value 0 is assigned.

clockType();
    //Default constructor
    //The time is set to 00:00:00.
    //Postcondition: hr = 0; min = 0; sec = 0;

private:
    int hr; //variable to store the hours
    int min; //variable to store the minutes
    int sec; //variable to store the seconds
};

```

//clockTypeImp.cpp, the implementation file

```

#include <iostream>
#include "clockType.h"

using namespace std;
.
.
.
//Place the definitions of the member functions of the class
//clockType here.
.
.
.

```

Next, we describe the user file containing the program that uses the `class` `clockType`.

//The user program that uses the class `clockType`

```

#include <iostream>
#include "clockType.h"

```

```
using namespace std;
.
.
.
//Place the definitions of the function main and the other
//user-defined functions here
.
.
.
```

NOTE

To save space, we have not provided the complete details of the implementation file and the file that contains the user program. However, you can find these files and the specification (header) file at the Web site accompanying this book.

Executable Code

The previous section discussed how to hide the implementation details of a class. To use an object in a program, during execution, the program must be able to access the implementation details of the object (that is, the algorithms to implement the operations on the object). This section discusses how a client's program obtains access to the implementation details of an object. For illustration purposes, we will use the `class clockType`.

As explained previously, to use the `class clockType`, the program must include the header file `clockType.h` via the `include` statement. For example, the following program segment includes the header file `clockType.h`:

```
//Program test.cpp

#include "clockType.h"
.
.
.
int main()
{
    .
    .
    .
}
```

The program `test.cpp` must include only the header file, not the implementation file. To create the executable code to run the program `test.cpp`, the following steps are required:

1. We separately compile the file `clockTypeImp.cpp` and create the object code file `clockTypeImp.obj`. The object code file contains the machine language code, but the code is not in an executable form.

Suppose that the command `cc` invokes the C++ compiler or linker, or both, on the computer's system command line. The command:

```
cc -c clockTypeImp.cpp
```

creates the object code file `clockTypeImp.obj`.

2. To create the executable code for the source code file `test.cpp`, we compile the source code file `test.cpp`, create the object code file `test.obj`, and then link the files `test.obj` and `clockTypeImp.obj` to create the executable file `test.exe`. The following command on the system command line creates the executable file `test.exe`:

```
cc test.cpp clockTypeImp.obj
```

NOTE

1. To create the object code file for any source code file, we use the command line option `-c` on the system command line. For example, to create the object code file for the source code file, called `exercise.cpp`, we use the following command on the system command line:

```
cc -c exercise.cpp
```

2. To link more than one object code file with a source code file, we list all of the object code files on the system command line. For example, to link `A.obj` and `B.obj` with the source code file `test.cpp`, we use the command:

```
cc test.cpp A.obj B.obj
```

3. If a source code file is modified, it must be recompiled.
4. If modifications in one source file affect other files, the other files must be recompiled and relinked.
5. The user must have access to the header file and the object code file. Access to the header file is needed to see what the objects do and how to use them. Access to the object code file is needed so that the user can link the program with the object code to produce an executable code. The user does not need access to the source code file containing the implementation details.

As stated in Chapter 1, IDEs Visual C++ 2008 Express, Visual Studio .NET, C++ Builder, and CodeWarrior put the editor, compiler, and linker all into one package. With one command, the program is compiled and linked with the other necessary files. These systems also manage multiple-file programs in the form of a project. Thus, a project consists of several files, called the project files. These systems usually have a command, called **build**, **rebuild**, or **make**. (Check your system's documentation.) When the build, rebuild, or make command is applied to a project, the system automatically compiles and links all of the files required to create the executable code.

When one or more files in the project change, you can use these commands to recompile and relink the files.

EXAMPLE 12-8

In Example 6-4, the function `rollDice` rolls a pair of dice until the sum of the numbers rolled is a given number and returns the number of times the dice are rolled to get the desired sum. In fact, we can design a class that implements the basic properties of a die. Consider the definition of the following `class die`.

```
class die
{
public:
    die();
        //Default constructor
        //Sets the default number rolled by a die to 1

    int roll();
        //Function to roll a die.
        //This function uses a random number generator to randomly
        //generate a number between 1 and 6, and stores the number
        //in the instance variable num and returns the number.

    int getNum() const;
        //Function to return the number on the top face of the die.
        //Returns the value of the instance variable num.

private
    int num;
};
```

The definitions of the member functions are given next.

```
die::die()
{
    num = 1;
    srand(time(0));
}

int die::roll()
{
    num = rand() % 6 + 1;

    return num;
}

int die::getNum() const
{
    return num;
}
```

The following program shows how to use the `class die` in a program.

```
//The user program that uses the class die

#include <iostream>
#include "die.h"

using namespace std;

int main()
{
    die die1; //Line 1
    die die2; //Line 2

    cout << "Line 4: die1: " << die1.getNum() << endl; //Line 4

    cout << "Line 5: die2: " << die2.getNum() << endl; //Line 5

    cout << "Line 6: After rolling die1: "
         << die1.roll() << endl; //Line 6

    cout << "Line 7: After rolling die2: "
         << die2.roll() << endl; //Line 7
    cout << "Line 8: The sum of the numbers rolled"
         << " by the dice is: "
         << die1.getNum() + die2.getNum() << endl; //Line 8

    cout << "Line 9: After again rolling, the sum of "
         << "the numbers rolled is: "
         << die1.roll() + die2.roll() << endl; //Line 9

    return 0; //Line 10
} //end main //Line 11
```

Sample Run:

```
Line 4: die1: 1
Line 5: die2: 1
Line 6: After rolling die1: 3
Line 7: After rolling die2: 4
Line 8: The sum of the numbers rolled by the dice is: 7
Line 9: After again rolling, the sum of the numbers rolled is: 5
```

The preceding program works as follows. The statements in Lines 2 and 3 create the objects `die1` and `die2`, and, using the default constructor, set both the dice to 1. The statements in Lines 4 and 5 output the number of both the dice. The statement in Line 6 rolls `die1` and outputs the number rolled. Similarly, the statement in Line 7 rolls `die2` and outputs the number rolled. The statement in Line 8 outputs the sum of the numbers rolled by `die1` and `die2`. The statement in Line 9 again rolls both the dice and outputs the sum of the numbers rolled.

Example 12-9 further illustrates how classes are designed and implemented. The `class` `personType` that is designed in Example 12-9 is very useful; we will use this class in subsequent chapters.

EXAMPLE 12-9

The most common attributes of a person are the person's first name and last name. The typical operations on a person's name are to set the name and print the name. The following statements define a class with these properties.

```
#include <string>

using namespace std;

class personType
{
public:
    void print() const;
        //Function to output the first name and last name
        //in the form firstName lastName.

    void setName(string first, string last);
        //Function to set firstName and lastName according
        //to the parameters.
        //Postcondition: firstName = first; lastName = last;


    string getFirstName() const;
        //Function to return the first name.
        //Postcondition: The value of firstName is returned.

    string getLastName() const;
        //Function to return the last name.
        //Postcondition: The value of lastName is returned.

    personType(string first = "", string last = "");
        //Constructor
        //Sets firstName and lastName according to the parameters.
        //The default values of the parameters are null strings.
        //Postcondition: firstName = first; lastName = last;

private:
    string firstName; //variable to store the first name
    string lastName;  //variable to store the last name
};
```

Figure 12-11 shows the UML class diagram of the `class` `personType`.

FIGURE 12-11 UML class diagram of the `class` `personType`

We now give the definitions of the member functions of the `class` `personType`.

```

void personType::print() const
{
    cout << firstName << " " << lastName;
}

void personType::setName(string first, string last)
{
    firstName = first;
    lastName = last;
}

string personType::getFirstName() const
{
    return firstName;
}

string personType::getLastName() const
{
    return lastName;
}

//constructor
personType::personType(string first, string last)
{
    firstName = first;
    lastName = last;
}
  
```

Static Members of a Class

NOTE

This section may be skipped without any loss of continuation.

In Chapter 7, we described two types of variables, automatic and **static**. Recall that if a local variable of a function is **static**, it exists between function calls. Similar to **static** variables, a class can have **static** members, functions, or variables. Let us note the following about the **static** members of a class:

- If a function of a class is **static**, in the class definition it is declared using the keyword **static** in its heading.
- If a member variable of a class is **static**, it is declared using the keyword **static**, as discussed in Chapter 7 and also illustrated in Example 12-10.
- A **public static** member, function, or variable of a class can be accessed using the class name and the scope resolution operator.

Example 12-10 clarifies the effect of the keyword **static**.

EXAMPLE 12-10

Consider the following definition of the **class** `illustrate`:

```
class illustrate
{
public:
    static int count;    //public static variable

    void print() const;
        //Function to output x, y, and count.

    void setX(int a);
        //Function to set x.
        //Postcondition: x = a;

    static void incrementY();
        //static function
        //Function to increment y by 1.
        //Postcondition: y = y + 1

    illustrate(int a = 0);
        //constructor
        //Postcondition: x = a;
        //      If no value is specified for a, x = 0;
```

```
private:
    int x;
    static int y; //private static variable
};
```

Suppose that the `static` member variables and the definitions of the member functions of the `class illustrate` are as follows. (These statements are all placed in the implementation file. Also, notice that all `static` member variables are initialized, as shown below.)

```
int illustrate::count = 0;
int illustrate::y = 0;

void illustrate::print() const
{
    cout << "x = " << x << ", y = " << y
        << ", count = " << count << endl;
}

void illustrate::setX(int a)
{
    x = a;
}

void illustrate::incrementY()
{
    y++;
}

illustrate::illustrate(int a)
{
    x = a;
}
```

Because the function `incrementY` is `static` and `public`, the following statement is legal:

```
illustrate::incrementY();
```

Similarly, because the member variable `count` is `static` and `public`, the following statement is legal:

```
illustrate::count++;
```

Next, we elaborate on `static` member variables a bit more. Suppose that you have a `class`, say, `myClass`, with member variables (`static` as well as non-`static`). When you create objects of type `myClass`, only non-`static` member variables of the `class myClass` become the member variables of each object. For each `static` member variable of a `class`, C++ allocates only one memory space. All `myClass` objects refer to the same memory space. In fact, `static` member variables of a `class` *exist* even when no

object of that **class** type exists. You can access the **public static** member variables outside of the **class**, as explained earlier in this section.

Next, we explain how memory space is allocated for **static** and non-**static** member variables of a class.

Suppose that you have the **class** `illustrate`, as given in Example 12-10. Memory space then exists for the **static** member variables `y` and `count`.

Consider the following statements:

```
illustrate illusObject1(3);    //Line 1
illustrate illusObject2(5);    //Line 2
```

The statements in Line 1 and Line 2 declare `illusObject1` and `illusObject2` to be `illustrate` type objects (see Figure 12-12).




FIGURE 12-12 `illusObject1` and `illusObject2`

Now, consider the following statements:

```
illustrate::incrementY();
illustrate::count++;
```

After these statements execute, the objects and static members are as shown in Figure 12-13.




FIGURE 12-13 `illusObject1` and `illusObject2` after the statements `illustrate::incrementY();` and `illustrate::count++;` execute

The output of the statement:

```
illusObject1.print();
```

is:

```
x = 3, y = 1, count = 1
```

Similarly, the output of the statement:

```
illusObject2.print();
```

is:

```
x = 5, y = 1, count = 1
```

Now consider the statement:

```
illustrate::count++;
```

After this statement executes, the objects and static members are as shown in Figure 12-14.




FIGURE 12-14 `illusObject1` and `illusObject2` after the statement `illustrate::count++;` executes

The output of the statements:

```
illusObject1.print();
```

```
illusObject2.print();
```

is:

```
x = 3, y = 1, count = 2
```

```
x = 5, y = 1, count = 2
```

The program in Example 12-11 further illustrates how `static` members of a class work.

EXAMPLE 12-11

```

#include <iostream>

#include "illustrate.h"

using namespace std;

int main()
{
    illustrate illusObject1(3);           //Line 1
    illustrate illusObject2(5);           //Line 2

    illustrate::incrementY();              //Line 3
    illustrate::count++;                   //Line 4
    illusObject1.print();                  //Line 5
    illusObject2.print();                  //Line 6
    cout << "Line 7: ***Increment y using "
          << "illusObject1***" << endl;    //Line 7

    illusObject1.incrementY();             //Line 8
    illusObject1.setX(8);                  //Line 9
    illusObject1.print();                  //Line 10
    illusObject2.print();                  //Line 11

    cout << "Line 12: ***Increment y using "
          << "illusObject2***" << endl;    //Line 12

    illusObject2.incrementY();             //Line 13
    illusObject2.setX(23);                 //Line 14
    illusObject1.print();                  //Line 15
    illusObject2.print();                  //Line 16

    return 0;
}

```

Sample Run:

```

x = 3, y = 1, count = 1
x = 5, y = 1, count = 1
Line 7: ***Increment y using illusObject1***
x = 8, y = 2, count = 1
x = 5, y = 2, count = 1
Line 12: ***Increment y using illusObject2***
x = 8, y = 3, count = 1
x = 23, y = 3, count = 1

```

The preceding program works as follows. The **static** member variables **y** and **count** are initialized to 0. The statement in Line 1 declares **illusObject1** to be an object of the **class** **illustrate** and initializes its member variable **x** to 3. The statement in

Line 2 declares `illusObject2` to be an object of the `class` `illustrate` and initializes its member variable `x` to 5.

The statement in Line 3 uses the name of the `class` `illustrate` and the function `incrementY` to increment `y`. Now, `count` is a `public static` member of the `class` `illustrate`. So the statement in Line 4 uses the name of the `class` `illustrate` to directly access `count` and increments it by 1. The statements in Lines 5 and 6 output the data stored in the objects `illusObject1` and `illusObject2`. Notice that the value of `y` for both objects is the same. Similarly, the value of `count` for both objects is the same.

The statement in Line 7 is an output statement. The statement in Line 8 uses the object `illusObject1` and the function `incrementY` to increment `y`. The statement in Line 9 sets the value of the member variable `x` of `illusObject1` to 8. Lines 10 and 11 output the data stored in the objects `illusObject1` and `illusObject2`. Notice that the value of `y` for both objects is the same. Similarly, the value of `count` for both objects is the same. Moreover, notice that the statement in Line 9 changes only the value of the member variable `x` of `illusObject1` because `x` is *not* a `static` member of the `class` `illustrate`.

The statement in Line 13 uses the object `illusObject2` and the function `incrementY` to increment `y`. The statement in Line 14 sets the value of the member variable `x` of `illusObject2` to 23. Lines 15 and 16 output the data stored in the objects `illusObject1` and `illusObject2`. Notice that the value of `y` for both objects is the same. Similarly, the value of `count` for both objects is the same. Moreover, notice that the statement in Line 14 changes only the value of the member variable `x` of `illusObject2`, because `x` is *not* a `static` member of the `class` `illustrate`.

NOTE

Here are some additional comments on `static` members of a class. As you have seen in this section, a `static` member function of a class does not need any object to be invoked. It can be called using the name of the class and the scope resolution operator, as illustrated. Therefore, a `static` member function cannot use anything that depends on a calling object. In other words, in the definition of a `static` member function, you cannot use a non-`static` member variable or a non-`static` function unless there is an object declared locally that accesses the non-`static` member variable or the non-`static` member function.

Let us again consider the `class` `illustrate`, as defined in Example 12-10. This class contains both `static` and non-`static` member variables. When we declare objects of this class, each object has its own copy of the member variable `x`, which is non-`static`, and all objects share the member variables `y` and `count`, which are `static`. Earlier in this chapter, we defined the terminology instance variables of a class using the `class` `clockType`. However, at that point, we did not discuss `static` member variables of a class. A class can have `static` as well as non-`static` member variables. We can, therefore, make the general statement that non-`static` member variables of a class are called the instance variables of the class.

PROGRAMMING EXAMPLE: Candy Machine

A common place to buy candy is from a machine. A new candy machine has been purchased for the gym, but it is not working properly. The machine sells candies, chips, gum, and cookies. You have been asked to write a program for this candy machine so that it can be put into operation.

The program should do the following:

1. Show the customer the different products sold by the candy machine.
2. Let the customer make the selection.
3. Show the customer the cost of the item selected.
4. Accept money from the customer.
5. Release the item.

Input The item selection and the cost of the item.

Output The selected item.

PROBLEM ANALYSIS AND ALGORITHM DESIGN

A candy machine has two main components: a built-in cash register and several dispensers to hold and release the products.

Cash Register Let us first discuss the properties of a cash register. The register has some cash on hand, it accepts the amount from the customer, and if the amount deposited is more than the cost of the item, then—if possible—it returns the change. For simplicity, we assume that the user deposits the money greater than or equal to the cost of the product. The cash register should also be able to show to the candy machine's owner the amount of money in the register at any given time. The following class defines the properties of a cash register:

```
class cashRegister
{
public:
    int getCurrentBalance() const;
    //Function to show the current amount in the cash
    //register.
    //Postcondition: The value of cashOnHand is returned.

    void acceptAmount(int amountIn);
    //Function to receive the amount deposited by
    //the customer and update the amount in the register.
    //Postcondition: cashOnHand = cashOnHand + amountIn;

    cashRegister(int cashIn = 500);
    //Constructor
    //Sets the cash in the register to a specific amount.
```

```

        //Postcondition: cashOnHand = cashIn;
        //                If no value is specified when the
        //                object is declared, the default value
        //                assigned to cashOnHand is 500.

private:
    int cashOnHand; //variable to store the cash
                   //in the register
};

```

Figure 12-15 shows the UML class diagram of the `class` `cashRegister`.




FIGURE 12-15 UML class diagram of the `class` `cashRegister`

Next, we give the definitions of the functions to implement the operations of the `class` `cashRegister`. The definitions of these functions are very simple and easy to follow.

The function `getCurrentBalance` shows the current amount in the cash register. It returns the value of the `private` member variable `cashOnHand`. So its definition is:

```

int cashRegister::getCurrentBalance() const
{
    return cashOnHand;
}

```

The function `acceptAmount` accepts the amount of money deposited by the customer. It updates the cash in the register by adding the amount deposited by the customer to the previous amount in the cash register. Essentially, the definition of this function is:

```

void cashRegister::acceptAmount(int amountIn)
{
    cashOnHand = cashOnHand + amountIn;
}

```

In the definition of the `class` `cashRegister`, the constructor is declared with a default value. Therefore, if the user does not specify any value when the object is declared, the default value is used to initialize the member variable `cashOnHand`. Recall that because we have specified the default value for the constructor's parameter in the

definition of the class, in the heading of the definition of the constructor, we do not specify the default value. The definition of the constructor is as follows:

```
cashRegister::cashRegister(int cashIn)
{
    if (cashIn >= 0)
        cashOnHand = cashIn;
    else
        cashOnHand = 500;
}
```

Note that the definition of the constructor checks for valid values of the parameter `cashIn`. If the value of `cashIn` is less than 0, the value assigned to the member variable `cashOnHand` is 500.

Dispenser The dispenser releases the selected item if it is not empty. It should show the number of items in the dispenser and the cost of the item. The following class defines the properties of a dispenser. Let us call this `class` `dispenserType`:

```
class dispenserType
{
public:
    int getNoOfItems() const;
        //Function to show the number of items in the machine.
        //Postcondition: The value of numberOfItems is returned.

    int getCost() const;
        //Function to show the cost of the item.
        //Postcondition: The value of cost is returned.

    void makeSale();
        //Function to reduce the number of items by 1.
        //Postcondition: numberOfItems--;

    dispenserType(int setNoOfItems = 50, int setCost = 50);
        //Constructor
        //Sets the cost and number of items in the dispenser
        //to the values specified by the user.
        //Postcondition: numberOfItems = setNoOfItems;
        //      cost = setCost;
        //      If no value is specified for a
        //      parameter, then its default value is
        //      assigned to the corresponding member
        //      variable.

private:
    int numberOfItems;    //variable to store the number of
                        //items in the dispenser
    int cost;    //variable to store the cost of an item
};
```

Figure 12-16 shows the UML class diagram of the `class` `dispenserType`.




FIGURE 12-16 UML class diagram of the `class` `dispenserType`

Because the candy machine sells four types of items, we shall declare four objects of type `dispenserType`. For example, the statement:

```
dispenserType chips(100, 65);
```

declares `chips` to be an object of type `dispenserType`, sets the number of chip bags in the dispenser to 100, and sets the cost of each chip bag to 65 cents (see Figure 12-17).




FIGURE 12-17 Object `chips`

Next, we discuss the definitions of the functions to implement the operations of the `class` `dispenserType`.

The function `getNoOfItems` returns the number of items of a particular product. Because the number of items currently in the dispenser is stored in the `private` member variable `numberOfItems`, the function returns the value of `numberOfItems`. The definition of this function is:

```
int dispenserType::getNoOfItems() const
{
    return numberOfItems;
}
```

The function `getCost` returns the cost of a product. Because the cost of a product is stored in the `private` member variable `cost`, the function returns the value of `cost`. The definition of this function is:

```
int dispenserType::getCost() const
{
    return cost;
}
```

When a product is sold, the number of items in that dispenser is reduced by 1. Therefore, the function `makeSale` reduces the number of items in the dispenser by 1. That is, it decrements the value of the `private` member variable `numberOfItems` by 1. The definition of this function is:

```
void dispenserType::makeSale()
{
    numberOfItems--;
}
```

The definition of the constructor checks for valid values of the parameters. If these values are less than 0, the default values are assigned to the member variables. The definition of the constructor is:

```
//constructor
dispenserType::dispenserType(int setNoOfItems, int setCost)
{
    if (setNoOfItems >= 0)
        numberOfItems = setNoOfItems;
    else
        numberOfItems = 50;

    if (setCost >= 0)
        cost = setCost;
    else
        cost = 50;
}
```

MAIN PROGRAM

When the program executes, it must do the following:

1. Show the different products sold by the candy machine.
2. Show how to select a particular product.
3. Show how to terminate the program.

Furthermore, these instructions must be displayed after processing each selection (except exiting the program) so that the user need not remember what to do if he or she wants to buy two or more items. Once the user has made the appropriate selection, the candy machine must act accordingly. If the user has opted to buy a product and that product is available, the candy machine should show the cost of the

product and ask the user to deposit the money. If the amount deposited is at least the cost of the item, the candy machine should sell the item and display an appropriate message.

This discussion translates into the following algorithm:

1. Show the selection to the customer.
2. Get the selection.
3. If the selection is valid and the dispenser corresponding to the selection is not empty, sell the product.

We divide this program into three functions: `showSelection`, `sellProduct`, and `main`.

`showSelection` This function displays the information necessary to help the user select and buy a product. This definition of the function `showSelection` is:

```
void showSelection()
{
    cout << "*** Welcome to Shelly's Candy Shop ***" << endl;
    cout << "To select an item, enter " << endl;
    cout << "1 for Candy" << endl;
    cout << "2 for Chips" << endl;
    cout << "3 for Gum" << endl;
    cout << "4 for Cookies" << endl;
    cout << "9 to exit" << endl;
} //end showSelection
```

`sellProduct` This function attempts to sell the product selected by the customer. Therefore, it must have access to the dispenser holding the product. The first thing that this function does is check whether the dispenser holding the product is empty. If the dispenser is empty, the function informs the customer that this product is sold out. If the dispenser is not empty, it tells the user to deposit the necessary amount to buy the product.

If the user does not deposit enough money to buy the product, `sellProduct` tells the user how much additional money must be deposited. If the user fails to deposit enough money in two tries to buy the product, the function simply returns the money. (Programming Exercise 9, at the end of this chapter, asks you to revise the definition of the method `sellProduct` so that it keeps asking the user to enter the additional amount as long as the user has not entered enough money to buy the product.) If the amount deposited by the user is sufficient, it accepts the money and sells the product. Selling the product means to decrement the number of items in the dispenser by 1 and to update the money in the cash register by adding the cost of the product. (Because this program does not return the extra money

deposited by the customer, the cash register is updated by adding the money entered by the user.)

From this discussion, it is clear that the function `sellProduct` must have access to the dispenser holding the product (to decrement the number of items in the dispenser by 1 and to show the cost of the item) as well as the cash register (to update the cash). Therefore, this function has two parameters: one corresponding to the dispenser and the other corresponding to the cash register. Furthermore, both parameters must be referenced.

In pseudocode, the algorithm for this function is:

1. If the dispenser is not empty,
 - a. Show and prompt the customer to enter the cost of the item.
 - b. Get the amount entered by the customer.
 - c. If the amount entered by the customer is less than the cost of the product,
 - i. Show and prompt the customer to enter the additional amount.
 - ii. Calculate the total amount entered by the customer.
 - d. If the amount entered by the customer is at least the cost of the product,
 - i. Update the amount in the cash register.
 - ii. Sell the product—that is, decrement the number of items in the dispenser by 1.
 - iii. Display an appropriate message.
 - e. If the amount entered by the user is less than the cost of the item, return the amount.
2. If the dispenser is empty, tell the user that this product is sold out.

This definition of the function `sellProduct` is:

```
void sellProduct(dispenserType& product,
                 cashRegister& pCounter)
{
    int amount; //variable to hold the amount entered
    int amount2; //variable to hold the extra amount needed

    if (product.getNoOfItems() > 0) //if the dispenser is not
                                    //empty
    {
        cout << "Please deposit " << product.getCost()
              << " cents" << endl;
        cin >> amount;
```

```

    if (amount < product.getCost())
    {
        cout << "Please deposit another "
              << product.getCost() - amount
              << " cents" << endl;
        cin >> amount2;
        amount = amount + amount2;
    }

    if (amount >= product.getCost())
    {
        pCounter.acceptAmount(amount);
        product.makeSale();
        cout << "Collect your item at the bottom and "
              << "enjoy." << endl;
    }
    else
        cout << "The amount is not enough. "
              << "Collect what you deposited." << endl;

    cout << "*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*"
          << endl << endl;
}
else
    cout << "Sorry, this item is sold out." << endl;
} //end sellProduct

```

Now that we have described the functions `showSelection` and `sellProduct`, the function `main` is described next.

main The algorithm for the function `main` is as follows:

1. Create the cash register—that is, declare an object of type `cashRegister`.
2. Create four dispensers—that is, declare four objects of type `dispenserType` and initialize these objects. For example, the statement:

```
dispenserType candy(100, 50);
```

creates a dispenser object, `candy`, to hold the candies. The number of items in the dispenser is 100, and the cost of an item is 50 cents.

3. Declare additional variables as necessary.
4. Show the selection; call the function `showSelection`.
5. Get the selection.
6. While not done (a selection of 9 exits the program),
 - a. Sell the product; call the function `sellProduct`.
 - b. Show the selection; call the function `showSelection`.
 - c. Get the selection.

The definition of the function `main` is as follows:

```
int main()
{
    cashRegister counter;
    dispenserType candy(100, 50);
    dispenserType chips(100, 65);
    dispenserType gum(75, 45);
    dispenserType cookies(100, 85);

    int choice; //variable to hold the selection

    showSelection();
    cin >> choice;

    while (choice != 9)
    {
        switch (choice)
        {
            case 1:
                sellProduct(candy, counter);
                break;
            case 2:
                sellProduct(chips, counter);
                break;
            case 3:
                sellProduct(gum, counter);
                break;
            case 4:
                sellProduct(cookies, counter);
                break;
            default :
                cout << "Invalid selection." << endl;
        } //end switch

        showSelection();
        cin >> choice;
    } //end while

    return 0;
} //end main
```

COMPLETE PROGRAM LISTING

In the previous sections, we designed the classes to implement cash registers and dispensers to implement a candy machine. In this section, for the sake of completeness, we give complete definitions of the classes, the implementation file, and the user program to implement a candy machine.

```

//*****
// Author: D.S. Malik
//
// class cashRegister
// This class specifies the members to implement a cash
// register.
//*****

class cashRegister
{
public:
    int getCurrentBalance() const;
        //Function to show the current amount in the cash
        //register.
        //Postcondition: The value of cashOnHand is returned.

    void acceptAmount(int amountIn);
        //Function to receive the amount deposited by
        //the customer and update the amount in the register.
        //Postcondition: cashOnHand = cashOnHand + amountIn;

    cashRegister(int cashIn = 500);
        //Constructor
        //Sets the cash in the register to a specific amount.
        //Postcondition: cashOnHand = cashIn;
        //
        //      If no value is specified when the
        //      object is declared, the default value
        //      assigned to cashOnHand is 500.

private:
    int cashOnHand;    //variable to store the cash
                      //in the register
};

//*****
// Author: D.S. Malik
//
// class dispenserType
// This class specifies the members to implement a dispenser.
//*****

class dispenserType
{
public:
    int getNoOfItems() const;
        //Function to show the number of items in the machine.
        //Postcondition: The value of numberOfItems is returned.

    int getCost() const;
        //Function to show the cost of the item.
        //Postcondition: The value of cost is returned.

    void makeSale();
        //Function to reduce the number of items by 1.
        //Postcondition: numberOfItems--;

```

```

        dispenserType(int setNoOfItems = 50, int setCost = 50);
        //Constructor
        //Sets the cost and number of items in the dispenser
        //to the values specified by the user.
        //Postcondition: numberOfItems = setNoOfItems;
        //      cost = setCost;
        //      If no value is specified for a
        //      parameter, then its default value is
        //      assigned to the corresponding member
        //      variable.

private:
    int numberOfItems;    //variable to store the number of
                          //items in the dispenser
    int cost;    //variable to store the cost of an item
};

//*****
// Author: D.S. Malik
//
// Implementation file candyMachineImp.cpp
// This file contains the definitions of the functions to
// implement the operations of the classes cashRegister and
// dispenserType.
//*****

#include <iostream>
#include "candyMachine.h"

using namespace std;

int cashRegister::getCurrentBalance() const
{
    return cashOnHand;
}

void cashRegister::acceptAmount(int amountIn)
{
    cashOnHand = cashOnHand + amountIn;
}

cashRegister::cashRegister(int cashIn)
{
    if (cashIn >= 0)
        cashOnHand = cashIn;
    else
        cashOnHand = 500;
}

int dispenserType::getNoOfItems() const
{
    return numberOfItems;
}

```

```

int dispenserType::getCost() const
{
    return cost;
}

void dispenserType::makeSale()
{
    numberOfItems--;
}

dispenserType::dispenserType(int setNoOfItems, int setCost)
{
    if (setNoOfItems >= 0)
        numberOfItems = setNoOfItems;
    else
        numberOfItems = 50;

    if (setCost >= 0)
        cost = setCost;
    else
        cost = 50;
}

```

```

Main //*****
Program // Author: D.S. Malik
//
// This program uses the classes cashRegister and
// dispenserType to implement a candy machine.
// *****

#include <iostream>
#include "candyMachine.h"

using namespace std;

void showSelection();
void sellProduct(dispenserType& product,
                cashRegister& pCounter);

int main()
{
    cashRegister counter;
    dispenserType candy(100, 50);
    dispenserType chips(100, 65);
    dispenserType gum(75, 45);
    dispenserType cookies(100, 85);

    int choice; //variable to hold the selection

    showSelection();
    cin >> choice;

    while (choice != 9)
    {
        switch (choice)

```

```

    {
        case 1:
            sellProduct(candy, counter);
            break;
        case 2:
            sellProduct(chips, counter);
            break;
        case 3:
            sellProduct(gum, counter);
            break;
        case 4:
            sellProduct(cookies, counter);
            break;
        default:
            cout << "Invalid selection." << endl;
    } //end switch
    showSelection();
    cin >> choice;
} //end while

return 0;
} //end main

void showSelection()
{
    cout << "*** Welcome to Shelly's Candy Shop ***" << endl;
    cout << "To select an item, enter " << endl;
    cout << "1 for Candy" << endl;
    cout << "2 for Chips" << endl;
    cout << "3 for Gum" << endl;
    cout << "4 for Cookies" << endl;
    cout << "9 to exit" << endl;
} //end showSelection

void sellProduct(dispenserType& product,
                 cashRegister& pCounter)
{
    int amount; //variable to hold the amount entered
    int amount2; //variable to hold the extra amount needed

    if (product.getNoOfItems() > 0) //if the dispenser is not
                                    //empty
    {
        cout << "Please deposit " << product.getCost()
              << " cents" << endl;
        cin >> amount;

        if (amount < product.getCost())
        {
            cout << "Please deposit another "
                  << product.getCost() - amount
                  << " cents" << endl;
            cin >> amount2;
            amount = amount + amount2;
        }
    }
}

```

```

        if (amount >= product.getCost())
        {
            pCounter.acceptAmount(amount);
            product.makeSale();
            cout << "Collect your item at the bottom and "
                  << "enjoy." << endl;
        }
        else
            cout << "The amount is not enough. "
                  << "Collect what you deposited." << endl;

        cout << "*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*"
              << endl << endl;
    }
    else
        cout << "Sorry, this item is sold out." << endl;
} //end sellProduct

```

Sample Run: In this sample run, the user input is shaded.

```

*** Welcome to Shelly's Candy Shop ***
To select an item, enter
1 for Candy
2 for Chips
3 for Gum
4 for Cookies
9 to exit
1
Please deposit 50 cents
50
Collect your item at the bottom and enjoy.
*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*

*** Welcome to Shelly's Candy Shop ***
To select an item, enter
1 for Candy
2 for Chips
3 for Gum
4 for Cookies
9 to exit
9

```

NOTE

We placed the definitions of the `classes` `cashRegister` and `dispenserType` in the same header file `candyMachine.h`. However, you can also place the definitions of these classes in separate header files and include those header files in the files that use these classes, such as the implementation file of these classes and the file that contains the main program. Similarly, you can also create separate implementation files for these classes. The Web site accompanying this book contains these header and implementation files.

QUICK REVIEW

1. A **class** is a collection of a fixed number of components.
2. Components of a **class** are called the members of the class.
3. Members of a **class** are accessed by name.
4. In C++, **class** is a reserved word.
5. Members of a class are classified into one of three categories: **private**, **protected**, and **public**.
6. The **private** members of a class are not accessible outside of the class.
7. The **public** members of a class are accessible outside of the class.
8. By default, all members of a class are **private**.
9. The **public** members are declared using the member access specifier **public** and the colon, `:`.
10. The **private** members are declared using the member access specifier **private** and the colon, `:`.
11. A member of a class can be a function or a variable.
12. If any member of a class is a function, you usually use the function prototype to declare it.
13. If any member of a class is a variable, it is declared like any other variable.
14. In the definition of a class, you cannot initialize a variable when you declare it.
15. In the Unified Modeling Language (UML) diagram of a class, the top box contains the name of the class. The middle box contains the member variables and their data types. The last box contains the member function name, parameter list, and the return type of the function. A + (plus) sign in front of a member indicates that this member is a **public** member. A - (minus) sign preceding a member indicates that this is a **private** member. The symbol # before the member name indicates that the member is a **protected** member.
16. In C++, a **class** is a definition. No memory is allocated for the **class** itself; memory is allocated for the class variables when you declare them.
17. In C++, class variables are called class objects or class instances or, simply, objects.
18. A class member is accessed using the class variable name, followed by the dot operator (`.`), followed by the member name.
19. The only built-in operations on classes are the assignment and member selection.
20. As parameters to functions, classes can be passed either by value or by reference.
21. A function can return a value of type **class**.
22. Any program (or software) that uses a class is called a client of the class.

- 23. A member function of a class that only accesses (that is, does not modify) the value(s) of the member variable(s) is called an accessor function.
- 24. A member function of a class that modifies the value(s) of the member variable(s) is called a mutator function.
- 25. A member function of a class is called a constant function if its heading contains the reserved word `const` at the end. Moreover, a constant member function of a class cannot modify the member variables of the class.
- 26. A constant member function of a class can only call the other constant member functions of the class.
- 27. Constructors guarantee that the member variables are initialized when an object is declared.
- 28. The name of a constructor is the same as the name of the class.
- 29. A class can have more than one constructor.
- 30. A constructor without parameters is called the default constructor.
- 31. Constructors automatically execute when a class object enters its scope.
- 32. Destructors automatically execute when a class object goes out of scope.
- 33. A class can have only one destructor, and the destructor has no parameters.
- 34. The name of a destructor is the tilde (~), followed by the class name (no spaces in between).
- 35. Constructors and destructors are functions without any type; that is, they are neither value-returning nor void. As a result, they cannot be called like other functions.
- 36. A data type that separates the logical properties from the implementation details is called an abstract data type (ADT).
- 37. Classes were specifically designed in C++ to handle ADTs.
- 38. To implement an ADT, you must represent the data and write related algorithms to implement the operations.
- 39. A precondition is a statement specifying the condition(s) that must be true before the function is called.
- 40. A postcondition is a statement specifying what is true after the function call is completed.
- 41. A `public static` member, function or variable, of a class can be accessed using the class name and the scope resolution operator.
- 42. For each `static` variable of a class, C++ allocates only one memory space. All objects of the class refer to the same memory space.
- 43. `static` member variables of a class exist even when no object of the `class` type exists.
- 44. Non-`static` member variables of a class are called the instance variables of the class.

EXERCISES

1. Mark the following statements as true or false.
 - a. The member variables of a class must be of the same type.
 - b. The member functions of a class must be `public`.
 - c. A class can have more than one constructor.
 - d. A class can have more than one destructor.
 - e. Both constructors and destructors can have parameters.
2. Find the syntax errors in the definitions of the following classes.

- a.

```
class AA
{
public:
    void print() const;
    int sum();
    AA();
    int AA(int, int);
private:
    int x;
    int y;
};
```
- b.

```
class BB
{
    int one;
    int two;
public:
    bool equal() const;
    print();
    BB(int, int);
}
```
- c.

```
class CC
{
public:
    void set(int, int);
    void print() const;
    CC();
    CC(int, int);
    bool CC(int, int);
private:
    int u;
    int v;
};
```

3. Consider the following declarations:

```
class xClass
{
public:
    void func();
    void print() const ;
```

```

    xClass ();
    xClass (int, double);
private:
    int u;
    double w;
};

```

and assume that the following statement is in a user program:

```
xClass x;
```

- a. How many members does `class xClass` have?
 - b. How many `private` members does `class xClass` have?
 - c. How many constructors does `class xClass` have?
 - d. Write the definition of the member function `func` so that `u` is set to 10 and `w` is set to 15.3.
 - e. Write the definition of the member function `print` that prints the contents of `u` and `w`.
 - f. Write the definition of the default constructor of the `class xClass` so that the `private` member variables are initialized to 0.
 - g. Write a C++ statement that prints the values of the member variables of the object `x`.
 - h. Write a C++ statement that declares an object `t` of type `xClass` and initializes the member variables of `t` to 20 and 35.0, respectively.
4. Consider the definition of the following class:

```

class CC
{
public :
    CC(); //Line 1
    CC(int); //Line 2
    CC(int, int); //Line 3
    CC(double, int); //Line 4
    .
    .
    .
private:
    int u;
    double v;
};

```

- a. Give the line number containing the constructor that is executed in each of the following declarations.
 - i. `CC one;`
 - ii. `CC two(5, 6);`
 - iii. `CC three(3.5, 8);`

- b. Write the definition of the constructor in Line 1 so that the **private** member variables are initialized to 0.
 - c. Write the definition of the constructor in Line 2 so that the **private** member variable `u` is initialized according to the value of the parameter, and the **private** member variable `v` is initialized to 0.
 - d. Write the definition of the constructors in Lines 3 and 4 so that the **private** member variables are initialized according to the values of the parameters.
5. Consider the definition of the following **class**:

```
class testClass
{
public:
    int sum();
    //Returns the sum of the private member variables
    void print() const;
    //Prints the values of the private member variables
    testClass();
    //Default constructor
    //Initializes the private member variables to 0
    testClass(int a, int b);
    //Constructors with parameters
    //initializes the private member variables to the values
    //specified by the parameters
    //Postcondition: x = a; y = b;
private:
    int x;
    int y;
};
```

- a. Write the definitions of the member functions as described in the definition of the **class** `testClass`.
 - b. Write a test program to test the various operations of the **class** `testClass`.
6. Given the definition of the **class** `clockType` with constructors (as described in this chapter), what is the output of the following C++ code?

```
clockType clock1;
clockType clock2(23, 13, 75);

clock1.printTime();
cout << endl;
clock2.printTime();
cout << endl;

clock1.setTime(6, 59, 39);
clock1.printTime();
cout << endl;

clock1.incrementMinutes();
clock1.printTime();
cout << endl;
```

```

clock1.setTime(0, 13, 0);

if (clock1.equalTime(clock2))
    cout << "Clock1 time is the same as clock2 time."
        << endl;
else
    cout << "The two times are different." << endl;

```

7. Assume the definition of the `class` `personType` as given in this chapter.
 - a. Write a C++ statement that declares `student` to be a `personType` object, and initialize its first name to "Buddy" and last name to "Arora".
 - b. Write a C++ statement that outputs the data stored in the object `student`.
 - c. Write C++ statements that change the first name of `student` to "Susan" and the last name to "Gilbert".
8. Explain why you would need both `public` and `private` members in a class.
9. What is a constructor? Why would you include a constructor in a class.?
10. Which of the following characters appears before a destructor's name?
 - a. # b. ! c. ~ d. \$
11. What is a destructor and what is its purpose?
12. Write the definition of a class that has the following properties:
 - a. The name of the `class` is `secretType`.
 - b. The `class` `secretType` has four member variables: `name` of type `string`, `age` and `weight` of type `int`, and `height` of type `double`.
 - c. The `class` `secretType` has the following member functions. (Make each accessor function constant.)

`print`—outputs the data stored in the member variables with the appropriate titles

`setName`—function to set the name

`setAge`—function to set the age

`setWeight`—function to set the weight

`setHeight`—function to set the height

`getName`—value-returning function to return the name

`getAge`—value-returning function to return the age

`getWeight`—value-returning function to return the weight

`getHeight`—value-returning function to return the height

constructor—with default parameters: The default value of `name` is the empty string " ", and the default values of `age`, `weight`, and `height` are 0.
 - d. Write the definition of the member functions of the `class` `secretType`, as described in Part c.

13. Consider the following definition of the `class` `myClass`:

```
class myClass
{
public:
    void setX(int a);
        //Function to set the value of x.
        //Postcondition: x = a;
    void printX() const;
        //Function to output x.
    static void printCount();
        //Function to output count.
    static void incrementCount();
        //Function to increment count.
        //Postcondition: count++;
    myClass(int a = 0);
        //constructor with default parameters
        //Postcondition x = a;
        //If no value is specified for a, x = 0;

private:
    int x;
    static int count;
};
```

- a. Write a C++ statement that initializes the member variable `count` to 0.
- b. Write a C++ statement that increments the value of `count` by 1.
- c. Write a C++ statement that outputs the value of `count`.
- d. Write the definitions of the functions of the `class` `myClass` as described in its definition.
- e. Write a C++ statement that declares `myObject1` to be a `myClass` object and initializes its member variable `x` to 5.
- f. Write a C++ statement that declares `myObject2` to be a `myClass` object and initializes its member variable `x` to 7.
- g. Which of the following statements are valid? (Assume that `myObject1` and `myObject2` are as declared in Parts e and f.)

```
myObject1.printCount();    //Line 1
myObject1.printX();        //Line 2
myClass.printCount();      //Line 3
myClass.printX();          //Line 4
myClass::count++;          //Line 5
```

- h. Assume that `myObject1` and `myObject2` are as declared in Parts e and f. What is the output of the following C++ code?

```
myObject1.printX();
cout << endl;
myObject1.incrementCount();
```

```

myClass::incrementCount();
myObject1.printCount();
cout << endl;
myObject2.printCount();
cout << endl;
myObject2.printX();
cout << endl;
myObject1.setX(14);
myObject1.incrementCount();
myObject1.printX();
cout << endl;
myObject1.printCount();
cout << endl;
myObject2.printCount();
cout << endl;

```

14. In Example 12-8, we designed the `class die`. Using this class, declare an array named `rolls`, of 100 components of type `die`. Write C++ statements to roll each die of the array `rolls`, find and output the highest number rolled and the number of times this number was rolled, and find and output the number that is rolled the maximum number of times together with its count. Also write a program to test your statements.

PROGRAMMING EXERCISES

1. Write a program that converts a number entered in Roman numerals to decimal. Your program should consist of a `class`, say, `romanType`. An object of type `romanType` should do the following:
 - a. Store the number as a Roman numeral.
 - b. Convert and store the number into decimal form.
 - c. Print the number as a Roman numeral or decimal number as requested by the user.

The decimal values of the Roman numerals are:

| | |
|---|------|
| M | 1000 |
| D | 500 |
| C | 100 |
| L | 50 |
| X | 10 |
| V | 5 |
| I | 1 |

- d. Test your program using the following Roman numerals: `MCXIV`, `CCCLIX`, `MDCLXVI`.

2. Design and implement a `class dayType` that implements the day of the week in a program. The `class dayType` should store the day, such as `Sun` for Sunday. The program should be able to perform the following operations on an object of type `dayType`:
 - a. Set the day.
 - b. Print the day.
 - c. Return the day.
 - d. Return the next day.
 - e. Return the previous day.
 - f. Calculate and return the day by adding certain days to the current day. For example, if the current day is Monday and we add 4 days, the day to be returned is Friday. Similarly, if today is Tuesday and we add 13 days, the day to be returned is Monday.
 - g. Add the appropriate constructors.
3. Write the definitions of the functions to implement the operations for the `class dayType` as defined in Programming Exercise 2. Also, write a program to test various operations on this class.
4. This chapter defines the `class clockType` to implement time in a program. Add functions to this class so that a program that uses this class can set only the hours, minutes, or seconds and retrieve only the hours, minutes, or seconds. Also write a program to test your class.
5. Example 12-9 defined a `class personType` to store the name of a person. The member functions that we included merely print the name and set the name of a person. Redefine the `class personType` so that, in addition to what the existing `class` does, you can:
 - a. Set the first name only.
 - b. Set the last name only.
 - c. Store and set the middle name.
 - d. Check whether a given first name is the same as the first name of this person.
 - e. Check whether a given last name is the same as the last name of this person.

Write the definitions of the member functions to implement the operations for this class. Also, write a program to test various operations on this class.
6. a. Some of the characteristics of a book are the title, author(s), publisher, ISBN, price, and year of publication. Design a `class bookType` that defines the book as an ADT.
 - i. Each object of the `class bookType` can hold the following information about a book: title, up to four authors, publisher, ISBN, price, and number of copies in stock. To keep track of the number of authors, add another member variable.

- ii. Include the member functions to perform the various operations on objects of type `bookType`. For example, the usual operations that can be performed on the title are to show the title, set the title, and check whether a title is the same as the actual title of the book. Similarly, the typical operations that can be performed on the number of copies in stock are to show the number of copies in stock, set the number of copies in stock, update the number of copies in stock, and return the number of copies in stock. Add similar operations for the publisher, ISBN, book price, and authors. Add the appropriate constructors and a destructor (if one is needed).
 - b. Write the definitions of the member functions of the `class bookType`.
 - c. Write a program that uses the `class bookType` and tests various operations on the objects of the `class bookType`. Declare an array of 100 components of type `bookType`. Some of the operations that you should perform are to search for a book by its title, search by ISBN, and update the number of copies of a book.
7. In this exercise, you will design a `class memberType`.
- a. Each object of `memberType` can hold the name of a person, member ID, number of books bought, and amount spent.
 - b. Include the member functions to perform the various operations on the objects of `memberType`—for example, modify, set, and show a person's name. Similarly, update, modify, and show the number of books bought and the amount spent.
 - c. Add the appropriate constructors.
 - d. Write the definitions of the member functions of `memberType`.
 - e. Write a program to test various operations of your `class memberType`.
8. Using the classes designed in Programming Exercises 6 and 7, write a program to simulate a bookstore. The bookstore has two types of customers: those who are members of the bookstore and those who buy books from the bookstore only occasionally. Each member has to pay a \$10 yearly membership fee and receives a 5% discount on each book purchased. For each member, the bookstore keeps track of the number of books purchased and the total amount spent. For every eleventh book that a member buys, the bookstore takes the average of the total amount of the last 10 books purchased, applies this amount as a discount, and then resets the total amount spent to 0. Write a program that can process up to 1000 book titles and 500 members. Your program should contain a menu that gives the user different choices to effectively run the program; in other words, your program should be user driven.
9. The method `sellProduct` of the Candy Machine programming example gives the user only two chances to enter enough money to buy the product.

Rewrite the definition of the method `sellProduct` so that it keeps prompting the user to enter more money as long as the user has not entered enough money to buy the product. Also, write a program to test your method.

10. Write the definition of a `class`, `swimmingPool`, to implement the properties of a swimming pool. Your class should have the instance variables to store the length (in feet), width (in feet), depth (in feet), the rate (in gallons per minute) at which the water is filling the pool, and the rate (in gallons per minute) at which the water is draining from the pool. Add appropriate constructors to initialize the instance variables. Also add member functions to do the following: determine the amount of water needed to fill an empty or partially filled pool; determine the time needed to completely or partially fill or empty the pool; add or drain water for a specific amount of time.
11. (Tic-Tac-Toe) Write a program that allows two players to play the tic-tac-toe game. Your program must contain the `class` `ticTacToe` to implement a `ticTacToe` object. Include a 3-by-3 two-dimensional array, as a `private` member variable, to create the board. If needed, include additional member variables. Some of the operations on a `ticTacToe` object are printing the current board, getting a move, checking if a move is valid, and determining the winner after each move. Add additional operations as needed.
12. The equation of a line in standard form is $ax + by = c$, wherein both a and b cannot be zero, and a , b , and c are real numbers. If $b \neq 0$, then $-a/b$ is the slope of the line. If $a = 0$, then it is a horizontal line, and if $b = 0$, then it is a vertical line. The slope of a vertical line is undefined. Two lines are parallel if they have the same slope or both are vertical lines. Two lines are perpendicular if either one of the lines is horizontal and the other is vertical or the product of their slopes is -1 . Design the `class` `lineType` to store a line. To store a line, you need to store the values of a (coefficient of x), b (coefficient of y), and c . Your class must contain the following operations.
 - a. If a line is nonvertical, then determine its slope.
 - b. Determine if two lines are equal. (Two lines $a_1x + b_1y = c_1$ and $a_2x + b_2y = c_2$ are equal if either $a_1 = a_2$, $b_1 = b_2$, and $c_1 = c_2$ or $a_1 = ka_2$, $b_1 = kb_2$, and $c_1 = kc_2$ for some real number k .)
 - c. Determine if two lines are parallel.
 - d. Determine if two lines are perpendicular.
 - e. If two lines are not parallel, then find the point of intersection.

Add appropriate constructors to initialize variables of `lineType`. Also write a program to test your class.

13. Typically, everyone saves money periodically for retirement, buying a house, or for some other purposes. If you are saving money for retirement, then the money you put in a retirement fund is tax sheltered, and the employer also makes some contribution into your retirement fund. In this exercise, for simplicity, we assume that the money is put into an account that pays a fixed interest rate, and money is deposited into the account at the end of the specified period. Suppose that a person deposits R dollars m times a year into an account that pays $r\%$ interest compounded m times a year for t years. Then the total accumulated at the end of t years is given by $R \left[\frac{(1+r/m)^{mt} - 1}{r/m} \right]$. For example, suppose that you deposit \$500 at the end of each month into an account that pays 4.8% interest per year compounded monthly for 25 years. Then the total money accumulated into the account is $500[(1 + 0.048/12)^{300} - 1]/(0.048/12) = \$289,022.42$.

On the other hand, suppose that you want to accumulate S dollars in t years and would like to know how much money, m times a year, you should deposit into an account that pays $r\%$ interest compounded m times a year. The periodic payment is given by the formula $\frac{s(r/m)}{(1+r/m)^{mt} - 1}$.

Design a class that uses the above formulas to determine the total accumulated into an account and the periodic deposits to accumulate a specific amount. Your class should have instance variables to store the periodic deposit, the value of m , the interest rate, and the number of years the money will be saved. Add appropriate constructors to initialize instance variable, functions to set the values of the instance variables, functions to retrieve the values of the instance variables, and functions to do the necessary calculations and output results.



13

CHAPTER

INHERITANCE AND COMPOSITION

IN THIS CHAPTER, YOU WILL:

- Learn about inheritance
- Learn about derived and base classes
- Explore how to redefine the member functions of a base class
- Examine how the constructors of base and derived classes work
- Learn how to construct the header file of a derived class
- Explore three types of inheritance: `public`, `protected`, and `private`
- Learn about composition (aggregation)
- Become familiar with the three basic principles of object-oriented design

Chapter 12 introduced classes, abstract data types (ADT), and ways to implement ADT in C++. By using classes, you can combine data and operations in a single unit. An object, therefore, becomes a self-contained entity. Operations can directly access the data, but the internal state of an object cannot be manipulated directly.

In addition to implementing ADT, classes have other features. For instance, classes can create new classes from existing classes. This important feature encourages code reuse. In C++, you can relate two or more classes in more than one way. Two common ways to relate classes in a meaningful way are:

- **Inheritance** (“is-a” relationship)
- **Composition (aggregation)** (“has-a” relationship)

Inheritance

Suppose that you want to design a **class**, `partTimeEmployee`, to implement and process the characteristics of a part-time employee. The main features associated with a part-time employee are the name, pay rate, and number of hours worked. In Example 12-9 (in Chapter 12), we designed a class to implement a person’s name. Every part-time employee is a person. Therefore, rather than design the **class** `partTimeEmployee` from scratch, we want to be able to extend the definition of the **class** `personType` (from Example 12-9) by adding additional members (data and/or functions).

Of course, we do not want to make the necessary changes directly to the **class** `personType`—that is, edit the **class** `personType` and add and/or delete members. In fact, we want to create the **class** `partTimeEmployee` without making any physical changes to the **class** `personType` by adding only the members that are necessary. For example, because the **class** `personType` already has members to store the first name and last name, we will not include any such members in the **class** `partTimeEmployee`. In fact, these member variables will be inherited from the **class** `personType`. (We will design such a **class** in Example 13-3.)

In Chapter 12, we extensively studied and designed the **class** `clockType` to implement the time of day in a program. The **class** `clockType` has three member variables to store the hours, minutes, and seconds. Certain applications, in addition to the hours, minutes, and seconds, might also require us to store the time zone. In this case, we would like to extend the definition of the **class** `clockType` and create a **class**, `extClockType`, to accommodate this new information. That is, we want to derive the **class** `extClockType` by adding a member variable—say, `timeZone`—and the necessary member functions to manipulate the time (see Programming Exercise 1 at the end of this chapter). In C++, the mechanism that allows us to accomplish this task is the principle of inheritance. Inheritance is an “is-a” relationship; for instance, “every employee is a person.”

Inheritance lets us create new classes from existing classes. The new classes that we create from the existing classes are called the **derived classes**; the existing classes are called the

base classes. The derived classes inherit the properties of the base classes. So rather than create completely new classes from scratch, we can take advantage of inheritance and reduce software complexity.

Each derived class, in turn, becomes a base class for a future derived class. Inheritance can be either single inheritance or multiple inheritance. In **single inheritance**, the derived class is derived from a single base class; in **multiple inheritance**, the derived class is derived from more than one base class. This chapter concentrates on single inheritance.

Inheritance can be viewed as a tree-like, or hierarchical, structure wherein a base class is shown with its derived classes. Consider the tree diagram shown in Figure 13-1.




FIGURE 13-1 Inheritance hierarchy

In this diagram, **shape** is the base class. The **classes** **circle** and **rectangle** are derived from **shape**, and the **class** **square** is derived from **rectangle**. Every **circle** and every **rectangle** is a **shape**. Every **square** is a **rectangle**.

The general syntax of a derived class is:

```
class className: memberAccessSpecifier baseClassName
{
    member list
};
```

in which **memberAccessSpecifier** is **public**, **protected**, or **private**. When no **memberAccessSpecifier** is specified, it is assumed to be a **private** inheritance. (We discuss **protected** inheritance later in this chapter.)

EXAMPLE 13-1

Suppose that we have defined a class called `shape`. The following statements specify that the `class circle` is derived from `shape`, and it is a `public` inheritance.

```
class circle: public shape
{
    .
    .
    .
};
```

On the other hand, consider the following definition of the `class circle`:

```
class circle: private shape
{
    .
    .
    .
};
```

This is a `private` inheritance. In this definition, the `public` members of `shape` become `private` members of the `class circle`. So any object of type `circle` cannot directly access these members. The previous definition of `circle` is equivalent to:

```
class circle: shape
{
    .
    .
    .
};
```

That is, if we do not use either the `memberAccessSpecifier` `public` or `private`, the `public` members of a base class are inherited as `private` members.

The following facts about the base and the derived classes should be kept in mind.

1. The `private` members of a base class are `private` to the base class; hence, the members of the derived class cannot directly access them. In other words, when you write the definitions of the member functions of the derived class, you cannot directly access the `private` members of the base class.
2. The `public` members of a base class can be inherited either as `public` members or as `private` members by the derived class. That is, the `public` members of the base class can become either `public` or `private` members of the derived class.
3. The derived class can include additional members—data and/or functions.

4. The derived class can redefine the **public** member functions of the base class. That is, in the derived class, you can have a member function with the same name, number, and types of parameters as a function in the base class. However, this redefinition applies only to the objects of the derived class, not to the objects of the base class.
5. All member variables of the base class are also member variables of the derived class. Similarly, the member functions of the base class (unless redefined) are also member functions of the derived class. (Remember Rule 1 when accessing a member of the base class in the derived class.)

The next sections describe two important issues related to inheritance. The first issue is the redefinition of the member functions of the base class in the derived class. While discussing this issue, we will also address how to access the **private** (data) members of the base class in the derived class. The second key inheritance issue is related to the constructor. The constructor of a derived class cannot *directly* access the **private** member variables of the base class. Thus, we need to ensure that the **private** member variables that are inherited from the base class are initialized when a constructor of the derived class executes.

Redefining (Overriding) Member Functions of the Base Class

Suppose that a **class** `derivedClass` is derived from the **class** `baseClass`. Further assume that both `derivedClass` and `baseClass` have some member variables. It then follows that the member variables of the **class** `derivedClass` are its own member variables, together with the member variables of `baseClass`. Suppose that `baseClass` contains a function, `print`, that prints the values of the member variables of `baseClass`. Now `derivedClass` contains member variables in addition to the member variables inherited from `baseClass`. Suppose that you want to include a function that prints the values of the member variables of `derivedClass`. You can give any name to this function. However, in the **class** `derivedClass`, you can also name this function as `print` (the same name used by `baseClass`). This is called redefining (or overriding) the member function of the base class. Next, we illustrate how to redefine the member functions of a base class with the help of an example.

NOTE

To redefine a **public** member function of a base class in the derived class, the corresponding function in the derived class must have the same name, number, and types of parameters. In other words, the name of the function being redefined in the derived class must have the same name and the same set of parameters. If the corresponding functions in the base class and the derived class have the same name but different sets of parameters, then this is function overloading in the derived class, which is also allowed.

Consider the definition of the following class:

```
class rectangleType
{
public:
    void setDimension(double l, double w);
        //Function to set the length and width of the rectangle.
        //Postcondition: length = l; width = w;

    double getLength() const;
        //Function to return the length of the rectangle.
        //Postcondition: The value of length is returned.

    double getWidth() const;
        //Function to return the width of the rectangle.
        //Postcondition: The value of width is returned.

    double area() const;
        //Function to return the area of the rectangle.
        //Postcondition: The area of the rectangle is
        //                  calculated and returned.

    double perimeter() const;
        //Function to return the perimeter of the rectangle.
        //Postcondition: The perimeter of the rectangle is
        //                  calculated and returned.

    void print() const;
        //Function to output the length and width of
        //the rectangle.

    rectangleType();
        //Default constructor
        //Postcondition: length = 0; width = 0;

    rectangleType(double l, double w);
        //Constructor with parameters
        //Postcondition: length = l; width = w;

private:
    double length;
    double width;
};
```

Figure 13-2 shows the UML class diagram of the `class` `rectangleType`.




FIGURE 13-2 UML class diagram of the `class` `rectangleType`

The `class` `rectangleType` has 10 members.

Suppose that the definitions of the member functions of the `class` `rectangleType` are as follows:

```

void rectangleType::setDimension(double l, double w)
{
    if (l >= 0)
        length = l;
    else
        length = 0;

    if (w >= 0)
        width = w;
    else
        width = 0;
}

double rectangleType::getLength() const
{
    return length;
}

double rectangleType::getWidth() const
{
    return width;
}

double rectangleType::area() const
{
    return length * width;
}
  
```

```

double rectangleType::perimeter() const
{
    return 2 * (length + width);
}

void rectangleType::print() const
{
    cout << "Length = " << length
          << "; Width = " << width;
}

rectangleType::rectangleType(double l, double w)
{
    setDimension(l, w);
}

rectangleType::rectangleType()
{
    length = 0;
    width = 0;
}

```

Now consider the definition of the following `class` `boxType`, derived from the `class` `rectangleType`:

```

class boxType: public rectangleType
{
public:
    void setDimension(double l, double w, double h);
        //Function to set the length, width, and height
        //of the box.
        //Postcondition: length = l; width = w; height = h;

    double getHeight() const;
        //Function to return the height of the box.
        //Postcondition: The value of height is returned.

    double area() const;
        //Function to return the surface area of the box.
        //Postcondition: The surface area of the box is
        //                  calculated and returned.

    double volume() const;
        //Function to return the volume of the box.
        //Postcondition: The volume of the box is
        //                  calculated and returned.

    void print() const;
        //Function to output the length, width, and height of a box.

    boxType();
        //Default constructor
        //Postcondition: length = 0; width = 0; height = 0;
}

```

```

boxType(double l, double w, double h);
    //Constructor with parameters
    //Postcondition: length = l; width = w; height = h;

private:
    double height;
};

```

Figure 13-3 shows the UML class diagram of the **class** `boxType` and the inheritance hierarchy.




FIGURE 13-3 UML class diagram of the **class** `boxType` and the inheritance hierarchy

From the definition of the **class** `boxType`, it is clear that the **class** `boxType` is derived from the **class** `rectangleType`, and it is a **public** inheritance. Therefore, all **public** members of the **class** `rectangleType` are **public** members of the **class** `boxType`. The **class** `boxType` also overrides (redefines) the functions `print` and `area`.

In general, while writing the definitions of the member functions of a derived class to specify a call to a **public** member function of the base class, we do the following:

- If the derived class overrides a **public** member function of the base class, then to specify a call to that **public** member function of the base class, you use the name of the base class, followed by the scope resolution operator, `::`, followed by the function name with the appropriate parameter list.
- If the derived class does not override a **public** member function of the base class, you may specify a call to that **public** member function by using the name of the function and the appropriate parameter list. (See the following note for member functions of the base class that are overloaded in the derived class.)

NOTE

If a derived class *overloads* a **public** member function of the base class, then while writing the definition of a member function of the derived class, to specify a call to that (overloaded) member function of the base class, you might need (depending on the compiler) to use the name of the base class, followed by the scope resolution operator, `::`, followed by the function name with the appropriate parameter list. For example, the **class** `boxType` overloads the member function `setDimension` of the **class** `rectangleType`. (See the definition of the function `setDimension` of the **class** `boxType`, given later in this section.)

Next, let us write the definition of the member function `print` of the **class** `boxType`.

The **class** `boxType` has three member variables: `length`, `width`, and `height`. The member function `print` of the **class** `boxType` prints the values of these member variables. To write the definition of the function `print` of the **class** `boxType`, keep in mind the following:

- The member variables `length` and `width` are **private** members of the **class** `rectangleType`, so they cannot be directly accessed in the **class** `boxType`. Therefore, when writing the definition of the function `print` of the **class** `boxType`, we cannot access `length` and `width` directly.
- The member variables `length` and `width` of the **class** `rectangleType` are accessible in the **class** `boxType` through the **public** member functions of the **class** `rectangleType`. Therefore, when writing the definition of the member function `print` of the **class** `boxType`, we first call the member function `print` of the **class** `rectangleType` to print the values of `length` and `width`. After printing the values of `length` and `width`, we output the values of `height`.

To call the member function `print` of `rectangleType` in the definition of the member function `print` of `boxType`, we must use the following statement:

```
rectangleType::print();
```

This statement ensures that we call the member function `print` of the base **class** `rectangleType`, not of the **class** `boxType`.

The definition of the member function `print` of the **class** `boxType` is:

```
void boxType::print() const
{
    rectangleType::print();
    cout << " Height = " << height;
}
```

Let us write the definitions of the remaining member functions of the **class** `boxType`.

The definition of the function `setDimension` is:

```
void boxType::setDimension(double l, double w, double h)
{
    rectangleType::setDimension(l, w);

    if (h >= 0)
        height = h;
    else
        height = 0;
}
```

Notice that in the preceding definition of the function `setDimension`, a call to the member function `setDimension` of the `class` `rectangleType` is preceded by the name of the class and the scope resolution operator, even though the `class` `boxType` overloads—not overrides—the function `setDimension`.

The definition of the function `getHeight` is:

```
double boxType::getHeight() const
{
    return height;
}
```

The member function `area` of the `class` `boxType` determines the surface area of a box. To determine the surface area of a box, we need to access the length and width of the box, which are declared as `private` members of the `class` `rectangleType`. Therefore, we use the member functions `getLength` and `getWidth` of the `class` `rectangleType` to retrieve the length and width, respectively. Because the `class` `boxType` does not contain any member functions that have the names `getLength` or `getWidth`, we call these member functions of the `class` `rectangleType` without using the name of the base class.

```
double boxType::area() const
{
    return 2 * (getLength() * getWidth()
               + getLength() * height
               + getWidth() * height);
}
```

The member function `volume` of the `class` `boxType` determines the volume of a box. To determine the volume of a box, you multiply the length, width, and height of the box or multiply the area of the base of the box by its height. Let us write the definition of the member function `volume` by using the second alternative. To do this, you can use the member function `area` of the `class` `rectangleType` to determine the area of the base. Because the `class` `boxType` overrides the member function `area`, to specify a call to the member function `area` of the `class` `rectangleType`, we use the name of the base class and the scope resolution operator, as shown in the following definition:

```
double boxType::volume() const
{
    return rectangleType::area() * height;
}
```

In the next section, we discuss how to specify a call to the constructor of the base class when writing the definition of a constructor of the derived class.

Constructors of Derived and Base Classes

A derived class can have its own **private** member variables, so a derived class can explicitly include its own constructors. A constructor typically serves to initialize the member variables. When we declare a derived class object, this object inherits the members of the base class, but the derived class object cannot directly access the **private** (data) members of the base class. The same is true for the member functions of a derived class. That is, the member functions of a derived class cannot directly access the **private** members of the base class.

As a consequence, the constructors of a derived class can (directly) initialize only the (**public** data) members inherited from the base class of the derived class. Thus, when a derived class object is declared, it must also automatically execute one of the constructors of the base class. Because constructors cannot be called like other functions, the execution of a derived class's constructor must trigger the execution of one of the base class's constructors. This is, in fact, what happens. Furthermore, a call to the base class's constructor is specified in the *heading of the definition* of a derived class constructor.

In the preceding section, we defined the **class** `rectangleType` and derived the **class** `boxType` from it. Moreover, we illustrated how to override a member function of the **class** `rectangleType`. Let us now discuss how to write the definitions of the constructors of the **class** `boxType`.

The **class** `rectangleType` has two constructors and two member variables. The **class** `boxType` has three member variables: `length`, `width`, and `height`. The member variables `length` and `width` are inherited from the **class** `rectangleType`.

First, let us write the definition of the default constructor of the **class** `boxType`. Recall that, if a class contains the default constructor and no values are specified when the object is declared, the default constructor executes and initializes the object. Because the **class** `rectangleType` contains the default constructor, when writing the definition of the default constructor of the **class** `boxType`, we do not specify any constructor of the base class.

```
boxType::boxType()
{
    height = 0.0;
}
```

Next, we discuss how to write the definitions of constructors with parameters. To trigger the execution of a constructor (with parameters) of the base class, you specify the name of a constructor of the base class with the parameters in the heading of the definition of the constructor of the derived class.

Consider the following definition of the constructor with parameters of the **class** `boxType`:

```
boxType::boxType(double l, double w, double h)
    : rectangleType(l, w)
{
    if (h >= 0)
        height = h;
    else
        height = 0;
}
```

In this definition, we specify the constructor of `rectangleType` with two parameters. When this constructor of `boxType` executes, it triggers the execution of the constructor with two parameters of type `double` of the **class** `rectangleType`.

Consider the following statements:

```
rectangleType myRectangle(5.0, 3.0); //Line 1
boxType myBox(6.0, 5.0, 4.0);      //Line 2
```

The statement in Line 1 creates the `rectangleType` object `myRectangle`. Thus, the object `myRectangle` has two member variables: `length` and `width`. The statement in Line 2 creates the `boxType` object `myBox`. Thus, the object `myBox` has three member variables: `length`, `width`, and `height` (see Figure 13-4).




FIGURE 13-4 Objects `myRectangle` and `myBox`

Consider the following statements:

```
myRectangle.print(); //Line 3
cout << endl;       //Line 4
myBox.print();      //Line 5
cout << endl;       //Line 6
```

In the statement in Line 3, the member function `print` of the **class** `rectangleType` is executed. In the statement in Line 5, the function `print` associated with the **class** `boxType` is executed. Recall that, if a derived class overrides a member function of the base class, the redefinition applies only to the objects of the derived class. Thus, the output of the statement in Line 3 is:

```
Length = 5.0; Width = 3.0
```

The output of the statement in Line 5 is:

```
Length = 6.0; Width = 5.0; Height = 4.0
```

When the object `myBox` enters its scope, the constructors of the **classes** `rectangleType` and `boxType` execute. Note that the constructors of a base class are *not* inherited in a derived class. A call to a constructor of a base class is specified in the definition of a constructor of the derived class. When a derived class constructor executes, first a constructor of the base class executes to initialize the data members inherited from the base class, and then the constructor of the derived class executes to initialize the data members declared by the derived class. So first, the constructor of the **class** `rectangleType` executes to initialize the instance variables `length` and `width`, and then the constructor of the **class** `boxType` executes to initialize the instance variable `height`.

The program in Example 13-2 shows how the objects of a base class and a derived class behave.

EXAMPLE 13-2

Consider the following C++ program:

```
#include <iostream>
#include <iomanip>
#include "rectangleType.h"
#include "boxType.h"

using namespace std;

int main()
{
    rectangleType myRectangle1;                //Line 1
    rectangleType myRectangle2(8, 6);          //Line 2

    boxType myBox1;                            //Line 3
    boxType myBox2(10, 7, 3);                  //Line 4

    cout << fixed << showpoint << setprecision(2); //Line 5

    cout << "Line 6: myRectangle1: ";          //Line 6
    myRectangle1.print();                      //Line 7
    cout << endl;                             //Line 8
    cout << "Line 9: Area of myRectangle1: "
         << myRectangle1.area() << endl;       //Line 9

    cout << "Line 10: myRectangle2: ";         //Line 10
    myRectangle2.print();                     //Line 11
    cout << endl;                             //Line 12
    cout << "Line 13: Area of myRectangle2: "
         << myRectangle2.area() << endl;       //Line 13
```

```

    cout << "Line 14: myBox1: ";           //Line 14
    myBox1.print();                       //Line 15
    cout << endl;                         //Line 16
    cout << "Line 17: Surface Area of myBox1: "
          << myBox1.area() << endl;       //Line 17
    cout << "Line 18: Volume of myBox1: "
          << myBox1.volume() << endl;     //Line 18

    cout << "Line 19: myBox2: ";           //Line 19
    myBox2.print();                       //Line 20
    cout << endl;                         //Line 21
    cout << "Line 22: Surface Area of myBox2: "
          << myBox2.area() << endl;       //Line 22
    cout << "Line 23: Volume of myBox2: "
          << myBox2.volume() << endl;     //Line 23

    return 0;                             //Line 24
}

```

Sample Run:

```

Line 6: myRectangle1: Length = 0.00; Width = 0.00
Line 9: Area of myRectangle1: 0.00
Line 10: myRectangle2: Length = 8.00; Width = 6.00
Line 13: Area of myRectangle2: 48.00
Line 14: myBox1: Length = 0.00; Width = 0.00; Height = 0.00
Line 17: Surface Area of myBox1: 0.00
Line 18: Volume of myBox1: 0.00
Line 19: myBox2: Length = 10.00; Width = 7.00; Height = 3.00
Line 22: Surface Area of myBox2: 242.00
Line 23: Volume of myBox2: 210.00

```

The preceding program works as follows: The statement in Line 1 creates the `rectangleType` object `myRectangle1` and initializes its member variables to 0. The statement in Line 2 creates the `rectangleType` object `myRectangle2` and initializes its member variables `length` and `width` to 8.0 and 6.0, respectively.

The statement in Line 3 creates the `boxType` object `myBox1` and initializes its member variables to 0. The statement in Line 4 creates the `boxType` object `myBox2` and initializes its member variables `length`, `width`, and `height` to 10.0, 7.0, and 3.0, respectively.

The statement in Line 5 sets the output of the decimal number to two decimal places in a fixed decimal format with the decimal point and trailing zeros.

The statements in Lines 6 through 9 output the length, width, and area of `myRectangle1`. Because the member variables of `myRectangle1` are initialized to 0 by the default constructor, the area of the rectangle is 0 square units. See Line 9 in the sample run.

The statements in Lines 10 through 13 output the length, width, and area of `myRectangle2`. Because the member variables `length` and `width` of `myRectangle2` are initialized to 8.0 and 6.0, respectively, by the constructor with parameters, the area of this rectangle is 48.0 square units. See Line 13 in the sample run.

The statements in Lines 14 through 18 output the length, width, height, surface area, and volume of `myBox1`. Because the member variables of `myBox1` are initialized to 0 by the default constructor, the surface area of this box is 0.0 square units, and the volume is 0.0 cubic units. See Lines 17 and 18 in the sample run.

The statements in Lines 19 through 23 output the length, width, height, surface area, and volume of `myBox2`. Because the member variables `length`, `width`, and `height` of `myBox2` are initialized to 10.0, 7.0, and 3.0, respectively, by the constructor with parameters, the surface area of this box is 242.0 square units, and the volume is 210.0 cubic units. See Lines 22 and 23 in the sample run.

From the output of this program, it follows that the redefinition of the functions `print` and `area` in the `class` `boxType` applies only to an object of type `boxType`.

NOTE

(Constructors with default parameters and the inheritance hierarchy) Recall that a class can have a constructor with default parameters. Therefore, a derived class can also have a constructor with default parameters. For example, suppose that the definition of the `class` `rectangleType` is as shown below. (To save space, these definitions have no documentation.)

```
class rectangleType
{
public:
    void setDimension(double l, double w);
    double getLength() const;
    double getWidth() const;
    double area() const;
    double perimeter() const;
    void print() const;
    rectangleType(double l = 0, double w = 0);
    //Constructor with default parameters

private:
    double length;
    double width;
};
```

Suppose the definition of the constructor is:

```
rectangleType::rectangleType(double l, double w)
{
    setDimension(l, w);
}
```

Now suppose that the definition of the `class` `boxType` is:

```
class boxType: public rectangleType
{
public:
    void setDimension(double l, double w, double h);
    double getHeight() const;
    double area() const;
    double volume() const;
    void print() const;
    boxType(double l = 0, double w = 0, double h = 0);
    //Constructor with default parameters

private:
    double height;
};
```

You can write the definition of the constructor of the `class` `boxType` as follows:

```
boxType::boxType(double l, double w, double h)
    : rectangleType(l, w)
{
    if (h >= 0)
        height = h;
    else
        height = 0;
}
```

Notice that this definition also takes care of the default constructor of the `class` `boxType`.

NOTE

Suppose that a base `class`, `baseClass`, has *private* member variables and constructors. Further suppose that the `class` `derivedClass` is derived from `baseClass`, and `derivedClass` has no member variables. Therefore, the member variables of `derivedClass` are the ones inherited from `baseClass`. A constructor cannot be called like other functions, and the member variables of `baseClass` cannot be directly accessed by the member functions of `derivedClass`. To guarantee the initialization of the inherited member variables of an object of type `derivedClass`, even though `derivedClass` has no member variables, it must have the appropriate constructors. A constructor (with parameters) of `derivedClass` merely issues a call to a constructor (with parameters) of `baseClass`. Therefore, when you write the definition of the constructor (with parameters) of `derivedClass`, the heading of the definition of the constructor contains a call to an appropriate constructor (with parameters) of `baseClass`, and the body of the constructor is empty—that is, it contains only the opening and closing braces.

EXAMPLE 13-3

Suppose that you want to define a class to group the attributes of an employee. There are both full-time employees and part-time employees. Part-time employees are paid based on the number of hours worked and an hourly rate. Suppose that you want to define a class to keep track of a part-time employee's information, such as `name`, `pay rate`, and `hours worked`. You can then print the employee's name together with his or her wages. Because every employee is a person and Example 12-9 (Chapter 12) defined the `class` `personType` to store the first name and the last name together with the necessary operations on `name`, we can define a `class` `partTimeEmployee` based on the `class` `personType`. You can also redefine the `print` function to print the appropriate information.

```
class partTimeEmployee: public personType
{
public:
    void print() const;
        //Function to output the first name, last name, and
        //the wages.
        //Postcondition: Outputs
        //      firstName lastName wages are $$$$.$$

    double calculatePay() const;
        //Function to calculate and return the wages.
        //Postcondition: Pay is calculated and returned

    void setNameRateHours(string first, string last,
                        double rate, double hours);
        //Function to set the first name, last name, payRate,
        //and hoursWorked according to the parameters.
        //Postcondition: firstName = first; lastName = last;
        //      payRate = rate; hoursWorked = hours

    partTimeEmployee(string first = "", string last = "",
                    double rate = 0, double hours = 0);
        //Constructor with parameters
        //Sets the first name, last name, payRate, and hoursWorked
        //according to the parameters. If no value is specified,
        //the default values are assumed.
        //Postcondition: firstName = first; lastName = last;
        //      payRate = rate; hoursWorked = hours

private:
    double payRate;        //variable to store the pay rate
    double hoursWorked;    //variable to store the hours worked
};
```

Figure 13-5 shows the UML class diagram of the `class` `partTimeEmployee` and the inheritance hierarchy.




FIGURE 13-5 UML class diagram of the `class` `partTimeEmployee` and inheritance hierarchy

The definitions of the member functions of the `class` `partTimeEmployee` are as follows:

```

void partTimeEmployee::print() const
{
    personType::print(); //print the name of the employee
    cout << "'s wages are: $" << calculatePay() << endl;
}

double partTimeEmployee::calculatePay() const
{
    return (payRate * hoursWorked);
}

void partTimeEmployee::setNameRateHours(string first,
                                         string last, double rate, double hours)
{
    personType::setName(first, last);
    payRate = rate;
    hoursWorked = hours;
}

//Constructor
partTimeEmployee::partTimeEmployee(string first, string last,
                                   double rate, double hours)
    : personType(first, last)
{
    if (rate >= 0)
        payRate = rate;
    else
        payRate = 0;

    if (hours >= 0)
        hoursWorked = hours;
    else
        hoursWorked = 0;
}
  
```

Destructors in a Derived Class

Recall from Chapter 12 that a class can have a destructor. As we will see in the next chapter, destructors are typically used to deallocate dynamic memory allocated by the objects of a class. (A memory space that is allocated during execution time is called a dynamic memory space. The next chapter explains how to create and work with dynamic memory.) Suppose that a base class and its derived class have destructors. When a derived class object goes out of scope, it automatically invokes its destructor. When the destructor of the derived class executes, it automatically invokes the destructor of the base class. So when writing the definition of the destructor of the derived class, an explicit call to the destructor of the base class is not needed. Furthermore, when the destructor of the derived class executes first, it executes its own code and then calls the destructor of the base class. For example, suppose that `class three` is derived from `class two`, `class two` is derived from `class one`, and these classes have destructors. When an object of `class three` goes out of scope, first the destructor of `class three` executes, then the destructor of `class two` executes, and finally, the destructor of `class one` executes. That is, the destructors execute in the reverse order.

HEADER FILE OF A DERIVED CLASS

The previous section explained how to derive new classes from previously defined classes. To define new classes, you create new header files. The base classes are already defined, and header files contain their definitions. Thus, to create new classes based on the previously defined classes, the header files of the new classes contain commands that tell the computer where to look for the definitions of the base classes.

Suppose that the definition of the `class personType` is placed in the header file `personType.h`. To create the definition of the `class partTimeEmployee`, the header file—say, `partTimeEmployee.h`—must contain the preprocessor directive:

```
#include "personType.h"
```

before the definition of the `class partTimeEmployee`. To be specific, the header file `partTimeEmployee.h` is as shown below.

```
//Header file partTimeEmployee

#include "personType.h"

class partTimeEmployee: public personType
{
public:
    void print() const;
    //Function to output the first name, last name, and
    //the wages.
    //Postcondition: Outputs
    //      firstName lastName wages are $$$$.$$
```

```

double calculatePay() const;
    //Function to calculate and return the wages.
    //Postcondition: Pay is calculated and returned

void setNameRateHours(string first, string last,
                      double rate, double hours);
    //Function to set the first name, last name, payRate,
    //and hoursWorked according to the parameters.
    //Postcondition: firstName = first; lastName = last;
    //                payRate = rate; hoursWorked = hours

partTimeEmployee(string first = "", string last = "",
                 double rate = 0, double hours = 0);
    //Constructor with parameters
    //Sets the first name, last name, payRate, and hoursWorked
    //according to the parameters. If no value is specified,
    //the default values are assumed.
    //Postcondition: firstName = first; lastName = last;
    //                payRate = rate; hoursWorked = hours

private:
    double payRate;      //variable to store the pay rate
    double hoursWorked;  //variable to store the hours worked
};

```

The definitions of the member functions can be placed in a separate file. Recall that to include a system-provided header file, such as `iostream`, in a user program, you enclose the header file between angular brackets; to include a user-defined header file in a program, you enclose the header file between double quotation marks.

Multiple Inclusions of a Header File

The previous section discussed how to create the header file of a derived class. To include a header file in a program, you use the preprocessor command. Recall that before a program is compiled, the preprocessor first processes the program. Consider the following header file:

```
//Header file test.h
```

```
const int ONE = 1;
const int TWO = 2;
```

Suppose that the header file `testA.h` includes the file `test.h` in order to use the identifiers `ONE` and `TWO`. To be specific, suppose that the header file `testA.h` looks like:

```
//Header file testA.h
```

```
#include "test.h"
.
.
.
```

Now, consider the following program code:

```
//Program headerTest.cpp
```

```
#include "test.h"
#include "testA.h"
.
.
.
```

When the program `headerTest.cpp` is compiled, it is first processed by the preprocessor. The preprocessor includes first the header file `test.h` and then the header file `testA.h`. When the header file `testA.h` is included, because it contains the preprocessor directive `#include "test.h"`, the header file `test.h` is included twice in the program. The second inclusion of the header file `test.h` results in compile-time errors, such as the identifier `ONE` already being declared. This problem occurs because the first inclusion of the header file `test.h` has already defined the variables `ONE` and `TWO`. To avoid multiple inclusion of a file in a program, we use certain preprocessor commands in the header file. Let us first rewrite the header file `test.h` using these preprocessor commands and then explain the meaning of these commands.

```
//Header file test.h
```

```
#ifndef H_test
#define H_test
const int ONE = 1;
const int TWO = 2;
#endif
```

- a. `#ifndef H_test` means “if not defined `H_test`”
- b. `#define H_test` means “define `H_test`”
- c. `#endif` means “end if”

Here, `H_test` is a preprocessor identifier.

The effect of these commands is as follows: If the identifier `H_test` is not defined, we must define the identifier `H_test` and let the remaining statements between `#define` and `#endif` pass through the compiler. If the header file `test.h` is included the second time in the program, the statement `#ifndef` fails and all of the statements until `#endif` are skipped. In fact, all header files are written using similar preprocessor commands.

C++ Stream Classes

Chapter 3 described in detail how to perform input/output (I/O) using standard I/O devices and file I/O. In particular, you used the object `cin`, the extraction operator `>>`, and functions such as `get` and `ignore` to read data from the standard input device. You also used the object `cout` and the insertion operator `<<` to send output to the standard output device. To use `cin` and `cout`, the programs included the header file `iostream`,

which includes the definitions of the classes `istream` and `ostream`. Moreover, for file I/O, the programs included the header file `fstream`, and they used objects of type `ifstream` for file input and objects of type `ofstream` for file output. This section briefly describes how stream classes are related and implemented in C++.

In C++, stream classes are implemented using the inheritance mechanism, as shown in Figure 13-6.




FIGURE 13-6 C++ stream classes hierarchy

Figure 13-6 shows the stream classes that we have encountered in previous chapters. From this figure, it follows that the `class ios` is the base class for all stream classes. Classes `istream` and `ostream` are directly derived from the `class ios`. The `class ifstream` is derived from the `class istream`, and the `class ofstream` is derived from the `class ostream`. Moreover, using the mechanism of multiple inheritance, the `class iostream` (not to be confused with the header file `iostream`—these are separate things) and the `class fstream` are derived from the `class iostream`. (The classes `iostream` and `fstream` are not discussed in this book.)

The `class ios` contains formatting flags and member functions to access and/or modify the setting of these flags. To identify the I/O status, the `class ios` contains an integer status word. This integer status word provides a continuous update reporting the status of the stream.

The `classes istream` and `ostream` are responsible for providing the operations for the data transfer between memory and devices. The `class istream` defines the extraction operator, `>>`, and functions such as `get` and `ignore`. The `class ostream` defines the insertion operator, `<<`, which is used by the object `cout`.

The `class ifstream` is derived from the `class istream` to provide the file input operations. Similarly, the `class ofstream` is derived from the `class ostream` to provide the file output operations. Objects of type `ifstream` are used for file input; objects of type `ofstream` are used for file output. The header file `fstream` contains the definitions of the `classes ifstream` and `ofstream`.

Protected Members of a Class

The **private** members of a class are **private** to the class and cannot be directly accessed outside of the class. Only member functions of that class can access the **private** members. As discussed previously, the derived class cannot directly access the **private** members of a base class. However, it is sometimes necessary (say, for efficiency and/or to simplify the code) for a derived class to directly access a **private** member of a base class. If you make a **private** member become **public**, then anyone can access that member. Recall that the members of a class are classified into three categories: **public**, **private**, and **protected**. So, for a base class to give access to a member to its derived class and still prevent its direct access outside of the class, you must declare that member under the `memberAccessSpecifier` **protected**. Thus, the accessibility of a **protected** member of a class is in between **public** and **private**. A derived class can directly access the **protected** members of a base class.

To summarize, if a member of a base class needs to be accessed by a derived class, that member is declared under the `memberAccessSpecifier` **protected**.

Inheritance as **public**, **protected**, or **private**

Suppose **class** B is derived from **class** A. Then, B cannot directly access the **private** members of A. That is, the **private** members of A are hidden in B. What about the **public** and **protected** members of A? This section gives the rules that generally apply when accessing the members of a base class.

Consider the following statement:

```
class B: memberAccessSpecifier A
{
    .
    .
    .
};
```

In this statement, `memberAccessSpecifier` is either **public**, **protected**, or **private**.

1. If `memberAccessSpecifier` is **public**—that is, the inheritance is **public**—then:
 - a. The **public** members of A are **public** members of B. They can be directly accessed in **class** B.
 - b. The **protected** members of A are **protected** members of B. They can be directly accessed by the member functions (and **friend** functions) of B.
 - c. The **private** members of A are hidden in B. They cannot be directly accessed in B. They can be accessed by the member functions (and **friend** functions) of B through the **public** or **protected** members of A.

2. If `memberAccessSpecifier` is **protected**—that is, the inheritance is **protected**—then:
 - a. The **public** members of **A** are **protected** members of **B**. They can be accessed by the member functions (and **friend** functions) of **B**.
 - b. The **protected** members of **A** are **protected** members of **B**. They can be accessed by the member functions (and **friend** functions) of **B**.
 - c. The **private** members of **A** are hidden in **B**. They cannot be directly accessed in **B**. They can be accessed by the member functions (and **friend** functions) of **B** through the **public** or **protected** members of **A**.
3. If `memberAccessSpecifier` is **private**—that is, the inheritance is **private**—then:
 - a. The **public** members of **A** are **private** members of **B**. They can be accessed by the member functions (and **friend** functions) of **B**.
 - b. The **protected** members of **A** are **private** members of **B**. They can be accessed by the member functions (and **friend** functions) of **B**.
 - c. The **private** members of **A** are hidden in **B**. They cannot be directly accessed in **B**. They can be accessed by the member functions (and **friend** functions) of **B** through the **public** or **protected** members of **A**.

NOTE

Chapter 15 describes the **friend** functions.

Example 13-4 illustrates how the member functions of a derived class can directly access a **protected** member of the base class.

EXAMPLE 13-4**(Accessing protected Members in the Derived Class)**

Consider the following definition of the **class** `bClass`:

```
class bClass
{
public:
    void setData(double);
    void setData(char, double);
    void print() const;
```

```

        bClass(char ch = '*', double u = 0.0);

protected:
    char bCh;

private:
    double bX;
};

```

The definition of the `class` `bClass` contains a `protected` member variable `bCh` of type `char` and a `private` member variable `bX` of type `double`. It also contains an overloaded member function `setData`. One version is used to set both member variables; the other version is used to set only the `private` member variable. The class also has a constructor with default parameters. Suppose that the definitions of the member functions and the constructor are as follows:

```

void bClass::setData(double u)
{
    bX = u;
}
void bClass::setData(char ch, double u)
{
    bCh = ch;
    bX = u;
}

void bClass::print() const
{
    cout << "Base class: bCh = " << bCh << ", bX = " << bX
        << endl;
}

bClass::bClass(char ch, double u)
{
    bCh = ch;
    bX = u;
}

```

Next, we derive a `class` `dClass` from the `class` `bClass` using `public` inheritance as follows:

```

class dClass: public bClass
{
public:
    void setData(char, double, int);
    void print() const;

    dClass(char ch = '*', double u = 0.0, int x = 0);

private:
    int dA;
};

```

The `class` `dClass` contains a `private` member variable `dA` of type `int`. It also contains a constructor, a member function `setData` with three parameters, and the function `print`.

Let us now write the definition of the function `setData`. Because `bCh` is a `protected` member variable of the `class` `bClass`, it can be directly accessed in the definition of the function `setData`. However, because `bX` is a `private` member variable of the `class` `bClass`, the function `setData` cannot directly access it. Thus, the function `setData` must set `bX` by using the function `setData` of the `class` `bClass`. The definition of the function `setData` of the `class` `dClass` can be written as follows:

```
void dClass::setData(char ch, double v, int a)
{
    bClass::setData(v);

    bCh = ch; //initialize bCh using the assignment statement
    dA = a;
}
```

Note that the definition of the function `setData` calls the function `bClass::setData`, with one parameter to set the member variable `bX`, and then directly sets the value of `bCh`. Next, let us write the definition of the function `print` (of the `class` `dClass`).

We now write the definition of the function `print` of the `class` `dClass`. Notice that in the definition of the `class` `bClass`, the member function `print` is not overloaded as in the member function `setData`. It prints the values of both member variables, `bCh` and `bX`. The member variable `bX` is a `private` member variable, so it cannot be directly accessed in the `class` `dClass`. Even though `bCh` is a `protected` member variable and it can be directly accessed in the `class` `dClass`, we must print its value using the function `print` of the `class` `bClass`, because this function outputs the values of both `bCh` and `dX`. For this reason, we first call the function `print` (of the `class` `bClass`) and then output only the value of `dA`. The definition of the function `print` is:

```
void dClass::print() const
{
    bClass::print();

    cout << "Derived class dA = " << dA << endl;
}
```

The definition of the constructor is:

```
dClass::dClass(char ch, double u, int x)
    : bClass(ch, u)
{
    dA = x;
}
```

The following program illustrates how the objects of `bClass` and `dClass` work. We assume that the definition of the `class` `bClass` is in the header file `protectMemClass.h`, and the definition of the `class` `dClass` is in the header file `protectMemInDerivedCl.h`.

```

//Accessing protected members of a base class in the derived
//class.

#include <iostream>
#include "protectMembClass.h"
#include "protectMembInDerivedCl.h"

using namespace std;

int main()
{
    bClass bObject;                                //Line 1
    dClass dObject;                                //Line 2

    bObject.print();                                //Line 3
    cout << endl;                                  //Line 4

    cout << "*** Derived class object ***" << endl; //Line 5

    dObject.setData('&', 2.5, 7);                    //Line 6

    dObject.print();                                //Line 7

    return 0;
}

```

Sample Run:

Base class: bCh = *, bX = 0

*** Derived class object ***

Base class: bCh = &, bX = 2.5

Derived class dA = 7

When you write the definitions of the member functions of the `class` `dClass`, the `protected` member variable `bCh` can be accessed directly. However, `dClass` objects cannot directly access `bCh`. That is, the following statement is illegal (it is, in fact, a syntax error):

```
dObject.bCh = '&';    //illegal
```

Composition (Aggregation)

Composition (aggregation) is another way to relate two classes. In **composition (aggregation)**, one or more members of a class are objects of another class type. Composition is a “has-a” relation; for example, “every person has a date of birth.”

Example 12-9 in Chapter 12 defined a class called `personType`. The `class` `personType` stores a person’s first name and last name. Suppose we want to keep track of additional information for a person, such as a personal ID (e.g., a Social Security number)

and a date of birth. Because every person has a personal ID and a date of birth, we can define a new class, called `personalInfo`, in which one of the members is an object of type `personType`. We can declare additional members to store the personal ID and date of birth for the `class personalInfo`.

First, we define another `class`, `dateType`, to store only a person's date of birth. Then, we construct the `class personalInfo` from the `classes personType` and `dateType`. This way, we can demonstrate how to define a new class using two classes.

To define the `class dateType`, we need three member variables—to store the month, day number, and year. Some of the operations that need to be performed on a date are to set the date and to print the date. The following statements define the `class dateType`:

```
class dateType
{
public:
    void setDate(int month, int day, int year);
        //Function to set the date.
        //The member variables dMonth, dDay, and dYear are set
        //according to the parameters.
        //Postcondition: dMonth = month; dDay = day;
        //                dYear = year

    int getDay() const;
        //Function to return the day.
        //Postcondition: The value of dDay is returned.

    int getMonth() const;
        //Function to return the month.
        //Postcondition: The value of dMonth is returned.

    int getYear() const;
        //Function to return the year.
        //Postcondition: The value of dYear is returned.

    void printDate() const;
        //Function to output the date in the form mm-dd-yyyy.

    dateType(int month = 1, int day = 1, int year = 1900);
        //Constructor to set the date
        //The member variables dMonth, dDay, and dYear are set
        //according to the parameters.
        //Postcondition: dMonth = month; dDay = day; dYear = year;
        //                If no values are specified, the default
        //                values are used to initialize the member
        //                variables.
```

```
private:
    int dMonth; //variable to store the month
    int dDay;   //variable to store the day
    int dYear;  //variable to store the year
};
```

Figure 13-7 shows the UML class diagram of the `class` `dateType`.




FIGURE 13-7 UML class diagram of the `class` `dateType`

The definitions of the member functions of the `class` `dateType` are as follows:

```
void dateType::setDate(int month, int day, int year)
{
    dMonth = month;
    dDay = day;
    dYear = year;
}
```

The definition of the function `setDate`, before storing the date into the member variables, does not check whether the date is valid. That is, it does not confirm whether `month` is between 1 and 12, `year` is greater than 0, and `day` is valid (for example, for January, `day` should be between 1 and 31). In Programming Exercise 2 at the end of this chapter, you are asked to rewrite the definition of the function `setDate` so that the date is validated before storing it in the member variables. The definitions of the remaining member functions are as follows:

```
int dateType::getDay() const
{
    return dDay;
}

int dateType::getMonth() const
{
    return dMonth;
}
```

```

int dateType::getYear() const
{
    return dYear;
}

void dateType::printDate() const
{
    cout << dMonth << "-" << dDay << "-" << dYear;
}

//Constructor with parameters
dateType::dateType(int month, int day, int year)
{
    dMonth = month;
    dDay = day;
    dYear = year;
}

```

Just as in the case of `setDate`, in Programming Exercise 2, you are asked to rewrite the definition of the constructor so that it checks for the valid values of `month`, `day`, and `year` before storing the date into the member variables.

Next, we give the definition of the `class` `personalInfo`.

```

class personalInfo
{
public:
    void setpersonalInfo(string first, string last, int month,
                        int day, int year, int ID);
    //Function to set the personal information.
    //The member variables are set according to the
    //parameters.
    //Postcondition: firstName = first; lastName = last;
    //                dMonth = month; dDay = day;
    //                dYear = year; personID = ID;

    void printpersonalInfo () const;
    //Function to print the personal information.

    personalInfo(string first = "", string last = "",
                int month = 1, int day = 1, int year = 1900,
                int ID = 0);

    //Constructor
    //The member variables are set according to the
    //parameters.
    //Postcondition: firstName = first; lastName = last;
    //                dMonth = month; dDay = day;
    //                dYear = year; personID = ID;
    //                If no values are specified, the default
    //                values are used to initialize the member
    //                variables.
}

```

```
private:
    personType name;
    dateType bDay;
    int personID;
};
```

Figure 13-8 shows the UML class diagram of the `class` `personalInfo` and composition (aggregation).




FIGURE 13-8 UML class diagram of the `class` `personalInfo` and composition (aggregation)

Before we give the definition of the member functions of the `class` `personalInfo`, let us discuss how the constructors of the objects `bDay` and `name` are invoked.

Recall that a class constructor is automatically executed when a class object enters its scope. Suppose that we have the following statement:

```
personalInfo student;
```

When the object `student` enters its scope, the objects `bDay` and `name`, which are members of `student`, also enter their scopes. As a result, one of their constructors is executed. We, therefore, need to know how to pass arguments to the constructors of the member objects (that is, `bDay` and `name`), which occurs when we give the definitions of the constructors of the class. Recall that constructors do not have a type and so cannot be called like other functions. The arguments to the constructor of a member object (such as `bDay`) are specified in the heading part of the definition of the constructor of the class. Furthermore, member objects of a class are constructed (that is, initialized) in the order they are declared (not in the order they are listed in the constructor's member initialization list) and before the containing class objects are constructed. Thus, in our case, the object `name` is initialized first, then `bDay`, and finally, `student`.

The following statements illustrate how to pass arguments to the constructors of the member objects `name` and `bDay`:

```
personalInfo::personalInfo(string first, string last, int month,
                           int day, int year, int ID)
    : name(first, last), bDay(month, day, year)
{
    .
    .
    .
}
```

The definitions of the member functions of the `class personalInfo` are as follows:

```
void personalInfo::setpersonalInfo(string first, string last,
                                    int month, int day, int year, int ID)
{
    name.setName(first, last);
    bDay.setDate(month, day, year);
    personID = ID;
}

void personalInfo::printpersonalInfo() const
{
    name.print();
    cout << "'s date of birth is ";
    bDay.printDate();
    cout << endl;
    cout << "and personal ID is " << personID;
}

personalInfo::personalInfo(string first, string last, int month,
                           int day, int year, int ID)
    : name(first, last), bDay(month, day, year)
{
    personID = ID;
}
```

NOTE

In the case of inheritance, use the class name to invoke the base class's constructor. In the case of composition, use the member object name to invoke its own constructor.

Object-Oriented Design (OOD) and Object-Oriented Programming (OOP)

The first 11 chapters of this book used the top-down approach to programming, also called structured programming, to write programs. Problems were broken down into modules, and each module solved a particular part of the problem. Data requirements were identified, and functions were written to manipulate the data. The functions and the data were kept separate, and the functions acted on the data in a passive way. Structured programming, therefore, has certain limitations. In structured programming, functions are

dependent on the data, and functions are designed specifically to solve a particular problem. It is quite difficult, if not impossible, to reuse a function written for one program in another program. For some of these reasons, structured programming is not very efficient for large software development.

Chapter 12 began with the introduction of classes. We learned how classes are defined and used. Later in that chapter, we concentrated on the data requirements of a problem and the logical operations on that data. With the help of classes, we combined the data—and the operations on that data—in a single unit. That is, the data and operations were encapsulated in a single unit. Also, with the help of classes, we were able to separate the data and the algorithms to manipulate that data. However, the functions to implement the operations on the data had direct access to the data. This chapter explains how to create new classes from existing classes through inheritance (and also using composition). Furthermore, an object has the capability to hide the information details. These are some of the features of object-oriented design (OOD).

The three basic principles of OOD are as follows:

- **Encapsulation**—The ability to combine data and operations on that data in a single unit.
- **Inheritance**—The ability to create new objects (classes) from existing objects (classes).
- **Polymorphism**—The ability to use the same expression to denote different operations.

In OOD, an object is a fundamental entity; in structured programming, a function is a fundamental entity. In OOD, we debug classes; in structured programming, we debug functions. In OOD, a program is a collection of interacting objects; in structured programming, a program is a collection of interacting functions. Also, OOD encourages code reuse. Once a class becomes error-free, it can be reused in many programs because it is a self-contained entity. Object-oriented programming (OOP) implements OOD.

To create objects, we must know how to represent the data and write functions to manipulate that data. Thus, we must know everything that we have learned in Chapters 2 through 9. The first nine chapters are essential for any type of programming, whether structured or object-oriented.

C++ supports OOP through the use of classes. We have already examined the first two features of OOP, encapsulation and inheritance, in this chapter and Chapter 12. Chapter 15 discusses the third feature of OOD: polymorphism. A polymorphic function or operator has many forms.

In C++, a function name and the operators can be overloaded. An example of function overloading occurs when the function is called, and the operator is evaluated according to the arguments used. For instance, if both operands are integers, the division operator yields an integer result; otherwise, the division operator yields a decimal result. Suppose a class has constructors. If no arguments are passed to an object when it is declared, the

default constructor is executed; otherwise, one of the constructors with parameters is executed. However, all constructors have the same name.

C++ also provides parametric polymorphism. In parametric polymorphism, the (data) type is left unspecified and then later instantiated. Templates (discussed in Chapter 15) provide parametric polymorphism. Also, C++ provides virtual functions as a means to implement polymorphism in an inheritance hierarchy, which allows the run-time selection of appropriate member functions. (Chapter 14 discusses virtual functions.)

There are several OOP languages in existence today, including Ada, Modula-2, Object Pascal, Turbo Pascal, Eiffel, C++, Java, and Smalltalk. The earliest OOP language was Simula, developed in 1967. The OOP terminology is influenced by the vocabulary of Smalltalk, the OOP language largely developed at a Xerox research center during the 1970s. An OOP language uses many “fancy” words, such as methods, message passing, and so forth.

OOP is a natural and intuitive way to view the programming process. When we view an object, we immediately think of what it can do. For example, when we think about a car, we also think about the operations on the car, such as starting the car and driving the car. When programmers think about a list, they also think about the operations on the list, such as searching, sorting, and inserting. OOP allows ADT to be created and used. In C++, we implement ADT through the use of classes.

Objects are created when class variables are declared. Objects interact with each other via function calls. Every object has an internal state and an external state. The **private** members form the internal state; the **public** members form the external state. Only the object can manipulate its internal state.

Identifying Classes, Objects, and Operations

In this book’s first 11 chapters, in the problem analysis phase, we analyzed the problem, identified the data, and outlined the algorithm. To reduce the complexity of the function **main**, we wrote functions to manipulate the data. In Chapter 12, we used the OOD technique and first identified the objects that made up the overall problem. The objects were designed and implemented independently of the main program. The hardest part in OOD is to identify the classes and objects. In this section, we describe a common and simple technique to identify classes and objects.

We begin with a description of the problem and then identify all of the nouns and verbs. We choose our classes from the list of nouns, and we choose our operations from the list of verbs.

For example, suppose that we want to write a program that calculates and prints the volume and surface area of a cylinder. We can state this problem as follows:

*Write a **program** to **input** the **dimensions** of a **cylinder** and **calculate** and **print** the **surface area** and **volume**.*

In this statement, the nouns are bold, and the verbs are italic. From the list of nouns—**program**, **dimensions**, **cylinder**, **surface area**, and **volume**—we can easily visualize

cylinder to be a class—say, `cylinderType`—from which we can create many cylinder objects of various dimensions. The nouns **dimensions**, **surface area**, and **volume** are characteristics of a **cylinder** and thus can hardly be considered classes.

After we identify a class, the next step is to determine three pieces of information:

- Operations that an object of that class type can perform
- Operations that can be performed on an object of that class type
- Information that an object of that class type must maintain

From the list of verbs identified in the problem description, we choose a list of possible operations that an object of that class can perform, or has performed, on itself. For example, from the list of verbs for the cylinder problem description—*write*, *input*, *calculate*, and *print*—the possible operations for a cylinder object are *input*, *calculate*, and *print*.

For the `class cylinderType`, the dimensions represent the data. The **center** of the base, **radius** of the base, and **height** of the cylinder are the characteristics of the dimensions. You can input data to the object either by a constructor or by a mutator function.

The verb *calculate* applies to determining the volume and the surface area. From this, you can deduce the operations: `cylinderVolume` and `cylinderSurfaceArea`. Similarly, the verb *print* applies to the display of the volume and the surface area on an output device. In Programming Exercise 5 at the end of this chapter, you are asked to design a class to implement the characteristics of a cylinder.

Identifying classes via the nouns and verbs from the descriptions of the problem is not the only technique possible. There are several other OOD techniques in the literature. However, this technique is sufficient for the programming exercises in this book.

PROGRAMMING EXAMPLE: Grade Report

This programming example further illustrates the concepts of inheritance and composition.

The mid-semester point at your local university is approaching. The registrar's office wants to prepare the grade reports as soon as the students' grades are recorded. However, some of the students enrolled have not yet paid their tuition.

1. If a student has paid the tuition, the grades are shown on the grade report together with the grade point average (GPA).
2. If a student has not paid the tuition, the grades are not printed. For these students, the grade report contains a message indicating that the grades have been held for nonpayment of the tuition. The grade report also shows the billing amount.

The registrar's office and the business office want your help in writing a program that can analyze the students' data and print the appropriate grade reports. The data is stored in a file in the following form:

```

15000 345
studentName studentID isTuitionPaid numberOfCourses
courseName courseNumber creditHours grade
courseName courseNumber creditHours grade
.
.
.
studentName studentID isTuitionPaid numberOfCourses
courseName courseNumber creditHours grade
courseName courseNumber creditHours grade
.
.
.

```

The first line indicates the number of students enrolled and the tuition rate per credit hour. The students' data is given thereafter.

A sample input file is as follows:

```

3 345
Lisa Miller 890238 Y 4
Mathematics MTH345 4 A
Physics PHY357 3 B
ComputerSci CSC478 3 B
History HIS356 3 A
.
.
.

```

The first line indicates that the input file contains three students' data, and the tuition rate is \$345 per credit hour. Next, the course data for student **Lisa Miller** is given: Lisa Miller's ID is 890238, she has paid the tuition, and she is taking four courses. The course number for the mathematics class she is taking is **MTH345**, the course has four credit hours, her mid-semester grade is **A**, and so on.

The desired output for each student is in the following form:

```

Student Name: Lisa Miller
Student ID: 890238
Number of courses enrolled: 4

```

| Course No | Course Name | Credits | Grade |
|-----------|-------------|---------|-------|
| CSC478 | ComputerSci | 3 | B |
| HIS356 | History | 3 | A |
| MTH345 | Mathematics | 4 | A |
| PHY357 | Physics | 3 | B |

```

Total number of credits: 13
Mid-Semester GPA: 3.54

```

It is clear from this output that the courses must be ordered according to the course number. To calculate the GPA, we assume that the grade **A** is equivalent to four

points, **B** is equivalent to three points, **C** is equivalent to two points, **D** is equivalent to one point, and **F** is equivalent to zero points.

Input A file containing the data in the form given previously. For easy reference, let us assume that the name of the input file is `stData.txt`.

Output A file containing the output in the form given previously.

**PROBLEM
ANALYSIS
AND
ALGORITHM
DESIGN**

We must first identify the main components of the program. The university has students, and every student takes courses. Thus, the two main components are the student and the course.

Let us first describe the course component.

Course The main characteristics of a course are the course name, course number, and number of credit hours.

Some of the basic operations that need to be performed on an object of the course type are:

1. Set the course information.
2. Print the course information.
3. Show the credit hours.
4. Show the course number.

The following class defines the course as an ADT:

```
class courseType
{
public:
    void setCourseInfo(string cName, string cNo, int credits);
        //Function to set the course information.
        //The course information is set according to the
        //parameters.
        //Postcondition: courseName = cName; courseNo = cNo;
        //                  courseCredits = credits;

    void print(ostream& outF);
        //Function to print the course information.
        //This function sends the course information to the
        //output device specified by the parameter outF. If the
        //actual parameter to this function is the object cout,
        //then the output is shown on the standard output device.
        //If the actual parameter is an ofstream variable, say,
        //outFile, then the output goes to the file specified by
        //outFile.

    int getCredits();
        //Function to return the credit hours.
        //Postcondition: The value of courseCredits is returned.
```

```

string getCourseNumber();
    //Function to return the course number.
    //Postcondition: The value of courseNo is returned.

string getCourseName();
    //Function to return the course name.
    //Postcondition: The value of courseName is returned.

courseType(string cName = "", string cNo = "",
            int credits = 0);
    //Constructor
    //The object is initialized according to the parameters.
    //Postcondition: courseName = cName; courseNo = cNo;
    //                  courseCredits = credits;

private:
    string courseName; //variable to store the course name
    string courseNo;   //variable to store the course number
    int courseCredits; //variable to store the credit hours
};

```

Figure 13-9 shows the UML class diagram of the `class` `courseType`.




FIGURE 13-9 UML class diagram of the `class` `courseType`

Next, we discuss the definitions of the functions to implement the operations of the `class` `courseType`. These definitions are quite straightforward and easy to follow.

The function `setCourseInfo` sets the values of the `private` member variables according to the values of the parameters. Its definition is:

```

void courseType::setCourseInfo(string cName, string cNo,
                               int credits)
{
    courseName = cName;
    courseNo = cNo;
    courseCredits = credits;
} //end setCourseInfo

```

The function `print` prints the course information. The parameter `outF` specifies the output device. Also, we print the course name and course number left-justified rather than right-justified (the default). Thus, we need to set the `left` manipulator. Before printing the credit hours, the manipulator is set to be right-justified. The following steps describe this function:

1. Set the `left` manipulator.
2. Print the course number.
3. Print the course name.
4. Set the `right` manipulator.
5. Print the credit hours.

The definition of the function `print` is:

```

void courseType::print(ostream& outF)
{
    outF << left;                                //Step 1
    outF << setw(8) << courseNo << "    ";        //Step 2
    outF << setw(15) << courseName;                //Step 3
    outF << right;                                //Step 4
    outF << setw(3) << courseCredits << "    ";    //Step 5
} //end print

```

The constructor is declared with the default values. If no values are specified when a `courseType` object is declared, the constructor uses the default to initialize the object. Using the default values, the object's member variables are initialized as follows: `courseNo` to blank, `courseName` to blank, and `courseCredits` to 0. Otherwise, the values specified in the object declaration are used to initialize the object. Its definition is:

```

courseType::courseType(string cName, string cNo, int credits)
{
    courseName = cName;
    courseNo = cNo;
    courseCredits = credits;
} //end default constructor

```

The definitions of the remaining functions are as follows:

```
int courseType::getCredits()
{
    return courseCredits;
} //end getCredits

string courseType::getCourseNumber()
{
    return courseNo;
} //end getCourseNumber

string courseType::getCourseName()
{
    return courseName;
} //end getCourseName
```

Next, we discuss the student component.

NOTE

Notice that in the definition of the **class** `courseType`, the member functions, such as `print` and `getCredits`, are accessor functions. This class also has other accessor functions. As noted in Chapter 12, we typically define the accessor functions with the keyword **const** at the end of their headings. We leave it as an exercise for you to redefine this class so that the accessor functions are declared as constant functions. (See Programming Exercise 13 at the end of this chapter.)

Student The main characteristics of a student are the student name, student ID, number of courses in which enrolled, courses in which enrolled, and grade for each course. Because every student has to pay tuition, we also include a member to indicate whether the student has paid the tuition.

Every student is a person, and every student takes courses. We have already designed a **class** `personType` to process a person's first name and last name. We have also designed a class to process the information for a course. Thus, we see that we can derive the **class** `studentType` to keep track of a student's information from the **class** `personType`, and one member of this class is of type `courseType`. We can add more members as needed.

The basic operations to be performed on an object of type `studentType` are as follows:

1. Set the student information.
2. Print the student information.
3. Calculate the number of credit hours taken.

4. Calculate the GPA.
5. Calculate the billing amount.
6. Because the grade report will print the courses in ascending order, sort the courses according to the course number.

The following class defines `studentType` as an ADT. We assume that a student takes no more than six courses per semester.

```
class studentType: public personType
{
public:
    void setInfo(string fName, string lName, int ID,
                int nOfCourses, bool isTPaid,
                courseType courses[], char courseGrades[]);
    //Function to set the student's information.
    //Postcondition: The member variables are set
    //              according to the parameters.

    void print(ostream& outF, double tuitionRate);
    //Function to print the student's grade report.
    //If the member variable isTuitionPaid is true, the grades
    //are shown; otherwise, three stars are printed. If the
    //actual parameter corresponding to outF is the object
    //cout, then the output is shown on the standard output
    //device. If the actual parameter corresponding to outF
    //is an ofstream object, say outFile, then the output
    //goes to the file specified by outFile.

    studentType();
    //Default constructor
    //The member variables are initialized.

    int getHoursEnrolled();
    //Function to return the credit hours a student is
    //enrolled in.
    //Postcondition: The number of credit hours is
    //              calculated and returned.

    double getGpa();
    //Function to return the grade point average.
    //Postcondition: The gpa is calculated and returned.

    double billingAmount(double tuitionRate);
    //Function to return the tuition fees.
    //Postcondition: The billing amount is calculated
    //and returned.
```

```

private:
    void sortCourses();
        //Function to sort the courses.
        //Postcondition: The array coursesEnrolled is sorted.
        //
        //          For each course, its grade is stored in
        //          the array coursesGrade. Therefore, when
        //          the array coursesEnrolled is sorted, the
        //          corresponding entries in the array
        //          coursesGrade are adjusted.

    int sId;                //variable to store the student ID
    int numberOfCourses;    //variable to store the number
                          //of courses
    bool isTuitionPaid;    //variable to indicate whether the
                          //tuition is paid
    courseType coursesEnrolled[6]; //array to store the courses
    char coursesGrade[6];    //array to store the course grades
};

```

Figure 13-10 shows the UML class diagram of the `class` `studentType` together with the inheritance and composition (aggregation) relation.




FIGURE 13-10 UML class diagram of the `class` `studentType` together with inheritance and composition (aggregation) relation

Before writing the definitions of the member functions of the `class` `studentType`, we make the following note.

NOTE

Notice that in the definition of the **class** `studentType`, the member functions, such as `print` and `getGpa`, are accessor functions. This class also has other accessor functions. As noted in Chapter 12, we typically define the accessor functions with the keyword **const** at the end of their headings. We leave it as an exercise for you to redefine this class so that the accessor functions are declared as constant functions. (See Programming Exercise 13 at the end of this chapter.)

Note that the member function `sortCourses` to sort the array `coursesEnrolled` is a **private** member of the **class** `studentType`. This is due to the fact that this function is needed for internal data manipulation, and the user of the class does not need to access this member.

Next, we discuss the definitions of the functions to implement the operations of the **class** `studentType`.

The function `setInfo` first initializes the **private** member variables according to the incoming parameters. This function then calls the function `sortCourses` to sort the array `coursesEnrolled` by course number. The **class** `studentType` is derived from the **class** `personType`, and the variables to store the first name and last name are **private** member variables of that class. Therefore, we call the member function `setName` of the **class** `personType` and pass the appropriate variables to set the first and last names. The definition of the function `setInfo` is as follows:

```
void studentType::setInfo(string fName, string lName, int ID,
                        int nOfCourses, bool isTPaid,
                        courseType courses[], char cGrades[])
{
    int i;

    setName(fName, lName);           //set the name

    sId = ID;                        //set the student ID
    isTuitionPaid = isTPaid;         //set isTuitionPaid
    numberOfCourses = nOfCourses;    //set the number of courses

    //set the course information
    for (i = 0; i < numberOfCourses; i++)
    {
        coursesEnrolled[i] = courses[i];
        coursesGrade[i] = cGrades[i];
    }

    sortCourses();                  //sort the array coursesEnrolled
} //end setInfo
```

The default constructor initializes the **private** member variables to the default values. Note that because the **private** member variable `coursesEnrolled` is of type `courseType` and is an array, the default constructor of the **class** `courseType` executes automatically, and the entire array is initialized.

```
studentType::studentType()
{
    numberOfCourses = 0;
    sId = 0;
    isTuitionPaid = false;

    for (int i = 0; i < 6; i++)
        coursesGrade[i] = '*';
} //end default constructor
```

The function `print` prints the grade report. The parameter `outF` specifies the output device. If the student has paid his or her tuition, the grades and the GPA are shown. Otherwise, three stars are printed in place of each grade, the GPA is not shown, a message indicates that the grades are being held for nonpayment of the tuition, and the amount due is shown. This function has the following steps:

1. Output the student's name.
2. Output the student's ID.
3. Output the number of courses in which the student is enrolled.
4. Output the heading:

| Course No | Course Name | Credits | Grade |
|-----------|-------------|---------|-------|
|-----------|-------------|---------|-------|
5. Print each course's information.
 For each course, print:
 - a. Course No, Course Name, Credits
 - b. **if** `isTuitionPaid` is **true**
 Output the grade
 else
 Output three stars.
6. Print the total credit hours.
7. To output the GPA and billing amount in a fixed decimal format with the decimal point and trailing zeros, set the necessary flag. Also, set the precision to two decimal places.
8. **if** `isTuitionPaid` is **true**
 Output the GPA
 else
 Output the billing amount and a message about withholding the grades.

NOTE

Let us take a look at the formal parameter of the function `print`. The formal parameter `outF` is an object of the `class ostream`. We can use this function to send the output to the standard output device, the screen, or to a file. As indicated in the definition of the class, if the actual parameter is, say, `cout`, then the output is displayed on the screen. If the actual parameter is, say, `outfile`, an object of the `class ofstream`, then the output is sent to the device indicated by `outfile`. As mentioned in the section, “C++ Stream Hierarchy,” the `class ofstream` is derived from the `class ostream`. Therefore, the `class ostream` is the base class. In C++, if a formal reference parameter is of the type `ostream`, it can refer to an object of the `class ofstream`.

In general, C++ allows a formal reference parameter of the base class type to refer to an object of the derived class. Of course, for user-defined classes, some other things need to be taken into account for this mechanism to work properly, which we will discuss in Chapter 14 (in the section “Inheritance, Pointers, and Virtual Functions”).

The function `getHoursEnrolled` calculates and returns the total credit hours that a student is taking. These credit hours are needed to calculate both the GPA and the billing amount. The total credit hours are calculated by adding the credit hours of each course in which the student is enrolled. Because the credit hours for a course are in the `private` member variable of an object of type `courseType`, we use the member function `getCredits` of the `class courseType` to retrieve the credit hours. The definition of this function is:

```
int studentType::getHoursEnrolled()
{
    int totalCredits = 0;
    int i;

    for (i = 0; i < numberOfCourses; i++)
        totalCredits += coursesEnrolled[i].getCredits();

    return totalCredits;
} //end getHoursEnrolled
```

If a student has not paid the tuition, the function `billingAmount` calculates and returns the amount due, based on the number of credit hours enrolled. The definition of this function is:

```
double studentType::billingAmount(double tuitionRate)
{
    return tuitionRate * getHoursEnrolled();
} //end billingAmount
```

We now discuss the function `getGpa`. This function calculates a student's GPA. To find the GPA, we find the equivalent points for each grade, add the points, and then divide the sum by the total credit hours the student is taking. The definition of this function is:

```
double studentType::getGpa()
{
    int i;
    double sum = 0.0;

    for (i = 0; i < numberOfCourses; i++)
    {
        switch (coursesGrade[i])
        {
            case 'A':
                sum += coursesEnrolled[i].getCredits() * 4;
                break;
            case 'B':
                sum += coursesEnrolled[i].getCredits() * 3;
                break;
            case 'C':
                sum += coursesEnrolled[i].getCredits() * 2;
                break;
            case 'D':
                sum += coursesEnrolled[i].getCredits() * 1;
                break;
            case 'F':
                break;
            default:
                cout << "Invalid Course Grade." << endl;
        }
    }

    return sum / getHoursEnrolled();
} //end getGpa
```

The function `sortCourses` sorts the array `coursesEnrolled` by course number. To sort the array, we use a selection sort algorithm. Because we will compare the course numbers, which are strings and `private` member variables of the `class` `courseType`, we first retrieve and store the course numbers in local variables.

```
void studentType::sortCourses()
{
    int i, j;
    int minIndex;
    courseType temp;    //variable to swap the data
    char tempGrade;     //variable to swap the grades
    string course1;
    string course2;
```

```

for (i = 0; i < numberOfCourses - 1; i++)
{
    minIndex = i;

    for (j = i + 1; j < numberOfCourses; j++)
    {
        //get the course numbers
        course1 =
            coursesEnrolled[minIndex].getCourseNumber();
        course2 = coursesEnrolled[j].getCourseNumber();

        if (course1 > course2)
            minIndex = j;
    } //end for

    temp = coursesEnrolled[minIndex];
    coursesEnrolled[minIndex] = coursesEnrolled[i];
    coursesEnrolled[i] = temp;

    tempGrade = coursesGrade[minIndex];
    coursesGrade[minIndex] = coursesGrade[i];
    coursesGrade[i] = tempGrade;
} //end for
} //end sortCourses

```

MAIN PROGRAM

Now that we have designed the classes `courseType` and `studentType`, we will use these classes to complete the program.

We will restrict our program to process a maximum of 10 students. Note that this program can easily be enhanced to process any number of students.

Because the `print` function of the class does the necessary computations to print the final grade report, the main program has very little work to do. In fact, all that is left for the main program is to declare the objects to hold the students' data, load the data into these objects, and then print the grade reports. Because the input is in a file and the output will be sent to a file, we declare stream variables to access the input and output files. Essentially, the main algorithm for the program is:

1. Declare the variables.
2. Open the input file.
3. If the input file does not exist, exit the program.
4. Open the output file.
5. Get the number of students registered and the tuition rate.
6. Load the students' data.
7. Print the grade reports.

VARIABLES

This program processes a maximum of 10 students. Therefore, we must declare an array of 10 components of type `studentType` to hold the students' data. We also need to store the number of students registered and the tuition rate. Because the data will be read from a file and because the output is sent to a file, we need two stream variables to access the input and output files. Thus, we need the following variables:

```
studentType studentList[MAX_NO_OF_STUDENTS]; //array to store
                                              //the students' data

int noOfStudents;    //variable to store the number of students
double tuitionRate;  //variable to store the tuition rate

ifstream infile;     //input stream variable
ofstream outfile;    //output stream variable
```

Function**getStudentData**

This function has three parameters: a parameter to access the input file, a parameter to access the array `studentList`, and a parameter to know the number of students registered. In pseudocode, the definition of this function is as follows:

For each student in the university,

1. Get the first name, last name, student ID, and `isPaid`.
2. `if isPaid` is 'Y'
 - set `isTuitionPaid` to `true`
 - `else`
 - set `isTuitionPaid` to `false`
3. Get the number of courses the student is taking.
4. For each course:
 - Get the course name, course number, credit hours, and grade.
 - Load the course information into a `courseType` object.
5. Load the data into a `studentType` object.

We need to declare several local variables to read and store the data. The definition of the function `getStudentData` is:

```
void getStudentData(ifstream& infile,
                   studentType studentList[],
                   int numberOfStudents)
{
    //local variables
    string fName;    //variable to store the first name
    string lName;    //variable to store the last name
    int ID;          //variable to store the student ID
    int noOfCourses; //variable to store the number of courses
    char isPaid;     //variable to store Y/N, that is,
                   //is tuition paid
    bool isTuitionPaid; //variable to store true/false
```

```

string cName; //variable to store the course name
string cNo;   //variable to store the course number
int credits;  //variable to store the course credit hours

int count;    //loop control variable
int i;        //loop control variable

courseType courses[6]; //array of objects to store the
                        //course information
char cGrades[6];       //array to hold the course grades

for (count = 0; count < numberOfStudents; count++)
{
    infile >> fName >> lName >> ID >> isPaid; //Step 1

    if (isPaid == 'Y')                        //Step 2
        isTuitionPaid = true;
    else
        isTuitionPaid = false;

    infile >> noOfCourses;                     //Step 3

    for (i = 0; i < noOfCourses; i++)         //Step 4
    {
        infile >> cName >> cNo >> credits
            >> cGrades[i];                     //Step 4.a
        courses[i].setCourseInfo(cName, cNo,
                                credits);       //Step 4.b
    }
    studentList[count].setInfo(fName, lName, ID,
                                noOfCourses,
                                isTuitionPaid,
                                courses, cGrades); //Step 5

} //end for
} //end getStudentData

```

Function This function prints the grade reports. For each student, it calls the function `print` of the `class` `studentType` to print the grade report. The definition of the function `printGradeReports` is:

```

void printGradeReports(ofstream& outfile,
                       studentType studentList[],
                       int numberOfStudents,
                       double tuitionRate)
{
    int count;
    for (count = 0; count < numberOfStudents; count++)
        studentList[count].print(outfile, tuitionRate);
} //end printGradeReports

```

PROGRAMMING LISTING

```

//*****
// Author: D.S. Malik
//
// class courseType
// This class specifies the members to implement a course's
// information.
//*****

#ifndef H_courseType
#define H_courseType

#include <fstream>
#include <string>

using namespace std;

//The definition of the class courseType goes here.
.
.
.
#endif

//*****
// Author: D.S. Malik
//
// Implementation file courseTypeImp.cpp
// This file contains the definitions of the functions to
// implement the operations of the class courseType.
//*****

#include <iostream>
#include <fstream>
#include <string>
#include <iomanip>
#include "courseType.h"

using namespace std;

//The definitions of the member functions of the class
//courseType go here.
.
.
.

```

```

//*****
// Author: D.S. Malik
//
// class personType
// This class specifies the members to implement a person's
// first name and last name.
//*****

#ifndef H_personType
#define H_personType

#include <string>

using namespace std;

//The definition of the class personType goes here.
.
.
.
#endif

//*****
// Author: D.S. Malik
//
// Implementation file personTypeImp.cpp
// This file contains the definitions of the functions to
// implement the operations of the class personType.
//*****

#include <iostream>
#include <string>
#include "personType.h"

using namespace std;

//The definitions of the member functions of the class
//personType go here.
.
.
.

//*****
// Author: D.S. Malik
//
// class studentType
// This class specifies the members to implement a student's
// information.
//*****

```

```

#ifndef H_studentType
#define H_studentType

#include <fstream>
#include <string>
#include "personType.h"
#include "courseType.h"

using namespace std;

//The definition of the class studentType goes here.
.
.
.

#endif

//*****
// Author: D.S. Malik
//
// Implementation file studentTypeImp.cpp
// This file contains the definitions of the functions to
// implement the operations of the class studentType.
//*****

#include <iostream>
#include <iomanip>
#include <fstream>
#include <string>
#include "personType.h"
#include "courseType.h"
#include "studentType.h"

using namespace std;

//The definitions of the member functions of the class
//studentType go here.
.
.
.

//*****
// Author: D.S. Malik
//
// This program reads students' data from a file and outputs
// the grades. If student has not paid the tuition, the
// grades are not shown, and an appropriate message is
// output. The output is stored in a file.
//*****

```

```

#include <iostream>
#include <fstream>
#include <string>
#include "studentType.h"

using namespace std;

const int MAX_NO_OF_STUDENTS = 10;

void getStudentData(ifstream& infile,
                   studentType studentList[],
                   int numberOfStudents);

void printGradeReports(ofstream& outfile,
                      studentType studentList[],
                      int numberOfStudents,
                      double tuitionRate);

int main()
{
    studentType studentList[MAX_NO_OF_STUDENTS];

    int noOfStudents;
    double tuitionRate;
    ifstream infile;
    ofstream outfile;

    infile.open("stData.txt");

    if (!infile)
    {
        cout << "The input file does not exist. "
              << "Program terminates." << endl;
        return 1;
    }

    outfile.open("sDataOut.txt");

    infile >> noOfStudents; //get the number of students
    infile >> tuitionRate; //get the tuition rate

    getStudentData(infile, studentList, noOfStudents);
    printGradeReports(outfile, studentList,
                      noOfStudents, tuitionRate);

    return 0;
}

//Place the definitions of the functions getStudentData and
//printGradeReports here.

```

Sample Run:

Student Name: Lisa Miller
 Student ID: 890238
 Number of courses enrolled: 4

| Course No | Course Name | Credits | Grade |
|-----------|-------------|---------|-------|
| CSC478 | ComputerSci | 3 | B |
| HIS356 | History | 3 | A |
| MTH345 | Mathematics | 4 | A |
| PHY357 | Physics | 3 | B |

Total number of credit hours: 13
 Mid-Semester GPA: 3.54

-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*

Student Name: Bill Wilton
 Student ID: 798324
 Number of courses enrolled: 5

| Course No | Course Name | Credits | Grade |
|-----------|-------------|---------|-------|
| BIO234 | Biology | 4 | *** |
| CHM256 | Chemistry | 4 | *** |
| ENG378 | English | 3 | *** |
| MTH346 | Mathematics | 3 | *** |
| PHL534 | Philosophy | 3 | *** |

Total number of credit hours: 17
 *** Grades are being held for not paying the tuition. ***
 Amount Due: \$5865.00

-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*

Student Name: Dandy Goat
 Student ID: 746333
 Number of courses enrolled: 6

| Course No | Course Name | Credits | Grade |
|-----------|-------------|---------|-------|
| BUS128 | Business | 3 | C |
| CHM348 | Chemistry | 4 | B |
| CSC201 | ComputerSci | 3 | B |
| ENG328 | English | 3 | B |
| HIS101 | History | 3 | A |
| MTH137 | Mathematics | 3 | A |

Total number of credit hours: 19
 Mid-Semester GPA: 3.16

-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*-*

Input File:

```

3 345
Lisa Miller 890238 Y 4
Mathematics MTH345 4 A
Physics PHY357 3 B
ComputerSci CSC478 3 B
History HIS356 3 A

Bill Wilton 798324 N 5
English ENG378 3 B
Philosophy PHL534 3 A
Chemistry CHM256 4 C
Biology BIO234 4 A
Mathematics MTH346 3 C

Dandy Goat 746333 Y 6
History HIS101 3 A
English ENG328 3 B
Mathematics MTH137 3 A
Chemistry CHM348 4 B
ComputerSci CSC201 3 B
Business BUS128 3 C

```

QUICK REVIEW

1. Inheritance and composition (aggregation) are meaningful ways to relate two or more classes.
2. Inheritance is an “is-a” relation.
3. Composition (aggregation) is a “has-a” relation.
4. In a single inheritance, the derived class is derived from only one existing class called the base class.
5. In a multiple inheritance, a derived class is derived from more than one base class.
6. The **private** members of a base class are **private** to the base class. The derived class cannot directly access them.
7. The **public** members of a base class can be inherited either as **public** or **private** by the derived class.
8. A derived class can redefine the member functions of a base class, but this redefinition applies only to the objects of the derived class.
9. A call to a base class’s constructor (with parameters) is specified in the heading of the definition of the derived class’s constructor.

10. If in the heading of the definition of a derived class's constructor, no call to a constructor (with parameters) of a base class is specified, then during the derived class's object declaration and initialization, the default constructor (if any) of the base class executes.
11. When initializing the object of a derived class, the constructor of the base class is executed first.
12. Review the inheritance rules given in this chapter.
13. In composition (aggregation), a member of a class is an object of another class.
14. In composition (aggregation), a call to the constructor of the member objects is specified in the heading of the definition of the class's constructor.
15. The three basic principles of OOD are encapsulation, inheritance, and polymorphism.
16. An easy way to identify classes, objects, and operations is to describe the problem in English and then identify all of the nouns and verbs. Choose your classes (objects) from the list of nouns and operations from the list of verbs.

EXERCISES

1. Mark the following statements as true or false.
 - a. The constructor of a derived class can specify a call to the constructor of the base class in the heading of the function definition.
 - b. The constructor of a derived class can specify a call to the constructor of the base class using the name of the class.
 - c. Suppose that **x** and **y** are classes, one of the member variables of **x** is an object of type **y**, and both classes have constructors. The constructor of **x** specifies a call to the constructor of **y** by using the object name of type **y**.
2. Draw a class hierarchy in which several classes are derived from a single base class.
3. Suppose that a **class employeeType** is derived from the **class personType** (see Example 12-9 in Chapter 12). Give examples of members—data and functions—that can be added to the **class employeeType**.
4. Consider the following statements:


```
class dog: public animal
{
    ...
};
```

In this declaration, which class is the base class, and which class is the derived class?

5. Consider the following class definition:

```
class circle
{
public:
    void print() const;
    void setRadius(double);
    double getRadius();
    double area();
    circle();
    circle(double);

private:
    double radius;
};

class cylinder: public circle
{
public:
    void print() const;
    void setHeight(double);
    double getHeight();
    double volume();
    double area();
    cylinder();
    cylinder(double, double);

private:
    double height;
};
```

Suppose that you have the declaration:

```
cylinder newCylinder;
```

Determine the private members of the object `newCylinder`.

6. Suppose that `class` three is derived from `class` two, `class` two is derived from `class` one, and each `class` has instance variables. Suppose that an object of `class` three enters its scope, so the constructors of these classes will execute. Determine the order in which the constructors of these `classes` will execute.
7. Consider the following class definition:

```
class aClass
{
public:
    void print() const;
    void set(int, int);
    aClass();
    aClass(int, int);

private:
    int u;
    int v;
};
```

What is wrong with the following class definitions?

- a. `class` bClass `public` aClass
- ```
{
public:
 void print();
 void set(int, int, int);

private:
 int z;
}
```

```
b. class cClass: public aClass
{
public:
 void print();
 int sum();
 cClass();
 cClass(int)
}
```

8. Consider the following statements:

```
class yClass
{
public:
 void one();
 void two(int, int);
 yClass();

private:
 int a;
 int b;
};
```

```
class xClass: public yClass
{
public:
 void one();
 xClass();

private:
 int z;
};
```

Suppose the following statements are in a user program (client code):

```
yClass y;
xClass x;
```

- a. The **private** members of **yClass** are **public** members of **xClass**. True or False?
- b. Mark the following statements as valid or invalid. If a statement is invalid, explain why.

```
i. void yClass::one()
{
 cout << a + b << endl;
}
```

```
ii. y.a = 15;
 x.b = 30;
```

```
iii. void xClass::one()
{
 a = 10;
 b = 15;
 z = 30;
 cout << a + b + z << endl;
}
```

```
iv. cout << y.a << " " << y.b << " " << x.z << endl;
```

9. Assume the declaration of Exercise 8.

- a. Write the definition of the default constructor of **yClass** so that the **private** member variables of **yClass** are initialized to 0.

- b. Write the definition of the default constructor of `xClass` so that the `private` member variables of `xClass` are initialized to 0.
  - c. Write the definition of the member function `two` of `yClass` so that the `private` member variable `a` is initialized to the value of the first parameter of `two`, and the `private` member variable `b` is initialized to the value of the second parameter of `two`.
10. Explain the difference between the `private` and `protected` members of a class.
  11. Explain the difference between the `protected` and `public` members of a class.
  12. Consider the following class definition:

```
class first
{
public:
 void setX();
 void print const();
protected:
 int y;
 void setY(int a);
private:
 int x;
};
```

Suppose that `class second` is derived from `class first` using the statement:

```
class second: private first
```

Determine which members of `class first` are `private`, `protected`, and `public` in `class second`.

13. Assume the declaration of Exercise 12. Suppose that `class third` is derived from `class first` using the statement:

```
class third: protected first
```

Determine which members of `class first` are `private`, `protected`, and `public` in `class third`.

14. Assume the declaration of Exercise 12. Suppose that `class fourth` is derived from `class first` using the statement:

```
class fourth: public first
```

Determine which members of `class first` are `private`, `protected`, and `public` in `class fourth`.

15. Assume the declaration of Exercise 12. Suppose that `class fifth` is derived from `class first` using the statement:

```
class fifth: first
```

Determine which members of `class` first are `private`, `protected`, and `public` in `class` fifth.

16. What is wrong with the following code?

```
class classA
{
protected:
 void setX(int a); //Line 1
 //Postcondition: x = a; //Line 2

private: //Line 3
 int x; //Line 4
};
.
.
.
int main()
{
 classA aObject; //Line 5

 aObject.setX(4); //Line 6
 return 0; //Line 7
}
```

17. Consider the following code:

```
class one
{
public:
 void print() const;
 //Output the values of x and y
protected:
 void setData(int u, int v);
 //Postcondition: x = u; y = v;
private:
 int x;
 int y;
};

class two: public one
{
public:
 void setData(int a, int b, int c);
 //Postcondition: x = a; y = b; z = c;
 void print() const;
 //Output the values of x, y, and z
private:
 int z;
};
```

- a. Write the definition of the function `setData` of the `class` two.
- b. Write the definition of the function `print` of the `class` two.

18. What is the output of the following C++ program?

```
#include <iostream>
#include <string>

using namespace std;

class baseClass
{
public:
 void print() const;

 baseClass(string s = " ", int a = 0);
 //Postcondition: str = s; x = a;

protected:
 int x;

private:
 string str;
};

class derivedClass: public baseClass
{
public:
 void print() const;

 derivedClass(string s = "", int a = 0, int b = 0);
 //Postcondition: str = s; x = a; y = b;

private:
 int y;
};

int main()
{
 baseClass baseObject("This is the base class", 2);
 derivedClass derivedObject("DDDDDD", 3, 7);

 baseObject.print();
 derivedObject.print();

 return 0;
}

void baseClass::print() const
{
 cout << x << " " << str << endl;
}
```

```

baseClass::baseClass(string s, int a)
{
 str = s;
 x = a;
}

void derivedClass::print() const
{
 cout << "Derived class: " << y << endl;
 baseClass::print();
}

derivedClass::derivedClass(string s, int a, int b)
 :baseClass("Hello Base", a + b)
{
 y = b;
}

```

19. Consider the following class definitions:

```

class baseClass
{
public:
 void print() const;
 int getX() const;
 baseClass(int a = 0);

protected:
 int x;
};

class derivedClass: public baseClass
{
public:
 void print() const;
 int getResult() const;
 derivedClass(int a = 0, int b = 0);

private:
 int y;
};

```

Suppose the definitions of the member functions of these classes are as follows:

```

void baseClass::print() const
{
 cout << "In base: x = " << x << endl;
}

baseClass::baseClass(int a)
{
 x = a;
}

```

```

int baseClass::getX() const
{
 return x;
}

void derivedClass::print() const
{
 cout << "In derived: x = " << x << ", y = " << y
 << "; x + y = " << x + y << endl;
}

int derivedClass::getResult() const
{
 return x + y;
}

derivedClass::derivedClass(int a, int b)
 : baseClass(a)
{
 y = b;
}

```

What is the output of the following function main?

```

int main()
{
 baseClass baseObject(7);
 derivedClass derivedObject(3, 8);

 baseObject.print();
 derivedObject.print();

 cout << "*****" << baseObject.getX() << endl;
 cout << "#####" << derivedObject.getResult() << endl;

 return 0;
}

```

## PROGRAMMING EXERCISES

1. In Chapter 12, the `class` `clockType` was designed to implement the time of day in a program. Certain applications, in addition to hours, minutes, and seconds, might require you to store the time zone. Derive the `class` `extClockType` from the `class` `clockType` by adding a member variable to store the time zone. Add the necessary member functions and constructors to make the class functional. Also, write the definitions of the member functions and the constructors. Finally, write a test program to test your `class`.
2. In this chapter, the `class` `dateType` was designed to implement the date in a program, but the member function `setDate` and the constructor do not

check whether the date is valid before storing the date in the member variables. Rewrite the definitions of the function `setDate` and the constructor so that the values for the month, day, and year are checked before storing the date into the member variables. Add a member function, `isLeapYear`, to check whether a year is a leap year. Moreover, write a test program to test your class.

3. A point in the  $x$ - $y$  plane is represented by its  $x$ -coordinate and  $y$ -coordinate. Design a `class`, `pointType`, that can store and process a point in the  $x$ - $y$  plane. You should then perform operations on the point, such as setting the coordinates of the point, printing the coordinates of the point, returning the  $x$ -coordinate, and returning the  $y$ -coordinate. Also, write a program to test various operations on the point.
4. Every circle has a center and a radius. Given the radius, we can determine the circle's area and circumference. Given the center, we can determine its position in the  $x$ - $y$  plane. The center of the circle is a point in the  $x$ - $y$  plane. Design a `class`, `circleType`, that can store the radius and center of the circle. Because the center is a point in the  $x$ - $y$  plane and you designed the class to capture the properties of a point in Programming Exercise 3, you must derive the `class` `circleType` from the `class` `pointType`. You should be able to perform the usual operations on the circle, such as setting the radius, printing the radius, calculating and printing the area and circumference, and carrying out the usual operations on the center. Also, write a program to test various operations on a circle.
5. Every cylinder has a base and height, wherein the base is a circle. Design a `class`, `cylinderType`, that can capture the properties of a cylinder and perform the usual operations on the cylinder. Derive this class from the `class` `circleType` designed in Programming Exercise 4. Some of the operations that can be performed on a cylinder are as follows: calculate and print the volume, calculate and print the surface area, set the height, set the radius of the base, and set the center of the base. Also, write a program to test various operations on a cylinder.
6. Using classes, design an online address book to keep track of the names, addresses, phone numbers, and dates of birth of family members, close friends, and certain business associates. Your program should be able to handle a maximum of 500 entries.
  - a. Define a `class`, `addressType`, that can store a street address, city, state, and ZIP code. Use the appropriate functions to print and store the address. Also, use constructors to automatically initialize the member variables.
  - b. Define a `class` `extPersonType` using the `class` `personType` (as defined in Example 12-9, Chapter 12), the `class` `dateType` (as designed in this chapter's Programming Exercise 2), and the `class` `addressType`. Add a member variable to this class to classify the person as a family

member, friend, or business associate. Also, add a member variable to store the phone number. Add (or override) the functions to print and store the appropriate information. Use constructors to automatically initialize the member variables.

- c. Define the `class addressBookType` using the previously defined classes. An object of the type `addressBookType` should be able to process a maximum of 500 entries.

The program should perform the following operations:

- i. Load the data into the address book from a disk.
  - ii. Sort the address book by last name.
  - iii. Search for a person by last name.
  - iv. Print the address, phone number, and date of birth (if it exists) of a given person.
  - v. Print the names of the people whose birthdays are in a given month.
  - vi. Print the names of all of the people between two last names.
  - vii. Depending on the user's request, print the names of all family members, friends, or business associates.
7. In Programming Exercise 2, the `class dateType` was designed and implemented to keep track of a date, but it has very limited operations. Redefine the `class dateType` so that it can perform the following operations on a date, in addition to the operations already defined:
  - a. Set the month.
  - b. Set the day.
  - c. Set the year.
  - d. Return the month.
  - e. Return the day.
  - f. Return the year.
  - g. Test whether the year is a leap year.
  - h. Return the number of days in the month. For example, if the date is 3-12-2013, the number of days to be returned is 31 because there are 31 days in March.
  - i. Return the number of days passed in the year. For example, if the date is 3-18-2013, the number of days passed in the year is 77. Note that the number of days returned also includes the current day.
  - j. Return the number of days remaining in the year. For example, if the date is 3-18-2013, the number of days remaining in the year is 288.
  - k. Calculate the new date by adding a fixed number of days to the date. For example, if the date is 3-18-2013 and the days to be added are 25, the new date is 4-12-2013.

8. Write the definitions of the functions to implement the operations defined for the `class dateType` in Programming Exercise 7.
9. The `class dateType` defined in Programming Exercise 7 prints the date in numerical form. Some applications might require the date to be printed in another form, such as March 24, 2013. Derive the `class extDateType` so that the date can be printed in either form.

Add a member variable to the `class extDateType` so that the month can also be stored in string form. Add a member function to output the month in the string format, followed by the year—for example, in the form March 2013.

Write the definitions of the functions to implement the operations for the `class extDateType`.

10. Using the `classes extDateType` (Programming Exercise 9) and `dayType` (Chapter 12, Programming Exercise 2), design the `class calendarType` so that, given the month and the year, we can print the calendar for that month. To print a monthly calendar, you must know the first day of the month and the number of days in that month. Thus, you must store the first day of the month, which is of the form `dayType`, and the month and the year of the calendar. Clearly, the month and the year can be stored in an object of the form `extDateType` by setting the day component of the date to 1 and the month and year as specified by the user. Thus, the `class calendarType` has two member variables: an object of the type `dayType` and an object of the type `extDateType`.

Design the `class calendarType` so that the program can print a calendar for any month starting January 1, 1500. Note that the day for January 1 of the year 1500 is a Monday. To calculate the first day of a month, you can add the appropriate days to Monday of January 1, 1500.

For the `class calendarType`, include the following operations:

- a. Determine the first day of the month for which the calendar will be printed. Call this operation `firstDayOfMonth`.
- b. Set the month.
- c. Set the year.
- d. Return the month.
- e. Return the year.
- f. Print the calendar for the particular month.
- g. Add the appropriate constructors to initialize the member variables.
11. a. Write the definitions of the member functions of the `class calendarType` (designed in Programming Exercise 10) to implement the operations of the `class calendarType`.

- b. Write a test program to print the calendar for either a particular month or a particular year. For example, the calendar for September 2013 is:

| September 2013 |     |     |     |     |     |     |
|----------------|-----|-----|-----|-----|-----|-----|
| Sun            | Mon | Tue | Wed | Thu | Fri | Sat |
| 1              | 2   | 3   | 4   | 5   | 6   | 7   |
| 8              | 9   | 10  | 11  | 12  | 13  | 14  |
| 15             | 16  | 17  | 18  | 19  | 20  | 21  |
| 22             | 23  | 24  | 25  | 26  | 27  | 28  |
| 29             | 30  |     |     |     |     |     |

12. In this exercise, you will design various classes and write a program to computerize the billing system of a hospital.
- Design the **class** `doctorType`, inherited from the **class** `personType`, defined in Chapter 12, with an additional data member to store a doctor's speciality. Add appropriate constructors and member functions to initialize, access, and manipulate the data members.
  - Design the **class** `billType` with data members to store a patient's ID and a patient's hospital charges, such as pharmacy charges for medicine, doctor's fee, and room charges. Add appropriate constructors and member functions to initialize and access and manipulate the data members.
  - Design the **class** `patientType`, inherited from the **class** `personType`, defined in Chapter 12, with additional data members to store a patient's ID, age, date of birth, attending physician's name, the date when the patient was admitted in the hospital, and the date when the patient was discharged from the hospital. (Use the **class** `dateType` to store the date of birth, admit date, discharge date, and the **class** `doctorType` to store the attending physician's name.) Add appropriate constructors and member functions to initialize, access, and manipulate the data members.
- Write a program to test your classes.
13. In the Programming Example Grade Report, in the definitions of the **classes** `courseType` and `studentType`, the accessor functions are not made constants; that is, they are not defined with the reserved word **const** at the end of their headings. Redefine these classes so that all of the accessor functions are constant functions. Accordingly, modify the definitions of the accessor functions and rerun the program.
14. a. Define the **class** `bankAccount` to store a bank customer's account number and balance. Suppose that account number is of type **int**, and balance is of type **double**. Your class should, at least, provide the following operations: set the account number, retrieve the account number, retrieve the balance, deposit and withdraw money, and print account information. Add appropriate constructors.

- b. Every bank offers a checking account. Derive the `class checkingAccount` from the `class bankAccount` (designed in part (a)). This class inherits members to store the account number and the balance from the base class. A customer with a checking account typically receives interest, maintains a minimum balance, and pays service charges if the balance falls below the minimum balance. Add member variables to store this additional information. In addition to the operations inherited from the base class, this class should provide the following operations: set interest rate, retrieve interest rate, set minimum balance, retrieve minimum balance, set service charges, retrieve service charges, post interest, verify if the balance is less than the minimum balance, write a check, withdraw (override the method of the base class), and print account information. Add appropriate constructors.
- c. Every bank offers a savings account. Derive the `class savingsAccount` from the `class bankAccount` (designed in part (a)). This class inherits members to store the account number and the balance from the base class. A customer with a savings account typically receives interest, makes deposits, and withdraws money. In addition to the operations inherited from the base class, this class should provide the following operations: set interest rate, retrieve interest rate, post interest, withdraw (override the method of the base class), and print account information. Add appropriate constructors.
- d. Write a program to test your classes designed in parts (b) and (c).



# 14

## CHAPTER

# POINTERS, CLASSES, VIRTUAL FUNCTIONS, AND ABSTRACT CLASSES

IN THIS CHAPTER, YOU WILL:

- Learn about the pointer data type and pointer variables
- Explore how to declare and manipulate pointer variables
- Learn about the address of operator and the dereferencing operator
- Discover dynamic variables
- Explore how to use the `new` and `delete` operators to manipulate dynamic variables
- Learn about pointer arithmetic
- Discover dynamic arrays
- Become aware of the shallow and deep copies of data
- Discover the peculiarities of classes with pointer member variables
- Learn about virtual functions
- Examine the relationship between the address of operator and classes
- Become aware of abstract classes

In Chapter 2, you learned that C++'s data types are classified into three categories: simple, structured, and pointers. Until now, you have studied only the first two data types. This chapter discusses the third data type called the pointer data type. You will first learn how to declare pointer variables (or pointers, for short) and manipulate the data to which they point. Later, you will use these concepts when you study dynamic arrays and linked lists. Linked lists are discussed in Chapter 18.

## Pointer Data Type and Pointer Variables

Chapter 2 defined a data type as a set of values together with a set of operations. Recall that the set of values is called the domain of the data type. In addition to these two properties, until now, all of the data types you have encountered have one more thing associated with them: the name of the data type. For example, there is a data type called `int`. The set of values belonging to this data type includes integers that range between  $-2147483648$  and  $2147483647$ , and the operations allowed on these values are the arithmetic operators described in Chapter 2. To manipulate numeric integer data in the range  $-2147483648$  to  $2147483647$ , you can declare variables using the word `int`. The name of the data type allows you to declare a variable. Next, we describe the pointer data type.

The values belonging to pointer data types are the memory addresses of your computer. As in many other languages, there is no name associated with the pointer data type in C++. Because the domain—that is, the set of values of a pointer data type—is the addresses (memory locations), a pointer variable is a variable whose content is an address, that is, a memory location.

**Pointer variable:** A variable whose content is an address (that is, a memory address).

### Declaring Pointer Variables

As remarked previously, there is no name associated with pointer data types. Moreover, pointer variables store memory addresses. So the obvious question is: If no name is associated with a pointer data type, how do you declare pointer variables?

The value of a pointer variable is an address. That is, the value refers to another memory space. The data is typically stored in this memory space. Therefore, when you declare a pointer variable, you also specify the data type of the value to be stored in the memory location pointed to by the pointer variable.

In C++, you declare a pointer variable by using the asterisk symbol (\*) between the data type and the variable name. The general syntax to declare a pointer variable is:

```
dataType *identifier;
```

As an example, consider the following statements:

```
int *p;
char *ch;
```

In these statements, both `p` and `ch` are pointer variables. The content of `p` (when properly assigned) points to a memory location of type `int`, and the content of `ch` points to a memory location of type `char`. Usually, `p` is called a pointer variable of type `int`, and `ch` is called a pointer variable of type `char`.

Before discussing how pointers work, let us make the following observations. The statement:

```
int *p;
```

is equivalent to the statement:

```
int* p;
```

which is equivalent to the statement:

```
int * p;
```

Thus, the character `*` can appear anywhere between the data type name and the variable name.

Now, consider the following statement:

```
int* p, q;
```

In this statement, only `p` is the pointer variable, not `q`. Here, `q` is an `int` variable. To avoid confusion, we prefer to attach the character `*` to the variable name. So the preceding statement is written as:

```
int *p, q;
```

Of course, the statement:

```
int *p, *q;
```

declares both `p` and `q` to be pointer variables of type `int`.

Now that you know how to declare pointers, next we will discuss how to make a pointer point to a memory space and how to manipulate the data stored in these memory locations.

Because the value of a pointer is a memory address, a pointer can store the address of a memory space of the designated type. For example, if `p` is a pointer of type `int`, `p` can store the address of any memory space of type `int`. C++ provides two operators—the address of operator (`&`) and the dereferencing operator (`*`)—to work with pointers. The next two sections describe these operators.

## Address of Operator (&)

In C++, the ampersand, `&`, called the **address of operator**, is a unary operator that returns the address of its operand. For example, given the statements:

```
int x;
int *p;
```

the statement:

```
p = &x;
```

assigns the address of **x** to **p**. That is, **x** and the value of **p** refer to the same memory location.

## Dereferencing Operator (\*)

Every chapter until now has used the asterisk character, **\***, as the binary multiplication operator. C++ also uses **\*** as a unary operator. When used as a unary operator, **\***, commonly referred to as the **dereferencing operator** or **indirection operator**, refers to the object to which its operand (that is, the pointer) points. For example, given the statements:

```
int x = 25;
int *p;
p = &x; //store the address of x in p
```

the statement:

```
cout << *p << endl;
```

prints the value stored in the memory space pointed to by **p**, which is the value of **x**. Also, the statement:

```
*p = 55;
```

stores 55 in the memory location pointed to by **p**—that is, in **x**.

### EXAMPLE 14-1

Let us consider the following statements:

```
int *p;
int num;
```

In these statements, **p** is a pointer variable of type **int**, and **num** is a variable of type **int**. Let us assume that memory location 1200 is allocated for **p**, and memory location 1800 is allocated for **num**. (See Figure 14-1.)







FIGURE 14-1 Variables **p** and **num**

Consider the following statements.

1. `num = 78;`
2. `p = &num;`
3. `*p = 24;`

The following shows the values of the variables after the execution of each statement.

| After Statement | Values of the Variables                                                                                                                                        | Explanation                                                                                                                                                                                                                                                   |
|-----------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1               |  <p>1200                      1800<br/>p                              num</p> | The statement <code>num = 78;</code> stores 78 into <code>num</code> .                                                                                                                                                                                        |
| 2               |  <p>1200                      1800<br/>p                              num</p> | The statement <code>p = &amp;num;</code> stores the address of <code>num</code> , which is 1800, into <code>p</code> .                                                                                                                                        |
| 3               |  <p>1200                      1800<br/>p                              num</p> | The statement <code>*p = 24;</code> stores 24 into the memory location to which <code>p</code> points. Because the value of <code>p</code> is 1800, statement 3 stores 24 into memory location 1800. Note that the value of <code>num</code> is also changed. |

Let us summarize the preceding discussion.

1. A declaration such as `int *p;` allocates memory for `p` only, not for `*p`. Later, you will learn how to allocate memory for `*p`.
2. The content of `p` points only to a memory location of type `int`.
3. `&p`, `p`, and `*p` all have different meanings.
4. `&p` means the address of `p`—that is, 1200 (in Figure 14-1).
5. `p` means the content of `p`, which is 1800, after the statement `p = &num;` executes.
6. `*p` means the content of the memory location to which `p` points. Note that after the statement `p = &num;` executes, the value of `*p` is 78; after the statement `*p = 24;` executes, the value of `*p` is 24.

### EXAMPLE 14-2

Consider the following statements:

```
int *p;
int x;
```

Suppose that we have the memory allocation for **p** and **x** as shown in Figure 14-2.




FIGURE 14-2 Main memory, **p**, and **x**

The values of **&p**, **p**, **\*p**, **&x**, and **x** are as follows:

|               |      |          |             |           |                            |               |      |          |             |
|---------------|------|----------|-------------|-----------|----------------------------|---------------|------|----------|-------------|
| <b>&amp;p</b> | 1400 | <b>p</b> | ? (unknown) | <b>*p</b> | Does not exist (undefined) | <b>&amp;x</b> | 1750 | <b>x</b> | ? (unknown) |
|---------------|------|----------|-------------|-----------|----------------------------|---------------|------|----------|-------------|

Suppose that the following statements are executed in the order given:

```
x = 50;
p = &x;
*p = 38;
```

The values of **&p**, **p**, **\*p**, **&x**, and **x** are shown after each of these statements executes.

After the statement **x = 50;** executes, the values of **&p**, **p**, **\*p**, **&x**, and **x** are as follows:

|               |      |          |             |           |                            |               |      |          |    |
|---------------|------|----------|-------------|-----------|----------------------------|---------------|------|----------|----|
| <b>&amp;p</b> | 1400 | <b>p</b> | ? (unknown) | <b>*p</b> | Does not exist (undefined) | <b>&amp;x</b> | 1750 | <b>x</b> | 50 |
|---------------|------|----------|-------------|-----------|----------------------------|---------------|------|----------|----|

After the statement **p = &x;** executes, the values of **&p**, **p**, **\*p**, **&x**, and **x** are as follows:

|               |      |          |      |           |    |               |      |          |    |
|---------------|------|----------|------|-----------|----|---------------|------|----------|----|
| <b>&amp;p</b> | 1400 | <b>p</b> | 1750 | <b>*p</b> | 50 | <b>&amp;x</b> | 1750 | <b>x</b> | 50 |
|---------------|------|----------|------|-----------|----|---------------|------|----------|----|

After the statement **\*p = 38;** executes, the values of **&p**, **p**, **\*p**, **&x**, and **x** are as follows. (Because **\*p** and **x** refer to the same memory space, the value of **x** is also changed to 38.)

|               |      |          |      |           |    |               |      |          |    |
|---------------|------|----------|------|-----------|----|---------------|------|----------|----|
| <b>&amp;p</b> | 1400 | <b>p</b> | 1750 | <b>*p</b> | 38 | <b>&amp;x</b> | 1750 | <b>x</b> | 38 |
|---------------|------|----------|------|-----------|----|---------------|------|----------|----|

Let us note the following:

1. `p` is a pointer variable.
2. The content of `p` points only to a memory location of type `int`.
3. Memory location `x` exists and is of type `int`. Therefore, the assignment statement:  
`p = &x;`  
 is legal. After this assignment statement executes, `*p` is valid and meaningful.

The program in Example 14-3 further illustrates how a pointer variable works.

### EXAMPLE 14-3

The following program illustrates how pointer variables work:

*//Chapter 14: Example 14-3*

```
#include <iostream>

using namespace std;

int main()
{
 int *p;
 int x = 37;

 cout << "Line 1: x = " << x << endl; //Line 1

 p = &x; //Line 2

 cout << "Line 3: *p = " << *p
 << ", x = " << x << endl; //Line 3

 *p = 58; //Line 4

 cout << "Line 5: *p = " << *p
 << ", x = " << x << endl; //Line 5

 cout << "Line 6: Address of p = " << &p << endl; //Line 6

 cout << "Line 7: Value of p = " << p << endl; //Line 7

 cout << "Line 8: Value of the memory location "
 << "pointed to by *p = " << *p << endl; //Line 8
 cout << "Line 9: Address of x = " << &x << endl; //Line 9
 cout << "Line 10: Value of x = " << x << endl; //Line 10

 return 0;
}
```

**Sample Run:**

```

Line 1: x = 37
Line 3: *p = 37, x = 37
Line 5: *p = 58, x = 58
Line 6: Address of p = 006BFDF4
Line 7: Value of p = 006BFDF0
Line 8: Value of the memory location pointed to by *p = 58
Line 9: Address of x = 006BFDF0
Line 10: Value of x = 58

```

The preceding program works as follows. The statement in Line 1 outputs the value of **x**, and the statement in Line 2 stores the address of **x** into **p**. The statement in Line 3 outputs the values of **\*p** and **x**. Because **p** contains the address of **p**, the values of **\*p** and **x** are the same, as shown by the output of Line 3. The statement in Line 4 changes the value of **\*p** to 58, and the statement in Line 5 outputs the values of **\*p** and **x**, which are again the same. The statements in Lines 6 through 10 output the address of **p**, the value of **p**, the value of **\*p**, the address of **x**, and the value of **x**. Note that the value of **p** and the address of **x** are the same because the address of **x** is stored in **p** by the statement in Line 2. (Note that the address of **p**, the value of **p**, and the address of **x**, as shown by the outputs of Lines 6, 7, and 9, respectively, are machine dependent. When you run this program on your machine, you are likely to get different values. Furthermore, the pointer values, that is, addresses, are printed in hexadecimal by default.)

---

## Classes, Structs, and Pointer Variables

---

In the previous section, you learned how to declare and manipulate pointers of simple data types, such as **int** and **char**. You can also declare pointers to other data types, such as classes. You will now learn how to declare and manipulate pointers to classes and structs. (Recall that both classes and structs have the same capabilities. The only difference between classes and structs is that, by default, all members of a class are **private**, and, by default, all members of a struct are **public**. Therefore, the following discussion applies to both.)

Consider the following declaration of a **struct**:

```

struct studentType
{
 char name[26];
 double gpa;
 int sID;
 char grade;
};

studentType student;
studentType *studentPtr;

```

In the preceding declaration, `student` is an object of type `studentType`, and `studentPtr` is a pointer variable of type `studentType`. The following statement stores the address of `student` in `studentPtr`:

```
studentPtr = &student;
```

The following statement stores 3.9 in the component `gpa` of the object `student`:

```
(*studentPtr).gpa = 3.9;
```

The expression `(*studentPtr).gpa` is a mixture of pointer dereferencing and the class component selection. In C++, the dot operator, `.`, has a higher precedence than the dereferencing operator.

Let us elaborate on this a bit. In the expression `(*studentPtr).gpa`, the operator `*` evaluates first, so the expression `*studentPtr` evaluates first. Because `studentPtr` is a pointer variable of type `studentType`, `*studentPtr` refers to a memory space of type `studentType`, which is a `struct`. Therefore, `(*studentPtr).gpa` refers to the component `gpa` of that `struct`.

Consider the expression `*studentPtr.gpa`. Let us see how this expression gets evaluated. Because `.` (dot) has a higher precedence than `*`, the expression `studentPtr.gpa` evaluates first. The expression `studentPtr.gpa` would result in a syntax error, as `studentPtr` is *not* a `struct` variable, so it has no such component as `gpa`.

As you can see, in the expression `(*studentPtr).gpa`, the parentheses are important. However, typos can be problematic. Therefore, to simplify the accessing of class or `struct` components via a pointer, C++ provides another operator called the **member access operator arrow**, `->`. The operator `->` consists of two consecutive symbols: a hyphen and the “greater than” sign.

The syntax for accessing a `class` (`struct`) member using the operator `->` is:

```
pointerVariableName->classMemberName
```

Thus, the statement:

```
(*studentPtr).gpa = 3.9;
```

is equivalent to the statement:

```
studentPtr->gpa = 3.9;
```

Accessing `class` (`struct`) components via pointers using the operator `->` thus eliminates the use of both parentheses and the dereferencing operator. Because typos are unavoidable and missing parentheses can result in either an abnormal program termination or erroneous results, when accessing `class` (`struct`) components via pointers, this book uses the arrow notation.

Example 14-4 illustrates how pointers work with class member functions.

#### EXAMPLE 14-4

Consider the following class:

```
class classExample
{
public:
 void setX(int a);
 //Function to set the value of x
 //Postcondition: x = a;
 void print() const;
 //Function to output the value of x

private:
 int x;
};
```

The definition of the member function is as follows:

```
void classExample::setX(int a)
{
 x = a;
}

void classExample::print() const
{
 cout << "x = " << x << endl;
}
```

Consider the following function main:

```
int main()
{
 classExample *cExpPtr; //Line 1
 classExample cExpObject; //Line 2

 cExpPtr = &cExpObject; //Line 3


 cExpPtr->setX(5); //Line 4
 cExpPtr->print(); //Line 5

 return 0;
}
```

#### Sample Run:


```
x = 5
```

In the function `main`, the statement in Line 1 declares `cExpPtr` to be a pointer of type `classExample`, and the statement in Line 2 declares `cExpObject` to be an object of type `classExample`. The statement in Line 3 stores the address of `cExpObject` into `cExpPtr` (see Figure 14-3).



**FIGURE 14-3** `cExpObject` and `cExpPtr` after the statement `cExpPtr = &cExpObject;` executes

In the statement in Line 4, the pointer `cExpPtr` accesses the member function `setX` to set the value of the member variable `x` (see Figure 14-4).



**FIGURE 14-4** `cExpObject` and `cExpPtr` after the statement `cExpPtr->setX(5);` executes

In the statement in Line 5, the pointer `cExpPtr` accesses the member function `print` to print the value of `x`, as shown above.

## Initializing Pointer Variables

Because C++ does not automatically initialize variables, pointer variables must be initialized if you do not want them to point to anything. Pointer variables are initialized using the constant value `0`, called the **null pointer**. Thus, the statement `p = 0;` stores the null pointer in `p`, that is, `p` points to nothing. Some programmers use the named constant `NULL` to initialize pointer variables. The following two statements are equivalent:

```
p = NULL;
p = 0;
```

The number `0` is the only number that can be directly assigned to a pointer variable.

## Dynamic Variables

In the previous sections, you learned how to declare pointer variables, how to store the address of a variable into a pointer variable of the same type as the variable, and how to manipulate data using pointers. However, you learned how to use pointers to manipulate data only into memory spaces that were created using other variables. In other words, the pointers manipulated data into existing memory spaces. So what is the benefit to using

pointers? You can access these memory spaces by working with the variables that were used to create them. In this section, you will learn about the power behind pointers. In particular, you will learn how to allocate and deallocate memory during program execution using pointers.

Variables that are created during program execution are called **dynamic variables**. With the help of pointers, C++ creates dynamic variables. C++ provides two operators, **new** and **delete**, to create and destroy dynamic variables, respectively. When a program requires a new variable, the operator **new** is used. When a program no longer needs a dynamic variable, the operator **delete** is used.

In C++, **new** and **delete** are reserved words.

## Operator new

The operator **new** has two forms: one to allocate a single variable and another to allocate an array of variables. The syntax to use the operator **new** is:

```
new dataType; //to allocate a single variable
new dataType[intExp]; //to allocate an array of variables
```

in which **intExp** is any expression evaluating to a positive integer.

The operator **new** allocates memory (a variable) of the designated type and returns a pointer to it—that is, the address of this allocated memory. Moreover, the allocated memory is uninitialized.

Consider the following declaration:

```
int *p;
char *q;
int x;
```

The statement:

```
p = &x;
```

stores the address of **x** in **p**. However, no new memory is allocated. On the other hand, consider the following statement:

```
p = new int;
```

This statement creates a variable during program execution somewhere in memory and stores the address of the allocated memory in **p**. The allocated memory is accessed via pointer dereferencing—namely, **\*p**. Similarly, the statement:

```
q = new char[16];
```

creates an array of 16 components of type **char** and stores the base address of the array in **q**.

Because a dynamic variable is unnamed, it cannot be accessed directly. It is accessed indirectly by the pointer returned by `new`. The following statements illustrate this concept:

```
int *p; //p is a pointer of type int
char *name; //name is a pointer of type char
string *str; //str is a pointer of type string

p = new int; //allocates memory of type int
 //and stores the address of the
 //allocated memory in p
*p = 28; //stores 28 in the allocated memory

name = new char[5]; //allocates memory for an array of
 //five components of type char and
 //stores the base address of the array
 //in name
strcpy(name, "John"); //stores John in name

str = new string; //allocates memory of type string
 //and stores the address of the
 //allocated memory in str
*str = "Sunny Day"; //stores the string "Sunny Day" in
 //the memory pointed to by str
```

#### NOTE

Recall that the operator `new` allocates memory space of a specific type and returns the address of the allocated memory space. However, if the operator `new` is unable to allocate the required memory space (for example, there is not enough memory space), then it throws a `bad_alloc` exception, and if this exception is not handled, it terminates the program with an error message. Exceptions are covered in detail in Chapter 16. This chapter also discusses `bad_alloc` exception.

## Operator delete


Suppose you have the following declaration:

```
int *p;
```

This statement declares `p` to be a pointer variable of type `int`. Next, consider the following statements:

```
p = new int; //Line 1
*p = 54; //Line 2
p = new int; //Line 3
*p = 73; //Line 4
```

Figure 14-5 shows the effect of these statements.



**FIGURE 14-5** `p` after the memory space it points to following the execution of various statements

(The number 1500 on top of the box indicates the address of the memory space.) The statement in Line 1 allocates memory space of type `int` and stores the address of the allocated memory space into `p`. Suppose that the address of allocated memory space is 1500. Then, the value of `p` after the execution of this statement is 1500 (see Figure 14-5(a)). The statement in Line 2 stores 54 into the memory space that `p` points to, which is 1500 (see Figure 14-5(b)).

Next, the statement in Line 3 executes, which allocates a memory space of type `int` and stores the address of the allocated memory space into `p`. Suppose the address of this allocated memory space is 1800. It follows that the value of `p` is now 1800 (see Figure 14-5(c)). The statement in Line 4 stores 73 into the memory space that `p` points to, which is 1800. In other words, after the execution of the statement in Line 4, the value stored into memory space at location 1800 is 73 (see Figure 14-5(d)).

Now the obvious question is what happened to the memory space 1500 that `p` was pointing to after execution of the statement in Line 1. After execution of the statement in Line 3, `p` points to the new memory space at location 1800. The previous memory space at location 1500 is now inaccessible. In addition, the memory space 1500 remains as marked allocated. In other words, it cannot be reallocated. This is called **memory leak**. That is, there is an unused memory space that cannot be allocated.

Imagine what would happen if you executed statements, such as Line 3, a few thousand or a few million times. There would be a good amount of memory leak. The program might then run out of memory spaces for data manipulation and eventually result in an abnormal termination of the program.

The question at hand is how to *avoid* memory leak. When a dynamic variable is no longer needed, it can be destroyed; that is, its memory can be deallocated. The C++

operator `delete` is used to destroy dynamic variables. The syntax to use the operator `delete` has two forms:

```
delete pointerVariable; //to deallocate a single
 //dynamic variable
delete [] pointerVariable; //to deallocate a dynamically
 //created array
```

Thus, given the declarations of the previous section, the statements:

```
delete p;
delete [] name;
delete str;
```

deallocate the memory spaces that the pointers `p`, `name`, and `str` point to.

Suppose `p` and `name` are pointer variables, as declared previously. Notice that an expression such as:

```
delete p;
```

or:

```
delete [] name;
```

only marks the memory spaces that these pointer variables point to as deallocated. Depending on a particular system, after these statements execute, these pointer variables may still contain the addresses of the deallocated memory spaces. In this case, we say that these pointers are **dangling**. Therefore, if later you access the memory spaces via these pointers without properly initializing them, depending on a particular system, either the program will access a wrong memory space, which may result in corrupting data, or the program will terminate with an error message. One way to avoid this pitfall is to set these pointers to `NULL` after the `delete` operation. Also note that for the operator `delete` to work properly, the pointer must point to a valid memory space.

## Operations on Pointer Variables

The operations that are allowed on pointer variables are the assignment and relational operations and some limited arithmetic operations. The value of one pointer variable can be assigned to another pointer variable of the same type. Two pointer variables of the same type can be compared for equality, and so on. Integer values can be added and subtracted from a pointer variable. The value of one pointer variable can be subtracted from another pointer variable.

For example, suppose that we have the following statements:

```
int *p, *q;
```

The statement:

```
p = q;
```

copies the value of `q` into `p`. After this statement executes, both `p` and `q` point to the same memory location. Any changes made to `*p` automatically change the value of `*q`, and vice versa.

The expression:

```
p == q
```

evaluates to `true` if `p` and `q` have the same value—that is, if they point to the same memory location. Similarly, the expression:

```
p != q
```

evaluates to `true` if `p` and `q` point to different memory locations.

The arithmetic operations that are allowed differ from the arithmetic operations on numbers. First, let us use the following statements to explain the increment and decrement operations on pointer variables:

```
int *p;
double *q;
char *chPtr;
studentType *stdPtr; //studentType is as defined before
```

Recall that the size of the memory allocated for an `int` variable is 4 bytes, a `double` variable is 8 bytes, and a `char` variable is 1 byte. The memory allocated for a variable of type `studentType` is then 40 bytes.

The statement:

```
p++; or p = p + 1;
```

increments the value of `p` by 4 bytes because `p` is a pointer of type `int`. Similarly, the statements:

```
q++;
chPtr++;
```

increment the value of `q` by 8 bytes and the value of `chPtr` by 1 byte, respectively. The statement:

```
stdPtr++;
```

increments the value of `stdPtr` by 40 bytes.

The increment operator increments the value of a pointer variable by the size of the memory to which it is pointing. Similarly, the decrement operator decrements the value of a pointer variable by the size of the memory to which it is pointing.

Moreover, the statement:

```
p = p + 2;
```

increments the value of `p` by 8 bytes.

Thus, when an integer is added to a pointer variable, the value of the pointer variable is incremented by the integer times the size of the memory that the pointer is pointing to. Similarly, when an integer is subtracted from a pointer variable, the value of the pointer variable is decremented by the integer times the size of the memory to which the pointer is pointing.

**NOTE**

Pointer arithmetic can be very dangerous. Using pointer arithmetic, the program can accidentally access the memory locations of other variables and change their content without warning, leaving the programmer trying to find out what went wrong. If a pointer variable tries to access either the memory spaces of other variables or an illegal memory space, some systems might terminate the program with an appropriate error message. Always exercise extra care when doing pointer arithmetic.

## Dynamic Arrays

In Chapter 9, you learned how to declare and process arrays. The arrays discussed in Chapter 9 are called static arrays because their size was fixed at compile time. One of the limitations of a static array is that every time you execute the program, the size of the array is fixed, so it might not be possible to use the same array to process different data sets of the same type. One way to handle this limitation is to declare an array that is large enough to process a variety of data sets. However, if the array is very big and the data set is small, such a declaration would result in memory waste. On the other hand, it would be helpful if, during program execution, you could prompt the user to enter the size of the array and then create an array of the appropriate size. This approach is especially helpful if you cannot even guess the array size. In this section, you will learn how to create arrays during program execution and process such arrays.

An array created during the execution of a program is called a **dynamic array**. To create a dynamic array, we use the second form of the `new` operator.

The statement:

```
int *p;
```

declares `p` to be a pointer variable of type `int`. The statement:

```
p = new int[10];
```

allocates 10 contiguous memory locations, each of type `int`, and stores the address of the first memory location into `p`. In other words, the operator `new` creates an array of 10 components of type `int`, it returns the base address of the array, and the assignment operator stores the base address of the array into `p`. Thus, the statement:

```
*p = 25;
```

stores 25 into the first memory location, and the statements:

```
p++; //p points to the next array component
*p = 35;
```

store 35 into the second memory location. Thus, by using the increment and decrement operations, you can access the components of the array. Of course, after performing a few increment operations, it is possible to lose track of the first array component. C++ allows us to use array notation to access these memory locations. For example, the statements:

```
p[0] = 25;
p[1] = 35;
```

store 25 and 35 into the first and second array components, respectively. That is, `p[0]` refers to the first array component, `p[1]` refers to the second array component, and so on. In general, `p[i]` refers to the  $(i + 1)$ th array component. After the preceding statements execute, `p` still points to the first array component. Moreover, the following `for` loop initializes each array component to 0:

```
for (j = 0; j < 10; j++)
 p[j] = 0;
```

in which `j` is an `int` variable.

When the array notation is used to process the array pointed to by `p`, `p` stays fixed at the first memory location. Moreover, `p` is a dynamic array created during program execution.

#### NOTE

The statement:

```
int list[5];
```

declares `list` to be an array of five components. Recall from Chapter 9 that `list` itself is a variable, and the value stored in `list` is the base address of the array—that is, the address of the first array component. Suppose the address of the first array component is 1000. Figure 14-6 shows `list` and the array `list`.





FIGURE 14-6 `list` and array `list`

Because the value of `list`, which is 1000, is a memory address, `list` is a pointer variable. However, the value stored in `list`, which is 1000, *cannot be altered during*

*program execution.* That is, the value of `list` is *constant*. Therefore, the increment and decrement operations cannot be applied to `list`. In fact, any attempt to use the increment or decrement operations on `list` results in a compile-time error.

Notice that here, we are *only* saying that the value of `list` cannot be changed. However, the data into the array `list` can be manipulated as before. For example, the statement `list[0] = 25;` stores 25 into the first array component. Similarly, the statement `list[3] = 78;` stores 78 into the fourth component of `list` (see Figure 14-7).



**FIGURE 14-7** Array `list` after the execution of the statements `list[0] = 25;` and `list[3] = 78;`

If `p` is a pointer variable of type `int`, then the statement:

```
p = list;
```

copies the value of `list`, which is 1000, the base address of the array, into `p`. We are allowed to perform increment and decrement operations on `p`.

*An array name is a constant pointer.*

## EXAMPLE 14-5

The following program segment illustrates how to obtain a user's response to get the array size and create a dynamic array during program execution. Consider the following statements:

```
int *intList; //Line 1
int arraySize; //Line 2

cout << "Enter array size: "; //Line 3
cin >> arraySize; //Line 4
cout << endl; //Line 5

intList = new int[arraySize]; //Line 6
```

The statement in Line 1 declares `intList` to be a pointer of type `int`, and the statement in Line 2 declares `arraySize` to be an `int` variable. The statement in Line 3 prompts the user to enter the size of the array, and the statement in Line 4 inputs the array size into the variable `arraySize`. The statement in Line 6 creates an array of the size specified by `arraySize`, and the base address of the array is stored in `intList`. From this point on, you can treat `intList` just like any other array. For example, you can use the array notation to process the elements of `intList` and pass `intList` as a parameter to the function.

---

## Functions and Pointers

A pointer variable can be passed as a parameter to a function either by value or by reference. To declare a pointer as a value parameter in a function heading, you use the same mechanism as you use to declare a variable. To make a formal parameter be a reference parameter, you use `&` when you declare the formal parameter in the function heading. Therefore, to declare a formal parameter as a reference pointer parameter, between the data type name and the identifier name, you must include `*` to make the identifier a pointer and `&` to make it a reference parameter. The obvious question is: In what order should `&` and `*` appear between the data type name and the identifier to declare a pointer as a reference parameter? In C++, to make a pointer a reference parameter in a function heading, `*` appears before the `&` between the data type name and the identifier. The following example illustrates this concept.

```
void pointerParameters(int* &p, double *q)
{
 .
 .
 .
}
```

In the function `pointerParameters`, both `p` and `q` are pointers. The parameter `p` is a reference parameter; the parameter `q` is a value parameter. Furthermore, the function `pointerParameters` can change the value of `*q`, but not the value of `q`. However, the function `pointerParameters` can change the value of both `p` and `*p`.

## Pointers and Function Return Values

In C++, the return type of a function can be a pointer. For example, the return type of the function:

```
int* testExp(...)
{
 .
 .
 .
}
```

is a pointer type `int`.

## Dynamic Two-Dimensional Arrays

The beginning of this section discussed how to create dynamic one-dimensional arrays. You can also create dynamic multidimensional arrays. In this section, we discuss how to create dynamic two-dimensional arrays. Dynamic multidimensional arrays are created similarly.

There are various ways you can create dynamic dimensional arrays. One way is as follows. Consider the statement:

```
int *board[4];
```

This statement declares `board` to be an array of four pointers wherein each pointer is of type `int`. Because `board[0]`, `board[1]`, `board[2]`, and `board[3]` are pointers, you can now use these pointers to create the rows of `board`. Suppose that each row of `board` has six columns. Then, the following `for` loop creates the rows of `board`.

```
for (int row = 0; row < 4; row++)
 board[row] = new int[6];
```

Note that the expression `new int[6]` creates an array of six components of type `int` and returns the base address of the array. The assignment statement then stores the returned address into `board[row]`. It follows that after the execution of the previous `for` loop, `board` is a two-dimensional array of four rows and six columns.

In the previous `for` loop, if you replace the number 6 with the number 10, then the loop will create a two-dimensional array of four rows and 10 columns. In other words, the number of columns of `board` can be specified during execution. However, the way `board` is declared, the number of rows is fixed. So in reality, `board` is not a true dynamic two-dimensional array.

Next, consider the following statement:

```
int **board;
```

This statement declares `board` to be a pointer to a pointer. In other words, `board` and `*board` are pointers. Now `board` can store the address of a pointer or an array of pointers of type `int`, and `*board` can store the address of an `int` memory space or an array of `int` values.

Suppose that you want `board` to be an array of 10 rows and 15 columns. To accomplish this, first we create an array of 10 pointers of type `int` and assign the address of that array to `board`. The following statement accomplishes this:

```
board = new int* [10];
```

Next, we create the columns of `board`. The following `for` loop accomplishes this.

```
for (int row = 0; row < 10; row++)
 board[row] = new int[15];
```

To access the components of `board`, you can use the array subscripting notation discussed in Chapter 9.

Note that the number of rows and the number of columns of `board` can be specified during program execution. The following program further explains how to create two-dimensional arrays.

### EXAMPLE 14-6

```
// Dynamic two-dimensional arrays

#include <iostream>
#include <iomanip>

using namespace std;

void fill(int **p, int rowSize, int columnSize);
void print(int **p, int rowSize, int columnSize);

int main()
{
 int **board; //Line 1

 int rows; //Line 2
 int columns; //Line 3

 cout << "Line 4: Enter the number of rows "
 <<"and columns: "; //Line 4
 cin >> rows >> columns; //Line 5
 cout << endl; //Line 6

 //Create the rows of board
 board = new int* [rows]; //Line 7

 //Create the columns of board
 for (int row = 0; row < rows; row++) //Line 8
 board[row] = new int[columns]; //Line 9

 //Insert elements into board
 fill(board, rows, columns); //Line 10

 cout << "Line 11: Board:" << endl; //Line 11

 //Output the elements of board
 print(board, rows, columns); //Line 12

 return 0;
}
```

```

void fill(int **p, int rowSize, int columnSize)
{
 for (int row = 0; row < rowSize; row++)
 {
 cout << "Enter " << columnSize << " number(s) for row "
 << "number " << row << ": ";
 for (int col = 0; col < columnSize; col++)
 cin >> p[row][col];
 cout << endl;
 }
}

void print(int **p, int rowSize, int columnSize)
{
 for (int row = 0; row < rowSize; row++)
 {
 for (int col = 0; col < columnSize; col++)
 cout << setw(5) << p[row][col];
 cout << endl;
 }
}

```

**Sample Run:** In this sample run, the user input is shaded.

Line 4: Enter the number of rows and columns: 3 4

Enter 4 number(s) for row number 0: 1 2 3 4

Enter 4 number(s) for row number 1: 5 6 7 8

Enter 4 number(s) for row number 2: 9 10 11 12

Line 11: Board:

|   |    |    |    |
|---|----|----|----|
| 1 | 2  | 3  | 4  |
| 5 | 6  | 7  | 8  |
| 9 | 10 | 11 | 12 |

The preceding program contains the functions `fill` and `print`. The function `fill` prompts the user to enter the elements of a two-dimensional array of type `int`. The function `print` outputs the elements of a two-dimensional array of type `int`.

For the most part, the preceding output is self-explanatory. Let us look at the statements in the function `main`. The statement in Line 1 declares `board` to be a pointer to a pointer of type `int`. The statements in Lines 2 and 3 declare `int` variables `rows` and `columns`. The statement in Line 4 prompts the user to input the number of rows and number of columns. The statement in Line 5 stores the number of rows in the variable `rows` and the number of columns in the variable `columns`. The statement in Line 7 creates the rows of `board`, and the `for` loop in Lines 8 and 9 creates the columns of `board`. The statement in Line 10 uses the function `fill` to fill the array `board`, and the statement in Line 12 uses the function `print` to output the elements of `board`.

## Shallow versus Deep Copy and Pointers

In an earlier section, we discussed pointer arithmetic and explained that if we are not careful, one pointer might access the data of another (completely unrelated) pointer. This event might result in unsuspected or erroneous results. Here, we discuss another peculiarity of pointers. To facilitate the discussion, we will use diagrams to show pointers and their related memory.

Consider the following statements:

```
int *first;
int *second;

first = new int[10];
```

The first two statements declare `first` and `second` pointer variables of type `int`. The third statement creates an array of 10 components, and the base address of the array is stored into `first` (see Figure 14-8). (Note that `first` together with the arrow indicates that `first` points to the allocated memory.)




FIGURE 14-8 Pointer `first` and the array to which it points

Suppose that some meaningful data is stored in the array pointed to by `first`. To be specific, suppose that this array is as shown in Figure 14-9.




FIGURE 14-9 Pointer `first` and its array

Next, consider the following statement:

```
second = first; //Line A
```

This statement copies the value of `first` into `second`. After this statement executes, both `first` and `second` point to the same array, as shown in Figure 14-10.




FIGURE 14-10 `first` and `second` after the statement `second = first;` executes

Let us next execute the following statement:

```
delete [] second;
```

After this statement executes, the array pointed to by `second` is deleted. This action results in Figure 14-11.




FIGURE 14-11 `first` and `second` after the statement `delete [] second;` executes

Because `first` and `second` point to the same array, after the statement:

```
delete [] second;
```

executes, `first` becomes invalid, that is, `first` (as well as `second`) are now dangling pointers. Therefore, if the program later tries to access the memory pointed to by `first`, either the program will access the wrong memory or it will terminate in an error. This case is an example of a shallow copy. More formally, in a **shallow copy**, two or more pointers of the same type point to the same memory; that is, they point to the same data.

On the other hand, suppose that instead of the earlier statement, `second = first;` (in Line A), we have the following statements:

```
second = new int[10];

for (int j = 0; j < 10; j++)
 second[j] = first[j];
```

The first statement creates an array of 10 components of type `int`, and the base address of the array is stored in `second`. The second statement copies the array pointed to by `first` into the array pointed to by `second` (see Figure 14-12).




FIGURE 14-12 `first` and `second` both pointing to their own data

Both `first` and `second` now point to their own data. If `second` deletes its memory, there is no effect on `first`. This case is an example of a deep copy. More formally, in a **deep copy**, two or more pointers have their own data.

From the preceding discussion, it follows that you must know when to use a shallow copy and when to use a deep copy.

## Classes and Pointers: Some Peculiarities

In the previous section, we discussed how to use the arrow notation to access class members via the pointer if a pointer variable is of a class type. Because a class can have pointer member variables, this section discusses some peculiarities of such classes. To facilitate the discussion, we will use the following class:

```
class ptrMemberVarType
{
public:
 .
 .
 .
private:
 int x;
 int lenP;
 int *p;
};
```

Also, consider the following statements (see Figure 14-13):

```
ptrMemberVarType objectOne;
ptrMemberVarType objectTwo;
```




FIGURE 14-13 Objects `objectOne` and `objectTwo`

## Destructor

The object `objectOne` has a pointer member variable `p`. Suppose that during program execution, the pointer `p` creates a dynamic array. When `objectOne` goes out of scope, all of the member variables of `objectOne` are destroyed. However, `p` created a dynamic array, and dynamic memory must be deallocated using the operator `delete`. Thus, if the pointer `p` does not use the `delete` operator to deallocate the dynamic array, the memory space of the dynamic array would stay marked as allocated, even though it cannot be accessed. How do we ensure that when `p` is destroyed, the dynamic memory created by `p` is also destroyed? Suppose that `objectOne` is as shown in Figure 14-14.




FIGURE 14-14 Object `objectOne` and its data

Recall that if a class has a destructor, the destructor automatically executes whenever a class object goes out of scope (see Chapter 12). Therefore, we can put the necessary code in the destructor to ensure that when `objectOne` goes out of scope, the memory created by the pointer `p` is deallocated. For example, the definition of the destructor for the `class ptrMemberVarType` is:

```
ptrMemberVarType::~~ptrMemberVarType()
{
 delete [] p;
}
```

Of course, you must include the destructor as a member of the class in its definition. Let us extend the definition of the `class ptrMemberVarType` by including the destructor. Moreover, the remainder of this section assumes that the definition of the destructor is as given previously—that is, the destructor deallocates the memory space pointed to by `p`.

```
class ptrMemberVarType
{
public:
 ~ptrMemberVarType();
 .
 .
 .


private:
 int x;
 int lenP;
 int *p;
};
```

#### NOTE

For the destructor to work properly, the pointer `p` must have a valid value. If `p` is not properly initialized (that is, if the value of `p` is garbage) and the destructor executes, either the program terminates with an error message or the destructor deallocates an unrelated memory space. For this reason, you should exercise extra caution while working with pointers.

# Assignment Operator

This section describes the limitations of the built-in assignment operators for classes with pointer member variables. Suppose that `objectOne` and `objectTwo` are as shown in Figure 14-15.




**FIGURE 14-15** Objects `objectOne` and `objectTwo`

Recall that one of the built-in operations on classes is the assignment operator. For example, the statement:

```
objectTwo = objectOne;
```

copies the member variables of `objectOne` into `objectTwo`. That is, the value of `objectOne.x` is copied into `objectTwo.x`, and the value of `objectOne.p` is copied into `objectTwo.p`. Because `p` is a pointer, this member-wise copying of the data would lead to a shallow copying of the data. That is, both `objectTwo.p` and `objectOne.p` would point to the same memory space, as shown in Figure 14-16.



**FIGURE 14-16** Objects `objectOne` and `objectTwo` after the statement `objectTwo = objectOne;` executes

Now, if `objectTwo.p` deallocates the memory space to which it points, `objectOne.p` would become invalid. This situation could very well happen if the `class ptrMemberVarType` has a destructor that deallocates the memory space pointed to by `p` when an object of type `ptrMemberVarType` goes out of scope. It suggests that there must be

a way to avoid this pitfall. To avoid this shallow copying of data for classes with a pointer member variable, C++ allows the programmer to extend the definition of the assignment operator. This process is called overloading the assignment operator. Chapter 15 explains how to accomplish this task by using operator overloading. Once the assignment operator is properly overloaded, both `objectOne` and `objectTwo` have their own data, as shown in Figure 14-17.




FIGURE 14-17 Objects `objectOne` and `objectTwo`

## Copy Constructor

When declaring a class object, you can initialize it by using the value of an existing object of the same type. For example, consider the following statement:

```
ptrMemberVarType objectThree(objectOne);
```

The object `objectThree` is being declared and is also being initialized by using the value of `objectOne`. That is, the values of the member variables of `objectOne` are copied into the corresponding member variables of `objectThree`. This initialization is called the default member-wise initialization. The default member-wise initialization is due to the constructor, called the **copy constructor** (provided by the compiler). Just as in the case of the assignment operator, because the `class ptrMemberVarType` has pointer member variables, this default initialization would lead to a shallow copying of the data, as shown in Figure 14-18. (Assume that `objectOne` is given as before.)




FIGURE 14-18 Objects `objectOne` and `objectThree`

Before describing how to overcome this deficiency, let us describe one more situation that could also lead to a shallow copying of the data. The solution to both these problems is the same. Recall that as parameters to a function, class objects can be passed either by reference or by value. Remember that the `class ptrMemberVarType` has the destructor, which deallocates the memory space pointed to by `p`. Suppose that `objectOne` is as shown in Figure 14-19.




FIGURE 14-19 Object `objectOne`

Let us consider the following function prototype:

```
void destroyList(ptrMemberVarType paramObject);
```

The function `destroyList` has a formal value parameter, `paramObject`. Now consider the following statement:

```
destroyList(objectOne);
```

In this statement, `objectOne` is passed as a parameter to the function `destroyList`. Because `paramObject` is a value parameter, the copy constructor copies the member variables of `objectOne` into the corresponding member variables of `paramObject`. Just as in the previous case, `paramObject.p` and `objectOne.p` would point to the same memory space, as shown in Figure 14-20.




FIGURE 14-20 Pointer member variables of objects `objectOne` and `paramObject` pointing to the same array

Because `objectOne` is passed by value, the member variables of `paramObject` should have their own copy of the data. In particular, `paramObject.p` should have its own memory space. How do we ensure that this is, in fact, the case?

If a class has pointer member variables:


- During object declaration, the initialization of one object using the value of another object would lead to a shallow copying of the data if the default member-wise copying of data is allowed.
- If, as a parameter, an object is passed by value and the default member-wise copying of data is allowed, it would lead to a shallow copying of the data.

In both cases, to force each object to have its own copy of the data, we must override the definition of the copy constructor provided by the compiler; that is, we must provide our own definition of the copy constructor. This is usually done by putting a statement that includes the copy constructor in the definition of the class and then writing the definition of the copy constructor. Then, whenever the copy constructor needs to be executed, the system would execute the definition provided by us, not the one provided by the compiler. Therefore, for the `class ptrMemberVarType`, we can overcome this shallow copying problem by including the copy constructor in the `class ptrMemberVarType`. Example 14-6 illustrates this.

The copy constructor automatically executes in three situations (the first two are described previously).

- When an object is declared and initialized by using the value of another object
- When, as a parameter, an object is passed by value
- When the return value of a function is an object

Therefore, once the copy constructor is properly defined for the `class ptrMemberVarType`, both `objectOne.p` and `objectThree.p` will have their own copies of the data. Similarly, `objectOne.p` and `paramObject.p` will have their own copies of the data, as shown in Figure 14-21.



**FIGURE 14-21** Pointer member variables of objects `objectOne` and `paramObject` with their own data

When the function `destroyList` exits, the formal parameter `paramObject` goes out of scope, and the destructor for the object `paramObject` deallocates the memory space pointed to by `paramObject.p`. However, this deallocation has no effect on `objectOne`.

The general syntax to include the copy constructor in the definition of a class is:

```
className(const className& otherObject);
```

Notice that the formal parameter of the copy constructor is a constant reference parameter.

Example 14-7 illustrates how to include the copy constructor in a class and how it works.

### EXAMPLE 14-7

Consider the following class:

```
class ptrMemberVarType
{
public:
 void print() const;
 //Function to output the data stored in the array p.

 void insertAt(int index, int num);
 //Function to insert num into the array p at the
 //position specified by index.
 //If index is out of bounds, the program is terminated.
 //If index is within bounds, but greater than the index
 //of the last item in the list, num is added at the end
 //of the list.

 ptrMemberVarType(int size = 10);
 //Constructor
 //Creates an array of the size specified by the
 //parameter size; the default array size is 10.

 ~ptrMemberVarType();
 //Destructor
 //deallocates the memory space occupied by the array p.

 ptrMemberVarType(const ptrMemberVarType& otherObject);
 //Copy constructor

private:
 int maxSize; //variable to store the maximum size of p
 int length; //variable to store the number elements in p
 int *p; //pointer to an int array
};
```

Suppose that the definitions of the members of the `class ptrMemberVarType` are as follows:

```

void ptrMemberVarType::print() const
{
 for (int i = 0; i < length; i++)
 cout << p[i] << " ";
}

void ptrMemberVarType::insertAt(int index, int num)
{
 //if index is out of bounds, terminate the program
 assert(index >= 0 && index < maxSize);

 if (index < length)
 p[index] = num;
 else
 {
 p[length] = num;
 length++;
 }
}

ptrMemberVarType::ptrMemberVarType(int size)
{
 if (size <= 0)
 {
 cout << "The array size must be positive." << endl;
 cout << "Creating an array of the size 10." << endl;

 maxSize = 10;
 }
 else
 maxSize = size;

 length = 0;

 p = new int[maxSize];
}

ptrMemberVarType::~ptrMemberVarType()
{
 delete [] p;
}

//copy constructor
ptrMemberVarType::ptrMemberVarType
 (const ptrMemberVarType& otherObject)
{
 maxSize = otherObject.maxSize;
 length = otherObject.length;
}

```



```

 cout << "Line 23: Calling the function testCopyConst"
 << endl; //Line 23

 //Call function testCopyConst
 testCopyConst(listOne); //Line 24

 cout << "Line 25: After a call to the function "
 << "testCopyConst, " << endl
 << " listOne is: "; //Line 25

 listOne.print(); //Line 26
 cout << endl; //Line 27

 return 0; //Line 28
}

void testCopyConst(ptrMemberVarType temp)
{
 cout << "Line 29: *** Inside the function "
 << "testCopyConst ***" << endl; //Line 29

 cout << "Line 30: Object temp data: "; //Line 30
 temp.print(); //Line 31
 cout << endl; //Line 32

 temp.insertAt(3, -100); //Line 33
 cout << "Line 34: After changing temp: "; //Line 34
 temp.print(); //Line 35
 cout << endl; //Line 36

 cout << "Line 37: *** Exiting the function "
 << "testCopyConst ***" << endl; //Line 37
}

```

**Sample Run:** In this sample run, the user input is shaded.

Line 4: Enter 5 integers.

14 8 34 2 58

Line 8: listOne: 14 8 34 2 58

Line 12: listTwo: 14 8 34 2 58

Line 17: After modifying listTwo: 14 8 -76 2 58 34

Line 20: After modifying listTwo, listOne: 14 8 34 2 58

Line 23: Calling the function testCopyConst

Line 29: \*\*\* Inside the function testCopyConst \*\*\*

Line 30: Object temp data: 14 8 34 2 58

Line 34: After changing temp: 14 8 34 -100 58

Line 37: \*\*\* Exiting the function testCopyConst \*\*\*

Line 25: After a call to the function testCopyConst,  
listOne is: 14 8 34 2 58

In the preceding program, the statement in Line 1 declares `listOne` to be an object of type `ptrMemberVarType`. The member variable `p` of `listOne` is an array of size 10, which is

the default array size. The `for` loop in Line 5 reads and stores five integers in `listOne.p`. The statement in Line 9 outputs the numbers stored in `listOne`, that is, the five numbers stored in `p`. (See the output of the line marked Line 8 in the sample run.)

The statement in Line 11 declares `listTwo` to be an object of type `ptrMemberVarType` and also initializes `listTwo` using the values of `listOne`. The statement in Line 13 outputs the numbers stored in `listTwo`. (See the output of the line marked Line 12 in the sample run.)

The statements in Lines 15 and 16 modify `listTwo`, and the statement in Line 18 outputs the modified data of `listTwo`. (See the output of the line marked Line 17 in the sample run.) The statement in Line 21 outputs the data stored in `listOne`. Notice that the data stored in `listOne` is unchanged, even though `listTwo` modified its data. It follows that the copy constructor used to initialize `listTwo` using `listOne` (at Line 11) provides `listTwo` its own copy of the data.

The statements in Lines 23 through 28 show that when `listOne` is passed as a parameter by value to the function `testCopyConst` (see Line 24), the corresponding formal parameter `temp` has its own copy of data. Notice that the function `testCopyConst` modifies the object `temp`; however, the object `listOne` remains unchanged. See the outputs of the lines marked Line 23 (before the function `testCopyConst` is called) and Line 25 (after the function `testCopyConst` terminates) in the sample run. Also notice that when the function `testCopyConst` terminates, the destructor of the `class ptrMemberVarType` deallocates the memory space occupied by `temp.p`, which has no effect on `listOne.p`.

For classes with pointer member variables, three things are normally done:

1. Include the destructor in the class.
2. Overload the assignment operator for the class.
3. Include the copy constructor.

Chapter 15 discusses overloading the assignment operator. Until then, whenever we discuss classes with pointer member variables, out of the three items in the previous list, we will implement only the destructor and the copy constructor.

## Inheritance, Pointers, and Virtual Functions

Recall that as a parameter, a class object can be passed either by value or by reference. Earlier chapters also said that the types of the actual and formal parameters must match. However, in the case of classes, C++ *allows the user to pass an object of a derived class to a formal parameter of the base class type*.

First, let us discuss the case in which the formal parameter is either a reference parameter or a pointer. To be specific, let us consider the following classes:

```
class petType
{
public:
```

```

 void print();
 petType(string n = "");

private:
 string name;
};

class dogType: public petType
{
public:
 void print();
 dogType(string n = "", string b = "");

private:
 string breed;
};

```

The `class` `petType` has three members. The `class` `dogType` is derived from the `class` `petType` and has three members of its own. Both classes have a member function `print`. Suppose that the definitions of the member functions of both classes are as follows:

```

void petType::print()
{
 cout << "Name: " << name;
}

petType::petType(string n)
{
 name = n;
}

void dogType::print()
{
 petType::print();
 cout << ", Breed: " << breed << endl;
}

```

Consider the following function in a user program (client code):

```

void callPrint(petType& p)
{
 p.print();
}

```

The function `callPrint` has a formal reference parameter `p` of type `petType`. You can call the function `callPrint` by using an object of either type `petType` or type `dogType` as a parameter. Moreover, the body of the function `callPrint` calls the member function `print`. Consider the following function `main`:

```

int main()
{
 petType pet("Lucky"); //Line 1
 dogType dog("Tommy", "German Shepherd"); //Line 2

 pet.print(); //Line 3
 cout << endl; //Line 4
 dog.print(); //Line 5
}

```

```

 cout << "*** Calling the function callPrint ***"
 << endl; //Line 6
 callPrint(pet); //Line 7
 cout << endl; //Line 8
 callPrint(dog); //Line 9

 return 0;
}

```

### Sample Run:

```

Name = Lucky
Name = Tommy, Breed = German Shepherd
*** Calling the function callPrint ***
Name = Lucky
Name = Tommy

```

The statements in Lines 1 through 6 are quite straightforward. Let us look at the statements in Lines 7 and 9. The statement in Line 7 calls the function `callPrint` and passes the object `pet` as the parameter; it generates the fourth line of the output. The statement in Line 9 also calls the function `callPrint` but passes the object `dog` as the parameter; it generates the fifth line of the output. The output generated by the statements in Lines 7 and 9 shows only the value of `name`, even though each time a different class object was passed as a parameter. Because in Line 9, object `dog` is passed as a parameter to the function `callPrint`, one would expect that the output generated by the statement in Line 9 should be the same as the second line of the output. What actually occurred is that for both statements (Lines 7 and 9), the member function `print` of the `class petType` was executed. This is due to the fact that the binding of the member function `print` in the body of the function `callPrint` occurred at compile time. Because the formal parameter `p` of the function `callPrint` is of type `petType`, for the statement `p.print();`, the compiler associates the function `print` of the `class petType`. More specifically, in **compile-time binding**, the necessary code to call a specific function is generated by the compiler. (Compile-time binding is also known as **static binding** or **early binding**.)

For the statement in Line 9, the actual parameter is of type `dogType`. Thus, when the body of the function `callPrint` executes, logically the `print` function of object `dog` should execute, which is not the case. So, during program execution, how does C++ correct this problem of making the call to the appropriate function? C++ corrects this problem by providing the mechanism of **virtual functions**. The binding of virtual functions occurs at program execution time, not at compile time. This kind of binding is called **run-time binding** or **late binding**. More formally, in run-time binding, the compiler does not generate the code to call a specific function. Instead, it generates enough information to enable the run-time system to generate the specific code for the appropriate function call. Run-time binding is also known as **dynamic binding**.

In C++, virtual functions are declared using the reserved word `virtual`. Let us redefine the previous classes using this feature.

```

class petType
{
public:
 virtual void print(); //virtual function
 petType(string n = "");

private:
 string name;
};

class dogType: public petType
{
public:
 void print();
 dogType(string n = "", string b = "");

private:
 string breed;
};

```

Note that we need to declare a **virtual** function only in the base **class**.

The definition of the member function **print** is the same as before. If we execute the previous program with these modifications, the output is as follows.

### Sample Run:

```

Name: Lucky
Name: Tommy, Breed: German Shepherd
*** Calling the function callPrint ***
Name: Lucky
Name: Tommy, Breed: German Shepherd

```

This output shows that for the statement in Line 9, the **print** function of **dogType** is executed (see the last two lines of the output).

The previous discussion also applies when a formal parameter is a pointer to a class, and a pointer of the derived class is passed as an actual parameter. To illustrate this feature, suppose we have the preceding classes. (We assume that the definition of the **class** **petType** is in the header file **petType.h**, and the definition of the **class** **dogType** is in the header file **dogType.h**.) Consider the following program:

```

#include <iostream>
#include "petType.h"
#include "dogType.h"

using namespace std;

void callPrint(petType *p);

int main()
{
 petType *q; //Line 1
 dogType *r; //Line 2

 q = new petType("Lucky"); //Line 3
 r = new dogType("Tommy", "German Shepherd"); //Line 4
}

```

```

 q->print(); //Line 5
 cout << endl; //Line 6
 r->print(); //Line 7

 cout << "*** Calling the function callPrint ***"
 << endl; //Line 8
 callPrint(q); //Line 9
 cout << endl; //Line 10
 callPrint(r); //Line 11

 return 0;
}

void callPrint(petType *p)
{
 p->print();
}

```

### Sample Run:

```

Name: Lucky
Name: Tommy, Breed: German Shepherd
*** Calling the function callPrint ***
Name: Lucky
Name: Tommy, Breed: German Shepherd

```

The preceding examples show that if a formal parameter, say **p** of a class type, is either a reference parameter or a pointer and **p** uses a virtual function of the base class, we can effectively pass a derived class object as an actual parameter to **p**.

However, if **p** is a *value parameter*, then this mechanism of passing a derived class object as an actual parameter to **p** does not work, even if **p** uses a virtual function. Recall that, if a formal parameter is a value parameter, the value of the actual parameter is copied into the formal parameter. Therefore, if a formal parameter is of a **class** type, the member variables of the actual object are copied into the corresponding member variables of the formal parameter.

Suppose that we have the above classes—that is, **petType** and **dogType**. Consider the following function definition:

```

void callPrint(petType p) //p is a value parameter
{
 p.print();
}

```

Further suppose that we have the following declaration:

```
dogType dog;
```

The object **dog** has two member variables, **name** and **breed**. The member variable **name** is inherited from the base class. Consider the following function call:

```
callPrint(dog);
```

In this statement, because the formal parameter `p` is a value parameter, the member variables of `dog` are copied into the member variables of `p`. However, because `p` is an object of type `petType`, it has only one member variable. Consequently, only the member variable `name` of `dog` will be copied into the member variable `name` of `p`. Also, the statement:

```
p.print();
```

in the body of the function will result in executing the member function `print` of the `class` `petType`.

The output of the following program further illustrates this concept. (As before, we assume that the definition of the `class` `petType` is in the header file `petType.h`, and the definition of the `class` `dogType` is in the header file `dogType.h`.)

#### //Chapter 14: Virtual Functions and Value Parameters

```
#include <iostream>
#include "petType.h"
#include "dogType.h"

using namespace std;

void callPrint(petType p);

int main()
{
 petType pet("Lucky"); //Line 1
 dogType dog("Tommy", "German Shepherd"); //Line 2

 pet.print(); //Line 3
 cout << endl; //Line 4
 dog.print(); //Line 5

 cout << "*** Calling the function callPrint ***"
 << endl; //Line 6
 callPrint(pet); //Line 7
 cout << endl; //Line 8
 callPrint(dog); //Line 9
 cout << endl; //Line 10

 return 0;
}

void callPrint(petType p) //p is a value parameter
{
 p.print();
}
```

#### Sample Run:

```
Name: Lucky
Name: Tommy, Breed: German Shepherd
*** Calling the function callPrint ***
Name: Lucky
Name: Tommy
```

Look closely at the output of the statements in Lines 7 and 9 (the last two lines of output). In Line 9, because the formal parameter `p` is a value parameter, the member variables of `dog` are copied into the corresponding member variables of `p`. However, because `p` is an object of type `petType`, it has only one member variable. Consequently, only the member variable `name` of `dog` is copied into the member variable `name` of `p`. Moreover, the statement `p.print();` in the function `callPrint` executes the function `print` of the `class` `petType`, not of the `class` `dogType`. Therefore, the last line of the output shows only the value of `name` (the member variable of `dog`).

**NOTE**

An object of the base class type cannot be passed to a formal parameter of the derived class type.

Before closing this section, we discuss another issue related to virtual functions.

Suppose that the definition of the `class` `petType` is as before, and the definition of the `class` `dogType` is modified slightly as follows:

```
class dogType: public petType
{
public:
 void print();
 void setBreed(string b = "");
 dogType(string n = "", string b = "");

private:
 string breed;
};
```

Consider the following statements:

```
petType pet("Lucky");
dogType dog("Tommy", "German Shepherd");

pet = dog;
```

C++ allows this type of assignment, that is, the values of a derived class object can be copied into a base class object. (Note that the reverse statement, that is, `dog = pet;` is not allowed.) Now, because the object `pet` has only one data member (`name`) and the object `dog` has two data members (`name` and `breed`), only the value of the data member `name` of `dog` is copied into the data member `name` of `pet`. This is called the **slicing problem**. The following statement will result in a compile-time error.

```
pet.setBreed("Siberian Husky");
```

C++ offers a way to treat a `dogType` object as a `petType` object without losing the additional properties of the `class` `dogType` by using pointers.

For example, suppose that you have the following statements:

```
petType *pet;
dogType *dog;

dog = new dogType("Tommy", "German Shepherd");
dog->setBreed("Siberian Husky ");

pet = dog;
```

In this case, the output of the statements `pet->print()`;

is: **Name: Tommy, Breed: Siberian Husky**

## Classes and Virtual Destructors

One thing recommended for classes with pointer member variables is that these classes should have the destructor. The destructor executes automatically when the class object goes out of scope. Thus, if the object creates dynamic memory space, the destructor can be designed to deallocate that memory space. If a derived class object is passed to a formal parameter of the base class type, the destructor of the base class executes regardless of whether the derived class object is passed by reference or by value. Logically, however, the destructor of the derived class should be executed when the derived class object goes out of scope.

To correct this problem, the destructor of the base class must be virtual. The **virtual destructor** of a base class automatically makes the destructor of a derived class virtual. When a derived class object is passed to a formal parameter of the base class type, then when the object goes out of scope, the destructor of the derived class executes. After executing the destructor of the derived class, the destructor of the base class executes. Therefore, when the derived class object is destroyed, the base class part (that is, the members inherited from the base class) of the derived class object is also destroyed.

If a base class contains virtual functions, make the destructor of the base class virtual.

## Abstract Classes and Pure Virtual Functions

The preceding sections discussed virtual functions. Other than enforcing run-time binding of functions, virtual functions also have another use, which is discussed in this section. Chapter 13 discussed the second principal of OOD—inheritance. Through inheritance we can derive new classes without designing them from scratch. The derived classes, in addition to inheriting the existing members of the base class, can add their own members and also redefine or override public and protected member functions of the base class. The base class can contain functions that you would want each derived class to implement. There are many scenarios for which a class is desired to be served as a base class for a number of derived classes; however, the base class may contain certain functions that may not have meaningful definitions in the base class.

Let us consider the `class shape` given in Chapter 13. As noted in that chapter, from the `class shape`, you can derive other `classes`, such as `rectangle`, `circle`, `ellipse`,

and so on. Some of the things common to every shape are its center, using the center to move a shape to a different location, and drawing the shape. We can include these in the `class shape`. For example, you could have the definition of the `class shape` similar to the following:

```
class shape
{
public:
 virtual void draw();
 //Function to draw the shape.

 virtual void move(double x, double y);
 //Function to move the shape at the position
 //(x, y).

 .
 .
 .
};
```

Because the definitions of the functions `draw` and `move` are specific to a particular shape, each derived class can provide an appropriate definition of these functions. Note that we have made the functions `draw` and `move` `virtual` to enforce run-time binding of these functions.

This definition of the `class shape` requires you to write the definitions of the functions `draw` and `move`. However, at this point, there is no shape to draw or move. Therefore, these function bodies have no code. One way to handle this is to make the body of these functions empty. This solution would work, but it has another drawback. Once we write the definitions of the functions of the `class shape`, then we could create an object of this class. Because there is no shape to work with, we would like to prevent the user from creating objects of the `class shape`. It follows that we would like to do the following two things—to not include the definitions of the functions `draw` and `move` and to prevent the user from creating objects of the `class shape`.

Because we do not want to include the definitions of the functions `draw` and `move` of the `class shape`, we must convert these functions to **pure virtual functions**. In this case, the prototypes of these functions are:

```
virtual void draw() = 0;
virtual void move(double x, double y) = 0;
```

Note the expression `= 0` before the semicolon. Once you make these functions pure `virtual` functions in the `class shape`, you no longer need to provide the definitions of these functions for the `class shape`.

Once a class contains one or more pure virtual functions, then that class is called an **abstract class**. Thus, the abstract definition of the `class shape` is similar to the following:

```

class shape
{
public:
 virtual void draw() = 0;
 //Function to draw the shape. Note that this is a
 //pure virtual function.
 virtual void move(double x, double y) = 0;
 //Function to move the shape at the position
 //(x, y). Note that this is a pure virtual
 //function.
 .
 .
 .
};

```

Because an abstract class is *not* a complete class, as it (or its implementation file) does not contain the definitions of certain functions, you cannot create objects of that class.

Now suppose that we derive the `class rectangle` from the `class shape`. To make `rectangle` a nonabstract class so that we can create objects of this class, the class (or its implementation file) must provide the definitions of the pure `virtual` functions of its base class, which is the `class shape`.

Note that in addition to the pure virtual functions, an abstract class can contain instance variables, constructors, and functions that are not pure virtual. However, the abstract class must provide the definitions of the constructor and functions that are not pure virtual. The following example further illustrates how abstract classes work.

#### EXAMPLE 14-8

In Chapter 13, we defined the `class partTimeEmployee`, which was derived from the `class personType`, to illustrate inheritance. We also noted that there are two types of employees full-time and part-time. The base salary of a full-time employee is usually fixed for a year. In addition, a full-time employee may receive a bonus. On the other hand, the salary of a part-time employee is usually calculated according to the pay rate per hour and the number of hours worked. In this example, we first define the `class employeeType`, derived from the `class personType`, to store an employee's name and ID. We include functions to set the ID and retrieve the ID. We also include pure `virtual` functions `print` and `calculatePay` to print an employee's data, which includes the employee's ID, name, and wages.

From the `class employeeType`, we derive the `classes fullTimeEmployee` and `partTimeEmployee` and provide the definitions of the pure `virtual` functions of the `class employeeType`.

The definition of the `class` `employeeType` is:

```
#include "personType.h"

class employeeType: public personType
{
public:
 virtual void print() const = 0;
 //Function to output employee's data.
 virtual double calculatePay() const = 0;
 //Function to calculate and return the wages.
 //Postcondition: Pay is calculated and returned

 void setId(long id);
 //Function to set the salary.
 //Postcondition: personId = id;

 long getId() const;
 //Function to retrieve the id.
 //Postcondition: returns personId

 employeeType(string first = "", string last = "",
 long id = 0);
 //Constructor with parameters
 //Sets the first name, last name, payRate, and
 //hoursWorked according to the parameters. If
 //no value is specified, the default values are
 //assumed.
 //Postcondition: firstName = first;
 // lastName = last; personId = id;

private:
 long personId; //stores the id
};
```

The definitions of the constructor and functions of the `class` `employeeType` that are not pure `virtual` are:

```
void employeeType::setId(long id)
{
 personId = id;
}

long employeeType::getId() const
{
 return personId;
}

employeeType::employeeType(string first, string last, long id)
 : personType(first, last)
{
 personId = id;
}
```

The definition of the `class` `fullTimeEmployee` is:

```
#include "employeeType.h"

class fullTimeEmployee: public employeeType
{
public:
 void set(string first, string last, long id,
 double salary, double bonus);
 //Function to set the first name, last name,
 //id, and salary according to the parameters.
 //Postcondition: firstName = first; lastName = last;
 // personId = id; empSalary = salary;
 // empBonus = bonus;

 void setSalary(double salary);
 //Function to set the salary.
 //Postcondition: empSalary = salary;

 double getSalary();
 //Function to retrieve the salary.
 //Postcondition: returns empSalary

 void setBonus(double bonus);
 //Function to set the bonus.
 //Postcondition: empBonus = bonus;

 double getBonus();
 //Function to retrieve the bonus.
 //Postcondition: returns empBonus;

 void print() const;
 //Function to output the first name, last name,
 //and the wages.
 //Postcondition: Outputs
 // Id:
 // Name: firstName lastName
 // Wages: $$$$.$$

 double calculatePay() const;
 //Function to calculate and return the wages.
 //Postcondition: Pay is calculated and returned

 fullTimeEmployee(string first = "", string last = "",
 long id = 0, double salary = 0,
 double bonus = 0);
 //Constructor with default parameters.
 //Sets the first name, last name, id, salary, and
 //bonus according to the parameters. If
 //no value is specified, the default values are
 //assumed.
 //Postcondition: firstName = first; lastName = last;
 // personId = id; empSalary = salary;
 // empBonus = bonus;
```

```
private:
 double empSalary;
 double empBonus;
};
```

The definitions of the constructor and functions of the `class` `fullTimeEmployee` are:

```
void fullTimeEmployee::set(string first, string last,
 long id,
 double salary, double bonus)
{
 setName(first, last);
 setId(id);
 empSalary = salary;
 empBonus = bonus;
}

void fullTimeEmployee::setSalary(double salary)
{
 empSalary = salary;
}

double fullTimeEmployee::getSalary()
{
 return empSalary;
}

void fullTimeEmployee::setBonus(double bonus)
{
 empBonus = bonus;
}

double fullTimeEmployee::getBonus()
{
 return empBonus;
}

void fullTimeEmployee::print() const
{
 cout << "Id: " << getId() << endl;
 cout << "Name: ";
 personType::print();
 cout << endl;
 cout << "Wages: $" << calculatePay() << endl;
}

double fullTimeEmployee::calculatePay() const
{
 return empSalary + empBonus;
}
```

```

fullTimeEmployee::fullTimeEmployee(string first, string last,
 long id, double salary,
 double bonus)
 : employeeType(first, last, id)
{
 empSalary = salary;
 empBonus = bonus;
}

```

The definition of the `class` `partTimeEmployee` is:

```

#include "employeeType.h"

class partTimeEmployee: public employeeType
{
public:
 void set(string first, string last, long id, double rate,
 double hours);
 //Function to set the first name, last name, id,
 //payRate, and hoursWorked according to the
 //parameters.
 //Postcondition: firstName = first; lastName = last;
 // personId = id;
 // payRate = rate; hoursWorked = hours

 double calculatePay() const;
 //Function to calculate and return the wages.
 //Postcondition: Pay is calculated and returned.

 void setPayRate(double rate);
 //Function to set the salary.
 //Postcondition: payRate = rate;

 double getPayRate();
 //Function to retrieve the salary.
 //Postcondition: returns payRate;

 void setHoursWorked(double hours);
 //Function to set the bonus.
 //Postcondition: hoursWorked = hours

 double getHoursWorked();
 //Function to retrieve the bonus.
 //Postcondition: returns empBonus;

 void print() const;
 //Function to output the id, first name, last name,
 //and the wages.
 //Postcondition: Outputs
 // Id:
 // Name: firstName lastName
 // Wages: $$$$.$$

```

```

partTimeEmployee(string first = "", string last = "",
 long id = 0,
 double rate = 0, double hours = 0);
 //Constructor with parameters
 //Sets the first name, last name, payRate, and
 //hoursWorked according to the parameters. If
 //no value is specified, the default values are
 //assumed.
 //Postcondition: firstName = first; lastName = last;
 // personId = id, payRate = rate;
 // hoursWorked = hours;

private:
 double payRate; //stores the pay rate
 double hoursWorked; //stores the hours worked
};

```

The definitions of the constructor and functions of the `class` `partTimeEmployee` are:

```

void partTimeEmployee::set(string first, string last, long id,
 double rate, double hours)
{
 setName(first, last);
 setId(id);
 payRate = rate;
 hoursWorked = hours;
}

void partTimeEmployee::setPayRate(double rate)
{
 payRate = rate;
}

double partTimeEmployee::getPayRate()
{
 return payRate;
}

void partTimeEmployee::setHoursWorked(double hours)
{
 hoursWorked = hours;
}

double partTimeEmployee::getHoursWorked()
{
 return hoursWorked;
}

void partTimeEmployee::print() const
{
 cout << "Id: " << getId() << endl;
 cout << "Name: ";
}

```

```

 personType::print();
 cout << endl;
 cout << "Wages: $" << calculatePay() << endl;
 }

 double partTimeEmployee::calculatePay() const
 {
 return (payRate * hoursWorked);
 }

 //constructor
 partTimeEmployee::partTimeEmployee(string first, string last,
 long id,
 double rate, double hours)
 : employeeType(first, last, id)
 {
 payRate = rate;
 hoursWorked = hours;
 }

```

The following function main tests these classes:

```

#include <iostream>
#include "partTimeEmployee.h"
#include "fullTimeEmployee.h"

int main()
{
 fullTimeEmployee newEmp("John", "Smith", 75, 56000, 5700);
 partTimeEmployee tempEmp("Bill", "Nielson", 275, 15.50, 57);

 newEmp.print();
 cout << endl;
 tempEmp.print();

 return 0;
}

```

### Sample Run:

```

Id: 75
Name: John Smith
Wages: $61700

Id: 275
Name: Bill Nielson
Wages: $883.5

```

The preceding output is self-explanatory. We leave the details as an exercise.

## Address of Operator and Classes

---

This chapter has used the address of operator, `&`, to store the address of a variable into a pointer variable. The address of operator is also used to create aliases to an object. Consider the following statements:

```
int x;
int &y = x;
```

The first statement declares `x` to be an `int` variable, and the second statement declares `y` to be an alias of `x`. That is, both `x` and `y` refer to the same memory location. Thus, `y` is like a constant pointer variable. The statement:

```
y = 25;
```

sets the value of `y` and, hence, the value of `x` to 25. Similarly, the statement:

```
x = 2 * x + 30;
```

updates the value of `x` and, hence, the value of `y`.

The address of operator can also be used to return the address of a `private` member variable of a class. However, if you are not careful, this operation can result in serious errors in the program. The following example helps illustrate this idea.

Consider the following class definition:

```
//header file testadd.h

#ifndef H_testAdd
#define H_testAdd

class testAddress
{
public:
 void setX(int);
 void printX() const;
 int& addressOfX(); //this function returns the address
 //of the x
private:
 int x;
};

#endif
```

The definitions of the functions to implement the member functions are as follows:

```
//Implementation file testAdd.cpp

#include <iostream>
#include "testAdd.h"
```

```
using namespace std;

void testAddress::setX(int inX)
{
 x = inX;
}
void testAddress::printX() const
{
 cout << x;
}

int& testAddress::addressOfX()
{
 return x;
}
```

Because the return type of the function `addressOfX`, which is `int&`, is an address of an `int` memory location, the effect of the statement:

```
return x;
```

is that the address of `x` is returned.

Next, let us write a simple program that uses the `class testAddress` and illustrates what can go wrong. Later, we will show how to fix the problem.

```
//Test program.
#include <iostream>
#include "testAdd.h"

using namespace std;

int main()
{
 testAddress a;
 int &y = a.addressOfX();

 a.setX(50);
 cout << "x in class testAddress = ";
 a.printX();
 cout << endl;

 y = 25;
 cout << "After y = 25, x in class testAddress = ";
 a.printX();
 cout << endl;

 return 0;
}
```

### Sample Run:

```
x in class testAddress = 50
After y = 25, x in class testAddress = 25
```

In the preceding program, after the statement:

```
int &y = a.addressOfX();
```

executes, `y` becomes an alias of the `private` member variable `x` of the object `a`. Thus, the statement:

```
y = 25;
```

changes the value of `x`.

Chapter 12 said that `private` member variables are not accessible outside of the class. However, by returning their addresses, the programmer can manipulate them. One way to resolve this problem is to never provide the user of the class with the addresses of the `private` member variables. Sometimes, however, it is necessary to return the address of a `private` member variable, as we will see in the next chapter. How can we prevent the program from directly manipulating the `private` member variables? To fix this problem, we use the word `const` before the return type of the function. This way, we can still return the addresses of the `private` member variables, but at the same time prevent the programmer from directly manipulating the `private` member variables. Let us rewrite the `class testAddress` using this feature.

```
#ifndef H_testAdd
#define H_testAdd

class testAddress
{
public:
 void setX(int);
 void printX() const;
 const int& addressOfX(); //this function returns the
 //address of the private data
 //member

private:
 int x;
};

#endif
```

The definition of the function `addressOfX` in the implementation file is:

```
const int& testAddress::addressOfX()
{
 return x;
}
```

The same program will now generate a compile-time error.

## QUICK REVIEW

---

1. Pointer variables contain the addresses of other variables as their values.
2. In C++, no name is associated with the pointer data type.

3. A pointer variable is declared using an asterisk, \*, between the data type and the variable. For example, the statements:

```
int *p;
char *ch;
```

declare **p** and **ch** to be pointer variables. The value of **p** points to a memory space of type **int**, and the value of **ch** points to a memory space of type **char**. Usually, **p** is called a pointer variable of type **int**, and **ch** is called a pointer variable of type **char**.

4. In C++, & is called the address of operator.
5. The address of operator returns the address of its operand. For example, if **p** is a pointer variable of type **int** and **num** is an **int** variable, the statement:

```
p = #
```

sets the value of **p** to the address of **num**.

6. When used as a unary operator, \* is called the dereferencing operator.
7. The memory location indicated by the value of a pointer variable is accessed by using the dereferencing operator, \*. For example, if **p** is a pointer variable of type **int**, the statement:

```
*p = 25;
```

sets the value of the memory location indicated by the value of **p** to 25.

8. You can use the member access operator arrow, ->, to access the component of an object pointed to by a pointer.
9. Pointer variables are initialized using either 0 (the integer zero), NULL, or the address of a variable of the same type.
10. The only number that can be directly assigned to a pointer variable is 0.
11. The only arithmetic operations allowed on pointer variables are increment (++), decrement (--), addition of an integer to a pointer variable, subtraction of an integer from a pointer variable, and subtraction of a pointer from another pointer.
12. Pointer arithmetic is different than ordinary arithmetic. When an integer is added to a pointer, the value added to the value of the pointer variable is the integer times the size of the object to which the pointer is pointing. Similarly, when an integer is subtracted from a pointer, the value subtracted from the value of the pointer variable is the integer times the size of the object to which the pointer is pointing.
13. Pointer variables can be compared using relational operators. (It makes sense to compare pointers of the same type.)
14. The value of one pointer variable can be assigned to another pointer variable of the same type.
15. A variable created during program execution is called a dynamic variable.

16. The operator `new` is used to create a dynamic variable.
17. The operator `delete` is used to deallocate the memory occupied by a dynamic variable.
18. In C++, both `new` and `delete` are reserved words.
19. The operator `new` has two forms: one to create a single dynamic variable and another to create an array of dynamic variables.
20. If `p` is a pointer of type `int`, the statement:  

```
p = new int;
```

allocates storage of type `int` somewhere in memory and stores the address of the allocated storage in `p`.
21. The operator `delete` has two forms: one to deallocate the memory occupied by a single dynamic variable and another to deallocate the memory occupied by an array of dynamic variables.
22. If `p` is a pointer of type `int`, the statement:  

```
delete p;
```

deallocates the memory pointed to by `p`.
23. The array name is a constant pointer. It always points to the same memory location, which is the location of the first array component.
24. To create a dynamic array, the form of the `new` operator that creates an array of dynamic variables is used. For example, if `p` is a pointer of type `int`, the statement:  

```
p = new int[10];
```

creates an array of 10 components of type `int`. The base address of the array is stored in `p`. We call `p` a dynamic array.
25. Array notation can be used to access the components of a dynamic array. For example, suppose `p` is a dynamic array of 10 components. Then, `p[0]` refers to the first array component, `p[1]` refers to the second array component, and so on. In particular, `p[i]` refers to the  $(i + 1)$ th component of the array.
26. An array created during program execution is called a dynamic array.
27. If `p` is a dynamic array, then the statement:  

```
delete [] p;
```

deallocates the memory occupied by `p`—that is, the components of `p`.
28. C++ allows a program to create dynamic multidimensional arrays.
29. In the statement `int **board;`, the variable `board` is a pointer to a pointer.
30. In a shallow copy, two or more pointers of the same type point to the same memory space; that is, they point to the same data.

31. In a deep copy, two or more pointers of the same type have their own copies of the data.
32. If a class has a destructor, the destructor is automatically executed whenever a class object goes out of scope.
33. If a class has pointer member variables, the built-in assignment operators provide a shallow copy of the data.
34. A copy constructor executes when an object is declared and initialized by using the value of another object and when an object is passed by value as a parameter.
35. C++ allows a user to pass an object of a derived class to a formal parameter of the base class type.
36. The binding of virtual functions occurs at execution time, not at compile time, and is called dynamic, or run-time, binding.
37. In C++, virtual functions are declared using the reserved word **virtual**.
38. A class is called an abstract class if it contains one or more pure virtual functions.
39. Because an abstract class is *not* a complete class—as it (or its implementation file) does not contain the definitions of certain functions—you cannot create objects of that class.
40. In addition to the pure virtual functions, an abstract class can contain instance variables, constructors, and functions that are not pure virtual. However, the abstract class must provide the definitions of constructors and functions that are not pure virtual.
41. The address of operator can be used to return the address of a **private** member variable of a class.

## EXERCISES

---

1. Mark the following statements as true or false.
  - a. In C++, pointer is a reserved word.
  - b. In C++, pointer variables are declared using the word pointer.
  - c. The statement **delete p;** deallocates the variable pointer **p**.
  - d. The statement **delete p;** deallocates the dynamic variable that is pointed to by **p**.
  - e. Given the declaration:
 

```
int list[10];
int *p;
```

 the statement:
 

```
p = list;
```

 is valid in C++.

- f. Given the declaration:

```
int *p;
```

the statement:

```
p = new int[50];
```

dynamically allocates an array of 50 components of type `int`, and `p` contains the base address of the array.

- g. The address of operator returns the address and value of its operand.  
 h. If `p` is a pointer variable, then the statement `p = p * 2;` is valid in C++.

2. Given the declaration:

```
int x;
int *p;
int *q;
```

mark the following statements as valid or invalid. If a statement is invalid, explain why.

- a. `p = q;`  
 b. `*p = 56;`  
 c. `p = x;`  
 d. `*p = *q;`  
 e. `q = &x;`  
 f. `*p = q;`
3. Explain how the operator `*` is used to work with pointers.  
 4. Consider the following statement:

```
int* p, q;
```

This statement could lead to what type of misinterpretation?

5. What is the output of the following C++ code?

```
int x;
int y;
int *p = &x;
int *q = &y;
*p = 35;
*q = 98;
*p = *q;
cout << x << " " << y << endl;
cout << *p << " " << *q << endl;
```

6. What is the output of the following C++ code?

```
int x;
int y;
int *p = &x;
int *q = &y;
x = 35;
y = 46;
p = q;
*p = 78;
```

```
cout << x << " " << y << endl;
cout << *p << " " << *q << endl;
```

7. Given the declaration:

```
int num = 6;
int *p = #
```

which of the following statements increment(s) the value of `num`?

- a. `p++;`
- b. `(*p)++;`
- c. `num++;`
- d. `(*num)++;`

8. What is the output of the following code?

```
int *p;
int *q;
p = new int;
q = p;
*p = 46;
*q = 39;
cout << *p << " " << *q << endl;
```

9. What is the output of the following code?

```
int *p;
int *q;
p = new int;
*p = 43;
q = p;
*q = 52;
p = new int;
*p = 78;
q = new int;
*q = *p;
cout << *p << " " << *q << endl;
```

10. What is the output of the following C++ code?

```
int *p;
int *q;
p = new int;
q = new int;
*p = 27;
*q = 35;
cout << *p << " " << *q << endl;
q = p;
*q = 73;
cout << *p << " " << *q << endl;
p = new int;
*p = 36;
*q = 42;
cout << *p << " " << *q << endl;
```

11. What is the output of the following C++ code?

```
int *p;
int *q;
p = new int;
q = new int;
*p = 27;
*q = 35;
cout << *p << " " << *q << endl;
*q = *p;
*p = 73;
cout << *p << " " << *q << endl;
p = new int;
*p = 36;
q = p;
cout << *p << " " << *q << endl;
```

12. What is wrong with the following code?

```
int *p; //Line 1
int *q; //Line 2

p = new int; //Line 3
*p = 43; //Line 4

q = p; //Line 5
*q = 52; //Line 6

delete q; //Line 7

cout << *p << " " << *q << endl; //Line 8
```

13. What is the output of the following code?

```
int x;
int *p;
int *q;
p = new int[10];
q = p;
*p = 4;

for (int j = 0; j < 10; j++)
{
 x = *p;
 p++;
 *p = x + j;
}

for (int k = 0; k < 10; k++)
{
 cout << *q << " ";
 q++;
}
cout << endl;
```

14. What does the operator `new` do?
15. What does the operator `delete` do?

16. What is the output of the following code?

```
int *secret;
int j;

secret = new int[10];
secret[0] = 10;
for (j = 1; j < 10; j++)
 secret[j] = secret[j - 1] + 5;
for (j = 0; j < 10; j++)
 cout << secret[j] << " ";
cout << endl;
```

17. Consider the following statement:

```
int *num;
```

- Write the C++ statement that dynamically creates an array of 10 components of type `int` and `num` contains the base address of the array.
- Write a C++ code that inputs data into the array `num` from the standard input device.
- Write a C++ statement that deallocates the memory space of array to which `num` points.

18. Consider the following C++ code:

```
int *p;
p = new int[10];
for (int j = 0; j < 10; j++)
 p[j] = 2 * j - 2;
```

Write the C++ statement that deallocates the memory space occupied by the array to which `p` points.

19. Explain the difference between a shallow copy and a deep copy of data.
20. What is wrong with the following code?

```
int *p; //Line 1
int *q; //Line 2

p = new int[5]; //Line 3
*p = 2; //Line 4

for (int i = 1; i < 5; i++) //Line 5
 p[i] = p[i - 1] + i; //Line 6

q = p; //Line 7

delete [] p; //Line 8

for (int j = 0; j < 5; j++) //Line 9
 cout << q[j] << " "; //Line 10

cout << endl; //Line 11
```

21. What is the output of the following code?

```
int *p;
int *q;
int i;

p = new int[5];
p[0] = 5;

for (i = 1; i < 5; i++)
 p[i] = p[i - 1] + 2 * i;

cout << "Array p: ";
for (i = 0; i < 5; i++)
 cout << p[i] << " ";
cout << endl;

q = new int[5];

for (i = 0; i < 5; i++)
 q[i] = p[4 - i];

cout << "Array q: ";
for (i = 0; i < 5; i++)
 cout << q[i] << " ";

cout << endl;
```

22. a. Write a statement that declares **sales** to be a pointer to a pointer of type **double**.
- b. Write a C++ code that dynamically creates a two-dimensional array of five rows and seven columns and **sales** contains the base address of that array.
- c. Write a C++ code that inputs data from the standard input device into the array **sales**.
- d. Write a C++ code that deallocates the memory space occupied by the two-dimensional array to which **sales** points.
23. What is the purpose of a copy constructor?
24. Name two situations in which a copy constructor executes.
25. Name three things that you should do for classes with pointer member variables.
26. Suppose that you have the following classes, **classA** and **classB**:

```
class classA
{
public:
 virtual void print() const;
 void doubleNum();
 classA(int a = 0);

private:
 int x;
};
```

```

void classA::print() const
{
 cout << "ClassA x: " << x << endl;
}

void classA::doubleNum()
{
 x = 2 * x;
}

classA::classA(int a)
{
 x = a;
}

class classB: public classA
{
public:
 void print() const;
 void doubleNum();
 classB(int a = 0, int b = 0);

private:
 int y;
};

void classB::print() const
{
 classA::print();
 cout << "ClassB y: " << y << endl;
}

void classB::doubleNum()
{
 classA::doubleNum();

 y = 2 * y;
}

classB::classB(int a, int b)
 : classA(a)
{
 y = b;
}

```

What is the output of the following function main?

```

int main()
{
 classA *ptrA;
 classA objectA(2);

 classB objectB(3, 5);
}

```

```
ptrA = &objectA;
ptrA->doubleNum();
ptrA->print();
cout << endl;
```

```
ptrA = &objectB;
```

```
ptrA->doubleNum();
ptrA->print();
cout << endl;
```

```
return 0;
```

```
}
```

27. What is the output of the function `main` of Exercise 26, if the definition of `classA` is replaced by the following definition?

```
class classA
{
public:
 virtual void print() const;
 virtual void doubleNum();
 classA(int a = 0);
```

```
private:
 int x;
};
```

28. What is the difference between compile-time binding and run-time binding?
29. Is it legal to have an abstract class with all member functions pure virtual?
30. Consider the following definition of the `class` `studentType`:

```
public studentType: public personType
{
public:
 void print();
 void calculateGPA();
 void setID(long id);
 void setCourses(const string c[], int noOfC);
 void setGrades(const char cG[], int noOfC);

 void getID();
 void getCourses(string c[], int noOfC);
 void getGrades(char cG[], int noOfC);
 void studentType(string fName = "", string lastName = "",
 long id, string c[] = NULL,
 char cG[] = NULL, int noOfC = 0);

private:
 long studentId;
 string courses[6];
 char coursesGrade[6]
 int noOfCourses;
}
```

Rewrite the definition of the `class` `studentType` so that the functions `print` and `calculateGPA` are pure `virtual` functions.

31. Suppose that the definitions of the `classes` `employeeType`, `fullTimeEmployee`, and `partTimeEmployee` are as given in Example 14-8 of this chapter. Which of the following statements is legal?
  - a. `employeeType tempEmp;`
  - b. `fullTimeEmployee newEmp();`
  - c. `partTimeEmployee pEmp("Molly", "Burton", 101, 0.0, 0);`

## PROGRAMMING EXERCISES

---

1. Redo Programming Exercise 5 of Chapter 9 using dynamic arrays.
2. Redo Programming Exercise 6 of Chapter 9 using dynamic arrays.
3. Redo Programming Exercise 7 of Chapter 9 using dynamic arrays. You must ask the user for the number of candidates and then create the appropriate arrays to hold the data.
4. Programming Exercise 11 in Chapter 9 explains how to add large integers using arrays. However, in that exercise, the program could add only integers of, at most, 20 digits. This chapter explains how to work with dynamic integers. Design a `class` named `largeIntegers` such that an object of this class can store an integer of any number of digits. Add operations to add, subtract, multiply, and compare integers stored in two objects. Also add constructors to properly initialize objects and functions to set, retrieve, and print the values of objects.
5. Banks offer various types of accounts, such as savings, checking, certificate of deposits, and money market, to attract customers as well as meet with their specific needs. Two of the most commonly used accounts are savings and checking. Each of these accounts has various options. For example, you may have a savings account that requires no minimum balance but has a lower interest rate. Similarly, you may have a checking account that limits the number of checks you may write. Another type of account that is used to save money for the long term is certificate of deposit (CD).

In this programming exercise, you use abstract classes and pure virtual functions to design classes to manipulate various types of accounts. For simplicity, assume that the bank offers three types of accounts: savings, checking, and certificate of deposit, as described next.

**Savings accounts:** Suppose that the bank offers two types of savings accounts: one that has no minimum balance and a lower interest rate and another that requires a minimum balance and has a higher interest rate.

**Checking accounts:** Suppose that the bank offers three types of checking accounts: one with a monthly service charge, limited check writing, no

minimum balance, and no interest; another with no monthly service charge, a minimum balance requirement, unlimited check writing and lower interest; and a third with no monthly service charge, a higher minimum requirement, a higher interest rate, and unlimited check writing.

**Certificate of deposit (CD):** In an account of this type, money is left for some time, and these accounts draw higher interest rates than savings or checking accounts. Suppose that you purchase a CD for six months. Then we say that the CD will mature in six months. Penalty for early withdrawal is stiff.

Figure 14-22 shows the inheritance hierarchy of these bank accounts.




FIGURE 14-22 Inheritance hierarchy of banking accounts

Note that the classes `bankAccount` and `checkingAccount` are abstract. That is, we cannot instantiate objects of these classes. The other classes in Figure 14-22 are not abstract.

**bankAccount:** Every bank account has an account number, the name of the owner, and a balance. Therefore, instance variables such as `name`, `accountNumber`, and `balance` should be declared in the abstract `class` `bankAccount`. Some operations common to all types of accounts are retrieve account owner's name, account number, and account balance; make deposits; withdraw money; and create monthly statement. So include functions to implement these operations. Some of these functions will be pure virtual.

**checkingAccount:** A checking account is a bank account. Therefore, it inherits all the properties of a bank account. Because one of the objectives of a checking account is to be able to write checks, include the pure virtual function `writeCheck` to write a check.

**serviceChargeChecking:** A service charge checking account is a checking account. Therefore, it inherits all the properties of a checking account. For simplicity, assume that this type of account does not pay any interest, allows the account holder to write a limited number of checks each month, and does not require any minimum balance. Include appropriate named constants, instance variables, and functions in this class.

**noServiceChargeChecking:** A checking account with no monthly service charge is a checking account. Therefore, it inherits all the properties of a checking account. Furthermore, this type of account pays interest, allows the account holder to write checks, and requires a minimum balance.

**highInterestChecking:** A checking account with high interest is a checking account with no monthly service charge. Therefore, it inherits all the properties of a no service charge checking account. Furthermore, this type of account pays higher interest and requires a higher minimum balance than the no service charge checking account.

**savingsAccount:** A savings account is a bank account. Therefore, it inherits all the properties of a bank account. Furthermore, a savings account also pays interest.

**highInterestSavings:** A high-interest savings account is a savings account. Therefore, it inherits all the properties of a savings account. It also requires a minimum balance.

**certificateOfDeposit:** A certificate of deposit account is a bank account. Therefore, it inherits all the properties of a bank account. In addition, it has instance variables to store the number of CD maturity months, interest rate, and the current CD month.

Write the definitions of the classes described in this programming exercise and a program to test your classes.

*This page intentionally left blank*



# 15

## CHAPTER

# OVERLOADING AND TEMPLATES

IN THIS CHAPTER, YOU WILL:

- Learn about overloading
- Become aware of the restrictions on operator overloading
- Examine the pointer `this`
- Learn about `friend` functions
- Explore the members and nonmembers of a class
- Discover how to overload various operators
- Learn about templates
- Explore how to construct function templates and class templates

In Chapter 12, you learned how classes in C++ are used to combine data and operations on that data in a single entity. The ability to combine data and operations on the data is called encapsulation. It is the first principle of object-oriented design (OOD). Chapter 12 defined the abstract data type (ADT) and described how classes in C++ implement ADT. Chapter 13 discussed how new classes can be derived from existing classes through the mechanism of inheritance. Inheritance, the second principle of OOD, encourages code reuse.

This chapter covers **operator overloading** and **templates**. Templates enable the programmer to write generic code for related functions and classes. We will also simplify function overloading (introduced in Chapter 7) through the use of templates, called **function templates**.

## Why Operator Overloading Is Needed

Chapter 12 defined and implemented the `class clockType`. It also showed how you can use the `class clockType` to represent the time of day in a program. Let us review some of the characteristics of the `class clockType`.

Consider the following statements:

```
clockType myClock(8, 23, 34);
clockType yourClock(4, 5, 30);
```

The first statement declares `myClock` to be an object of type `clockType` and initializes the member variables `hr`, `min`, and `sec` of `myClock` to 8, 23, and 34, respectively. The second statement declares `yourClock` to be an object of type `clockType` and initializes the member variables `hr`, `min`, and `sec` of `yourClock` to 4, 5, and 30, respectively.

Now consider the following statements:

```
myClock.printTime();

myClock.incrementSeconds();

if (myClock.equalTime(yourClock))
{
 .
 .
 .
}
```

The first statement prints the value of `myClock` in the form `hr:min:sec`. The second statement increments the value of `myClock` by one second. The third statement checks whether the value of `myClock` is the same as the value of `yourClock`.

These statements do their job. However, if we can use the insertion operator `<<` to output the value of `myClock`, the increment operator `++` to increment the value of `myClock` by one second, and relational operators for comparison, we can enhance the

flexibility of the `class clockType` considerably. More specifically, we prefer to use the following statements instead of the previous statements:

```
cout << myClock;

myClock++;

if (myClock == yourClock)
.
.
.
```

Recall that the only built-in operations on classes are the assignment operator and the member selection operator. Therefore, other operators cannot be directly applied to class objects. However, C++ allows the programmer to extend the definitions of most of the operators so that operators—such as relational operators, arithmetic operators, the insertion operator for data output, and the extraction operator for data input—can be applied to classes. In C++ terminology, this is called **operator overloading**.

## Operator Overloading

Recall how the arithmetic operator `/` works. If both operands of `/` are integers, the result is an integer; otherwise, the result is a floating-point number. Similarly, the stream insertion operator, `<<`, and the stream extraction operator, `>>`, are overloaded. The operator `>>` is used as both a stream extraction operator and a right shift operator. The operator `<<` is used as both a stream insertion operator and a left shift operator. These are examples of operator overloading. (Note that the operators `<<` and `>>` have also been overloaded for various data types, such as `int`, `double`, and `string`.)

Other examples of overloaded operators are `+` and `-`. The results of `+` and `-` are different for integer arithmetic, floating-point arithmetic, and pointer arithmetic.

C++ allows the user to overload most of the operators so that the operators can work effectively in a specific application. It does not allow the user to create new operators. Most of the existing operators can be overloaded to manipulate class objects.

In order to overload operators, you must write functions (that is, the header and body). The name of the function that overloads an operator is the reserved word `operator` followed by the operator to be overloaded. For example, the name of the function to overload the operator `>=` is:

```
operator>=
```

**Operator function:** The function that overloads an operator.

## Syntax for Operator Functions

The result of an operation is a value. Therefore, the operator function is a value-returning function.

The syntax of the heading for an operator function is:

```
returnType operator operatorSymbol(formal parameter list)
```

In C++, **operator** is a reserved word.

Recall that the only built-in operations on classes are assignment (=) and member selection. To use other operators on class objects, they must be explicitly overloaded. Operator overloading provides the same concise expressions for user-defined data types as it does for built-in data types.

To overload an operator for a class:

1. Include the statement to declare the function to overload the operator (that is, the operator function) prototype in the definition of the class.
2. Write the definition of the operator function.

Certain rules must be followed when you include an operator function in a class definition. These rules are described in the section, “Operator Functions as Member Functions and Nonmember Functions” later in this chapter.

## Overloading an Operator: Some Restrictions

When overloading an operator, keep the following in mind:

1. You cannot change the precedence of an operator.
2. The associativity cannot be changed. (For example, the associativity of the arithmetic operator addition is from left to right, and it cannot be changed.)
3. Default parameters cannot be used with an overloaded operator.
4. You cannot change the number of parameters an operator takes.
5. You cannot create new operators. Only existing operators can be overloaded.
6. The operators that cannot be overloaded are:  
`.   .*   ::   ?:   sizeof`
7. The meaning of how an operator works with built-in types, such as `int`, remains the same.
8. Operators can be overloaded either for objects of the user-defined types, or for a combination of objects of the user-defined type and objects of the built-in type.

## Pointer `this`

A member function of a class can (directly) access the member variables of that class for a given object. Sometimes, it is necessary for a member function to refer to the object as a whole, rather than the object's individual member variables. How do you refer to the object as a whole (that is, as a single unit) in the definition of the member function, especially when the object is not passed as a parameter? Every object of a class maintains a (hidden) pointer to itself, and the name of this pointer is `this`. In C++, `this` is a reserved word. The pointer `this` (in a member function) is available for you to use. When an object invokes a member function, the member function references the pointer `this` of the object. For example, suppose that `test` is a class and has a member function called `one`. Further suppose that the definition of `one` looks like the following:

```
test test::one()
{
 .
 .
 .
 return *this;
}
```

If `x` and `y` are objects of type `test`, then the statement:

```
y = x.one();
```

copies the value of object `x` into object `y`. That is, the member variables of `x` are copied into the corresponding member variables of `y`. When object `x` invokes function `one`, the pointer `this` in the definition of member function `one` refers to object `x`, so `this` means the address of `x` and `*this` means the value of `x`.

The following example illustrates how the pointer `this` works.

### EXAMPLE 15-1

Consider the following class:

```
class thisPointerClass
{
public:
 void set(int a, int b, int c);
 void print() const;

 thisPointerClass updateXYZ();
 // Postcondition: x = 2 * x; y = y + 2;
 // z = z * z;

 thisPointerClass(int a = 0, int b = 0, int c = 0);
```

```
private:
```

```
 int x;
 int y;
 int z;
```

```
};
```

Suppose that the definitions of the member functions of the `class thisPointerClass` are as follows:

```
void thisPointerClass::set(int a, int b, int c)
```

```
{
 x = a;
 y = b;
 z = c;
}
```

```
void thisPointerClass::print() const
```

```
{
 cout << "x = " << x
 << ", y = " << y
 << ", z = " << z << endl;
}
```

```
thisPointerClass thisPointerClass::updateXYZ()
```

```
{
 x = 2 * x;
 y = y + 2;
 z = z * z;

 return *this;
}
```

The definition of the function `updateXYZ` updates the values of `x`, `y`, and `z`. Using the pointer `this` returns the value of the entire object. That is, the values of the member variables `x`, `y`, and `z` are returned.

```
thisPointerClass::thisPointerClass(int a, int b, int c)
```

```
{
 x = a;
 y = b;
 z = c;
}
```

Consider the following function `main`:

```
//Chapter 15: this pointer illustration
```

```
#include <iostream>
#include "thisPointerIllus.h"
```

```
using namespace std;
```

```

int main()
{
 thisPointerClass object1(3, 5, 7); //Line 1
 thisPointerClass object2; //Line 2

 cout << "Object 1: "; //Line 3
 object1.print(); //Line 4

 object2 = object1.updateXYZ(); //Line 5

 cout << "After updating object1: "; //Line 6
 object1.print(); //Line 7

 cout << "Object 2: "; //Line 8
 object2.print(); //Line 9

 return 0;
}

```

### Sample Run:

```

Object 1: x = 3, y = 5, z = 7
After updating object1: x = 6, y = 7, z = 49
Object 2: x = 6, y = 7, z = 49

```

For the most part, the output is self-explanatory. The statement in Line 5 evaluates the expression `object1.updateXYZ()`, which updates the values of the member variables of `object1`. The value of `object1` is then returned by the pointer `this`, as shown in the definition of the function `updateXYZ`. The assignment operator then copies the value into `object2`.

---

The following example also shows how the pointer `this` works.

---

### EXAMPLE 15-2

In Example 12-9 in (Chapter 12), we designed a class to implement a person's name in a program. Here, we extend the definition of the `class personType` to individually set a person's first name and last name and then return the entire object. The extended definition of the `class personType` is:

```

class personType
{
public:
 void print() const;
 //Function to output the first name and last name.
 //the form firstName lastName

 void setName(string first, string last);
 //Function to set firstName and lastName according
 //to the parameters.
 //Postcondition: firstName = first; lastName = last

```

```

personType& setFirstName(string first);
 //Function to set the first name.
 //Postcondition: firstName = first
 // After setting the first name, a reference
 // to the object, that is, the address of the
 // object, is returned.

personType& setLastName(string last);
 //Function to set the last name.
 //Postcondition: lastName = last
 // After setting the last name, a reference
 // to the object, that is, the address of the
 // object, is returned.

string getFirstName() const;
 //Function to return the first name.
 //Postcondition: The value of firstName is returned.

string getLastName() const;
 //Function to return the last name.
 //Postcondition: The value of lastName is returned.

personType(string first = "", string last = "");
 //Constructor
 //Sets firstName and lastName according to the parameters.
 //Postcondition: firstName = first; lastName = last

private:
 string firstName; //variable to store the first name
 string lastName; //variable to store the last name
};

```

Notice that in this definition of the `class` `personType`, we replace the default constructor and the constructor with parameters by one constructor with default parameters.

The definitions of the functions `print`, `setName`, `getFirstName`, `getLastName`, and the constructor are the same as before (see Example 12-9). The definitions of the functions `setFirstName` and `setLastName` are as follows:

```

personType& personType::setLastName(string last)
{
 lastName = last;

 return *this;
}

personType& personType::setFirstName(string first)
{
 firstName = first;

 return *this;
}

```

The following program shows how to use the `class` `personType`. (We assume that the definition of this class is in the file `personType.h`)

```
//Test Program: class personType

#include <iostream>
#include <string>
#include "personType.h"

using namespace std;

int main()
{
 personType student1("Angela", "Smith"); //Line 1

 personType student2; //Line 2

 personType student3; //Line 3

 cout << "Line 4 -- Student 1: "; //Line 4
 student1.print(); //Line 5
 cout << endl; //Line 6

 student2.setFirstName("Shelly").setLastName("Malik"); //Line 7

 cout << "Line 8 -- Student 2: "; //Line 8
 student2.print(); //Line 9
 cout << endl; //Line 10

 student3.setFirstName("Chelsea"); //Line 11

 cout << "Line 12 -- Student 3: "; //Line 12
 student3.print(); //Line 13
 cout << endl; //Line 14

 student3.setLastName("Tomek"); //Line 15

 cout << "Line 16 -- Student 3: "; //Line 16
 student3.print(); //Line 17
 cout << endl; //Line 18

 return 0;
}
```

### Sample Run:

```
Line 4 -- Student 1: Angela Smith
Line 8 -- Student 2: Shelly Malik
Line 12 -- Student 3: Chelsea
Line 16 -- Student 3: Chelsea Tomek
```

The statements in Lines 1, 2, and 3 declare and initialize the objects `student1`, `student2`, and `student3`, respectively. The objects `student2` and `student3` are initialized to empty strings. The statement in Line 5 outputs the value of `student1` (see Line 4 in the sample

run, which contains the output of Lines 4, 5, and 6). The statement in Line 7 works as follows. In the statement:

```
student2.setFirstName("Shelly").setLastName("Malik");
```

first, the expression:

```
student2.setFirstName("Shelly")
```

is executed because the associativity of the dot operator is from left to right. This expression sets the first name to **"Shelly"** and returns a reference of the object, which is **student2**. Thus, the next expression executed is:

```
student2.setLastName("Malik")
```

which sets the last name of **student2** to **"Malik"**. The statement in Line 9 outputs the value of **student2**. The statement in Line 11 sets the first name of the object **student3** to **"Chelsea"** and ignores the value returned. The statement in Line 13 outputs the value of **student3**. Notice the output in Line 12. The output shows only the first name, not the last name, because we have not yet set the last name of **student3**. The last name of **student3** is still empty, which was set by the statement in Line 3 when **student3** was declared. Next, the statement in Line 15 sets the last name of **student3**, and the statement in Line 17 outputs the value of **student3**.

## Friend Functions of Classes

A **friend function** of a class is a nonmember function of the class but has access to all of the members (**public** or non-**public**) of the class. To make a function be a friend to a class, the reserved word **friend** precedes the function prototype (in the class definition). The word **friend** appears only in the function prototype in the class definition, not in the definition of the friend function.

Consider the following statements:

```
class classIllusFriend
{
 friend void two(/*parameters*/);
 .
 .
 .
};
```

In the definition of the **class classIllusFriend**, **two** is declared as a **friend** of the **class classIllusFriend**. That is, it is a nonmember function of the **class classIllusFriend**. When you write the definition of the function **two**, any object of type **classIllusFriend**—which is either a local variable of **two** or a formal parameter of **two**—can access its **private** members within the definition of the function **two**. (Example 15-3 illustrates this concept.) Moreover, because a **friend** function is not a member of a class, its declaration can be placed within the **private**, **protected**, or **public** part of the class. However, they are typically placed before any member function declaration.

## DEFINITION OF A **friend** FUNCTION

When writing the definition of a **friend** function, the name of the class and the scope resolution operator do not precede the name of the **friend** function in the function heading. Also, recall that the word **friend** does not appear in the heading of the **friend** function's definition. Thus, the definition of the function **two** in the previous **class** **classIllusFriend** is:

```
void two(/*parameters*/)
{
 .
 .
 .
}
```

Of course, we will place the definition of the **friend** function in the implementation file.

The next section illustrates the difference between a member function and a nonmember function (**friend** function) when we overload some of the operators for a specific class.

The following example shows how a **friend** function accesses the **private** members of a class.

### EXAMPLE 15-3

Consider the following class:

```
class classIllusFriend
{
 friend void two(classIllusFriend cIFObject);

public:
 void print();
 void setx(int a);

private:
 int x;
};
```

In the definition of the **class** **classIllusFriend**, **two** is declared as a **friend** function. Suppose that the definitions of the member functions of the **class** **classIllusFriend** are as follows:

```
void classIllusFriend::print()
{
 cout << "In class classIllusFriend: x = " << x << endl;
}

void classIllusFriend::setx(int a)
{
 x = a;
}
```

Consider the following definition of the function `two`:

```
void two(classIllusFriend cIFObject) //Line 1
{
 classIllusFriend localTwoObject; //Line 2

 localTwoObject.x = 45; //Line 3

 localTwoObject.print(); //Line 4

 cout << "Line 5: In Friend Function two "
 << "accessing private member variable "
 << "x = " << localTwoObject.x
 << endl; //Line 5

 cIFObject.x = 88; //Line 6

 cIFObject.print(); //Line 7

 cout << "Line 8: In Friend Function two "
 << "accessing private member variable "
 << "x = " << cIFObject.x << endl; //Line 8
}
```

The function `two` contains a formal parameter `cIFObject` and a local variable `localTwoObject`, both of type `classIllusFriend`. In the statement in Line 3, the object `localTwoObject` accesses its `private` member variable `x` and sets its value to 45. If `two` is not declared as a `friend` function of the `class` `classIllusFriend`, then this statement would result in a syntax error because an object cannot directly access its `private` members. Similarly, in the statement in Line 6, the formal parameter `cIFObject` accesses its `private` member variable `x` and sets its value to 88. Once again, this statement would result in a syntax error if `two` is not declared a `friend` function of the `class` `classIllusFriend`. The statement in Line 5 outputs the value of the `private` member variable `x` of `localTwoObject` by directly accessing `x`. Similarly, the statement in Line 8 outputs the value of `x` of `cIFObject` by directly accessing it. The function `two` also prints the value of `x` by using the function `print` (see the statements in Lines 4 and 7).

Now consider the definition of the following function `main`:

```
int main()
{
 classIllusFriend aObject; //Line 9

 aObject.setx(32); //Line 10

 cout << "Line 11: aObject.x: "; //Line 11
 aObject.print(); //Line 12
 cout << endl; //Line 13
}
```

```

cout << "***~*~*~*~*~* Testing Friend Function "
 << "two *~*~*~*~*~*" << endl << endl; //Line 14

two(aObject); //Line 15

return 0;
}

```

### Sample Run:

Line 11: aObject.x: In class classIllusFriend: x = 32

\*\*\*~\*~\*~\*~\*~\* Testing Friend Function two \*~\*~\*~\*~\*~\*

In class classIllusFriend: x = 45

Line 5: In Friend Function two accessing private member variable x = 45

In class classIllusFriend: x = 88

Line 8: In Friend Function two accessing private member variable x = 88

For the most part, the output is self-explanatory. The statement in Line 15 calls the function `two` (a `friend` function of the `class` `classIllusFriend`) and passes the object `aObject` as an actual parameter. Notice that the function `two` generates the last four lines of the output.

---

Later in this chapter, you will learn that for a class, stream insertion and extraction operators can be overloaded only as `friend` functions.

## Operator Functions as Member Functions and Nonmember Functions

The beginning of this chapter stated that certain rules must be followed when you include an operator function in the definition of a class. This section describes these rules.

Most operator functions can be either member functions or nonmember functions—that is, `friend` functions of a class. To make an operator function be a member or nonmember function of a class, keep the following in mind:

1. The function that overloads any of the operators `()`, `[]`, `->`, or `=` for a class must be declared as a member of the class.
2. Suppose that an operator `op` is overloaded for a class—say, `opOverClass`. (Here, `op` stands for an operator that can be overloaded, such as `+` or `>>`.)
  - a. If the far left operand of `op` is an object of a different type (that is, not of type `opOverClass`), the function that overloads the operator `op` for `opOverClass` must be a nonmember—that is, a friend of the `class` `opOverClass`.
  - b. If the operator function that overloads the operator `op` for the `class` `opOverClass` is a member of the `class` `opOverClass`, then when applying `op` on objects of type `opOverClass`, the far left operand of `op` must be of type `opOverClass`.

You must follow these rules when including an operator function in a class definition.

You will see later in this chapter that functions that overload the insertion operator, `<<`, and the extraction operator, `>>`, for a class must be nonmembers—that is, **friend** functions of the class.

Except for certain operators noted previously, operators can be overloaded either as member functions or as nonmember functions. The following discussion shows the difference between these two types of functions.

To facilitate our discussion of operator overloading, we will use the **class** `rectangleType`, given next. (Although Chapter 13 defines this class, Chapter 13 is not a prerequisite for this chapter. For easy reference, we reproduce the definition of this class and the definitions of the member functions.)

```
class rectangleType
{
public:
 void setDimension(double l, double w);
 //Function to set the length and width of the rectangle.
 //Postcondition: length = l; width = w;

 double getLength() const;
 //Function to return the length of the rectangle.
 //Postcondition: The value of length is returned.

 double getWidth() const;
 //Function to return the width of the rectangle.
 //Postcondition: The value of width is returned.

 double area() const;
 //Function to return the area of the rectangle.
 //Postcondition: The area of the rectangle is
 // calculated and returned.

 double perimeter() const;
 //Function to return the perimeter of the rectangle.
 //Postcondition: The perimeter of the rectangle is
 // calculated and returned.

 void print() const;
 //Function to output the length and width of
 //the rectangle.

 rectangleType();
 //Default constructor
 //Postcondition: length = 0; width = 0;

 rectangleType(double l, double w);
 //Constructor with parameters
 //Postcondition: length = l; width = w;
```

```
private:
 double length;
 double width;
};
```

The definitions of the member functions of the `class rectangleType` are as follows:

```
void rectangleType::setDimension(double l, double w)
{
 if (l >= 0)
 length = l;
 else
 length = 0;

 if (w >= 0)
 width = w;
 else
 width = 0;
}

double rectangleType::getLength() const
{
 return length;
}

double rectangleType::getWidth() const
{
 return width;
}

double rectangleType::area() const
{
 return length * width;
}

double rectangleType::perimeter() const
{
 return 2 * (length + width);
}

void rectangleType::print() const
{
 cout << "Length = " << length
 << "; Width = " << width;
}

rectangleType::rectangleType(double l, double w)
{
 setDimension(l, w);
}
```

```
rectangleType::rectangleType()
{
 length = 0;
 width = 0;
}
```

The `class` `rectangleType` has two `private` member variables: `length` and `width`, both of type `double`. We will add operator functions to the `class` `rectangleType` as we overload the operators.

Also, suppose that you have the following statements:

```
rectangleType myRectangle;
rectangleType yourRectangle;
rectangleType tempRect;
```

That is, `myRectangle`, `yourRectangle`, and `tempRect` are objects of type `rectangleType`.

C++ consists of both binary and unary operators. It also has a ternary operator, which *cannot* be overloaded. The next few sections discuss how to overload various binary and unary operators.

## Overloading Binary Operators

Suppose that `#` represents a binary operator (arithmetic, such as `+`; or relational, such as `==`) that is to be overloaded for the `class` `rectangleType`. This operator can be overloaded as either a member function of the class or as a `friend` function. We will describe both ways to overload this operator.

### OVERLOADING THE BINARY OPERATORS AS MEMBER FUNCTIONS

Suppose that `#` is overloaded as a member function of the `class` `rectangleType`. The name of the function to overload `#` for the `class` `rectangleType` is:

```
operator#
```

Because `myRectangle` and `yourRectangle` are objects of type `rectangleType`, you can perform the operation:

```
myRectangle # yourRectangle
```

The compiler translates this expression into the following expression:

```
myRectangle.operator#(yourRectangle)
```

This expression clearly shows that the function `operator#` has only one parameter, which is `yourRectangle`.

Because `operator#` is a member of the `class` `rectangleType` and `myRectangle` is an object of type `rectangleType`, in the previous statement, `operator#` has direct access to the `private` members of the object `myRectangle`. Thus, the first parameter of `operator#` is the object that is invoking the function `operator#`, and the second parameter is passed as a parameter to this function.

## GENERAL SYNTAX TO OVERLOAD THE BINARY (ARITHMETIC OR RELATIONAL) OPERATORS AS MEMBER FUNCTIONS

This section describes the general form of the functions to overload the binary operators as member functions of a class.

**Function Prototype** (to be included in the definition of the class):

```
returnType operator#(const className&) const;
```

in which # stands for the binary operator, arithmetic or relational, to be overloaded; `returnType` is the type of value returned by the function; and `className` is the name of the class for which the operator is being overloaded.

**Function Definition:**

```
returnType className::operator#
 (const className& otherObject) const
{
 //algorithm to perform the operation

 return value;
}
```

### NOTE

The return type of the functions that overload relational operators is `bool`.

## EXAMPLE 15-4

Let us overload +, \*, ==, and != for the `class rectangleType`. These operators are overloaded as member functions.

```
class rectangleType
{
public:
 void setDimension(double l, double w);
 double getLength() const;
 double getWidth() const;
 double area() const;
 double perimeter() const;
 void print() const;

 rectangleType operator+(const rectangleType&) const;
 //Overload the operator +
 rectangleType operator*(const rectangleType&) const;
 //Overload the operator *
```

```

 bool operator==(const rectangleType&) const;
 //Overload the operator ==
 bool operator!=(const rectangleType&) const;
 //Overload the operator !=

 rectangleType();
 rectangleType(double l, double w);

private:
 double length;
 double width;
};

```

The definition of the function `operator+` is as follows:

```

rectangleType rectangleType::operator+
 (const rectangleType& rectangle) const
{
 rectangleType tempRect;

 tempRect.length = length + rectangle.length;
 tempRect.width = width + rectangle.width;

 return tempRect;
}

```

Notice that `operator +` adds the corresponding lengths and widths of the two rectangles. The definition of the function `operator*` is as follows:

```

rectangleType rectangleType::operator*
 (const rectangleType& rectangle) const
{
 rectangleType tempRect;

 tempRect.length = length * rectangle.length;
 tempRect.width = width * rectangle.width;

 return tempRect;
}

```

Notice that `operator*` multiplies the corresponding lengths and widths of the two rectangles.

Two rectangles are equal if their lengths and widths are equal. Therefore, the definition of the function to overload the operator `==` is:

```

bool rectangleType::operator==
 (const rectangleType& rectangle) const
{
 return (length == rectangle.length &&
 width == rectangle.width);
}

```

Two rectangles are not equal if either their lengths are not equal or their widths are not equal. Therefore, the definition of the function to overload the operator `!=` is:

```
bool rectangleType::operator!=
 (const rectangleType& rectangle) const
{
 return (length != rectangle.length ||
 width != rectangle.width);
}
```

(Note that after writing the definition of the function to overload the operator ==, you can use it to write the definition of the function to overload the operator !=. We leave the details as an exercise.)

Consider the following program. (We assume that the definition of the `class rectangleType` is in the header file `rectangleType.h`.)

```
//This program shows how to use the class rectangleType.

#include <iostream>
#include "rectangleType.h"

using namespace std;

int main()
{
 rectangleType rectangle1(23, 45); //Line 1
 rectangleType rectangle2(12, 10); //Line 2
 rectangleType rectangle3; //Line 3
 rectangleType rectangle4; //Line 4

 cout << "Line 5: rectangle1: "; //Line 5
 rectangle1.print(); //Line 6
 cout << endl; //Line 7

 cout << "Line 8: rectangle2: "; //Line 8
 rectangle2.print(); //Line 9
 cout << endl; //Line 10

 rectangle3 = rectangle1 + rectangle2; //Line 11

 cout << "Line 12: rectangle3: "; //Line 12
 rectangle3.print(); //Line 13
 cout << endl; //Line 14

 rectangle4 = rectangle1 * rectangle2; //Line 15

 cout << "Line 16: rectangle4: "; //Line 16
 rectangle4.print(); //Line 17
 cout << endl; //Line 18

 if (rectangle1 == rectangle2) //Line 19
 cout << "Line 20: rectangle1 and "
 << "rectangle2 are equal." << endl; //Line 20
 else //Line 21
 cout << "Line 22: rectangle1 and "
 << "rectangle2 are not equal."
 << endl; //Line 22
}
```

```

 if (rectangle1 != rectangle3) //Line 23
 cout << "Line 24: rectangle1 and "
 << "rectangle3 are not equal."
 << endl; //Line 24
 else //Line 25
 cout << "Line 25: rectangle1 and "
 << "rectangle3 are equal." << endl; //Line 26

 return 0;
}

```

### Sample Run:

```

Line 5: rectangle1: Length = 23; Width = 45
Line 8: rectangle2: Length = 12; Width = 10
Line 12: rectangle3: Length = 35; Width = 55
Line 16: rectangle4: Length = 276; Width = 450
Line 22: rectangle1 and rectangle2 are not equal.
Line 24: rectangle1 and rectangle3 are not equal.

```

For the most part, the preceding output is self-explanatory. However, let us look at the statements in Lines 11, 15, 19, and 23. The statement in Line 11 uses the operator `+` to add the lengths and widths of `rectangle1` and `rectangle2` and stores the result in `rectangle3`. (That is, after the execution of this statement, the length of `rectangle3` is the sum of the lengths of `rectangle1` and `rectangle2`, and the width of `rectangle3` is the sum of the widths of `rectangle1` and `rectangle2`. The statement in Line 12 outputs the length and width of `rectangle3`.) Similarly, the statement in Line 15 uses the operator `*` to multiply the lengths and widths of `rectangle1` and `rectangle2` and stores the result in `rectangle4`. (The statement in Line 17 outputs the length and width of `rectangle4`.) The statement in Line 19 uses the relational operator `==` to determine whether the dimensions of `rectangle1` and `rectangle2` are the same. Similarly, the statement in Line 23 uses the relational operator `!=` to determine whether the dimensions of `rectangle1` and `rectangle3` are the same.

## OVERLOADING THE BINARY OPERATORS (ARITHMETIC OR RELATIONAL) AS NONMEMBER FUNCTIONS

Suppose that `#` represents the binary operator (arithmetic or relational) that is to be overloaded as a *nonmember* function of the `class` `rectangleType`.

Further suppose that the following operation is to be performed:

```
myRectangle # yourRectangle
```

In this case, the expression is compiled as:

```
operator#(myRectangle, yourRectangle)
```

Here, we see that the function `operator#` has two parameters. This expression also clearly shows that the function `operator#` is neither a member of the object `myRectangle`



```

{
 rectangleType tempRect;

 tempRect.length = firstRect.length + secondRect.length;
 tempRect.width = firstRect.width + secondRect.width;

 return tempRect;
}

```

In the preceding definition, the corresponding member variables of `firstRect` and `secondRect` are added, and the result is stored in `tempRect`. Recall that the `private` members of a class are local to the class and, therefore, cannot be accessed outside of the class. If we follow this rule, then because `operator+` is not a member of the `class rectangleType`, its definition expressions such as `firstRect.length` must be illegal because `length` is a `private` member of `firstRect`. However, because `operator+`, as declared as a `friend` function of the `class rectangleType`, an object of type `rectangleType` can access its `private` members in the definition of `operator+`. Also, note that in the function heading, the name of the class—that is, `rectangleType`—and the scope resolution operator *are not included* before the name of the function `operator+`, because the function `operator+` is not a member of the class.

To include the operator function `operator==` as a nonmember function of the `class rectangleType`, its prototype in the definition of `rectangleType` is:

```

friend bool operator==(const rectangleType& ,
 const rectangleType&);

```

The definition of the function `operator==` is as follows:

```

bool operator==(const rectangleType& firstRect,
 const rectangleType& secondRect)
{
 return (firstRect.length == secondRect.length &&
 firstRect.width == secondRect.width);
}

```

You can write a program similar to the one in Example 15-4 to test the overloading of the operators `+` and `==` as nonmembers.

## Overloading the Stream Insertion (<<) and Extraction (>>) Operators

The operator function that overloads the insertion operator, `<<`, or the extraction operator, `>>`, for a class must be a nonmember function of that class for the following reason.

Consider the expression:

```
cout << myRectangle;
```

In this expression, the far left operand of `<<` (that is, `cout`) is an `ostream` object, not an object of type `rectangleType`. Because the far left operand of `<<` is not an object of

type `rectangleType`, the operator function that overloads the insertion operator for `rectangleType` must be a *nonmember* function of the `class` `rectangleType`.

Similarly, the operator function that overloads the stream extraction operator for `rectangleType` must be a nonmember function of the `class` `rectangleType`.

### OVERLOADING THE STREAM INSERTION OPERATOR (<<)

The general syntax to overload the stream insertion operator, <<, for a class is described next.

**Function Prototype** (to be included in the definition of the class):

```
friend ostream& operator<<(ostream&, const className&);
```

#### Function Definition:

```
ostream& operator<<(ostream& osObject, const className& cObject)
{
 //local declaration, if any
 //Output the members of cObject.
 //osObject << . . .

 //Return the stream object.
 return osObject;
}
```

In this function definition:

- Both parameters are reference parameters.
- The first parameter—that is, `osObject`—is a reference to an `ostream` object.
- The second parameter is usually a `const` reference to a particular class, because (recall from Chapter 12) the most effective way to pass an object as a parameter to a class is by reference. In this case, the formal parameter does not need to copy the member variables of the actual parameter. The word `const` appears before the class name because we want to print only the member variables of the object. That is, the function should not modify the member variables of the object.
- The function return type is a reference to an `ostream` object.

The return type of the function to overload the operator << must be a reference to an `ostream` object for the following reasons.

Suppose that the operator << is overloaded for the `class` `rectangleType`. The statement:

```
cout << myRectangle;
```

is equivalent to the statement:

```
operator<<(cout, myRectangle);
```

This is a perfectly legal statement because both of the actual parameters are objects, not the value of the objects. The first parameter, `cout`, is of type `ostream`; the second parameter, `myRectangle`, is of type `rectangleType`.

Now consider the following statement:

```
cout << myRectangle << yourRectangle;
```

This statement is equivalent to the statement:

```
operator<<(operator<<(cout, myRectangle), yourRectangle); //Line A
```

because the associativity of the operator `<<` is from left to right.

To execute the previous statement, you must first execute the expression:

```
cout << myRectangle
```

that is, the expression:

```
operator<<(cout, myRectangle)
```

After executing this expression, which outputs the value of `myRectangle`, whatever is returned by the function `operator <<` will become the left-side parameter of the operator `<<` (that is, the first parameter of the function `operator<<`) in order to output the value of object `yourRectangle` (see the statement in Line A). Because the left-side parameter of the operator `<<` must be an object of the `ostream` type, the expression:

```
cout << myRectangle
```

must return the object `cout` (not its value) in order to output the value of `yourRectangle`.

Therefore, the return type of the function `operator<<` must be a reference to an object of the `ostream` type.

## OVERLOADING THE STREAM EXTRACTION OPERATOR (>>)

The general syntax to overload the stream extraction operator, `>>`, for a class is described next.

**Function Prototype** (to be included in the definition of the class):

```
friend istream& operator>>(istream&, className&);
```

**Function Definition:**

```
istream& operator>>(istream& isObject, className& cObject)
{
 //local declaration, if any
 //Read the data into cObject.
 //isObject >> . . .

 //Return the stream object.
 return isObject;
}
```

In this function definition:

- Both parameters are reference parameters.
- The first parameter—that is, `isObject`—is a reference to an `istream` object.
- The second parameter is usually a reference to a particular class. The data read will be stored in the object.
- The function return type is a reference to an `istream` object.

For the same reasons as explained previously (when we overloaded the insertion operator `<<`), the return type of the function `operator>>` must be a reference to an `istream` object. We can then successfully execute statements of the following type:

```
cin >> myRectangle >> yourRectangle;
```

Example 15-6 shows how the stream insertion and extraction operators are overloaded for the `class` `rectangleType`.

### EXAMPLE 15-6

The definition of the `class` `rectangleType` and the definitions of the operator functions are:

```
#include <iostream>

using namespace std;

class rectangleType
{
 //Overload the stream insertion and extraction operators
 friend ostream& operator<< (ostream&, const rectangleType &);
 friend istream& operator>> (istream&, rectangleType &);

public:
 void setDimension(double l, double w);
 double getLength() const;
 double getWidth() const;
 double area() const;
 double perimeter() const;
 void print() const;

 rectangleType operator+(const rectangleType&) const;
 //Overload the operator +
 rectangleType operator*(const rectangleType&) const;
 //Overload the operator *

 bool operator==(const rectangleType&) const;
 //Overload the operator ==
 bool operator!=(const rectangleType&) const;
 //Overload the operator !=
```

```

 rectangleType();
 rectangleType(double l, double w);

private:
 double length;
 double width;
};

```

Notice that we have removed the member function `print` because we are overloading the stream insertion operator `<<`.

```

 //The definitions of the functions operator+, operator*,
 //operator==, and operator!= are the same as in Example 15-5.

ostream& operator<< (ostream& osObject,
 const rectangleType& rectangle)
{
 osObject << "Length = " << rectangle.length
 << "; Width = " << rectangle.width;

 return osObject;
}

istream& operator>> (istream& isObject,
 rectangleType& rectangle)
{
 isObject >> rectangle.length >> rectangle.width;

 return isObject;
}

```

Consider the following program. (We assume that the definition of the `class rectangleType` is in the header file `rectangleType.h`.)

```

//This program shows how to use the modified class rectangleType.

#include <iostream>

#include "rectangleType.h"

using namespace std;

int main()
{
 rectangleType myRectangle(23, 45); //Line 1
 rectangleType yourRectangle; //Line 2

 cout << "Line 3: myRectangle: " << myRectangle
 << endl; //Line 3

 cout << "Line 4: Enter the length and width "
 << "of a rectangle: "; //Line 4
 cin >> yourRectangle; //Line 5
 cout << endl; //Line 6
}

```

```

 cout << "Line 7: yourRectangle: "
 << yourRectangle << endl; //Line 7

 cout << "Line 8: myRectangle + yourRectangle: "
 << myRectangle + yourRectangle << endl; //Line 8
 cout << "Line 9: myRectangle * yourRectangle: "
 << myRectangle * yourRectangle << endl; //Line 9

 return 0;
}

```

**Sample Run:** In this sample run, the user input is shaded.

Line 3: myRectangle: Length = 23; Width = 45

Line 4: Enter the length and width of a rectangle: 32 15

Line 7: yourRectangle: Length = 32; Width = 15

Line 8: myRectangle + yourRectangle: Length = 55; Width = 60

Line 9: myRectangle \* yourRectangle: Length = 736; Width = 675

The statements in Lines 1 and 2 declare and initialize `myRectangle` and `yourRectangle` to be objects of type `rectangleType`. The statement in Line 3 outputs the value of `myRectangle` using `cout` and the insertion operator. The statement in Line 5 inputs the data into `yourRectangle` using `cin` and the extraction operator. The statement in Line 7 outputs the value of `yourRectangle` using `cout` and the insertion operator. The `cout` statement in Line 8 adds the lengths and widths of `myRectangle` and `yourRectangle` and outputs the result. Similarly, the `cout` statement in Line 9 multiplies the lengths and widths of `myRectangle` and `yourRectangle` and outputs the result. The output shows that both the stream insertion and stream extraction operators were overloaded successfully.

## Overloading the Assignment Operator (=)

One of the built-in operations on classes is the assignment operation. The assignment operator causes a member-wise copy of the member variables of the class. For example, the statement:

```
myRectangle = yourRectangle;
```

is equivalent to the statements:

```
myRectangle.length = yourRectangle.length;
myRectangle.width = yourRectangle.width;
```

From Chapter 14, recall that the built-in assignment operator works well for classes that do not have pointer member variables, but not for classes with pointer member variables. Therefore, to avoid the shallow copy of data for classes with pointer member variables, we must explicitly overload the assignment operator.

Recall that to overload the assignment operator `=` for a class, the operator function **operator=** must be a member of that class.

**GENERAL SYNTAX TO OVERLOAD THE ASSIGNMENT OPERATOR = FOR A CLASS**

The general syntax to overload the assignment operator = for a class is described next.

**Function Prototype** (to be included in the definition of the class):

```
const className& operator=(const className&);
```

**Function Definition:**

```
const className& className::operator=
 (const className& rightObject)
{
 //local declaration, if any

 if (this != &rightObject) //avoid self-assignment
 {
 //algorithm to copy rightObject into this object
 }

 //Return the object assigned.
 return *this;
}
```

In the definition of the function `operator=`:

- There is only one formal parameter.
- The formal parameter is usually a `const` reference to a particular class.
- The function return type is a `constant` reference to a particular class.

We now explain why the return type of the function `operator=` should be a reference of the class type.

Suppose that the assignment operator = is overloaded for the `class rectangleType`. The statement:

```
myRectangle = yourRectangle;
```

is equivalent to the statement:

```
myRectangle.operator=(yourRectangle);
```

That is, the object `yourRectangle` becomes the actual parameter to the function:

```
operator=
```

Now consider the statement:

```
myRectangle = yourRectangle = tempRect;
```

Because the associativity of the operator = is from right to left, this statement is equivalent to the statement:

```
myRectangle.operator=(yourRectangle.operator=(tempRect)); //Line A
```

Clearly, we must first execute the expression:

```
yourRectangle.operator=(tempRect)
```

that is, the expression:

```
yourRectangle = tempRect
```

The value returned by the expression:

```
yourRectangle.operator=(tempRect)
```

will become the parameter to the function `operator=` in order to assign a value to the object `myRectangle` (see the statement in Line A). Because the formal parameter of the function `operator=` is a reference parameter, the expression:

```
yourRectangle.operator=(tempRect)
```

must return a reference to the object, rather than its value. That is, it must return a reference to the object `yourRectangle`, not the value of `yourRectangle`. For this reason, the return type of the function to overload the assignment operator `=` for a class must be a reference to the class type.

Now consider the statement:

```
myRectangle = myRectangle; //Line B
```

Here, we are trying to copy the value of `myRectangle` into `myRectangle`; that is, this statement is a self-assignment. One reason why we must prevent such assignments is because they waste computer time. First, however, we explain how the body of the assignment operator prevents such assignments.

As noted above, the body of the function `operator=` does prevent assignments, such as the one given in Line B. Let us see how.

Consider the `if` statement in the body of the operator function `operator=`:

```
if (this != &rightObject) //avoid self-assignment
{
 //algorithm to copy rightObject into this object
}
```

The statement:

```
myRectangle = myRectangle;
```

is compiled into the statement:

```
myRectangle.operator=(myRectangle);
```

Because the function `operator=` is invoked by the object `myRectangle`, the pointer `this` in the body of the function `operator=` refers to the object `myRectangle`. Furthermore, because `myRectangle` is also a parameter of the function `operator=`,

the formal parameter `rightObject` also refers to the object `myRectangle`. Therefore, in the expression:

```
this != &rightObject
```

`this` and `&rightObject` both mean the address of `myRectangle`. Thus, the expression will evaluate to `false` and, therefore, the body of the `if` statement will be skipped.

#### NOTE

This note illustrates another reason why the body of the operator function must prevent self-assignments. Let us consider the following class:

```
class arrayClass
{
public:
 const arrayClass& operator= (const& arrayClass);
 .
 .
private:
 int *list;
 int length;
 int maxSize;
};
```

The `class arrayClass` has a pointer member variable, `list`, which is used to create an array to store integers. Suppose that the definition of the function to overload the assignment operator for the `class arrayClass` is written without the `if` statement, as follows:

```
const arrayClass & arrayClass::operator=
 (const arrayClass& otherList)
{
 delete [] list; //Line 1
 maxSize = otherList.maxSize; //Line 2
 length = otherList.length; //Line 3

 list = new int[maxSize]; //Line 4

 for (int i = 0; i < length; i++) //Line 5
 list[i] = otherList.list[i]; //Line 6

 return *this; //Line 7
}
```

Suppose that we have the following declaration in a user program:

```
arrayClass myList;
```

Consider the following statement:

```
myList = myList;
```

This is a self-assignment. When this statement executes in the body of the function `operator=`:

1. `list` means `myList.list`, `maxSize` means `myList.maxSize`, and `length` means `myList.length`.
2. `otherList` is the same as `myList`.

The statement in Line 1 destroys `list`, that is, `myList.list`, so the array holding the numbers no longer exists. That is, it is not valid. The problem is in Line 6. Here, the expression `list[i] = otherList.list[i]` is equivalent to the statement `myList.list[i] = myList.list[i]`. Because `myList.list[i]` has no valid data (it was destroyed in Line 1), the statement in Line 6 produces garbage.

It follows that the definition of the function `operator=` must prevent self-assignments. The correct definition of `operator=` for the `class` `arrayClass` is:

```
const arrayClass& arrayClass::operator=
 (const arrayClass& otherList)
{
 if (this != & otherList) //Line 1
 {
 delete [] list; //Line 2
 maxSize = otherList.maxSize; //Line 3
 length = otherList.length; //Line 4

 list = new int[maxSize]; //Line 5

 for (int i = 0; i < length; i++) //Line 6
 list[i] = otherList.list[i]; //Line 7
 }

 return *this; //Line 8
}
```

The following example illustrates how to overload the assignment operator.

### EXAMPLE 15-7

Consider the following class:

```
class cAssignmentOprOverload
{
public:
 const cAssignmentOprOverload&
 operator=(const cAssignmentOprOverload& otherList);
 //Overload assignment operator
```

```

void print() const;
 //Function to print the list

void insertEnd(int item);
 //Function to insert an item at the end of the list
 //Postcondition: if the list is not full,
 // length++; list[length] = item;
 // if the list is full,
 // output an appropriate message

void destroyList();
 //Function to destroy the list
 //Postcondition: length = 0; maxSize = 0; list = NULL;

cAssignmentOprOverload(int size = 0);
 //Constructor
 //Postcondition: length = 0; maxSize = size;
 // list is an array of size maxSize

private:
 int maxSize;
 int length;
 int *list;
};

```

The definitions of the member functions of the `class` `cAssignmentOprOverload` are:

```

void cAssignmentOprOverload::print() const
{
 if (length == 0)
 cout << "The list is empty." << endl;
 else
 {
 for (int i = 0; i < length; i++)
 cout << list[i] << " ";
 cout << endl;
 }
}

void cAssignmentOprOverload::insertEnd(int item)
{
 if (length == maxSize)
 cout << "List is full" << endl;
 else
 list[length++] = item;
}

void cAssignmentOprOverload::destroyList()
{
 delete [] list;
 list = NULL;
 length = 0;
 maxSize = 0;
}

```

```

cAssignmentOprOverload::cAssignmentOprOverload(int size)
{
 maxSize = size;
 length = 0;

 if (maxSize == 0)
 list = NULL;
 else
 list = new int[maxSize];
}

const cAssignmentOprOverload& cAssignmentOprOverload::operator=
 (const cAssignmentOprOverload& otherList)
{
 if (this != &otherList) //avoid self-assignment; Line 1
 {
 delete [] list; //Line 2
 maxSize = otherList.maxSize; //Line 3
 length = otherList.length; //Line 4

 list = new int[maxSize]; //Line 5

 for (int i = 0; i < length; i++) //Line 6
 list[i] = otherList.list[i]; //Line 7
 }

 return *this; //Line 8
}

```

The function to overload the assignment operator works as follows. The statement in Line 1 checks whether an object is copying itself. The statement in Line 2 destroys `list`. The statements in Lines 3 and 4 copy the values of the member variables `maxSize` and `length` of `otherList` into the member variables `maxSize` and `length` of `list`, respectively. The statement in Line 5 creates the array to store the numbers. The `for` loop in Line 6 copies `otherList` into `list`. The statement in Line 8 returns the address of this object, because the return type of the function `operator=` is a reference type.

The following program tests the `class` `cAssignmentOprOverload`:

```

#include <iostream>

#include "classAssignmentOverload.h"

using namespace std;
int main()
{
 cAssignmentOprOverload intList1(10); //Line 9
 cAssignmentOprOverload intList2; //Line 10
 cAssignmentOprOverload intList3; //Line 11
}

```

```

 int i; //Line 12
 int number; //Line 13

 cout << "Line 14: Enter 5 integers: "; //Line 14

 for (i = 0; i < 5; i++) //Line 15
 {
 cin >> number; //Line 16
 intList1.insertEnd(number); //Line 17
 }

 cout << endl; //Line 18
 cout << "Line 19: intList1: "; //Line 19
 intList1.print(); //Line 20

 intList3 = intList2 = intList1; //Line 21

 cout << "Line 22: intList2: "; //Line 22
 intList2.print(); //Line 23

 intList2.destroyList(); //Line 24

 cout << endl; //Line 25
 cout << "Line 26: intList2: "; //Line 26
 intList2.print(); //Line 27

 cout << "Line 28: After destroying intList2, "
 << "intList1: "; //Line 28
 intList1.print(); //Line 29

 cout << "Line 30: After destroying intList2, "
 << "intList3: "; //Line 30
 intList3.print(); //Line 31
 cout << endl; //Line 32

 return 0;
}

```

**Sample Run:** In this sample run, the user input is shaded.

Line 14: Enter 5 integers: 8 5 3 7 2

Line 19: intList1: 8 5 3 7 2

Line 22: intList2: 8 5 3 7 2

Line 26: intList2: The list is empty.

Line 28: After destroying intList2, intList1: 8 5 3 7 2

Line 30: After destroying intList2, intList3: 8 5 3 7 2

The statement in Line 9 creates `intList1` of size 10; the statements in Lines 10 and 11 create `intList2` and `intList3` of (default) size 50. The statements in Lines 15 through 17 input the data into `intList1`, and the statement in Line 20 outputs `intList1`. The

statement in Line 21 copies `intList1` into `intList2` and then copies `intList2` into `intList3`. The statement in Line 23 outputs `intList2` (see Line 22 in the sample run, which contains the output of Lines 22 and 23). The statement in Line 24 destroys `intList2`. The statement in Line 27 outputs `intList2`, which is empty. (See Line 26 in the sample run, which contains the output of Lines 26 and 27.) After destroying `intList2`, the program outputs the contents of `intList1` and `intList3` (see Lines 28 and 30 in the sample run). The sample run clearly shows that the destruction of `intList2` affects neither `intList1` nor `intList3`, because `intList1` and `intList3` each have their own data.

## Overloading Unary Operators

The process of overloading unary operators is similar to the process of overloading binary operators. The only difference is that in the case of binary operators, the operator has two operands. In the case of unary operators, the operator has only one parameter. Therefore, to overload a unary operator for a class:

1. If the operator function is a member of the class, it has no parameters.
2. If the operator function is a nonmember—that is, a **friend** function of the class—it has one parameter.

Next, we describe how to overload the increment and decrement operators.

### OVERLOADING THE INCREMENT (++) AND DECREMENT (--) OPERATORS

The increment operator has two forms: pre-increment (`++u`) and post-increment (`u++`), in which `u` is a variable, say, of type `int`. In the case of pre-increment, `++u`, the value of the variable, `u`, is incremented by 1 before the value of `u` is used in an expression. In the case of post-increment, the value of `u` is used in the expression before it is incremented by 1.

*Overloading the Pre-Increment Operator.* Overloading the pre-increment operator is quite straightforward. In the function definition, first we increment the value of the object, and then we use the pointer `this` to return the object's value.

For example, suppose that we overload the pre-increment operator for the **class** `rectangleType` to increment the length and width of a rectangle by 1. Also, suppose that the operator function `operator++` is a member of the **class** `rectangleType`. The operator function `operator++` then has no parameters. Because the operator function `operator++` has no parameters, we use the pointer `this` to return the incremented value of the object:

```
rectangleType rectangleType::operator++()
{
 //increment the length and width
 ++length;
 ++width;
```

```
 return *this; //return the incremented value of the object
}
```

Because `myRectangle` is an object of type `rectangleType`, the statement:

```
++myRectangle;
```

increments the values of the length and width of `myRectangle` by 1. Moreover, the pointer `this` associated with `myRectangle` returns the incremented value of `myRectangle`, which is ignored.

Now, `yourRectangle` is also an object of type `rectangleType`, so the statement:

```
yourRectangle = ++myRectangle;
```

increments the length and width of `myRectangle` by 1, and the pointer `this` associated with `myRectangle` returns the incremented value of `myRectangle`, which is copied into `yourRectangle`.

### GENERAL SYNTAX TO OVERLOAD THE PRE-INCREMENT OPERATOR ++ AS A MEMBER FUNCTION

The general syntax to overload the pre-increment operator `++` as a member function is described next.

**Function Prototype** (to be included in the definition of the class):

```
className operator++();
```

#### Function Definition:

```
className className::operator++()
{
 //increment the value of the object by 1
 return *this;
}
```

The operator function to overload the pre-increment operator can also be a nonmember of the `class` `rectangleType`, which we describe next.

Because the operator function `operator++` is a nonmember function of the `class` `rectangleType`, it has one parameter, which is an object of type `rectangleType`. (As before, we assume that the increment operator increments the length and width of a rectangle by 1.)

```
rectangleType operator++(rectangleType& rectangle)
{
 //increment the length and width of the rectangle
 (rectangle.length)++;
 (rectangle.width)++;
 return rectangle; //return the incremented
 //value of the object
}
```

**GENERAL SYNTAX TO OVERLOAD THE PRE-INCREMENT OPERATOR ++ AS A NONMEMBER FUNCTION**

The general syntax to overload the pre-increment operator ++ as a nonmember function is described next.

**Function Prototype** (to be included in the definition of the class):

```
friend className operator++(className&);
```

**Function Definition:**

```
className operator++(className& incObj)
{
 //increment incObj by 1
 return incObj;
}
```

**OVERLOADING THE POST-INCREMENT OPERATOR**

We now discuss how to overload the post-increment operator. As in the case of the pre-increment operator, we first describe the overloading of this operator as a member of a class.

Let us overload the post-increment operator for the `class rectangleType`. In both cases, pre- and post-increment, the name of the operator function is the same—`operator++`. To distinguish between pre- and post-increment operator overloading, we use a dummy parameter (of type `int`) in the function heading of the operator function. Thus, the function prototype for the post-increment operator of the `class rectangleType` is:

```
rectangleType operator++(int);
```

The statement:

```
myRectangle++;
```

is compiled by the compiler in the statement:

```
myRectangle.operator++(0);
```

and so the function `operator++` with a parameter executes. The parameter 0 is used merely to distinguish between the pre- and post-increment operator functions.

The post-increment operator first uses the value of the object in the expression and then increments the value of the object. So the steps required to implement this function are:

1. Save the value of the object—in, say, `temp`.
2. Increment the value of the object.
3. Return the value that was saved in `temp`.

The function definition of the post-increment operator for the `class rectangleType` is:

```
rectangleType rectangleType::operator++(int u)
```

```

{
 rectangleType temp = *this; //use this pointer to copy
 //the value of the object

 //increment the length and width
 length++;
 width++;

 return temp; //return the old value of the object
}

```

### GENERAL SYNTAX TO OVERLOAD THE POST-INCREMENT OPERATOR ++ AS A MEMBER FUNCTION

The general syntax to overload the post-increment operator ++ as a member function is described next.

**Function Prototype** (to be included in the definition of the class):

```
className operator++(int);
```

**Function Definition:**

```

className className::operator++(int u)
{
 className temp = *this; //use this pointer to copy
 //the value of the object

 //increment the object

 return temp; //return the old value of the object
}

```

The post-increment operator can also be overloaded as a nonmember function of the class. In this situation, the operator function `operator++` has two parameters. The definition of the function to overload the post-increment operator for the `class rectangleType` as a nonmember is:

```

rectangleType operator++(rectangleType& rectangle, int u)
{
 rectangleType temp = rectangle; //copy rectangle into temp

 //increment the length and width of rectangle
 (rectangle.length)++;
 (rectangle.width)++;

 return temp; //return the old value of the object
}

```

### GENERAL SYNTAX TO OVERLOAD THE POST-INCREMENT OPERATOR ++ AS A NONMEMBER FUNCTION

The general syntax to overload the post-increment operator ++ as a nonmember function is described next.

**Function Prototype** (to be included in the definition of the class):

```
friend className operator++(className&, int);
```

**Function Definition:**

```
className operator++(className& incObj, int u)
{
 className temp = incObj; //copy incObj into temp

 //increment incObj

 return temp; //return the old value of the object
}
```

The decrement operators can be overloaded in a similar way, the details of which are left as an exercise for you.

Let us now write the definition of the `class rectangleType` and show how the operator functions appear in the class definition. Because certain operators can be overloaded as either member or nonmember functions, we give two equivalent definitions of the `class rectangleType`. In the first definition, the increment, decrement, arithmetic, and relational operators are overloaded as member functions. In the second definition, the increment, decrement, arithmetic, and relational operators are overloaded as nonmember functions.

The definition of the `class rectangleType` is as follows:

```
//Definition of the class rectangleType
//The increment, decrement, arithmetic, and relational
//operator functions are members of the class.

#include <iostream>

using namespace std;

class rectangleType
{
 //Overload the stream insertion and extraction operators
 friend ostream& operator<<(ostream&, const rectangleType &);
 friend istream& operator>>(istream&, rectangleType &);

public:
 void setDimension(double l, double w);
 double getLength() const;
 double getWidth() const;
 double area() const;
 double perimeter() const;

 //Overload the arithmetic operators
 rectangleType operator+(const rectangleType &) const;
 rectangleType operator-(const rectangleType &) const;
```



```

 //Overload the increment and decrement operators
 friend rectangleType operator++(rectangleType&);
 //pre-increment
 friend rectangleType operator++(rectangleType&, int);
 //post-increment
 friend rectangleType operator--(rectangleType&);
 //pre-decrement
 friend rectangleType operator--(rectangleType&, int);
 //post-decrement

 //Overload the relational operators
 friend bool operator==(const rectangleType&,
 const rectangleType&);
 friend bool operator!=(const rectangleType&,
 const rectangleType&);
 friend bool operator<=(const rectangleType&,
 const rectangleType&);
 friend bool operator<(const rectangleType&,
 const rectangleType&);
 friend bool operator>=(const rectangleType&,
 const rectangleType&);
 friend bool operator>(const rectangleType&,
 const rectangleType&);

public:
 void setDimension(double l, double w);
 double getLength() const;
 double getWidth() const;
 double area() const;
 double perimeter() const;

 //Constructors
 rectangleType();
 rectangleType(double l, double w);

private:
 double length;
 double width;
};

```

The definitions of the functions to overload the operators for the `class rectangleType` are left as an exercise for you. (See Programming Exercises 1 and 2 at the end of this chapter.)

## Operator Overloading: Member versus Nonmember

The preceding sections discussed and illustrated how to overload operators. Certain operators must be overloaded as member functions of the class, and some must be overloaded as nonmember (`friend`) functions. What about the operators that can be overloaded as either member functions or nonmember functions? For example, the binary arithmetic operator `+` can be overloaded as a member function or a nonmember function. If you overload `+` as a member function, then the operator `+` has direct access to the member variables of one of the objects, and you need to pass only one object as a

parameter. On the other hand, if you overload `+` as a nonmember function, then you must pass both objects as parameters. When both objects are passed as parameters, the code may become somewhat clearer. So it is a matter of preference whether you overload `+` as a member or as a nonmember function. In the remainder of this chapter, if we overload an operator as a member function, we will leave it as an exercise for you to overload it as a nonmember function.

## Classes and Pointer Member Variables (Revisited)

Chapter 14 described the peculiarities of classes with pointer member variables. Now that we have discussed how to overload various operators, let us review the peculiarities of classes with pointer member variables, for the sake of completeness, and how to avoid them.

Recall that the only built-in operations on classes are assignment and member selection. The assignment operator provides a member-wise copy of the data. That is, the member variables of an object are copied into the corresponding member variables of another object of the same type. We have seen that this member-wise copy does not work well for classes with pointer member variables. Other problems that may arise with classes with pointer member variables relate to deallocating dynamic memory when an object goes out of scope and passing a class object as a parameter by value. To resolve these problems, classes with pointer member variables must:

1. Explicitly overload the assignment operator
2. Include the copy constructor
3. Include the destructor

## Operator Overloading: One Final Word

Next, we look at three examples that illustrate operator overloading. Before delving into these examples, you must remember the following: Suppose that an operator `op` is overloaded for a `class`—say, `rectangleType`. Whenever we use the operator `op` on objects of type `rectangleType`, the body of the function that overloads the operator `op` for the `class rectangleType` executes. Therefore, whatever code you put in the body of the function executes.

### PROGRAMMING EXAMPLE: `clockType`

Chapter 12 defined a `class clockType` to implement the time of day in a program. We implemented the operations to print the time, increment the time, and compare the two times for equality using functions. This example redefines the `class clockType`. It also overloads the stream insertion and extraction operators for easy input and output, relational operators for comparisons, and the increment operator to increment the time by one second. The program that uses the `class clockType` requires the user to input the time in the form `hr:min:sec`.

The definition of the `class` `clockType` is as follows:

```
//Header file newClock.h

#ifndef H_newClock
#define H_newClock

#include <iostream>

using namespace std;

class clockType
{
 friend ostream& operator<<(ostream&, const clockType&);
 friend istream& operator>>(istream&, clockType&);

public:
 void setTime(int hours, int minutes, int seconds);
 //Function to set the member variables hr, min, and sec.
 //Postcondition: hr = hours; min = minutes; sec = seconds;

 void getTime(int& hours, int& minutes, int& seconds) const;
 //Function to return the time.
 //Postcondition: hours = hr; minutes = min; seconds = sec;

 clockType operator++();
 //Overload the pre-increment operator.
 //Postcondition: The time is incremented by one second.

 bool operator==(const clockType& otherClock) const;
 //Overload the equality operator.
 //Postcondition: Returns true if the time of this clock
 // is equal to the time of otherClock,
 // otherwise it returns false.

 bool operator!=(const clockType& otherClock) const;
 //Overload the not equal operator.
 //Postcondition: Returns true if the time of this clock
 // is not equal to the time of otherClock,
 // otherwise it returns false.

 bool operator<=(const clockType& otherClock) const;
 //Overload the less than or equal to operator.
 //Postcondition: Returns true if the time of this clock
 // is less than or equal to the time of
 // otherClock, otherwise it returns false.

 bool operator<(const clockType& otherClock) const;
 //Overload the less than operator.
 //Postcondition: Returns true if the time of this clock
 // is less than the time of otherClock,
 // otherwise it returns false.
```

```

bool operator>=(const clockType& otherClock) const;
 //Overload the greater than or equal to operator.
 //Postcondition: Returns true if the time of this clock
 // is greater than or equal to the time of
 // otherClock, otherwise it returns false.

bool operator>(const clockType& otherClock) const;
 //Overload the greater than operator.
 //Postcondition: Returns true if the time of this clock
 // is greater than the time of otherClock,
 // otherwise it returns false.

clockType(int hours = 0, int minutes = 0, int seconds = 0);
 //Constructor to initialize the object with the values
 //specified by the user. If no values are specified,
 //the default values are assumed.
 //Postcondition: hr = hours; min = minutes;
 // sec = seconds;

private:
 int hr; //variable to store the hours
 int min; //variable to store the minutes
 int sec; //variable to store the seconds
};

#endif

```

Figure 15-1 shows a UML class diagram of the `class` `clockType`.




FIGURE 15-1 UML class diagram of the `class` `clockType`

Let us now write the definitions of the functions to implement the operations of the `class clockType`. Notice that the `class clockType` overloads only the pre-increment operator. For consistency, however, the class should also overload the post-increment operator. This step is left as an exercise for you. (See Programming Exercise 3 at the end of this chapter.)

First, we write the definition of the function `operator++`. The algorithm to increment the time by one second is as follows:

- a. Increment the seconds by 1.
- b. If seconds > 59,
  - b.1. Set the seconds to 0.
  - b.2. Increment the minutes by 1.
  - b.3. If minutes > 59
    - b.3.1. Set the minutes to 0.
    - b.3.2. Increment the hours by 1.
    - b.3.3. If hours > 23,
      - b.3.3.1. Set the hours to 0.
- c. Return the incremented value of the object.

The definition of the function `operator++` is:

```
//Overload the pre-increment operator.
clockType clockType::operator++()
{
 sec++; //Step a

 if (sec > 59) //Step b
 {
 sec = 0; //Step b.1
 min++; //Step b.2

 if (min > 59) //Step b.3
 {
 min = 0; //Step b.3.1
 hr++; //Step b.3.2

 if (hr > 23) //Step b.3.3
 hr = 0; //Step b.3.3.1
 }
 }

 return *this; //Step c
}
```

The definition of the function `operator==` is quite simple. The two times are the same if they have the same hours, minutes, and seconds. Therefore, the definition of the function `operator==` is:

```

//Overload the equality operator.
bool clockType::operator==(const clockType& otherClock) const
{
 return (hr == otherClock.hr && min == otherClock.min
 && sec == otherClock.sec);
}

```

The definition of the function `operator<=` is given next. The first time is less than or equal to the second time if:

1. The hours of the first time are less than the hours of the second time, or
2. The hours of the first time and the second time are the same, but the minutes of the first time are less than the minutes of the second time, or
3. The hours and minutes of the first time and the second time are the same, but the seconds of the first time are less than or equal to the seconds of the second time.

The definition of the function `operator<=` is:

```

//Overload the less than or equal to operator.
bool clockType::operator<=(const clockType& otherClock) const
{
 return ((hr < otherClock.hr) ||
 (hr == otherClock.hr && min < otherClock.min) ||
 (hr == otherClock.hr && min == otherClock.min &&
 sec <= otherClock.sec));
}

```

In a similar manner, we can write the definitions of the other relational operator functions as follows:

```

//Overload the not equal operator.
bool clockType::operator!=(const clockType& otherClock) const
{
 return (hr != otherClock.hr || min != otherClock.min
 || sec != otherClock.sec);
}

```

```

//Overload the less than operator.
bool clockType::operator<(const clockType& otherClock) const
{
 return ((hr < otherClock.hr) ||
 (hr == otherClock.hr && min < otherClock.min) ||
 (hr == otherClock.hr && min == otherClock.min &&
 sec < otherClock.sec));
}

```

```

//Overload the greater than or equal to operator.
bool clockType::operator>=(const clockType& otherClock) const

```

```

{
 return ((hr > otherClock.hr) ||
 (hr == otherClock.hr && min > otherClock.min) ||
 (hr == otherClock.hr && min == otherClock.min &&
 sec >= otherClock.sec));
}

//Overload the greater than operator.
bool clockType::operator>(const clockType& otherClock) const
{
 return ((hr > otherClock.hr) ||
 (hr == otherClock.hr && min > otherClock.min) ||
 (hr == otherClock.hr && min == otherClock.min &&
 sec > otherClock.sec));
}

```

(Note that after writing the definition of the function to overload the operator `==`, you can use the operator `==` to write the definition of the function to overload the operator `!=`. Similarly, you can use the operators `==` and `<` to write the definition of the function to overload the operator `<=`, and so on. We leave the details as an exercise.)

The definitions of the functions `setTime` and `getTime` are the same as given in Chapter 12. They are included here for the sake of completeness. Moreover, we have modified the definition of the constructor so that it uses the function `setTime` to set the time. The definitions are as follows:

```

void clockType::setTime(int hours, int minutes, int seconds)
{
 if (0 <= hours && hours < 24)
 hr = hours;
 else
 hr = 0;

 if (0 <= minutes && minutes < 60)
 min = minutes;
 else
 min = 0;

 if (0 <= seconds && seconds < 60)
 sec = seconds;
 else
 sec = 0;
}

void clockType::getTime(int& hours, int& minutes,
 int& seconds) const
{
 hours = hr;
 minutes = min;
 seconds = sec;
}

```

```

 //Constructor
clockType::clockType(int hours, int minutes, int seconds)
{
 setTime(hours, minutes, seconds);
}

```

We now discuss the definition of the function `operator<<`. The time must be output in the form:

```
hh:mm:ss
```

The algorithm to output the time in this format is the same as the body of the `printTime` function of `clockType` given in Chapter 12. Here, after printing the time in the previous format, we must return the `ostream` object. Therefore, the definition of the function `operator<<` is:

```

//Overload the stream insertion operator.
ostream& operator<<(ostream& osObject, const clockType& timeOut)
{
 if (timeOut.hr < 10)
 osObject << '0';
 osObject << timeOut.hr << ':';

 if (timeOut.min < 10)
 osObject << '0';
 osObject << timeOut.min << ':';

 if (timeOut.sec < 10)
 osObject << '0';
 osObject << timeOut.sec;

 return osObject; //return the ostream object
}

```

Let us now discuss the definition of the function `operator>>`. The input to the program is of the form:

```
hh:mm:ss
```

That is, the input is the hours followed by a colon, followed by the minutes, followed by a colon, followed by the seconds. Clearly, the algorithm to input the time is:

- Get the input, which is a number, and store it in the member variable `hr`. Also check if the input is valid.
- Get the next input, which is a colon, and discard it.
- Get the next input, which is a number, and store it in the member variable `min`. Also check if the input is valid.
- Get the next input, which is a colon, and discard it.
- Get the next input, which is a number, and store it in the member variable `sec`. Also check if the input is valid.
- Return the `istream` object.

Clearly, we need a local variable of type `char` to read the colon.

The definition of the function `operator>>` is:

```
//overload the stream extraction operator
istream& operator>> (istream& is, clockType& timeIn)
{
 char ch;

 is >> timeIn.hr; //Step a

 if (timeIn.hr < 0 || timeIn.hr >= 24) //Step a
 timeIn.hr = 0;

 is.get(ch); //Read and discard :. Step b

 is >> timeIn.min; //Step c

 if (timeIn.min < 0 || timeIn.min >= 60) //Step c
 timeIn.min = 0;

 is.get(ch); //Read and discard :. Step d

 is >> timeIn.sec; //Step e

 if (timeIn.sec < 0 || timeIn.sec >= 60) //Step e
 timeIn.sec = 0;

 return is; //Step f
}
```

The following test program uses the `class` `clockType`:

```
//*****
// Author: D.S. Malik
//
// This program shows how to use the class clockType.
//*****

#include <iostream>
#include "newClock.h"

using namespace std;

int main()
{
 clockType myClock(5, 6, 23); //Line 1
 clockType yourClock; //Line 2

 cout << "Line 3: myClock = " << myClock
 << endl; //Line 3
}
```

```

 cout << "Line 4: yourClock = " << yourClock
 << endl; //Line 4

 cout << "Line 5: Enter the time in the form "
 << "hr:min:sec "; //Line 5
 cin >> myClock; //Line 6
 cout << endl; //Line 7

 cout << "Line 8: The new time of myClock = "
 << myClock << endl; //Line 8

 ++myClock; //Line 9

 cout << "Line 10: After incrementing the time, "
 << "myClock = " << myClock << endl; //Line 10

 yourClock.setTime(13, 35, 38); //Line 11

 cout << "Line 12: After setting the time, "
 << "yourClock = " << yourClock << endl; //Line 12

 if (myClock == yourClock) //Line 13
 cout << "Line 14: The times of myClock and "
 << "yourClock are equal." << endl; //Line 14
 else //Line 15
 cout << "Line 16: The times of myClock and "
 << "yourClock are not equal." << endl; //Line 16

 if (myClock <= yourClock) //Line 17
 cout << "Line 18: The time of myClock is "
 << "less than or equal to " << endl
 << "the time of yourClock." << endl; //Line 18
 else //Line 19
 cout << "Line 20: The time of myClock is "
 << "greater than the time of "
 << "yourClock." << endl; //Line 20

 return 0;
}

```

**Sample Run:** In this sample run, the user input is shaded.

```

Line 3: myClock = 05:06:23
Line 4: yourClock = 00:00:00
Line 5: Enter the time in the form hr:min:sec 4:50:59

```

```

Line 8: The new time of myClock = 04:50:59
Line 10: After incrementing the time, myClock = 04:51:00
Line 12: After setting the time, yourClock = 13:35:38
Line 16: The times of myClock and yourClock are not equal.
Line 18: The time of myClock is less than or equal to
the time of yourClock.

```

## PROGRAMMING EXAMPLE: Complex Numbers

A number of the form  $a + ib$ , in which  $i^2 = -1$  and  $a$  and  $b$  are real numbers, is called a **complex number**. We call  $a$  the real part and  $b$  the imaginary part of  $a + ib$ . Complex numbers can also be represented as ordered pairs  $(a, b)$ . The addition and multiplication of complex numbers are defined by the following rules:

$$(a + ib) + (c + id) = (a + c) + i(b + d)$$

$$(a + ib) \star (c + id) = (ac - bd) + i(ad + bc)$$

Using the ordered pair notation, these rules are written as:

$$(a, b) + (c, d) = ((a + c), (b + d))$$

$$(a, b) \star (c, d) = ((ac - bd), (ad + bc))$$

C++ has no built-in data type that allows us to manipulate complex numbers. In this example, we will construct a data type, `complexType`, that can be used to process complex numbers. We will overload the stream insertion and stream extraction operators for easy input and output. We will also overload the operators  $+$  and  $\star$  to perform addition and multiplication of complex numbers. If  $x$  and  $y$  are complex numbers, we can evaluate expressions such as  $x + y$  and  $x \star y$ .

```
//Specification file complexType.h

#ifndef H_complexNumber
#define H_complexNumber

#include <iostream>
using namespace std;

class complexType
{
 //Overload the stream insertion and extraction operators
 friend ostream& operator<<(ostream&, const complexType&);
 friend istream& operator>>(istream&, complexType&);

public:
 void setComplex(const double& real, const double& imag);
 //Function to set the complex numbers according to
 //the parameters.
 //Postcondition: realPart = real; imaginaryPart = imag;

 void getComplex(double& real, double& imag) const;
 //Function to retrieve the complex number.
 //Postcondition: real = realPart; imag = imaginaryPart;
```

```

complexType(double real = 0, double imag = 0);
 //Constructor
 //Initializes the complex number according to
 //the parameters.
 //Postcondition: realPart = real; imaginaryPart = imag;

complexType operator+
 (const complexType& otherComplex) const;
 //Overload the operator +

complexType operator*
 (const complexType& otherComplex) const;
 //Overload the operator *

bool operator==(const complexType& otherComplex) const;
 //Overload the operator ==
private:
 double realPart; //variable to store the real part
 double imaginaryPart; //variable to store the
 //imaginary part
};

#endif

```

Figure 15-2 shows a UML class diagram of the `class` `complexType`.




FIGURE 15-2 UML class diagram of the `class` `complexType`

Next, we write the definitions of the functions to implement various operations of the `class` `complexType`.

The definitions of most of these functions are straightforward. We will discuss only the definitions of the functions to overload the stream insertion operator, `<<`, and the stream extraction operator, `>>`.

To output a complex number in the form:

(a, b)

in which **a** is the real part and **b** is the imaginary part, clearly the algorithm is:

- a. Output the left parenthesis, (.
- b. Output the real part.
- c. Output the comma and a space.
- d. Output the imaginary part.
- e. Output the right parenthesis, ).

Therefore, the definition of the function `operator<<` is:

```
ostream& operator<<(ostream& osObject,
 const complexType& complex)
{
 osObject << "("; //Step a
 osObject << complex.realPart; //Step b
 osObject << ", "; //Step c
 osObject << complex.imaginaryPart; //Step d
 osObject << ")"; //Step e

 return osObject; //return the ostream object
}
```

Next, we discuss the definition of the function to overload the stream extraction operator, `>>`.

The input is of the form:

(3, 5)

In this input, the real part of the complex number is 3, and the imaginary part is 5. Clearly, the algorithm to read this complex number is:

- a. Read and discard the left parenthesis.
- b. Read and store the real part.
- c. Read and discard the comma.
- d. Read and store the imaginary part.
- e. Read and discard the right parenthesis.

Following these steps, the definition of the function `operator>>` is:

```
istream& operator>>(istream& isObject, complexType& complex)
{
 char ch;

 isObject >> ch; //Step a
 isObject >> complex.realPart; //Step b
```

```

 isObject >> ch; //Step c
 isObject >> complex.imaginaryPart; //Step d
 isObject >> ch; //Step e

 return isObject; //return the istream object
 }

```

The definitions of the other functions are as follows:

```

bool complexType::operator==
 (const complexType& otherComplex) const
{
 return (realPart == otherComplex.realPart &&
 imaginaryPart == otherComplex.imaginaryPart);
}

//Constructor
complexType::complexType(double real, double imag)
{
 realPart = real;
 imaginaryPart = imag;
}

//Function to set the complex number after the object
//has been declared.
void complexType::setComplex(const double& real,
 const double& imag)
{
 realPart = real;
 imaginaryPart = imag;
}

void complexType::getComplex(double& real, double& imag) const
{
 real = realPart;
 imag = imaginaryPart;
}

//overload the operator +
complexType complexType::operator+
 (const complexType& otherComplex) const
{
 complexType temp;

 temp.realPart = realPart + otherComplex.realPart;
 temp.imaginaryPart = imaginaryPart
 + otherComplex.imaginaryPart;

 return temp;
}

```

```

 //overload the operator *
complexType complexType::operator*
 (const complexType& otherComplex) const
{
 complexType temp;
 temp.realPart = (realPart * otherComplex.realPart) -
 (imaginaryPart * otherComplex.imaginaryPart);
 temp.imaginaryPart = (realPart * otherComplex.imaginaryPart)
 + (imaginaryPart * otherComplex.realPart);
 return temp;
}

```

The following program illustrates the use of the `class` `complexType`:

```

//*****
// Author: D.S. Malik
//
// This program shows how to use the class complexType.
//*****

#include <iostream>
#include "complexType.h"

using namespace std;

int main()
{
 complexType num1(23, 34); //Line 1
 complexType num2; //Line 2
 complexType num3; //Line 3

 cout << "Line 4: Num1 = " << num1 << endl; //Line 4
 cout << "Line 5: Num2 = " << num2 << endl; //Line 5

 cout << "Line 6: Enter the complex number "
 << "in the form (a, b) "; //Line 6
 cin >> num2; //Line 7
 cout << endl; //Line 8

 cout << "Line 9: New value of num2 = "
 << num2 << endl; //Line 9

 num3 = num1 + num2; //Line 10

 cout << "Line 11: Num3 = " << num3 << endl; //Line 11

 cout << "Line 12: " << num1 << " + " << num2
 << " = " << num1 + num2 << endl; //Line 12

 cout << "Line 13: " << num1 << " * " << num2
 << " = " << num1 * num2 << endl; //Line 13

 return 0;
}

```

**Sample Run:** In this sample run, the user input is shaded.

```
Line 4: Num1 = (23, 34)
Line 5: Num2 = (0, 0)
Line 6: Enter the complex number in the form (a, b) (3, 4)
Line 9: New value of num2 = (3, 4)
Line 11: Num3 = (26, 38)
Line 12: (23, 34) + (3, 4) = (26, 38)
Line 13: (23, 34) * (3, 4) = (-67, 194)
```

You can extend this data type to perform subtraction and division on complex numbers.

Next, we will define a class, called `newString`, and overload the assignment and relational operators. That is, when we declare a variable of type `newString`, we will be able to use the assignment operator to copy one string into another and relational operators to compare the two strings.

Before discussing the `class newString`, however, we examine the overloading of the operator `[]`. Recall that we have used the operator `[]` to access the components of an array. To access individual characters in a string of type `newString`, we have to overload the operator `[]` for the `class newString`.

## Overloading the Array Index (Subscript) Operator (`[]`)

Recall that the function to overload the operator `[]` for a class must be a member of the class. Furthermore, because an array can be declared as constant or nonconstant, we need to overload the operator `[]` to handle both cases.

The syntax to declare the operator function `operator[]` as a member of a class for nonconstant arrays is:

```
Type& operator[](int index);
```

The syntax to declare the operator function `operator[]` as a member of a class for constant arrays is:

```
const Type& operator[](int index) const;
```

in which `Type` is the data type of the array elements.

Suppose that `classTest` is a class that has an array member variable. The definition of `classTest` to overload the operator `[]` is:

```
class classTest
{
public:
```

```

Type& operator[](int index);
 //Overload the operator for nonconstant arrays
const Type& operator[](int index) const;
 //Overload the operator for constant arrays
 .
 .
 .
private:
 Type *list; //pointer to the array
 int arraySize;
};

```

in which `Type` is the data type of the array elements.

The definitions of the functions to overload the operator `[]` for `classTest` are:

```

 //Overload the operator [] for nonconstant arrays
Type& classTest::operator[](int index)
{
 assert(0 <= index && index < arraySize);
 return list[index]; //return a pointer of the
 //array component
}

 //Overload the operator [] for constant arrays
const Type& classTest::operator[](int index) const
{
 assert(0 <= index && index < arraySize);
 return list[index]; //return a pointer of the
 //array component
}

```

#### NOTE

The preceding function definitions use the `assert` statement. (For an explanation of the `assert` statement, see Chapter 4 or the Appendix.)

Consider the following statements:

```

classTest list1;
classTest list2;
const classTest list3;

```

In the case of the statement:

```
list1[2] = list2[3];
```

the body of the operator function `operator[]` for nonconstant arrays is executed. In the case of the statement:

```
list1[2] = list3[5];
```

first, the body of the operator function `operator[]` for constant arrays is executed because `list3` is a constant array. Next, the body of the operator function `operator[]` for nonconstant arrays is executed to complete the execution of the assignment statement.

## PROGRAMMING EXAMPLE: newString

Chapter 9 discussed C-strings. Recall that:

1. A C-string is a sequence of one or more characters.
2. C-strings are enclosed in double quotation marks.
3. C-strings are null terminated.
4. C-strings are stored in character arrays.

The only aggregate operations allowed on C-strings are input and output. To use other operations, the programmer needs to include the header file `cstring`, which contains the specifications of many functions for string manipulation.

Initially, C++ did not provide any built-in data types to handle C-strings. More recent versions of C++, however, provide a string class to handle C-strings and operations on C-strings.

Our objective in this example is to define our own class for C-string manipulation and, at the same time, to further illustrate operator overloading. More specifically, we overload the assignment operator, the relational operators, and the stream insertion and extraction operators for easy input and output. Let us call this `class newString`. First, we give the definition of the `class newString`:

```
//Header file myString.h

#ifndef H_myString
#define H_myString

#include <iostream>

using namespace std;

class newString
{
 //Overload the stream insertion and extraction operators.
 friend ostream& operator << (ostream&, const newString&);
 friend istream& operator >> (istream&, newString&);

public:
 const newString& operator=(const newString&);
 //overload the assignment operator
 newString(const char *);
 //constructor; conversion from the char string
 newString();
 //Default constructor to initialize the string to null
 newString(const newString&);
 //Copy constructor
```

```

~newString();
 //Destructor
char &operator[] (int);
const char &operator[](int) const;

 //overload the relational operators
bool operator==(const newString& const;
bool operator!=(const newString& const;
bool operator<=(const newString& const;
bool operator<(const newString& const;
bool operator>=(const newString& const;
bool operator>(const newString& const;

private:
 char *strPtr; //pointer to the char array
 //that holds the string
 int strLength; //variable to store the length
 //of the string
};

#endif

```

The `class newString` has two `private` member variables: one to store the C-string and one to store the length of the C-string.

Next, we give the definitions of the functions to implement the `newString` operations. The implementation file includes the header file `cassert` because we are using the function `assert`. (For an explanation of the function `assert`, see Chapter 4 or the header file `cassert` in the Appendix).

```

//Implementation file myStringImp.cpp
#include <iostream>
#include <iomanip>
#include <cstring>
#include <cassert>
#include "myString.h"

using namespace std;

 //Constructor: conversion from the char string to newString
newString::newString(const char *str)
{
 strLength = strlen(str);
 strPtr = new char[strLength + 1]; //allocate memory to
 //store the char string
 strcpy(strPtr, str); //copy string into strPtr
}

```

```

 //Default constructor to store the null string
newString::newString()
{
 strLength = 0;
 strPtr = new char[1];
 strcpy(strPtr, "");
}

newString::newString(const newString& rightStr) //copy constructor
{
 strLength = rightStr.strLength;
 strPtr = new char[strLength + 1];
 strcpy(strPtr, rightStr.strPtr);
}

newString::~newString() //destructor
{
 delete [] strPtr;
}

//overload the assignment operator
const newString& newString::operator=(const newString& rightStr)
{
 if (this != &rightStr) //avoid self-copy
 {
 delete [] strPtr;
 strLength = rightStr.strLength;
 strPtr = new char[strLength + 1];
 strcpy(strPtr, rightStr.strPtr);
 }

 return *this;
}

char& newString::operator[] (int index)
{
 assert(0 <= index && index < strLength);
 return strPtr[index];
}

const char& newString::operator[](int index) const
{
 assert(0 <= index && index < strLength);
 return strPtr[index];
}

//Overload the relational operators.
bool newString::operator==(const newString& rightStr) const
{
 return (strcmp(strPtr, rightStr.strPtr) == 0);
}

```

```

bool newString::operator<(const newString& rightStr) const
{
 return (strcmp(strPtr, rightStr.strPtr) < 0);
}

bool newString::operator<=(const newString& rightStr) const
{
 return (strcmp(strPtr, rightStr.strPtr) <= 0);
}

bool newString::operator>(const newString& rightStr) const
{
 return (strcmp(strPtr, rightStr.strPtr) > 0);
}

bool newString::operator>=(const newString& rightStr) const
{
 return (strcmp(strPtr, rightStr.strPtr) >= 0);
}

bool newString::operator!=(const newString& rightStr) const
{
 return (strcmp(strPtr, rightStr.strPtr) != 0);
}

//Overload the stream insertion operator <<
ostream& operator << (ostream& osObject, const newString& str)
{
 osObject << str.strPtr;

 return osObject;
}

//Overload the stream extraction operator >>
istream& operator >> (istream& isObject, newString& str)
{
 char temp[81];

 isObject >> setw(81) >> temp;
 str = temp;
 return isObject;
}

```

Consider the statement:

```
isObject >> setw(81) >> temp;
```

in the definition of the function `operator>>`. Because `temp` is declared to be an array of size 81, the largest string that can be stored into `temp` is of length 80. The manipulator `setw` in this statement (that is, in the input statement) ensures that no more than 80 characters are read into `temp`.



```

newString str3; //initialize str3 to the empty string
newString str4; //initialize str4 to the empty string

cout << "Line 1: " << str1 << " " << str2
 << " ***" << str3 << "###." << endl; //Line 1

if (str1 <= str2) //compare str1 and str2; Line 2
 cout << "Line 3: " << str1 << " is less "
 << "than or equal to" << str2 << endl; //Line 3
else //Line 4
 cout << "Line 5: " << str2 << " is less "
 << "than " << str1 << endl; //Line 5

cout << "Line 6: Enter a string with a length "
 << "of at least 7: "; //Line 6
cin >> str1; //input str1; Line 7
cout << endl; //Line 8

cout << "Line 9: The new value of "
 << "str1 = " << str1 << endl; //Line 9

str4 = str3 = "Birth Day"; //Line 10

cout << "Line 11: str3 = " << str3
 << ", str4 = " << str4 << endl; //Line 11

str3 = str1; //Line 12
cout << "Line 13: The new value of str3 = "
 << str3 << endl; //Line 13

str1 = "Bright Sky"; //Line 14

str3[1] = str1[5]; //Line 15
cout << "Line 16: After replacing the second "
 << "character of str3 = " << str3 << endl; //Line 16

str3[2] = str2[0]; //Line 17
cout << "Line 18: After replacing the third "
 << "character of str3 = " << str3 << endl; //Line 18

str3[5] = 'g'; //Line 19
cout << "Line 20: After replacing the sixth "
 << "character of str3 = " << str3 << endl; //Line 20

return 0;
}

```

**Sample Run:** In this sample run, the user input is shaded.

```

Line 1: Sunny Warm ***###.
Line 3: Sunny is less than or equal to Warm

```

```

Line 6: Enter a string with a length of at least 7: 123456789
Line 9: The new value of str1 = 123456789
Line 11: str3 = Birth Day, str4 = Birth Day
Line 13: The new value of str3 = 123456789
Line 16: After replacing the second character of str3 = 1t3456789
Line 18: After replacing the third character of str3 = 1tW456789
Line 20: After replacing the sixth character of str3 = 1tW45g789

```

The preceding program works as follows. The statement in Line 1 outputs the values of `str1`, `str2`, and `str3`. Notice that the value of `str3` is to be printed between `***` and `###`. Because `str3` is empty, nothing is printed between `***` and `###`; see Line 1 in the sample run. The statements in Lines 2 through 5 compare `str1` and `str2` and output the result. The statement in Line 7 inputs a string with a length of at least 7 into `str1`, and the statement in Line 9 outputs the new value of `str1`. Note that in the statement (see Line 10):

```
str4 = str3 = "Birth Day";
```

Because the associativity of the assignment operator is from right to left, first the statement `str3 = "Birth Day";` executes, and then the statement `str4 = str3;` executes. The statement in Line 11 outputs the values of `str3` and `str4`. The statements in Lines 15, 17, and 19 use the array subscripting operator `[]` to individually manipulate the characters of `str3`. The meanings of the remaining statements are straightforward.

## Function Overloading

The previous section discussed operator overloading. Operator overloading provides the programmer with the same concise notation for user-defined data types as the operator has for built-in types. The types of parameters used with an operator determine the action to take. Similar to operator overloading, C++ allows the programmer to overload a function name. Chapter 7 introduced function overloading. For easy reference in the following discussion, let us review this concept.

Recall that a class can have more than one constructor, but all constructors of a class have the same name, which is the name of the class. This is an example of overloading a function. Further recall that overloading a function refers to having several functions with the same name but different parameter lists. The parameter list determines which function will execute.

For function overloading to work, we must give the definition of each function. The next section teaches you how to overload functions with a single code segment and leave the job of generating code for separate functions for the compiler.

# Templates

Templates are a very powerful feature of C++. They allow you to write a single code segment for a set of related functions, called a **function template**, and for a set of related classes, called a **class template**. The syntax we use for templates is:

```
template <class Type>
declaration;
```

in which **Type** is the name of a data type, built-in or user-defined, and **declaration** is either a function declaration or a class declaration. In C++, **template** is a reserved word. The word **class** in the heading refers to any user-defined type or built-in type. **Type** is referred to as a formal parameter to the template. (Note that in the first line, **template <class Type>**, the keyword **class** can be replaced with the keyword **typename**.)

Similar to variables being parameters to functions, types (that is, data types) are parameters to templates.

## Function Templates

In Chapter 7, when we introduced function overloading, the function **larger** was overloaded to find the larger of two integers, characters, floating-point numbers, or strings. To implement the function **larger**, we need to write four function definitions for the data type: one for **int**, one for **char**, one for **double**, and one for **string**. However, the body of each function is similar. C++ simplifies the process of overloading functions by providing function templates.

The syntax of the function template is:

```
template <class Type>
function definition;
```

in which **Type** is referred to as a formal parameter of the template. It is used to specify the type of parameters to the function and the return type of the function and to declare variables within the function.

The statements:

```
template <class Type>
Type larger(Type x, Type y)
{
 if (x >= y)
 return x;
 else
 return y;
}
```

define a function template **larger**, which returns the larger of two items. In the function heading, the type of the formal parameters **x** and **y** is **Type**, which will be specified by the type of the actual parameters when the function is called. The statement:

```
cout << larger(5, 6) << endl;
```

is a call to the function template `larger`. Because 5 and 6 are of type `int`, the data type `int` is substituted for `Type`, and the compiler generates the appropriate code.

Note that the function template `larger` will work only for those data types for which the operator `>=` has been defined.

If we omit the body of the function in the function template definition, the function template, as usual, is the prototype.

The following example illustrates the use of function templates.

### EXAMPLE 15-8

The following program uses the function template `larger` to determine the larger of the two items.

```
// Template larger
#include <iostream>
#include "myString.h"

using namespace std;

template <class Type>
Type larger(Type x, Type y);

int main()
{
 cout << "Line 1: Larger of 5 and 6 = "
 << larger(5, 6) << endl; //Line 1
 cout << "Line 2: Larger of A and B = "
 << larger('A', 'B') << endl; //Line 2
 cout << "Line 3: Larger of 5.6 and 3.2 = "
 << larger(5.6, 3.2) << endl; //Line 3

 newString str1 = "Hello"; //Line 4
 newString str2 = "Happy"; //Line 5

 cout << "Line 6: Larger of " << str1 << " and "
 << str2 << " = " << larger(str1, str2)
 << endl; //Line 6

 return 0;
}

template <class Type>
Type larger(Type x, Type y)
{
 if (x >= y)
```

```

 return x;
 else
 return y;
}

```

### Sample Run:

```

Line 1: Larger of 5 and 6 = 6
Line 2: Larger of A and B = B
Line 3: Larger of 5.6 and 3.2 = 5.6
Line 6: Larger of Hello and Happy = Hello

```

## Class Templates

Like function templates, class templates are used to write a single code segment for a set of related classes. For example, in Chapter 12, we defined a list as an ADT; our list element type was `int`. If the list element type changes from `int` to, say, `char`, `double`, or `string`, we need to write separate classes for each element type. For the most part, the operations on the list and the algorithms to implement those operations remain the same. Using class templates, we can create a generic `class listType`, and the compiler can generate the appropriate source code for a specific implementation.

The syntax we use for a class template is:

```

template <class Type>
class declaration

```

Class templates are called **parameterized types** because, based on the parameter type, a specific class is generated.

The following statements define `listType` to be a class template:

```

template<class elemType>
class listType
{
public:
 bool isEmpty() const;
 //Function to determine whether the list is empty.
 //Postcondition: Returns true if the list is empty,
 // otherwise it returns false.

 bool isFull() const;
 //Function to determine whether the list is full.
 //Postcondition: Returns true if the list is full,
 // otherwise it returns false.

 bool search(const elemType& searchItem) const;
 //Function to search the list for searchItem.
 //Postcondition: Returns true if searchItem
 // is found in the list, and
 // false otherwise.
}

```

```

void insert(const elemType& newElement);
 //Function to insert newElement in the list.
 //Precondition: Prior to insertion, the list must
 // not be full.
 //Postcondition: The list is the old list plus
 // newElement.

void remove(const elemType& removeElement);
 //Function to remove removeElement from the list.
 //Postcondition: If removeElement is found in the list,
 // it is deleted from the list, and the
 // list is the old list minus removeElement.
 // If the list is empty, output the message
 // "Cannot delete from the empty list."

void destroyList();
 //Function to destroy the list.
 //Postcondition: length = 0;

void printList();
 //Function to output the elements of the list.

listType();
 //Default constructor
 //Sets the length of the list to 0.
 //Postcondition: length = 0;

protected:
 elemType list[100]; //array to hold the list elements
 int length; //variable to store the number of
 //elements in the list
};

```

This definition of the class template `listType` is a generic definition and includes only the basic operations on a list. To derive a specific list from this list and to add or rewrite the operations, we declare the array containing the list elements and the length of the list as `protected`.

Next, we describe a specific list. Suppose that you want to create a list to process integer data. The statement:

```
listType<int> intList; //Line 1
```

declares `intList` to be an object of `listType`. The `protected` member `list` is an array of 100 components, with each component being of type `int`. Similarly, the statement:

```
listType<newString> stringList; //Line 2
```

declares `stringList` to be an object of `listType`. The `protected` member `list` is an array of 100 components, with each component being of type `newString`.

In the statements in Lines 1 and 2, `listType<int>` and `listType<newString>` are referred to as *template instantiations* or *instantiations of the class template `listType<elemType>`*, in which `elemType` is the class parameter in the template header. A template instantiation can be created with either a built-in or user-defined type.

The function members of a class template are considered function templates. Thus, when giving the definitions of the function members of a class template, we must follow the definition of the function template. For example, the definition of the member `insert` of the `class listType` is:

```
template <class elemType>
void listType<elemType>::insert(elemType newElement)
{
 .
 .
 .
}
```

In the heading of the member function's definition, the name of the class is specified with the parameter `elemType`.

The statement in Line 1 declares `intList` to be a list of 100 components. When the compiler generates the code for `intList`, it replaces the word `elemType` with `int` in the definition of the `class listType`. The template parameter in the definitions of the member functions (for example, `elemType` in the definition of `insert`) of the `class listType` is also replaced by `int`.

## HEADER FILE AND IMPLEMENTATION FILE OF A CLASS TEMPLATE

Until now, we have placed the definition of the class (in the header file) and the definitions of the member functions (in the implementation file) in separate files. The object code was generated from the implementation file and linked with the user code. However, this mechanism of separating the class definition and the definitions of the member functions does not work with class templates. Passing parameters to a function has an effect at run time, whereas passing a parameter to a class template has an effect at compile time. Because the actual parameter to a class is specified in the user code and because the compiler cannot instantiate a function template without the actual parameter to the template, we can no longer compile the implementation file independently of the user code.

This problem has several possible solutions. We could put the class definition and the definitions of the function templates directly in the client code, or we could put the class definition and the definitions of the function templates together in the same header file. Another alternative is to put the class definition and the definitions of the functions in separate files (as usual) but include a directive to the implementation file at the end of the header file. In either case, the function definitions and the client code are compiled together. For illustrative purposes, we will put the class definition and the function definitions in the same header file.

The following example demonstrates the use of class templates.

**EXAMPLE 15-9**

In this example, we will write a program that uses the `class listType`. Some of the operations included are as follows: check whether the list is empty, check whether the list is full, sort the list, and print the list. Because we can dynamically allocate arrays, the user will have the option to specify the size of the array. The default array size is 50. We will manipulate a list of integers and a list of strings. Because the `class newString` that we defined earlier allows us to use relational operators for comparison and the assignment operator for assignment, we will use the `class newString` to declare strings.

The definition of the `class listType` is:

```
#ifndef H_listType
#define H_listType

#include <iostream>
#include <cassert>

using namespace std;

template <class elemType>
class listType
{
public:
 bool isEmpty() const;
 //Function to determine whether the list is empty.
 //Postcondition: Returns true if the list is empty,
 // otherwise it returns false.

 bool isFull() const;
 //Function to determine whether the list is full.
 //Postcondition: Returns true if the list is full,
 // otherwise it returns false.

 int getLength() const;
 //Function to return the number of elements in the list.
 //Postcondition: The value of length is returned.

 int getMaxSize() const;
 //Function to return the maximum number of elements
 //that can be stored in the list.
 //Postcondition: The value of maxSize is returned.

 void sort();
 //Function to sort the list.
 //Postcondition: The list elements are in ascending order.

 void print() const;
 //Outputs the elements of the list.

 void insertAt(const elemType& item, int position);
 //Function to insert item in the list at the location
```

```

 //specified by position.
 //Postcondition: list[position] = item; length++;
 // If position is out of range, the program
 // is aborted.

listType(int listSize = 50);
 //Constructor
 //Creates an array of the size specified by the
 //parameter listSize; the default array size is 50.
 //Postcondition: list contains the base address of the
 // array; length = 0; maxSize = listSize;
~listType();
 //Destructor
 //Deletes all the elements of the list.
 //Postcondition: The array list is deleted.

private:
 int maxSize; //variable to store the maximum size
 //of the list
 int length; //variable to store the number of elements
 //in the list
 elemType *list; //pointer to the array that holds the
 //list elements
};

template <class elemType>
bool listType<elemType>::isEmpty() const
{
 return (length == 0)
}

template <class elemType>
bool listType<elemType>::isFull() const
{
 return (length == maxSize);
}

template <class elemType>
int listType<elemType>::getLength() const
{
 return length;
}

template <class elemType>
int listType<elemType>::getMaxSize() const
{
 return maxSize;
}

 //Constructor; the default array size is 50
template <class elemType>

```

```

listType<elemType>::listType(int listSize)
{
 maxSize = listSize;
 length = 0;
 list = new elemType[maxSize];
}

template <class elemType>
listType<elemType>::~~listType() //destructor
{
 delete [] list;
}

template <class elemType>
void listType<elemType>::sort() //selection sort
{
 int i, j;
 int min;
 elemType temp;

 for (i = 0; i < length; i++)
 {
 min = i;
 for (j = i + 1; j < length; ++j)
 if (list[j] < list[min])
 min = j;

 temp = list[i];
 list[i] = list[min];
 list[min] = temp;
 } //end for
} //end sort

template <class elemType>
void listType<elemType>::print() const
{
 int i;
 for (i = 0; i < length; ++i)
 cout << list[i] << " ";
 cout << endl;
} //end print

template <class elemType>
void listType<elemType>::insertAt(const elemType& item,
 int position)
{
 assert(position >= 0 && position < maxSize);
 list[position] = item;
 length++;
}

#endif

```

Consider the following program:

```
//This program shows how to use the class template listType.

#include <iostream>

#include "myString.h"
#include "listType.h"

using namespace std;

int main()
{
 listType<int> intList(100); //Line 1
 listType<newString> stringList; //Line 2
 int index; //Line 3
 int number; //Line 4

 cout << "List 5: Processing the integer list"
 << endl; //Line 5
 cout << "List 6: Enter 5 integers: "; //Line 6

 for (index = 0; index < 5; index++) //Line 7
 {
 cin >> number; //Line 8
 intList.insertAt(number, index); //Line 9
 }

 cout << endl; //Line 10
 cout << "List 11: intList: "; //Line 11
 intList.print(); //Line 12
 cout << endl; //Line 13

 //Sort intList
 intList.sort(); //Line 14

 cout << "Line 15: After sorting, intList: "; //Line 15
 intList.print(); //Line 16
 cout << endl; //Line 17

 newString str; //Line 18

 cout << "Line 19: Processing the string list"
 << endl; //Line 19

 cout << "Line 20: Enter 5 strings: "; //Line 20

 for (index = 0; index < 5; index++) //Line 21
 {
 cin >> str; //Line 22
 stringList.insertAt(str, index); //Line 23
 }
```

```

 cout << endl; //Line 24
 cout << "Line 25: stringList: "; //Line 25
 stringList.print(); //Line 26
 cout << endl; //Line 27

 //Sort stringList
 stringList.sort(); //Line 28

 cout << "Line 29: After sorting, stringList: "; //Line 29
 stringList.print(); //Line 30
 cout << endl; //Line 31

 int intListSize; //Line 32

 cout << "Line 33: Enter the size of the integer "
 << "list: "; //Line 33
 cin >> intListSize; //Line 34
 cout << endl; //Line 35

 listType<int> intList2(intListSize); //Line 36

 cout << "Line 37: Processing the integer list"
 << endl; //Line 37
 cout << "Line 38: Enter " << intListSize
 << " integers: "; //Line 38

 for (index = 0; index < intListSize; index++) //Line 39
 {
 cin >> number; //Line 40
 intList2.insertAt(number, index); //Line 41
 }

 cout << endl; //Line 42

 cout << "Line 43: intList2: "; //Line 43
 intList2.print(); //Line 44
 cout << endl; //Line 45

 //Sort intList2
 intList2.sort(); //Line 46

 cout << "Line 47: After sorting, intList2: "; //Line 47
 intList2.print(); //Line 48
 cout << endl; //Line 49

 cout << "Line 50: Length of intList2: "
 << intList2.getLength() << endl; //Line 50
 cout << "Line 51: Maximum size of intList2: "
 << intList2.getMaxSize() << endl; //Line 51

 return 0;
}

```

**Sample Run:** In this sample run, the user input is shaded.

List 5: Processing the integer list

List 6: Enter 5 integers: 19 15 66 24 34

List 11: intList: 19 15 66 24 34

Line 15: After sorting, intList: 15 19 24 34 66

Line 19: Processing the string list

Line 20: Enter 5 strings: summer cold hot warm sunny

Line 25: stringList: summer cold hot warm sunny

Line 29: After sorting, stringList: cold hot summer sunny warm

Line 33: Enter the size of the integer list: 10

Line 37: Processing the integer list

Line 38: Enter 10 integers: 23 65 34 8 11 5 3 16 45 2

Line 43: intList2: 23 65 34 8 11 5 3 16 45 2

Line 47: After sorting, intList2: 2 3 5 8 11 16 23 34 45 65

Line 50: Length of intList2: 10

Line 51: Maximum size of intList2: 10

---

## QUICK REVIEW

1. An operator that has different meanings with different data types is said to be overloaded.
2. In C++, >> is used as a stream extraction operator and as a right shift operator. Similarly, << is used as a stream insertion operator and as a left shift operator. Both are examples of operator overloading.
3. Any function that overloads an operator is called an operator function.
4. The syntax of the heading of the operator function is:  
`returnType operator operatorSymbol(parameters)`
5. In C++, `operator` is a reserved word.
6. Operator functions are value-returning functions.
7. Except for the assignment operator and the member selection operator, to use an operator on class objects, that operator must be overloaded. The assignment operator performs a default member-wise copy.
8. For classes with pointer member variables, the assignment operator must be explicitly overloaded.

9. Operator overloading provides the same concise notation for user-defined data types as is available for built-in data types.
10. When an operator is overloaded, its precedence cannot be changed, its associativity cannot be changed, default parameters cannot be used with an overloaded operator, the number of parameters that the operator takes cannot be changed, and the meaning of how an operator works with built-in data types remains the same.
11. It is not possible to create new operators. Only existing operators can be overloaded.
12. Most C++ operators can be overloaded.
13. The operators that cannot be overloaded are `.`, `.*`, `::`, `?:`, and `sizeof`.
14. The pointer `this` refers to the object as a whole.
15. The operator functions that overload the operators `()`, `[]`, `->`, or `=` for a class must be members of that class.
16. A friend function is a nonmember of a class.
17. The heading of the prototype of a friend function is preceded by the word `friend`.
18. In C++, `friend` is a reserved word.
19. If an operator function is a member of a class, the far left operand of the operator must be a class object (or a reference to a class object) of that operator's class.
20. The binary operator function as a member of a class has only one parameter; as a nonmember of a class, it has two parameters.
21. The operator functions that overload the stream insertion operator, `<<`, and the stream extraction operator, `>>`, for a class must be friend functions of that class.
22. To overload the pre-increment (`++`) operator for a class if the operator function is a member of that class, it must have no parameters. Similarly, to overload the pre-decrement (`--`) operator for a class if the operator function is a member of that class, it must have no parameters.
23. To overload the post-increment (`++`) operator for a class if the operator function is a member of that class, it must have one parameter, of type `int`. The user does not specify any value for the parameter. The dummy parameter in the function heading helps the compiler generate the correct code. The post-decrement operator has similar conventions.
24. A conversion constructor is a single-parameter function.
25. A conversion constructor converts its argument to an object of the constructor's class. The compiler implicitly calls such constructors.

- 26. Classes with pointer member variables must overload the assignment operator and include both the copy constructor and the destructor.
- 27. In C++, a function name can be overloaded.
- 28. In C++, **template** is a reserved word.
- 29. Using templates, you can write a single code segment for a set of related functions—called the function template.
- 30. Using templates, you can write a single code segment for a set of related classes—called the class template.
- 31. The syntax of a template is:

```
template <class Type>
declaration;
```

in which **Type** is a user-defined identifier, which is used to pass types (that is, data types) as parameters, and **declaration** is either a function or a class. The word **class** in the heading refers to any user-defined data type or built-in data type.

- 32. Class templates are called parameterized types.
- 33. In a class template, the parameter **Type** specifies how a generic class template is to be customized to form a specific template class.
- 34. The parameter **Type** is mentioned in every class header and member function definition.
- 35. Suppose **cType** is a class template, and **func** is a member function of **cType**. The heading of the function definition of **func** is:

```
template <class Type>
funcType cType<Type>::func(parameters)
```

in which **funcType** is the type of the function, such as **void**.

- 36. Suppose **cType** is a class template, which can take **int** as a parameter. The statement:

```
cType<int> x;
```

declares **x** to be an object of type **cType**, and the type passed to the **class** **cType** is **int**.

## EXERCISES

- 1. Mark the following statements as true or false.
  - a. In C++, all operators can be overloaded for user-defined data types.
  - b. In C++, operators cannot be redefined for built-in types.
  - c. The function that overloads an operator is called the operator function.
  - d. C++ allows users to create their own operators.

- e. The precedence of an operator cannot be changed, but its associativity can be changed.
  - f. Every instance of an overloaded function has the same number of parameters.
  - g. It is not necessary to overload relational operators for classes that have only `int` member variables.
  - h. The member function of a `class` template is a function template.
  - i. When writing the definition of a `friend` function, the keyword `friend` must appear in the function heading.
  - j. Templates provide the capability for software reuse.
  - k. The function heading of the operator function to overload the pre-increment operator (`++`) and the post-increment operator (`++`) is the same because both operators have the same symbols.
2. What is a `friend` function?
  3. What is the difference between a `friend` function of a class and a member function of a class?
  4. Consider the definition of the `class dateType` given in Chapter 13.
    - a. Write the statement that includes a `friend` function named `before` in the `class dateType` that takes as parameters two objects of type `dateType` and returns `true` if the date represented by the first object comes before the date represented by the second object; otherwise the function returns `false`.
    - b. Write the definition of the function you defined in part a.
  5. Suppose that the operator `<<` is to be overloaded for a user-defined `class mystery`. Why must `<<` be overloaded as a `friend` function?
  6. Suppose that the binary operator `+` is overloaded as a member function for a `class strange`. How many parameters does the function `operator+` have?
  7. When should a class overload the assignment operator and define the copy constructor?
  8. Consider the following declaration:
 

```
class strange
{
 .
 .
 .
};
```

    - a. Write a statement that shows the declaration in the `class strange` to overload the operator `>>`.
    - b. Write a statement that shows the declaration in the `class strange` to overload the operator `=`.
    - c. Write a statement that shows the declaration in the `class strange` to overload the binary operator `+` as a member function.

- d. Write a statement that shows the declaration in the `class strange` to overload the operator `==` as a member function.
- e. Write a statement that shows the declaration in the `class strange` to overload the post-increment operator `++` as a member function.
9. Assume the declaration of Exercise 8.
  - a. Write a statement that shows the declaration in the `class strange` to overload the binary operator `+` as a `friend` function.
  - b. Write a statement that shows the declaration in the `class strange` to overload the operator `==` as a `friend` function.
  - c. Write a statement that shows the declaration in the `class strange` to overload the post-increment operator `++` as a `friend` function.
10. Find the error(s) in the following code:

```
class mystery //Line 1
{
 .
 .
 .
 bool operator<=(mystery); //Line 2
 .
 .
 .
};

bool mystery::<=(mystery rightObj) //Line 3
{
 .
 .
 .
}
```

- 11.** Find the error(s) in the following code:

```
class mystery //Line 1
{
 .
 .
 .
 bool operator<=(mystery, mystery); //Line 2
 .
 .
 .
};
```

- 12.** Find the error(s) in the following code:

[illegible]

```

friend operator+(mystery); //Line 2
//overload binary +
.
.
.
};

```

13. In a class, why do you include the function that overloads the stream insertion operator, `<<`, as a friend function?
14. In a class, why do you include the function that overloads the stream extraction operator, `>>`, as a friend function?
15. What is returned by the function that overloads the operator `>>` for a class?
16. What is returned by the function that overloads the operator `<<` for a class?
17. What is the purpose of a dummy parameter in a function that overloads the post-increment or post-decrement operator for a class?
18. What type of value should be returned by a function that overloads a relational operator?
19. How many parameters are required to overload the pre-increment operator for a class as a member function?
20. How many parameters are required to overload the pre-increment operator for a class as a **friend** function?
21. How many parameters are required to overload the post-increment operator for a class as a member function?
22. How many parameters are required to overload the post-increment operator for a class as a **friend** function?
23. Let  $a + ib$  be a complex number. The conjugate of  $a + ib$  is  $a - ib$ , and the absolute value of  $a + ib$  is  $\sqrt{a^2 + b^2}$ . Extend the definition of the **class** `complexType` of the Programming Example: Complex Numbers by overloading the operators `~` and `!` as member functions so that `~` returns the conjugate of a complex number and `!` returns the absolute value. Also, write the definitions of these operator functions.
24. Redo Exercise 23 so that the operators `~` and `!` are overloaded as non-member functions.
25. Find the error(s) in the following code:

```

template <class type> //Line 1
class strange //Line 2
{
 .
 .
 .
};

strange<int> s1; //Line 3
strange<type> s2; //Line 4

```

26. Consider the following declaration:

```
template <class type>
class strange
{
 .
 .
 .
private:
 type a;
 type b;
};
```

- Write a statement that declares `sObj` to be an object of type `strange` such that the `private` member variables `a` and `b` are of type `int`.
  - Write a statement that shows the declaration in the `class strange` to overload the operator `==` as a member function.
  - Assume that two objects of type `strange` are equal if their corresponding member variables are equal. Write the definition of the function `operator==` for the `class strange`, which is overloaded as a member function.
27. Consider the definition of the following function template:

```
template <class Type>
Type surprise(Type x, Type y)
{
 return x + y;
}
```

What is the output of the following statements?

- `cout << surprise(5, 7) << endl;`
  - `string str1 = "Sunny";`  
`string str2 = " Day";`  
`cout << surprise(str1, str2) << endl;`
28. Consider the definition of the following function template:

```
template <class Type>
Type funcExp(Type list[], int size)
{
 int j;
 Type x = list[0];
 Type y = list[size - 1];

 for (j = 1; j < (size - 1)/2; j++)
 {
 if (x < list[j])
 x = list[j];
 if (y > list[size - 1 - j])
 y = list[size - 1 - j];
 }

 return x + y;
}
```

Further suppose that you have the following declarations:

```
int list[10] = {5, 3, 2, 10, 4, 19, 45, 13, 61, 11};
string strList[] = {"One", "Hello", "Four", "Three",
 "How", "Six"};
```

What is the output of the following statements?

- a. `cout << funExp(list, 10);`
  - b. `cout << funExp(strList, 6) << endl;`
29. Write the definition of the function template that swaps the contents of two variables.
30. a. Overload the operator `+` for the `class newString` to perform string concatenation. For example, if `s1` is "Hello " and `s2` is "there", the statement:
- ```
s3 = s1 + s2;
```
- should assign "Hello there" to `s3`, in which `s1`, `s2`, and `s3` are `newString` objects.
- b. Overload the operator `+=` for the `class newString` to perform the following string concatenation. Suppose that `s1` is "Hello " and `s2` is "there". Then, the statement:
- ```
s1 += s2;
```
- should assign "Hello there" to `s1`, in which `s1` and `s2` are `newString` objects.

## PROGRAMMING EXERCISES

---

1. a. Write the definitions of the functions to overload the increment, decrement, arithmetic, and relational operators as members of the `class rectangleType`.
- b. Write a test program that tests various operations on the `class rectangleType`.
2. a. Write the definitions of the functions to overload the increment, decrement, arithmetic, and relational operators as nonmembers of the `class rectangleType`.
- b. Write a test program that tests various operations on the `class rectangleType`.
3. a. Extend the definition of the `class clockType` by overloading the post-increment operator function as a member of the `class clockType`.
- b. Write the definition of the function to overload the post-increment operator for the `class clockType` as defined in part a.

4.
  - a. The increment and relational operators in the `class clockType` are overloaded as member functions. Rewrite the definition of the `class clockType` so that these operators are overloaded as nonmember functions. Also, overload the post-increment operator for the `class clockType` as a nonmember.
  - b. Write the definitions of the member functions of the `class clockType` as designed in part a.
  - c. Write a test program that tests various operations on the class as designed in parts a and b.
5.
  - a. Extend the definition of the `class complexType` so that it performs the subtraction and division operations. Overload the operators subtraction and division for this class as member functions.  
 If  $(a, b)$  and  $(c, d)$  are complex numbers:  
 $(a, b) - (c, d) = (a - c, b - d)$ .  
 If  $(c, d)$  is nonzero:  
 $(a, b) / (c, d) = ((ac + bd) / (c^2 + d^2), (-ad + bc) / (c^2 + d^2))$ .
  - b. Write the definitions of the functions to overload the operators `-` and `/` as defined in part a.
  - c. Write a test program that tests various operations on the `class complexType`. Format your answer with two decimal places.
6.
  - a. Rewrite the definition of the `class complexType` so that the arithmetic and relational operators are overloaded as nonmember functions.
  - b. Write the definitions of the member functions of the `class complexType` as designed in part a.
  - c. Write a test program that tests various operations on the `class complexType` as designed in parts a and b. Format your answer with two decimal places.
7.
  - a. Extend the definition of the `class newString` as follows:
    - i. Overload the operators `+` and `+=` to perform the string concatenation operations.
    - ii. Add the function `length` to return the length of the string.
  - b. Write the definition of the function to implement the operations defined in part a.
  - c. Write a test program to test various operations on the `newString` objects.
8.
  - a. Rewrite the definition of the `class newString` as defined and extended in Programming Exercise 7 so that the relational operators are overloaded as nonmember functions.
  - b. Write the definition of the `class newString` as designed in part a.
  - c. Write a test program that tests various operations on the `class newString`.

9. Rational fractions are of the form  $a / b$ , in which  $a$  and  $b$  are integers and  $b \neq 0$ . In this exercise, by “fractions” we mean rational fractions. Suppose  $a / b$  and  $c / d$  are fractions. Arithmetic operations on fractions are defined by the following rules:

$$a/b + c/d = (ad + bc)/bd$$

$$a/b - c/d = (ad - bc)/bd$$

$$a/b \times c/d = ac/bd$$

$$(a/b)/(c/d) = ad/bc, \text{ in which } c/d \neq 0.$$

Fractions are compared as follows:  $a / b \text{ op } c / d$  if  $ad \text{ op } bc$ , in which  $\text{op}$  is any of the relational operations. For example,  $a / b < c / d$  if  $ad < bc$ .

Design a **class**—say, **fractionType**—that performs the arithmetic and relational operations on fractions. Overload the arithmetic and relational operators so that the appropriate symbols can be used to perform the operation. Also, overload the stream insertion and stream extraction operators for easy input and output.

Write a C++ program that, using the **class** **fractionType**, performs operations on fractions.

Among other things, test the following: Suppose **x**, **y**, and **z** are objects of type **fractionType**. If the input is 2/3, the statement:

```
cin >> x;
```

should store 2/3 in **x**. The statement:

```
cout << x + y << endl;
```

should output the value of **x + y** in fraction form. The statement:

```
z = x + y;
```

should store the sum of **x** and **y** in **z** in fraction form. Your answer need not be in the lowest terms.

10. Recall that in C++, there is no check on an array index out of bounds. However, during program execution, an array index out of bounds can cause serious problems. Also, in C++, the array index starts at 0.

Design and implement the **class** **myArray** that solves the array index out of bounds problem and also allows the user to begin the array index starting at any integer, positive or negative. Every object of type **myArray** is an array of type **int**. During execution, when accessing an array component,

if the index is out of bounds, the program must terminate with an appropriate error message. Consider the following statements:

```
myArray<int> list(5); //Line 1
myArray<int> myList(2, 13); //Line 2
myArray<int> yourList(-5, 9); //Line 3
```

The statement in Line 1 declares `list` to be an array of 5 components, the component type is `int`, and the components are: `list[0]`, `list[1]`, ..., `list[4]`; the statement in Line 2 declares `myList` to be an array of 11 components, the component type is `int`, and the components are: `myList[2]`, `myList[3]`, ..., `myList[12]`; the statement in Line 3 declares `yourList` to be an array of 14 components, the component type is `int`, and the components are: `yourList[-5]`, `yourList[-4]`, ..., `yourList[0]`, ..., `yourList[8]`. Write a program to test the `class myArray`.

11. Programming Exercise 10 processes only `int` arrays. Redesign the `class myArray` using class templates so that the `class` can be used in any application that requires arrays to process data.
12. Design a class to perform various matrix operations. A matrix is a set of numbers arranged in rows and columns. Therefore, every element of a matrix has a row position and a column position. If  $A$  is a matrix of **five** rows and **six** columns, we say that the matrix  $A$  is of the size  $5 \times 6$  and sometimes denote it as  $A_{5 \times 6}$ . Clearly, a convenient place to store a matrix is in a two-dimensional array. Two matrices can be added and subtracted if they have the same size. Suppose  $A = [a_{ij}]$  and  $B = [b_{ij}]$  are two matrices of the size  $m \times n$ , in which  $a_{ij}$  denotes the element of  $A$  in the  $i$ th row and the  $j$ th column, and so on. The sum and difference of  $A$  and  $B$  are given by:

$$A + B = [a_{ij} + b_{ij}]$$

$$A - B = [a_{ij} - b_{ij}]$$

The multiplication of  $A$  and  $B$  ( $A * B$ ) is defined only if the number of columns of  $A$  is the same as the number of rows of  $B$ . If  $A$  is of the size  $m \times n$  and  $B$  is of the size  $n \times t$ , then  $A * B = [c_{ik}]$  is of the size  $m \times t$  and the element  $c_{ik}$  is given by the formula:

$$c_{ik} = a_{i1}b_{1k} + a_{i2}b_{2k} + \cdots + a_{in}b_{nk}$$

Design and implement a `class matrixType` that can store a matrix of any size. Overload the operators `+`, `-`, and `*` to perform the addition, subtraction, and multiplication operations, respectively, and overload the operator `<<` to output a matrix. Also, write a test program to test various operations on the matrices.

13. a. In Programming Exercise 1 in Chapter 12, we defined a `class romanType` to implement Roman numbers in a program. In that exercise, we also implemented a function, `romanToDecimal`, to con-

vert a Roman number into its equivalent decimal number.

Modify the definition of the `class romanType` so that the member variables are declared as `protected`. Use the `class newString`, as designed in Programming Exercise 7, to manipulate strings. Furthermore, overload the stream insertion and stream extraction operators for easy input and output. The stream insertion operator outputs the Roman number in the Roman format.

Also, include a member function, `decimalToRoman`, that converts the decimal number (the decimal number must be a positive integer) to an equivalent Roman number format. Write the definition of the member function `decimalToRoman`.

For simplicity, we assume that only the letter I can appear in front of another letter and that it appears only in front of the letters V and X. For example, 4 is represented as IV, 9 is represented as IX, 39 is represented as XXXIX, and 49 is represented as XXXXIX. Also, 40 will be represented as XXXX, 190 will be represented as CLXXXX, and so on.

- b. Derive a `class extRomanType` from the `class romanType` to do the following: In the `class extRomanType`, overload the arithmetic operators `+`, `-`, `*`, and `/` so that arithmetic operations can be performed on Roman numbers. Also, overload the pre- and post-increment and decrement operators as member functions of the `class extRomanType`.

To add (subtract, multiply, or divide) Roman numbers, add (subtract, multiply, or divide, respectively) their decimal representations and then convert the result to the Roman number format. For subtraction, if the first number is smaller than the second number, output a message saying that, “Because the first number is smaller than the second, the numbers cannot be subtracted”. Similarly, for division, the numerator must be larger than the denominator. Use similar conventions for the increment and decrement operators.

- c. Write the definitions of the functions to overload the operators described in part b.
- d. Test your `class extRomanType` on the following program. (Include the appropriate header files.)

```
int main()
{
 extRomanType num1("XXXIV");
 extRomanType num2("XV");
 extRomanType num3;

 cout << "Num1 = " << num1 << endl;
 cout << "Num2 = " << num2 << endl;
 cout << "Num1 + Num2 = " << num1 + num2 << endl;
```

```

 cout << "Num1 * Num2 = " << num1 * num2 << endl;

 cout << "Enter two numbers in Roman format: ";
 cin >> num1 >> num2;
 cout << endl;

 cout << "Num1 = " << num1 << endl;
 cout << "Num2 = " << num2 << endl;

 num3 = num2 * num1;
 cout << "Num3 = " << num3 << endl;

 cout << "--num3: " << --num3 << endl;
 cout << "++num3: " << ++num3 << endl;

 return 0;
}

```

14. In Example 15-9, the class template `listType` is designed to implement a list in a program. For illustration purposes, that example included only the sorting operation. Extend the definition of the class template to include the remove and search operations. Write the definitions of the member functions to implement the class template `listType`. Also, write a test program to test various operations on a list.
15. Consider the `class dateType` given in Chapter 13. In this class, add the functions to overload the increment and decrement operators to increase the date by a day and decrease the data by a day, respectively; relational operators to compare two dates; and stream operators for easy input and output. (Assume that the date is input and output in the form `MM-DD-YYYY`.) Also write a program to test your class.
16. Programming Exercise 12, Chapter 12, describes how to design the `class lineType` to implement a line. Redo this programming exercise so that the `class lineType`:
  - a. Overloads the stream insertion operator, `<<`, for easy output.
  - b. Overloads the stream extraction operator, `>>`, for easy input. (The line  $ax + by = c$  is input as  $(a, b, c)$ .)
  - c. Overloads the assignment operator to copy a line into another line.
  - d. Overloads the unary operator `+`, as a member function, so that it returns `true` if a line is vertical; `false` otherwise.
  - e. Overloads the unary operator `-`, as a member function, so that it returns `true` if a line is horizontal; `false` otherwise.
  - f. Overloads the operator `==`, as a member function, so that it returns `true` if two lines are equal; `false` otherwise.
  - g. Overloads the operator `||`, as a member function, so that it returns `true` if two lines are parallel; `false` otherwise.

- h. Overloads the operator `&&`, as a member function, so that it returns `true` if two lines are perpendicular; `false` otherwise.

Write a program to test your class.

17. Consider the classes `cashRegister` and `dispenserType` given in the programming example in Chapter 12.

- a. In the class `cashRegister`, add the functions to overload the binary operators `+` and `-` to add and subtract an amount in a cash register; the relational operators to compare the amount in two cash registers; and the stream insertion operator for easy output.
- b. The `dispenserType`, in the programming example in Chapter 12, is designed to implement a dispenser to hold and release products. In this class, add the functions to overload the increment and decrement operators to increment and decrement the number of items by one, respectively, and the stream insertion operator for easy output.

Write a program to test the classes designed in parts a and b.

18. (**Stock Market**) Write a program to help a local stock trading company automate its systems. The company invests only in the stock market. At the end of each trading day, the company would like to generate and post the listing of its stocks so that investors can see how their holdings performed that day. We assume that the company invests in, say, 10 different stocks. The desired output is to produce two listings, one sorted by stock symbol and another sorted by percent gain from highest to lowest.

The input data is provided in a file in the following format:

```
symbol openingPrice closingPrice todayHigh todayLow
prevClose volume
```

For example, the sample data is:

```
MSMT 112.50 115.75 116.50 111.75 113.50 6723823
CBA 67.50 75.50 78.75 67.50 65.75 378233
.
.
.
```

The first line indicates that the stock symbol is `MSMT`, today's opening price was `112.50`, the closing price was `115.75`, today's high price was `116.50`, today's low price was `111.75`, yesterday's closing price was `113.50`, and the number of shares currently being held is `6723823`.

The listing sorted by stock symbols must be of the following form:



- b. Now that you have designed and implemented the `class stockType` to implement a stock object in a program, it is time to create a list of stock objects.

Let us call the class to implement a list of stock objects `stockListType`.

The `class stockListType` must be derived from the `class listType`, which you designed and implemented in the previous exercise. However, the `class stockListType` is a very specific class, designed to create a list of stock objects. Therefore, the `class stockListType` is no longer a template.

Add and/or overwrite the operations of the `class listType` to implement the necessary operations on a stock list.

The following statement derives the `class stockListType` from the `class listType`.

```
class stockListType: public listType<stockType>
{
 member list
};
```

The member variables to hold the list elements, the length of the list, and the `max listSize` were declared as `protected` in the `class listType`. Therefore, these members can be directly accessed in the `class stockListType`.

Because the company also requires you to produce the list ordered by the percent gain/loss, you need to sort the stock list by this component. However, you are not to physically sort the list by the component percent gain/loss. Instead, you will provide a logical ordering with respect to this component.

To do so, add a member variable, an array, to hold the indices of the stock list ordered by the component percent gain/loss. Call this array `sortIndicesGainLoss`. When printing the list ordered by the component percent gain/loss, use the array `sortIndicesGainLoss` to print the list. The elements of the array `sortIndicesGainLoss` will tell which component of the stock list to print next.

- c. Write a program that uses these two classes to automate the company's analysis of stock data.



# 16

## CHAPTER

# EXCEPTION HANDLING

IN THIS CHAPTER, YOU WILL:

- Learn what an exception is
- Learn how to handle exceptions within a program
- See how a `try/catch` block is used to handle exceptions
- Become familiar with C++ exception classes
- Learn how to create your own exception classes
- Discover how to throw and rethrow an exception
- Explore stack unwinding

An exception is an occurrence of an undesirable situation that can be detected during program execution. For example, division by zero is an exception. Similarly, trying to open an input file that does not exist is an exception, as is an array index that goes out of bounds.

Until now, we have dealt with certain exceptions by using either an `if` statement or the `assert` function. For instance, in Examples 5-3 and 5-4, before dividing `sum` by `counter` or `count`, we checked whether `counter` or `count` was nonzero. Similarly, in the Programming Example `newString` (Chapter 15), we used the `assert` function to determine whether the array index is within bounds.

On the other hand, there were places where we simply ignored the exception. For instance, while determining a substring in a string (Chapter 8), we never checked whether the starting position of the substring was within range. Also, we did not handle the array index out-of-bounds exception. However, in all of these cases, if exceptions occurred during program execution, either we included code to terminate the program or the program terminated with an appropriate error message. For instance, if we opened an input file in the function `main` and the input file did not exist, we terminated the function `main`, so the program was terminated.

There are situations when an exception occurs, but you don't want the program to simply ignore the exception and terminate. For example, a program that monitors stock performance should not automatically sell if the account balance goes below a certain level. It should inform the stockholder and request an appropriate action. Similarly, a program that monitors a patient's heartbeat cannot be terminated if the blood pressure goes very high. A program that monitors a satellite in space cannot be terminated if there is a temporary power failure in some section of the satellite.

The code to handle exceptions depends on the type of application you develop. One common way to provide exception-handling code is to add exception-handling code at the point where an error can occur. This technique allows the programmer reading the code to see the exception-handling code together with the actual code and to determine whether the error-checking code is properly implemented. The disadvantage of this approach is that the program can become cluttered with exception-handling code, which can make understanding and maintaining the program difficult. This can distract the programmer from ensuring that the program functions correctly.

## Handling Exceptions within a Program

In Chapter 3, we noted that if you try to input invalid data into a variable, the input stream enters the fail state, so an exception occurs. This occurs, for example, if you try to input a letter into an `int` variable. Chapter 3 also showed how to clear and restore the input stream. Chapter 4 introduced the `assert` function and explained how to use it to avoid certain unforeseeable errors, such as division by zero. Even though the function `assert` can check whether an expression meets the required condition(s), if the conditions are not met, it terminates the program. As indicated in the previous section, situations occur in which, if something goes wrong, the program should not be simply terminated.

This section discusses how to handle exceptions. However, first we offer some examples that show what can happen if an exception is not handled. We also review some of the ways to handle exceptions.

The program in Example 16-1 shows what happens when division by zero occurs and the problem is not addressed.

### EXAMPLE 16-1

```
// Division by zero.

#include <iostream>

using namespace std;

int main()
{
 int dividend, divisor, quotient; //Line 1

 cout << "Line 2: Enter the dividend: "; //Line 2
 cin >> dividend; //Line 3
 cout << endl; //Line 4

 cout << "Line 5: Enter the divisor: "; //Line 5
 cin >> divisor; //Line 6
 cout << endl; //Line 7

 quotient = dividend / divisor; //Line 8
 cout << "Line 9: Quotient = " << quotient //Line 9
 << endl;

 return 0; //Line 10
}
```

#### Sample Run 1:

Line 2: Enter the dividend: 12

Line 5: Enter the divisor: 5

Line 9: Quotient = 2

#### Sample Run 2:

Line 2: Enter the dividend: 24

Line 5: Enter the divisor: 0

CPP\_Proj1.exe has encountered a problem and needs to close. We are sorry for the inconvenience.

In Sample Run 1, the value of `divisor` is nonzero, so no exception occurs. The program calculates and outputs the quotient and terminates normally.

In Sample Run 2, the value entered for `divisor` is 0. The statement in Line 8 divides `dividend` by the divisor. However, the program does not check whether `divisor` is 0 before dividing `dividend` by `divisor`. So the program crashes with the message shown. Notice that the error message is platform independent, that is, IDE dependent. Some IDEs might not give this error message and might simply hang.

Next, consider Example 16-2. This is the same program as in Example 16-1, except that in Line 8, the program checks whether `divisor` is zero.

### EXAMPLE 16-2

*// Checking division by zero.*

```
#include <iostream>

using namespace std;

int main()
{
 int dividend, divisor, quotient; //Line 1

 cout << "Line 2: Enter the dividend: "; //Line 2
 cin >> dividend; //Line 3
 cout << endl; //Line 4

 cout << "Line 5: Enter the divisor: "; //Line 5
 cin >> divisor; //Line 6
 cout << endl; //Line 7

 if (divisor != 0) //Line 8
 {
 quotient = dividend / divisor; //Line 9
 cout << "Line 10: Quotient = " << quotient //Line 10
 << endl;
 }
 else //Line 11
 cout << "Line 12: Cannot divide by zero." //Line 12
 << endl;
 return 0; //Line 13
}
```

#### Sample Run 1:

Line 2: Enter the dividend: 12

Line 5: Enter the divisor: 5

Line 10: Quotient = 2

**Sample Run 2:**

Line 2: Enter the dividend: 24

Line 5: Enter the divisor: 0

Line 12: Cannot divide by zero.

In Sample Run 1, the value of `divisor` is nonzero, so no exception occurs. The program calculates and outputs the quotient and terminates normally.

In Sample Run 2, the value entered for `divisor` is 0. In Line 8, the program checks whether `divisor` is 0. Because `divisor` is 0, the expression in the `if` statement fails, so the `else` part executes, which outputs the third line of the sample run.

The program in Example 16-3 uses the function `assert` to determine whether the divisor is zero. If the divisor is zero, the function `assert` terminates the program with an error message.

**EXAMPLE 16-3**

*// Division by zero and the assert function.*

```
#include <iostream>
#include <cassert>

using namespace std;

int main()
{
 int dividend, divisor, quotient; //Line 1

 cout << "Line 2: Enter the dividend: "; //Line 2
 cin >> dividend; //Line 3
 cout << endl; //Line 4

 cout << "Line 5: Enter the divisor: "; //Line 5
 cin >> divisor; //Line 6
 cout << endl; //Line 7

 assert(divisor != 0); //Line 8
 quotient = dividend / divisor; //Line 9

 cout << "Line 10: Quotient = " << quotient //Line 10
 << endl;

 return 0; //Line 11
}
```

**Sample Run 1:**

Line 2: Enter the dividend: 26

Line 5: Enter the divisor: 7

Line 10: Quotient = 3

**Sample Run 2:**

Line 2: Enter the dividend: 24

Line 5: Enter the divisor: 0

Assertion failed: divisor != 0, file c:\chapter 16 source code\ch16\_exp3.cpp, line 20

In Sample Run 1, the value of `divisor` is nonzero, so no exception occurs. The program calculates and outputs the quotient and terminates normally.

In Sample Run 2, the value entered for `divisor` is 0. In Line 8, the function `assert` checks whether `divisor` is nonzero. Because `divisor` is 0, the expression in the `assert` statement evaluates to `false`, and the function `assert` terminates the program with the error message shown in the third line of the output.

## C++ Mechanisms of Exception Handling

Examples 16-1 through 16-3 show what happens when an exception occurs in a program and is not processed. This section describes how to include the necessary code to handle exceptions within a program.

### try/catch Block

The statements that may generate an exception are placed in a `try` block. The `try` block also contains statements that should not be executed if an exception occurs. The `try` block is followed by one or more `catch` blocks. A `catch` block specifies the type of exception it can catch and contains an exception handler.

The general syntax of the `try/catch` block is:

```
try
{
 //statements
}
catch (dataType1 identifier)
{
 //exception-handling code
}
.
.
.
catch (dataTypeN identifier)
{
 //exception-handling code
}
.
.
.
catch (...)
{
 //exception-handling code
}
```

Suppose there is a statement that can generate an exception, for example, division by 0. Usually, before executing such a statement, we check whether certain conditions are met. For example, before performing the division, we check whether the divisor is nonzero. If the conditions are not met, we typically generate an exception, which in C++ terminology is called throwing an exception. This is typically done using the `throw` statement, which we will explain shortly. We will show what is typically thrown to generate an exception.

Let us now note the following about `try/catch` blocks.

- If no exception is thrown in a `try` block, all `catch` blocks associated with that `try` block are ignored and program execution resumes after the last `catch` block.
- If an exception is thrown in a `try` block, the remaining statements in that `try` block are ignored. The program searches the `catch` blocks in the order they appear after the `try` block and looks for an appropriate exception handler. If the type of thrown exception matches the parameter type in one of the `catch` blocks, the code of that `catch` block executes, and the remaining `catch` blocks after this `catch` block are ignored.
- The last `catch` block that has an ellipsis (three dots) is designed to catch any type of exception.

Consider the following `catch` block:

```
catch (int x)
{
 //exception-handling code
}
```

In this `catch` block:

- The identifier `x` acts as a parameter. In fact, it is called a `catch` block parameter.
- The data type `int` specifies that this `catch` block can catch an exception of type `int`.
- A `catch` block can have *at most* one `catch` block parameter.

Essentially, the `catch` block parameter becomes a placeholder for the value thrown. In this case, `x` becomes a placeholder for any thrown value that is of type `int`. In other words, if the thrown value is caught by this `catch` block, then the thrown value is stored in the `catch` block parameter. This way, if the exception-handling code wants to do something with that value, it can be accessed via the `catch` block parameter.

Suppose in a `catch` block heading only the data type is specified, that is, there is no `catch` block parameter. The thrown value then *may not* be accessible in the `catch` block exception-handling code.

## THROWING AN EXCEPTION

In order for an exception to occur in a `try` block and be caught by a `catch` block, the exception must be thrown in the `try` block. The general syntax to `throw` an exception is:

```
throw expression;
```

in which **expression** is a constant value, variable, or object. The object being thrown can be either a specific object or an anonymous object. It follows that in C++, an *exception is a value*.

In C++, **throw** is a reserved word.

Example 16-4 illustrates how to use a **throw** statement.

#### EXAMPLE 16-4

Suppose we have the following declaration:

```
int num = 5;
string str = "Something is wrong!!!";
```

##### **throw expression**

```
throw 4;
throw x;
throw str;
throw string("Exception found!");
```

##### **Effect**

The constant value 4 is thrown.  
 The value of the variable **x** is thrown.  
 The object **str** is thrown.  
 An anonymous **string** object with the string "Exception found!" is thrown.

#### ORDER OF **catch** BLOCKS

A **catch** block can catch either all exceptions of a specific type or all types of exceptions. The heading of a **catch** block specifies the type of exception it handles. As noted previously, the **catch** block that has an ellipses (three dots) is designed to catch any type of exception. Therefore, if we put this **catch** block first, then this **catch** block can catch all types of exceptions.

Suppose that an exception occurs in a **try** block and is caught by a **catch** block. The remaining **catch** blocks associated with that **try** block are then ignored. Therefore, you should be careful about the order in which you list **catch** blocks following a **try** block. For example, consider the following sequence of **try/catch** blocks:

```
try //Line 1
{
 //statements
}
catch (...) //Line 2
{
 //statements
}
catch (int x) //Line 3
{
 //statements
}
```

Suppose that an exception is thrown in the `try` block. Because the `catch` block in Line 2 can catch exceptions of all types, the `catch` block in Line 3 cannot be reached. For this sequence of `try/catch` blocks, some compilers might, in fact, give a syntax error (check your compiler's documentation).

In a sequence of `try/catch` blocks, if the `catch` block with an ellipsis (in the heading) is needed, then it should be the last `catch` block of that sequence.

### USING `try/catch` BLOCKS IN A PROGRAM

Next, we provide examples that illustrate how a `try/catch` block might appear in a program.

A common error that might occur when performing numeric calculations is division by zero with integer values. If, during program execution, division by zero occurs with integer values and is not addressed by the program, the program might terminate with an error message or might simply hang. Example 16-5 shows how to handle division by zero exceptions.

#### EXAMPLE 16-5

This example illustrates how to catch and handle division by zero exceptions. It also shows how a `try/catch` block might appear in a program.

```
// Handling division by zero exception.

#include <iostream>

using namespace std;

int main()
{
 int dividend, divisor, quotient; //Line 1

 try //Line 2
 {
 cout << "Line 3: Enter the dividend: "; //Line 3
 cin >> dividend; //Line 4
 cout << endl; //Line 5

 cout << "Line 6: Enter the divisor: "; //Line 6
 cin >> divisor; //Line 7
 cout << endl; //Line 8

 if (divisor == 0) //Line 9
 throw 0; //Line 10

 quotient = dividend / divisor; //Line 11

 cout << "Line 12: Quotient = " << quotient //Line 12
 << endl;

 }
 catch (int) //Line 13
}
```

```

 {
 cout << "Line 14: Division by 0." << endl; //Line 14
 }

 return 0; //Line 15
}

```

**Sample Run 1:** In this sample run, the user input is shaded.

Line 3: Enter the dividend: 17

Line 6: Enter the divisor: 8

Line 12: Quotient = 2

**Sample Run 2:** In this sample run, the user input is shaded.

Line 3: Enter the dividend: 34

Line 6: Enter the divisor: 0

Line 14: Division by 0.

This program works as follows. The statement in Line 1 declares the `int` variables `dividend`, `divisor`, and `quotient`. The `try` block starts at Line 2. The statement in Line 3 prompts the user to enter the value for the dividend; the statement in Line 4 stores this number in the variable `dividend`. The statement in Line 6 prompts the user to enter the value for the divisor, and the statement in Line 7 stores this number in the variable `divisor`. The statement in Line 9 checks whether the value of `divisor` is 0. If the value of `divisor` is 0, the statement in Line 10 throws the constant value 0. The statement in Line 11 calculates the quotient and stores it in `quotient`. The statement in Line 12 outputs the value of `quotient`.

The `catch` block starts in Line 13 and catches an exception of type `int`.

In Sample Run 1, the program does not throw any exception.

In Sample Run 2, the entered value of `divisor` is 0. Therefore, the statement in Line 10 throws 0, which is caught by the `catch` block starting in Line 13. The statement in Line 14 outputs the appropriate message.

---

The program in Example 16-6 is the same as the program in Example 16-5, except that the `throw` statement throws the value of the variable `divisor`.

### EXAMPLE 16-6

*// Handling division by zero exception.*

```
#include <iostream>
```

```
using namespace std;
```

```

int main()
{
 int dividend, divisor, quotient; //Line 1

 try //Line 2
 {
 cout << "Line 3: Enter the dividend: "; //Line 3
 cin >> dividend; //Line 4
 cout << endl; //Line 5

 cout << "Line 6: Enter the divisor: "; //Line 6
 cin >> divisor; //Line 7
 cout << endl; //Line 8

 if (divisor == 0) //Line 9
 throw divisor; //Line 10

 quotient = dividend / divisor; //Line 11

 cout << "Line 12: Quotient = " << quotient //Line 12
 << endl;

 }
 catch (int x) //Line 13
 {
 cout << "Line 14: Division by " << x //Line 14
 << endl;

 }

 return 0; //Line 15
}

```

**Sample Run 1:** In this sample run, the user input is shaded.

Line 3: Enter the dividend: 14

Line 6: Enter the divisor: 5

Line 12: Quotient = 2

**Sample Run 2:** In this sample run, the user input is shaded.

Line 3: Enter the dividend: 23

Line 6: Enter the divisor: 0

Line 14: Division by 0

This program works the same way as the program in Example 16-5.

---

The program in Example 16-7 illustrates how to handle division by zero, division by a negative integer, and input failure exceptions. It also shows how to throw and catch an object. This program is similar to the programs in Examples 16-5 and 16-6.

**EXAMPLE 16-7**

```

// Handle division by zero, division by a negative integer,
// and input failure exceptions.

#include <iostream>
#include <string>

using namespace std;

int main()
{
 int dividend, divisor = 1, quotient; //Line 1

 string inpStr
 = "The input stream is in the fail state."; //Line 2

 try //Line 3
 {
 cout << "Line 4: Enter the dividend: "; //Line 4
 cin >> dividend; //Line 5
 cout << endl; //Line 6

 cout << "Line 7: Enter the divisor: "; //Line 7
 cin >> divisor; //Line 8
 cout << endl; //Line 9

 if (divisor == 0) //Line 10
 throw divisor; //Line 11
 else if (divisor < 0) //Line 12
 throw string("Negative divisor."); //Line 13
 else if (!cin) //Line 14
 throw inpStr; //Line 15

 quotient = dividend / divisor; //Line 16

 cout << "Line 17: Quotient = " << quotient
 << endl; //Line 17
 }
 catch (int x) //Line 18
 {
 cout << "Line 19: Division by " << x
 << endl; //Line 19
 }
 catch (string s) //Line 20
 {
 cout << "Line 21: " << s << endl; //Line 21
 }

 return 0; //Line 22
}

```

**Sample Run 1:** In this sample run, the user input is shaded.

Line 4: Enter the dividend: 23

Line 7: Enter the divisor: 6

Line 17: Quotient = 3

**Sample Run 2:** In this sample run, the user input is shaded.

Line 4: Enter the dividend: 34

Line 7: Enter the divisor: -6

Line 21: Negative divisor.

**Sample Run 3:** In this sample run, the user input is shaded.

Line 4: Enter the dividend: 34

Line 7: Enter the divisor: g

Line 21: The input stream is in the fail state.

In this program, the statements in Lines 1 and 2 declare the variables used in the program. Notice that the `string` object `inpStr` is also initialized.

The statements in Lines 4 through 9 input the data into the variables `dividend` and `divisor`. The statement in Line 10 checks whether `divisor` is 0; the statement in Line 12 checks whether `divisor` is negative; and the statement in Line 14 checks whether the standard input stream is in the fail state.

The statement in Line 11 throws the variable `divisor`; the statement in Line 13 throws an anonymous string object with the string "Negative divisor."; and the statement in Line 15 throws the object `inpStr`.

The `catch` block in Line 18 catches an exception of type `int`, and the `catch` block in Line 20 catches an exception of type `string`. If the exception is thrown by the statement in Line 11, it is caught and processed by the `catch` block in Line 18. If the exception is thrown by the statements in Lines 13 or 15, it is caught and processed by the `catch` block in Line 20.

In Sample Run 1, the program does not encounter any problems. In Sample Run 2, division by a negative number occurs. In Sample Run 3, the standard input stream enters the fail state.

---

## Using C++ Exception Classes

C++ provides support to handle exceptions via a hierarchy of classes. The `class exception` is the base of the classes designed to handle exceptions. Among others, this class contains the function `what`. The function `what` returns a string containing an

appropriate message. All derived classes of the `class exception` override the function `what` to issue their own error messages.

Two classes are immediately derived from the `class exception`: `logic_error` and `runtime_error`. Both of these classes are defined in the header file `stdexcept`.

To deal with logical errors in a program, such as a string subscript out of range or an invalid argument to a function call, several classes are derived from the `class logic_error`. For example, the `class invalid_argument` is designed to deal with illegal arguments used in a function call. The `class out_of_range` deals with the string subscript out of range error. If a length greater than the maximum allowed for a string object is used, the `class length_error` deals with this error. For example, recall that every string object has a maximum length (see Chapter 8). If a length larger than the maximum length allowed for a string is used, then the `length_error` exception is generated. If the operator `new` cannot allocate memory space, this operator throws a `bad_alloc` exception.

The `class runtime_error` is designed to deal with errors that can be detected only during program execution. For example, to deal with arithmetic overflow and underflow exceptions, the `classes overflow_error` and `underflow_error` are derived from the `class runtime_error`.

Examples 16-8 and 16-9 illustrate how C++'s exception classes are used to handle exceptions in a program.

The program in Example 16-8 shows how to handle the exceptions `out_of_range` and `length_error`. Notice that in this program, these exceptions are thrown by the string functions `substr` and the string concatenation operator `+`. Because the exceptions are thrown by these functions, we do not include any `throw` statement in the `try` block.

### EXAMPLE 16-8

*// Handling out\_of\_range and length\_error exceptions.*

```
#include <iostream>
#include <string>

using namespace std;

int main()
{
 string sentence; //Line 1
 string str1, str2, str3; //Line 2

 try //Line 3
 {
 sentence = "Testing string exceptions!"; //Line 4
 cout << "Line 5: sentence = " << sentence
 << endl; //Line 5
 }
```

```

 cout << "Line 6: sentence.length() = "
 << static_cast<int>(sentence.length())
 << endl; //Line 6

 str1 = sentence.substr(8, 20); //Line 7
 cout << "Line 8: str1 = " << str1
 << endl; //Line 8

 str2 = sentence.substr(28, 10); //Line 9
 cout << "Line 10: str2 = " << str2
 << endl; //Line 10

 str3 = "Exception handling. " + sentence; //Line 11
 cout << "Line 12: str3 = " << str3
 << endl; //Line 12

}
catch (out_of_range re) //Line 13
{
 cout << "Line 14: In the out_of_range "
 << "catch block: " << re.what()
 << endl; //Line 14
}
catch (length_error le) //Line 15
{
 cout << "Line 16: In the length_error "
 << "catch block: " << le.what()
 << endl; //Line 16
}

return 0; //Line 17
}

```

### Sample Run:

```

Line 5: sentence = Testing string exceptions!
Line 6: sentence.length() = 26
Line 8: str1 = string exceptions!
Line 14: In the out_of_range catch block: invalid string position

```

In this program, the statement in Line 7 uses the function `substr` to determine a substring in the string object `sentence`. The length of the string `sentence` is 26. Because the starting position of the substring is 8, which is less than 26, no exception is thrown. However, in the statement in Line 9, the starting position of the substring is 28, which is greater than 26 (the length of `sentence`). Therefore, the function `substr` throws an `out_of_range` exception, which is caught and processed by the `catch` block in Line 13. Notice that in the statement in Line 14, the object `re` uses the function `what` to return the error message, `invalid string position`.

---

The program in Example 16-9 illustrates how to handle the exception `bad_alloc` thrown by the operator `new`.

**EXAMPLE 16-9**

```

// Handling bad_alloc exception thrown by the operator new.

#include <iostream>

using namespace std;

int main()
{
 int *list[100]; //Line 1

 try //Line 2
 {
 for (int i = 0; i < 100; i++) //Line 3
 {
 list[i] = new int[500000000]; //Line 4
 cout << "Line 4: Created list[" << i
 << "] of 500000000 components." //Line 5
 << endl;
 }
 }
 catch (bad_alloc be) //Line 6
 {
 cout << "Line 7: In the bad_alloc catch "
 << "block: " << be.what() << "."
 << endl; //Line 7
 }

 return 0; //Line 8
}

```

**Sample Run:**

```

Line 4: Created list[0] of 50000000 components.
Line 4: Created list[1] of 50000000 components.
Line 4: Created list[2] of 50000000 components.
Line 4: Created list[3] of 50000000 components.
Line 4: Created list[4] of 50000000 components.
Line 4: Created list[5] of 50000000 components.
Line 4: Created list[6] of 50000000 components.
Line 4: Created list[7] of 50000000 components.
Line 7: In the bad_alloc catch block: bad allocation.

```

The preceding program works as follows. The statement in Line 1 declares `list` to be an array of 100 pointers. The body of the `for` loop in Line 3 is designed to execute 100 times. For each iteration of the `for` loop, the statement in Line 4 uses the operator `new` to allocate an array of 500000000 components of type `int`. As shown in the sample run, the operator `new` is able to create eight arrays of 500000000 components each. In the ninth iteration, the operator `new` is unable to create the array and throws a `bad_alloc`

exception. This exception is caught and processed by the `catch` block in Line 6. Notice that the expression `be.what()` returns the string `bad allocation`. (Moreover, the string returned by `be.what()` is SDK dependent. Some SDKs might return the string `bad_alloc`.) After the statement in Line 7 executes, control exits the `try/catch` block, and the statement in Line 8 terminates the program.

## Creating Your Own Exception Classes

Whenever you create your own classes or write programs, exceptions are likely to occur. As you have seen, C++ provides numerous exception classes to deal with these situations. However, it does not provide all of the exception classes you will ever need. Therefore, C++ enables programmers to create their own exception classes to handle both the exceptions not covered by C++'s exception classes and their own exceptions. This section describes how to create your own exception classes.

C++ uses the same mechanism to process the exceptions that you define as it uses for built-in exceptions. However, you must throw your own exceptions using the `throw` statement.

In C++, any class can be considered an exception class. Therefore, an exception class is simply a class. It need not be inherited from the `class exception`. What makes a class an exception is how you use it.

The exception class that you define can be very simple in the sense that it does not contain any members. For example, the following code can be considered an exception class.

```
class dummyExceptionClass
{
};
```

The program in Example 16-10 uses a user-defined class (with no members) to throw an exception.

### EXAMPLE 16-10

*// Using a user-defined exception class.*

```
#include <iostream>
```

```
using namespace std;
```

```
class divByZero
{};
```

```
int main()
{
```

```
 int dividend, divisor, quotient;
```

*//Line 1*

```

try //Line 2
{
 cout << "Line 3: Enter the dividend: "; //Line 3
 cin >> dividend; //Line 4
 cout << endl; //Line 5

 cout << "Line 6: Enter the divisor: "; //Line 6
 cin >> divisor; //Line 7
 cout << endl; //Line 8

 if (divisor == 0) //Line 9
 throw divByZero(); //Line 10

 quotient = dividend / divisor; //Line 11
 cout << "Line 12: Quotient = " << quotient //Line 12
 << endl; //Line 12
}
catch (divByZero) //Line 13
{
 cout << "Line 14: Division by zero!" //Line 14
 << endl; //Line 14
}

return 0; //Line 15
}

```

**Sample Run 1:** In this sample run, the user input is shaded.

Line 3: Enter the dividend: 34

Line 6: Enter the divisor: 5

Line 12: Quotient = 6

**Sample Run 2:** In this sample run, the user input is shaded.

Line 3: Enter the dividend: 56

Line 6: Enter the divisor: 0

Line 14: Division by zero!

The preceding program works as follows. If the user enters 0 for the divisor, the statement in Line 10 throws an anonymous object of the `class divByZero`. The `class divByZero` has no members, so we cannot really do anything with the thrown object. Therefore, in the `catch` block in Line 13, we specify only the data type name without the parameter name. The statement in Line 14 outputs the appropriate error message.

Let us again consider the statement `throw divByZero();` in Line 10. Notice that in this statement, `divByZero` is the name of the class, the expression `divByZero()` creates an anonymous object of this class, and the `throw` statement throws the object.

---

The exception `class` `divByZero` designed and used in Example 16-10 has no members. Next, we illustrate how to create exception classes with members.

If you want to include members in your exception class, you typically include constructors and the function `what`. Consider the following definition of the `class` `divisionByZero`.

```
// User-defined exception class.

#include <iostream>
#include <string>

using namespace std;

class divisionByZero //Line 1
{ //Line 2
public: //Line 3
 divisionByZero() //Line 4
 {
 message = "Division by zero"; //Line 5
 } //Line 6

 divisionByZero(string str) //Line 7
 {
 message = str; //Line 8
 } //Line 9
 //Line 10

 string what() //Line 11
 {
 return message; //Line 12
 } //Line 13
 //Line 14

private: //Line 15
 string message; //Line 16
}; //Line 17
```

The definition of the `class` `divisionByZero` contains two constructors: the default constructor and the constructor with parameters. The default constructor stores the string "Division by zero" in an object. The constructor with parameters allows users to create their own error messages. The function `what` is used to return the string stored in the object.

#### NOTE

In the definition of the `class` `divisionByZero`, the constructors can also be written as:

```
divisionByZero() : message("Division by zero"){ }
divisionByZero(string str) : message(str){ }
```

The program in Example 16-11 uses the preceding class to throw an exception.

**EXAMPLE 16-11**

```

// Using user-defined exception class divisionByZero with
// default error message.

#include <iostream>
#include "divisionByZero.h"

using namespace std;

int main()
{
 int dividend, divisor, quotient; //Line 1

 try //Line 2
 {
 cout << "Line 3: Enter the dividend: "; //Line 3
 cin >> dividend; //Line 4
 cout << endl; //Line 5

 cout << "Line 6: Enter the divisor: "; //Line 6
 cin >> divisor; //Line 7
 cout << endl; //Line 8

 if (divisor == 0) //Line 9
 throw divisionByZero(); //Line 10

 quotient = dividend / divisor; //Line 11
 cout << "Line 12: Quotient = " << quotient //Line 12
 << endl;

 }
 catch (divisionByZero divByZeroObj) //Line 13
 {
 cout << "Line 14: In the divisionByZero "
 << "catch block: "
 << divByZeroObj.what() << endl; //Line 14
 }

 return 0; //Line 15
}

```

**Sample Run 1:** In this sample run, the user input is shaded.

Line 3: Enter the dividend: 34

Line 6: Enter the divisor: 5

Line 12: Quotient = 6

**Sample Run 2:** In this sample run, the user input is shaded.

Line 3: Enter the dividend: 56

Line 6: Enter the divisor: 0

Line 14: In the divisionByZero catch block: Division by zero

In this program, the statement in Line 10 throws an object (exception) of the `class` `divisionByZero` if the user enters 0 for the `divisor`. This thrown exception is caught and processed by the `catch` block in Line 13. The parameter `divByZeroObj` in the `catch` block catches the value of the thrown object and then uses the function `what` to return the string stored in the object. The statement in Line 14 outputs the appropriate error message.

The program in Example 16-12 is similar to the program in Example 16-11. Here, the thrown object is still an anonymous object, but the error message is specified by the user (see the statement in Line 10).

## EXAMPLE 16-12

```
// Using user-defined exception class divisionByZero with a
// specific error message.

#include <iostream>
#include "divisionByZero.h"

using namespace std;

int main()
{
 int dividend, divisor, quotient; //Line 1

 try //Line 2
 {
 cout << "Line 3: Enter the dividend: "; //Line 3
 cin >> dividend; //Line 4
 cout << endl; //Line 5

 cout << "Line 6: Enter the divisor: "; //Line 6
 cin >> divisor; //Line 7
 cout << endl; //Line 8

 if (divisor == 0) //Line 9
 throw divisionByZero("Found division by zero"); //Line 10

 quotient = dividend / divisor; //Line 11
 cout << "Line 12: Quotient = " << quotient //Line 12
 << endl;
 }
}
```

```
catch (divisionByZero divByZeroObj) //Line 13
{
 cout << "Line 14: In the divisionByZero "
 << "catch block: "
 << divByZeroObj.what() << endl; //Line 14
}

return 0; //Line 15
}
```

```

void doDivision()
{
 int dividend, divisor, quotient; //Line 3

 try
 {
 cout << "Line 4: Enter the dividend: "; //Line 4
 cin >> dividend; //Line 5
 cout << endl; //Line 6

 cout << "Line 7: Enter the divisor: "; //Line 7
 cin >> divisor; //Line 8
 cout << endl; //Line 9

 if (divisor == 0) //Line 10
 throw divisionByZero(); //Line 11

 quotient = dividend / divisor; //Line 12
 cout << "Line 13: Quotient = " << quotient //Line 13
 << endl;

 }
 catch (divisionByZero divByZeroObj) //Line 14
 {
 cout << "Line 15: In the function "
 << "doDivision: "
 << divByZeroObj.what() << endl; //Line 15
 }
}

```

**Sample Run 1:** In this sample run, the user input is shaded.

Line 4: Enter the dividend: 34

Line 7: Enter the divisor: 5

Line 13: Quotient = 6

**Sample Run 2:** In this sample run, the user input is shaded.

Line 4: Enter the dividend: 56

Line 7: Enter the divisor: 0

Line 15: In the function doDivision: Division by zero

## Rethrowing and Throwing an Exception

When an exception occurs in a `try` block, control immediately passes to one of the `catch` blocks. Typically, a `catch` block either handles the exception or partially processes the exception and then rethrows the same exception, or it rethrows another exception in order for the calling environment to handle the exception. The `catch` block in Examples 16-4 through 16-13 handles the exception. The mechanism of rethrowing or throwing an exception is quite useful in cases in which a `catch` block catches the exception but cannot handle the exception, or if the `catch` block decides that the exception should be

handled by the calling block or environment. This allows the programmer to provide the exception-handling code all in one place.

To rethrow or throw an exception, we use the `throw` statement. The general syntax to rethrow an exception caught by a `catch` block is:

```
throw;
```

(in this case, the same exception is rethrown) or:

```
throw expression;
```

in which `expression` is a constant value, variable, or object. The object being thrown can be either a specific object or an anonymous object.

A function specifies the exceptions it throws (to be handled somewhere) in its heading using the `throw` clause. For example, the following function specifies that it throws exceptions of type `int`, `string`, and `divisionByZero`, in which `divisionByZero` is the class, as defined previously.

```
void exmpThrowExcep(int x) throw (int, string, divisionByZero)
{
 .
 .
 .
 //include the appropriate throw statements
 .
 .
 .
}
```

The program in Example 16-14 further explains how a function specifies the exception it throws.

#### EXAMPLE 16-14

```
// Handling an exception, in the main function, thrown by another
// function. The function throws the same exception object.
```

```
#include <iostream>
#include "divisionByZero.h"

using namespace std;

void doDivision() throw (divisionByZero);
```

```

int main()
{
 try //Line 1
 {
 doDivision(); //Line 2
 }
 catch (divisionByZero divByZeroObj) //Line 3
 {
 cout << "Line 4: In main: "
 << divByZeroObj.what() << endl; //Line 4
 }

 return 0; //Line 5
}

void doDivision() throw (divisionByZero)
{
 int dividend, divisor, quotient; //Line 6

 try //Line 7
 {
 cout << "Line 8: Enter the dividend: "; //Line 8
 cin >> dividend; //Line 9
 cout << endl; //Line 10

 cout << "Line 11: Enter the divisor: "; //Line 11
 cin >> divisor; //Line 12
 cout << endl; //Line 13

 if (divisor == 0) //Line 14
 throw divisionByZero("Found division by 0!"); //Line 15

 quotient = dividend / divisor; //Line 16
 cout << "Line 17: Quotient = " << quotient
 << endl; //Line 17
 }
 catch (divisionByZero) //Line 18
 {
 throw; //Line 19
 }
}

```

**Sample Run 1:** In this sample run, the user input is shaded.

Line 8: Enter the dividend: 34

Line 11: Enter the divisor: 5

Line 17: Quotient = 6

**Sample Run 2:** In this sample run, the user input is shaded.

Line 8: Enter the dividend: 56

Line 11: Enter the divisor: 0

Line 4: In main: Found division by 0!

In this program, if the value of `divisor` is 0, the statement in Line 15 throws an exception of type `divisionByZero`, which is an anonymous object of this class, with the message string:

```
"Found division by 0!"
```

The statement in Line 19, in the `catch` block, throws the same exception value, which in this case is an object.

In Sample Run 1, no exception is thrown.

Let us see what happens in Sample Run 2. The function `main` calls the function `doDivision` in the `try` block. In the function `doDivision`, the value of `divisor` is 0, so the statement in Line 15 throws an exception. The exception is caught by the `catch` block in Line 18. The statement in Line 19 rethrows the same exception. In other words, the `catch` block catches and rethrows the same exception. Therefore, the function call statement in Line 2 results in throwing an exception. This exception is caught and processed by the `catch` block in Line 3.

---

### EXAMPLE 16-15

```
// Handling exception, in the main function, thrown by another
// function. The function throws a different exception object.
```

```
#include <iostream>
#include "divisionByZero.h"

using namespace std;

void doDivision() throw (divisionByZero);

int main()
{
 try //Line 1
 {
 doDivision(); //Line 2
 }
 catch (divisionByZero divByZeroObj) //Line 3
 {
 cout << "Line 4: In main: "
 << divByZeroObj.what() << endl; //Line 4
 }

 return 0; //Line 5
}
```

```

void doDivision() throw (divisionByZero)
{
 int dividend, divisor, quotient; //Line 6

 try //Line 7
 {
 cout << "Line 8: Enter the dividend: "; //Line 8
 cin >> dividend; //Line 9
 cout << endl; //Line 10

 cout << "Line 11: Enter the divisor: "; //Line 11
 cin >> divisor; //Line 12
 cout << endl; //Line 13

 if (divisor == 0) //Line 14
 throw divisionByZero(); //Line 15

 quotient = dividend / divisor; //Line 16
 cout << "Line 17: Quotient = " << quotient //Line 17
 << endl;

 }
 catch (divisionByZero) //Line 18
 {
 throw
 divisionByZero("Division by zero found!"); //Line 19
 }
}

```

**Sample Run 1:** In this sample run, the user input is shaded.

Line 8: Enter the dividend: 34

Line 11: Enter the divisor: 5

Line 17: Quotient = 6

**Sample Run 2:** In this sample run, the user input is shaded.

Line 8: Enter the dividend: 56

Line 11: Enter the divisor: 0

Line 4: In main: Division by zero found!

This program works the same way as the program in Example 16-14. The only difference is that here, the `catch` block in Line 18 rethrows a different exception value, that is, object.

---

The programs in Examples 16-14 and 16-15 illustrate how a function can rethrow the same exception or throw another exception for the calling function to handle. This mechanism is quite useful because it allows a program to handle all of the exceptions in one location, rather than spread the exception-handling code throughout the program.

## Exception-Handling Techniques

When an exception occurs in a program, the programmer usually has three choices: terminate the program, include code in the program to recover from the exception, or log the error and continue. The following sections discuss each of these situations.

### Terminate the Program

In some cases, it is best to let the program terminate when an exception occurs. Suppose you have written a program that inputs data from a file. If the input file does not exist when the program executes, then there is no point in continuing with the program. In this case, the program can output an appropriate error message and terminate.

### Fix the Error and Continue

In other cases, you will want to handle the exception and let the program continue. Suppose that you have a program that takes as input an integer. If a user inputs a letter in place of a number, the input stream will enter the fail state. This is a situation in which you can include the necessary code to keep prompting the user to input a number until the entry is valid. The program in Example 16-16 illustrates this situation.

#### EXAMPLE 16-16

// Handle exceptions by fixing the errors. The program continues to  
// prompt the user until a valid input is entered.

```
#include <iostream>
#include <string>

using namespace std;

int main()
{
 int number; //Line 1
 bool done = false; //Line 2

 string str =
 "The input stream is in the fail state."; //Line 3

 do //Line 4
 { //Line 5
 try //Line 6
 { //Line 7
 cout << "Line 8: Enter an integer: "; //Line 8
 cin >> number; //Line 9
 }
 }
}
```

```

 cout << endl; //Line 10

 if (!cin) //Line 11
 throw str; //Line 12

 done = true; //Line 13
 cout << "Line 14: Number = " << number
 << endl; //Line 14
 } //Line 15
 catch (string messageStr) //Line 16
 { //Line 17
 cout << "Line 18: " << messageStr
 << endl; //Line 18
 cout << "Line 19: Restoring the "
 << "input stream." << endl; //Line 19
 cin.clear(); //Line 20
 cin.ignore(100, '\n'); //Line 21
 } //Line 22
 }
 while (!done); //Line 23

 return 0; //Line 24
}

```

**Sample Run:** In this sample run, the user input is shaded.

Line 8: Enter an integer: **r5**

Line 18: The input stream is in the fail state.

Line 19: Restoring the input stream.

Line 8: Enter an integer: **d45**

Line 18: The input stream is in the fail state.

Line 19: Restoring the input stream.

Line 8: Enter an integer: **hw3**

Line 18: The input stream is in the fail state.

Line 19: Restoring the input stream.

Line 8: Enter an integer: **48**

Line 14: Number = 48

This program prompts the user to enter an integer. If the input is invalid, the standard input stream enters the fail state. In the `try` block, the statement in Line 12 throws an exception, which is a string object. Control passes to the `catch` block, and the exception is caught and processed. The statement in Line 20 restores the input stream to its good state, and the statement in Line 21 clears the rest of the input from the line. The `do...while` loop continues to prompt the user until the user inputs a valid number.

## Log the Error and Continue

The program that terminates when an exception occurs usually assumes that this termination is reasonably safe. However, if your program is designed to run a nuclear reactor or continuously monitor a satellite, it cannot be terminated if an exception occurs. These programs should report the exception, but the program must continue to run.

For example, consider a program that analyzes an airline's ticketing transactions. Because numerous ticketing transactions occur each day, a program is run at the end of each day to validate that day's transactions. This type of program would take an enormous amount of time to process the transactions and use exceptions to identify any erroneous entries. Instead, when an exception occurs, the program should write the exception into a file and continue to analyze the transactions.

## Stack Unwinding

The examples given in this chapter show how to catch and process an exception. In particular, you learned how to catch and process an exception in the same block, as well as process the caught exception in the calling environment.

When an exception is thrown in, say, a function, the function can do the following:

- Do nothing.
- Partially process the exception and throw the same exception or a new exception.
- Throw a new exception.

In each of these cases, the function-call stack is unwound so that the exception can be caught in the next `try/catch` block. When the function call stack is unwound, the function in which the exception was not caught and/or rethrown terminates, and the memory for its local variables is destroyed. The stack unwinding continues until either a `try/catch` handles the exception or the program does not handle the exception. If the program does not handle the exception, then the function `terminate` is called to terminate the program.

Examples 16-17 and 16-18 illustrate how the exceptions are propagated. For this, let us define the following exception class:

```
// User-defined myException class.

#include <string>

using namespace std;
```

```

class myException
{
public:
 myException()
 {
 message = "Something is wrong!";
 }

 myException(string str)
 {
 message = str;
 }

 string what()
 {
 return message;
 }

private:
 string message;
};

```

**NOTE**

In the definition of the `class myException`, the constructors can also be written as follows:

```

myException() : message("Something is wrong!"){ }
myException(string str) : message(str){ }

```

The program in Example 16-17 illustrates how exceptions thrown in a function get processed in the calling environment.

**EXAMPLE 16-17**

```

// Processing exceptions thrown by a function in the calling
// environment.

```

```

#include <iostream>
#include "myException.h"

using namespace std;

void functionA() throw (myException);
void functionB() throw (myException);
void functionC() throw (myException);

int main()
{
 try
 {
 functionA();
 }
}

```

```

 catch (myException me)
 {
 cout << me.what() << " Caught in main." << endl;
 }

 return 0;
 }

 void functionA() throw (myException)
 {
 functionB();
 }

 void functionB() throw (myException)
 {
 functionC();
 }

 void functionC() throw (myException)
 {
 throw myException("Exception generated in function C.");
 }

```

**Sample Run:**

Exception generated in function C. Caught in main.

In this program, the function `main` calls `functionA`, `functionA` calls `functionB`, and `functionB` calls `functionC`. The function `functionC` creates and throws an exception of type `myException`. The functions `functionA` and `functionB` do not process the exception thrown by `functionC`.

The function `main` calls `functionA` in the `try` block and catches the exception thrown by `functionC`. The parameter `me` in the `catch` block heading catches the value of the exception and then uses the function `what` to return the string stored in that object. The output statement in the `catch` block outputs the appropriate message.

---

The program in Example 16-18 is similar to the program in Example 16-17. Here, the exception is caught and processed by the immediate calling environment.

**EXAMPLE 16-18**

```

// Processing exceptions, thrown by a function, in the
// immediate calling environment.

#include <iostream>
#include "myException.h"

```

```

using namespace std;

void functionA();
void functionB();
void functionC() throw (myException);

int main()
{
 try
 {
 functionA();
 }
 catch (myException e)
 {
 cout << e.what() << " Caught in main." << endl;
 }

 return 0;
}

void functionA()
{
 functionB();
}

void functionB()
{
 try
 {
 functionC();
 }
 catch (myException me)
 {
 cout << me.what() << " Caught in functionB." << endl;
 }
}

void functionC() throw (myException)
{
 throw myException("Exception generated in functionC.");
}

```

**Sample Run:**

Exception generated in functionC. Caught in functionB.

In this program, the exception is caught and processed by `functionB`. Even though the function `main` contains the `try/catch` block, the `try` block does not throw any exceptions because the exception thrown by `functionC` is caught and processed by `functionB`.

---

## QUICK REVIEW

---

1. An exception is an occurrence of an undesirable situation that can be detected during program execution.
2. Some typical ways of dealing with exceptions are to use an **if** statement or the **assert** function.
3. The function **assert** can check whether an expression meets the required condition(s). If the conditions are not met, it terminates the program.
4. The **try/catch** block is used to handle exceptions within a program.
5. Statements that may generate an exception are placed in a **try** block. The **try** block also contains statements that should not be executed if an exception occurs.
6. The **try** block is followed by one or more **catch** blocks.
7. A **catch** block specifies the type of exception it can catch and contains an exception handler.
8. If the heading of a **catch** block contains **...**(ellipses) in place of parameters, then this **catch** block can catch exceptions of all types.
9. If no exceptions are thrown in a **try** block, all **catch** blocks associated with that **try** block are ignored and program execution resumes after the last **catch** block.
10. If an exception is thrown in a **try** block, the remaining statements in the **try** block are ignored. The program searches the **catch** blocks, in the order they appear after the **try** block, and looks for an appropriate exception handler. If the type of the thrown exception matches the parameter type in one of the **catch** blocks, then the code in that **catch** block executes and the remaining **catch** blocks after this **catch** block are ignored.
11. The data type of the **catch** block parameter specifies the type of exception that the **catch** block can catch.
12. A **catch** block can have, at most, one **catch** block parameter.
13. If only the data type is specified in a **catch** block heading, that is, if there is no **catch** block parameter, then the thrown value may not be accessible in the **catch** block exception-handling code.
14. In order for an exception to occur in a **try** block and be caught by a **catch** block, the exception must be thrown in the **try** block.
15. The general syntax to **throw** an exception is:  
**throw expression;**  
in which **expression** is a constant value, variable, or object. The object being thrown can be either a specific object or an anonymous object.
16. C++ provides support to handle exceptions via a hierarchy of classes.

17. The `class exception` is the base class of the exception classes provided by C++.
18. The function `what` returns the string containing the exception object thrown by C++'s built-in exception classes.
19. The `class exception` is contained in the header file `exception`.
20. The two classes that are immediately derived from the `class exception` are `logic_error` and `runtime_error`. Both of these classes are defined in the header file `stdexcept`.
21. The `class invalid_argument` is designed to deal with illegal arguments used in a function call.
22. The `class out_of_range` deals with the string subscript `out_of_range` error.
23. If a length greater than the maximum allowed for a string object is used, the `class length_error` deals with the error that occurs when a length greater than the maximum size allowed for the object being manipulated is used.
24. If the operator `new` cannot allocate memory space, this operator throws a `bad_alloc` exception.
25. The `class runtime_error` is designed to deal with errors that can be detected only during program execution. For example, to deal with arithmetic overflow and underflow exceptions, the classes `overflow_error` and `underflow_error` are derived from the `class runtime_error`.
26. A `catch` block typically handles the exception or partially processes the exception and then either rethrows the same exception or rethrows another exception in order for the calling environment to handle the exception.
27. C++ enables programmers to create their own exception classes to handle both the exceptions not covered by C++'s exception classes and their own exceptions.
28. C++ uses the same mechanism to process the exceptions you define as it uses for built-in exceptions. However, you must throw your own exceptions using the `throw` statement.
29. In C++, any class can be considered an exception class. It need not be inherited from the `class exception`. What makes a class an exception is how it is used.
30. The general syntax to rethrow an exception caught by a `catch` block is:  
`throw;`  
 (in this case, the same exception is rethrown) or:  
`throw expression;`  
 in which `expression` is a constant value, variable, or object. The object being thrown can be either a specific object or an anonymous object.

31. A function specifies the exceptions it throws in its heading using the `throw` clause.
32. When an exception is thrown in a function, the function can do the following: do nothing; partially process the exception and throw the same exception or a new exception; or throw a new exception. In each of these cases, the function-call stack is unwound so that the exception can be caught in the next `try/catch` block. The stack unwinding continues until a `try/catch` handles the exception or the program does not handle the exception.
33. If the program does not handle the exception, then the function `terminate` is called to terminate the program.

## EXERCISES

---

1. Mark the following statements as true or false.
  - a. The order in which `catch` blocks are listed is not important.
  - b. An exception can be caught either in the function where it occurred or in any of the functions that led to the invocation of this method.
  - c. One way to handle an exception is to print an error message and exit the program.
  - d. All exceptions need to be reported to avoid compilation errors.
2. What is the difference between a `try` block and a `catch` block?
3. What will happen if an exception is thrown but not caught?
4. What happens if no exception is thrown in a `try` block?
5. What happens if an exception is thrown in a `try` block?
6. Consider the following C++ code:

```
double balance;

try
{
 cout << "Enter the balance: ";
 cin >> balance;
 cout << endl;

 if (balance < 1000.00)
 throw balance;

 cout << "Leaving the try block." << endl;
}
catch (double x)
{
 cout << "Current balance: " << x << endl
 << "Balance must be greater than 1000.00" << endl;
}
```

- a. In this code, identify the `try` block.
  - b. In this code, identify the `catch` block.
  - c. In this code, identify the `catch` block parameter and its type.
  - d. In this code, identify the `throw` statement.
7. Assume the code given in Exercise 6.
    - a. What is the output if the input is 1200?
    - b. What is the output if the input is 975?
    - c. What is the output if the input is -2000?
  8. Consider the following C++ code:

```
int lowerLimit;
.
.
.
try
{
 cout << "Entering the try block." << endl;

 if (lowerLimit < 100)
 throw exception("Lower limit violation.");

 cout << "Exiting the try block." << endl;
}
catch (exception eObj)
{
 cout << "Exception: " << eObj.what() << endl;
}
cout << "After the catch block" << endl;
```

What is the output if:

- a. The value of `lowerLimit` is 50?
  - b. The value of `lowerLimit` is 150?
9. Consider the following C++ code:

```
int lowerLimit;
int divisor;
int result;

try
{
 cout << "Entering the try block." << endl;

 if (divisor == 0)
 throw 0;
 if (lowerLimit < 100)
 throw string("Lower limit violation.");

 result = lowerLimit / divisor;
```

```

 cout << "Exiting the try block." << endl;
 }
 catch (int x)
 {
 cout << "Exception: " << x << endl;
 result = 120;
 }
 catch (string str)
 {
 cout << "Exception: " << str << endl;
 }

 cout << "After the catch block" << endl;

```

What is the output if:

- a. The value of `lowerLimit` is 50, and the value of `divisor` is 10?
  - b. The value of `lowerLimit` is 50, and the value of `divisor` is 0?
  - c. The value of `lowerLimit` is 150, and the value of `divisor` is 10?
  - d. The value of `lowerLimit` is 150, and the value of `divisor` is 0?
10. If you define your own exception class, what typically is included in that class?
  11. What type of statement is used to rethrow an exception?
  12. Define an exception `class` called `tornadoException`. The class should have two constructors, including the default constructor. If the exception is thrown with the default constructor, the method `what` should return `"Tornado: Take cover immediately!"`. The other constructor has a single parameter, say, `m`, of the `int` type. If the exception is thrown with this constructor, the method `what` should return `"Tornado: m miles away; and approaching!"`
  13. Write a C++ program to test the `class` `tornadoException` specified in Exercise 12.
  14. Suppose the exception `class` `myException` is defined as follows:

```

class myException
{
public:
 myException()
 {
 message = "myException thrown!";
 cout << "Immediate attention required!"
 << endl;
 }

 myException(string msg)
 {
 message = msg;
 cout << "Attention required!" << endl;
 }
}

```

```

 string what()
 {
 return message;
 }

private:
 string message;
}

```

Suppose that in a user program, the `catch` block has the following form:

```

catch (myException mE)
{
 cout << mE.what() << endl;
}

```

What output will be produced if the exception is thrown with the default constructor? Also, what output will be produced if the exception is thrown with the constructor with parameters with the following actual parameter?

**"May Day, May Day"**

15. If a function throws an exception, how does it specify that exception?
16. Name three exception-handling techniques.

## PROGRAMMING EXERCISES

1. Write a program that prompts the user to enter a length in feet and inches and outputs the equivalent length in centimeters. If the user enters a negative number or a nondigit number, throw and handle an appropriate exception and prompt the user to enter another set of numbers.
2. Redo Programming Exercise 7 of Chapter 8 so that your program handles exceptions such as division by zero and invalid input.
3. Write a program that prompts the user to enter time in 12-hour notation. The program then outputs the time in 24-hour notation. Your program must contain three exception `classes`: `invalidHr`, `invalidMin`, and `invalidSec`. If the user enters an invalid value for hours, then the program should throw and catch an `invalidHr` object. Similar conventions for the invalid values of minutes and seconds.
4. Write a program that prompts the user to enter a person's date of birth in numeric form such as 8-27-1980. The program then outputs the date of birth in the form: August 27, 1980. Your program must contain at least two exception `classes`: `invalidDay` and `invalidMonth`. If the user enters an invalid value for day, then the program should throw and catch an `invalidDay` object. Similar conventions for the invalid values of month and year. (Note that your program must handle a leap year.)

*This page intentionally left blank*



# 17

## CHAPTER

# RECURSION

IN THIS CHAPTER, YOU WILL:

- Learn about recursive definitions
- Explore the base case and the general case of a recursive definition
- Discover what is a recursive algorithm
- Learn about recursive functions
- Explore how to use recursive functions to implement recursive algorithms

In previous chapters, to devise solutions to problems, we used the most common technique called iteration. For certain problems, however, using the iterative technique to obtain the solution is quite complicated. This chapter introduces another problem-solving technique called recursion and provides several examples demonstrating how recursion works.

## Recursive Definitions

The process of solving a problem by reducing it to smaller versions of itself is called **recursion**. Recursion is a very powerful way to solve certain problems for which the solution would otherwise be very complicated. Let us consider a problem that is familiar to most everyone.

In mathematics, the factorial of a nonnegative integer is defined as follows:

$$0! = 1 \quad (17-1)$$

$$n! = n \times (n - 1)! \quad \text{if } n > 0 \quad (17-2)$$

In this definition,  $0!$  is defined to be 1, and if  $n$  is an integer greater than 0, first we find  $(n - 1)!$  and then multiply it by  $n$ . To find  $(n - 1)!$ , we apply the definition again. If  $(n - 1) > 0$ , then we use Equation 17-2; otherwise, we use Equation 17-1. Thus, for an integer  $n$  greater than 0,  $n!$  is obtained by first finding  $(n - 1)!$  (that is,  $n!$  is reduced to a smaller version of itself) and then multiplying  $(n - 1)!$  by  $n$ .

Let us apply this definition to find  $3!$ . Here,  $n = 3$ . Because  $n > 0$ , we use Equation 17-2 to obtain:

$$3! = 3 \times 2!$$

Next, we find  $2!$ . Here,  $n = 2$ . Because  $n > 0$ , we use Equation 17-2 to obtain:

$$2! = 2 \times 1!$$

Now, to find  $1!$ , we again use Equation 17-2 because  $n = 1 > 0$ . Thus:

$$1! = 1 \times 0!$$

Finally, we use Equation 17-1 to find  $0!$ , which is 1. Substituting  $0!$  into  $1!$  gives  $1! = 1$ . This gives  $2! = 2 \times 1! = 2 \times 1 = 2$ , which, in turn, gives  $3! = 3 \times 2! = 3 \times 2 = 6$ .

The solution in Equation 17-1 is direct—that is, the right side of the equation contains no factorial notation. The solution in Equation 17-2 is given in terms of a smaller version of itself. The definition of the factorial given in Equations 17-1 and 17-2 is called a **recursive definition**. Equation 17-1 is called the **base case** (that is, the case for which the solution is obtained directly); Equation 17-2 is called the **general case**.

**Recursive definition:** A definition in which something is defined in terms of a smaller version of itself.

From the previous example (factorial), it is clear that:

1. Every recursive definition must have one (or more) base cases.
2. The general case must eventually be reduced to a base case.
3. The base case stops the recursion.

The concept of recursion in computer science works similarly. Here, we talk about recursive algorithms and recursive functions. An algorithm that finds the solution to a given problem by reducing the problem to smaller versions of itself is called a **recursive algorithm**. The recursive algorithm must have one or more base cases, and the general solution must eventually be reduced to a base case.


A function that calls itself is called a **recursive function**. That is, the body of the recursive function contains a statement that causes the same function to execute again before completing the current call. Recursive algorithms are implemented using recursive functions.

Next, let us write the recursive function that implements the factorial function.

```
int fact(int num)
{
 if (num == 0)
 return 1;
 else
 return num * fact(num - 1);
}
```

Figure 17-1 traces the execution of the following statement:

```
cout << fact(4) << endl;
```



**FIGURE 17-1** Execution of `fact(4)`

The output of the previous `cout` statement is:

24

In Figure 17-1, the down arrow represents the successive calls to the function `fact`, and the upward arrows represent the values returned to the caller, that is, the calling function.

Let us note the following from the preceding example, involving the factorial function.

- Logically, you can think of a recursive function as having an unlimited number of copies of itself.
- Every call to a recursive function—that is, every recursive call—has its own code and its own set of parameters and local variables.

- After completing a particular recursive call, control goes back to the calling environment, which is the previous call. The current (recursive) call must execute completely before control goes back to the previous call. The execution in the previous call begins from the point immediately following the recursive call.

## Direct and Indirect Recursion

A function is called **directly recursive** if it calls itself. A function that calls another function and eventually results in the original function call is said to be **indirectly recursive**. For example, if a function **A** calls a function **B** and function **B** calls function **A**, then function **A** is indirectly recursive. Indirect recursion can be several layers deep. For example, suppose that function **A** calls function **B**, function **B** calls function **C**, function **C** calls function **D**, and function **D** calls function **A**. Function **A** is then indirectly recursive.

Indirect recursion requires the same careful analysis as direct recursion. The base cases must be identified, and appropriate solutions to them must be provided. However, tracing through indirect recursion can be tedious. You must, therefore, exercise extra care when designing indirect recursive functions. For simplicity, the problems in this book involve only direct recursion.

A recursive function in which the last statement executed is the recursive call is called a **tail recursive function**. The function **fact** is an example of a tail recursive function.

## Infinite Recursion

Figure 17-1 shows that the sequence of recursive calls eventually reached a call that made no further recursive calls. That is, the sequence of recursive calls eventually reached a base case. On the other hand, if every recursive call results in another recursive call, then the recursive function (algorithm) is said to have infinite recursion. In theory, infinite recursion executes forever. Every call to a recursive function requires the system to allocate memory for the local variables and formal parameters. The system also saves this information so that after completing a call, control can be transferred back to the right caller. Therefore, because computer memory is finite, if you execute an infinite recursive function on a computer, the function executes until the system runs out of memory and results in an abnormal termination of the program.

Recursive functions (algorithms) must be carefully designed and analyzed. You must make sure that every recursive call eventually reduces to a base case. This chapter provides several examples that illustrate how to design and implement recursive algorithms.

To design a recursive function, you must do the following:

- a. Understand the problem requirements.
- b. Determine the limiting conditions. For example, for a list, the limiting condition is the number of elements in the list.

- c. Identify the base cases and provide a direct solution to each base case.
- d. Identify the general cases and provide a solution to each general case in terms of smaller versions of itself.

## Problem Solving Using Recursion

Examples 17-1 through 17-3 illustrate how recursive algorithms are developed and implemented in C++ using recursive functions.

### EXAMPLE 17-1: LARGEST ELEMENT IN AN ARRAY

In Chapter 9, we used a loop to find the largest element in an array. In this example, we use a recursive algorithm to find the largest element in an array. Consider the list given in Figure 17-2.

|      | [0] | [1] | [2] | [3] | [4] | [5] | [6] |
|------|-----|-----|-----|-----|-----|-----|-----|
| list | 5   | 8   | 2   | 10  | 9   | 4   |     |

FIGURE 17-2 list with six elements

The largest element in the list in Figure 17-2 is 10.

Suppose `list` is the name of the array containing the list elements. Also, suppose that `list[a]...list[b]` stands for the array elements `list[a]`, `list[a + 1]`, ..., and `list[b]`. For example, `list[0]...list[5]` represents the array elements `list[0]`, `list[1]`, `list[2]`, `list[3]`, `list[4]`, and `list[5]`. Similarly, `list[1]...list[5]` represents the array elements `list[1]`, `list[2]`, `list[3]`, `list[4]`, and `list[5]`. To write a recursive algorithm to find the largest element in `list`, let us think in terms of recursion.

If `list` is of length 1, then `list` has only one element, which is the largest element. Suppose the length of `list` is greater than 1. To find the largest element in `list[a]...list[b]`, we first find the largest element in `list[a + 1]...list[b]` and then compare this largest element with `list[a]`. That is, the largest element in `list[a]...list[b]` is given by:

```
maximum(list[a], largest(list[a + 1]...list[b]))
```

Let us apply this formula to find the largest element in the list shown in Figure 17-2. This list has six elements, given by `list[0]...list[5]`. Now, the largest element in `list` is:

```
maximum(list[0], largest(list[1]...list[5]))
```

That is, the largest element in `list` is the maximum of `list[0]` and the largest element in `list[1]...list[5]`. To find the largest element in `list[1]...list[5]`, we use the same formula again because the length of this list is greater than 1. The largest element in `list[1]...list[5]` is then:

```
maximum(list[1], largest(list[2]...list[5]))
```

and so on. We see that every time we use the preceding formula to find the largest element in a sublist, the length of the sublist in the next call is reduced by one. Eventually, the sublist is of length 1, in which case the sublist contains only one element, which is the largest element in the sublist. From this point onward, we backtrack through the recursive calls. This discussion translates into the following recursive algorithm, which is presented in pseudocode.

**Base Case:** The size of the list is 1

The only element in the list is the largest element

**General Case:** The size of the list is greater than 1

To find the largest element in `list[a]...list[b]`

- a. Find the largest element in `list[a + 1]...list[b]`  
and call it `max`
- b. Compare the elements `list[a]` and `max`  
     **if** (`list[a] >= max`)  
         the largest element in `list[a]...list[b]` is `list[a]`  
     **otherwise**  
         the largest element in `list[a]...list[b]` is `max`

This algorithm translates into the following C++ function to find the largest element in an array:

```
int largest(const int list[], int lowerIndex, int upperIndex)
{
 int max;

 if (lowerIndex == upperIndex) //size of the sublist is one
 return list[lowerIndex];
 else
 {
 max = largest(list, lowerIndex + 1, upperIndex);

 if (list[lowerIndex] >= max)
 return list[lowerIndex];
 else
 return max;
 }
}
```

Consider the `list` given in Figure 17-3.




FIGURE 17-3 list with four elements

Let us trace the execution of the following statement:

```
cout << largest(list, 0, 3) << endl;
```

Here, `upperIndex` = 3 and the list have four elements. Figure 17-4 traces the execution of `largest(list, 0, 3)`.




FIGURE 17-4 Execution of `largest(list, 0, 3)`

The value returned by the expression `largest(list, 0, 3)` is 12, which is the largest element in `list`.

The following C++ program uses the function `largest` to determine the largest element in a list.

```

//Largest Element in an Array

#include <iostream>

using namespace std;

int largest(const int list[], int lowerIndex, int upperIndex);

int main()
{
 int intArray[10] = {23, 43, 35, 38, 67, 12, 76, 10, 34, 8};

 cout << "The largest element in intArray: "
 << largest(intArray, 0, 9);
 cout << endl;

 return 0;
}

int largest(const int list[], int lowerIndex, int upperIndex)
{
 int max;

 if (lowerIndex == upperIndex) //size of the sublist is one
 return list[lowerIndex];
 else
 {
 max = largest(list, lowerIndex + 1, upperIndex);

 if (list[lowerIndex] >= max)
 return list[lowerIndex];
 else
 return max;
 }
}

```

**Sample Run:**

The largest element in intArray: 76

---

**EXAMPLE 17-2: FIBONACCI NUMBER**

In Chapter 5, we designed a program to determine the desired Fibonacci number. In this example, we write a recursive function, **rFibNum**, to determine the desired Fibonacci number. The function **rFibNum** takes as parameters three numbers representing the first two numbers of the Fibonacci sequence and a number *n*, the desired *n*th Fibonacci number. The function **rFibNum** returns the *n*th Fibonacci number in the sequence.

Recall that the third Fibonacci number is the sum of the first two Fibonacci numbers. The fourth Fibonacci number in a sequence is the sum of the second and third Fibonacci numbers. Therefore, to calculate the fourth Fibonacci number, we add the second Fibonacci number and the third Fibonacci number (which is itself the sum of the first two Fibonacci numbers). The following recursive algorithm calculates the  $n$ th Fibonacci number, in which  $a$  denotes the first Fibonacci number,  $b$  the second Fibonacci number, and  $n$  the  $n$ th Fibonacci number.

$$rFibNum(a,b,n) = \begin{cases} a & \text{if } n = 1 \\ b & \text{if } n = 2 \\ rFibNum(a,b,n-1) + rFibNum(a,b,n-2) & \text{if } n > 2. \end{cases} \quad (17-3)$$

Suppose that we want to determine:

`rFibNum(2, 5, 4)`

Here,  $a=2$ ,  $b=5$ , and  $n=4$ . That is, we want to determine the fourth Fibonacci number of the sequence whose first number is 2 and whose second number is 5. Because  $n$  is  $4 > 2$ :

$$1. \quad rFibNum(2, 5, 4) = rFibNum(2, 5, 3) + rFibNum(2, 5, 2)$$

Next, we determine `rFibNum(2, 5, 3)` and `rFibNum(2, 5, 2)`. Let us first determine `rFibNum(2, 5, 3)`. Here,  $a = 2$ ,  $b = 5$ , and  $n$  is 3. Because  $n$  is 3:

$$1.a. \quad rFibNum(2, 5, 3) = rFibNum(2, 5, 2) + rFibNum(2, 5, 1)$$

This statement requires us to determine `rFibNum(2, 5, 2)` and `rFibNum(2, 5, 1)`. In `rFibNum(2, 5, 2)`,  $a = 2$ ,  $b = 5$ , and  $n = 2$ . Therefore, from the definition given in Equation 17-3, it follows that:

$$1.a.1. \quad rFibNum(2, 5, 2) = 5$$

To find `rFibNum(2, 5, 1)`, note that  $a = 2$ ,  $b = 5$ , and  $n = 1$ . Therefore, by the definition given in Equation 17-3:

$$1.a.2. \quad rFibNum(2, 5, 1) = 2$$

We substitute the values of `rFibNum(2, 5, 2)` and `rFibNum(2, 5, 1)` into (1.a) to get:

$$rFibNum(2, 5, 3) = 5 + 2 = 7$$

Next, we determine `rFibNum(2, 5, 2)`. As in (1.a.1), `rFibNum(2, 5, 2) = 5`. We can substitute the values of `rFibNum(2, 5, 3)` and `rFibNum(2, 5, 2)` into (1) to get:

$$rFibNum(2, 5, 4) = 7 + 5 = 12$$

The following recursive function implements this algorithm.

```
int rFibNum(int a, int b, int n)
{
 if (n == 1)
 return a;
 else if (n == 2)
 return b;
 else
 return rFibNum(a, b, n - 1) + rFibNum(a, b, n - 2);
}
```

Let us trace the execution of the following statement:

```
cout << rFibNum(2, 3, 5) << endl;
```

In this statement, the first number is 2, the second number is 3, and we want to determine the fifth Fibonacci number of the sequence. Figure 17-5 traces the execution of the expression `rFibNum(2,3,5)`. The value returned is 13, which is the fifth Fibonacci number of the sequence whose first number is 2 and second number is 3.




FIGURE 17-5 Execution of `rFibNum(2, 3, 5)`

The following C++ program uses the function `rFibNum`:

```
//Chapter 17: Fibonacci Number
```

```
#include <iostream>

using namespace std;

int rFibNum(int a, int b, int n);

int main()
{
 int firstFibNum;
 int secondFibNum;
 int nth;

 cout << "Enter the first Fibonacci number: ";
 cin >> firstFibNum;
 cout << endl;

 cout << "Enter the second Fibonacci number: ";
 cin >> secondFibNum;
 cout << endl;

 cout << "Enter the position of the desired Fibonacci number: ";
 cin >> nth;
 cout << endl;

 cout << "The Fibonacci number at position " << nth
 << " is: " << rFibNum(firstFibNum, secondFibNum, nth)
 << endl;

 return 0;
}

int rFibNum(int a, int b, int n)
{
 if (n == 1)
 return a;
 else if (n == 2)
 return b;
 else
 return rFibNum(a, b, n - 1) + rFibNum(a, b, n - 2);
}
```

**Sample Runs:** In these sample runs, the user input is shaded.

#### Sample Run 1

Enter the first Fibonacci number: 2

Enter the second Fibonacci number: 5

Enter the position of the desired Fibonacci number: 6

The Fibonacci number at position 6 is: 31

### Sample Run 2

Enter the first Fibonacci number: 12

Enter the second Fibonacci number: 18

Enter the position of the desired Fibonacci number: 15

The Fibonacci number at position 15 is: 9582

## EXAMPLE 17-3: TOWER OF HANOI

In the nineteenth century, a game called the Tower of Hanoi became popular in Europe. This game represents work that is underway in the temple of Brahma. At the creation of the universe, priests in the temple of Brahma were supposedly given three diamond needles, with one needle containing 64 golden disks. Each golden disk is slightly smaller than the disk below it. The priests' task is to move all 64 disks from the first needle to the third needle. The rules for moving the disks are as follows:

1. Only one disk can be moved at a time.
2. The removed disk must be placed on one of the needles.
3. A larger disk cannot be placed on top of a smaller disk.

The priests were told that once they had moved all of the disks from the first needle to the third needle, the universe would come to an end.

Our objective is to write a program that prints the sequence of moves needed to transfer the disks from the first needle to the third needle. Figure 17-6 shows the Tower of Hanoi problem with three disks.





FIGURE 17-6 Tower of Hanoi problem with three disks

As before, we think in terms of recursion. Let us first consider the case in which the first needle contains only one disk. In this case, the disk can be moved directly from needle 1 to needle 3. So let us consider the case in which the first needle contains only two disks. In this case, first we move the first disk from needle 1 to needle 2, and then we move the second disk from needle 1 to needle 3. Finally, we move the first disk from needle 2 to needle 3. Next, we consider the case in which the first needle contains three disks and then generalize this to the case of 64 disks (in fact, to an arbitrary number of disks).

Suppose that needle 1 contains three disks. To move disk number 3 to needle 3, the top two disks must first be moved to needle 2. Disk number 3 can then be moved from needle 1 to needle 3. To move the top two disks from needle 2 to needle 3, we use the same strategy as before. This time, we use needle 1 as the intermediate needle. Figure 17-7 shows a solution to the Tower of Hanoi problem with three disks.



**FIGURE 17-7** Solution to Tower of Hanoi problem with three disks

Let us now generalize this problem to the case of 64 disks. To begin, the first needle contains all 64 disks. Disk number 64 cannot be moved from needle 1 to needle 3 unless the top 63 disks are on the second needle. So first, we move the top 63 disks from needle 1 to needle 2, and then we move disk number 64 from needle 1 to needle 3. Now the top 63 disks are all on needle 2. To move disk number 63 from needle 2 to needle 3, we first move the top 62 disks from needle 2 to needle 1, and then we move disk number 63 from needle 2 to needle 3. To move the remaining 62 disks, we use a similar procedure. This discussion translates into the following recursive algorithm given in pseudocode. Suppose that needle 1 contains  $n$  disks, in which  $n \geq 1$ .

1. Move the top  $n - 1$  disks from needle 1 to needle 2, using needle 3 as the intermediate needle.
2. Move disk number  $n$  from needle 1 to needle 3.
3. Move the top  $n - 1$  disks from needle 2 to needle 3, using needle 1 as the intermediate needle.

This recursive algorithm translates into the following C++ function:

```
void moveDisks(int count, int needle1, int needle3, int needle2)
{
 if (count > 0)
 {
 moveDisks(count - 1, needle1, needle2, needle3);

 cout << "Move disk " << count << " from " << needle1
 << " to " << needle3 << "." << endl;

 moveDisks(count - 1, needle2, needle3, needle1);
 }
}
```

## Tower of Hanoi: Analysis

Let us determine how long it would take to move all 64 disks from needle 1 to needle 3. If needle 1 contains three disks, then the number of moves required to move all three disks from needle 1 to needle 3 is  $2^3 - 1 = 7$ . Similarly, if needle 1 contains 64 disks, then the number of moves required to move all 64 disks from needle 1 to needle 3 is  $2^{64} - 1$ . Because  $2^{10} = 1024 \approx 1000 = 10^3$ , we have:

$$2^{64} = 2^4 \times 2^{60} \approx 2^4 \times 10^{18} = 1.6 \times 10^{19}$$

The number of seconds in one year is approximately  $3.2 \times 10^7$ . Suppose the priests move one disk per second and they do not rest. Now:

$$1.6 \times 10^{19} = 5 \times 3.2 \times 10^{18} = 5 \times (3.2 \times 10^7) \times 10^{11} = (3.2 \times 10^7) \times (5 \times 10^{11})$$

The time required to move all 64 disks from needle 1 to needle 3 is roughly  $5 \times 10^{11}$  years. It is estimated that our universe is about 15 billion years old ( $1.5 \times 10^{10}$ ). Also,  $5 \times 10^{11} = 50 \times 10^{10} \approx 33 \times (1.5 \times 10^{10})$ . This calculation shows that our universe would last about 33 times as long as it already has.

Assume that a computer can generate 1 billion ( $10^9$ ) moves per second. Then the number of moves that the computer can generate in one year is:

$$(3.2 \times 10^7) \times 10^9 = 3.2 \times 10^{16}$$

So the computer time required to generate  $2^{64}$  moves is:

$$2^{64} \approx 1.6 \times 10^{19} = 1.6 \times 10^{16} \times 10^3 = (3.2 \times 10^{16}) \times 500$$

Thus, it would take about 500 years for the computer to generate  $2^{64}$  moves at the rate of 1 billion moves per second.

## Recursion or Iteration?

In Chapter 5, we designed a program to determine a desired Fibonacci number. That program used a loop to perform the calculation. In other words, the programs in Chapter 5 used an iterative control structure to repeat a set of statements. More formally, **iterative control structures** use a looping structure, such as `while`, `for`, or `do...while`, to repeat a set of statements. In Example 17-2, we designed a recursive function to calculate a Fibonacci number. From the examples here, it follows that in recursion, a set of statements is repeated by having the function call itself. Moreover, a selection control structure is used to control the repeated calls in recursion.

Similarly, in Chapter 9, we used an iterative control structure (a `for` loop) to determine the largest element in a list. In this chapter, we use recursion to determine the largest element in a list. In addition, this chapter began by designing a recursive function to find the factorial of a nonnegative integer. Using an iterative control structure, we can also write an algorithm to find the factorial of a nonnegative integer. The only reason to give a recursive solution to a factorial problem is to illustrate how recursion works.

We thus see that there are usually two ways to solve a particular problem—iteration and recursion. The obvious question is which method is better—iteration or recursion? There is no simple answer. In addition to the nature of the problem, the other key factor in determining the best solution method is efficiency.

Example 7-7 (Chapter 7), while tracing the execution of the problem, showed us that whenever a function is called, memory space for its formal parameters and (automatic) local variables is allocated. When the function terminates, that memory space is then deallocated.

This chapter, while tracing the execution of recursive functions, also shows us that every (recursive) call has its own set of parameters and (automatic) local variables. That is, every (recursive) call requires the system to allocate memory space for its formal parameters and (automatic) local variables and then deallocate the memory space when the function exits. Thus, there is overhead associated with executing a (recursive) function both in terms of memory space and computer time. Therefore, a recursive function executes more slowly than its iterative counterpart. On slower computers, especially those with limited memory space, the (slow) execution of a recursive function would be visible.

Today's computers, however, are fast and have inexpensive memory. Therefore, the execution of a recursion function is not noticeable. Keeping the power of today's computers

in mind, the choice between the two alternatives—iteration or recursion—depends on the nature of the problem. Of course, for problems such as mission control systems, efficiency is absolutely critical and, therefore, the efficiency factor would dictate the solution method.

As a general rule, if you think that an iterative solution is more obvious and easier to understand than a recursive solution, use the iterative solution, which would be more efficient. On the other hand, problems exist for which the recursive solution is more obvious or easier to construct, such as the Tower of Hanoi problem. (In fact, it turns out that it is difficult to construct an iterative solution for the Tower of Hanoi problem.) Keeping the power of recursion in mind, if the definition of a problem is inherently recursive, then you should consider a recursive solution.

## PROGRAMMING EXAMPLE: Converting a Number from Binary to Decimal

In Chapter 1, we explained that the language of a computer, called machine language, is a sequence of 0s and 1s. When you press the key **A** on the keyboard, 01000001 is stored in the computer. Also, you know that the collating sequence of **A** in the ASCII character set is 65. In fact, the binary representation of **A** is 01000001, and the decimal representation of **A** is 65.

The numbering system we use is called the decimal system, or base 10 system. The numbering system that the computer uses is called the binary system, or base 2 system. In this and the next programming example, we discuss how to convert a number from base 2 to base 10 and from base 10 to base 2.

**Binary to Decimal** To convert a number from base 2 to base 10, we first find the weight of each bit in the binary number. The weight of each bit in the binary number is assigned from right to left. The weight of the rightmost bit is 0. The weight of the bit immediately to the left of the rightmost bit is 1, the weight of the bit immediately to the left of it is 2, and so on. Consider the binary number 1001101. The weight of each bit is as follows:

|        |   |   |   |   |   |   |   |
|--------|---|---|---|---|---|---|---|
| Weight | 6 | 5 | 4 | 3 | 2 | 1 | 0 |
|        | 1 | 0 | 0 | 1 | 1 | 0 | 1 |

We use the weight of each bit to find the equivalent decimal number. For each bit, we multiply the bit by 2 to the power of its weight and then we add all of the numbers. For the above binary number, the equivalent decimal number is:

$$\begin{aligned}
 &1 \times 2^6 + 0 \times 2^5 + 0 \times 2^4 + 1 \times 2^3 + 1 \times 2^2 + 0 \times 2^1 + 1 \times 2^0 \\
 &= 64 + 0 + 0 + 8 + 4 + 0 + 1 \\
 &= 77
 \end{aligned}$$

To write a program that converts a binary number into the equivalent decimal number, we note two things: (1) the weight of each bit in the binary number must be known, and (2) the weight is assigned from right to left. Because we do not know in advance how many bits are in the binary number, we must process the bits from right to left. After processing a bit, we can add 1 to its weight, giving the weight of the bit immediately to the left of it. Also, each bit must be extracted from the binary number and multiplied by 2 to the power of its weight. To extract a bit, we can use the mod operator. Consider the following recursive algorithm, which is given in pseudocode.

```

if (binaryNumber > 0)
{
 bit = binaryNumber % 10; //extract the rightmost bit
 decimal = decimal + bit * power(2, weight);
 binaryNumber = binaryNumber / 10; //remove the rightmost
 //bit
 weight++;
 convert the binaryNumber into decimal
}

```

This algorithm assumes that the memory locations `decimal` and `weight` have been initialized to 0 before using the algorithm. This algorithm translates to the following C++ recursive function:

```

void binToDec(int binaryNumber, int& decimal, int& weight)
{
 int bit;

 if (binaryNumber > 0)
 {
 bit = binaryNumber % 10;
 decimal = decimal
 + bit * static_cast<int>(pow(2.0, weight));
 binaryNumber = binaryNumber / 10;
 weight++;
 binToDec(binaryNumber, decimal, weight);
 }
}

```

In this function, both `decimal` and `weight` are reference parameters. The actual parameters corresponding to these parameters are initialized to 0. After extracting the rightmost bit, this function updates the decimal number and the weight of the next bit. Suppose `decimalNumber` and `bitWeight` are `int` variables. Consider the following statements:

```

decimalNumber = 0;
bitWeight = 0;
binToDec(1101, decimalNumber, bitWeight);

```

Figure 17-8 traces the execution of the last statement, that is, `binToDec(1101, decimalNumber, bitWeight);`. It shows the content of the variables `decimalNumber` and `bitWeight` next to each function call.




FIGURE 17-8 Execution of `binToDec(1101, decimalNumber, bitWeight);`

In Figure 17-8, each down arrow represents the successive function call. Because the last statement of the function `binToDec` is a function call, after this statement executes, nothing happens. After the statement:

```
binToDec(1101, decimalNumber, bitWeight);
```

executes, the value of the variable `decimalNumber` is 13.

The following C++ program tests the function `binToDec`:

```
//*****
// Author: D. S. Malik
//
// Program: Binary to decimal
// This program uses recursion to find the decimal
// representation of a binary number.
//*****

#include <iostream>
#include <cmath>

using namespace std;

void binToDec(int binaryNumber, int& decimal, int& weight);

int main()
{
 int decimalNum;
 int bitWeight;
 int binaryNum;

 decimalNum = 0;
 bitWeight = 0;

 cout << "Enter number in binary: ";
 cin >> binaryNum;
 cout << endl;

 binToDec(binaryNum, decimalNum, bitWeight);
 cout << "Binary " << binaryNum << " = " << decimalNum
 << " decimal" << endl;

 return 0;
}

void binToDec(int binaryNumber, int& decimal, int& weight)
{
 int bit;

 if (binaryNumber > 0)
 {
 bit = binaryNumber % 10;
 decimal = decimal
 + bit * static_cast<int>(pow(2.0, weight));
 binaryNumber = binaryNumber / 10;
 }
}
```

```

 weight++;
 binToDec(binaryNumber, decimal, weight);
 }
}

```

**Sample Run:** In this sample run, the user input is shaded.

Enter a number in binary: 11010110

Binary 11010110 = 214 decimal

1  
7

## PROGRAMMING EXAMPLE: Converting a Number from Decimal to Binary

The previous programming example discussed and designed a program to convert a number from a binary representation to a decimal format—that is, from base 2 to base 10. This programming example discusses and designs a program that uses recursion to convert a nonnegative integer in decimal format—that is, base 10—into the equivalent binary number—that is, base 2. First, we define some terms.

Let  $x$  be an integer. We call the remainder of  $x$  after division by 2 the **rightmost bit** of  $x$ .

Thus, the rightmost bit of 33 is 1 because  $33 \% 2$  is 1, and the rightmost bit of 28 is 0 because  $28 \% 2$  is 0.

We first illustrate the algorithm to convert an integer in base 10 to the equivalent number in binary format, with the help of an example.

Suppose we want to find the binary representation of 35. First, we divide 35 by 2. The quotient is 17, and the remainder—that is, the rightmost bit of 35—is 1. Next, we divide 17 by 2. The quotient is 8, and the remainder—that is, the rightmost bit of 17—is 1. Next, we divide 8 by 2. The quotient is 4, and the remainder—that is, the rightmost bit of 8—is 0. We continue this process until the quotient becomes 0.

The rightmost bit of 35 cannot be printed until we have printed the rightmost bit of 17. The rightmost bit of 17 cannot be printed until we have printed the rightmost bit of 8, and so on. Thus, the binary representation of 35 is the binary representation of 17 (that is, the quotient of 35 after division by 2), followed by the rightmost bit of 35.

Thus, to convert an integer  $num$  in base 10 into the equivalent binary number, we first convert the quotient  $num / 2$  into an equivalent binary number and then append the rightmost bit of  $num$  to the binary representation of  $num / 2$ .

This discussion translates into the following recursive algorithm, in which `binary(num)` denotes the binary representation of  $num$ .

1. `binary(num) = num` if `num = 0`.
2. `binary(num) = binary(num / 2)` followed by `num % 2` if `num > 0`.

The following recursive function implements this algorithm:

```
void decToBin(int num, int base)
{
 if (num > 0)
 {
 decToBin(num / base, base);
 cout << num % base;
 }
}
```

Figure 17-9 traces the execution of the following statement:

`decToBin(13, 2);`

in which `num` is 13 and `base` is 2.




FIGURE 17-9 Execution of `decToBin(13, 2)`

Because the `if` statement in call 5 fails, this call does not print anything. The first output is produced by call 4, which prints 1; the second output is produced by call 3, which prints 1; the third output is produced by call 2, which prints 0; and the fourth output is produced by call 1, which prints 1. Thus, the output of the statement:

```
decToBin(13, 2);
```

is:

```
1101
```

The following C++ program tests the function `decToBin`.

```
//*****
// Author: D. S. Malik
//
// Program: Decimal to binary
// This program uses recursion to find the binary
// representation of a nonnegative integer.
//*****

#include <iostream>

using namespace std;

void decToBin(int num, int base);

int main()
{
 int decimalNum;
 int base;

 base = 2;

 cout << "Enter number in decimal: ";
 cin >> decimalNum;
 cout << endl;

 cout << "Decimal " << decimalNum << " = ";
 decToBin(decimalNum, base);
 cout << " binary" << endl;

 return 0;
}

void decToBin(int num, int base)
{
 if (num > 0)
 {
 decToBin(num / base, base);
 cout << num % base;
 }
}
```

**Sample Run:** In this sample run, the user input is shaded.

Enter a number in decimal: 57

Decimal 57 = 111001 binary

## QUICK REVIEW

---

1. The process of solving a problem by reducing it to smaller versions of itself is called recursion.
2. A recursive definition defines a problem in terms of smaller versions of itself.
3. Every recursive definition has one or more base cases.
4. A recursive algorithm solves a problem by reducing it to smaller versions of itself.
5. Every recursive algorithm has one or more base cases.
6. The solution to the problem in a base case is obtained directly.
7. A function is called recursive if it calls itself.
8. Recursive algorithms are implemented using recursive functions.
9. Every recursive function must have one or more base cases.
10. The general solution breaks the problem into smaller versions of itself.
11. The general case must eventually be reduced to a base case.
12. The base case stops the recursion.
13. While tracing a recursive function:
  - Logically, you can think of a recursive function as having an unlimited number of copies of itself.
  - Every call to a recursive function—that is, every recursive call—has its own code and its own set of parameters and local variables.
  - After completing a particular recursive call, control goes back to the calling environment, which is the previous call. The current (recursive) call must execute completely before control goes back to the previous call. The execution in the previous call begins from the point immediately following the recursive call.
14. A function is called directly recursive if it calls itself.
15. A function that calls another function and eventually results in the original function call is said to be indirectly recursive.
16. A recursive function in which the last statement executed is the recursive call is called a tail recursive function.

17. To design a recursive function, you must do the following:
  - a. Understand the problem requirements.
  - b. Determine the limiting conditions. For example, for a list, the limiting condition is the number of elements in the list.
  - c. Identify the base cases and provide a direct solution to each base case.
  - d. Identify the general cases and provide a solution to each general case in terms of smaller versions of itself.

## EXERCISES

1. Mark the following statements as true or false.
  - a. Every recursive definition must have one or more base cases.
  - b. Every recursive function must have one or more base cases.
  - c. The general case stops the recursion.
  - d. In the general case, the solution to the problem is obtained directly.
  - e. A recursive function always returns a value.
2. What is a base case?
3. What is a recursive case?
4. What is direct recursion?
5. What is indirect recursion?
6. What is tail recursion?
7. Consider the following recursive function:
 

```
int mystery(int number) //Line 1
{
 if (number == 0) //Line 2
 return number; //Line 3
 else //Line 4
 return (number + mystery(number - 1)); //Line 5
}
```

  - a. Identify the base case.
  - b. Identify the general case.
  - c. What valid values can be passed as parameters to the function `mystery`?
  - d. If `mystery(0)` is a valid call, what is its value? If not, explain why.
  - e. If `mystery(5)` is a valid call, what is its value? If not, explain why.
  - f. If `mystery(-3)` is a valid call, what is its value? If not, explain why.
8. Consider the following recursive function:
 

```
void funcRec(int u, char v) //Line 1
{
 if (u == 0) //Line 2
 cout << v; //Line 3
}
```

```

 else if (u == 1) //Line 4
 cout << static_cast<char>
 (static_cast<int>(v) + 1); //Line 5
 else //Line 6
 funcRec(u - 1, v); //Line 7
 }

```

Answer the following questions:

- a. Identify the base case.
- b. Identify the general case.
- c. What is the output of the following statement?

```
funcRec(5, 'A');
```

9. Consider the following recursive function:

```

void recFun(int x)
{
 if (x > 10)
 {
 recFun(x / 10);
 cout << x % 10 << endl;
 }
 else
 cout << x << endl;
}

```

What is the output of the following statements?

- a. `recFun(258);` b. `recFun(7);` c. `recFun(36);` d. `recFun(-85);`

10. Consider the following recursive function:

```

void recFun(int u)
{
 if (u == 1)
 cout << "Stop! ";
 else
 {
 cout << "Go ";
 recFun(u - 1);
 }
}

```

What is the output, if any, of the following statements?

- a. `recFun(7);` b. `recFun(3);` c. `recFun(-6);`

11. Consider the following recursive function:

```

void exercise(int x)
{
 if (x > 0 && x < 10)

```

```

 {
 cout << x << " ";
 exercise(x + 1);
 }
}

```

What is the output of the following statements?

a. `exercise(0);` b. `exercise(5);` c. `exercise(10);` d. `exercise(-5);`

12. Consider the following function:

```

int test(int x, int y)
{
 if (x == y)
 return x;
 else if (x > y)
 return (x + y);
 else
 return test(x + 1, y - 1);
}

```

What is the output of the following statements?

a. `cout << test(5, 10) << endl;`

b. `cout << test(3, 9) << endl;`

13. Consider the following function:

```

int func(int x)
{
 if (x == 0)
 return 2;
 else if (x == 1)
 return 3;
 else
 return (func(x - 1) + func(x - 2));
}

```

What is the output of the following statements?

a. `cout << func(0) << endl;`

b. `cout << func(1) << endl;`

c. `cout << func(2) << endl;`

d. `cout << func(5) << endl;`

14. Suppose that `intArray` is an array of integers, and `length` specifies the number of elements in `intArray`. Also, suppose that `low` and `high` are two integers such that  $0 \leq \text{low} < \text{length}$ ,  $0 \leq \text{high} < \text{length}$ , and  $\text{low} < \text{high}$ . That is, `low` and `high` are two indices in `intArray`. Write a recursive definition that reverses the elements in `intArray` between `low` and `high`.
15. Write a recursive algorithm to multiply two positive integers  $m$  and  $n$  using repeated addition. Specify the base case and the recursive case.

16. Consider the following problem: How many ways can a committee of four people be selected from a group of 10 people? There are many other similar problems in which you are asked to find the number of ways to select a set of items from a given set of items. The general problem can be stated as follows: Find the number of ways  $r$  different things can be chosen from a set of  $n$  items, in which  $r$  and  $n$  are nonnegative integers and  $r \leq n$ . Suppose  $C(n, r)$  denotes the number of ways  $r$  different things can be chosen from a set of  $n$  items. Then,  $C(n, r)$  is given by the following formula:

$$C(n, r) = \frac{n!}{r!(n-r)!}$$

in which the exclamation point denotes the factorial function. Moreover,  $C(n, 0) = C(n, n) = 1$ . It is also known that  $C(n, r) = C(n-1, r-1) + C(n-1, r)$ .

- a. Write a recursive algorithm to determine  $C(n, r)$ . Identify the base case(s) and the general case(s).
- b. Using your recursive algorithm, determine  $C(5, 3)$  and  $C(9, 4)$ .

## PROGRAMMING EXERCISES

---

1. Write a recursive function that takes as a parameter a nonnegative integer and generates the following pattern of stars. If the nonnegative integer is 4, then the pattern generated is:

```


**
*
*
**


```

Also, write a program that prompts the user to enter the number of lines in the pattern and uses the recursive function to generate the pattern. For example, specifying 4 as the number of lines generates the above pattern.

2. Write a recursive function to generate a pattern of stars, such as the following:

```
*
**

**
*
```

Also, write a program that prompts the user to enter the number of lines in the pattern and uses the recursive function to generate the pattern. For example, specifying 4 as the number of lines generates the above pattern.

3. Write a recursive function to generate the following pattern of stars:

```

 *
 * *
 * * *
 * * * *
 * * * *
 * * * *
* * * *

```

Also, write a program that prompts the user to enter the number of lines in the pattern and uses the recursive function to generate the pattern. For example, specifying 4 as the number of lines generates the above pattern.

4. Write a recursive function, `vowels`, that returns the number of vowels in a string. Also, write a program to test your function.
5. Write a recursive function named `sumSquares` that returns the sum of the squares of the numbers from 0 to `num`, in which `num` is a nonnegative `int` variable. Do not use global variables; use the appropriate parameters. Also write a program to test your function.
6. Write a recursive function that finds and returns the sum of the elements of an `int` array. Also, write a program to test your function.
7. A palindrome is a string that reads the same both forward and backward. For example, the string "madam" is a palindrome. Write a program that uses a recursive function to check whether a string is a palindrome. Your program must contain a value-returning recursive function that returns `true` if the string is a palindrome and `false` otherwise. Do not use any global variables; use the appropriate parameters.
8. Write a program that uses a recursive function to print a string backward. Do not use any global variables; use the appropriate parameters.
9. Write a recursive function, `reverseDigits`, that takes an integer as a parameter and returns the number with the digits reversed. Also, write a program to test your function.
10. Write a recursive function, `power`, that takes as parameters two integers  $x$  and  $y$  such that  $x$  is nonzero and returns  $x^y$ . You can use the following recursive definition to calculate  $x^y$ . If  $y \geq 0$ :

$$power(x, y) = \begin{cases} 1 & \text{if } y = 0 \\ x & \text{if } y = 1 \\ x \times power(x, y - 1) & \text{if } y > 1. \end{cases}$$

If  $y < 0$ :

$$\text{power}(x, y) = \frac{1}{\text{power}(x, -y)}.$$

Also, write a program to test your function.

11. **(Greatest Common Divisor)** Given two integers  $x$  and  $y$ , the following recursive definition determines the greatest common divisor of  $x$  and  $y$ , written  $\text{gcd}(x, y)$ .

$$\text{gcd}(x, y) = \begin{cases} x & \text{if } y = 0 \\ \text{gcd}(y, x \% y) & \text{if } y \neq 0 \end{cases}$$

*Note:* In this definition,  $\%$  is the mod operator.

Write a recursive function, `gcd`, that takes as parameters two integers and returns the greatest common divisor of the numbers. Also, write a program to test your function.

12. **(Ackermann's Function)** The Ackermann's function is defined as follows:

$$A(m, n) = \begin{cases} n + 1, & \text{if } m = 0 \\ A(m - 1, 1), & \text{if } n = 0 \\ A(m - 1, A(m, n - 1)), & \text{otherwise,} \end{cases}$$

in which  $m$  and  $n$  are nonnegative integers. Write a recursive function to implement Ackermann's function. Also write a program to test your function. What happens when you call the function with  $m = 4$  and  $n = 3$ ?

13. Write a recursive function to implement the recursive algorithm of Exercise 12 (reversing the elements of an array between two indices). Also, write a program to test your function.
14. Write a recursive function to implement the recursive algorithm of Exercise 15 (multiplying two positive integers using repeated addition). Also, write a program to test your function.
15. Write a recursive function to implement the recursive algorithm of Exercise 16 (determining the number of ways to select a set of things from a given set of things). Also, write a program to test your function.
16. **(Recursive Sequential Search)** The sequential search algorithm given in Chapter 9 is nonrecursive. Write and implement a recursive version of the sequential search algorithm.
17. **(Recursive Binary Search)** The binary search algorithm given in Chapter 10 is nonrecursive. Write and implement a recursive version of the binary search algorithm.
18. In the Programming Example, Converting a Number from Decimal to Binary, given in this chapter, you learned how to convert a decimal number into the

equivalent binary number. Two more number systems, octal (base 8) and hexadecimal (base 16), are of interest to computer scientists. In fact, in C++, you can instruct the computer to store a number in octal or hexadecimal.

The digits in the octal number system are 0, 1, 2, 3, 4, 5, 6, and 7. The digits in the hexadecimal number system are 0, 1, 2, 3, 4, 5, 6, 7, 8, 9, A, B, C, D, E, and F. So A in hexadecimal is 10 in decimal, B in hexadecimal is 11 in decimal, and so on.

The algorithm to convert a positive decimal number into an equivalent number in octal (or hexadecimal) is the same as discussed for binary numbers. Here, we divide the decimal number by 8 (for octal) and by 16 (for hexadecimal). Suppose  $a_b$  represents the number  $a$  to the base  $b$ . For example,  $75_{10}$  means 75 to the base 10 (that is decimal), and  $83_{16}$  means 83 to the base 16 (that is, hexadecimal). Then:

$$753_{10} = 1361_8$$

$$753_{10} = 2F1_{16}$$

The method of converting a decimal number to base 2, 8, or 16 can be extended to any arbitrary base. Suppose you want to convert a decimal number  $n$  into an equivalent number in base  $b$ , in which  $b$  is between 2 and 36. You then divide the decimal number  $n$  by  $b$  as in the algorithm for converting decimal to binary.

Note that the digits in, say, base 20, are 0, 1, 2, 3, 4, 5, 6, 7, 8, 9, A, B, C, D, E, F, G, H, I, and J.

Write a program that uses a recursive function to convert a number in decimal to a given base  $b$ , in which  $b$  is between 2 and 36. Your program should prompt the user to enter the number in decimal and in the desired base.

Test your program on the following data:

9098 and base 20

692 and base 2

753 and base 16

19. The function `sqrt` from the header file `cmath` can be used to find the square root of a nonnegative real number. Using Newton's method, you can also write an algorithm to find the square root of a nonnegative real number within a given tolerance as follows: Suppose  $x$  is a nonnegative real number,  $a$  is the approximate square root of  $x$ , and *epsilon* is the tolerance. Start with  $a = x$ .

- a. If  $|a^2 - x| \leq \text{epsilon}$ , then  $a$  is the square root of  $x$  within the tolerance; otherwise:
- b. Replace  $a$  with  $(a^2 + x) / (2a)$  and repeat Step a  
in which  $|a^2 - x|$  denotes the absolute value of  $a^2 - x$ .

Write a recursive function to implement this algorithm to find the square root of a nonnegative real number. Also, write a program to test your function.

*This page intentionally left blank*



# 18

## CHAPTER

# LINKED LISTS

IN THIS CHAPTER, YOU WILL:

- Learn about linked lists
- Become aware of the basic properties of linked lists
- Explore the insertion and deletion operations on linked lists
- Discover how to build and manipulate a linked list
- Learn how to construct a doubly linked list

You have already seen how data is organized and processed sequentially using an array called a *sequential list*. You have performed several operations on sequential lists, such as sorting, inserting, deleting, and searching. You also found that if data is not sorted, then searching for an item in the list can be very time consuming especially with large lists. Once the data is sorted, you can use a binary search and improve the search algorithm. However, in this case, insertion and deletion become time consuming especially with large lists, because these operations require data movement. Also, because the array size must be fixed during execution, new items can be added only if there is room. Thus, there are limitations on when you organize data in an array.

This chapter helps you to overcome some of these problems. Chapter 14 showed how memory (variables) can be dynamically allocated and deallocated using pointers. This chapter uses pointers to organize and process data in lists called **linked lists**. Recall that when data is stored in an array, memory for the components of the array is contiguous—that is, the blocks are allocated one after the other. However, as we will see, the components (called nodes) of a linked list need not be contiguous.

## Linked Lists

A linked list is a collection of components called **nodes**. Every node (except the last node) contains the address of the next node. Thus, every node in a linked list has two components: one to store the relevant information (that is, data) and one to store the address, called the **link**, of the next node in the list. The address of the first node in the list is stored in a separate location called the **head** or **first**. Figure 18-1 is a pictorial representation of a node.




FIGURE 18-1 Structure of a node

**Linked list:** A list of items, called **nodes**, in which the order of the nodes is determined by the address, called the **link**, stored in each node.

The list in Figure 18-2 is an example of a linked list.




FIGURE 18-2 Linked list

The arrow in each node indicates that the address of the node to which it is pointing is stored in that node. The down arrow in the last node indicates that this link field is **NULL**.

For a better understanding of this notation, suppose that the first node is at memory location 1200, and the second node is at memory location 1575. We thus have Figure 18-3.




FIGURE 18-3 Linked list and values of the links

The value of the head is 1200, the data part of the first node is 45, and the link component of the first node contains 1575, the address of the second node. If no confusion arises, then we will use the arrow notation whenever we draw the figure of a linked list.

For simplicity and for the ease of understanding and clarity, Figures 18-3 through 18-6 use decimal integers as the values of memory addresses. However, in computer memory, the memory addresses are in binary.

Because each node of a linked list has two components, we need to declare each node as a **class** or **struct**. The data type of each node depends on the specific application—that is, what kind of data is being processed. However, the link component of each node is a pointer. The data type of this pointer variable is the node type itself. For the previous linked list, the definition of the node is as follows. (Suppose that the data type is **int**.)

```
struct nodeType
{
 int info;
 nodeType *link;
};
```

The variable declaration is:

```
nodeType *head;
```

## Linked Lists: Some Properties

To help you better understand the concept of a linked list and a node, some important properties of linked lists are described next.

Consider the linked list in Figure 18-4.




FIGURE 18-4 Linked list with four nodes

This linked list has four nodes. The address of the first node is stored in the pointer `head`. Each node has two components: `info`, to store the info, and `link`, to store the address of the next node. For simplicity, we assume that `info` is of type `int`.


Suppose that the first node is at location 2000, the second node is at location 2800, the third node is at location 1500, and the fourth node is at location 3600. Therefore, the value of `head` is 2000, the value of the component `link` of the first node is 2800, the value of the component `link` of the second node is 1500, and so on. Also, the value 0 in the component `link` of the last node means that this value is `NULL`, which we indicate by drawing a down arrow. The number at the top of each node is the address of that node. The following table shows the values of `head` and some other nodes in the list shown in Figure 18-4.

|                                     | Value | Explanation                                                                                             |
|-------------------------------------|-------|---------------------------------------------------------------------------------------------------------|
| <code>head</code>                   | 2000  |                                                                                                         |
| <code>head-&gt;info</code>          | 17    | Because <code>head</code> is 2000 and the <code>info</code> of the node at location 2000 is 17          |
| <code>head-&gt;link</code>          | 2800  |                                                                                                         |
| <code>head-&gt;link-&gt;info</code> | 92    | Because <code>head-&gt;link</code> is 2800 and the <code>info</code> of the node at location 2800 is 92 |

Suppose that `current` is a pointer of the same type as the pointer `head`. Then, the statement:

```
current = head;
```

copies the value of `head` into `current` (see Figure 18-5).



**FIGURE 18-5** Linked list after the statement `current = head;` executes


Clearly, in Figure 18-5:

|                                        | Value |
|----------------------------------------|-------|
| <code>current</code>                   | 2000  |
| <code>current-&gt;info</code>          | 17    |
| <code>current-&gt;link</code>          | 2800  |
| <code>current-&gt;link-&gt;info</code> | 92    |

Now consider the statement:

```
current = current->link;
```

This statement copies the value of `current->link`, which is 2800, into `current`. Therefore, after this statement executes, `current` points to the second node in the list. (When working with linked lists, we typically use these types of statements to advance a pointer to the next node in the list.) See Figure 18-6.



**FIGURE 18-6** List after the statement `current = current->link;` executes

In Figure 18-6:

|                                        | Value |
|----------------------------------------|-------|
| <code>current</code>                   | 2800  |
| <code>current-&gt;info</code>          | 92    |
| <code>current-&gt;link</code>          | 1500  |
| <code>current-&gt;link-&gt;info</code> | 63    |

Finally, note that in Figure 18-6:

|                                                          | Value             |
|----------------------------------------------------------|-------------------|
| <code>head-&gt;link-&gt;link</code>                      | 1500              |
| <code>head-&gt;link-&gt;link-&gt;info</code>             | 63                |
| <code>head-&gt;link-&gt;link-&gt;link</code>             | 3600              |
| <code>head-&gt;link-&gt;link-&gt;link-&gt;info</code>    | 45                |
| <code>current-&gt;link-&gt;link</code>                   | 3600              |
| <code>current-&gt;link-&gt;link-&gt;info</code>          | 45                |
| <code>current-&gt;link-&gt;link-&gt;link</code>          | 0 (that is, NULL) |
| <code>current-&gt;link-&gt;link-&gt;link-&gt;info</code> | Does not exist    |

From now on, when working with linked lists, we will use only the arrow notation.

### TRAVERSING A LINKED LIST

The basic operations of a linked list are as follows: search the list to determine whether a particular item is in the list, insert an item in the list, and delete an item from the list.

These operations require the list to be traversed. That is, given a pointer to the first node of the list, we must step through the nodes of the list.

Suppose that the pointer `head` points to the first node in the list, and the link of the last node is `NULL`. We cannot use the pointer `head` to traverse the list because if we use `head` to traverse the list, we would lose the nodes of the list. This problem occurs because the links are in only one direction. The pointer `head` contains the address of the first node, the first node contains the address of the second node, the second node contains the address of the third node, and so on. If we move `head` to the second node, the first node is lost (unless we save a pointer to this node). If we keep advancing `head` to the next node, we will lose all of the nodes of the list (unless we save a pointer to each node before advancing `head`, which is impractical because it would require additional computer time and memory space to maintain the list).

Therefore, we always want `head` to point to the first node. It now follows that we must traverse the list using another pointer of the same type. Suppose that `current` is a pointer of the same type as `head`. The following code traverses the list:

```
current = head;

while (current != NULL)
{
 //Process the current node
 current = current->link;
}
```

For example, suppose that `head` points to a linked list of numbers. The following code outputs the data stored in each node:

```
current = head;

while (current != NULL)
{
 cout << current->info << " ";
 current = current->link;
}
```

## ITEM INSERTION AND DELETION

This section discusses how to insert an item into, and delete an item from, a linked list. Consider the following definition of a node. (For simplicity, we assume that the `info` type is `int`. The next section, which discusses linked lists as an abstract data type (ADT) using templates, uses the generic definition of a node.)

```
struct nodeType
{
 int info;
 nodeType *link;
};
```

We will use the following variable declaration:

```
nodeType *head, *p, *q, *newNode;
```

INSERTION

Consider the linked list shown in Figure 18-7.




FIGURE 18-7 Linked list before item insertion

Suppose that **p** points to the node with **info 65**, and a new node with **info 50** is to be created and inserted after **p**. Consider the following statements:

```
newNode = new nodeType; //create newNode
newNode->info = 50; //store 50 in the new node
newNode->link = p->link;
p->link = newNode;
```

Table 18-1 shows the effect of these statements.


TABLE 18-1 Inserting a Node in a Linked List

| Statement                                   | Effect |
|---------------------------------------------|--------|
| <code>newNode = new nodeType;</code>        |        |
| <code>newNode-&gt;info = 50;</code>         |        |
| <code>newNode-&gt;link = p-&gt;link;</code> |        |
| <code>p-&gt;link = newNode;</code>          |        |

Note that the sequence of statements to insert the node is very important because to insert `newNode` in the list, we use only one pointer, `p`, to adjust the links of the node of the linked list. Suppose that we reverse the sequence of the statements and execute the statements in the following order:

```
p->link = newNode;
newNode->link = p->link;
```


Figure 18-8 shows the resulting list after these statements execute.



**FIGURE 18-8** List after the execution of the statement `p->link = newNode;` followed by the execution of the statement `newNode->link = p->link;`

From Figure 18-8, it is clear that `newNode` points back to itself and the remainder of the list is lost.

Using two pointers, we can simplify the insertion code somewhat. Suppose `q` points to the node with `info` 34 (see Figure 18-9).



**FIGURE 18-9** List with pointers `p` and `q`

The following statements insert `newNode` between `p` and `q`.



```
newNode->link = q;
p->link = newNode;
```

The order in which these statements execute does not matter. To illustrate this, suppose that we execute the statements in the following order:

```
p->link = newNode;
newNode->link = q;
```

Table 18-2 shows the effect of these statements.

TABLE 18-2 Inserting a Node in a Linked List Using Two Pointers

| Statement                          | Effect                                                                             |
|------------------------------------|------------------------------------------------------------------------------------|
| <code>p-&gt;link = newNode;</code> |  |
| <code>newNode-&gt;link = q;</code> |  |

## Deletion

Consider the linked list shown in Figure 18-10.




FIGURE 18-10 Node to be deleted is with info 34

Suppose that the node with info 34 is to be deleted from the list. The following statement removes the node from the list.

`p->link = p->link->link;`

Figure 18-11 shows the resulting list after the preceding statement executes.




FIGURE 18-11 List after the statement `newNode->link = q;` executes




From Figure 18-11, it is clear that the node with info 34 is removed from the list. However, the memory is still occupied by this node, and this memory is inaccessible; that is, this node is dangling. To deallocate the memory, we need a pointer to this node. The

following statements delete the node from the list and deallocate the memory occupied by this node.

```
q = p->link;
p->link = q->link;
delete q;
```

Table 18-3 shows the effect of these statements.

**TABLE 18-3** Deleting a Node from a Linked List

| Statement                             | Effect                                                                             |
|---------------------------------------|------------------------------------------------------------------------------------|
| <code>q = p-&gt;link;</code>          |  |
| <code>p-&gt;link = q-&gt;link;</code> |  |
| <code>delete q;</code>                |  |

## Building a Linked List

Now that we know how to insert a node in a linked list, let us see how to build a linked list. First, we consider a linked list in general. If the data we read is unsorted, the linked list will be unsorted. Such a list can be built in two ways: forward and backward. In the forward manner, a new node is always inserted at the end of the linked list. In the backward manner, a new node is always inserted at the beginning of the list. We will consider both cases.

### BUILDING A LINKED LIST FORWARD

Suppose that the nodes are in the usual `info-link` form, and `info` is of type `int`. Let us assume that we process the following data:

2 15 8 24 34

We need three pointers to build the list: one to point to the first node in the list, which cannot be moved; one to point to the last node in the list; and one to create the new node. Consider the following variable declaration:

```
nodeType *first, *last, *newNode;
int num;
```

Suppose that `first` points to the first node in the list. Initially, the list is empty, so both `first` and `last` are `NULL`. Thus, we must have the statements:

```
first = NULL;
last = NULL;
```

to initialize `first` and `last` to `NULL`.

Next, consider the following statements:

```
1 cin >> num; //read and store a number in num
2 newNode = new nodeType; //allocate memory of type nodeType
 //and store the address of the
 //allocated memory in newNode
3 newNode->info = num; //copy the value of num into the
 //info field of newNode
4 newNode->link = NULL; //initialize the link field of
 //newNode to NULL
5 if (first == NULL) //if first is NULL, the list is empty;
 //make first and last point to newNode
 {
5a first = newNode;
5b last = newNode;
 }
6 else //list is not empty
 {
6a last->link = newNode; //insert newNode at the end of the list
6b last = newNode; //set last so that it points to the
 //actual last node in the list
 }
```

Let us now execute these statements. Initially, both `first` and `last` are `NULL`. Therefore, we have the list as shown in Figure 18-12.




FIGURE 18-12 Empty list

After statement 1 executes, `num` is 2. Statement 2 creates a node and stores the address of that node in `newNode`. Statement 3 stores 2 in the `info` field of `newNode`, and statement 4 stores `NULL` in the link field of `newNode` (see Figure 18-13).






FIGURE 18-13 `newNode` with `info` 2

Because `first` is `NULL`, we execute statements 5a and 5b. Figure 18-14 shows the resulting list.




**FIGURE 18-14** List after inserting `newNode` in it

We now repeat statements 1 through 6b. After statement 1 executes, `num` is 15. Statement 2 creates a node and stores the address of this node in `newNode`. Statement 3 stores 15 in the `info` field of `newNode`, and statement 4 stores `NULL` in the link field of `newNode` (see Figure 18-15).




**FIGURE 18-15** List and `newNode` with `info` 15

Because `first` is not `NULL`, we execute statements 6a and 6b. Figure 18-16 shows the resulting list.



**FIGURE 18-16** List after inserting `newNode` at the end

We now repeat statements 1 through 6b three more times. Figure 18-17 shows the resulting list.



**FIGURE 18-17** List after inserting 8, 24, and 34

To build the linked list, we can put the previous statements in a loop and execute the loop until certain conditions are met. We can, in fact, write a C++ function to build a linked list.

Suppose that we read a list of integers ending with -999. The following function, `buildListForward`, builds a linked list (in a forward manner) and returns the pointer of the built list.

```

nodeType* buildListForward()
{
 nodeType *first, *newNode, *last;
 int num;

 cout << "Enter a list of integers ending with -999."
 << endl;
 cin >> num;
 first = NULL;

 while (num != -999)
 {
 newNode = new nodeType;
 newNode->info = num;
 newNode->link = NULL;

 if (first == NULL)
 {
 first = newNode;
 last = newNode;
 }
 else
 {
 last->link = newNode;
 last = newNode;
 }
 cin >> num;
 } //end while

 return first;
} //end buildListForward

```

## BUILDING A LINKED LIST BACKWARD

Now we consider the case of building a linked list backward. For the previously given data—2, 15, 8, 24, and 34—the linked list is as shown in Figure 18-18.




FIGURE 18-18 List after building it backward

Because the new node is always inserted at the beginning of the list, we do not need to know the end of the list, so the pointer `last` is not needed. Also, after inserting the new node at the beginning, the new node becomes the first node in the list. Thus, we need to update the value of the pointer `first` to correctly point to the first node in the list. We see, then, that we need only two pointers to build the linked list: one to point to the list and one to create the new node. Because initially the list is empty, the pointer `first` must be initialized to `NULL`. In pseudocode, the algorithm is:

1. Initialize `first` to `NULL`.
2. For each item in the list,
  - a. Create the new node, `newNode`.
  - b. Store the item in `newNode`.
  - c. Insert `newNode` before `first`.
  - d. Update the value of the pointer `first`.

The following C++ function builds the linked list backward and returns the pointer of the built list.

```

nodeType* buildListBackward()
{
 nodeType *first, *newNode;
 int num;

 cout << "Enter a list of integers ending with -999."
 << endl;
 cin >> num;
 first = NULL;

 while (num != -999)
 {
 newNode = new nodeType; //create a node
 newNode->info = num; //store the data in newNode
 newNode->link = first; //put newNode at the beginning
 }
}

```

```

 first = newNode;
 cin >> num;
 }

 return first;
} //end buildListBackward

```

*//of the list*  
*//update the head pointer of*  
*//the list, that is, first*  
*//read the next number*

## Linked List as an ADT

The previous sections taught you the basic properties of linked lists and how to construct and manipulate them. Because a linked list is a very important data structure, rather than discuss specific lists such as a list of integers or a list of strings, this section discusses linked lists as an abstract data type (ADT). Using templates, this section gives a generic definition of linked lists, which is then used in the next section and later in this book. The programming example at the end of this chapter also uses this generic definition of linked lists.

The basic operations on linked lists are:

1. Initialize the list.
2. Determine whether the list is empty.
3. Print the list.
4. Find the length of the list.
5. Destroy the list.
6. Retrieve the **info** contained in the first node.
7. Retrieve the **info** contained in the last node.
8. Search the list for a given item.
9. Insert an item in the list.
10. Delete an item from the list.
11. Make a copy of the linked list.

In general, there are two types of linked lists—sorted lists, whose elements are arranged according to some criteria, and unsorted lists, whose elements are in no particular order. The algorithms to implement the operations search, insert, and remove slightly differ for sorted and unsorted lists. Therefore, we will define the **class** `linkedListType` to implement the basic operations on a linked list as an **abstract class**. Using the principle of inheritance, we, in fact, will derive two **classes**—`unorderedLinkedList` and `orderedLinkedList`—from the **class** `linkedListType`.

Objects of the **class** `unorderedLinkedList` would arrange list elements in no particular order, that is, these lists may not be sorted. On the other hand, objects of the **class** `orderedLinkedList` would arrange elements according to some comparison criteria, usually less than or equal to. That is, these lists will be in ascending order. Moreover, after

inserting an element into or removing an element from an ordered list, the resulting list will be ordered.

If a linked list is unordered, we can insert a new item at either the end or the beginning. Furthermore, you can build such a list in either a forward manner or a backward manner. The function `buildListForward` inserts the new item at the end, whereas the function `buildListBackward` inserts the new item at the beginning. To accommodate both operations, we will write two functions: `insertFirst` to insert the new item at the beginning of the list and `insertLast` to insert the new item at the end of the list. Also, to make the algorithms more efficient, we will use two pointers in the list: `first`, which points to the first node in the list, and `last`, which points to the last node in the list.

## Structure of Linked List Nodes

Recall that each node of a linked list must store the data as well as the address for the next node in the list (except the last node of the list). Therefore, the node has two member variables. To simplify operations such as insert and delete, we define the class to implement the node of a linked list as a `struct`. The definition of the `struct` `nodeType` is:

```
//Definition of the node

template <class Type>
struct nodeType
{
 Type info;
 nodeType<Type> *link;
};
```

### NOTE

The class to implement the node of a linked list is declared as a `struct`. Programming Exercise 9, at the end of this chapter, asks you to redefine the class to implement the nodes of a linked list so that the member variables of the `class` `nodeType` are `private`.

## Member Variables of the `class` `linkedListType`

To maintain a linked list, we use two pointers: `first` and `last`. The pointer `first` points to the first node in the list, and `last` points to the last node in the list. We also keep a count of the number of nodes in the list. Therefore, the `class` `linkedListType` has three member variables, as follows:

```
protected:
 int count; //variable to store the number of
 //elements in the list
 nodeType<Type> *first; //pointer to the first node
 //of the list
 nodeType<Type> *last; //pointer to the last node
 //of the list
```

## Linked List Iterators

One of the basic operations performed on a list is to process each node of the list. This requires the list to be traversed, starting at the first node. Moreover, a specific application requires each node to be processed in a very specific way. A common technique to accomplish this is to provide an iterator. So what is an iterator? An **iterator** is an object that produces each element of a container, such as a linked list, one element at a time. The two most common operations on iterators are ++ (the increment operator) and \* (the dereferencing operator). The increment operator advances the iterator to the next node in the list, and the dereferencing operator returns the info of the current node.

Note that an iterator is an object. So we need to define a class, which we will call `LinkedListIterator`, to create iterators to objects of the `class` `LinkedListType`. The iterator class would have one member variable pointing to (the current) node.

```
template <class Type>
class LinkedListIterator
{
public:
 LinkedListIterator();
 //Default constructor.
 //Postcondition: current = NULL;

 LinkedListIterator(nodeType<Type> *ptr);
 //Constructor with a parameter.
 //Postcondition: current = ptr;

 Type operator*();
 //Function to overload the dereferencing operator *.
 //Postcondition: Returns the info contained in the node.

 LinkedListIterator<Type> operator++();
 //Overload the pre-increment operator.
 //Postcondition: The iterator is advanced to the next
 // node.

 bool operator==(const LinkedListIterator<Type>& right) const;
 //Overload the equality operator.
 //Postcondition: Returns true if this iterator is equal to
 // the iterator specified by right,
 // otherwise it returns false.

 bool operator!=(const LinkedListIterator<Type>& right) const;
 //Overload the not equal to operator.
 //Postcondition: Returns true if this iterator is not equal
 // to the iterator specified by right,
 // otherwise it returns false.

private:
 nodeType<Type> *current; //pointer to point to the current
 //node in the linked list
};
```

Figure 18-19 shows the UML class diagram of the `class` `linkedListIterator`.




FIGURE 18-19 UML class diagram of the `class` `linkedListIterator`

The definitions of the functions of the `class` `linkedListIterator` are:

```

template <class Type>
linkedListIterator<Type>::linkedListIterator()
{
 current = NULL;
}

template <class Type>
linkedListIterator<Type>::
 linkedListIterator(nodeType<Type> *ptr)
{
 current = ptr;
}

template <class Type>
Type linkedListIterator<Type>::operator* ()
{
 return current->info;
}

template <class Type>
linkedListIterator<Type> linkedListIterator<Type>::operator++()
{
 current = current->link;

 return *this;
}

template <class Type>
bool linkedListIterator<Type>::operator==
 (const linkedListIterator<Type>& right) const
{
 return (current == right.current);
}

```

```

template <class Type>
bool linkedListIterator<Type>::operator!=
 (const linkedListIterator<Type>& right) const
{
 return (current != right.current);
}

```

Now that we have defined the classes to implement the node of a linked list and an iterator to a linked list, next we describe the `class` `linkedListType` to implement the basic properties of a linked list.

The following abstract class defines the basic properties of a linked list as an ADT.

```

template <class Type>
class linkedListType
{
public:
 const linkedListType<Type>& operator=
 (const linkedListType<Type>&);
 //Overload the assignment operator.

 void initializeList();
 //Initialize the list to an empty state.
 //Postcondition: first = NULL, last = NULL, count = 0;

 bool isEmptyList() const;
 //Function to determine whether the list is empty.
 //Postcondition: Returns true if the list is empty,
 // otherwise it returns false.

 void print() const;
 //Function to output the data contained in each node.
 //Postcondition: none

 int length() const;
 //Function to return the number of nodes in the list.
 //Postcondition: The value of count is returned.

 void destroyList();
 //Function to delete all the nodes from the list.
 //Postcondition: first = NULL, last = NULL, count = 0;

 Type front() const;
 //Function to return the first element of the list.
 //Precondition: The list must exist and must not be
 // empty.
 //Postcondition: If the list is empty, the program
 // terminates; otherwise, the first
 // element of the list is returned.

 Type back() const;
 //Function to return the last element of the list.
 //Precondition: The list must exist and must not be
 // empty.
 //Postcondition: If the list is empty, the program
 // terminates; otherwise, the last
 // element of the list is returned.
}

```

```

virtual bool search(const Type& searchItem) const = 0;
 //Function to determine whether searchItem is in the list.
 //Postcondition: Returns true if searchItem is in the
 // list, otherwise the value false is
 // returned.

virtual void insertFirst(const Type& newItem) = 0;
 //Function to insert newItem at the beginning of the list.
 //Postcondition: first points to the new list, newItem is
 // inserted at the beginning of the list,
 // last points to the last node in the list,
 // and count is incremented by 1.

virtual void insertLast(const Type& newItem) = 0;
 //Function to insert newItem at the end of the list.
 //Postcondition: first points to the new list, newItem
 // is inserted at the end of the list,
 // last points to the last node in the list,
 // and count is incremented by 1.

virtual void deleteNode(const Type& deleteItem) = 0;
 //Function to delete deleteItem from the list.
 //Postcondition: If found, the node containing
 // deleteItem is deleted from the list.
 // first points to the first node, last
 // points to the last node of the updated
 // list, and count is decremented by 1.

linkedListIterator<Type> begin();
 //Function to return an iterator at the beginning of the
 //linked list.
 //Postcondition: Returns an iterator such that current is
 // set to first.

linkedListIterator<Type> end();
 //Function to return an iterator one element past the
 //last element of the linked list.
 //Postcondition: Returns an iterator such that current is
 // set to NULL.

linkedListType();
 //default constructor
 //Initializes the list to an empty state.
 //Postcondition: first = NULL, last = NULL, count = 0;

linkedListType(const linkedListType<Type>& otherList);
 //copy constructor

~linkedListType();
 //destructor
 //Deletes all the nodes from the list.
 //Postcondition: The list object is destroyed.

protected:
 int count; //variable to store the number of
 //elements in the list

```

```

nodeType<Type> *first; //pointer to the first node of the list
nodeType<Type> *last; //pointer to the last node of the list

private:
 void copyList(const linkedListType<Type>& otherList);
 //Function to make a copy of otherList.
 //Postcondition: A copy of otherList is created and
 // assigned to this list.
};

```

Figure 18-20 shows the UML class diagram of the `class` `linkedListType`.



FIGURE 18-20 UML class diagram of the `class` `linkedListType`

Note that typically, in the UML diagram, the name of an abstract class and abstract function is shown in italics.

The instance variables `first` and `last`, as defined earlier, of the `class` `linkedListType` are `protected`, not `private`, because as noted previously, we will derive the `classes` `unorderedLinkedList` and `orderedLinkedList` from the `class` `linkedListType`. Because each of the `classes` `unorderedLinkedList`

and `orderedLinkedList` will provide separate definitions of the functions `search`, `insertFirst`, `insertLast`, and `deleteNode` and because these functions would access the instance variable, to provide direct access to the instance variables, the instance variables are declared as `protected`.

The definition of the `class linkedListType` includes a member function to overload the assignment operator. For classes that include pointer data members, the assignment operator must be explicitly overloaded (see Chapters 14 and 15). For the same reason, the definition of the class also includes a copy constructor.

Notice that the definition of the `class linkedListType` contains the member function `copyList`, which is declared as a `private` member. This is due to the fact that this function is used only to implement the copy constructor and overload the assignment operator.

Next, we write the definitions of the nonabstract functions of the `class LinkedListClass`.

The list is empty if `first` is `NULL`. Therefore, the definition of the function `isEmptyList` to implement this operation is as follows:

```
template <class Type>
bool linkedListType<Type>::isEmptyList() const
{
 return (first == NULL);
}
```

## DEFAULT CONSTRUCTOR

The default constructor, `linkedListType`, is quite straightforward. It simply initializes the list to an empty state. Recall that when an object of the `linkedListType` type is declared and no value is passed, the default constructor is executed automatically.

```
template <class Type>
linkedListType<Type>::linkedListType() //default constructor
{
 first = NULL;
 last = NULL;
 count = 0;
}
```

## DESTROY THE LIST

The function `destroyList` deallocates the memory occupied by each node. We traverse the list starting from the first node and deallocate the memory by calling the operator `delete`. We need a temporary pointer to deallocate the memory. Once the entire list is destroyed, we must set the pointers `first` and `last` to `NULL` and `count` to 0.

```
template <class Type>
void linkedListType<Type>::destroyList()
{
 nodeType<Type> *temp; //pointer to deallocate the memory
 //occupied by the node
}
```

```

while (first != NULL) //while there are nodes in the list
{
 temp = first; //set temp to the current node
 first = first->link; //advance first to the next node
 delete temp; //deallocate the memory occupied by temp
}

last = NULL; //initialize last to NULL; first has already
 //been set to NULL by the while loop
count = 0;
}

```

## INITIALIZE THE LIST

The function `initializeList` initializes the list to an empty state. Note that the default constructor or the copy constructor has already initialized the list when the list object was declared. This operation, in fact, reinitializes the list to an empty state, so it must delete the nodes (if any) from the list. This task can be accomplished by using the `destroyList` operation, which also resets the pointers `first` and `last` to `NULL` and sets `count` to 0.

```

template <class Type>
void linkedListType<Type>::initializeList()
{
 destroyList(); //if the list has any nodes, delete them
}

```

## Print the List

The member function `print` prints the data contained in each node. To do so, we must traverse the list, starting at the first node. Because the pointer `first` always points to the first node in the list, we need another pointer to traverse the list. (If we use `first` to traverse the list, the entire list will be lost.)

```

template <class Type>
void linkedListType<Type>::print() const
{
 nodeType<Type> *current; //pointer to traverse the list

 current = first; //set current so that it points to
 //the first node
 while (current != NULL) //while more data to print
 {
 cout << current->info << " ";
 current = current->link;
 }
} //end print

```

## Length of a List

The length of a linked list (that is, how many nodes are in the list) is stored in the variable `count`. Therefore, this function returns the value of this variable:

```
template <class Type>
int linkedListType<Type>::length() const
{
 return count;
}
```

## Retrieve the Data of the First Node

The function `front` returns the `info` contained in the first node, and its definition is straightforward:

```
template <class Type>
Type linkedListType<Type>::front() const
{
 assert(first != NULL);

 return first->info; //return the info of the first node
} //end front
```

Notice that if the list is empty, the `assert` statement terminates the program. Therefore, before calling this function, check to see whether the list is nonempty.

## Retrieve the Data of the Last Node

The function `back` returns the `info` contained in the last node, and its definition is straightforward:

```
template <class Type>
Type linkedListType<Type>::back() const
{
 assert(last != NULL);

 return last->info; //return the info of the last node
} //end back
```

Notice that if the list is empty, the `assert` statement terminates the program. Therefore, before calling this function, check to see whether the list is nonempty.

## Begin and End

The function `begin` returns an iterator to the first node in the linked list, and the function `end` returns an iterator to one past the last node in the linked list. Their definitions are:

```
template <class Type>
linkedListIterator<Type> linkedListType<Type>::begin()
{
 linkedListIterator<Type> temp(first);

 return temp;
}
```

```

template <class Type>
LinkedListIterator<Type> LinkedListType<Type>::end()
{
 LinkedListIterator<Type> temp(NULL);

 return temp;
}

```

## Copy the List

The function `copyList` makes an identical copy of a linked list. Therefore, we traverse the list to be copied, starting at the first node. Corresponding to each node in the original list, we:

- Create a node, and call it `newNode`.
- Copy the info of the node (in the original list) into `newNode`.
- Insert `newNode` at the end of the list being created.

The definition of the function `copyList` is:

```

template <class Type>
void LinkedListType<Type>::copyList
 (const LinkedListType<Type>& otherList)
{
 NodeType<Type> *newNode; //pointer to create a node
 NodeType<Type> *current; //pointer to traverse the list

 if (first != NULL) //if the list is nonempty, make it empty
 destroyList();

 if (otherList.first == NULL) //otherList is empty
 {
 first = NULL;
 last = NULL;
 count = 0;
 }
 else
 {
 current = otherList.first; //current points to the
 //list to be copied
 count = otherList.count;

 //copy the first node
 first = new NodeType<Type>; //create the node
 first->info = current->info; //copy the info
 first->link = NULL; //set the link field of
 //the node to NULL
 last = first; //make last point to the
 //first node
 current = current->link; //make current point to
 //the next node
 }
}

```

```

 //copy the remaining list
 while (current != NULL)
 {
 newNode = new nodeType<Type>; //create a node
 newNode->info = current->info; //copy the info
 newNode->link = NULL; //set the link of
 //newNode to NULL
 last->link = newNode; //attach newNode after last
 last = newNode; //make last point to
 //the actual last node
 current = current->link; //make current point
 //to the next node
 } //end while
 } //end else
} //end copyList

```

## Destructor

The destructor deallocates the memory occupied by the nodes of a list when the class object goes out of scope. Because memory is allocated dynamically, resetting the pointers `first` and `last` does not deallocate the memory occupied by the nodes in the list. We must traverse the list, starting at the first node, and delete each node in the list. The list can be destroyed by calling the function `destroyList`. Therefore, the definition of the destructor is:

```

template <class Type>
linkedListType<Type>::~linkedListType() //destructor
{
 destroyList();
}

```

## Copy Constructor

Because the `class` `linkedListType` contains pointer data members, the definition of this class contains the copy constructor. Recall that if a formal parameter is a value parameter, the copy constructor provides the formal parameter with its own copy of the data. The copy constructor also executes when an object is declared and initialized using another object. (For more information, see Chapter 14.)

The copy constructor makes an identical copy of the linked list. This can be done by calling the function `copyList`. Because the function `copyList` checks whether the original is empty by checking the value of `first`, we must first initialize the pointer `first` to `NULL` before calling the function `copyList`.

The definition of the copy constructor is:

```

template <class Type>
linkedListType<Type>::linkedListType
 (const linkedListType<Type>& otherList)
{
 first = NULL;
 copyList(otherList);
} //end copy constructor

```

## Overloading the Assignment Operator

The definition of the function to overload the assignment operator for the `class` `linkedListType` is similar to the definition of the copy constructor. We give its definition for the sake of completeness.

```
//overload the assignment operator
template <class Type>
const linkedListType<Type>& linkedListType<Type>::operator=
 (const linkedListType<Type>& otherList)
{
 if (this != &otherList) //avoid self-copy
 {
 copyList(otherList);
 }//end else

 return *this;
}
```

1  
8

## Unordered Linked Lists

As described in the preceding section, we derive the `class` `unorderedLinkedList` from the abstract `class` `linkedListType` and implement the operations `search`, `insertFirst`, `insertLast`, and `deleteNode`.

The following class defines an unordered linked list as an ADT.

```
template <class Type>
class unorderedLinkedList: public linkedListType<Type>
{
public:
 bool search(const Type& searchItem) const;
 //Function to determine whether searchItem is in the list.
 //Postcondition: Returns true if searchItem is in the
 // list, otherwise the value false is
 // returned.

 void insertFirst(const Type& newItem);
 //Function to insert newItem at the beginning of the list.
 //Postcondition: first points to the new list, newItem is
 // inserted at the beginning of the list,
 // last points to the last node in the
 // list, and count is incremented by 1.

 void insertLast(const Type& newItem);
 //Function to insert newItem at the end of the list.
 //Postcondition: first points to the new list, newItem
 // is inserted at the end of the list,
 // last points to the last node in the
 // list, and count is incremented by 1.


 void deleteNode(const Type& deleteItem);
 //Function to delete deleteItem from the list.
 //Postcondition: If found, the node containing
```

```

// deleteItem is deleted from the list.
// first points to the first node, last
// points to the last node of the updated
// list, and count is decremented by 1.
};

```

Figure 18-21 shows a UML class diagram of the `class unorderedLinkedList` and the inheritance hierarchy.



**FIGURE 18-21** UML class diagram of the `class unorderedLinkedList` and inheritance hierarchy

Next, we give the definitions of the member functions of the `class unorderedLinkedList`.

## Search the List

The member function `search` searches the list for a given item. If the item is found, it returns `true`; otherwise, it returns `false`. Because a linked list is not a random-access data structure, we must sequentially search the list, starting from the first node.

This function has the following steps:

1. Compare the search item with the current node in the list. If the `info` of the current node is the same as the search item, stop the search; otherwise, make the next node the current node.
2. Repeat Step 1 until either the item is found or no more data is left in the list to compare with the search item.

```

template <class Type>
bool unorderedLinkedList<Type>::
 search(const Type& searchItem) const
{
 nodeType<Type> *current; //pointer to traverse the list
 bool found = false;
 current = first; //set current to point to the first
 //node in the list

```

```

while (current != NULL && !found) //search the list
 if (current->info == searchItem) //searchItem is found
 found = true;
 else
 current = current->link; //make current point to
 //the next node

return found;
} //end search

```

**NOTE**

The function `search` can also be written as:

```

template <class Type>
bool unorderedLinkedList<Type>::search(const Type& searchItem)
 const
{
 nodeType<Type> *current; //pointer to traverse the list

 current = first; //set current to point to the first
 //node in the list

 while (current != NULL) //search the list
 if (current->info == searchItem) //searchItem is found
 return true;
 else
 current = current->link; //make current point to
 //the next node

 return false; //searchItem is not in the list, return false
} //end search

```

## Insert the First Node

The function `insertFirst` inserts the new item at the beginning of the list—that is, before the node pointed to by `first`. The steps needed to implement this function are as follows:

1. Create a new node.
2. Store the new item in the new node.
3. Insert the node before `first`.
4. Increment count by 1.

```

template <class Type>
void unorderedLinkedList<Type>::insertFirst(const Type& newItem)
{
 nodeType<Type> *newNode; //pointer to create the new node
 newNode = new nodeType<Type>; //create the new node
 newNode->info = newItem; //store the new item in the node

```

```

newNode->link = first; //insert newNode before first
first = newNode; //make first point to the
 //actual first node
count++; //increment count

if (last == NULL) //if the list was empty, newNode is also
 //the last node in the list
 last = newNode;
} //end insertFirst

```

## Insert the Last Node

The definition of the member function `insertLast` is similar to the definition of the member function `insertFirst`. Here, we insert the new node after `last`. Essentially, the function `insertLast` is:

```

template <class Type>
void unorderedLinkedList<Type>::insertLast(const Type& newItem)
{
 nodeType<Type> *newNode; //pointer to create the new node

 newNode = new nodeType<Type>; //create the new node
 newNode->info = newItem; //store the new item in the node
 newNode->link = NULL; //set the link field of newNode
 //to NULL

 if (first == NULL) //if the list is empty, newNode is
 //both the first and last node
 {
 first = newNode;
 last = newNode;
 count++; //increment count
 }
 else //the list is not empty, insert newNode after last
 {
 last->link = newNode; //insert newNode after last
 last = newNode; //make last point to the actual
 //last node in the list
 count++; //increment count
 }
} //end insertLast

```

## DELETE A NODE

Next, we discuss the implementation of the member function `deleteNode`, which deletes a node from the list with a given `info`. We need to consider several cases:

**Case 1:** The list is empty.

**Case 2:** The first node is the node with the given `info`. In this case, we need to adjust the pointer `first`.

**Case 3:** The node with the given `info` is somewhere in the list. If the node to be deleted is the last node, then we must adjust the pointer `last`.

**Case 4:** The list does not contain the node with the given `info`.

If `list` is empty, we can simply print a message indicating that the list is empty. If `list` is not empty, we search the list for the node with the given `info` and, if such a node is found, we delete this node. After deleting the node, `count` is decremented by 1. In pseudocode, the algorithm is:


```
if list is empty
 Output(cannot delete from an empty list);
else
{
 if the first node is the node with the given info
 adjust the head pointer, that is, first, and deallocate
 the memory;
 else
 {
 search the list for the node with the given info
 if such a node is found, delete it and adjust the
 values of last (if necessary) and count.
 }
}
```

**Case 1:** The list is empty.

If the list is empty, output an error message as shown in the pseudocode.

**Case 2:** The list is not empty. The node to be deleted is the first node.


This case has two scenarios: `list` has only one node, and `list` has more than one node. Consider the list with one node, as shown in Figure 18-22.



**FIGURE 18-22** `list` with one node


Suppose that we want to delete 37. After deletion, the list becomes empty. Therefore, after deletion, both `first` and `last` are set to `NULL`, and `count` is set to 0.

Now consider the list of more than one node, as shown in Figure 18-23.



**FIGURE 18-23** list with more than one node

Suppose that the node to be deleted is 28. After deleting this node, the second node becomes the first node. Therefore, after deleting this node, the value of the pointer **first** changes; that is, after deletion, **first** contains the address of the node with **info** 17, and **count** is decremented by 1. Figure 18-24 shows the list after deleting 28.




**FIGURE 18-24** list after deleting node with **info** 28

**Case 3:** The node to be deleted is not the first node but is somewhere in the list.

This case has two subcases: (a) the node to be deleted is not the last node, and (b) the node to be deleted is the last node. Let us illustrate both cases.

**Case 3a:** The node to be deleted is not the last node.

Consider the list shown in Figure 18-25.



**FIGURE 18-25** list before deleting 37

Suppose that the node to be deleted is 37. After deleting this node, the resulting list is as shown in Figure 18-26. (Notice that the deletion of 37 does not require us to change the

values of **first** and **last**. The link field of the previous node—that is, 17—changes. After deletion, the node with **info** 17 contains the address of the node with 24.)




FIGURE 18-26 list after deleting 37

**Case 3b:** The node to be deleted is the last node.

Consider the list shown in Figure 18-27. Suppose that the node to be deleted is 54.




FIGURE 18-27 list before deleting 54

After deleting 54, the node with **info** 24 becomes the last node. Therefore, the deletion of 54 requires us to change the value of the pointer **last**. After deleting 54, **last** contains the address of the node with **info** 24. Also, **count** is decremented by 1. Figure 18-28 shows the resulting list.




FIGURE 18-28 list after deleting 54

**Case 4:** The node to be deleted is not in the list. In this case, the list requires no adjustment. We simply output an error message, indicating that the item to be deleted is not in the list.

From Cases 2, 3, and 4, it follows that the deletion of a node requires us to traverse the list. Because a linked list is not a random-access data structure, we must sequentially search the list. We handle Case 1 separately, because it does not require us to traverse the list. We sequentially search the list, starting at the second node. If the node to be deleted is in the middle of the list, we need to adjust the link field of the node just before the node to be deleted. Thus, we need a pointer to the previous node. When we search the list for the given `info`, we use two pointers: one to check the `info` of the current node and one to keep track of the node just before the current node. If the node to be deleted is the last node, we must adjust the pointer `last`.

The definition of the function `deleteNode` is:

```
template <class Type>
void unorderedLinkedList<Type>::deleteNode(const Type& deleteItem)
{
 nodeType<Type> *current; //pointer to traverse the list
 nodeType<Type> *trailCurrent; //pointer just before current
 bool found;

 if (first == NULL) //Case 1; the list is empty
 cout << "Cannot delete from an empty list."
 << endl;
 else
 {
 if (first->info == deleteItem) //Case 2
 {
 current = first;
 first = first->link;
 count--;

 if (first == NULL) //the list has only one node
 last = NULL;

 delete current;
 }
 else //search the list for the node with the given info
 {
 found = false;
 trailCurrent = first; //set trailCurrent to point
 //to the first node
 current = first->link; //set current to point to
 //the second node

 while (current != NULL && !found)
 {
 if (current->info != deleteItem)
 {
 trailCurrent = current;
 current = current-> link;
 }
 else
 found = true;
 }
 }
 }
}
```

```

 if (found) //Case 3; if found, delete the node
 {
 trailCurrent->link = current->link;
 count--;

 if (last == current) //node to be deleted
 //was the last node
 last = trailCurrent; //update the value
 //of last
 delete current; //delete the node from the list
 }
 else
 cout << "The item to be deleted is not in "
 << "the list." << endl;
 } //end else
} //end deleteNode
} //end deleteNode

```

## Header File of the Unordered Linked List

For the sake of completeness, we will show how to create the header file that defines the `class unorderedLinkedList` and the operations on such lists. (We assume that the definition of the `class linkedListType` and the definitions of the functions to implement the operations are in the header file `linkedList.h`.)

```

#ifndef H_UnorderedLinkedList
#define H_UnorderedLinkedList

#include "linkedList.h"

using namespace std;

template <class Type>
class unorderedLinkedList: public linkedListType<Type>
{
public:
 bool search(const Type& searchItem) const;
 //Function to determine whether searchItem is in the list.
 //Postcondition: Returns true if searchItem is in the
 // list, otherwise the value false is
 // returned.

 void insertFirst(const Type& newItem);
 //Function to insert newItem at the beginning of the list.
 //Postcondition: first points to the new list, newItem is
 // inserted at the beginning of the list,
 // last points to the last node in the
 // list, and count is incremented by 1.

 void insertLast(const Type& newItem);
 //Function to insert newItem at the end of the list.
 //Postcondition: first points to the new list, newItem
 // is inserted at the end of the list,
 // last points to the last node in the
 // list, and count is incremented by 1.

```

```

void deleteNode(const Type& deleteItem);
//Function to delete deleteItem from the list.
//Postcondition: If found, the node containing
// deleteItem is deleted from the list.
// first points to the first node, last
// points to the last node of the updated
// list, and count is decremented by 1.
};

//Place the definitions of the functions search,
//insertFirst, insertLast, and deleteNode here.
.
.
.
#endif

```

**NOTE**

The Web site accompanying this book contains several programs illustrating how to use the `class unorderedLinkedList`.

## Ordered Linked Lists

The preceding section described the operations on an unordered linked list. This section deals with ordered linked lists. As noted earlier, we derive the `class orderedLinkedList` from the `class linkedListType` and provide the definitions of the abstract functions `insertFirst`, `insertLast`, `search`, and `deleteNode` to take advantage of the fact that the elements of an ordered linked list are arranged using some ordering criteria. For simplicity, we assume that elements of an ordered linked list are arranged in ascending order.

Because the elements of an ordered linked list are in order, we include the function `insert` to insert an element in an ordered list at the proper place.

The following class defines an ordered linked list as an ADT:

```

template <class Type>
class orderedLinkedList: public linkedListType<Type>
{
public:
 bool search(const Type& searchItem) const;
 //Function to determine whether searchItem is in the list.
 //Postcondition: Returns true if searchItem is in the list,
 // otherwise the value false is returned.

 void insert(const Type& newItem);
 //Function to insert newItem in the list.
 //Postcondition: first points to the new list, newItem
 // is inserted at the proper place in the
 // list, and count is incremented by 1.

 void insertFirst(const Type& newItem);
 //Function to insert newItem at the beginning of the list.
 //Postcondition: first points to the new list, newItem is

```

```

// inserted at the proper place in the list,
// last points to the last node in the
// list, and count is incremented by 1.

void insertLast(const Type& newItem);
//Function to insert newItem at the end of the list.
//Postcondition: first points to the new list, newItem is
// inserted at the proper place in the list,
// last points to the last node in the
// list, and count is incremented by 1.

void deleteNode(const Type& deleteItem);
//Function to delete deleteItem from the list.
//Postcondition: If found, the node containing
// deleteItem is deleted from the list;
// first points to the first node of the
// new list, and count is decremented by 1.
// If deleteItem is not in the list, an
// appropriate message is printed.

};

```

1  
8

Figure 18-29 shows a UML class diagram of the `class` `orderedLinkedList` and the inheritance hierarchy.




FIGURE 18-29 UML class diagram of the `class` `orderedLinkedList` and the inheritance hierarchy

Next, we give the definitions of the member functions of the `class` `orderedLinkedList`.

## Search the List

First, we discuss the search operation. The algorithm to implement the search operation is similar to the search algorithm for general lists discussed earlier. Here, because the list is sorted, we can improve the search algorithm somewhat. As before, we start the search at the first node in the list. We stop the search as soon as we find a node in the list with `info` greater than or equal to the search item or when we have searched the entire list.

The following steps describe this algorithm:

1. Compare the search item with the current node in the list. If the `info` of the current node is greater than or equal to the search item, stop the search; otherwise, make the next node the current node.
2. Repeat Step 1 until either an item in the list that is greater than or equal to the search item is found or no more data is left in the list to compare with the search item.

Note that the loop does not explicitly check whether the search item is equal to an item in the list. Thus, after the loop executes, we must check whether the search item is equal to the item in the list.

```
template <class Type>
bool orderedLinkedList<Type>::
 search(const Type& searchItem) const
{
 bool found = false;
 nodeType<Type> *current; //pointer to traverse the list

 current = first; //start the search at the first node

 while (current != NULL && !found)
 if (current->info >= searchItem)
 found = true;
 else
 current = current->link;

 if (found)
 found = (current->info == searchItem); //test for equality

 return found;
} //end search
```

## Insert a Node

To insert an item in an ordered linked list, we first find the place where the new item is supposed to go, and then we insert the item in the list. To find the place for the new item, as before, we search the list. Here, we use two pointers, `current` and `trailCurrent`, to search the list. The pointer `current` points to the node whose `info` is being compared with the item to be inserted, and `trailCurrent` points to the node just before `current`. Because the list is in order, the search algorithm is the same as before. The following cases arise:

- Case 1:** The list is initially empty. The node containing the new item is the only node and thus the first node in the list.
- Case 2:** The new item is smaller than the smallest item in the list. The new item goes at the beginning of the list. In this case, we need to adjust the list's head pointer—that is, `first`. Also, `count` is incremented by 1.
- Case 3:** The item is to be inserted somewhere in the list.

- 3a:** The new item is larger than all of the items in the list. In this case, the new item is inserted at the end of the list. Thus, the value of `current` is `NULL`, and the new item is inserted after `trailCurrent`. Also, `count` is incremented by 1.
- 3b:** The new item is to be inserted somewhere in the middle of the list. In this case, the new item is inserted between `trailCurrent` and `current`. Also, `count` is incremented by 1.

The following statements can accomplish both Cases 3a and 3b. Assume `newNode` points to the new node.

```
trailCurrent->link = newNode;
newNode->link = current;
```

Let us next illustrate these cases.

**Case 1:** The list is empty.

Consider the list shown in Figure 18-30(a).




FIGURE 18-30 list

Suppose that we want to insert 27 in the list. To accomplish this task, we create a node, copy 27 into the node, set the link of the node to `NULL`, and make `first` point to the node. Figure 18-30(b) shows the resulting list. Notice that, after inserting 27, the values of both `first` and `count` change.

**Case 2:** The list is not empty, and the item to be inserted is smaller than the smallest item in the list. Consider the list shown in Figure 18-31.





FIGURE 18-31 Nonempty list before inserting 10


Suppose that 10 is to be inserted. After inserting 10 in the list, the node with info 10 becomes the first node of `list`. This requires us to change the value of `first`. Also, `count` is incremented by 1. Figure 18-32 shows the resulting list.



**FIGURE 18-32** `list` after inserting 10


**Case 3:** The list is not empty, and the item to be inserted is larger than the first item in the list. As indicated previously, this case has two scenarios.

**Case 3a:** The item to be inserted is larger than the largest item in the list; that is, it goes at the end of the list. Consider the list shown in Figure 18-33.



**FIGURE 18-33** `list` before inserting 65

Suppose that we want to insert 65 in the list. After inserting 65, the resulting list is as shown in Figure 18-34.



**FIGURE 18-34** `list` after inserting 65

**Case 3b:** The item to be inserted goes somewhere in the middle of the list. Consider the list shown in Figure 18-35.




FIGURE 18-35 list before inserting 27

Suppose that we want to insert 27 in this list. Clearly, 27 goes between 17 and 38, which would require the link of the node with info 17 to be changed. After inserting 27, the resulting list is as shown in Figure 18-36.




FIGURE 18-36 list after inserting 27

From Case 3, it follows that we must first traverse the list to find the place where the new item is to be inserted. It also follows that we should traverse the list with two pointers—say, `current` and `trailCurrent`. The pointer `current` is used to traverse the list and compare the `info` of the node in the list with the item to be inserted. The pointer `trailCurrent` points to the node just before `current`. For example, in Case 3b, when the search stops, `trailCurrent` points to node 17 and `current` points to node 38. The item is inserted after `trailCurrent`. In Case 3a, after searching the list to find the place for 65, `trailCurrent` points to node 54 and `current` is `NULL`.

Essentially, the function `insert` is as follows:

```

template <class Type>
void orderedLinkedList<Type>::insert(const Type& newItem)
{
 nodeType<Type> *current; //pointer to traverse the list
 nodeType<Type> *trailCurrent; //pointer just before current
 nodeType<Type> *newNode; //pointer to create a node

```

```

bool found;

newNode = new nodeType<Type>; //create the node
newNode->info = newItem; //store newItem in the node
newNode->link = NULL; //set the link field of the node
 //to NULL

if (first == NULL) //Case 1
{
 first = newNode;
 last = newNode;
 count++;
}
else
{
 current = first;
 found = false;

 while (current != NULL && !found) //search the list
 if (current->info >= newItem)
 found = true;
 else
 {
 trailCurrent = current;
 current = current->link;
 }

 if (current == first) //Case 2
 {
 newNode->link = first;
 first = newNode;
 count++;
 }
 else //Case 3
 {
 trailCurrent->link = newNode;
 newNode->link = current;

 if (current == NULL)
 last = newNode;

 count++;
 }
} //end else
} //end insert

```

## Insert First and Insert Last

The function `insertFirst` inserts the new item at the beginning of the list. However, because the resulting list must be sorted, the new item must be inserted at the proper place. Similarly, the function `insertLast` must insert the new item at the proper place.

Therefore, we use the function `insertNode` to insert the new item at its proper place. The definitions of these functions are:

```
template <class Type>
void orderedLinkedList<Type>::insertFirst(const Type& newItem)
{
 insert(newItem);
} //end insertFirst

template <class Type>
void orderedLinkedList<Type>::insertLast(const Type& newItem)
{
 insert(newItem);
} //end insertLast
```

Note that in reality, the functions `insertFirst` and `insertLast` do not apply to ordered linked lists because the new item must be inserted at the proper place in the list. However, you must provide its definition as these functions are declared as abstract in the parent class.

## Delete a Node

To delete a given item from an ordered linked list, first we search the list to see whether the item to be deleted is in the list. The function to implement this operation is the same as the delete operation on general linked lists. Here, because the list is sorted, we can somewhat improve the algorithm for ordered linked lists.

As in the case of `insertNode`, we search the list with two pointers, `current` and `trailCurrent`. Similar to the operation `insertNode`, several cases arise:

- Case 1:** The list is initially empty. We have an error. We cannot delete from an empty list.
- Case 2:** The item to be deleted is contained in the first node of the list. We must adjust the head pointer of the list—that is, `first`.
- Case 3:** The item to be deleted is somewhere in the list. In this case, `current` points to the node containing the item to be deleted, and `trailCurrent` points to the node just before the node pointed to by `current`.
- Case 4:** The list is not empty, but the item to be deleted is not in the list.

After deleting a node, `count` is decremented by 1. The definition of the function `deleteNode` is:

```
template <class Type>
void orderedLinkedList<Type>::deleteNode(const Type& deleteItem)
{
 nodeType<Type> *current; //pointer to traverse the list
 nodeType<Type> *trailCurrent; //pointer just before current
 bool found;
```

```

if (first == NULL) //Case 1
 cout << "Cannot delete from an empty list." << endl;
else
{
 current = first;
 found = false;

 while (current != NULL && !found) //search the list
 if (current->info == deleteItem)
 found = true;
 else
 {
 trailCurrent = current;
 current = current->link;
 }

 if (current == NULL) //Case 4
 cout << "The item to be deleted is not in the "
 << "list." << endl;
 else
 if (current->info == deleteItem) //the item to be
 //deleted is in the list
 {
 if (first == current) //Case 2
 {
 first = first->link;

 if (first == NULL)
 last = NULL;

 delete current;
 }
 else //Case 3
 {
 trailCurrent->link = current->link;

 if (current == last)
 last = trailCurrent;

 delete current;
 }
 count--;
 }
 else //Case 4
 cout << "The item to be deleted is not in the "
 << "list." << endl;
 }
} //end deleteNode

```

## Header File of the Ordered Linked List

For the sake of completeness, we will show how to create the header file that defines the `class orderedListType`, as well as the operations on such lists. (We assume that the

definition of the `class` `linkedListType` and the definitions of the functions to implement the operations are in the header file `linkedList.h`.)

```
#ifndef H_orderedListType
#define H_orderedListType

#include "linkedList.h"

using namespace std;

template <class Type>
class orderedLinkedList: public linkedListType<Type>
{
public:
 bool search(const Type& searchItem) const;
 //Function to determine whether searchItem is in the list.
 //Postcondition: Returns true if searchItem is in the list,
 // otherwise the value false is returned.

 void insert(const Type& newItem);
 //Function to insert newItem in the list.
 //Postcondition: first points to the new list, newItem
 // is inserted at the proper place in the
 // list, and count is incremented by 1.

 void insertFirst(const Type& newItem);
 //Function to insert newItem at the beginning of the list.
 //Postcondition: first points to the new list, newItem is
 // inserted at the proper place in the list,
 // last points to the last node in the
 // list, and count is incremented by 1.

 void insertLast(const Type& newItem);
 //Function to insert newItem at the end of the list.
 //Postcondition: first points to the new list, newItem is
 // inserted at the proper place in the list,
 // last points to the last node in the
 // list, and count is incremented by 1.

 void deleteNode(const Type& deleteItem);
 //Function to delete deleteItem from the list.
 //Postcondition: If found, the node containing
 // deleteItem is deleted from the list;
 // first points to the first node of the
 // new list, and count is decremented by 1.
 // If deleteItem is not in the list, an
 // appropriate message is printed.
};

//Place the definitions of the functions search, insert,
//insertFirst, insertLast, and deleteNode here.
.
.
.
#endif
```

The following program tests various operations on an ordered linked list.

```
//Program to test the various operations on an ordered linked list
```

[illegible]

**Sample Run:** In this sample run, the user input is shaded.

```
Line 3: Enter numbers ending with -999.
23 65 34 72 12 82 36 55 29 -999

Line 9: list1: 12 23 29 34 36 55 65 72 82
Line 13: list2: 12 23 29 34 36 55 65 72 82
Line 16: Enter the number to be deleted: 34

Line 20: After deleting 34, list2:
12 23 29 36 55 65 72 82
```

The preceding output is self-explanatory. The details are left as an exercise for you.


#### NOTE

Notice that the function `insert` does not check whether the item to be inserted is already in the list, that is, it does not check for duplicates. Programming Exercise 8 at the end of this chapter asks you to revise the definition of the function `insert` so that before inserting the item, it checks whether it is already in the list. If the item to be inserted is already in the list, the function outputs an appropriate error message. In other words, duplicates are not allowed.

## Print a Linked List in Reverse Order (Recursion Revisited)

The nodes of an ordered list (as constructed previously) are in ascending order. Certain applications, however, might require the data to be printed in descending order, which means that we must print the list backward. We now discuss the function `reversePrint`. Given a pointer to a list, this function prints the elements of the list in reverse order.

Consider the linked list shown in Figure 18-37.



**FIGURE 18-37** Linked list

For the list in Figure 18-37, the output should be in the following form:

```
20 15 10 5
```

Because the links are in only one direction, we cannot traverse the list backward starting from the last node. Let us see how we can effectively use recursion to print the list in reverse order.

Let us think in terms of recursion. We cannot print the `info` of the first node until we have printed the remainder of the list (that is, the tail of the first node). Similarly, we cannot print the `info` of the second node until we have printed the tail of the second node, and so on. Every time we consider the tail of a node, we reduce the size of the list by 1. Eventually, the size of the list will be reduced to zero, in which case the recursion will stop. Let us first write the algorithm in pseudocode. (Suppose that `current` is a pointer to a linked list.)

```
if (current != NULL)
{
 reversePrint(current->link); //print the tail
 cout << current->info << endl; //print the node
}
```

Here, we do not see the base case; it is hidden. The list is printed only if the pointer to the list is not `NULL`. Also, in the body of the `if` statement, the recursive call is on the tail of the list. Because eventually the tail of the list will be empty, the `if` statement in the next call will fail, and the recursion will stop. Also, note that statements (for example, printing the `info` of the node) appear after the recursive call; thus, when the transfer comes back to the calling function, we must execute the remaining statements. Recall that the function exits only after the last statement executes. (By the “last statement,” we do not mean the physical last statement, but rather the logical last statement.)

Let us write the previous function in C++ and then apply it to a list.


```
template <class Type>
void linkedListType<Type>::reversePrint
 (nodeType<Type> *current) const
{
 if (current != NULL)
 {
 reversePrint(current->link); //print the tail
 cout << current->info << " "; //print the node
 }
}
```

Consider the statement:

```
reversePrint(first);
```

in which `first` is a pointer of type `nodeType<Type>`.

Let us trace the execution of this statement, which is a function call, for the list shown in Figure 18-37. Because the formal parameter is a value parameter, the value of the actual parameter is passed to the formal parameter. See Figure 18-38.

FIGURE 18-38 Execution of the statement `reversePrint(first);`

## printListReverse

Now that we have written the function `reversePrint`, we can write the definition of the function `printListReverse`. Its definition is:


```

template <class Type>
void linkedListType<Type>::printListReverse() const
{
 reversePrint(first);
 cout << endl;
}

```

## Doubly Linked Lists

A doubly linked list is a linked list in which every node has a next pointer and a back pointer. In other words, every node contains the address of the next node (except the last node), and every node contains the address of the previous node (except the first node) (see Figure 18-39).



**FIGURE 18-39** Doubly linked list

A doubly linked list can be traversed in either direction. That is, we can traverse the list starting at the first node or, if a pointer to the last node is given, we can traverse the list starting at the last node.

As before, the typical operations on a doubly linked list are:

1. Initialize the list.
2. Destroy the list.
3. Determine whether the list is empty.
4. Search the list for a given item.
5. Retrieve the first element of the list.
6. Retrieve the last element of the list.
7. Insert an item in the list.
8. Delete an item from the list.
9. Find the length of the list.
10. Print the list.
11. Make a copy of the doubly linked list.

Next, we describe these operations for an ordered doubly linked list. The following class defines a doubly linked list as an ADT.

```
//Definition of the node
template <class Type>
struct nodeType
{
 Type info;
 nodeType<Type> *next;
 nodeType<Type> *back;
};
```

```

template <class Type>
class doublyLinkedList
{
public:
 const doublyLinkedList<Type>& operator=
 (const doublyLinkedList<Type> &);
 //Overload the assignment operator.

 void initializeList();
 //Function to initialize the list to an empty state.
 //Postcondition: first = NULL; last = NULL; count = 0;

 bool isEmptyList() const;
 //Function to determine whether the list is empty.
 //Postcondition: Returns true if the list is empty,
 // otherwise returns false.

 void destroy();
 //Function to delete all the nodes from the list.
 //Postcondition: first = NULL; last = NULL; count = 0;

 void print() const;
 //Function to output the info contained in each node.

 void reversePrint() const;
 //Function to output the info contained in each node
 //in reverse order.

 int length() const;
 //Function to return the number of nodes in the list.
 //Postcondition: The value of count is returned.

 Type front() const;
 //Function to return the first element of the list.
 //Precondition: The list must exist and must not be empty.
 //Postcondition: If the list is empty, the program
 // terminates; otherwise, the first
 // element of the list is returned.

 Type back() const;
 //Function to return the last element of the list.
 //Precondition: The list must exist and must not be empty.
 //Postcondition: If the list is empty, the program
 // terminates; otherwise, the last
 // element of the list is returned.

 bool search(const Type& searchItem) const;
 //Function to determine whether searchItem is in the list.
 //Postcondition: Returns true if searchItem is found in
 // the list, otherwise returns false.

```

```

void insert(const Type& insertItem);
 //Function to insert insertItem in the list.
 //Precondition: If the list is nonempty, it must be in
 // order.
 //Postcondition: insertItem is inserted at the proper place
 // in the list, first points to the first
 // node, last points to the last node of the
 // new list, and count is incremented by 1.

void deleteNode(const Type& deleteItem);
 //Function to delete deleteItem from the list.
 //Postcondition: If found, the node containing deleteItem
 // is deleted from the list; first points
 // to the first node of the new list, last
 // points to the last node of the new list,
 // and count is decremented by 1; otherwise
 // an appropriate message is printed.

doublyLinkedList();
 //default constructor
 //Initializes the list to an empty state.
 //Postcondition: first = NULL; last = NULL; count = 0;

doublyLinkedList(const doublyLinkedList<Type>& otherList);
 //copy constructor
~doublyLinkedList();
 //destructor
 //Postcondition: The list object is destroyed.

protected:
 int count;
 nodeType<Type> *first; //pointer to the first node
 nodeType<Type> *last; //pointer to the last node

private:
 void copyList(const doublyLinkedList<Type>& otherList);
 //Function to make a copy of otherList.
 //Postcondition: A copy of otherList is created and
 // assigned to this list.
};

```

We leave the UML class diagram of the `class` `doublyLinkedList` as an exercise for you.

The functions to implement the operations of a doubly linked list are similar to the ones discussed earlier. Here, because every node has two pointers, `back` and `next`, some of the operations require the adjustment of two pointers in each node. For the insert and delete operations, because we can traverse the list in either direction, we use only one pointer to traverse the list. Let us call this pointer `current`. We can set the value of `trailCurrent` by using both the `current` pointer and the `back` pointer of the node pointed to by `current`. We give the definition of each function here, with four exceptions. Definitions

of the functions `copyList`, the copy constructor, overloading the assignment operator, and the destructor are left as exercises for you. (See Programming Exercise 11 at the end of this chapter.) Moreover, the function `copyList` is used only to implement the copy constructor and overload the assignment operator.

## Default Constructor

The default constructor initializes the doubly linked list to an empty state. It sets `first` and `last` to `NULL` and `count` to 0.

```
template <class Type>
doublyLinkedList<Type>::doublyLinkedList()
{
 first= NULL;
 last = NULL;
 count = 0;
}
```

## isEmptyList

This operation returns `true` if the list is empty; otherwise, it returns `false`. The list is empty if the pointer `first` is `NULL`.

```
template <class Type>
bool doublyLinkedList<Type>::isEmptyList() const
{
 return (first == NULL);
}
```

## Destroy the List

This operation deletes all of the nodes in the list, leaving the list in an empty state. We traverse the list starting at the first node and then delete each node. Furthermore, `count` is set to 0.

```
template <class Type>
void doublyLinkedList<Type>::destroy()
{
 nodeType<Type> *temp; //pointer to delete the node

 while (first != NULL)
 {
 temp = first;
 first = first->next;
 delete temp;
 }

 last = NULL;
 count = 0;
}
```

## Initialize the List

This operation reinitializes the doubly linked list to an empty state. This task can be done by using the operation `destroy`. The definition of the function `initializeList` is:

```
template <class Type>
void doublyLinkedList<Type>::initializeList()
{
 destroy();
}
```

## Length of the List

The length of a linked list (that is, how many nodes are in the list) is stored in the variable `count`. Therefore, this function returns the value of this variable.

```
template <class Type>
int doublyLinkedList<Type>::length() const
{
 return count;
}
```

## Print the List

The function `print` outputs the info contained in each node. We traverse the list, starting from the first node.

```
template <class Type>
void doublyLinkedList<Type>::print() const
{
 nodeType<Type> *current; //pointer to traverse the list

 current = first; //set current to point to the first node

 while (current != NULL)
 {
 cout << current->info << " "; //output info
 current = current->next;
 } //end while
} //end print
```

## Reverse Print the List

This function outputs the info contained in each node in reverse order. We traverse the list in reverse order, starting from the last node. Its definition is:

```
template <class Type>
void doublyLinkedList<Type>::reversePrint() const
{
 nodeType<Type> *current; //pointer to traverse
 //the list
```

```

current = last; //set current to point to the
 //last node

while (current != NULL)
{
 cout << current->info << " ";
 current = current->back;
} //end while
} //end reversePrint

```

## Search the List

The function `search` returns `true` if `searchItem` is found in the list; otherwise, it returns `false`. The search algorithm is exactly the same as the search algorithm for an ordered linked list.

```

template <class Type>
bool doublyLinkedList<Type>::
 search(const Type& searchItem) const
{
 bool found = false;
 nodeType<Type> *current; //pointer to traverse the list

 current = first;

 while (current != NULL && !found)
 if (current->info >= searchItem)
 found = true;
 else
 current = current->next;

 if (found)
 found = (current->info == searchItem); //test for
 //equality

 return found;
} //end search

```

## First and Last Elements

The function `front` returns the first element of the list, and the function `back` returns the last element of the list. If the list is empty, both functions terminate the program. Their definitions are:

```

template <class Type>
Type doublyLinkedList<Type>::front() const
{
 assert(first != NULL);

 return first->info;
}

```

```

template <class Type>
Type doublyLinkedList<Type>::back() const
{
 assert(last != NULL);

 return last->info;
}

```

### INSERT A NODE

Because we are inserting an item in a doubly linked list, the insertion of a node in the list requires the adjustment of two pointers in certain nodes. As before, we find the place where the new item is supposed to be inserted, create the node, store the new item, and adjust the link fields of the new node and other particular nodes in the list. There are four cases:

**Case 1:** Insertion in an empty list


**Case 2:** Insertion at the beginning of a nonempty list

**Case 3:** Insertion at the end of a nonempty list

**Case 4:** Insertion somewhere in a nonempty list

Both Cases 1 and 2 require us to change the value of the pointer **first**. Cases 3 and 4 are similar. After inserting an item, **count** is incremented by 1. Next, we show Case 4.

Consider the doubly linked list shown in Figure 18-40.



**FIGURE 18-40** Doubly linked list before inserting 20

Suppose that 20 is to be inserted in the list. After inserting 20, the resulting list is as shown in Figure 18-41.




FIGURE 18-41 Doubly linked list after inserting 20

From Figure 18-41, it follows that the `next` pointer of node 15, the `back` pointer of node 24, and both the `next` and `back` pointers of node 20 need to be adjusted.

The definition of the function `insert` is:

```
template <class Type>
void doublyLinkedList<Type>::insert(const Type& insertItem)
{
 nodeType<Type> *current; //pointer to traverse the list
 nodeType<Type> *trailCurrent; //pointer just before current
 nodeType<Type> *newNode; //pointer to create a node
 bool found;

 newNode = new nodeType<Type>; //create the node
 newNode->info = insertItem; //store the new item in the node
 newNode->next = NULL;
 newNode->back = NULL;

 if (first == NULL) //if the list is empty, newNode is
 //the only node
 {
 first = newNode;
 last = newNode;
 count++;
 }
 else
 {
 found = false;
 current = first;

 while (current != NULL && !found) //search the list
 if (current->info >= insertItem)
 found = true;
 else
 {
 trailCurrent = current;
 current = current->next;
 }
 }
}
```

```

if (current == first) //insert newNode before first
{
 first->back = newNode;
 newNode->next = first;
 first = newNode;
 count++;
}
else
{
 //insert newNode between trailCurrent and current
 if (current != NULL)
 {
 trailCurrent->next = newNode;
 newNode->back = trailCurrent;
 newNode->next = current;
 current->back = newNode;
 }
 else
 {
 trailCurrent->next = newNode;
 newNode->back = trailCurrent;
 last = newNode;
 }

 count++;
} //end else
} //end else
} //end insert

```

## DELETE A NODE

This operation deletes a given item (if found) from the doubly linked list. As before, we first search the list to see whether the item to be deleted is in the list. The search algorithm is the same as before. Similar to the `insertNode` operation, this operation (if the item to be deleted is in the list) requires the adjustment of two pointers in certain nodes. The delete operation has several cases:

**Case 1:** The list is empty.

**Case 2:** The item to be deleted is in the first node of the list, which would require us to change the value of the pointer `first`.

**Case 3:** The item to be deleted is somewhere in the list.

**Case 4:** The item to be deleted is not in the list.

After deleting a node, `count` is decremented by 1. Let us demonstrate Case 3. Consider the list shown in Figure 18-42.




FIGURE 18-42 Doubly linked list before deleting 17

Suppose that the item to be deleted is 17. First, we search the list with two pointers and find the node with `info 17` and then adjust the link field of the affected nodes (see Figure 18-43).




FIGURE 18-43 List after adjusting the links of the nodes before and after the node with `info 17`

Next, we delete the node pointed to by `current` (see Figure 18-44).




FIGURE 18-44 List after deleting the node with `info 17`

The definition of the function `deleteNode` is:

```
template <class Type>
void doublyLinkedList<Type>::deleteNode(const Type& deleteItem)
{
 nodeType<Type> *current; //pointer to traverse the list
 nodeType<Type> *trailCurrent; //pointer just before current

 bool found;

 if (first == NULL)
 cout << "Cannot delete from an empty list." << endl;
 else if (first->info == deleteItem) //node to be deleted is
 //the first node
 {
 current = first;
 first = first->next;

 if (first != NULL)
 first->back = NULL;
 else
 last = NULL;

 count--;

 delete current;
 }
 else
 {
 found = false;
 current = first;

 while (current != NULL && !found) //search the list
 if (current->info == deleteItem)
 found = true;
 else
 current = current->next;

 if (current == NULL)
 cout << "The item to be deleted is not in "
 << "the list." << endl;
 else if (current->info == deleteItem) //check for
 //equality
 {
 trailCurrent = current->back;
 trailCurrent->next = current->next;

 if (current->next != NULL)
 current->next->back = trailCurrent;

 if (current == last)
 last = trailCurrent;

 count--;
 delete current;
 }
 }
}
```


```

else
 cout << "The item to be deleted is not in list."
 << endl;
} //end else
} //end deleteNode

```

## Circular Linked Lists

A linked list in which the last node points to the first node is called a **circular linked list**. Figure 18-45 show various circular linked lists.



**FIGURE 18-45** Circular linked lists

In a circular linked list with more than one node, as in Figure 18-45(c), it is convenient to make the pointer `first` point to the last node of the list. Then, by using `first`, you can access both the first and the last nodes of the list. For example, `first` points to the last node, and `first->link` points to the first node.

As before, the usual operations on a circular list are:

1. Initialize the list (to an empty state).
2. Determine if the list is empty.
3. Destroy the list.
4. Print the list.
5. Find the length of the list.
6. Search the list for a given item.
7. Insert an item in the list.
8. Delete an item from the list.
9. Copy the list.

We leave it as an exercise for you to design a class to implement a sorted circular linked list. (See Programming Exercise 13 at the end of this chapter.)

## PROGRAMMING EXAMPLE: Video Store

For a family or an individual, a favorite place to go on weekends or holidays is to a video store to rent movies. A new video store in your neighborhood is about to open. However, it does not have a program to keep track of its videos and customers. The store managers want someone to write a program for their system so that the video store can function. The program should be able to perform the following operations:

1. Rent a video; that is, check out a video.
2. Return, or check in, a video.
3. Create a list of videos owned by the store.
4. Show the details of a particular video.
5. Print a list of all of the videos in the store.
6. Check whether a particular video is in the store.
7. Maintain a customer database.
8. Print a list of all of the videos rented by each customer.

Let us write a program for the video store. This example further illustrates the object-oriented design methodology and, in particular, inheritance and overloading.

The programming requirement tells us that the video store has two major components: videos and customers. We will describe these two components in detail. We also need to maintain the following lists:

- A list of all of the videos in the store
- A list of all of the store's customers
- Lists of the videos currently rented by the customers

We will develop the program in two parts. In Part 1, we design, implement, and test the video component. In Part 2, we design and implement the customer component, which is then added to the video component developed in Part 1. That is, after completing Parts 1 and 2, we can perform all of the operations listed previously.

### PART 1: VIDEO COMPONENT

**Video Object** This is the first stage, wherein we discuss the video component. The common things associated with a video are:

- Name of the movie
- Names of the stars
- Name of the producer
- Name of the director

- Name of the production company
- Number of copies in the store

From this list, we see that some of the operations to be performed on a video object are:

1. Set the video information—that is, the title, stars, production company, and so on.
2. Show the details of a particular video.
3. Check the number of copies in the store.
4. Check out (that is, rent) the video. In other words, if the number of copies is greater than zero, decrement the number of copies by one.
5. Check in (that is, return) the video. To check in a video, first we must check whether the store owns such a video and, if it does, increment the number of copies by one.
6. Check whether a particular video is available—that is, check whether the number of copies currently in the store is greater than zero.

The deletion of a video from the video list requires that the list be searched for the video to be deleted. Thus, we need to check the title of a video to find out which video is to be deleted from the list. For simplicity, we assume that two videos are the same if they have the same title.

The following class defines the video object as an ADT.

```
//*****
// Author: D.S. Malik
//
// class videoType
// This class specifies the members to implement a video.
//*****

#include <iostream>
#include <string>

using namespace std;

class videoType
{
 friend ostream& operator<< (ostream&, const videoType&);

public:
 void setVideoInfo(string title, string star1,
 string star2, string producer,
 string director, string productionCo,
 int setInStock);
 //Function to set the details of a video.
 //The member variables are set according to the
 //parameters.
```

```

 //Postcondition: videoTitle = title; movieStar1 = star1;
 // movieStar2 = star2; movieProducer = producer;
 // movieDirector = director;
 // movieProductionCo = productionCo;
 // copiesInStock = setInStock;

int getNoOfCopiesInStock() const;
 //Function to check the number of copies in stock.
 //Postcondition: The value of copiesInStock is returned.

void checkOut();
 //Function to rent a video.
 //Postcondition: The number of copies in stock is
 // decremented by one.

void checkIn();
 //Function to check in a video.
 //Postcondition: The number of copies in stock is
 // incremented by one.

void printTitle() const;
 //Function to print the title of a movie.

void printInfo() const;
 //Function to print the details of a video.
 //Postcondition: The title of the movie, stars,
 // director, and so on are displayed
 // on the screen.

bool checkTitle(string title);
 //Function to check whether the title is the same as the
 //title of the video.
 //Postcondition: Returns the value true if the title
 // is the same as the title of the video;
 // false otherwise.

void updateInStock(int num);
 //Function to increment the number of copies in stock by
 //adding the value of the parameter num.
 //Postcondition: copiesInStock = copiesInStock + num;

void setCopiesInStock(int num);
 //Function to set the number of copies in stock.
 //Postcondition: copiesInStock = num;

string getTitle() const;
 //Function to return the title of the video.
 //Postcondition: The title of the video is returned.

videoType(string title = "", string star1 = "",
 string star2 = "", string producer = "",

```

```

 string director = "", string productionCo = "",
 int setInStock = 0);
//constructor
//The member variables are set according to the
//incoming parameters. If no values are specified, the
//default values are assigned.
//Postcondition: videoTitle = title; movieStar1 = star1;
// movieStar2 = star2;
// movieProducer = producer;
// movieDirector = director;
// movieProductionCo = productionCo;
// copiesInStock = setInStock;

//Overload the relational operators.
bool operator==(const videoType&) const;
bool operator!=(const videoType&) const;

private:
 string videoTitle; //variable to store the name
 //of the movie
 string movieStar1; //variable to store the name
 //of the star
 string movieStar2; //variable to store the name
 //of the star
 string movieProducer; //variable to store the name
 //of the producer
 string movieDirector; //variable to store the name
 //of the director
 string movieProductionCo; //variable to store the name
 //of the production company
 int copiesInStock; //variable to store the number of
 //copies in stock
};

```

We leave the UML diagram of the `class` `videoType` as an exercise for you.

For easy output, we will overload the output stream insertion operator, `<<`, for the `class` `videoType`.

Next, we write the definitions of each function in the `class` `videoType`. The definitions of these functions, as given below, are quite straightforward and easy to follow.

```

void videoType::setVideoInfo(string title, string star1,
 string star2, string producer,
 string director,
 string productionCo,
 int setInStock)
{
 videoTitle = title;
 movieStar1 = star1;

```

```

 movieStar2 = star2;
 movieProducer = producer;
 movieDirector = director;
 movieProductionCo = productionCo;
 copiesInStock = setInStock;
 }

 void videoType::checkOut()
 {
 if (getNoOfCopiesInStock() > 0)
 copiesInStock--;
 else
 cout << "Currently out of stock" << endl;
 }

 void videoType::checkIn()
 {
 copiesInStock++;
 }

 int videoType::getNoOfCopiesInStock() const
 {
 return copiesInStock;
 }

 void videoType::printTitle() const
 {
 cout << "Video Title: " << videoTitle << endl;
 }

 void videoType::printInfo() const
 {
 cout << "Video Title: " << videoTitle << endl;
 cout << "Stars: " << movieStar1 << " and "
 << movieStar2 << endl;
 cout << "Producer: " << movieProducer << endl;
 cout << "Director: " << movieDirector << endl;
 cout << "Production Company: " << movieProductionCo
 << endl;
 cout << "Copies in stock: " << copiesInStock
 << endl;
 }

 bool videoType::checkTitle(string title)
 {
 return(videoTitle == title);
 }

 void videoType::updateInStock(int num)
 {
 copiesInStock += num;
 }

```

```

void videoType::setCopiesInStock(int num)
{
 copiesInStock = num;
}

string videoType::getTitle() const
{
 return videoTitle;
}

videoType::videoType(string title, string star1,
 string star2, string producer,
 string director,
 string productionCo, int setInStock)
{
 setVideoInfo(title, star1, star2, producer, director,
 productionCo, setInStock);
}

bool videoType::operator==(const videoType& other) const
{
 return (videoTitle == other.videoTitle);
}

bool videoType::operator!=(const videoType& other) const
{
 return (videoTitle != other.videoTitle);
}

ostream& operator<< (ostream& osObject, const videoType& video)
{
 osObject << endl;
 osObject << "Video Title: " << video.videoTitle << endl;
 osObject << "Stars: " << video.movieStar1 << " and "
 << video.movieStar2 << endl;
 osObject << "Producer: " << video.movieProducer << endl;
 osObject << "Director: " << video.movieDirector << endl;
 osObject << "Production Company: "
 << video.movieProductionCo << endl;
 osObject << "Copies in stock: " << video.copiesInStock
 << endl;
 osObject << "_____ "
 << endl;

 return osObject;
}

```

**Video List** This program requires us to maintain a list of all of the videos in the store. We also should be able to add a new video to our list. In general, we would not know how many videos are in the store, and adding or deleting a video from the store would change the number of videos in the store. Therefore, we will use a linked list to create a list of videos (see Figure 18-46).




FIGURE 18-46 videoList

Earlier in this chapter, we defined the `class unorderedLinkedList` to create a linked list of objects. We also defined the basic operations such as insertion and deletion of a video in the list. However, some operations are very specific to the video list, such as check out a video, check in a video, set the number of copies of a video, and so on. These operations are not available in the `class unorderedLinkedList`. We will, therefore, derive a `class videoListType` from the `class unorderedLinkedList` and add these operations.

The definition of the `class videoListType` is:

```

//*****
// Author: D.S. Malik
//
// class videoListType
// This class specifies the members to implement a list of
// videos.
//*****

#include <string>
#include "unorderedLinkedList.h"
#include "videoType.h"

using namespace std;

class videoListType:public unorderedLinkedList<videoType>
{
public:
 bool videoSearch(string title) const;
 //Function to search the list to see whether a
 //particular title, specified by the parameter title,
 //is in the store.
 //Postcondition: Returns true if the title is found,
 //and false otherwise.

 bool isVideoAvailable(string title) const;
 //Function to determine whether a copy of a particular
 //video is in the store.
 //Postcondition: Returns true if at least one copy of the
 //video specified by title is in the store,
 //and false otherwise.

```

```

void videoCheckOut(string title);
 //Function to check out a video, that is, rent a video.
 //Postcondition: copiesInStock is decremented by one.

void videoCheckIn(string title);
 //Function to check in a video returned by a customer.
 //Postcondition: copiesInStock is incremented by one.

bool videoCheckTitle(string title) const;
 //Function to determine whether a particular video is in
 //the store.
 //Postcondition: Returns true if the video's title is
 //the same as title, and false otherwise.

void videoUpdateInStock(string title, int num);
 //Function to update the number of copies of a video
 //by adding the value of the parameter num. The
 //parameter title specifies the name of the video for
 //which the number of copies is to be updated.
 //Postcondition: copiesInStock = copiesInStock + num;

void videoSetCopiesInStock(string title, int num);
 //Function to reset the number of copies of a video.
 //The parameter title specifies the name of the video
 //for which the number of copies is to be reset, and the
 //parameter num specifies the number of copies.
 //Postcondition: copiesInStock = num;

void videoPrintTitle() const;
 //Function to print the titles of all the videos in
 //the store.

private:
 void searchVideoList(string title, bool& found,
 nodeType<videoType>* ¤t) const;
 //This function searches the video list for a
 //particular video, specified by the parameter title.
 //Postcondition: If the video is found, the parameter
 //found is set to true, otherwise it is set
 //to false. The parameter current points
 //to the node containing the video.
};

```


Note that the `class` `videoListType` is derived from the `class` `unorderedLinkedList` via a `public` inheritance. Furthermore, `unorderedLinkedList` is a class template, and we have passed the `class` `videoType` as a parameter to this class. That is, the `class` `videoListType` is

not a template. Because we are now dealing with a very specific data type, the `class` `videoListType` is no longer required to be a template. Thus, the `info` type of each node in the linked list is now `videoType`. Through the member functions of the `class` `videoType`, certain members—such as `videoTitle` and `copiesInStock` of an object of type `videoType`—can now be accessed.

The definitions of the functions to implement the operations of the `class` `videoListType` are given next.

The primary operations on the video list are to check in a video and to check out a video. Both operations require the list to be searched and the location of the video being checked in or checked out to be found in the video list. Other operations, such as determining whether a particular video is in the store, updating the number of copies of a video, and so on, also require the list to be searched. To simplify the search process, we will write a function that searches the video list for a particular video. If the video is found, it sets a parameter `found` to `true` and returns a pointer to the video so that check-in, check-out, and other operations on the video object can be performed. Note that the function `searchVideoList` is a `private` data member of the `class` `videoListType` because it is used only for internal manipulation. First, we describe the search procedure.

Consider the node of the video list shown in Figure 18-47.



**FIGURE 18-47** Node of a video list

The component `info` is of type `videoType` and contains the necessary information about a video. In fact, the component `info` of the node has seven members: `videoTitle`, `movieStar1`, `movieStar2`, `movieProducer`, `movieDirector`, `movieProductionCo`, and `copiesInStock`. (See the definition of the `class` `videoType`.) Therefore, the node of a video list has the form shown in Figure 18-48.




FIGURE 18-48 Video list node showing components of `info`

These member variables are all **private** and cannot be accessed directly. The member functions of the **class** `videoType` will help us in checking and/or setting the value of a particular component.

Suppose a pointer—say, `current`—points to a node in the video list (see Figure 18-49).




FIGURE 18-49 Pointer `current` and video list node

Now:

```
current->info
```

refers to the `info` part of the node. Suppose that we want to know whether the title of the video stored in this node is the same as the title specified by the variable `title`. The expression:

```
current->info.checkTitle(title)
```

is `true` if the title of the video stored in this node is the same as the title specified by the parameter `title`, and `false` otherwise. (Note that the member function `checkTitle` is a value-returning function. See its declaration in the `class` `videoType`.)

As another example, suppose that we want to set `copiesInStock` of this node to 10. Because `copiesInStock` is a `private` member, it cannot be accessed directly. Therefore, the statement:

```
current->info.copiesInStock = 10; //illegal
```

is incorrect and will generate a compile-time error. We have to use the member function `setCopiesInStock` as follows:

```
current->info.setCopiesInStock(10);
```

Now that we know how to access a member variable of a video stored in a node, let us describe the algorithm to search the video list.

```
while (not found)
 if the title of the current video is the same as the desired
 title, stop the search
 else
 check the next node
```

The following function definition performs the desired search.

```
void videoListType::searchVideoList(string title, bool& found,
 nodeType<videoType>* ¤t) const
{
 found = false; //set found to false

 current = first; //set current to point to the first node
 //in the list

 while (current != NULL && !found) //search the list
 if (current->info.checkTitle(title)) //the item is found
 found = true;
 else
 current = current->link; //advance current to
 //the next node
} //end searchVideoList
```

If the search is successful, the parameter `found` is set to `true` and the parameter `current` points to the node containing the video info. If it is unsuccessful, `found` is set to `false` and `current` will be `NULL`.

The definitions of the other functions of the `class` `videoListType` follow:

```
bool videoListType::isVideoAvailable(string title) const
{
 bool found;
 nodeType<videoType> *location;

 searchVideoList(title, found, location);

 if (found)
 found = (location->info.getNoOfCopiesInStock() > 0);
 else
 found = false;

 return found;
}

void videoListType::videoCheckIn(string title)
{
 bool found = false;
 nodeType<videoType> *location;

 searchVideoList(title, found, location); //search the list

 if (found)
 location->info.checkIn();
 else
 cout << "The store does not carry " << title
 << endl;
}

void videoListType::videoCheckOut(string title)
{
 bool found = false;
 nodeType<videoType> *location;

 searchVideoList(title, found, location); //search the list

 if (found)
 location->info.checkOut();
 else
 cout << "The store does not carry " << title
 << endl;
}
```

```

bool videoListType::videoCheckTitle(string title) const
{
 bool found = false;
 nodeType<videoType> *location;

 searchVideoList(title, found, location); //search the list

 return found;
}

void videoListType::videoUpdateInStock(string title, int num)
{
 bool found = false;
 nodeType<videoType> *location;

 searchVideoList(title, found, location); //search the list

 if (found)
 location->info.updateInStock(num);
 else
 cout << "The store does not carry " << title
 << endl;
}

void videoListType::videoSetCopiesInStock(string title, int num)
{
 bool found = false;
 nodeType<videoType> *location;

 searchVideoList(title, found, location);

 if (found)
 location->info.setCopiesInStock(num);
 else
 cout << "The store does not carry " << title
 << endl;
}

bool videoListType::videoSearch(string title) const
{
 bool found = false;
 nodeType<videoType> *location;

 searchVideoList(title, found, location);

 return found;
}

```

```

void videoListType::videoPrintTitle() const
{
 nodeType<videoType>* current;

 current = first;
 while (current != NULL)
 {
 current->info.printTitle();
 current = current->link;
 }
}

```

## PART 2: CUSTOMER COMPONENT

**Customer Object** The customer object stores information about a customer, such as the first name, last name, account number, and a list of videos rented by the customer.

Every customer is a person. We have already designed the `class personType` in Example 12-9 (Chapter 12) and described the necessary operations on the name of a person. Therefore, we can derive the `class customerType` from the `class personType` and add the additional members that we need. First, however, we must redefine the `class personType` to take advantage of the new features of object-oriented design that you have learned, such as operator overloading, and then derive the `class customerType`.

Recall that the basic operations on an object of type `personType` are:

1. Print the name.
2. Set the name.
3. Show the first name.
4. Show the last name.

Similarly, the basic operations on an object of type `customerType` are:

1. Print the name, account number, and the list of rented videos.
2. Set the name and the account number.
3. Rent a video; that is, add the rented video to the list.
4. Return a video; that is, delete the rented video from the list.
5. Show the account number.

The details of implementing the customer component are left as an exercise for you. (See Programming Exercise 14 at the end of this chapter.)

**Main Program** We will now write the main program to test the video object. We assume that the necessary data for the videos are stored in a file. We will open the file and create the

list of videos owned by the video store. The data in the input file is in the following form:

```
video title (that is, the name of the movie)
movie star1
movie star2
movie producer
movie director
movie production co.
number of copies
.
.
.
```

We will write a function, `createVideoList`, to read the data from the input file and create the list of videos. We will also write a function, `displayMenu`, to show the different choices—such as check in a movie or check out a movie—that the user can make. The algorithm of the function `main` is:

1. Open the input file.  
If the input file does not exist, exit the program.
2. Create the list of videos (`createVideoList`).
3. Show the menu (`displayMenu`).
4. While not done  
Perform various operations.

Opening the input file is straightforward. Let us describe Steps 2 and 3, which are accomplished by writing two separate functions: `createVideoList` and `displayMenu`.

**`createVideoList`** This function reads the data from the input file and creates a linked list of videos. Because the data will be read from a file and the input file was opened in the function `main`, we pass the input file pointer to this function. We also pass the video list pointer, declared in the function `main`, to this function. Both parameters are reference parameters. Next, we read the data for each video and then insert the video in the list. The general algorithm is:

- a. Read the data and store it in a video object.
- b. Insert the video in the list.
- c. Repeat steps a and b for each video's data in the file.

**`displayMenu`** This function informs the user what to do. It contains the following output statements:

Select one of the following:

1. To check whether the store carries a particular video
2. To check out a video

3. To check in a video
4. To check whether a particular video is in stock
5. To print only the titles of all the videos
6. To print a list of all the videos
9. To exit

In pseudocode, Step 4 (of the main program) is:

```

a. get choice
b.
 while (choice != 9)
 {
 switch (choice)
 {
 case 1:
 a. get the movie name
 b. search the video list
 c. if found, report success
 else report "failure"
 break;
 case 2:
 a. get the movie name
 b. search the video list
 c. if found, check out the video
 else report "failure"
 break;
 case 3:
 a. get the movie name
 b. search the video list
 c. if found, check in video
 else report "failure"
 break;
 case 4:
 a. get the movie name
 b. search the video list
 c. if found
 if number of copies > 0
 report "success"
 else
 report "currently out of stock"
 else report "failure"
 break;
 case 5:
 print the titles of the videos
 break;
 case 6:
 print all the videos in the store
 break;
 default: bad selection
 } //end switch
 }

```

```

 displayMenu();
 get choice;
 } //end while

```

PROGRAM  
LISTING

```

/*****
// Author: D.S. Malik
//
// This program uses the classes videoType and videoListType to
// create a list of videos for a video store. It also performs
// basic operations such as check in and check out videos.
*****/

#include <iostream>
#include <fstream>
#include <string>
#include "videoType.h"
#include "videoListType.h"

using namespace std;

void createVideoList(ifstream& infile,
 videoListType& videoList);
void displayMenu();

int main()
{
 videoListType videoList;
 int choice;
 char ch;
 string title;

 ifstream infile;

 //open the input file
 infile.open("videoDat.txt");
 if (!infile)
 {
 cout << "The input file does not exist. "
 << "The program terminates!!!" << endl;
 return 1;
 }

 //create the video list
 createVideoList(infile, videoList);
 infile.close();

 //show the menu
 displayMenu();
 cout << "Enter your choice: ";
 cin >> choice; //get the request
 cin.get(ch);
 cout << endl;

```

```

 //process the requests
while (choice != 9)
{
 switch (choice)
 {
 case 1:
 cout << "Enter the title: ";
 getline(cin, title);
 cout << endl;

 if (videoList.videoSearch(title))
 cout << "The store carries " << title
 << endl;
 else
 cout << "The store does not carry "
 << title << endl;
 break;

 case 2:
 cout << "Enter the title: ";
 getline(cin, title);
 cout << endl;

 if (videoList.videoSearch(title))
 {
 if (videoList.isVideoAvailable(title))
 {
 videoList.videoCheckOut(title);
 cout << "Enjoy your movie: "
 << title << endl;
 }
 else
 cout << "Currently " << title
 << " is out of stock." << endl;
 }
 else
 cout << "The store does not carry "
 << title << endl;
 break;

 case 3:
 cout << "Enter the title: ";
 getline(cin, title);
 cout << endl;

 if (videoList.videoSearch(title))
 {
 videoList.videoCheckIn(title);
 cout << "Thanks for returning "
 << title << endl;
 }
 }
}

```

```

 else
 cout << "The store does not carry "
 << title << endl;
 break;

 case 4:
 cout << "Enter the title: ";
 getline(cin, title);
 cout << endl;

 if (videoList.videoSearch(title))
 {
 if (videoList.isVideoAvailable(title))
 cout << title << " is currently in "
 << "stock." << endl;
 else
 cout << title << " is currently out "
 << "of stock." << endl;
 }
 else
 cout << "The store does not carry "
 << title << endl;
 break;

 case 5:
 videoList.videoPrintTitle();
 break;

 case 6:
 videoList.print();
 break;

 default:
 cout << "Invalid selection." << endl;
} //end switch

displayMenu(); //display menu

cout << "Enter your choice: ";
cin >> choice; //get the next request
cin.get(ch);
cout << endl;
} //end while

return 0;
}

```

```

void createVideoList(ifstream& infile,
 videoListType& videoList)
{
 string title;
 string star1;
 string star2;
 string producer;
 string director;
 string productionCo;

 char ch;
 int inStock;

 videoType newVideo;

 getline(infile, title);

 while (infile)
 {
 getline(infile, star1);
 getline(infile, star2);
 getline(infile, producer);
 getline(infile, director);
 getline(infile, productionCo);
 infile >> inStock;
 infile.get(ch);
 newVideo.setVideoInfo(title, star1, star2, producer,
 director, productionCo, inStock);
 videoList.insertFirst(newVideo);

 getline(infile, title);
 } //end while
} //end createVideoList

void displayMenu()
{
 cout << "Select one of the following:" << endl;
 cout << "1: To check whether the store carries a "
 << "particular video." << endl;
 cout << "2: To check out a video." << endl;
 cout << "3: To check in a video." << endl;
 cout << "4: To check whether a particular video is "
 << "in stock." << endl;
 cout << "5: To print only the titles of all the videos."
 << endl;
 cout << "6: To print a list of all the videos." << endl;
 cout << "9: To exit" << endl;
} //end displayMenu

```

## QUICK REVIEW

---


1. A linked list is a list of items, called nodes, in which the order of the nodes is determined by the address, called a link, stored in each node.
2. The pointer to a linked list—that is, the pointer to the first node in the list—is stored in a separate location called the head or first.
3. A linked list is a dynamic data structure.
4. The length of a linked list is the number of nodes in the list.
5. Item insertion and deletion from a linked list do not require data movement; only the pointers are adjusted.
6. A (single) linked list is traversed in only one direction.
7. The search on a linked list is sequential.
8. The first (or head) pointer of a linked list is always fixed, pointing to the first node in the list.
9. To traverse a linked list, the program must use a pointer different than the head pointer of the list, initialized to the first node in the list.
10. In a doubly linked list, every node has two links: one points to the next node, and one points to the previous node.
11. A doubly linked list can be traversed in either direction.
12. In a doubly linked list, item insertion and deletion require the adjustment of two pointers in a node.
13. A linked list in which the last node points to the first node is called a circular linked list.

## EXERCISES

---

1. Mark the following statements as true or false.
  - a. In a linked list, the order of the elements is determined by the order in which the nodes were created to store the elements.
  - b. In a linked list, memory allocated for the nodes is sequential.
  - c. A single linked list can be traversed in either direction.
  - d. In a linked list, nodes are always inserted either at the beginning or the end because a linked list is not a random-access data structure.
2. Describe the two typical components of a single linked list node.
3. What is stored in the link field of the last node of a nonempty single linked list?
4. Suppose that `first` is a pointer to a linked list. What is stored in `first`?
5. Suppose that the fourth node of a linked list is to be deleted, and `p` points to the fourth node? Why do you need a pointer to the third node of the linked list?

Consider the linked list shown in Figure 18-50. Assume that the nodes are in the usual `info-link` form. Use this list to answer Exercises 6 through 12. If necessary, declare additional variables. (Assume that `list`, `p`, `s`, `A`, and `B` are pointers of type `nodeType`.)



**FIGURE 18-50** Linked list for exercises 6 through 12

6. What is the output of each of the following C++ statements?
  - a. `cout << list->info;`
  - b. `cout << A->info;`
  - c. `cout << B->link->info;`
  - d. `cout << list->link->link->info;`
7. What is the value of each of the following relational expressions?
  - a. `list->info >= 18`
  - b. `list->link == A`
  - c. `A->link->info == 16`
  - d. `B->link == NULL`
  - e. `list->info == 18`
8. Mark each of the following statements as valid or invalid. If a statement is invalid, explain why.
  - a. `A = B;`
  - b. `list->link = A->link;`
  - c. `list->link->info = 45;`
  - d. `*list = B;`
  - e. `*A = *B;`
  - f. `B = A->link->info;`
  - g. `A->info = B->info;`
  - h. `list = B->link->link;`
  - i. `B = B->link->link->link;`

9. Write C++ statements to do the following.
  - a. Make **A** point to the node containing **info 23**.
  - b. Make **list** point to the node containing **16**.
  - c. Make **B** point to the last node in the list.
  - d. Make **list** point to an empty list.
  - e. Set the value of the node containing **25** to **35**.
  - f. Create and insert the node with **info 10** after the node pointed to by **A**.
  - g. Delete the node with **info 23**. Also, deallocate the memory occupied by this node.

10. What is the output of the following C++ code?

```
p = list;

while (p != NULL)
 cout << p->info << " ";
 p = p->link;
cout << endl;
```

11. If the following C++ code is valid, show the output. If it is invalid, explain why.

```
s = A;
p = B;
s->info = B;
p = p->link;
cout << s->info << " " << p->info << endl;
```

12. If the following C++ code is valid, show the output. If it is invalid, explain why.

```
p = A;
p = p->link;
s = p;
p->link = NULL;
s = s->link;
cout << p->info << " " << s->info << endl;
```

13. Show what is produced by the following C++ code. Assume the node is in the usual **info-link** form with the **info** of type **int**. (**list** and **ptr** are pointers of type **nodeType**.)

```
list = new NodeType;
list->info = 10;
ptr = new NodeType;
ptr->info = 13;
ptr->link = NULL;
list->link = ptr;
ptr = new NodeType;
ptr->info = 18;
ptr->link = list->link;
list->link = ptr;
```

```
cout << list->info << " " << ptr->info << " ";
ptr = ptr->link;
cout << ptr->info << endl;
```

14. Show what is produced by the following C++ code. Assume the node is in the usual **info-link** form with the **info** of type **int**. (**list** and **ptr** are pointers of type **nodeType**.)

```
list = new nodeType;
list->info = 20;
ptr = new nodeType;
ptr->info = 28;
ptr->link = NULL;
list->link = ptr;
ptr = new nodeType;
ptr->info = 30;
ptr->link = list;
list = ptr;
ptr = new nodeType;
ptr->info = 42;
ptr->link = list->link;
list->link = ptr;
ptr = list;
while (ptr != NULL)
{
 cout << ptr->info << endl;
 ptr = ptr->link;
}
```

15. Assume that the node of a linked list is in the usual **info-link** form with the **info** of type **int**. The following data, as described in parts (a) to (d), is to be inserted into an initially linked list: 72, 43, 8, 12. Suppose that **head** is a pointer of type **nodeType**. After the linked list is created, **head** should point to the first node of the list. Declare additional variables as you need them. Write the C++ code to create the linked list. After the linked list is created, write a code to print the list. What is the output of your code?

- a. Insert 72 into an empty linked list.
- b. Insert 43 before 72.
- c. Insert 8 at the end of the list.
- d. Insert 12 after 43.

16. Assume that the node of a linked list is in the usual **info-link** form with the **info** of type **int**. (**list** and **ptr** are pointers of type **nodeType**.) The following code creates a linked list.

```
ptr = new nodeType;
ptr->info = 16;
list = new nodeType;
list->info = 25;
list->link = ptr;
ptr = new nodeType;
```

```
ptr->info = 12;
ptr->link = NULL;
list->link->link = ptr;
```

Use the linked list created by this code to answer the following questions. (These questions are independent of each other.) Declare additional pointers if you need them.

- a. Which pointer points to the first node of the linked list?
  - b. Determine the order of the nodes of the linked list.
  - c. Write a C++ code that creates and inserts a node with **info 45** after the node with **info 16**.
  - d. Write a C++ code that creates and inserts a node with **info 58** before the node with **info 25**. Does this require you to change the value of the pointer that was pointing to the first node of the linked list?
  - e. Write a C++ code that deletes the node with **info 25**. Does this require you to change the value of the pointer that was pointing to the first node of the linked list?
17. Consider the following C++ statements. (The `class unorderedLinkedList` is as defined in this chapter.)

```
unorderedLinkedList<int> list;

list.insertFirst(15);
list.insertLast(28);
list.insertFirst(30);
list.insertFirst(2);
list.insertLast(45);
list.insertFirst(38);
list.insertLast(25);
list.deleteNode(30);
list.insertFirst(18);
list.deleteNode(28);
list.deleteNode(12);
list.print();
```

What is the output of this program segment?

18. Suppose the input is:
- ```
18 30 4 32 45 36 78 19 48 75 -999
```

What is the output of the following C++ code? (The `class unorderedLinkedList` is as defined in this chapter.)

```
unorderedLinkedList<int> list;
unorderedLinkedList<int> copyList;
int num;

cin >> num;
while (num != -999)
```

```

{
    if (num % 5 == 0 || num % 5 == 3)
        list.insertFirst(num);
    else
        list.insertLast(num);
    cin >> num;
}

list.print();
cout << endl;

copyList = list;

copyList.deleteNode(78);
copyList.deleteNode(35);

cout << "Copy List = ";
copyList.print();
cout << endl;

```

19. Draw the UML diagram of the **class** `doublyLinkedList` as discussed in this chapter.
20. Draw the UML diagram of the **class** `videoType` of the Video Store programming example.
21. Draw the UML diagram of the **class** `videoListType` of the Video Store programming example.

PROGRAMMING EXERCISES

1. (**Online Address Book revisited**) Programming Exercise 6 in Chapter 13 could handle a maximum of only 500 entries. Using linked lists, redo the program to handle as many entries as required. Add the following operations to your program:
 - a. Add or delete a new entry to the address book.
 - b. Allow the user to save the data in the address book.
2. Extend the **class** `linkedListType` by adding the following operations:
 - a. Find and delete the node with the smallest `info` in the list. (Delete only the first occurrence and traverse the list only once.)
 - b. Find and delete all occurrences of a given `info` from the list. (Traverse the list only once.)

Add these as abstract functions in the **class** `linkedListType` and provide the definitions of these functions in the **class** `unorderedLinkedList`. Also, write a program to test these functions.

3. Extend the `class linkedListType` by adding the following operations:
 - a. Write a function that returns the info of the k^{th} element of the linked list. If no such element exists, terminate the program.
 - b. Write a function that deletes the k^{th} element of the linked list. If no such element exists, terminate the program.

Provide the definitions of these functions in the `class linkedListType`. Also, write a program to test these functions. (Use either the `class unorderedLinkedList` or the `class orderedLinkedList` to test your function.)

4. **(Printing a single linked list backward)** Include the functions `reversePrint` and `recursiveReversePrint`, as discussed in this chapter, in the `class linkedListType`. Also, write a program function to print a (single) linked list backward. (Use either the `class unorderedLinkedList` or the `class orderedLinkedList` to test your function.)
5. **(Dividing a linked list into two sublists of almost equal sizes)**
 - a. Add the operation `divideMid` to the `class linkedListType` as follows:

```
void divideMid(linkedListType<Type> &sublist);
//This operation divides the given list into two sublists
//of (almost) equal sizes.
//Postcondition: first points to the first node and last
//                points to the last node of the first
//                sublist.
//                sublist.first points to the first node
//                and sublist.last points to the last node
//                of the second sublist.
```

Consider the following statements:

```
unorderedLinkedList<int> myList;
unorderedLinkedList<int> subList;
```

Suppose `myList` points to the list with elements 34 65 27 89 12 (in this order). The statement:

```
myList.divideMid(subList);
```

divides `myList` into two sublists: `myList` points to the list with the elements 34 65 27, and `subList` points to the sublist with the elements 89 12.

- b. Write the definition of the function template to implement the operation `divideMid`. Also, write a program to test your function.
6. **(Splitting a linked list, at a given node, into two sublists)**

- a. Add the following operation to the `class` `linkedListType`:

```
void divideAt(linkedListType<Type> &secondList,
             const Type& item);
//Divide the list at the node with the info item into two
//sublists.
//Postcondition: first and last point to the first and
//               last nodes of the first sublist.
//               secondList.first and secondList.last
//               point to the first and last nodes of the
//               second sublist.
```

Consider the following statements:

```
unorderedLinkedList<int> myList;
unorderedLinkedList<int> otherList;
```

Suppose `myList` points to the list with the elements 34 65 18 39 27 89 12 (in this order). The statement:

```
myList.divideAt(otherList, 18);
```

divides `myList` into two sublists: `myList` points to the list with the elements 34 65, and `otherList` points to the sublist with the elements 18 39 27 89 12.

- b. Write the definition of the function template to implement the operation `divideAt`. Also, write a program to test your function.
7. a. Add the following operation to the `class` `orderedLinkedList`:

```
void mergeLists(orderedLinkedList<Type> &list1,
               orderedLinkedList<Type> &list2);
//This function creates a new list by merging the
//elements of list1 and list2.
//Postcondition: first points to the merged list
//               list1 and list2 are empty
```

Consider the following statements:

```
orderedLinkedList<int> newList;
orderedLinkedList<int> list1;
orderedLinkedList<int> list2;
```

Suppose `list1` points to the list with the elements 2 6 7, and `list2` points to the list with the elements 3 5 8. The statement:

```
newList.mergeLists(list1, list2);
```

creates a new linked list with the elements in the order 2 3 5 6 7 8, and the object `newList` points to this list. Also, after the preceding statement executes, `list1` and `list2` are empty.

- b. Write the definition of the function template `mergeLists` to implement the operation `mergeLists`.
8. The function `insert` of the `class orderedLinkedList` does not check if the item to be inserted is already in the list; that is, it does not check for duplicates. Rewrite the definition of the function `insert` so that before inserting the item, it checks whether the item to be inserted is already in the list. If the item to be inserted is already in the list, the function outputs an appropriate error message. Also, write a program to test your function.
9. In this chapter, the class to implement the nodes of a linked list is defined as a `struct`. The following rewrites the definition of the `struct nodeType` so that it is declared as a class and the member variables are `private`.

```
template <class Type>
class nodeType
{
public:
    const nodeType<Type>& operator=(const nodeType<Type>&);
    //Overload the assignment operator.

    void setInfo(const Type& elem);
    //Function to set the info of the node.
    //Postcondition: info = elem;

    Type getInfo() const;
    //Function to return the info of the node.
    //Postcondition: The value of info is returned.

    void setLink(nodeType<Type> *ptr);
    //Function to set the link of the node.
    //Postcondition: link = ptr;

    nodeType<Type>* getLink() const;
    //Function to return the link of the node.
    //Postcondition: The value of link is returned.

    nodeType();
    //Default constructor
    //Postcondition: link = NULL;

    nodeType(const Type& elem, nodeType<Type> *ptr);
    //Constructor with parameters
    //Sets info to point to the object elem points to, and
    //link is set to point to the object ptr points to.
    //Postcondition: info = elem; link = ptr
```

```

nodeType(const nodeType<Type> &otherNode);
    //Copy constructor
~nodeType();
    //Destructor

private:
    Type info;
    nodeType<Type> *link;
};

```

Write the definitions of the member functions of the `class` `nodeType`. Also, write a program to test your class.

10. Programming Exercise 9 asks you to redefine the class to implement the nodes of a linked list so that the instance variables are `private`. Therefore, the `class` `linkedListType` and its derived `classes` `unorderedLinkedList` and `orderedLinkedList` can no longer directly access the instance variables of the `class` `nodeType`. Rewrite the definitions of these classes so that they use the member functions of the `class` `nodeType` to access the `info` and `link` fields of a node. Also, write programs to test various operations of the classes `unorderedLinkedList` and `orderedLinkedList`.
11. Write the definitions of the function `copyList`, the copy constructor, and the function to overload the assignment operator for the `class` `doublyLinkedList`.
12. Write a program to test various operations of the `class` `doublyLinkedList`.
13. (**Circular linked lists**) This chapter defined and identified various operations on a circular linked list.
 - a. Write the definitions of the `class` `circularLinkedList` and its member functions. (You may assume that the elements of the circular linked list are in ascending order.)
 - b. Write a program to test various operations of the class defined in (a).
14. (**Video Store programming example**)
 - a. Complete the design and implementation of the `class` `customerType` defined in the Video Store programming example.
 - b. Design and implement the `class` `customerListType` to create and maintain a list of customers for the video store.
15. (**Video Store programming example**) Complete the design and implementation of the video store program. In other words, write a program that uses the classes designed in the Video Store programming example and in Programming Exercise 14 to make a video store operational.

16. Extend the `class linkedListType` by adding the following function:

```
void rotate();  
//Function to remove the first node of a linked list and put it  
//at the end of the linked list.
```

Also write a program to test your function. Use the `class unorderedLinkedList` to create a linked list.

17. Write a program that prompts the user to input a string and then outputs the string in the pig Latin form. The rules for converting a string into pig Latin form are described in Programming Example: Pig Latin Strings of Chapter 8. Your program must store the characters of a string into a linked and use the function `rotate`, as described in Programming Exercise 16, to rotate the string.



19

CHAPTER

STACKS AND QUEUES

IN THIS CHAPTER, YOU WILL:

- Learn about stacks
- Examine various stack operations
- Learn how to implement a stack as an array
- Learn how to implement a stack as a linked list
- Discover stack applications
- Learn how to use a stack to remove recursion
- Learn about queues
- Examine various queue operations
- Learn how to implement a queue as an array
- Learn how to implement a queue as a linked list
- Discover queue applications

This chapter discusses two very useful data structures, stacks and queues. Both stacks and queues have numerous applications in computer science.

Stacks

Suppose that you have a program with several functions. To be specific, suppose that you have functions A, B, C, and D in your program. Now suppose that function A calls function B, function B calls function C, and function C calls function D. When function D terminates, control goes back to function C; when function C terminates, control goes back to function B; and when function B terminates, control goes back to function A. During program execution, how do you think the computer keeps track of the function calls? What about recursive functions? How does the computer keep track of the recursive calls? In Chapter 18, we designed a recursive function to print a linked list backward. What if you want to write a nonrecursive algorithm to print a linked list backward?

This section discusses the data structure called the **stack**, which the computer uses to implement function calls. You can also use stacks to convert recursive algorithms into nonrecursive algorithms, especially recursive algorithms that are not tail recursive. Stacks have numerous applications in computer science. After developing the tools necessary to implement a stack, we will examine some applications of stacks.

A stack is a list of homogeneous elements in which the addition and deletion of elements occur only at one end, called the **top** of the stack. For example, in a cafeteria, the second tray in a stack of trays can be removed only if the first tray has been removed. For another example, to get to your favorite computer science book, which is underneath your math and history books, you must first remove the math and history books. After removing these books, the computer science book becomes the top book—that is, the top element of the stack. Figure 19-1 shows some examples of stacks.




FIGURE 19-1 Various types of stacks

The elements at the bottom of the stack have been in the stack the longest. The top element of the stack is the last element added to the stack. Because the elements are added and removed from one end (that is, the top), it follows that the item that is added last will be removed first. For this reason, a stack is also called a **Last In First Out (LIFO)** data structure.

Stack: A data structure in which the elements are added and removed from one end only; a Last In First Out (LIFO) data structure.

Now that you know what a stack is, let us see what kinds of operations can be performed on a stack. Because new items can be added to the stack, we can perform the add operation, called **push**, to add an element onto the stack. Similarly, because the top item can be retrieved and/or removed from the stack, we can perform the operation **top** to retrieve the top element of the stack and the operation **pop** to remove the top element from the stack.

The **push**, **top**, and **pop** operations work as follows: Suppose there are boxes lying on the floor that need to be stacked on a table. Initially, all of the boxes are on the floor, and the stack is empty (see Figure 19-2).




FIGURE 19-2 Empty stack

First, we push box **A** onto the stack. After the push operation, the stack is as shown in Figure 19-3(a).




FIGURE 19-3 Stack operations

We then push box **B** onto the stack. After this push operation, the stack is as shown in Figure 19-3(b). Next, we push box **C** onto the stack. After this push operation, the stack is as shown in Figure 19-3(c). Next, we look, that is, peek, at the top element of the stack. After this operation, the stack is unchanged and shown in Figure 19-3(d). We then push box **D** onto the stack. After this push operation, the stack is as shown in Figure 19-3(e). Next, we pop the stack. After the pop operation, the stack is as shown in Figure 19-3(f).

An element can be removed from the stack only if there is something in the stack, and an element can be added to the stack only if there is room. The two operations that immediately follow from **push**, **top**, and **pop** are **isFullStack** (checks whether the stack is full) and **isEmptyStack** (checks whether the stack is empty). Because a stack keeps changing as we add and remove elements, the stack must be empty before we first start using it. Thus, we need another operation, called **initializeStack**, which initializes the stack to an empty state. Therefore, to successfully implement a stack, we need at least these six operations, which are described in the next section. We might also need other operations on a stack, depending on the specific implementation.

Stack Operations

- **initializeStack**: Initializes the stack to an empty state.
- **isEmptyStack**: Determines whether the stack is empty. If the stack is empty, it returns the value **true**; otherwise, it returns the value **false**.
- **isFullStack**: Determines whether the stack is full. If the stack is full, it returns the value **true**; otherwise, it returns the value **false**.
- **push**: Adds a new element to the top of the stack. The input to this operation consists of the stack and the new element. Prior to this operation, the stack must exist and must not be full.
- **top**: Returns the top element of the stack. Prior to this operation, the stack must exist and must not be full.
- **pop**: Removes the top element of the stack. Prior to this operation, the stack must exist and must not be empty.

The following abstract **class** **stackADT** defines these operations as an ADT.

```
template <class Type>
class stackADT
{
public:
    virtual void initializeStack() = 0;
        //Method to initialize the stack to an empty state.
        //Postcondition: Stack is empty.

    virtual bool isEmptyStack() const = 0;
        //Function to determine whether the stack is empty.
        //Postcondition: Returns true if the stack is empty,
        //                otherwise returns false.
```

```

virtual bool isFullStack() const = 0;
    //Function to determine whether the stack is full.
    //Postcondition: Returns true if the stack is full,
    //               otherwise returns false.

virtual void push(const Type& newItem) = 0;
    //Function to add newItem to the stack.
    //Precondition: The stack exists and is not full.
    //Postcondition: The stack is changed and newItem
    //               is added to the top of the stack.

virtual Type top() const = 0;
    //Function to return the top element of the stack.
    //Precondition: The stack exists and is not empty.
    //Postcondition: If the stack is empty, the program
    //               terminates; otherwise, the top element
    //               of the stack is returned.

virtual void pop() = 0;
    //Function to remove the top element of the stack.
    //Precondition: The stack exists and is not empty.
    //Postcondition: The stack is changed and the top
    //               element is removed from the stack.
};

```

Figure 19-4 shows the UML class diagram of the `class` `stackADT`.




FIGURE 19-4 UML class diagram of the `class` `stackADT`

We now consider the implementation of our abstract stack data structure. Because all of the elements of a stack are of the same type, a stack can be implemented as either an array or a linked structure. Both implementations are useful and are discussed in this chapter.

Implementation of Stacks as Arrays

Because all of the elements of a stack are of the same type, you can use an array to implement a stack. The first element of the stack can be put in the first array slot, the second element of the stack in the second array slot, and so on. The top of the stack is the index of the last element added to the stack.

In this implementation of a stack, stack elements are stored in an array, and an array is a random access data structure; that is, you can directly access any element of the array. However, by definition, a stack is a data structure in which the elements are accessed (popped or pushed) at only one end—that is, a Last In First Out data structure. Thus, a stack element is accessed only through the top, not through the bottom or middle. This feature of a stack is extremely important and must be recognized in the beginning.

To keep track of the top position of the array, we can simply declare another variable called `stackTop`.

The following `class`, `stackType`, implements the functions of the abstract `class` `stackADT`. By using a pointer, we can dynamically allocate arrays, so we will leave it for the user to specify the size of the array (that is, the stack size). We assume that the default stack size is 100. Because the `class` `stackType` has a pointer member variable (the pointer to the array to store the stack elements), we must overload the assignment operator and include the copy constructor and destructor. Moreover, we give a generic definition of the stack. Depending on the specific application, we can pass the stack element type when we declare a stack object.

```
template <class Type>
class stackType: public stackADT<Type>
{
public:
    const stackType<Type>& operator=(const stackType<Type>&);
    //Overload the assignment operator.

    void initializeStack();
    //Function to initialize the stack to an empty state.
    //Postcondition: stackTop = 0;

    bool isEmptyStack() const;
    //Function to determine whether the stack is empty.
    //Postcondition: Returns true if the stack is empty,
    //               otherwise returns false.

    bool isFullStack() const;
    //Function to determine whether the stack is full.
    //Postcondition: Returns true if the stack is full,
    //               otherwise returns false.

    void push(const Type& newItem);
    //Function to add newItem to the stack.
    //Precondition: The stack exists and is not full.
    //Postcondition: The stack is changed and newItem
    //               is added to the top of the stack.
```

```

Type top() const;
    //Function to return the top element of the stack.
    //Precondition: The stack exists and is not empty.
    //Postcondition: If the stack is empty, the program
    //                terminates; otherwise, the top element
    //                of the stack is returned.

void pop();
    //Function to remove the top element of the stack.
    //Precondition: The stack exists and is not empty.
    //Postcondition: The stack is changed and the top
    //                element is removed from the stack.

stackType(int stackSize = 100);
    //Constructor
    //Create an array of the size stackSize to hold
    //the stack elements. The default stack size is 100.
    //Postcondition: The variable list contains the base
    //                address of the array, stackTop = 0, and
    //                maxStackSize = stackSize.

stackType(const stackType<Type>& otherStack);
    //Copy constructor

~stackType();
    //Destructor
    //Remove all the elements from the stack.
    //Postcondition: The array (list) holding the stack
    //                elements is deleted.

private:
    int maxStackSize; //variable to store the maximum stack size
    int stackTop;     //variable to point to the top of the stack
    Type *list;       //pointer to the array that holds the
                     //stack elements

    void copyStack(const stackType<Type>& otherStack);
        //Function to make a copy of otherStack.
        //Postcondition: A copy of otherStack is created and
        //                assigned to this stack.
};

```

Figure 19-5 shows the UML class diagram of the `class` `stackType`.




FIGURE 19-5 UML class diagram of the `class` `stackType`

NOTE

Because C++ arrays begin with the index 0, we need to distinguish between the value of `stackTop` and the array position indicated by `stackTop`. If `stackTop` is 0, the stack is empty; if `stackTop` is nonzero, then the stack is nonempty and the top element of the stack is given by `stackTop - 1`.

Notice that the function `copyStack` is included as a `private` member. This is because we want to use this function only to implement the copy constructor and overload the assignment operator. To copy a stack into another stack, the program can use the assignment operator.

Figure 19-6 shows this data structure, wherein `stack` is an object of type `stackType`. Note that `stackTop` can range from 0 to `maxStackSize`. If `stackTop` is nonzero, then `stackTop - 1` is the index of the `stackTop` element of the stack. Suppose that `maxStackSize = 100`.




FIGURE 19-6 Example of a stack

Note that the pointer `list` contains the base address of the array (holding the stack elements)—that is, the address of the first array component. Next, we discuss how to implement the member functions of the `class stackType`.

Initialize Stack

Let us consider the `initializeStack` operation. Because the value of `stackTop` indicates whether the stack is empty, we can simply set `stackTop` to 0 to initialize the stack (see Figure 19-7).




FIGURE 19-7 Empty stack

The definition of the function `initializeStack` is:

```
template <class Type>
void stackType<Type>::initializeStack()
{
    stackTop = 0;
} //end initializeStack
```

Empty Stack

We have seen that the value of `stackTop` indicates whether the stack is empty. If `stackTop` is 0, the stack is empty; otherwise, the stack is not empty. The definition of the function `isEmptyStack` is:

```
template <class Type>
bool stackType<Type>::isEmptyStack() const
{
    return (stackTop == 0);
} //end isEmptyStack
```

Full Stack

Next, we consider the operation `isFullStack`. It follows that the stack is full if `stackTop` is equal to `maxStackSize`. The definition of the function `isFullStack` is:

```
template <class Type>
bool stackType<Type>::isFullStack() const
{
    return (stackTop == maxStackSize);
} //end isFullStack
```


Push

Adding, or pushing, an element onto the stack is a two-step process. Recall that the value of `stackTop` indicates the number of elements in the stack, and `stackTop - 1` gives the position of the top element of the stack. Therefore, the `push` operation is as follows:


1. Store the `newItem` in the array component indicated by `stackTop`.
2. Increment `stackTop`.

Figures 19-8 and 19-9 illustrate the `push` operation.

Suppose that before the `push` operation, the stack is as shown in Figure 19-8.

FIGURE 19-8 Stack before pushing *y*

Assume `newItem` is 'y'. After the `push` operation, the stack is as shown in Figure 19-9.

FIGURE 19-9 Stack after pushing *y*

Using the previous algorithm, the definition of the function `push` is:

```
template <class Type>
void stackType<Type>::push(const Type& newItem)
{
    if (!isFullStack())
    {
        list[stackTop] = newItem;    //add newItem to the
                                     //top of the stack
        stackTop++; //increment stackTop
    }
    else
        cout << "Cannot add to a full stack." << endl;
} //end push
```

If we try to add a new item to a full stack, the resulting condition is called an **overflow**. Error checking for an overflow can be handled in different ways. One way is as shown previously. Or, we can check for an overflow before calling the function `push`, as shown next (assuming `stack` is an object of type `stackType`).

```
if (!stack.isFullStack())
    stack.push(newItem);
```

Return the Top Element

The operation `top` returns the top element of the stack. Its definition is:

```
template <class Type>
Type stackType<Type>::top() const
{
    assert(stackTop != 0);           //if stack is empty,
                                     //terminate the program
    return list[stackTop - 1];       //return the element of the
                                     //stack indicated by
                                     //stackTop - 1
} //end top
```

Pop

To remove, or `pop`, an element from the stack, we simply decrement `stackTop` by 1.

Figures 19-10 and 19-11 illustrate the `pop` operation.

Suppose that before the `pop` operation, the stack is as shown in Figure 19-10.




FIGURE 19-10 Stack before popping D

After the **pop** operation, the stack is as shown in Figure 19-11.




FIGURE 19-11 Stack after popping D

The definition of the function `pop` is:

```
template <class Type>
void stackType<Type>::pop()
{
    if (!isEmptyStack())
        stackTop--;           //decrement stackTop
    else
        cout << "Cannot remove from an empty stack." << endl;
} //end pop
```

If we try to remove an item from an empty stack, the resulting condition is called an **underflow**. Error checking for an underflow can be handled in different ways. One way is as shown in the definition of the function `pop`. Or, we can check for an underflow before calling the function `pop`, as shown next (assuming `stack` is an object of type `stackType`).

```
if (!stack.isEmptyStack())
    stack.pop();
```

Copy Stack

The function `copyStack` makes a copy of a stack. The stack to be copied is passed as a parameter to the function `copyStack`. We will, in fact, use this function to implement the copy constructor and overload the assignment operator. The definition of this function is:

```
template <class Type>
void stackType<Type>::copyStack(const stackType<Type>& otherStack)
{
    delete [] list;
    maxStackSize = otherStack.maxStackSize;
    stackTop = otherStack.stackTop;

    list = new Type[maxStackSize];

    //copy otherStack into this stack
    for (int j = 0; j < stackTop; j++)
        list[j] = otherStack.list[j];
} //end copyStack
```

Constructor and Destructor

The functions to implement the constructor and the destructor are straightforward. The constructor with parameters sets the stack size to the size specified by the user, sets `stackTop` to 0, and creates an appropriate array in which to store the stack elements. If the user does not specify the size of the array in which to store the stack elements, the constructor uses the default value, which is 100, to create an array of size 100. The destructor simply deallocates the memory occupied by the array (that is, the stack) and sets `stackTop` to 0. The definitions of the constructor and destructor are:

```

template <class Type>
stackType<Type>::stackType(int stackSize)
{
    if (stackSize <= 0)
    {
        cout << "Size of the array to hold the stack must "
              << "be positive." << endl;
        cout << "Creating an array of size 100." << endl;

        maxStackSize = 100;
    }
    else
        maxStackSize = stackSize;    //set the stack size to
                                     //the value specified by
                                     //the parameter stackSize

    stackTop = 0;                    //set stackTop to 0
    list = new Type[maxStackSize];   //create the array to
                                     //hold the stack elements
} //end constructor

template <class Type>
stackType<Type>::~~stackType() //destructor
{
    delete [] list; //deallocate the memory occupied
                  //by the array
} //end destructor

```

Copy Constructor

The copy constructor is called when a stack object is passed as a (value) parameter to a function. It copies the values of the member variables of the actual parameter into the corresponding member variables of the formal parameter. Its definition is:

```

template <class Type>
stackType<Type>::stackType(const stackType<Type>& otherStack)
{
    list = NULL;

    copyStack(otherStack);
} //end copy constructor

```

Overloading the Assignment Operator (=)

Recall that for classes with pointer member variables, the assignment operator must be explicitly overloaded. The definition of the function to overload the assignment operator for the `class` `stackType` is:

```

template <class Type>
const stackType<Type>& stackType<Type>::operator=
    (const stackType<Type>& otherStack)

```

```

{
    if (this != &otherStack) //avoid self-copy
        copyStack(otherStack);

    return *this;
} //end operator=

```

Stack Header File

Now that you know how to implement the stack operations, you can put the definitions of the class and the functions to implement the stack operations together to create the stack header file. For the sake of completeness, we next describe the header file. (To save space, only the definition of the class is shown; no documentation is provided.) Suppose that the name of the header file containing the definition of the `class stackType` is `myStack.h`. We will refer to this header file in any program that uses a stack.

```

//Header file: myStack.h

#ifndef H_stackType
#define H_stackType

#include <iostream>
#include <cassert>

#include "stackADT.h"

using namespace std;

template <class Type>
class stackType: public stackADT<Type>
{
public:
    const stackType<Type>& operator=(const stackType<Type>&);

    void initializeStack();

    bool isEmptyStack() const;

    bool isFullStack() const;

    void push(const Type& newItem);

    Type top() const;

    void pop();

    stackType(int stackSize = 100);

    stackType(const stackType<Type>& otherStack);

    ~stackType();

```

```

private:
    int maxStackSize; //variable to store the maximum stack size
    int stackTop;     //variable to point to the top of the stack
    Type *list;       //pointer to the array that holds the
                     //stack elements

    void copyStack(const stackType<Type>& otherStack);
};

template <class Type>
void stackType<Type>::initializeStack()
{
    stackTop = 0;
} //end initializeStack

template <class Type>
bool stackType<Type>::isEmptyStack() const
{
    return (stackTop == 0);
} //end isEmptyStack

template <class Type>
bool stackType<Type>::isFullStack() const
{
    return (stackTop == maxStackSize);
} //end isFullStack

template <class Type>
void stackType<Type>::push(const Type& newItem)
{
    if (!isFullStack())
    {
        list[stackTop] = newItem; //add newItem to the
                                   //top of the stack
        stackTop++; //increment stackTop
    }
    else
        cout << "Cannot add to a full stack." << endl;
} //end push

template <class Type>
Type stackType<Type>::top() const
{
    assert(stackTop != 0); //if stack is empty,
                           //terminate the program
    return list[stackTop - 1]; //return the element of the
                               //stack indicated by
                               //stackTop - 1
} //end top

template <class Type>
void stackType<Type>::pop()
{
    if (!isEmptyStack())
        stackTop--; //decrement stackTop
    else
        cout << "Cannot remove from an empty stack." << endl;
} //end pop

```

```

template <class Type>
stackType<Type>::stackType(int stackSize)
{
    if (stackSize <= 0)
    {
        cout << "Size of the array to hold the stack must "
              << "be positive." << endl;
        cout << "Creating an array of size 100." << endl;

        maxStackSize = 100;
    }
    else
        maxStackSize = stackSize;    //set the stack size to
                                     //the value specified by
                                     //the parameter stackSize

    stackTop = 0;                    //set stackTop to 0
    list = new Type[maxStackSize];   //create the array to
                                     //hold the stack elements
} //end constructor

template <class Type>
stackType<Type>::~~stackType() //destructor
{
    delete [] list; //deallocate the memory occupied
                   //by the array
} //end destructor

template <class Type>
void stackType<Type>::copyStack(const stackType<Type>& otherStack)
{
    delete [] list;
    maxStackSize = otherStack.maxStackSize;
    stackTop = otherStack.stackTop;

    list = new Type[maxStackSize];

    //copy otherStack into this stack
    for (int j = 0; j < stackTop; j++)
        list[j] = otherStack.list[j];
} //end copyStack

template <class Type>
stackType<Type>::stackType(const stackType<Type>& otherStack)
{
    list = NULL;

    copyStack(otherStack);
} //end copy constructor

template <class Type>
const stackType<Type>& stackType<Type>::operator=
    (const stackType<Type>& otherStack)
{
    if (this != &otherStack) //avoid self-copy
        copyStack(otherStack);
}

```

```

        return *this;
    } //end operator=

#endif

```

EXAMPLE 19-1

Before we give a programming example, let us first write a simple program that uses the `class` `stackType` and tests some of the stack operations. Among others, we will test the assignment operator and the copy constructor. The program and its output are as follows:

```

//Program to test the various operations of a stack

#include <iostream>
#include "myStack.h"

using namespace std;

void testCopyConstructor(stackType<int> otherStack);

int main()
{
    stackType<int> stack(50);
    stackType<int> copyStack(50);
    stackType<int> dummyStack(100);

    stack.initializeStack();
    stack.push(23);
    stack.push(45);
    stack.push(38);
    copyStack = stack; //copy stack into copyStack

    cout << "The elements of copyStack: ";

    while (!copyStack.isEmptyStack()) //print copyStack
    {
        cout << copyStack.top() << " ";
        copyStack.pop();
    }
    cout << endl;

    copyStack = stack;
    testCopyConstructor(stack); //test the copy constructor

    if (!stack.isEmptyStack())
        cout << "The original stack is not empty." << endl
            << "The top element of the original stack: "
            << copyStack.top() << endl;

    dummyStack = stack; //copy stack into dummyStack
    cout << "The elements of dummyStack: ";
}

```

```

    while (!dummyStack.isEmptyStack()) //print dummyStack
    {
        cout << dummyStack.top() << " ";
        dummyStack.pop();
    }
    cout << endl;

    return 0;
}

void testCopyConstructor(stackType<int> otherStack)
{
    if (!otherStack.isEmptyStack())
        cout << "otherStack is not empty." << endl
            << "The top element of otherStack: "
            << otherStack.top() << endl;
}

```

Sample Run:

```

The elements of copyStack: 38 45 23
otherStack is not empty.
The top element of otherStack: 38
The original stack is not empty.
The top element of the original stack: 38
The elements of dummyStack: 38 45 23

```

It is recommended that you do a walk-through of this program.

PROGRAMMING EXAMPLE: Highest GPA

In this example, we write a C++ program that reads a data file consisting of each student's GPA followed by the student's name. The program then prints the highest GPA and the names of all of the students who received that GPA. The program scans the input file only once. Moreover, we assume that there is a maximum of 100 students in the class.

Input The program reads an input file consisting of each student's GPA, followed by the student's name. Sample data is:

```

3.5 Bill
3.6 John
2.7 Lisa
3.9 Kathy
3.4 Jason
3.9 David
3.4 Jack

```

Output The highest GPA and all of the names associated with the highest GPA. For example, for the above data, the highest GPA is 3.9, and the students with that GPA are **Kathy** and **David**.

**PROBLEM
ANALYSIS
AND
ALGORITHM
DESIGN**

We read the first GPA and the name of the student. Because this data is the first item read, it is the highest GPA so far. Next, we read the second GPA and the name of the student. We then compare this (second) GPA with the highest GPA so far. Three cases arise:

1. The new GPA is greater than the highest GPA so far. In this case, we:
 - a. Update the value of the highest GPA so far.
 - b. Initialize the stack—that is, remove the names of the students from the stack.
 - c. Save the name of the student having the highest GPA so far in the stack.
2. The new GPA is equal to the highest GPA so far. In this case, we add the name of the new student to the stack.
3. The new GPA is smaller than the highest GPA so far. In this case, we discard the name of the student having this grade.

We then read the next GPA and the name of the student and repeat Steps 1 through 3. We continue this process until we reach the end of the input file.

From this discussion, it is clear that we need the following variables:

```
double GPA;           //variable to hold the current GPA
double highestGPA;    //variable to hold the highest GPA
string name;          //variable to hold the name of the student
stackType<string> stack(100); //object to implement the stack
```

The preceding discussion translates into the following algorithm:

1. Declare the variables and initialize stack.
2. Open the input file.
3. If the input file does not exist, exit the program.
4. Set the output of the floating-point numbers to a fixed decimal format with a decimal point and trailing zeroes. Also, set the precision to two decimal places.
5. Read the GPA and the student name.
6. **highestGPA = GPA;**

7. `while` (not end of file)
 - {
 - 7.1. `if` (GPA > highestGPA)
 - {
 - 7.1.1. `clearstack(stack);`
 - 7.1.2. `push(stack, student name);`
 - 7.1.3. `highestGPA = GPA;`
 - 7.2. `else`
 - `if` (GPA is equal to highestGPA)
 - `push(stack, student name);`
 - 7.3. Read GPA and student name;
 - }
8. Output the highest GPA.
9. Output the names of the students having the highest GPA.

PROGRAM LISTING

```

//*****
// Author: D.S. Malik
//
// This program uses the class myStack to determine the
// highest GPA from a list of students with their GPA.
// The program also outputs the names of the students
// who received the highest GPA.
//*****

#include <iostream>
#include <iomanip>
#include <fstream>
#include <string>

#include "myStack.h"

using namespace std;

int main()
{
    //Step 1
    double GPA;
    double highestGPA;
    string name;

    stackType<string> stack(100);

    ifstream infile;

```

```

infile.open("HighestGPAData.txt");           //Step 2

if (!infile)                                 //Step 3
{
    cout << "The input file does not "
        << "exist. Program terminates!"
        << endl;
    return 1;
}

cout << fixed << showpoint;                 //Step 4
cout << setprecision(2);                     //Step 4

infile >> GPA >> name;                       //Step 5

highestGPA = GPA;                             //Step 6

while (infile)                                //Step 7
{
    if (GPA > highestGPA)                     //Step 7.1
    {
        stack.initializeStack();             //Step 7.1.1

        if (!stack.isFullStack())            //Step 7.1.2
            stack.push(name);

        highestGPA = GPA;                     //Step 7.1.3
    }
    else if (GPA == highestGPA)               //Step 7.2
    {
        if (!stack.isFullStack())
            stack.push(name);
        else
        {
            cout << "Stack overflows. "
                << "Program terminates!"
                << endl;
            return 1; //exit program
        }
    }
    infile >> GPA >> name;                     //Step 7.3
}

cout << "Highest GPA = " << highestGPA
    << endl;                                   //Step 8
cout << "The students holding the "
    << "highest GPA are:" << endl;

while (!stack.isEmptyStack())                 //Step 9
{
    cout << stack.top() << endl;
    stack.pop();
}

```

```

        cout << endl;

    return 0;
}

```

Sample Run:

Input File (HighestGPAData.txt)

```

3.4 Randy
3.2 Kathy
2.5 Colt
3.4 Tom
3.8 Ron
3.8 Mickey
3.6 Peter
3.5 Donald
3.8 Cindy
3.7 Dome
3.9 Andy
3.8 Fox
3.9 Minnie
2.7 Gilda
3.9 Vinay
3.4 Danny

```

Output

```

Highest GPA = 3.90
The students holding the highest GPA are:
Vinay
Minnie
Andy

```

Note that the names of the students with the highest GPA are output in the reverse order, relative to the order they appear in the input, due to the fact that the top element of the stack is the last element added to the stack.

Linked Implementation of Stacks

Because an array size is fixed, in the array (linear) representation of a stack, only a fixed number of elements can be pushed onto the stack. If in a program the number of elements to be pushed exceeds the size of the array, the program may terminate in an error. We must overcome these problems.

We have seen that by using pointer variables, we can dynamically allocate and deallocate memory, and by using linked lists, we can dynamically organize data (such as an ordered list). Next, we will use these concepts to implement a stack dynamically.

Recall that in the linear representation of a stack, the value of `stackTop` indicates the number of elements in the stack, and the value of `stackTop - 1` points to the top item in the stack. With the help of `stackTop`, we can do several things: find the top element, check whether the stack is empty, and so on.

Similar to the linear representation, in a linked representation, `stackTop` is used to locate the top element in the stack. However, there is a slight difference. In the former case, `stackTop` gives the index of the array. In the latter case, `stackTop` gives the address (memory location) of the top element of the stack.

The following class implements the functions of the abstract `class stackADT`.

```
//Definition of the node
template <class Type>
struct nodeType
{
    Type info;
    nodeType<Type> *link;
};

template <class Type>
class linkedStackType: public stackADT<Type>
{
public:
    const linkedStackType<Type>& operator=
        (const linkedStackType<Type>&);
    //Overload the assignment operator.

    bool isEmptyStack() const;
    //Function to determine whether the stack is empty.
    //Postcondition: Returns true if the stack is empty;
    //                otherwise returns false.

    bool isFullStack() const;
    //Function to determine whether the stack is full.
    //Postcondition: Returns false.

    void initializeStack();
    //Function to initialize the stack to an empty state.
    //Postcondition: The stack elements are removed;
    //                stackTop = NULL;

    void push(const Type& newItem);
    //Function to add newItem to the stack.
    //Precondition: The stack exists and is not full.
    //Postcondition: The stack is changed and newItem
    //                is added to the top of the stack.
```

```

Type top() const;
    //Function to return the top element of the stack.
    //Precondition: The stack exists and is not empty.
    //Postcondition: If the stack is empty, the program
    //                terminates; otherwise, the top
    //                element of the stack is returned.
void pop();
    //Function to remove the top element of the stack.
    //Precondition: The stack exists and is not empty.
    //Postcondition: The stack is changed and the top
    //                element is removed from the stack.

linkedStackType();
    //Default constructor
    //Postcondition: stackTop = NULL;

linkedStackType(const linkedStackType<Type>& otherStack);
    //Copy constructor

~linkedStackType();
    //Destructor
    //Postcondition: All the elements of the stack are
    //                removed from the stack.

private:
    nodeType<Type> *stackTop; //pointer to the stack

    void copyStack(const linkedStackType<Type>& otherStack);
        //Function to make a copy of otherStack.
        //Postcondition: A copy of otherStack is created and
        //                assigned to this stack.
};

```

NOTE

In this linked implementation of stacks, the memory to store the stack elements is allocated dynamically. Logically, the stack is never full. The stack is full only if we run out of memory space. Therefore, in reality, the function `isFullStack` does not apply to linked implementation of stacks. However, the `class linkedStackType` must provide the definition of the function `isFullStack`, because it is defined in the parent abstract `class stackADT`.

We leave the UML class diagram of the `class linkedStackType` as an exercise for you. (See Exercise 26 at the end of this chapter.)

EXAMPLE 19-2

Suppose that `stack` is an object of type `linkedStackType`. Figure 19-12(a) shows an empty stack, and Figure 19-12(b) shows a nonempty stack.




FIGURE 19-12 Empty and nonempty linked stack

In Figure 19-12(b), the top element of the stack is C; that is, the last element pushed onto the stack is C.

Next, we discuss the definitions of the functions to implement the operations of a linked stack.

Default Constructor

The first operation that we consider is the default constructor. The default constructor initializes the stack to an empty state when a stack object is declared. Thus, this function sets `stackTop` to `NULL`. The definition of this function is:

```
template <class Type>
linkedStackType<Type>::linkedStackType()
{
    stackTop = NULL;
}
```

Empty Stack and Full Stack

The operations `isEmptyStack` and `isFullStack` are quite straightforward. The stack is empty if `stackTop` is `NULL`. Also, because the memory for a stack element is allocated and deallocated dynamically, the stack is never full. (The stack is full only if we run out of memory.) Thus, the function `isFullStack` always returns the value `false`. The definitions of the functions to implement these operations are:

```
template <class Type>
bool linkedStackType<Type>::isEmptyStack() const
```

```

{
    return (stackTop == NULL);
} //end isEmptyStack

template <class Type>
bool linkedStackType<Type>:: isFullStack() const
{
    return false;
} //end isFullStack

```

Recall that in the linked implementation of stacks, the function `isFullStack` does not apply because, logically, the stack is never full. However, you must provide its definition because it is included as an abstract function in the parent `class stackADT`.

Initialize Stack

The operation `initializeStack` reinitializes the stack to an empty state. Because the stack may contain some elements and we are using a linked implementation of a stack, we must deallocate the memory occupied by the stack elements and set `stackTop` to `NULL`. The definition of this function is:

```

template <class Type>
void linkedStackType<Type>:: initializeStack()
{
    nodeType<Type> *temp; //pointer to delete the node

    while (stackTop != NULL) //while there are elements in
                             //the stack
    {
        temp = stackTop;    //set temp to point to the
                             //current node
        stackTop = stackTop->link; //advance stackTop to the
                                 //next node
        delete temp;        //deallocate memory occupied by temp
    }
} //end initializeStack

```

Next, we consider the `push`, `top`, and `pop` operations. From Figure 19-12(b), it is clear that the `newElement` will be added (in the case of `push`) at the beginning of the linked list pointed to by `stackTop`. In the case of `pop`, the node pointed to by `stackTop` will be removed. In both cases, the value of the pointer `stackTop` is updated. The operation `top` returns the `info` of the node that `stackTop` is pointing to.

Push

Consider the stack shown in Figure 19-13.




FIGURE 19-13 Stack before the push operation

Figure 19-14 shows the steps of the push operation. (Assume that the new element to be pushed is 'D'.)




FIGURE 19-14 Push operation

The statements:

```
newNode = new nodeType<Type>; //create the new node
newNode->info = newElement;
```

create a node, store the address of the node into the variable `newNode`, and store `newElement` into the `info` field of `newNode`. See Figure 19-14(a).

The statement:

```
newNode->link = stackTop;
```

inserts `newNode` at the top of the stack, as shown in Figure 19-14(b).

Finally, the statement:

```
stackTop = newNode;
```

updates the value of `stackTop`, which results in Figure 19-14(c).

The definition of the function `push` is:

```
template <class Type>
void linkedStackType<Type>::push(const Type& newElement)
{
    nodeType<Type> *newNode;    //pointer to create the new node

    newNode = new nodeType<Type>; //create the node

    newNode->info = newElement; //store newElement in the node
    newNode->link = stackTop;   //insert newNode before stackTop
    stackTop = newNode;        //set stackTop to point to the
                                //top node
} //end push
```

We do not need to check whether the stack is full before we push an element onto the stack because in this implementation, logically, the stack is never full.

Return the Top Element

The operation to return the top element of the stack is quite straightforward. Its definition is:

```
template <class Type>
Type linkedStackType<Type>::top() const
{
    assert(stackTop != NULL); //if stack is empty,
                                //terminate the program
    return stackTop->info;     //return the top element
} //end top
```

Pop

Now we consider the `pop` operation, which removes the top element of the stack. Consider the stack shown in Figure 19-15.




FIGURE 19-15 Stack before the `pop` operation

Figure 19-16 shows the `pop` operation.




FIGURE 19-16 Pop operation

The statement:

```
temp = stackTop;
```

makes `temp` point to the top of the stack. See Figure 19-16(a). Next, the statement:

```
stackTop = stackTop->link;
```

makes the second element of the stack become the top element of the stack. See Figure 19-16(b).

Finally, the statement:

```
delete temp;
```

deallocates the memory pointed to by `temp`. See Figure 19-16(c).

The definition of the function `pop` is:

```
template <class Type>
void linkedStackType<Type>::pop()
{
    nodeType<Type> *temp;    //pointer to deallocate memory

    if (stackTop != NULL)
    {
        temp = stackTop;    //set temp to point to the top node

        stackTop = stackTop->link;    //advance stackTop to the
                                     //next node
        delete temp;    //delete the top node
    }
    else
        cout << "Cannot remove from an empty stack." << endl;
} //end pop
```

Copy Stack

The function `copyStack` makes an identical copy of a stack. Its definition is similar to the definition of `copyList` for linked lists, given in Chapter 18. The definition of the function `copyStack` is:

```
template <class Type>
void linkedStackType<Type>::copyStack
    (const linkedStackType<Type>& otherStack)
{
    nodeType<Type> *newNode, *current, *last;

    if (stackTop != NULL) //if stack is nonempty, make it empty
        initializeStack();

    if (otherStack.stackTop == NULL)
        stackTop = NULL;
    else
    {
        current = otherStack.stackTop;    //set current to point
                                         //to the stack to be copied

        //copy the stackTop element of the stack
        stackTop = new nodeType<Type>;    //create the node

        stackTop->info = current->info;    //copy the info
```

```

stackTop->link = NULL;    //set the link field of the
                           //node to NULL
last = stackTop;          //set last to point to the node
current = current->link;   //set current to point to
                           //the next node

    //copy the remaining stack
while (current != NULL)
{
    newNode = new nodeType<Type>;

    newNode->info = current->info;
    newNode->link = NULL;
    last->link = newNode;
    last = newNode;
    current = current->link;
} //end while
} //end else
} //end copyStack

```

Constructors and Destructors

We have already discussed the default constructor. To complete the implementation of the stack operations, next we give the definitions of the functions to implement the copy constructor and the destructor and to overload the assignment operator. (These functions are similar to those discussed for linked lists in Chapter 18.)

```

    //copy constructor
template <class Type>
linkedStackType<Type>::linkedStackType(
    const linkedStackType<Type>& otherStack)
{
    stackTop = NULL;
    copyStack(otherStack);
} //end copy constructor

    //destructor
template <class Type>
linkedStackType<Type>::~~linkedStackType()
{
    initializeStack();
} //end destructor

```

Overloading the Assignment Operator (=)

The definition of the function to overload the assignment operator for the `class` `linkedStackType` is:

```

template <class Type>
const linkedStackType<Type>& linkedStackType<Type>::operator=
    (const linkedStackType<Type>& otherStack)

```

```

{
    if (this != &otherStack) //avoid self-copy
        copyStack(otherStack);

    return *this;
} //end operator=

```

The definition of a stack and the functions to implement the stack operations discussed previously are generic. Also, as in the case of an array representation of a stack, in the linked representation of a stack, we must put the definition of the stack and the functions to implement the stack operations together in a (header) file. A client's program can include this header file via the `include` statement.

Example 19-3 illustrates how a `linkedStack` object is used in a program.

EXAMPLE 19-3

We assume that the definition of the `class` `linkedStackType` and the functions to implement the stack operations are included in the header file `"linkedStack.h"`.

//This program tests various operations of a linked stack

```

#include <iostream>
#include "linkedStack.h"

using namespace std;

void testCopy(linkedStackType<int> OStack);

int main()
{
    linkedStackType<int> stack;
    linkedStackType<int> otherStack;
    linkedStackType<int> newStack;

    //Add elements into stack
    stack.push(34);
    stack.push(43);
    stack.push(27);

    //Use the assignment operator to copy the elements
    //of stack into newStack
    newStack = stack;

    cout << "After the assignment operator, newStack: "
         << endl;

    //Output the elements of newStack
    while (!newStack.isEmptyStack())
    {
        cout << newStack.top() << endl;
        newStack.pop();
    }
}

```

```

        //Use the assignment operator to copy the elements
        //of stack into otherStack
otherStack = stack;

cout << "Testing the copy constructor." << endl;

testCopy(otherStack);

cout << "After the copy constructor, otherStack: " << endl;

while (!otherStack.isEmptyStack())
{
    cout << otherStack.top() << endl;
    otherStack.pop();
}

return 0;
}

//Function to test the copy constructor
void testCopy(linkedStackType<int> OStack)
{
    cout << "Stack in the function testCopy:" << endl;

    while (!OStack.isEmptyStack())
    {
        cout << OStack.top() << endl;
        OStack.pop();
    }
}

```

Sample Run:

```

After the assignment operator, newStack:
27
43
34
Testing the copy constructor.
Stack in the function testCopy:
27
43
34
After the copy constructor, otherStack:
27
43
34

```

Stack as Derived from the `class unorderedLinkedList`

If we compare the `push` function of the stack with the `insertFirst` function discussed for general lists in Chapter 18, we see that the algorithms to implement these operations are similar. A comparison of other functions—such as `initializeStack` and `initializeList`, `isEmptyList` and `isEmptyStack`, and so on—suggests that the `class linkedStackType` can be derived from the `class linkedListType`. Moreover, the functions `pop` and `isFullStack` can be implemented as in the previous section. Note that the `class linkedListType` is an abstract and does not implement all of the operations. However, the `class unorderedLinkedListType` is derived from the `class linkedListType` and provides the definitions of the abstract functions of the `class linkedListType`. Therefore, we can derive the `class linkedStackType` from the `class unorderedLinkedListType`.

Next, we define the `class linkedStackType` that is derived from the `class unorderedLinkedList`. The definitions of the functions to implement the stack operations are also given.

```
#include <iostream>
#include "unorderedLinkedList.h"

using namespace std;

template <class Type>
class linkedStackType: public unorderedLinkedList<Type>
{
public:
    void initializeStack();
    bool isEmptyStack() const;
    bool isFullStack() const;
    void push(const Type& newItem);
    Type top() const;
    void pop();
};

template <class Type>
void linkedStackType<Type>::initializeStack()
{
    unorderedLinkedList<Type>::initializeList();
}

template <class Type>
bool linkedStackType<Type>::isEmptyStack() const
{
    return unorderedLinkedList<Type>::isEmptyList();
}

template <class Type>
bool linkedStackType<Type>::isFullStack() const
{
    return false;
}
```

```

template <class Type>
void linkedStackType<Type>::push(const Type& newElement)
{
    unorderedLinkedList<Type>::insertFirst(newElement);
}

template <class Type>
Type linkedStackType<Type>::top() const
{
    return unorderedLinkedList<Type>::front();
}

template <class Type>
void linkedStackType<Type>::pop()
{
    nodeType<Type> *temp;

    temp = first;
    first = first->link;
    delete temp;
}

```

Application of Stacks: Postfix Expressions Calculator

The usual notation for writing arithmetic expressions (the notation we learned in elementary school) is called **infix** notation, in which the operator is written between the operands. For example, in the expression $a + b$, the operator $+$ is between the operands a and b . In infix notation, the operators have precedence. That is, we must evaluate expressions from left to right, and multiplication and division have higher precedence than do addition and subtraction. If we want to evaluate the expression in a different order, we must include parentheses. For example, in the expression $a + b * c$, we first evaluate $*$ using the operands b and c , and then we evaluate $+$ using the operand a and the result of $b * c$.

In the early 1920s, the Polish mathematician Jan Lukasiewicz discovered that if operators were written before the operands (**prefix** or **Polish** notation; for example, $+ a b$), the parentheses could be omitted. In the late 1950s, the Australian philosopher and early computer scientist Charles L. Hamblin proposed a scheme in which the operators *follow* the operands (postfix operators), resulting in the **Reverse Polish** notation. This has the advantage that the operators appear in the order required for computation.

For example, the expression:

$$a + b * c$$

in a postfix expression is:

$$a b c * +$$

The following example shows various infix expressions and their equivalent postfix expressions.

EXAMPLE 19-4

| Infix Expression | Equivalent Postfix Expression |
|-----------------------------|-------------------------------|
| $a + b$ | $a b +$ |
| $a + b * c$ | $a b c * +$ |
| $a * b + c$ | $a b * c +$ |
| $(a + b) * c$ | $a b + c *$ |
| $(a - b) * (c + d)$ | $a b - c d + *$ |
| $(a + b) * (c - d / e) + f$ | $a b + c d e / - * f +$ |

Shortly after Lukasiewicz’s discovery, it was realized that postfix notation had important applications in computer science. In fact, many compilers now first translate arithmetic expressions into some form of postfix notation and then translate this postfix expression into machine code. Postfix expressions can be evaluated using the following algorithm:

Scan the expression from left to right. When an operator is found, back up to get the required number of operands, perform the operation, and continue.

Consider the following postfix expression:

$6\ 3\ +\ 2\ *\ =$

Let us evaluate this expression using a stack and the previous algorithm. Figure 19-17 shows how this expression gets evaluated.




FIGURE 19-17 Evaluating the postfix expression: $6\ 3\ +\ 2\ *\ =$

Read the first symbol, 6, which is a number. Push the number onto the stack (see Figure 19-17(a)). Read the next symbol, 3, which is a number. Push the number onto the stack (see Figure 19-17(b)). Read the next symbol, +, which is an operator. Because an operator requires two operands to be evaluated, pop the stack twice (see Figure 19-17(c)). Perform the operation and put the result back onto the stack (see Figure 19-17(d)).

Read the next symbol, 2, which is a number. Push the number onto the stack (see Figure 19-17(e)). Read the next symbol, *, which is an operator. Because an operator requires two operands to be evaluated, pop the stack twice (see Figure 19-17(f)). Perform the operation, and put the result back onto the stack (see Figure 19-17(g)).

Scan the next symbol, =, which is the equal sign, indicating the end of the expression. Therefore, print the result. The result of the expression is in the stack, so pop and print (see Figure 19-17(h)).

The value of the expression $6\ 3 + 2\ * = 18$.

From this discussion, it is clear that when we read a symbol other than a number, the following cases arise:

1. The symbol we read is one of the following: +, -, *, /, or =.
 - a. If the symbol is +, -, *, or /, the symbol is an operator, so we must evaluate it. Because an operator requires two operands, the stack must have at least two elements; otherwise, the expression has an error.
 - b. If the symbol is = (an equal sign), the expression ends and we must print the answer. At this step, the stack must contain exactly one element; otherwise, the expression has an error.
2. The symbol we read is something other than +, -, *, /, or =. In this case, the expression contains an illegal operator.

It is also clear that when an operand (number) is encountered in an expression, it is pushed onto the stack because the operator comes after the operands.

Consider the following expressions:

- a. $7\ 6 + 3\ ;\ 6 - =$
- b. $14 + 2\ 3\ * =$
- c. $14\ 2\ 3 + =$

Expression (a) has an illegal operator, expression (b) does not have enough operands for +, and expression (c) has too many operands. In the case of expression (c), when we encounter the equal sign (=), the stack will have two elements, and this error cannot be discovered until we are ready to print the value of the expression.

To make the input easier to read, we assume that the postfix expressions are in the following form:

$\#6\ \#3 + \#2\ * =$

The symbol # precedes each number in the expression. If the symbol scanned is #, then the next input is a number (that is, an operand). If the symbol scanned is not #, then it is either an operator (may be illegal) or an equal sign (indicating the end of the expression). Furthermore, we assume that each expression contains only the +, -, *, and / operators.

This program outputs the entire postfix expression together with the answer. If the expression has an error, the expression is discarded. In this case, the program outputs the expression together with an appropriate error message. Because an expression may contain an error, we must clear the stack before processing the next expression. Also, the stack must be initialized; that is, the stack must be empty.

Main Algorithm

Following the previous discussion, the main algorithm in pseudocode is:

```
Read the first character
while not the end of input data
{
    a. initialize the stack
    b. process the expression
    c. output result
    d. get the next expression
}
```

To simplify the complexity of the function `main`, we write four functions: `evaluateExpression`, `evaluateOpr`, `discardExp`, and `printResult`. The function `evaluateExpression`, if possible, evaluates the expression and leaves the result in the stack. If the postfix expression is error free, the function `printResult` outputs the result. The function `evaluateOpr` evaluates an operator, and the function `discardExp` discards the current expression if there is any error in the expression.

Function `evaluateExpression`

The function `evaluateExpression` evaluates each postfix expression. Each expression ends with the symbol =. The general algorithm is:

```
while (ch is not = '=') //process each expression
                        //marks the end of an expression
{
    switch (ch)
    {
        case '#':
            read a number
            output the number;
            push the number onto the stack;
            break;
        default:
            assume that ch is an operation
            evaluate the operation;
    } //end switch
}
```

```

    if no error was found, then
    {
        read next ch;
        output ch;
    }
    else
        Discard the expression
} //end while

```

From this algorithm, it follows that this method has five parameters—one to access the input file, one to access the output file, one to access the stack, one to pass a character of the expression, and one to indicate whether there is an error in the expression. The definition of this function is:

```

void evaluateExpression(ifstream& inpF, ofstream& outF,
                       stackType<double>& stack,
                       char& ch, bool& isExpOk)
{
    double num;

    while (ch != '=')
    {
        switch (ch)
        {
            case '#':
                inpF >> num;
                outF << num << " ";
                if (!stack.isFullStack())
                    stack.push(num);
                else
                {
                    cout << "Stack overflow. "
                        << "Program terminates!" << endl;
                    exit(0); //terminate the program
                }

                break;
            default:
                evaluateOpr(outF, stack, ch, isExpOk);
        } //end switch

        if (isExpOk) //if no error
        {
            inpF >> ch;
            outF << ch;

            if (ch != '#')
                outF << " ";
        }
        else
            discardExp(inpF, outF, ch);
    } //end while (ch != '=')
}

```

Note that the function `exit` terminates the program.

Function `evaluateOpr`

This function (if possible) evaluates an expression. Two operands are needed to evaluate an operation, and operands are saved in the stack. Therefore, the stack must contain at least two numbers. If the stack contains fewer than two numbers, then the expression has an error. In this case, the entire expression is discarded, and an appropriate message is printed. This function also checks for any illegal operations. In pseudocode, this function is:

```

if stack is empty
{
    error in the expression
    set expressionOk to false
}
else
{
    retrieve the top element of stack into op2
    pop stack
    if stack is empty
    {
        error in the expression
        set expressionOk to false
    }
    else
    {
        retrieve the top element of stack into op1
        pop stack

        //If the operation is legal, perform the
        //operation and push the result onto the stack.
        switch (ch)
        {
            case '+':
                //Perform the operation and push the result
                //onto the stack.
                stack.push(op1 + op2);
                break;
            case '-':
                //Perform the operation and push the result
                //onto the stack.
                stack.push(op1 - op2);
                break;
            case '*':
                //Perform the operation and push the
                //result onto the stack.
                stack.push(op1 * op2);
                break;
            case '/':
                //If (op2 != 0), perform the operation and
                //push the result onto the stack.
                stack.push(op1 / op2);
        }
    }
}

```

```

        //Otherwise, report the error.
        //Set expressionOk to false.
        break;
    otherwise operation is illegal
    {
        output an appropriate message;
        set expressionOk to false
    }
} //end switch
}

```

Following this pseudocode, the definition of the function `evaluateOpr` is:

```

void evaluateOpr(ofstream& out, stackType<double>& stack,
                char& ch, bool& isExpOk)
{
    double op1, op2;

    if (stack.isEmptyStack())
    {
        out << " (Not enough operands)";
        isExpOk = false;
    }
    else
    {
        op2 = stack.top();
        stack.pop();

        if (stack.isEmptyStack())
        {
            out << " (Not enough operands)";
            isExpOk = false;
        }
        else
        {
            op1 = stack.top();
            stack.pop();

            switch (ch)
            {
            case '+':
                stack.push(op1 + op2);
                break;
            case '-':
                stack.push(op1 - op2);
                break;
            case '*':
                stack.push(op1 * op2);
                break;
            case '/':
                if (op2 != 0)
                    stack.push(op1 / op2);
            }
        }
    }
}

```

```

        else
        {
            out << " (Division by 0)";
            isExpOk = false;
        }
        break;
    default:
        out << " (Illegal operator)";
        isExpOk = false;
    } //end switch
} //end else
} //end evaluateOpr

```

Function `discardExp`

This function is called whenever an error is discovered in the expression. It reads and writes the input data only until the input is '=', the end of the expression. The definition of this function is:

```

void discardExp(istream& in, ostream& out, char& ch)
{
    while (ch != '=')
    {
        in.get(ch);
        out << ch;
    }
} //end discardExp

```

Function `printResult`

If the postfix expression contains no errors, the function `printResult` prints the result; otherwise, it outputs an appropriate message. The result of the expression is in the stack, and the output is sent to a file. Therefore, this function must have access to the stack and the output file. Suppose that no errors were encountered by the method `evaluateExpression`. If the stack has only one element, then the expression is error free and the top element of the stack is printed. If either the stack is empty or it has more than one element, then there is an error in the postfix expression. In this case, this method outputs an appropriate error message. The definition of this method is:

```

void printResult(ostream& outF, stackType<double>& stack,
                bool isExpOk)
{
    double result;

    if (isExpOk) //if no error, print the result

```

```

{
    if (!stack.isEmptyStack())
    {
        result = stack.top();
        stack.pop();

        if (stack.isEmptyStack())
            outF << result << endl;
        else
            outF << " (Error: Too many operands)" << endl;
    } //end if
    else
        outF << " (Error in the expression)" << endl;

    outF << " _____"
        << endl << endl;
} //end printResult

```

PROGRAM LISTING

```

//*****
// Author: D.S. Malik
//
// Program: Postfix Calculator
// This program evaluates postfix expressions.
//*****

#include <iostream>
#include <iomanip>
#include <fstream>
#include "mystack.h"

using namespace std;

void evaluateExpression(ifstream& inpF, ofstream& outF,
                      stackType<double>& stack,
                      char& ch, bool& isExpOk);
void evaluateOpr(ofstream& out, stackType<double>& stack,
                char& ch, bool& isExpOk);
void discardExp(ifstream& in, ofstream& out, char& ch);
void printResult(ofstream& outF, stackType<double>& stack,
                bool isExpOk);

int main()
{
    bool expressionOk;
    char ch;

```

```

    stackType<double> stack(100);
    ifstream infile;
    ofstream outfile;

    infile.open("RpnData.txt");

    if (!infile)
    {
        cout << "Cannot open the input file. "
              << "Program terminates!" << endl;
        return 1;
    }

    outfile.open("RpnOutput.txt");

    outfile << fixed << showpoint;
    outfile << setprecision(2);

    infile >> ch;
    while (infile)
    {
        stack.initializeStack();
        expressionOk = true;
        outfile << ch;

        evaluateExpression(infile, outfile, stack, ch,
                          expressionOk);
        printResult(outfile, stack, expressionOk);
        infile >> ch; //begin processing the next expression
    } //end while

    infile.close();
    outfile.close();

    return 0;

} //end main
//Place the definitions of the function evaluateExpression,
//evaluateOpr, discardExp, and printResult as described
//previously here.

```

Sample Run:

Input File

```

#35 #27 + #3 * =
#26 #28 + #32 #2 ; - #5 / =
#23 #30 #15 * / =
#2 #3 #4 + =
#20 #29 #9 * ; =
#25 #23 - + =
#34 #24 #12 #7 / * + #23 - =

```

Output

```
#35.00 #27.00 + #3.00 * = 186.00
```

```
#26.00 #28.00 + #32.00 #2.00 ; (Illegal operator) - #5 / = (Error in the expression)
```

```
#23.00 #30.00 #15.00 * / = 0.05
```

```
#2.00 #3.00 #4.00 += (Error: Too many operands)
```

```
#20.00 #29.00 #9.00 * ; (Illegal operator) = (Error in the expression)
```

```
#25.00 #23.00 - + (Not enough operands) = (Error in the expression)
```

```
#34.00 #24.00 #12.00 #7.00 / * + #23.00 -= 52.14
```

Removing Recursion: Nonrecursive Algorithm to Print a Linked List Backward

In Chapter 18, we used recursion to print a linked list backward. In this section, you will learn how a stack can be used to design a nonrecursive algorithm to print a linked list backward.

Consider the linked list shown in Figure 19-18.




FIGURE 19-18 Linked list

To print the list backward, first we need to get to the last node of the list, which we can do by traversing the linked list starting at the first node. However, once we are at the last node, how do we get back to the previous node, especially given that links go in only one direction? You can again traverse the linked list with the appropriate loop termination condition, but this approach might waste a considerable amount of computer time, especially if the list is very large. Moreover, if we do this for every node in the list, the program might execute very slowly. Next, we show how to use a stack effectively to print the list backward.

After printing the **info** of a particular node, we need to move to the node immediately behind this node. For example, after printing 15, we need to move to the node with

info 10. Thus, while initially traversing the list to move to the last node, we must save a pointer to each node. For example, for the list in Figure 19-18, we must save a pointer to each of the nodes with **info 5** and **10**. After printing **15**, we go back to the node with **info 10**; after printing **10**, we go back to the node with **info 5**. From this, it follows that we must save pointers to each node in a stack, so as to implement the Last In First Out principle.

Because the number of nodes in a linked list is usually not known, we will use the linked implementation of a stack. Suppose that **stack** is an object of type **LinkedListType**, and **current** is a pointer of the same type as the pointer **first**. Consider the following statements:

```
current = first;           //Line 1
while (current != NULL)    //Line 2
{
    stack.push(current);    //Line 3
    current = current->link; //Line 4
}
```

After the statement in Line 1 executes, **current** points to the first node. (See Figure 19-19.)




FIGURE 19-19 List after the statement `current = first;` executes

Because **current** is not **NULL**, the statements in Lines 3 and 4 execute. (See Figure 19-20.)




FIGURE 19-20 List and stack after the statements `stack.push(current);` and `current = current->link;` execute

After the statement in Line 4 executes, the loop condition in Line 2 is re-evaluated. Because **current** is not **NULL**, the loop condition evaluates to **true**, so the statements in Lines 3 and 4 execute. (See Figure 19-21.)




FIGURE 19-21 List and stack after the statements `stack.push(current);` and `current = current->link;` execute

After the statement in Line 4 executes, the loop condition, in Line 2, is evaluated again. Because **current** is not **NULL**, the loop condition evaluates to **true**, so the statements in Lines 3 and 4 execute. (See Figure 19-22.)




FIGURE 19-22 List and stack after the statements `stack.push(current);` and `current = current->link;` execute

After the statement in Line 4 executes, the loop condition in Line 2 is evaluated again. Because **current** is **NULL**, the loop condition evaluates to **false**, and the **while** loop in

Line 2 terminates. From Figure 19-22, it follows that a pointer to each node in the linked list is saved in the stack. The top element of the stack contains a pointer to the last node in the list, and so on. Let us now execute the following statements:

```
while (!stack.isEmptyStack())           //Line 5
{
    current = stack.top();               //Line 6
    stack.pop();                        //Line 7
    cout << current->info << " ";      //Line 8
}
```

The loop condition in Line 5 evaluates to **true** because the stack is nonempty. Therefore, the statements in Lines 6, 7, and 8 execute. After the statement in Line 6 executes, **current** points to the last node. The statement in Line 7 removes the top element of the stack. (See Figure 19-23.)




FIGURE 19-23 List and stack after the statements `current = stack.top();` and `stack.pop();` execute

The statement in Line 8 outputs **current->info**, which is 15. Next, the loop condition in Line 5 is evaluated. Because the loop condition evaluates to **true**, the statements in Lines 6, 7, and 8 execute. After the statements in Lines 6 and 7 execute, Figure 19-24 results.




FIGURE 19-24 List and stack after the statements `current = stack.top();` and `stack.pop();` execute

The statement in Line 8 outputs `current->info`, which is 10. Next, the loop condition in Line 5 is evaluated. Because the loop condition evaluates to `true`, the statements in Lines 6, 7, and 8 execute. After the statements in Lines 6 and 7 execute, Figure 19-25 results.




FIGURE 19-25 List and stack after the statements `current = stack.top()`; and `stack.pop()`; execute

The statement in Line 8 outputs `current->info`, which is 5. Next, the loop condition in Line 5 is evaluated. Because the loop condition evaluates to `false`, the `while` loop terminates. The `while` loop in Line 5 produces the following output:

15 10 5

Queues

This section discusses another important data structure called a **queue**. The notion of a queue in computer science is the same as the notion of the queues to which you are accustomed in everyday life. There are queues of customers in a bank or in a grocery store and queues of cars waiting to pass through a tollbooth. Similarly, because a computer can send a print request faster than a printer can print, a queue of documents is often waiting to be printed at a printer. The general rule to process elements in a queue is that the customer at the front of the queue is served next, and when a new customer arrives, he or she stands at the end of the queue. That is, a queue is a First In First Out data structure.

Queues have numerous applications in computer science. Whenever a system is modeled on the First In First Out principle, queues are used. At the end of this section, we will discuss one of the most widely used applications of queues, computer simulation. First, however, we need to develop the tools necessary to implement a queue. The next few sections discuss how to design classes to implement queues as an ADT.

A queue is a set of elements of the same type in which the elements are added at one end, called the **back** or **rear**, and deleted from the other end, called the **front**. For example, consider a line of customers in a bank, wherein the customers are waiting to withdraw/deposit money or to conduct some other business. Each new customer gets in the line at the rear. Whenever a teller is ready for a new customer, the customer at the front of the line is served.

The rear of the queue is accessed whenever a new element is added to the queue, and the front of the queue is accessed whenever an element is deleted from the queue. As in a

stack, the middle elements of the queue are inaccessible, even if the queue elements are stored in an array.

Queue: A data structure in which the elements are added at one end, called the rear, and deleted from the other end, called the front; a First In First Out (FIFO) data structure.

Queue Operations

From the definition of queues, we see that the two key operations are add and delete. We call the add operation **addQueue** and the delete operation **deleteQueue**. Because elements can be neither deleted from an empty queue nor added to a full queue, we need two more operations to successfully implement the **addQueue** and **deleteQueue** operations: **isEmptyQueue** (checks whether the queue is empty) and **isFullQueue** (checks whether a queue is full).

We also need an operation, **initializeQueue**, to initialize the queue to an empty state. Moreover, to retrieve the first and last elements of the queue, we include the operations **front** and **back**, as described in the following list. Some of the queue operations are:

- **initializeQueue:** Initializes the queue to an empty state.
- **isEmptyQueue:** Determines whether the queue is empty. If the queue is empty, it returns the value **true**; otherwise, it returns the value **false**.
- **isFullQueue:** Determines whether the queue is full. If the queue is full, it returns the value **true**; otherwise, it returns the value **false**.
- **front:** Returns the front, that is, the first element of the queue. Input to this operation consists of the queue. Prior to this operation, the queue must exist and must not be empty.
- **back:** Returns the last element of the queue. Input to this operation consists of the queue. Prior to this operation, the queue must exist and must not be empty.
- **addQueue:** Adds a new element to the rear of the queue. Input to this operation consists of the queue and the new element. Prior to this operation, the queue must exist and must not be full.
- **deleteQueue:** Removes the front element from the queue. Input to this operation consists of the queue. Prior to this operation, the queue must exist and must not be empty.

As in the case of a stack, a queue can be stored in an array or in a linked structure. We will consider both implementations. Because elements are added at one end and removed from the other end, we need two pointers to keep track of the front and rear of the queue, called **queueFront** and **queueRear**.

The following abstract `class` `queueADT` defines these operations as an ADT.

```
template <class Type>
class queueADT
{
public:
    virtual bool isEmptyQueue() const = 0;
        //Function to determine whether the queue is empty.
        //Postcondition: Returns true if the queue is empty,
        //                otherwise returns false.

    virtual bool isFullQueue() const = 0;
        //Function to determine whether the queue is full.
        //Postcondition: Returns true if the queue is full,
        //                otherwise returns false.

    virtual void initializeQueue() = 0;
        //Function to initialize the queue to an empty state.
        //Postcondition: The queue is empty.

    virtual Type front() const = 0;
        //Function to return the first element of the queue.
        //Precondition: The queue exists and is not empty.
        //Postcondition: If the queue is empty, the program
        //                terminates; otherwise, the first
        //                element of the queue is returned.

    virtual Type back() const = 0;
        //Function to return the last element of the queue.
        //Precondition: The queue exists and is not empty.
        //Postcondition: If the queue is empty, the program
        //                terminates; otherwise, the last
        //                element of the queue is returned.

    virtual void addQueue(const Type& queueElement) = 0;
        //Function to add queueElement to the queue.
        //Precondition: The queue exists and is not full.
        //Postcondition: The queue is changed and queueElement
        //                is added to the queue.

    virtual void deleteQueue() = 0;
        //Function to remove the first element of the queue.
        //Precondition: The queue exists and is not empty.
        //Postcondition: The queue is changed and the first
        //                element is removed from the queue.
};
```

We leave it as an exercise for you to draw the UML class diagram of the `class` `queueADT`.

Implementation of Queues as Arrays

Before giving the definition of the class to implement a queue as an ADT, we need to decide how many member variables are needed to implement the queue. Of course, we need an array to store the queue elements, the variables `queueFront` and `queueRear` to keep track of the first and last elements of the queue and the variable `maxQueueSize` to specify the maximum size of the queue. Thus, we need at least four member variables.

Before writing the algorithms to implement the queue operations, we need to decide how to use `queueFront` and `queueRear` to access the queue elements. How do `queueFront` and `queueRear` indicate that the queue is empty or full? Suppose that `queueFront` gives the index of the first element of the queue, and `queueRear` gives the index of the last element of the queue. To add an element to the queue, first we advance `queueRear` to the next array position, and then we add the element to the position that `queueRear` is pointing to. To delete an element from the queue, first we retrieve the element that `queueFront` is pointing to, and then we advance `queueFront` to the next element of the queue. Thus, `queueFront` changes after each `deleteQueue` operation, and `queueRear` changes after each `addQueue` operation.

Let us see what happens when `queueFront` changes after a `deleteQueue` operation and `queueRear` changes after an `addQueue` operation. Assume that the array to hold the queue elements is of size 100.

Initially, the queue is empty. After the operation:

```
addQueue (Queue, 'A') ;
```

the array is as shown in Figure 19-26.




FIGURE 19-26 Queue after the first `addQueue` operation

After two more `addQueue` operations:

```
addQueue (Queue, 'B') ;
addQueue (Queue, 'C') ;
```

the array is as shown in Figure 19-27.




FIGURE 19-27 Queue after two more `addQueue` operations

Now consider the `deleteQueue` operation:

`deleteQueue()` ;

After this operation, the array containing the queue is as shown in Figure 19-28.




FIGURE 19-28 Queue after the `deleteQueue` operation

Will this queue design work? Suppose **A** stands for adding (that is, `addQueue`) an element to the queue, and **D** stands for deleting (that is, `deleteQueue`) an element from the queue. Consider the following sequence of operations:

AAADADADADADADA...

This sequence of operations would eventually set the index `queueRear` to point to the last array position, giving the impression that the queue is full. However, the queue has only two or three elements, and the front of the array is empty (see Figure 19-29).




FIGURE 19-29 Queue after the sequence of operations **AAADADADADADA...**

One solution to this problem is that when the queue overflows to the rear (that is, `queueRear` points to the last array position), we can check the value of the index `queueFront`. If the value of `queueFront` indicates that there is room in the front of the array, then when `queueRear` gets to the last array position, we can slide all of the queue elements toward the first array position. This solution is good if the queue size is very small; otherwise, the program may execute more slowly.

Another solution to this problem is to assume that the array is circular—that is, the first array position immediately follows the last array position (see Figure 19-30).




FIGURE 19-30 Circular queue

We will consider the array containing the queue to be circular, although we will draw the figures of the array holding the queue elements as before.

Suppose that we have the queue as shown in Figure 19-31(a).




FIGURE 19-31 Queue before and after the add operation

After the operation `addQueue (Queue, 'Z') ;`, the queue is as shown in Figure 19-31(b).

Because the array containing the queue is circular, we can use the following statement to advance `queueRear` (`queueFront`) to the next array position.

```
queueRear = (queueRear + 1) % maxQueueSize;
```

If `queueRear < maxQueueSize - 1`, then `queueRear + 1 <= maxQueueSize - 1`, so `(queueRear + 1) % maxQueueSize = queueRear + 1`. If `queueRear == maxQueueSize - 1` (that is, `queueRear` points to the last array position), `queueRear + 1 == maxQueueSize`, so `(queueRear + 1) % maxQueueSize = 0`. In this case, `queueRear` will be set to 0, which is the first array position.

This queue design seems to work well. Before we write the algorithms to implement the queue operations, consider the following two cases.

Case 1: Suppose that after certain operations, the array containing the queue is as shown in Figure 19-32(a).




FIGURE 19-32 Queue before and after the delete operation

After the operation `deleteQueue()`, the resulting array is as shown in Figure 19-32(b).

Case 2: Let us now consider the queue shown in Figure 19-33(a).




FIGURE 19-33 Queue before and after the add operation

After the operation `addQueue(Queue, 'Z')`, the resulting array is as shown in Figure 19-33(b).

The arrays in Figures 19-32(b) and 19-33(b) have identical values for `queueFront` and `queueRear`. However, the resulting array in Figure 19-32(b) represents an empty queue, whereas the resulting array in Figure 19-33(b) represents a full queue. This latest queue design has brought up another problem of distinguishing between an empty and a full queue.

This problem has several solutions. One solution is to keep a count. In addition to the member variables `queueFront` and `queueRear`, we need another variable, `count`, to implement the queue. The value of `count` is incremented whenever a new element is added to the queue, and it is decremented whenever an element is removed from the queue. In this case, the function `initializeQueue` initializes `count` to 0. This solution is very useful if the user of the queue frequently needs to know the number of elements in the queue.

Another solution is to let `queueFront` indicate the index of the array position *preceding* the first element of the queue, rather than the index of the (actual) first element itself. In this case, assuming `queueRear` still indicates the index of the last element in the queue, the queue is empty if `queueFront == queueRear`. In this solution, the slot indicated by the index `queueFront` (that is, the slot preceding the first true element) is reserved. The queue will be full if the next available space is the special reserved slot indicated by `queueFront`. Finally, because the array position indicated by `queueFront` is to be kept empty, if the array size is, say, 100, then 99 elements can be stored in the queue (see Figure 19-34).




FIGURE 19-34 Array to store the queue elements with a reserved slot

Let us implement the queue using the first solution. That is, we use the variable `count` to indicate whether the queue is empty or full. The following class implements the functions of the abstract `class queueADT`. Because arrays can be allocated dynamically, we will leave it for the user to specify the size of the array to implement the queue. The default size of the array is 100.

```
template <class Type>
class queueType: public queueADT<Type>
{
public:
    const queueType<Type>& operator=(const queueType<Type>&);
    //Overload the assignment operator.
```

```

bool isEmptyQueue() const;
    //Function to determine whether the queue is empty.
    //Postcondition: Returns true if the queue is empty,
    //                otherwise returns false.

bool isFullQueue() const;
    //Function to determine whether the queue is full.
    //Postcondition: Returns true if the queue is full,
    //                otherwise returns false.

void initializeQueue();
    //Function to initialize the queue to an empty state.
    //Postcondition: The queue is empty.

Type front() const;
    //Function to return the first element of the queue.
    //Precondition: The queue exists and is not empty.
    //Postcondition: If the queue is empty, the program
    //                terminates; otherwise, the first
    //                element of the queue is returned.
Type back() const;
    //Function to return the last element of the queue.
    //Precondition: The queue exists and is not empty.
    //Postcondition: If the queue is empty, the program
    //                terminates; otherwise, the last
    //                element of the queue is returned.

void addQueue(const Type& queueElement);
    //Function to add queueElement to the queue.
    //Precondition: The queue exists and is not full.
    //Postcondition: The queue is changed and queueElement
    //                is added to the queue.

void deleteQueue();
    //Function to remove the first element of the queue.
    //Precondition: The queue exists and is not empty.
    //Postcondition: The queue is changed and the first
    //                element is removed from the queue.

queueType(int queueSize = 100);
    //Constructor

queueType(const queueType<Type>& otherQueue);
    //Copy constructor

~queueType();
    //Destructor

private:
    int maxQueueSize; //variable to store the maximum queue size
    int count;        //variable to store the number of
                      //elements in the queue
    int queueFront;   //variable to point to the first
                      //element of the queue
    int queueRear;    //variable to point to the last
                      //element of the queue
    Type *list;       //pointer to the array that holds
                      //the queue elements
};

```

We leave the UML class diagram of the `class queueType` as an exercise for you. (See Exercise 28 at the end of this chapter.)

Next, we consider the implementation of the queue operations.

EMPTY QUEUE AND FULL QUEUE

As discussed earlier, the queue is empty if `count == 0`, and the queue is full if `count == maxQueueSize`. So the functions to implement these operations are:

```
template <class Type>
bool queueType<Type>::isEmptyQueue() const
{
    return (count == 0);
} //end isEmptyQueue

template <class Type>
bool queueType<Type>::isFullQueue() const
{
    return (count == maxQueueSize);
} //end isFullQueue
```

INITIALIZE QUEUE

This operation initializes a queue to an empty state. The first element is added at the first array position. Therefore, we initialize `queueFront` to 0, `queueRear` to `maxQueueSize - 1`, and `count` to 0. See Figure 19-35.




FIGURE 19-35 Empty queue

The definition of the function `initializeQueue` is:

```
template <class Type>
void queueType<Type>::initializeQueue()
{
    queueFront = 0;
    queueRear = maxQueueSize - 1;
    count = 0;
} //end initializeQueue
```

FRONT

This operation returns the first element of the queue. If the queue is nonempty, the element of the queue indicated by the index `queueFront` is returned; otherwise, the program terminates.

```
template <class Type>
Type queueType<Type>::front() const
{
    assert(!isEmptyQueue());
    return list[queueFront];
} //end front
```

BACK

This operation returns the last element of the queue. If the queue is nonempty, the element of the queue indicated by the index `queueRear` is returned; otherwise the program terminates.

```
template <class Type>
Type queueType<Type>::back() const
{
    assert(!isEmptyQueue());
    return list[queueRear];
} //end back
```

addQueue

Next, we implement the `addQueue` operation. Because `queueRear` points to the last element of the queue, to add a new element to the queue, we first advance `queueRear` to the next array position and then add the new element to the array position indicated by `queueRear`. We also increment `count` by 1. So the function `addQueue` is:

```
template <class Type>
void queueType<Type>::addQueue(const Type& newElement)
{
    if (!isFullQueue())
    {
        queueRear = (queueRear + 1) % maxQueueSize; //use the
                                                    //mod operator to advance queueRear
                                                    //because the array is circular

        count++;
        list[queueRear] = newElement;
    }
    else
        cout << "Cannot add to a full queue." << endl;
} //end addQueue
```

deleteQueue

To implement the `deleteQueue` operation, we access the index `queueFront`. Because `queueFront` points to the array position containing the first element of the queue, in order to remove the first queue element, we decrement `count` by 1 and advance `queueFront` to the next queue element. So the function `deleteQueue` is:

```

template <class Type>
void queueType<Type>::deleteQueue()
{
    if (!isEmptyQueue())
    {
        count--;
        queueFront = (queueFront + 1) % maxQueueSize; //use the
                                                    //mod operator to advance queueFront
                                                    //because the array is circular
    }
    else
        cout << "Cannot remove from an empty queue." << endl;
} //end deleteQueue

```

CONSTRUCTORS AND DESTRUCTORS

To complete the implementation of the queue operations, we next consider the implementation of the constructor and the destructor. The constructor gets the `maxQueueSize` from the user, sets the variable `maxQueueSize` to the value specified by the user, and creates an array of size `maxQueueSize`. If the user does not specify the queue size, the constructor uses the default value, which is 100, to create an array of size 100. The constructor also initializes `queueFront` and `queueRear` to indicate that the queue is empty. The definition of the function to implement the constructor is:

```

template <class Type>
queueType<Type>::queueType(int queueSize)
{
    if (queueSize <= 0)
    {
        cout << "Size of the array to hold the queue must "
              << "be positive." << endl;
        cout << "Creating an array of size 100." << endl;

        maxQueueSize = 100;
    }
    else
        maxQueueSize = queueSize; //set maxQueueSize to
                                //queueSize

    queueFront = 0; //initialize queueFront
    queueRear = maxQueueSize - 1; //initialize queueRear
    count = 0;
    list = new Type[maxQueueSize]; //create the array to
                                //hold the queue elements
} //end constructor

```

The array to store the queue elements is created dynamically. Therefore, when the queue object goes out of scope, the destructor simply deallocates the memory occupied by the array that stores the queue elements. The definition of the function to implement the destructor is:

```
template <class Type>
queueType<Type>::~~queueType()
{
    delete [] list;
}
```

The implementation of the copy constructor and overloading the assignment operator are left as exercises for you. (The definitions of these functions are similar to those discussed for linked lists and stacks.)

Linked Implementation of Queues

Because the size of the array to store the queue elements is fixed, only a finite number of queue elements can be stored in the array. Also, the array implementation of the queue requires the array to be treated in a special way together with the values of the indices `queueFront` and `queueRear`. The linked implementation of a queue simplifies many of the special cases of the array implementation and, because the memory to store a queue element is allocated dynamically, the queue is never full. This section discusses the linked implementation of a queue.

Because elements are added at one end and removed from the other end, we need to know the front of the queue and the rear of the queue. Thus, we need two pointers, `queueFront` and `queueRear`, to maintain the queue. The following class implements the functions of the abstract `class queueADT`.

```
//Definition of the node
template <class Type>
struct nodeType
{
    Type info;
    nodeType<Type> *link;
};

template <class Type>
class linkedQueueType: public queueADT<Type>
{
public:
    const linkedQueueType<Type>& operator=
        (const linkedQueueType<Type>&);
    //Overload the assignment operator.

    bool isEmptyQueue() const;
    //Function to determine whether the queue is empty.
    //Postcondition: Returns true if the queue is empty,
    //               otherwise returns false.

    bool isFullQueue() const;
    //Function to determine whether the queue is full.
    //Postcondition: Returns true if the queue is full,
    //               otherwise returns false.
```

```

void initializeQueue();
    //Function to initialize the queue to an empty state.
    //Postcondition: queueFront = NULL; queueRear = NULL

Type front() const;
    //Function to return the first element of the queue.
    //Precondition: The queue exists and is not empty.
    //Postcondition: If the queue is empty, the program
    //                terminates; otherwise, the first
    //                element of the queue is returned.

Type back() const;
    //Function to return the last element of the queue.
    //Precondition: The queue exists and is not empty.
    //Postcondition: If the queue is empty, the program
    //                terminates; otherwise, the last
    //                element of the queue is returned.

void addQueue(const Type& queueElement);
    //Function to add queueElement to the queue.
    //Precondition: The queue exists and is not full.
    //Postcondition: The queue is changed and queueElement
    //                is added to the queue.

void deleteQueue();
    //Function to remove the first element of the queue.
    //Precondition: The queue exists and is not empty.
    //Postcondition: The queue is changed and the first
    //                element is removed from the queue.

linkedQueueType();
    //Default constructor

linkedQueueType(const linkedQueueType<Type>& otherQueue);
    //Copy constructor

~linkedQueueType();
    //Destructor

private:
    nodeType<Type> *queueFront; //pointer to the front of
                                //the queue
    nodeType<Type> *queueRear;  //pointer to the rear of
                                //the queue
};

```

The UML class diagram of the `class` `linkedQueueType` is left as an exercise for you. (See Exercise 29 at the end of this chapter.)

Next, we write the definitions of the functions of the `class` `linkedQueueType`.

EMPTY AND FULL QUEUE

The queue is empty if `queueFront` is `NULL`. Memory to store the queue elements is allocated dynamically. Therefore, the queue is never full, so the function to implement

the `isFullQueue` operation returns the value `false`. (The queue is full only if we run out of memory.)

```
template <class Type>
bool linkedQueueType<Type>::isEmptyQueue() const
{
    return (queueFront == NULL);
} //end

template <class Type>
bool linkedQueueType<Type>::isFullQueue() const
{
    return false;
} //end isFullQueue
```

Note that in reality, in the linked implementation of queues, the function `isFullQueue` does not apply because, logically, the queue is never full. However, you must provide its definition because it is included as an abstract function in the parent `class queueADT`.

INITIALIZE QUEUE

The operation `initializeQueue` initializes the queue to an empty state. The queue is empty if there are no elements in the queue. Note that the constructor initializes the queue when the queue object is declared. So this operation must remove all of the elements, if any, from the queue. Therefore, this operation traverses the list containing the queue starting at the first node, and it deallocates the memory occupied by the queue elements. The definition of this function is:

```
template <class Type>
void linkedQueueType<Type>::initializeQueue()
{
    nodeType<Type> *temp;

    while (queueFront != NULL)    //while there are elements left
                                   //in the queue
    {
        temp = queueFront;    //set temp to point to the
                               //current node
        queueFront = queueFront->link;    //advance first to
                                           //the next node
        delete temp;    //deallocate memory occupied by temp
    }

    queueRear = NULL;    //set rear to NULL
} //end initializeQueue
```

addQueue, front, back, AND deleteQueue OPERATIONS

The `addQueue` operation adds a new element at the end of the queue. To implement this operation, we access the pointer `queueRear`.

If the queue is nonempty, the operation `front` returns the first element of the queue, and so the element of the queue indicated by the pointer `queueFront` is returned. If the queue is empty, the function `front` terminates the program.

If the queue is nonempty, the operation `back` returns the last element of the queue, so the element of the queue indicated by the pointer `queueRear` is returned. If the queue is empty, the function `back` terminates the program. Similarly, if the queue is nonempty, the operation `deleteQueue` removes the first element of the queue, so we access the pointer `queueFront`.

The definitions of the functions to implement these operations are:

```
template <class Type>
void linkedQueueType<Type>::addQueue(const Type& newElement)
{
    nodeType<Type> *newNode;

    newNode = new nodeType<Type>;    //create the node

    newNode->info = newElement; //store the info
    newNode->link = NULL;    //initialize the link field to NULL

    if (queueFront == NULL) //if initially the queue is empty
    {
        queueFront = newNode;
        queueRear = newNode;
    }
    else    //add newNode at the end
    {
        queueRear->link = newNode;
        queueRear = queueRear->link;
    }
} //end addQueue

template <class Type>
Type linkedQueueType<Type>::front() const
{
    assert(queueFront != NULL);
    return queueFront->info;
} //end front

template <class Type>
Type linkedQueueType<Type>::back() const
{
    assert(queueRear != NULL);
    return queueRear->info;
} //end back
```

```

template <class Type>
void linkedQueueType<Type>::deleteQueue()
{
    nodeType<Type> *temp;

    if (!isEmptyQueue())
    {
        temp = queueFront; //make temp point to the
                           //first node
        queueFront = queueFront->link; //advance queueFront

        delete temp; //delete the first node

        if (queueFront == NULL) //if after deletion the
                               //queue is empty
            queueRear = NULL; //set queueRear to NULL
    }
    else
        cout << "Cannot remove from an empty queue" << endl;
} //end deleteQueue

```

The definition of the default constructor is:

```

template<class Type>
linkedQueueType<Type>::linkedQueueType()
{
    queueFront = NULL; //set front to null
    queueRear = NULL; //set rear to null
} //end default constructor

```

When the queue object goes out of scope, the destructor destroys the queue; that is, it deallocates the memory occupied by the elements of the queue. The definition of the function to implement the destructor is similar to the definition of the function `initializeQueue`. Also, the functions to implement the copy constructor and overload the assignment operators are similar to the corresponding functions for stacks. Implementing these operations is left as an exercise for you.

EXAMPLE 19-5

The following program tests various operations on a queue. It uses the `class` `linkedQueueType` to implement a queue.

//Test Program linked queue

```

#include <iostream>
#include "linkedQueue.h"

using namespace std;
int main()

```

```

{
    linkedQueueType<int> queue;
    int x, y;

    queue.initializeQueue();
    x = 4;
    y = 5;
    queue.addQueue(x);
    queue.addQueue(y);
    x = queue.front();
    queue.deleteQueue();
    queue.addQueue(x + 5);
    queue.addQueue(16);
    queue.addQueue(x);
    queue.addQueue(y - 3);

    cout << "Queue Elements: ";

    while (!queue.isEmptyQueue())
    {
        cout << queue.front() << " ";
        queue.deleteQueue();
    }

    cout << endl;

    return 0;
}

```

Sample Run:

Queue Elements: 5 9 16 4 2

Queue Derived from the `class unorderedLinkedListType`

From the definitions of the functions to implement the queue operations, it is clear that the linked implementation of a queue is similar to the implementation of a linked list created in a forward manner (see Chapter 18). The `addQueue` operation is similar to the operation `insertFirst`. Likewise, the operations `initializeQueue` and `initializeList` and `isEmptyQueue` and `isEmptyList` are similar. The `deleteQueue` operation can be implemented as before. The pointer `queueFront` is the same as the pointer `first`, and the pointer `queueRear` is the same as the pointer `last`. This correspondence suggests that we can derive the class to implement the queue from the `class linkedListType` (see Chapter 18). Note that the `class linkedListType` is an abstract class and does not implement all of the operations. However, the `class unorderedLinkedListType` is derived from the `class linkedListType` and provides the definitions of the abstract functions of the `class linkedListType`. Therefore, we can derive the `class linkedQueueType` from the `class unorderedLinkedListType`.

We leave it as an exercise for you to write the definition of the `class linkedQueueType` that is derived from the `class unorderedLinkedListType`. See Programming Exercise 17 at the end of this chapter.

Application of Queues: Simulation

A technique in which one system models the behavior of another system is called simulation. For example, physical simulators include wind tunnels used to experiment with the design of car bodies and flight simulators used to train airline pilots. Simulation techniques are used when it is too expensive or dangerous to experiment with real systems. You can also design computer models to study the behavior of real systems. (We will describe some real systems modeled by computers shortly.)

Simulating the behavior of an expensive or dangerous experiment using a computer model is usually less expensive than using the real system and is a good way to gain insight without putting human life in danger. Moreover, computer simulations are particularly useful for complex systems when it is difficult to construct a mathematical model. For such systems, computer models can retain descriptive accuracy. In computer simulations, the steps of a program are used to model the behavior of a real system. Let us consider one such problem.

The manager of a local movie theater is hearing complaints from customers about the length of time they have to wait in line to buy tickets. The theater currently has only one cashier. Another theater is preparing to open in the neighborhood, and the manager is afraid of losing customers. The manager wants to hire enough cashiers so that a customer does not have to wait too long to buy a ticket but does not want to hire extra cashiers on a trial basis and potentially waste time and money. One thing that the manager would like to know is the average time a customer has to wait for service. The manager wants someone to write a program to simulate the behavior of the theater.

In computer simulation, the objects being studied are usually represented as data. For the theater problem, some of the objects are the customers and the cashier. The cashier serves the customers, and we want to determine a customer's average waiting time. Actions are implemented by writing algorithms, which in a programming language are implemented with the help of functions. Thus, functions are used to implement the actions of the objects. In C++, we can combine the data and the operations on that data into a single unit with the help of classes. Thus, objects can be represented as classes. The member variables of the class describe the properties of the objects, and the function members describe the actions on that data. This change in simulation results can also occur if we change the values of the data or modify the definitions of the functions (that is, modify the algorithms implementing the actions). The main goal of a computer simulation is to either generate results showing the performance of an existing system or predict the performance of a proposed system.

In the theater problem, when the cashier is serving a customer, the other customers must wait. Because customers are served on a first come, first served basis and queues are an

effective way to implement a First In First Out system, queues are important data structures for use in computer simulations. This section examines computer simulations in which queues are the basic data structure. These simulations model the behavior of systems, called **queuing systems**, in which queues of objects are waiting to be served by various servers. In other words, a queuing system consists of servers and queues of objects waiting to be served. We deal with a variety of queuing systems on a daily basis. For example, a grocery store and a banking system are both queuing systems. Furthermore, when you send a print request to a networked printer that is shared by many people, your print request goes in a queue. Print requests that arrived before your print request are usually completed before yours. Thus, the printer acts as the server when a queue of documents is waiting to be printed.

Designing a Queuing System

In this section, we describe a queuing system that can be used in a variety of applications, such as a bank, grocery store, movie theater, printer, or a mainframe environment in which several people are trying to use the same processors to execute their programs. To describe a queuing system, we use the term **server** for the object that provides the service. For example, in a bank, a teller is a server; in a grocery store or movie theater, a cashier is a server. We will call the object receiving the service the **customer**, and the service time—the time it takes to serve a customer—the **transaction time**.

Because a queuing system consists of servers and a queue of waiting objects, we will model a system that consists of a list of servers and a waiting queue holding the customers to be served. The customer at the front of the queue waits for the next available server. When a server becomes free, the customer at the front of the queue moves to the free server to be served.

When the first customer arrives, all servers are free and the customer moves to the first server. When the next customer arrives, if a server is available, the customer immediately moves to the available server; otherwise, the customer waits in the queue. To model a queuing system, we need to know the number of servers, the expected arrival time of a customer, the time between the arrivals of customers, and the number of events affecting the system.

Let us again consider the movie theater system. The performance of the system depends on how many servers are available, how long it takes to serve a customer, and how often a customer arrives. If it takes too long to serve a customer and customers arrive frequently, then more servers are needed. This system can be modeled as a time-driven simulation. In a **time-driven simulation**, the clock is implemented as a counter, and the passage of, say, one minute can be implemented by incrementing the counter by 1. The simulation is run for a fixed amount of time. If the simulation needs to be run for 100 minutes, the counter starts at 1 and goes up to 100, which can be implemented by using a loop.

For the simulation described in this section, we want to determine the average wait time for a customer. To calculate the average wait time for a customer, we need to add the waiting

time of each customer and then divide the sum by the number of customers who have arrived. When a customer arrives, he or she goes to the end of the queue and the customer's waiting time begins. If the queue is empty and a server is free, the customer is served immediately, so this customer's waiting time is zero. On the other hand, if a customer arrives and either the queue is nonempty or all of the servers are busy, the customer must wait for the next available server and, therefore, this customer's waiting time begins. We can keep track of the customer's waiting time by using a timer for each customer. When a customer arrives, the timer is set to 0, which is incremented after each time unit.

Suppose that, on average, it takes five minutes for a server to serve a customer. When a server becomes free and the waiting customer's queue is nonempty, the customer at the front of the queue proceeds to begin the transaction. Thus, we must keep track of the time a customer is with a server. When the customer arrives at a server, the transaction time is set to five and is decremented after each time unit. When the transaction time becomes zero, the server is marked free. Hence, the two objects needed to implement a time-driven computer simulation of a queuing system are the customer and the server.

Next, before designing the main algorithm to implement the simulation, we design classes to implement each of the two objects: *customer* and *server*.

Customer

Every customer has a customer number, arrival time, waiting time, transaction time, and departure time. If we know the arrival time, waiting time, and transaction time, we can determine the departure time by adding these three times. Let us call the class to implement the customer object `customerType`. It follows that the `class` `customerType` has four member variables: the `customerNumber`, `arrivalTime`, `waitingTime`, and `transactionTime`, each of the data type `int`. The basic operations that must be performed on an object of type `customerType` are as follows: set the customer's number, arrival time, and waiting time; increment the waiting time by one time unit; return the waiting time; return the arrival time; return the transaction time; and return the customer number. The following `class`, `customerType`, implements the customer as an ADT.

```
class customerType
{
public:
    customerType(int cN = 0, int arrvTime = 0, int wTime = 0,
                int tTime = 0);
    //Constructor to initialize the instance variables
    //according to the parameters.
    //If no value is specified in the object declaration,
    //the default values are assigned.
    //Postcondition: customerNumber = cN;
    //                arrivalTime = arrvTime;
    //                waitingTime = wTime;
    //                transactionTime = tTime
```

```

void setCustomerInfo(int customerN = 0, int inTime = 0,
                    int wTime = 0, int tTime = 0);
    //Function to initialize the instance variables.
    //Instance variables are set according to the parameters.
    //Postcondition: customerNumber = customerN;
    //                arrivalTime = arrvTime;
    //                waitingTime = wTime;
    //                transactionTime = tTime;

int getWaitingTime() const;
    //Function to return the waiting time of a customer.
    //Postcondition: The value of waitingTime is returned.

void setWaitingTime(int time);
    //Function to set the waiting time of a customer.
    //Postcondition: waitingTime = time;

void incrementWaitingTime();
    //Function to increment the waiting time by one time unit.
    //Postcondition: waitingTime++;

int getArrivalTime() const;
    //Function to return the arrival time of a customer.
    //Postcondition: The value of arrivalTime is returned.

int getTransactionTime() const;
    //Function to return the transaction time of a customer.
    //Postcondition: The value of transactionTime is returned.

int getCustomerNumber() const;
    //Function to return the customer number.
    //Postcondition: The value of customerNumber is returned.

private:
    int customerNumber;
    int arrivalTime;
    int waitingTime;
    int transactionTime;
};

```

Figure 19-36 shows the UML class diagram of the `class` `customerType`.




FIGURE 19-36 UML class diagram of the **class** `customerType`

The definitions of the member functions of the **class** `customerType` follow easily from their descriptions. Next, we give the definitions of the member functions of the **class** `customerType`.

The function `setCustomerInfo` uses the values of the parameters to initialize `customerNumber`, `arrivalTime`, `waitingTime`, and `transactionTime`. The definition of `setCustomerInfo` is:

```

void customerType::setCustomerInfo(int customerN, int arrvTime,
                                   int wTime, int tTime)
{
    customerNumber = customerN;
    arrivalTime = arrvTime;
    waitingTime = wTime;
    transactionTime = tTime;
}
  
```

The definition of the constructor is similar to the definition of the function `setCustomerInfo`. It uses the values of the parameters to initialize `customerNumber`, `arrivalTime`, `waitingTime`, and `transactionTime`. To make debugging easier, we use the function `setCustomerInfo` to write the definition of the constructor, which is given next, as follows:

```
customerType::customerType(int customerN, int arrvTime,
                           int wTime, int tTime)
{
    setCustomerInfo(customerN, arrvTime, wTime, tTime);
}
```

The function `getWaitingTime` returns the current waiting time. The definition of the function `getWaitingTime` is:

```
int customerType::getWaitingTime() const
{
    return waitingTime;
}
```

The function `incrementWaitingTime` increments the value of `waitingTime`. Its definition is:

```
void customerType::incrementWaitingTime()
{
    waitingTime++;
}
```

The definitions of the functions `setWaitingTime`, `getArrivalTime`, `getTransactionTime`, and `getCustomerNumber` are left as an exercise for you.

Server

At any given time unit, the server is either busy serving a customer or is free. We use a `string` variable to set the status of the server. Every server has a timer and, because the program might need to know which customer is served by which server, the server also stores the information of the customer being served. Thus, three member variables are associated with a server: the `status`, the `transactionTime`, and the `currentCustomer`. Some of the basic operations that must be performed on a server are as follows: check whether the server is free; set the server as free; set the server as busy; set the transaction time (that is, how long it takes to serve the customer); return the remaining transaction time (to determine whether the server should be set to free); if the server is busy after each time unit, decrement the transaction time by one time unit; and so on. The following `class`, `serverType`, implements the server as an ADT.

```
class serverType
{
public:
    serverType();
    //Default constructor
    //Sets the values of the instance variables to their default
    //values.
    //Postcondition: currentCustomer is initialized by its
    //                default constructor; status = "free"; and
    //                the transaction time is initialized to 0.
```

```

bool isFree() const;
    //Function to determine if the server is free.
    //Postcondition: Returns true if the server is free,
    //               otherwise returns false.

void setBusy();
    //Function to set the status of the server to busy.
    //Postcondition: status = "busy";

void setFree();
    //Function to set the status of the server to "free".
    //Postcondition: status = "free";

void setTransactionTime(int t);
    //Function to set the transaction time according to the
    //parameter t.
    //Postcondition: transactionTime = t;

void setTransactionTime();
    //Function to set the transaction time according to
    //the transaction time of the current customer.
    //Postcondition:
    //    transactionTime = currentCustomer.transactionTime;

int getRemainingTransactionTime() const;
    //Function to return the remaining transaction time.
    //Postcondition: The value of transactionTime is returned.

void decreaseTransactionTime();
    //Function to decrease the transactionTime by one unit.
    //Postcondition: transactionTime--;

void setCurrentCustomer(customerType cCustomer);
    //Function to set the info of the current customer
    //according to the parameter cCustomer.
    //Postcondition: currentCustomer = cCustomer;

int getCurrentCustomerNumber() const;
    //Function to return the customer number of the current
    //customer.
    //Postcondition: The value of customerNumber of the
    //               current customer is returned.

int getCurrentCustomerArrivalTime() const;
    //Function to return the arrival time of the current
    //customer.
    //Postcondition: The value of arrivalTime of the current
    //               customer is returned.

int getCurrentCustomerWaitingTime() const;
    //Function to return the current waiting time of the
    //current customer.

```

```

        //Postcondition: The value of transactionTime is
        //                    returned.

int getCurrentCustomerTransactionTime() const;
    //Function to return the transaction time of the
    //current customer.
    //Postcondition: The value of transactionTime of the
    //                    current customer is returned.

private:
    customerType currentCustomer;
    string status;
    int transactionTime;
};

```

Figure 19-37 shows the UML class diagram of the `class` `serverType`.




FIGURE 19-37 UML class diagram of the `class` `serverType`

The definitions of some of the member functions of the `class` `serverType` are:

```

serverType::serverType()
{
    status = "free";
    transactionTime = 0;
}

```

```

bool serverType::isFree() const
{
    return (status == "free");
}

void serverType::setBusy()
{
    status = "busy";
}

void serverType::setFree()
{
    status = "free";
}

void serverType::setTransactionTime(int t)
{
    transactionTime = t;
}

void serverType::setTransactionTime()
{
    int time;

    time = currentCustomer.getTransactionTime();

    transactionTime = time;
}

void serverType::decreaseTransactionTime()
{
    transactionTime--;
}

```

We leave the definitions of the functions `getRemainingTransactionTime`, `setCurrentCustomer`, `getCurrentCustomerNumber`, `getCurrentCustomerArrivalTime`, `getCurrentCustomerWaitingTime`, and `getCurrentCustomerTransactionTime` as an exercise for you.

Because we are designing a simulation program that can be used in a variety of applications, we need to design two more classes: one to create and process a list of servers and one to create and process a queue of waiting customers. The next two sections describe each of these classes.

Server List

A server list is a set of servers. At any given time, a server is either free or busy. For the customer at the front of the queue, we need to find a server in the list that is free. If all of the servers are busy, then the customer must wait until one of the servers becomes free. Thus, the class that implements a list of servers has two member variables: one to store the

number of servers and one to maintain a list of servers. Using dynamic arrays, depending on the number of servers specified by the user, a list of servers is created during program execution. Some of the operations that must be performed on a server list are as follows: return the server number of a free server; when a customer gets ready to do business and a server is available, set the server to busy; when the simulation ends, some of the servers might still be busy, so return the number of busy servers; after each time unit, reduce the `transactionTime` of each busy server by one time unit; and if the `transactionTime` of a server becomes zero, set the server to free. The following `class`, `serverListType`, implements the list of servers as an ADT.

```
class serverListType
{
public:
    serverListType(int num = 1);
        //Constructor to initialize a list of servers
        //Postcondition: numServers = num
        //
        //      A list of servers, specified by num,
        //      is created and each server is
        //      initialized to "free".

    ~serverListType();
        //Destructor
        //Postcondition: The list of servers is destroyed.

    int getFreeServerID() const;
        //Function to search the list of servers.
        //Postcondition: If a free server is found, returns
        //      its ID; otherwise, returns -1.

    int getNumberOfBusyServers() const;
        //Function to return the number of busy servers.
        //Postcondition: The number of busy servers is returned.

    void setServerBusy(int serverID, customerType cCustomer,
        int tTime);
        //Function to set a server as busy.
        //Postcondition: The server specified by serverID is set
        //      to "busy", to serve the customer
        //      specified by cCustomer, and the
        //      transaction time is set according to the
        //      parameter tTime.

    void setServerBusy(int serverID, customerType cCustomer);
        //Function to set a server as busy.
        //Postcondition: The server specified by serverID is set
        //      to "busy", to serve the customer
        //      specified by cCustomer.

    void updateServers(ostream& outFile);
        //Function to update the status of a server.
        //Postcondition: The transaction time of each busy
```

```

//          server is decremented by one unit. If
//          the transaction time of a busy server
//          is reduced to zero, the server is set
//          to "free". Moreover, if the actual
//          parameter corresponding to outFile is
//          cout, a message indicating which customer
//          has been served is printed on the screen,
//          together with the customer's departing
//          time. Otherwise, the output is sent to
//          a file specified by the user.

private:
    int numOfServers;
    serverType *servers;
};

```

Figure 19-38 shows the UML class diagram of the `class` `serverListType`.




FIGURE 19-38 UML class diagram of the `class` `serverListType`

Following are the definitions of the member functions of the `class` `serverListType`. The definitions of the constructor and destructor are straightforward.

```

serverListType::serverListType(int num)
{
    numOfServers = num;
    servers = new serverType[num];
}

serverListType::~serverListType()
{
    delete [] servers;
}

```

The function `getFreeServerID` searches the list of servers. If a free server is found, it returns the server's ID; otherwise, the value `-1` is returned, which indicates that all of the servers are busy. The definition of this function is:

```
int serverListType::getFreeServerID() const
{
    int serverID = -1;

    int i;

    for (i = 0; i < numOfServers; i++)
        if (servers[i].isFree())
        {
            serverID = i;
            break;
        }

    return serverID;
}
```

The function `getNumberOfBusyServers` searches the list of servers and determines and returns the number of busy servers. The definition of this function is:

```
int serverListType::getNumberOfBusyServers() const
{
    int busyServers = 0;

    int i;

    for (i = 0; i < numOfServers; i++)
        if (!servers[i].isFree())
            busyServers++;

    return busyServers;
}
```

The function `setServerBusy` sets a server to busy. This function is overloaded. The `serverID` of the server that is set to busy is passed as a parameter to this function. One function sets the server's transaction time according to the parameter `tTime`; the other function sets it by using the transaction time stored in the object `cCustomer`. The transaction time is later needed to determine the average wait time. The definitions of these functions are:

```
void serverListType::setServerBusy(int serverID,
                                   customerType cCustomer,
                                   int tTime)
{
    servers[serverID].setBusy();
    servers[serverID].setTransactionTime(tTime);
    servers[serverID].setCurrentCustomer(cCustomer);
}
```

```

void serverListType::setServerBusy(int serverID,
                                   customerType cCustomer)
{
    int time;

    time = cCustomer.getTransactionTime();

    servers[serverID].setBusy();
    servers[serverID].setTransactionTime(time);
    servers[serverID].setCurrentCustomer(cCustomer);
}

```

The definition of the function `updateServers` is quite straightforward. Starting at the first server, it searches the list of servers for busy servers. When a busy server is found, its `transactionTime` is decremented by 1. If the `transactionTime` reduces to zero, the server is set to **free**. If the `transactionTime` of a busy server reduces to zero, then the transaction of the customer being served by the server is complete. If the actual parameter corresponding to `outFile` is `cout`, a message indicating which customer has been served is printed on the screen, together with the customer's departing time. Otherwise, the output is sent to a file specified by the user. The definition of this function is as follows:

```

void serverListType::updateServers(ostream& outFile)
{
    int i;

    for (i = 0; i < numOfServers; i++)
        if (!servers[i].isFree())
        {
            servers[i].decreaseTransactionTime();

            if (servers[i].getRemainingTransactionTime() == 0)
            {
                outFile << "From server number " << (i + 1)
                        << " customer number "
                        << servers[i].getCurrentCustomerNumber()
                        << "\n    departed at time unit "
                        << servers[i].
                            getCurrentCustomerArrivalTime()
                            + servers[i].
                                getCurrentCustomerWaitingTime()
                            + servers[i].
                                getCurrentCustomerTransactionTime()
                        << endl;
                servers[i].setFree();
            }
        }
}

```

Waiting Customers Queue

When a customer arrives, he or she goes to the end of the queue. When a server becomes available, the customer at the front of the queue leaves to conduct the transaction. After each time unit, the waiting time of each customer in the queue is incremented by 1. The ADT `queueType` designed in this chapter has all the operations needed to implement a queue, except the operation of incrementing the waiting time of each customer in the queue by one time unit. We will derive a `class`, `waitingCustomerQueueType`, from the `class` `queueType` and add the additional operations to implement the customer queue. The definition of the `class` `waitingCustomerQueueType` is as follows:

```
class waitingCustomerQueueType: public queueType<customerType>
{
public:
    waitingCustomerQueueType(int size = 100);
        //Constructor
        //Postcondition: The queue is initialized according to
        //                the parameter size. The value of size
        //                is passed to the constructor of queueType.

    void updateWaitingQueue();
        //Function to increment the waiting time of each
        //customer in the queue by one time unit.
};
```

NOTE

Notice that the `class` `waitingCustomerQueueType` is derived from the `class` `queueType`, which implements the queue in an array. You can also derive it from the `class` `linkedQueueType`, which implements the queue in a linked list. We leave the details as an exercise for you.

The definitions of the member functions are given next. The definition of the constructor is as follows:

```
waitingCustomerQueueType::waitingCustomerQueueType(int size)
    :queueType<customerType>(size)
{
}
```

The function `updateWaitingQueue` increments the waiting time of each customer in the queue by one time unit. The `class` `waitingCustomerQueueType` is derived from the `class` `queueType`. Because the member variables of `queueType` are `private`, the function `updateWaitingQueue` cannot directly access the elements of the queue. The only way to access the elements of the queue is to use the `deleteQueue` operation. After incrementing the waiting time, the element can be put back into the queue by using the `addQueue` operation.

The `addQueue` operation inserts the element at the end of the queue. If we perform the `deleteQueue` operation followed by the `addQueue` operation for each element of the queue, then eventually the front element again becomes the front element. Given that each `deleteQueue` operation is followed by an `addQueue` operation, how do we determine that all of the elements of the queue have been processed? We cannot use the `isEmptyQueue` or `isFullQueue` operations on the queue, because the queue will never be empty or full.

One solution to this problem is to create a temporary queue. Every element of the original queue is removed, processed, and inserted into the temporary queue. When the original queue becomes empty, all of the elements in the queue are processed. We can then copy the elements from the temporary queue back into the original queue. However, this solution requires us to use extra memory space, which could be significant. Also, if the queue is large, extra computer time is needed to copy the elements from the temporary queue back into the original queue. Let us look into another solution.

In the second solution, before starting to update the elements of the queue, we can insert a dummy customer with a wait time of, say, `-1`. During the update process, when we arrive at the customer with the wait time of `-1`, we can stop the update process without processing the customer with the wait time of `-1`. If we do not process the customer with the wait time of `-1`, this customer is removed from the queue and, after processing all of the elements of the queue, the queue will contain no extra elements. This solution does not require us to create a temporary queue, so we do not need extra computer time to copy the elements back into the original queue. We will use this solution to update the queue. Therefore, the definition of the function `updateWaitingQueue` is:

```
void waitingCustomerQueueType::updateWaitingQueue()
{
    customerType cust;

    cust.setWaitingTime(-1);
    int wTime = 0;

    addQueue(cust);

    while (wTime != -1)
    {
        cust = front();
        deleteQueue();

        wTime = cust.getWaitingTime();
        if (wTime == -1)
            break;
        cust.incrementWaitingTime();
        addQueue(cust);
    }
}
```

Main Program

To run the simulation, we first need to get the following information:

- The number of time units the simulation should run. Assume that each time unit is one minute.
- The number of servers.
- The amount of time it takes to serve a customer—that is, the transaction time.
- The approximate time between customer arrivals.

These pieces of information are called simulation parameters. By changing the values of these parameters, we can observe the changes in the performance of the system. We can write a function, `setSimulationParameters`, to prompt the user to specify these values. The definition of this function is:

```
void setSimulationParameters(int& sTime, int& numOfServers,
                           int& transTime,
                           int& tBetweenCArrival)
{
    cout << "Enter the simulation time: ";
    cin >> sTime;
    cout << endl;

    cout << "Enter the number of servers: ";
    cin >> numOfServers;
    cout << endl;

    cout << "Enter the transaction time: ";
    cin >> transTime;
    cout << endl;

    cout << "Enter the time between customer arrivals: ";
    cin >> tBetweenCArrival;
    cout << endl;
}
```

When a server becomes free and the customer queue is nonempty, we can move the customer at the front of the queue to the free server to be served. Moreover, when a customer starts the transaction, the waiting time ends. The waiting time of the customer is added to the total waiting time. The general algorithm to start the transaction (supposing that `serverID` denotes the ID of the free server) is:

1. Remove the customer from the front of the queue.


```
customer = customerQueue.front();
customerQueue.deleteQueue();
```
2. Update the total wait time by adding the current customer's wait time to the previous total wait time.


```
totalWait = totalWait + customer.getWaitingTime();
```

3. Set the free server to begin the transaction.

```
serverList.setServerBusy(serverID, customer, transTime);
```

To run the simulation, we need to know the number of customers arriving at a given time unit and how long it takes to serve the customer. We use the Poisson distribution from statistics, which says that the probability of γ events occurring at a given time is given by the formula:

$$P(\gamma) = \frac{\lambda^\gamma e^{-\lambda}}{\gamma!}, \gamma = 0, 1, 2, \dots,$$

in which λ is the expected value that γ events occur at that time. Suppose that, on average, a customer arrives every four minutes. During this four-minute period, the customer can arrive at any one of the four minutes. Assuming an equal likelihood of each of the four minutes, the expected value that a customer arrives in each of the four minutes is, therefore, $1 / 4 = .25$. Next, we need to determine whether or not the customer actually arrives at a given minute.

Now, $P(0) = e^{-\lambda}$ is the probability that no event occurs at a given time. One of the basic assumptions of the Poisson distribution is that the probability of more than one outcome occurring in a short time interval is negligible. For simplicity, we assume that only one customer arrives at a given time unit. Thus, we use $e^{-\lambda}$ as the cutoff point to determine whether a customer arrives at a given time unit. Suppose that, on average, a customer arrives every four minutes. Then, $\lambda = 0.25$. We can use an algorithm to generate a number between 0 and 1. If the value of the number generated is $> e^{-0.25}$, we can assume that the customer arrived at a particular time unit. For example, suppose that $rNum$ is a random number such that $0 \leq rNum \leq 1$. If $rNum > e^{-0.25}$, the customer arrived at the given time unit.

We now describe the function `runSimulation` to implement the simulation. Suppose that we run the simulation for 100 time units and customers arrive at time units 93, 96, and 100. The average transaction time is five minutes—that is, five time units. For simplicity, assume that we have only one server and that the server becomes free at time unit 97, and that all customers arriving before time unit 93 have been served. When the server becomes free at time unit 97, the customer arriving at time unit 93 starts the transaction. Because the transaction of the customer arriving at time unit 93 starts at time unit 97 and it takes five minutes to complete a transaction, when the simulation loop ends, the customer arriving at time unit 93 is still at the server. Moreover, customers arriving at time units 96 and 100 are in the queue. For simplicity, we assume that when the simulation loop ends, the customers at the servers are considered served. The general algorithm for this function is:

1. Declare and initialize the variables, such as the simulation parameters, customer number, clock, total and average waiting times, number of customers arrived, number of customers served, number of customers left in the waiting queue, number of customers left with the servers, `waitingCustomersQueue`, and a list of servers.

2. The main loop is:


```
for (clock = 1; clock <= simulationTime; clock++)
{
    2.1. Update the server list to decrement the transaction time of each busy server
        by one time unit.

    2.2. If the customer's queue is nonempty, increment the waiting time of each
        customer by one time unit.

    2.3. If a customer arrives, increment the number of customers by 1 and add the
        new customer to the queue.

    2.4. If a server is free and the customer's queue is nonempty, remove a
        customer from the front of the queue and send the customer to
        the free server.
}
```
3. Print the appropriate results. Your results must include the number of customers left in the queue, the number of customers still with servers, the number of customers arrived, and the number of customers who actually completed a transaction.

Once you have designed the function `runSimulation`, the definition of the function `main` is simple and straightforward because the function `main` calls only the function `runSimulation`.

When we tested our version of the simulation program, we generated the following results. (The program was executed two times.) We assumed that the average transaction time is five minutes and that, on average, a customer arrives every four minutes, and we used a random number generator to generate a number between 0 and 1 to decide whether a customer arrived at a given time unit.

Sample Runs:

Sample Run 1:

```
Customer number 1 arrived at time unit 4
Customer number 2 arrived at time unit 8
From server number 1 customer number 1
    departed at time unit 9
Customer number 3 arrived at time unit 9
Customer number 4 arrived at time unit 12
From server number 1 customer number 2
    departed at time unit 14
From server number 1 customer number 3
    departed at time unit 19
Customer number 5 arrived at time unit 21
From server number 1 customer number 4
    departed at time unit 24
From server number 1 customer number 5
    departed at time unit 29
```

Customer number 6 arrived at time unit 37
 Customer number 7 arrived at time unit 38
 Customer number 8 arrived at time unit 41
 From server number 1 customer number 6
 departed at time unit 42
 Customer number 9 arrived at time unit 43
 Customer number 10 arrived at time unit 44
 From server number 1 customer number 7
 departed at time unit 47
 Customer number 11 arrived at time unit 49
 Customer number 12 arrived at time unit 51
 From server number 1 customer number 8
 departed at time unit 52
 Customer number 13 arrived at time unit 52
 Customer number 14 arrived at time unit 53
 Customer number 15 arrived at time unit 54
 From server number 1 customer number 9
 departed at time unit 57
 Customer number 16 arrived at time unit 59
 From server number 1 customer number 10
 departed at time unit 62
 Customer number 17 arrived at time unit 66
 From server number 1 customer number 11
 departed at time unit 67
 Customer number 18 arrived at time unit 71
 From server number 1 customer number 12
 departed at time unit 72
 From server number 1 customer number 13
 departed at time unit 77
 Customer number 19 arrived at time unit 78
 From server number 1 customer number 14
 departed at time unit 82
 From server number 1 customer number 15
 departed at time unit 87
 Customer number 20 arrived at time unit 90
 From server number 1 customer number 16
 departed at time unit 92
 Customer number 21 arrived at time unit 92
 From server number 1 customer number 17
 departed at time unit 97

The simulation ran for 100 time units
 Number of servers: 1
 Average transaction time: 5
 Average arrival time difference between customers: 4
 Total waiting time: 269
 Number of customers that completed a transaction: 17
 Number of customers left in the servers: 1
 The number of customers left in queue: 3
 Average waiting time: 12.81
 ***** END SIMULATION *****

Sample Run 2:

Customer number 1 arrived at time unit 4
 Customer number 2 arrived at time unit 8
 From server number 1 customer number 1
 departed at time unit 9

Customer number 3 arrived at time unit 9
Customer number 4 arrived at time unit 12
From server number 2 customer number 2
departed at time unit 13
From server number 1 customer number 3
departed at time unit 14
From server number 2 customer number 4
departed at time unit 18
Customer number 5 arrived at time unit 21
From server number 1 customer number 5
departed at time unit 26
Customer number 6 arrived at time unit 37
Customer number 7 arrived at time unit 38
Customer number 8 arrived at time unit 41
From server number 1 customer number 6
departed at time unit 42
From server number 2 customer number 7
departed at time unit 43
Customer number 9 arrived at time unit 43
Customer number 10 arrived at time unit 44
From server number 1 customer number 8
departed at time unit 47
From server number 2 customer number 9
departed at time unit 48
Customer number 11 arrived at time unit 49
Customer number 12 arrived at time unit 51
From server number 1 customer number 10
departed at time unit 52
Customer number 13 arrived at time unit 52
Customer number 14 arrived at time unit 53
From server number 2 customer number 11
departed at time unit 54
Customer number 15 arrived at time unit 54
From server number 1 customer number 12
departed at time unit 57
From server number 2 customer number 13
departed at time unit 59
Customer number 16 arrived at time unit 59
From server number 1 customer number 14
departed at time unit 62
From server number 2 customer number 15
departed at time unit 64
Customer number 17 arrived at time unit 66
From server number 1 customer number 16
departed at time unit 67
From server number 2 customer number 17
departed at time unit 71
Customer number 18 arrived at time unit 71
From server number 1 customer number 18
departed at time unit 76
Customer number 19 arrived at time unit 78
From server number 1 customer number 19
departed at time unit 83
Customer number 20 arrived at time unit 90
Customer number 21 arrived at time unit 92
From server number 1 customer number 20
departed at time unit 95

From server number 2 customer number 21
departed at time unit 97

The simulation ran for 100 time units
Number of servers: 2
Average transaction time: 5
Average arrival time difference between customers: 4
Total waiting time: 20
Number of customers that completed a transaction: 21
Number of customers left in the servers: 0
The number of customers left in queue: 0
Average waiting time: 0.95
***** END SIMULATION *****

QUICK REVIEW

1. A stack is a data structure in which the items are added and deleted from one end only.
2. A stack is a Last In First Out (LIFO) data structure.
3. The basic operations on a stack are as follows: push an item onto the stack, pop an item from the stack, retrieve the top element of the stack, initialize the stack, check whether the stack is empty, and check whether the stack is full.
4. A stack can be implemented as an array or a linked list.
5. The middle elements of a stack should not be accessed directly.
6. Stacks are restricted versions of arrays and linked lists.
7. Postfix notation does not require the use of parentheses to enforce operator precedence.
8. In postfix notation, the operators are written after the operands.
9. Postfix expressions are evaluated according to the following rules:
 - a. Scan the expression from left to right.
 - b. If an operator is found, back up to get the required number of operands, evaluate the operator, and continue.
10. A queue is a data structure in which the items are added at one end and removed from the other end.
11. A queue is a First In First Out (FIFO) data structure.
12. The basic operations on a queue are as follows: add an item to the queue, remove an item from the queue, retrieve the first or last element of the queue, initialize the queue, check whether the queue is empty, and check whether the queue is full.
13. A queue can be implemented as an array or a linked list.
14. The middle elements of a queue should not be accessed directly.
15. Queues are restricted versions of arrays and linked lists.

EXERCISES

1. Describe the two basic operations on a `stack`.
2. Suppose that `stack` is an object of type `stackType<int>`. What is the difference between `stack.top` and `stack.top - 1`?

3. Consider the following statements:

```
stackType<int> stack;
int x, y;
```

Show what is output by the following segment of code:

```
x = 4;
y = 0;
stack.push(7);
stack.push(x);
stack.push(x + 5);
y = stack.top();
stack.pop();
stack.push(x + y);
stack.push(y - 2);
stack.push(3);
x = stack.top();
stack.pop();

cout << "x = " << x << endl;
cout << "y = " << y << endl;

while (!stack.isEmptyStack())
{
    cout << stack.top() << endl;
    stack.pop();
}
```

4. Consider the following statements:

```
stackType<int> stack;
int x;
```

Suppose that the input is:

```
14 45 34 23 10 5 -999
```

Show what is output by the following segment of code:

```
stack.push(5);

cin >> x;

while (x != -999)
{
    if (x % 2 == 0)
    {
        if (!stack.isFullStack())
            stack.push(x);
    }
}
```

```

    else
        cout << "x = " << x << endl;
        cin >> x;
    }

```

```

cout << "Stack Elements: ";

```

```

while (!stack.isEmptyStack())
{
    cout << " " << stack.top();
    stack.pop();
}
cout << endl;

```

5. Evaluate the following postfix expressions:

- a. $8\ 2\ +\ 3\ *\ 16\ 4\ /\ -\ =$
- b. $12\ 25\ 5\ 1\ /\ /\ *\ 8\ 7\ +\ -\ =$
- c. $70\ 14\ 4\ 5\ 15\ 3\ /\ *\ -\ -\ /\ 6\ +\ =$
- d. $3\ 5\ 6\ *\ +\ 13\ -\ 18\ 2\ /\ +\ =$

6. Convert the following infix expressions to postfix notations.

- a. $(A + B) * (C + D) - E$
- b. $A - (B + C) * D + E / F$
- c. $((A + B) / (C - D) + E) * F - G$
- d. $A + B * (C + D) - E / F * G + H$

7. Write the equivalent infix expression for the following postfix expressions.

- a. $A\ B\ *\ C\ +$
- b. $A\ B\ +\ C\ D\ -\ *$
- c. $A\ B\ -\ C\ -\ D\ *$

8. What is the output of the following program?

```

#include <iostream>
#include <string>
#include "myStack.h"

using namespace std;

template <class type>
void mystery(stackType<type>& s, stackType<type>& t);

int main()
{
    stackType<string> s1;
    stackType<string> s2;

    string list[] = {"Winter", "Spring", "Summer", "Fall",
                    "Cold", "Warm", "Hot"};

```

```

    for (int i = 0; i < 7; i++)
        s1.push(list[i]);

    mystery(s1, s2);

    while (!s2.isEmptyStack())
    {
        cout << s2.top() << " ";
        s2.pop();
    }
    cout << endl;
}

template <class type>
void mystery(stackType<type>& s, stackType<type>& t)
{
    while (!s.isEmptyStack())
    {
        t.push(s.top());
        s.pop();
    }
}

```

9. What is the output of the following program?

```

#include <iostream>
#include <string>
#include "myStack.h"

using namespace std;

void mystery(stackType<int>& s, stackType<int>& t);

int main()
{
    int list[] = {5, 10, 15, 20, 25};

    stackType<int> s1;
    stackType<int> s2;

    for (int i = 0; i < 5; i++)
        s1.push(list[i]);

    mystery(s1, s2);

    while (!s2.isEmptyStack())
    {
        cout << s2.top() << " ";
        s2.pop();
    }
    cout << endl;
}

```

```

void mystery(stackType<int>& s, stackType<int>& t)
{
    while (!s.isEmptyStack())
    {
        t.push(2 * s.top());
        s.pop();
    }
}

```

10. Explain why, in the linked implementation of a **stack**, it is not necessary to implement the operation to determine whether the **stack** is full.
11. Suppose that **stack** is an object of type **linkedStackType<int>**. What is the difference between the statements **stack.top()**; and **stack.pop()**;
12. Write the definition of the function template **printListReverse** that uses a stack to print a linked list in reverse order. Assume that this function is a member of the **class** **linkedListType**, designed in Chapter 18.
13. Write the definition of the method **second** that takes as a parameter a stack object and returns the second element of the stack. The original stack remains unchanged.

14. Consider the following statements:

```

queueType<int> queue;
int x, y;

```

Show what is output by the following segment of code:

```

x = 4;
y = 5;
queue.addQueue(x);
queue.addQueue(y);
x = queue.front();
queue.deleteQueue();
queue.addQueue(x + 5);
queue.addQueue(16);
queue.addQueue(x);
queue.addQueue(y - 3);

cout << "Queue Elements: ";
while (!queue.isEmptyQueue())
{
    cout << queue.front() << " ";
    queue.deleteQueue();
}
cout << endl;

```

15. Consider the following statements:

```

stackType<int> stack;
queueType<int> queue;
int x;

```

Suppose the input is:

```
15 28 14 22 64 35 19 32 7 11 13 30 -999
```

Show what is written by the following segment of code:

```
stack.push(0);
queue.addQueue(0);
cin >> x;

while (x != -999)
{
    switch (x % 4)
    {
        case 0:
            stack.push(x);
            break;
        case 1:
            if (!stack.isEmptyStack())
            {
                cout << "Stack Element = " << stack.top()
                    << endl;
                stack.pop();
            }
            else
                cout << "Sorry, the stack is empty." << endl;
            break;
        case 2:
            queue.addQueue(x);
            break;
        case 3:
            if (!queue.isEmptyQueue())
            {
                cout << "Queue Element = " << queue.front()
                    << endl;
                queue.deleteQueue();
            }
            else
                cout << "Sorry, the queue is empty." << endl;
            break;
    } //end switch

    cin >> x;
} //end while

cout << "Stack Elements: ";
while (!stack.isEmptyStack())
{
    cout << stack.top() << " ";
    stack.pop();
}

cout << endl;
```

```

cout << "Queue Elements: ";
while (!queue.isEmptyQueue())
{
    cout << queue.front() << " ";
    queue.deleteQueue();
}
cout << endl;

```

16. What does the following function do?

```

void mystery(queueType<int>& q)
{
    stackType<int> s;

    while (!q.isEmptyQueue())
    {
        s.push(q.front());
        q.deleteQueue();
    }

    while (!s.isEmptyStack())
    {
        q.addQueue(2 * s.top());
        s.pop();
    }
}

```

17. Suppose that `queue` is a `queueType` object and the size of the array implementing `queue` is 100. Also, suppose that the value of `queueFront` is 50 and the value of `queueRear` is 99.
- What are the values of `queueFront` and `queueRear` after adding an element to `queue`?
 - What are the values of `queueFront` and `queueRear` after removing an element from `queue`?
18. Suppose that `queue` is a `queueType` object and the size of the array implementing `queue` is 100. Also, suppose that the value of `queueFront` is 99 and the value of `queueRear` is 25.
- What are the values of `queueFront` and `queueRear` after adding an element to `queue`?
 - What are the values of `queueFront` and `queueRear` after removing an element from `queue`?
19. Suppose that `queue` is a `queueType` object and the size of the array implementing `queue` is 100. Also, suppose that the value of `queueFront` is 25 and the value of `queueRear` is 75.
- What are the values of `queueFront` and `queueRear` after adding an element to `queue`?

- b. What are the values of `queueFront` and `queueRear` after removing an element from `queue`?
- 20. Suppose that `queue` is a `queueType` object and the size of the array implementing `queue` is 100. Also, suppose that the value of `queueFront` is 99 and the value of `queueRear` is 99.
 - a. What are the values of `queueFront` and `queueRear` after adding an element to `queue`?
 - b. What are the values of `queueFront` and `queueRear` after removing an element from `queue`?
- 21. Suppose that `queue` is implemented as an array with the special reserved slot, as described in this chapter. Also, suppose that the size of the array implementing `queue` is 100. If the value of `queueFront` is 50, what is the position of the first `queue` element?
- 22. Suppose that `queue` is implemented as an array with the special reserved slot, as described in this chapter. Suppose that the size of the array implementing `queue` is 100. Also, suppose that the value of `queueFront` is 74 and the value of `queueRear` is 99.
 - a. What are the values of `queueFront` and `queueRear` after adding an element to `queue`?
 - b. What are the values of `queueFront` and `queueRear` after removing an element from `queue`? Also, what is the position of the removed `queue` element?
- 23. Write a function template, `reverseStack`, that takes as a parameter a stack object and uses a queue object to reverse the elements of the stack.
- 24. Write a function template, `reverseQueue`, that takes as a parameter a queue object and uses a stack object to reverse the elements of the queue.
- 25. Add the operation `queueCount` to the `class` `queueType` (the array implementation of queues), which returns the number of elements in the queue. Write the definition of the function template to implement this operation.
- 26. Draw the UML class diagram of the `class` `linkedStackType`.
- 27. Draw the UML class diagram of the `class` `queueADT`.
- 28. Draw the UML class diagram of the `class` `queueType`.
- 29. Draw the UML class diagram of the `class` `linkedQueueType`.

PROGRAMMING EXERCISES

1. Two stacks of the same type are the same if they have the same number of elements and their elements at the corresponding positions are the same. Overload the relational operator `==` for the `class` `stackType` that returns

true if two stacks of the same type are the same; it returns **false** otherwise. Also, write the definition of the function template to overload this operator.

2. Repeat Exercise 1 for the **class** `linkedStackType`.
3. a. Add the following operation to the **class** `stackType`.

```
void reverseStack(stackType<Type> &otherStack);
```

This operation copies the elements of a stack in reverse order onto another stack.

Consider the following statements:

```
stackType<int> stack1;
stackType<int> stack2;
```

The statement:

```
stack1.reverseStack(stack2);
```

copies the elements of `stack1` onto `stack2` in reverse order. That is, the top element of `stack1` is the bottom element of `stack2`, and so on. The old contents of `stack2` are destroyed, and `stack1` is unchanged.

- b. Write the definition of the function **template** to implement the operation `reverseStack`.
4. Repeat Exercises 3a and 3b for the **class** `linkedStackType`.
5. Write a program that takes as input an arithmetic expression. The program outputs whether the expression contains matching grouping symbols. For example, the arithmetic expressions `{25 + (3 - 6) * 8}` and `7 + 8 * 2` contain matching grouping symbols. However, the expression `5 + { (13 + 7) / 8 - 2 * 9` does not contain matching grouping symbols.
6. Write a program that uses a stack to print the prime factors of a positive integer in descending order.
7. The Programming Example, Converting a Number from Binary to Decimal, in Chapter 17, uses recursion to convert a binary number into an equivalent decimal number. Write a program that uses a stack to convert a binary number into an equivalent decimal number.
8. The Programming Example, Converting a Number from Decimal to Binary, in Chapter 17, contains a program that uses recursion to convert a decimal number into an equivalent binary number. Write a program that uses a stack to convert a decimal number into an equivalent binary number.
9. Write a program that reads a string consisting of a positive integer or a positive decimal number and converts the number to the numeric format. If the string consists of a decimal number, the program must use a stack to convert the decimal number to the numeric format.

- 10. (Infix to Postfix)** Write a program that converts an infix expression into an equivalent postfix expression.

The rules to convert an infix expression into an equivalent postfix expression are as follows:

Suppose **infx** represents the infix expression and **pfxf** represents the postfix expression. The rules to convert **infx** into **pfxf** are as follows:

- a. Initialize **pfxf** to an empty expression and also initialize the stack.
- b. Get the next symbol, **sym**, from **infx**.
 - b.1. If **sym** is an operand, append **sym** to **pfxf**.
 - b.2. If **sym** is **(**, push **sym** into the stack.
 - b.3. If **sym** is **)**, pop and append all of the symbols from the stack until the most recent left parentheses. Pop and discard the left parentheses.
 - b.4. If **sym** is an operator:
 - b.4.1. Pop and append all of the operators from the stack to **pfxf** that are above the most recent left parentheses and have precedence greater than or equal to **sym**.
 - b.4.2. Push **sym** onto the stack.
- c. After processing **infx**, some operators might be left in the stack. Pop and append to **pfxf** everything from the stack.

In this program, you will consider the following (binary) arithmetic operators: **+**, **-**, *****, and **/**. You may assume that the expressions you will process are error free.

Design a class that stores the infix and postfix strings. The class must include the following operations:

- **getInfix**: Stores the infix expression.
- **showInfix**: Outputs the infix expression.
- **showPostfix**: Outputs the postfix expression.

Some other operations that you might need are:

- **convertToPostfix**: Converts the infix expression into a postfix expression. The resulting postfix expression is stored in **pfxf**.
- **precedence**: Determines the precedence between two operators. If the first operator is of higher or equal precedence than the second operator, it returns the value **true**; otherwise, it returns the value **false**.

Include the constructors and destructors for automatic initialization and dynamic memory deallocation.

Test your program on the following expressions:

- a. $A + B - C;$
- b. $(A + B) * C;$
- c. $(A + B) * (C - D);$
- d. $A + ((B + C) * (E - F) - G) / (H - I);$
- e. $A + B * (C + D) - E / F * G + H;$

For each expression, your answer must be in the following form:

Infix Expression: $A + B - C;$

Postfix Expression: $A B + C -$

11. Write the definitions of the functions to overload the assignment operator and copy constructor for the `class queueType`. Also, write a program to test these operations.
12. Write the definitions of the functions to overload the assignment operator and copy constructor for the `class linkedQueueType`. Also, write a program to test these operations.
13. This chapter describes the array implementation of queues that use a special array slot, called the reserved slot, to distinguish between an empty and a full queue. Write the definition of the class and the definitions of the function members of this queue design. Also, write a test program to test various operations on a queue.
14. Write the definition of the function `moveNthFront` that takes as a parameter a positive integer, n . The function moves the n th element of the queue to the front. The order of the remaining elements remains unchanged. For example, suppose:

`queue = {5, 11, 34, 67, 43, 55}` and $n = 3$.

After a call to the function `moveNthFront`:

`queue = {34, 5, 11, 67, 43, 55}`.

Add this function to the `class queueType`. Also, write a program to test your method.

15. Write a program that reads a line of text, changes each uppercase letter to lowercase, and places each letter both in a queue and onto a stack. The program should then verify whether the line of text is a palindrome (a set of letters or numbers that is the same whether read forward or backward).
16. The implementation of a queue in an array, as given in this chapter, uses the variable `count` to determine whether the queue is empty or full. You can also use the variable `count` to return the number of elements in the `queue`. On the other hand, `class linkedQueueType` does not use such a variable to keep track of the number of elements in the queue. Redefine the `class linkedQueueType` by adding the variable `count` to keep track of the number of elements in the queue. Modify the definitions of the functions

`addQueue` and `deleteQueue` as necessary. Add the function `queueCount` to return the number of elements in the queue. Also, write a program to test various operations of the class you defined.

17. Write the definition of the `class` `linkedQueueType`, which is derived from the `class` `unorderedLinkedList`, as explained in this chapter. Also, write a program to test various operations of this class.
18.
 - a. Write the definitions of the functions `setWaitingTime`, `getArrivalTime`, `getTransactionTime`, and `getCustomerNumber` of the `class` `customerType` defined in the section Application of Queues: Simulation.
 - b. Write the definitions of the functions `getRemainingTransactionTime`, `setCurrentCustomer`, `getCurrentCustomerNumber`, `getCurrentCustomerArrivalTime`, `getCurrentCustomerWaitingTime`, and `getCurrentCustomerTransactionTime` of the `class` `serverType` defined in the section Application of Queues: Simulation.
 - c. Write the definition of the function `runSimulation` to complete the design of the computer simulation program (see the section Application of Queues: Simulation). Test run your program for a variety of data. Moreover, use a random number generator to decide whether a customer arrived at a given time unit.



APPENDIX A

RESERVED WORDS

| | | | |
|-------------------------------|------------------------|--------------------------|-----------------------|
| <code>and</code> | <code>and_eq</code> | <code>asm</code> | <code>auto</code> |
| <code>bitand</code> | <code>bitor</code> | <code>bool</code> | <code>break</code> |
| <code>case</code> | <code>catch</code> | <code>char</code> | <code>class</code> |
| <code>compl</code> | <code>const</code> | <code>const_cast</code> | <code>continue</code> |
| <code>default</code> | <code>delete</code> | <code>do</code> | <code>double</code> |
| <code>dynamic_cast</code> | <code>else</code> | <code>enum</code> | <code>explicit</code> |
| <code>export</code> | <code>extern</code> | <code>false</code> | <code>float</code> |
| <code>for</code> | <code>friend</code> | <code>goto</code> | <code>if</code> |
| <code>include</code> | <code>inline</code> | <code>int</code> | <code>long</code> |
| <code>mutable</code> | <code>namespace</code> | <code>new</code> | <code>not</code> |
| <code>not_eq</code> | <code>operator</code> | <code>or</code> | <code>or_eq</code> |
| <code>private</code> | <code>protected</code> | <code>public</code> | <code>register</code> |
| <code>reinterpret_cast</code> | <code>return</code> | <code>short</code> | <code>signed</code> |
| <code>sizeof</code> | <code>static</code> | <code>static_cast</code> | <code>struct</code> |
| <code>switch</code> | <code>template</code> | <code>this</code> | <code>throw</code> |
| <code>true</code> | <code>try</code> | <code>typedef</code> | <code>typeid</code> |
| <code>typename</code> | <code>union</code> | <code>unsigned</code> | <code>using</code> |
| <code>virtual</code> | <code>void</code> | <code>volatile</code> | <code>wchar_t</code> |
| <code>while</code> | <code>xor</code> | <code>xor_eq</code> | |

This page intentionally left blank

APPENDIX B

OPERATOR PRECEDENCE

The following table shows the precedence (highest to lowest) and associativity of the operators in C++.

| Operator | Associativity |
|---------------------------------------------------|---------------|
| :: (binary scope resolution) | Left to right |
| :: (unary scope resolution) | Right to left |
| () | Left to right |
| [] -> . | Left to right |
| ++ -- (as postfix operators) | Right to left |
| typeid dynamic_cast | Right to left |
| static_cast const_cast | Right to left |
| reinterpret_cast | Right to left |
| ++ -- (as prefix operators) ! + (unary) - (unary) | Right to left |
| ~ & (address of) * (dereference) | Right to left |
| new delete sizeof | Right to left |
| ->* -- .* | Left to right |
| * / % | Left to right |
| + - | Left to right |
| << >> | Left to right |
| < <= > >= | Left to right |
| == != | Left to right |
| & | Left to right |
| ^ | Left to right |

| Operator | Associativity |
|----------------------------------|---------------|
| | Left to right |
| && | Left to right |
| | Left to right |
| ? : | Right to left |
| = += -= *= /= % = | Right to left |
| <<= >>= &= = ^= | Right to left |
| throw | Right to left |
| , (the sequencing operator) | Left to right |



APPENDIX C

CHARACTER SETS

ASCII (American Standard Code for Information Interchange)

The following table shows the ASCII character set.

| ASCII | | | | | | | | | | |
|-------|-----|-----|----------|-----|-----|-----|-----|-----|-----|-----|
| | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
| 0 | nul | soh | stx | etx | eot | enq | ack | bel | bs | ht |
| 1 | lf | vt | ff | cr | so | si | dle | dc1 | dc2 | dc3 |
| 2 | dc4 | nak | syn | etb | can | em | sub | esc | fs | gs |
| 3 | rs | us | <u>b</u> | ! | " | # | \$ | % | & | ' |
| 4 | (|) | * | + | , | - | . | / | 0 | 1 |
| 5 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | : | ; |
| 6 | < | = | > | ? | @ | A | B | C | D | E |
| 7 | F | G | H | I | J | K | L | M | N | O |
| 8 | P | Q | R | S | T | U | V | W | X | Y |
| 9 | Z | [| \ |] | ^ | _ | ` | a | b | c |
| 10 | d | e | f | g | h | i | j | k | l | m |
| 11 | n | o | p | q | r | s | t | u | v | w |
| 12 | x | y | z | { | | } | ~ | del | | |

The numbers 0-12 in the first column specify the left digit(s), and the numbers 0-9 in the second row specify the right digit of each character in the ASCII data set. For example,

| EBCDIC | | | | | | | | | | |
|--------|---|---|---|---|---|---|---|---|---|---|
| 11 | > | ? | | | | | | | | |
| 12 | | ` | : | # | @ | ' | = | " | | a |
| 13 | b | c | d | e | f | g | h | i | | |
| 14 | | | | | | j | k | l | m | n |
| 15 | o | p | q | r | | | | | | |
| 16 | | ~ | s | t | u | v | w | x | y | z |
| 17 | | | | | | | | | | |
| 18 | [|] | | | | | | | | |
| 19 | | | | A | B | C | D | E | F | G |
| 20 | H | I | | | | | | | | J |
| 21 | K | L | M | N | O | P | Q | R | | |
| 22 | | | | | | | S | T | U | V |
| 23 | W | X | Y | Z | | | | | | |
| 24 | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |

The numbers 6–24 in the first column specify the left digit(s), and the numbers 0–9 in the second row specify the right digits of the characters in the EBCDIC data set. For example, the character in the row marked 19 (the number in the first column) and the column marked 3 (the number in the second row) is **A**. Therefore, the character at position 193 (which is the 194th character) is **A**. Moreover, the character b at position 64 represents the space character. The preceding table does not show all the characters in the EBCDIC character set. In fact, the characters at positions 00–63 and 250–255 are nonprintable control characters.

This page intentionally left blank



APPENDIX D

OPERATOR OVERLOADING

The following table lists the operators that can be overloaded.

| Operators that can be overloaded | | | | | | | |
|----------------------------------|----|----|----|-----|-----|-----|--------|
| + | - | * | / | % | ^ | & | |
| ! | && | | = | == | < | <= | > |
| >= | != | += | -= | *= | /= | %= | ^= |
| = | &= | << | >> | >>= | <<= | ++ | - |
| ->* | , | -> | [] | () | ~ | new | delete |

The following table lists the operators that cannot be overloaded.

| Operators that cannot be overloaded | | | | |
|-------------------------------------|----|----|----|--------|
| . | .* | :: | :: | sizeof |

This page intentionally left blank



APPENDIX E

ADDITIONAL C++ TOPICS

Binary (Base 2) Representation of a Nonnegative Integer

Converting a Base 10 Number to a Binary Number (Base 2)

Chapter 1 remarked that **A** is the 66th character in the ASCII character set, but its position is 65 because the position of the first character is 0. Furthermore, the binary number 1000001 is the binary representation of 65. The number system that we use daily is called the **decimal number system** or **base 10 system**. The number system that the computer uses is called the **binary number system** or **base 2 system**. In this section, we describe how to find the binary representation of a nonnegative integer and vice versa.

Consider 65. Note that:

$$65 = 1 \times 2^6 + 0 \times 2^5 + 0 \times 2^4 + 0 \times 2^3 + 0 \times 2^2 + 0 \times 2^1 + 1 \times 2^0$$

Similarly:

$$711 = 1 \times 2^9 + 0 \times 2^8 + 1 \times 2^7 + 1 \times 2^6 + 0 \times 2^5 + 0 \times 2^4 + 0 \times 2^3 + 1 \times 2^2 + 1 \times 2^1 + 1 \times 2^0$$

In general, if m is a nonnegative integer, then m can be written as:

$$m = a_k \times 2^k + a_{k-1} \times 2^{k-1} + a_{k-2} \times 2^{k-2} + \cdots + a_1 \times 2^1 + a_0 \times 2^0,$$

for some nonnegative integer k , and where $a_i = 0$ or 1 , for each $i = 0, 1, 2, \dots, k$. The binary number $a_k a_{k-1} a_{k-2} \dots a_1 a_0$ is called the **binary** or **base 2 representation** of m . In this case, we usually write:

$$m_{10} = (a_k a_{k-1} a_{k-2} \dots a_1 a_0)_2$$

and say that m to the base 10 is $a_k a_{k-1} a_{k-2} \dots a_1 a_0$ to the base 2.

For example, for the integer 65, $k = 6$, $a_6 = 1$, $a_5 = 0$, $a_4 = 0$, $a_3 = 0$, $a_2 = 0$, $a_1 = 0$, $a_0 = 1$. Thus, $a_6 a_5 a_4 a_3 a_2 a_1 a_0 = 1000001$, so the binary representation of 65 is 1000001, that is:

$$65_{10} = (1000001)_2.$$

If no confusion arises, then we write $(1000001)_2$ as 1000001_2 .

Similarly, for the number 711, $k = 9$, $a_9 = 1$, $a_8 = 0$, $a_7 = 1$, $a_6 = 1$, $a_5 = 0$, $a_4 = 0$, $a_3 = 0$, $a_2 = 1$, $a_1 = 1$, $a_0 = 1$. Thus:

$$711_{10} = 1011000111_2.$$

It follows that to find the binary representation of a nonnegative, we need to find the coefficients, which are 0 or 1, of various powers of 2. However, there is an easy algorithm, described next, that can be used to find the binary representation of a nonnegative integer. First, note that:

$$0_{10} = 0_2, 1_{10} = 1_2, 2_{10} = 10_2, 3_{10} = 11_2, 4_{10} = 100_2, 5_{10} = 101_2, 6_{10} = 110_2, \\ \text{and } 7_{10} = 111_2.$$

Let us consider the integer 65. Note that $65 / 2 = 32$ and $65 \% 2 = 1$, where $\%$ is the mod operator. Next, $32 / 2 = 16$, and $32 \% 2 = 0$, and so on. It can be shown that $a_0 = 65 \% 2 = 1$, $a_1 = 32 \% 2 = 0$, and so on. We can show this continuous division and obtaining the remainder with the help of Figure E-1.




FIGURE E-1 Determining the binary representation of 65

Notice that in Figure E-1(a), starting at the second row, the second column contains the quotient when the number in the previous row is divided by 2 and the third column contains the remainder of that division. For example, in the second row, $65 / 2 = 32$, and $65 \% 2 = 1$. In the third row, $32 / 2 = 16$ and $32 \% 2 = 0$, and so on. For each row, the number in the second column is divided by 2, the quotient is written in the next row, below the current row, and the remainder is written in the third column. When using a

figure, such as E-1, to find the binary representation of a nonnegative integer, typically, we show only the quotients and remainders as in Figure E-1(b). You can write the binary representation of the number starting with the last remainder in the third column, followed by the second last remainder, and so on. Thus:

$65_{10} = 1000001_2.$

Next, consider the number 711. Figure E-2 shows the quotients and the remainders.




FIGURE E-2 Determining the binary representation of 711

From Figure E-2, it follows that:

$711_{10} = 1011000111_2.$

Converting a Binary Number (Base 2) to Base 10

To convert a number from base 2 to base 10, we first find the weight of each bit in the binary number. The weight of each bit in the binary number is assigned from right to left. The weight of the rightmost bit is 0. The weight of the bit immediately to the left of the rightmost bit is 1, the weight of the bit immediately to the left of it is 2, and so on. Consider the binary number 1001101. The weight of each bit is as follows:

| | | | | | | | |
|--------|---|---|---|---|---|---|---|
| weight | 6 | 5 | 4 | 3 | 2 | 1 | 0 |
| | 1 | 0 | 0 | 1 | 1 | 0 | 1 |

We use the weight of each bit to find the equivalent decimal number. For each bit, we multiply the bit by 2 to the power of its weight and then we add all of the numbers. For the above binary number, the equivalent decimal number is:

$$\begin{aligned} &1 \times 2^6 + 0 \times 2^5 + 0 \times 2^4 + 1 \times 2^3 + 1 \times 2^2 + 0 \times 2^1 + 1 \times 2^0 \\ &= 64 + 0 + 0 + 8 + 4 + 0 + 1 \\ &= 77. \end{aligned}$$

Converting a Binary Number (Base 2) to Octal (Base 8) and Hexadecimal (Base 16)

The previous sections described how to convert a binary number to a decimal number (base 2). Even though the language of a computer is binary, if the binary number is too long, then it will be hard to manipulate it manually. To effectively deal with binary numbers, two more number systems, octal (base 8) and hexadecimal (base 16), are of interest to computer scientists.

The digits in the octal number system are 0, 1, 2, 3, 4, 5, 6, and 7. The digits in the hexadecimal number system are 0, 1, 2, 3, 4, 5, 6, 7, 8, 9, A, B, C, D, E, and F. So A in hexadecimal is 10 in decimal, B in hexadecimal is 11 in decimal, and so on.

The algorithm to convert a binary number into an equivalent number in octal (or hexadecimal) is quite simple. Before we describe the method to do so, let us review some notations. Suppose a_b represents the number a to the base b . For example, $2A0_{16}$ means 2A0 to the base 16, and 63_8 means 63 to the base 8.

First we describe how to convert a binary number into an equivalent octal number and vice versa. Table E-1 describes the first eight octal numbers.

TABLE E-1 Binary representation of first eight octal numbers

| Binary | Octal | Binary | Octal |
|--------|-------|--------|-------|
| 000 | 0 | 100 | 4 |
| 001 | 1 | 101 | 5 |
| 010 | 2 | 110 | 6 |
| 011 | 3 | 111 | 7 |

Consider the binary number 1101100010101. To find the equivalent octal number, starting from right to left we consider three digits at a time and write their octal representation. Note that the binary number 1101100010101 has only 13 digits. So when

we consider three digits at a time, at the end we will be left with only one digit. In this case, we just add two 0s to the left of the binary number; the equivalent binary number is 001101100010101. Thus,

$$\begin{aligned}
 1101100010101_2 &= 001101100010101_2 \\
 &= 001\ 101\ 100\ 010\ 101 \\
 &= 15425_8 \text{ because } 001_2 = 1_8, 101_2 = 5_8, 100_2 = 4_8, 010_2 = 2_8, \\
 &\quad \text{and } 101_2 = 5_8
 \end{aligned}$$

Thus, $1101100010101_2 = 15425_8$.

To convert an octal number into an equivalent binary number, using Table E-1, write the binary representation of each octal digit in the number. For example,

$$\begin{aligned}
 3761_8 &= 011\ 111\ 110\ 001_2 \\
 &= 011111110001_2 \\
 &= 11111110001_2
 \end{aligned}$$

Thus, $3761_8 = 11111110001_2$.

Next we discuss how to convert a binary number into an equivalent hexadecimal number and vice versa. The method to do so is similar to converting a number from binary to octal and vice versa, except that here we work with four binary digits. Table E-2 gives the binary representation of the first 16 hexadecimal numbers.

TABLE E-2 Binary representation of first 16 hexadecimal numbers

| Binary | Hexadecimal | Binary | Hexadecimal |
|--------|-------------|--------|-------------|
| 0000 | 0 | 1000 | 8 |
| 0001 | 1 | 1001 | 9 |
| 0010 | 2 | 1010 | A |
| 0011 | 3 | 1011 | B |
| 0100 | 4 | 1100 | C |
| 0101 | 5 | 1101 | D |
| 0110 | 6 | 1110 | E |
| 0111 | 7 | 1111 | F |

Consider the binary number 1111101010001010101_2 . Now,

$$\begin{aligned} 1111101010001010101_2 &= 111\ 1101\ 0100\ 0101\ 0101_2 \\ &= 0111\ 1101\ 0100\ 0101\ 0101_2, \text{ add one zero to the left} \\ &= 7D455_{16} \end{aligned}$$

Hence, $1111101010001010101_2 = 7D455_{16}$.

Next, to convert a hexadecimal number into an equivalent binary number, write the four-digit binary representation of each hexadecimal digit into that number. For example,

$$\begin{aligned} A7F32_{16} &= 1010\ 0111\ 1111\ 0011\ 0010_2 \\ &= 10100111111100110010_2 \end{aligned}$$

Thus, $A7F32_{16} = 10100111111100110010_2$.

More on File Input/Output

In Chapter 3, you learned how to read data from and write data to a file. This section expands on the concepts introduced in that chapter.

Binary Files

In Chapter 3, you learned how to make a program read data from and write data to a file. However, the files that the programs have used until now are called text files. Data in a text file is stored in the character format. For example, consider the number 45. If 45 is stored in a file, then it is stored as a sequence of two characters—the character '4' followed by the character '5'. The eight-bit machine representation of '4' is 00000100 and the eight-bit machine representation of '5' is 00000101. Therefore, in a text file, 45 is stored as 00000100000000101. When this number is read by a C++ program, it must first be converted to its binary format. Suppose that the integers are represented as 16-bit binary numbers. The 16-bit binary representation of 45 is then 0000000000101101. Similarly, when a program stores the number 45 in a text file, it first must be converted to its text format. It thus follows that reading data from and writing data to a text file is not efficient, because the data must be converted from the text to the binary format and vice versa.

On the other hand, when data is stored in a file in the binary format, reading and writing data is faster because no time is lost in converting the data from one format to another format. Such files are called binary files. More formally, **binary files** are files in which data is stored in the binary format. Data in a text file is also called **formatted data**, and in a binary file it is called **raw data**.

C++ allows a programmer to create binary files. This section explains how to create binary files and also how to read data from binary files.

To create a binary file, the file must be opened in the binary mode. Suppose `outFile` is an `ofstream` variable (object). Consider the following statement:

```
outFile.open("employee.dat", ios::binary);
```

This statement opens the file `employee.dat`. Data in this file will be written in its binary format. Therefore, the file opening mode `ios::binary` specifies that the file is opened in the binary mode.

Next, you use the stream function `write` to write data to the file `employee.dat`. The syntax to use the function `write` is:

```
fileVariableName.write(reinterpret_cast<const char *> (buffer),
                        sizeof(buffer));
```

where `fileVariableName` is the object used to open the output file, and the first argument `buffer` specifies the starting address of the location in memory where the data is stored. The expression `sizeof(buffer)` specifies the size of the data, in bytes, to be written.

For example, suppose `num` is an `int` variable. The following statement writes the value of `num` in the binary format to the file associated with `outFile`:

```
outFile.write(reinterpret_cast<const char *> (&num),
              sizeof(num));
```

Similarly, suppose `empSalary` is an array of, say, 100 components and the component type is `double`. The following statement writes the entire array to the file associated with `outFile`:

```
outFile.write(reinterpret_cast<const char *> (empSalary),
              sizeof(empSalary));
```

Next, let us discuss how to read data from a binary file. The operation of reading data from a binary file is similar to writing data to a binary file. First, the binary file must be opened. For example, suppose `inFile` is an `ifstream` variable, and a program has already created the binary file `employee.dat`. The following statement opens this file:

```
inFile.open("employee.dat");
```

or:

```
inFile.open("employee.dat", ios::binary);
```

To read data in the binary format, the stream function `read` is used. The syntax to use the function `read` is:

```
fileVariableName.read(reinterpret_cast<char *> (buffer),
                      sizeof(buffer));
```

The first argument `buffer` specifies the starting address of the location in memory where the data is to be stored. The expression `sizeof(buffer)` specifies the size of the data, in bytes, to be read.

The program in the following example further explains how to create binary files and read data from a binary file.

EXAMPLE E-1

//Creating and reading binary files

```
#include <iostream>
#include <fstream>

using namespace std;

struct studentType
{
    char firstName[15];
    char lastName[15];
    int ID;
};

int main()
{
    //create and initialize an array of students' IDs
    int studentIDs[5] = {111111, 222222, 333333,
                        444444, 555555};           //Line 1

    //declare and initialize the struct newStudent
    studentType newStudent = {"John", "Wilson",
                             777777};           //Line 2

    ofstream outFile;                               //Line 3

    //open the output file as a binary file
    outFile.open("ids.dat", ios::binary);          //Line 4

    //write the array in the binary format
    outFile.write(reinterpret_cast<const char *> (studentIDs),
                 sizeof(studentIDs));              //Line 5
    //write the newStudent data in the binary format
    outFile.write(reinterpret_cast<const char *> (&newStudent),
                 sizeof(newStudent));              //Line 6

    outFile.close(); //close the file              //Line 7

    ifstream inFile;                               //Line 8
    int arrayID[5];                                //Line 9
    studentType student;                          //Line 10
```

```

        //open the input file
inFile.open("ids.dat");                                //Line 11

if (!inFile)                                            //Line 12
{
    cout << "The input file does not exist. "
        << "The program terminates!!!!" << endl; //Line 13
    return 1;                                         //Line 14
}

        //input the data into the array arrayID
inFile.read(reinterpret_cast<char *> (arrayID),
            sizeof(arrayID));                        //Line 15
        //output the data of the array arrayID
for (int i = 0; i < 5; i++)                            //Line 16
    cout << arrayID[i] << " ";                      //Line 17
cout << endl;                                         //Line 18

        //read the student's data
inFile.read(reinterpret_cast<char *> (&student),
            sizeof(student));                        //Line 19

        //output studentData
cout << student.ID << " " << student.firstName
    << " " << student.lastName << endl;            //Line 20

inFile.close();    //close the file                //Line 21

return 0;                                              //Line 22
}

```

Sample Run:

```

111111 222222 333333 444444 555555
777777 John Wilson

```

The output of the preceding program is self-explanatory. The details are left as an exercise for you.

NOTE

In the program in Example E-1, the statement in Line 2 declares the **struct** variable **newStudent** and also initializes it. Because **newStudent** has three components and we want to initialize all the components, three values are specified in braces separated by commas. In other words, **struct** variables can also be initialized when they are declared.

The program in the following example further explains how to create binary files and then read the data from the binary files.

EXAMPLE E-2

```

//Creating and reading a binary file consisting of
//bank customers' data

#include <iostream>
#include <fstream>
#include <iomanip>

using namespace std;

struct customerType
{
    char firstName[15];
    char lastName[15];
    int ID;
    double balance;
};

int main()
{
    customerType cust;
    ifstream inFile;
    ofstream outFile;

    inFile.open("customerData.txt");

    if (!inFile)
    {
        cout << "The input file does not exist. "
              << "The program terminates!!!!" << endl;
        return 1;
    }

    outFile.open("customer.dat", ios::binary);

    inFile >> cust.ID >> cust.firstName >> cust.lastName
              >> cust.balance;

    while (inFile)
    {
        outFile.write(reinterpret_cast<const char *> (&cust),
                      sizeof(cust));
        inFile >> cust.ID >> cust.firstName >> cust.lastName
              >> cust.balance;

    }

    inFile.close();
    inFile.clear();
    outFile.close();

```

```

inFile.open("customer.dat", ios::binary);           //Line 16

if (!inFile)                                       //Line 17
{
    cout << "The input file does not exist. "
        << "The program terminates!!!!" << endl; //Line 18
    return 1;                                     //Line 19
}

cout << left << setw(8) << "ID"
    << setw(16) << "First Name"
    << setw(16) << "Last Name"
    << setw(10) << " Balance" << endl;           //Line 20
cout << fixed << showpoint << setprecision(2);   //Line 21

    //read and output the data from the binary
    //file customer.dat
inFile.read(reinterpret_cast<char *> (&cust),
    sizeof(cust));                               //Line 22
while (inFile)                                   //Line 23
{
    cout << left << setw(8) << cust.ID
        << setw(16) << cust.firstName
        << setw(16) << cust.lastName
        << right << setw(10) << cust.balance
        << endl;                               //Line 24
    inFile.read(reinterpret_cast<char *> (&cust),
        sizeof(cust));                         //Line 25
}

inFile.close();                                  //close the file           //Line 26

return 0;                                         //Line 27
}

```

Sample Run:

| ID | First Name | Last Name | Balance |
|-------|------------|-----------|-----------|
| 77234 | Ashley | White | 4563.50 |
| 12345 | Brad | Smith | 128923.45 |
| 87123 | Lisa | Johnson | 2345.93 |
| 81234 | Sheila | Robinson | 674.00 |
| 11111 | Rita | Gupta | 14863.50 |
| 23422 | Ajay | Kumar | 72682.90 |
| 22222 | Jose | Ramey | 25345.35 |
| 54234 | Sheila | Duffy | 65222.00 |
| 55555 | Tommy | Pitts | 892.85 |
| 23452 | Salma | Quade | 2812.90 |
| 32657 | Jennifer | Ackerman | 9823.89 |
| 82722 | Steve | Sharma | 78932.00 |

Random File Access

In Chapter 3 and the preceding section, you learned how to read data from and write data to a file. More specifically, you used `ifstream` objects to read data from a file and `ofstream` objects to write data to a file. However, the files were read and/or written sequentially. Reading data from a file sequentially does not work very well for a variety of applications. For example, consider a program that processes customers' data in a bank. Typically, there are thousands or even millions of customers in a bank. Suppose we want to access a customer's data from the file that contains such data, say, for an account update. If the data is accessed sequentially, starting from the first position and read until the desired customer's data is found, this process might be extremely time consuming. Similarly, in an airline's reservation system to access a passenger's reservation information sequentially, this might also be very time consuming. In such cases, the data retrieval must be efficient. A convenient way to do this is to be able to read the data randomly from a file, that is, randomly access any record in the file.

In the preceding section, you learned how to use the stream function `read` to read a specific number of bytes, and the function `write` to write a specific number of bytes.

The stream function `seekg` is used to move the read position to any byte in the file. The general syntax to use the function `seekg` is:

```
fileVariableName.seekg(offset, position);
```

The stream function `seekp` is used to move the write position to any byte in the file. The general syntax to use the function `seekp` is:

```
fileVariableName.seekp(offset, position);
```

The `offset` specifies the number of bytes the reading/writing positions are to be moved, and `position` specifies where to begin the offset. The offset can be calculated from the beginning of the file, end of the file, or the current position in the file. Moreover, `offset` is a long integer representation of an offset. Table E-3 shows the values that can be used for `position`.

TABLE E-3 Values of `position`

| position | Description |
|-----------------------|---------------------------------------------------------------------------------------|
| <code>ios::beg</code> | The offset is calculated from the beginning of the file. |
| <code>ios::cur</code> | The offset is calculated from the current position of the reading marker in the file. |
| <code>ios::end</code> | The offset is calculated from the end of the file. |

EXAMPLE E-3

Suppose you have the following line of text stored in a file, say, `digitsAndLetters.txt`:

```
0123456789ABCDEFGHIJKLMNOPQRSTUVWXYZ
```

Also, suppose that `inFile` is an `ifstream` object and the file `digitsAndLetters.txt` has been opened using the object `inFile`. One byte is used to store each character of this line of text. Moreover, the position of the first character is 0.

| Statement | Explanation |
|-------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>inFile.seekp(10L, ios::beg);</code> | Sets the reading position of <code>inFile</code> to the 11 th byte (character), which is at position 10. That is, it sets the reading position just after the digit 9 or just before the letter A. |
| <code>inFile.seekp(5L, ios::cur);</code> | Moves the reading position of <code>inFile</code> five bytes to the right of its current position. |
| <code>inFile.seekp(-6L, ios::end);</code> | Sets the reading position of <code>inFile</code> to the sixth byte (character) from the end. That is, it sets the reading position just before the letter U. |

The program in the following example further explains how the functions `seekg` and `seekp` work.

EXAMPLE E-4

```
#include <iostream>
#include <fstream>

using namespace std;

int main()
{
    char ch;                                //Line 1
    ifstream inFile;                        //Line 2

    inFile.open("digitsAndAlphabet.txt");    //Line 3

    if (!inFile)                            //Line 4
    {
        cout << "The input file does not exist. "
              << "The program terminates!!!!" << endl; //Line 5
        return 1;                               //Line 6
    }
}
```

```

inFile.get(ch); //Line 7
cout << "Line 8: The first byte: " << ch << endl; //Line 8

    //position the reading marker six bytes to the
    //right of its current position
inFile.seekg(6L, ios::cur); //Line 9
inFile.get(ch); //read the character //Line 10
cout << "Line 11: Current byte read: " << ch
    << endl; //Line 11

    //position the reading marker seven bytes
    //from the beginning
inFile.seekg(7L, ios::beg); //Line 12
inFile.get(ch); //read the character //Line 13
cout << "Line 14: Seventh byte from the beginning: "
    << ch << endl; //Line 14

    //position the reading marker 26 bytes
    //from the end
inFile.seekg(-26L, ios::end); //Line 15
inFile.get(ch); //read the character //Line 16
cout << "Line 17: Byte 26 from the end: " << ch
    << endl; //Line 17

return 0; //Line 18
}

```

Sample Run:

```

Line 8: The first byte: 0
Line 11: Current byte read: 7
Line 14: Seventh byte from the beginning: 7
Line 17: Byte 26 from the end: A

```

The input file contains the following line of text:

```
0123456789ABCDEFGHIJKLMNOPQRSTUVWXYZ
```

The following program illustrates how the function `seekg` works with `structs`.

EXAMPLE E-5

Suppose `customerType` is a `struct` defined as follows:

```

struct customerType
{
    char firstName[15];
    char lastName[15];
    int ID;
    double balance;
};

```

The program in Example E-2 created the binary file `customer.dat` consisting of certain customers' data. You can use the function `seekg` to move the reading position of this file to any record. Suppose `inFile` is an `ifstream` object used to open the binary file `customer.dat`.

The following statement calculates the size of a `customerType` `struct` and stores it in the variable `custSize`:

```
long custSize = sizeof(cust);
```

We can use the value of the variable `custSize` to move the reading position to a specific record in the file. For example, consider the following statement:

```
inFile.seekg(6 * custSize, ios::beg);
```

This statement moves the reading position just after the sixth customer's record, that is, just before the seventh customer's record.

The following program further illustrates how the function `seekg` works with `structs`.

EXAMPLE E-6

//Reading a file randomly

```
#include <iostream>
#include <fstream>
#include <iomanip>

using namespace std;

struct customerType
{
    char firstName[15];
    char lastName[15];
    int ID;
    double balance;
};

void printCustData(const customerType& customer);

int main()
{
    customerType cust;                                     //Line 1
    ifstream inFile;                                       //Line 2

    long custSize = sizeof(cust);                           //Line 3

    inFile.open("customer.dat", ios::binary);               //Line 4
    if (!inFile)                                           //Line 5
```

```

{
    cout << "The input file does not exist. "
          << "The program terminates!!!!" << endl; //Line 6
    return 1; //Line 7
}

cout << fixed << showpoint << setprecision(2); //Line 8

    //randomly read the records and output them
inFile.seekg(6 * custSize, ios::beg); //Line 9
inFile.read(reinterpret_cast<char*> (&cust),
            sizeof(cust)); //Line 10
cout << "Seventh customer's data: " << endl; //Line 11
printCustData(cust); //Line 12

inFile.seekg(8 * custSize, ios::beg); //Line 13
inFile.read(reinterpret_cast<char*> (&cust),
            sizeof(cust)); //Line 14
cout << "Ninth customer's data: " << endl; //Line 15
printCustData(cust);

inFile.seekg(-8 * custSize, ios::end); //Line 16
inFile.read(reinterpret_cast<char*> (&cust),
            sizeof(cust)); //Line 17
cout << "Eighth (from the end) customer's data: "
      << endl; //Line 18
printCustData(cust); //Line 19

inFile.close(); //close the file //Line 20

return 0; //Line 21
}

void printCustData(const customerType& customer)
{
    cout << " ID: " << customer.ID << endl
          << " First Name: " << customer.firstName << endl
          << " Last Name: " << customer.lastName << endl
          << " Account Balance: $" << customer.balance
          << endl;
}

```

Sample Run:

```

Seventh customer's data:
ID: 22222
First Name: Jose
Last Name: Ramey
Account Balance: $25345.35
Ninth customer's data:
ID: 55555
First Name: Tommy
Last Name: Pitts

```

```

Account Balance: $892.85
Eighth (from the end) customer's data:
ID: 11111
First Name: Rita
Last Name: Gupta
Account Balance: $14863.50

```

The program in Example E-6 illustrates how the function `seekg` works. Using the function `seekg`, the reading position in a file can be moved to any location in the file. Similarly, the function `seekp` can be used to move the write position in a file to any location. Furthermore, these functions can be used to create a binary file in which the data is organized according to the values of either a variable or a particular component of a `struct`. For example, suppose there are at most, say, 100 students in a class. Each student has a unique ID in the range 1 to 100. Using the students' IDs, we can create a random access binary file in such a way that in the file, a student's data is written at the location specified by its ID. This is like treating the file as an array. The advantage is that, once the file is created, a student's data from the file can be read, directly, using the student's ID. Another advantage is that in the file, the data is sorted according to the IDs.

Here, we are assuming that the student IDs are in the range 1 to 100. However, if you use, say, a three-, four-, or five-digit number as a student ID and there are only a few students in the class, the data in the file could be scattered. In other words, a lot of space could be used just to store only a few students' data. In such cases, more advanced techniques are used to organize the data so that it can be accessed efficiently.

The program in Example E-7 illustrates how to use the students' IDs to organize the data in a binary file. The program also shows how to output the file.

EXAMPLE E-7

//Creating and reading a random access file.

```

#include <iostream>
#include <fstream>
#include <iomanip>

using namespace std;

struct studentType
{
    char firstName[15];
    char lastName[15];
    int ID;
    double GPA;
};

void printStudentData(const studentType& student);

```

```

int main()
{
    studentType st;                                //Line 1
    ifstream inFile;                                //Line 2
    ofstream outFile;                                //Line 3

    long studentSize = sizeof(st);                  //Line 4

    //open the input file, which is a text file
    inFile.open("studentData.txt");                  //Line 5

    if (!inFile)                                    //Line 6
    {
        cout << "The input file does not exist. "
              << "The program terminates!!!!" << endl; //Line 7
        return 1;                                    //Line 8
    }

    //open a binary output file
    outFile.open("student.dat", ios::binary);         //Line 9

    inFile >> st.ID >> st.firstName
              >> st.lastName >> st.GPA;             //Line 10

    while (inFile)                                   //Line 11
    {
        outFile.seekp((st.ID - 1) * studentSize,
                      ios::beg);                     //Line 12
        outFile.write(reinterpret_cast<const char *> (&st),
                      sizeof(st));                   //Line 13
        inFile >> st.ID >> st.firstName
              >> st.lastName >> st.GPA;             //Line 14
    };

    inFile.close();                                  //Line 15
    inFile.clear();                                  //Line 16
    outFile.close();                                  //Line 17

    cout << left << setw(3) << "ID"
          << setw(16) << "First Name"
          << setw(16) << "Last Name"
          << setw(12) << "Current GPA" << endl;      //Line 18
    cout << fixed << showpoint << setprecision(2);  //Line 19

    //open the input file, which is a binary file
    inFile.open("student.dat", ios::binary);         //Line 20

    if (!inFile)                                    //Line 21
    {
        cout << "The input file does not exist. "
              << "The program terminates!!!!" << endl; //Line 22
        return 1;                                    //Line 23
    }
}

```

```

        //read the data at location 0 in the file
inFile.read(reinterpret_cast<char*>(&st),
            sizeof(st)); //Line 24
while (inFile) //Line 25
{
    if (st.ID != 0) //Line 26
        printStudentData(st); //Line 27

    //read the data at the current reading position
    inFile.read(reinterpret_cast<char*>(&st),
        sizeof(st)); //Line 28
};

return 0; //Line 29
}

void printStudentData(const studentType& student)
{
    cout << left << setw(3) << student.ID
        << setw(16) << student.firstName
        << setw(16) << student.lastName
        << right << setw(10) << student.GPA
        << endl;
}

```

Sample Run:

| ID | First Name | Last Name | Current GPA |
|----|------------|-----------|-------------|
| 2 | Sheila | Duffy | 4.00 |
| 10 | Ajay | Kumar | 3.60 |
| 12 | Ashley | White | 3.90 |
| 16 | Tommy | Pitts | 2.40 |
| 23 | Rita | Gupta | 3.40 |
| 34 | Brad | Smith | 3.50 |
| 36 | Salma | Quade | 3.90 |
| 41 | Steve | Sharma | 3.50 |
| 45 | Sheila | Robinson | 2.50 |
| 56 | Lisa | Johnson | 2.90 |
| 67 | Jose | Ramey | 3.80 |
| 75 | Jennifer | Ackerman | 4.00 |

The data in the file studentData.txt is as follows:

```

12 Ashley White 3.9
34 Brad Smith 3.5
56 Lisa Johnson 2.9
45 Sheila Robinson 2.5
23 Rita Gupta 3.4
10 Ajay Kumar 3.6
67 Jose Ramey 3.8
2 Sheila Duffy 4.0
16 Tommy Pitts 2.4

```

36 Salma Quade 3.9
75 Jennifer Ackerman 4.0
41 Steve Sharma 3.5

Naming Conventions of Header Files in ANSI/ISO Standard C++ and Standard C++

The programs in this book are written using ANSI/ISO Standard C++. As indicated in Chapter 1, there are two versions of C++—ANSI/ISO Standard C++ and Standard C++. For the most part, these two standards are the same. The header files in Standard C++ have the extension `.h`, while the header files in ANSI/ISO Standard C++ have no extension. Moreover, the names of certain header files, such as `math.h`, in ANSI/ISO Standard C++ start with the letter `c`. The language C++ evolved from C. Therefore, certain header files—such as `math.h`, `stdlib.h`, and `string.h`—were brought from C into C++. The header files—such as `iostream.h`, `iomanip.h`, and `fstream.h`—were specially designed for C++. Recall that when a header file is included in a program, the global identifiers of the header file also become the global identifiers of the program. In ANSI/ISO Standard C++, to take advantage of the `namespace` mechanism, all of the header files were modified so that the identifiers are declared within a `namespace`. Recall that the name of this `namespace` is `std`.

In ANSI/ISO Standard C++, the extension `.h` of the header files that were specially designed for C++ was dropped. For the header files that were brought from C into C++, the extension `.h` was dropped and the names of these header files start with the letter `c`. Following are the names of the most commonly used header files in Standard C++ and ANSI/ISO Standard C++:

| Standard C++ Header File Name | ANSI/ISO Standard C++ Header File Name |
|-------------------------------|----------------------------------------|
| <code>assert.h</code> | <code>cassert</code> |
| <code>cctype</code> | <code>cctype</code> |
| <code>float.h</code> | <code>cfloat</code> |
| <code>fstream.h</code> | <code>fstream</code> |
| <code>iomanip.h</code> | <code>iomanip</code> |
| <code>iostream.h</code> | <code>iostream</code> |
| <code>limits.h</code> | <code>climits</code> |
| <code>math.h</code> | <code>cmath</code> |
| <code>stdlib.h</code> | <code>cstdlib</code> |
| <code>string.h</code> | <code>cstring</code> |

To include a header file, say, `iostream`, the following statement is required:

```
#include <iostream>
```

Furthermore, to use identifiers, such as `cin`, `cout`, `endl`, and so on, the program should use either the statement:

```
using namespace std;
```

or the prefix `std::` before the identifier.

This page intentionally left blank



APPENDIX F HEADER FILES

The C++ standard library contains many predefined functions, named constants, and specialized data types. This appendix discusses some of the most widely used library routines (and several named constants). For additional explanation and information on functions, named constants, and so on, check your system documentation. The names of the Standard C++ header files are shown in parentheses.

Header File `cassert` (`cassert.h`)

The following table describes the function `assert`. Its specification is contained in the header file `cassert` (`cassert.h`).

| | | |
|---------------------------------|----------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>assert(expression)</code> | <code>expression</code> is any <code>int expression</code> ; <code>expression</code> is usually a logical expression | <ul style="list-style-type: none">• If the value of <code>expression</code> is nonzero (<code>true</code>), the program continues to execute.• If the value of <code>expression</code> is 0 (<code>false</code>), execution of the program terminates immediately. The expression, the name of the file containing the source code, and the line number in the source code are displayed. |
|---------------------------------|----------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

NOTE

To disable all of the `assert` statements, place the preprocessor directive `#define NDEBUG` before the directive `#include <cassert>`.

Header File `cctype` (`cctype.h`)

The following table shows various functions from the header file `cctype` (`cctype.h`).

| Function Name and Parameters | Parameter(s) Types | Function Return Value |
|------------------------------|----------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>isalnum(ch)</code> | <code>ch</code> is a <code>char</code> value | Function returns an <code>int</code> value as follows: <ul style="list-style-type: none">If <code>ch</code> is a letter or a digit character, that is ('A'-'Z', 'a'-'z', '0'-'9'), it returns a nonzero value (<code>true</code>)0 (<code>false</code>), otherwise |
| <code>iscntrl(ch)</code> | <code>ch</code> is a <code>char</code> value | Function returns an <code>int</code> value as follows: <ul style="list-style-type: none">If <code>ch</code> is a control character (in ASCII, a character value 0-31 or 127), it returns a nonzero value (<code>true</code>)0 (<code>false</code>), otherwise |
| <code>isdigit(ch)</code> | <code>ch</code> is a <code>char</code> value | Function returns an <code>int</code> value as follows: <ul style="list-style-type: none">If <code>ch</code> is a digit ('0'-'9'), it returns a nonzero value (<code>true</code>)0 (<code>false</code>), otherwise |
| <code>islower(ch)</code> | <code>ch</code> is a <code>char</code> value | Function returns an <code>int</code> value as follows: <ul style="list-style-type: none">If <code>ch</code> is lowercase ('a'-'z'), it returns a nonzero value (<code>true</code>)0 (<code>false</code>), otherwise |
| <code>isprint(ch)</code> | <code>ch</code> is a <code>char</code> value | Function returns an <code>int</code> value as follows: <ul style="list-style-type: none">If <code>ch</code> is a printable character, including blank (in ASCII, ' ' through '~'), it returns a nonzero value (<code>true</code>)0 (<code>false</code>), otherwise |
| <code>ispunct(ch)</code> | <code>ch</code> is a <code>char</code> value | Function returns an <code>int</code> value as follows: <ul style="list-style-type: none">If <code>ch</code> is a punctuation character, it returns a nonzero value (<code>true</code>)0 (<code>false</code>), otherwise |
| <code>isspace(ch)</code> | <code>ch</code> is a <code>char</code> value | Function returns an <code>int</code> value as follows: <ul style="list-style-type: none">If <code>ch</code> is a whitespace character (blank, newline, tab, carriage return, form feed), it returns a nonzero value (<code>true</code>)0 (<code>false</code>), otherwise |

| Function Name and Parameters | Parameter(s) Types | Function Return Value |
|------------------------------|----------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>isupper(ch)</code> | <code>ch</code> is a <code>char</code> value | Function returns an <code>int</code> value as follows: <ul style="list-style-type: none"> If <code>ch</code> is an uppercase letter (<code>'A'–'Z'</code>), it returns a nonzero value (<code>true</code>) 0 (<code>false</code>), otherwise |
| <code>tolower(ch)</code> | <code>ch</code> is a <code>char</code> value | Function returns an <code>int</code> value as follows: <ul style="list-style-type: none"> If <code>ch</code> is an uppercase letter, it returns the ASCII value of the lowercase equivalent of <code>ch</code> ASCII value of <code>ch</code>, otherwise |
| <code>toupper(ch)</code> | <code>ch</code> is a <code>char</code> value | Function returns an <code>int</code> value as follows: <ul style="list-style-type: none"> If <code>ch</code> is a lowercase letter, it returns the ASCII value of the uppercase equivalent of <code>ch</code> ASCII value of <code>ch</code>, otherwise |

Header File `cfloat (float.h)`

In Chapter 2, we listed the largest and smallest values belonging to the floating-point data types. We also remarked that these values are system dependent. These largest and smallest values are stored in named constants. The header file `cfloat` contains many such named constants. The following table lists some of these constants.

| Named Constant | Description |
|-----------------------|------------------------------------------------------------------------------|
| <code>FLT_DIG</code> | Approximate number of significant digits in a <code>float</code> value |
| <code>FLT_MAX</code> | Maximum positive <code>float</code> value |
| <code>FLT_MIN</code> | Minimum positive <code>float</code> value |
| <code>DBL_DIG</code> | Approximate number of significant digits in a <code>double</code> value |
| <code>DBL_MAX</code> | Maximum positive <code>double</code> value |
| <code>DBL_MIN</code> | Minimum positive <code>double</code> value |
| <code>LDBL_DIG</code> | Approximate number of significant digits in a <code>long double</code> value |
| <code>LDBL_MAX</code> | Maximum positive <code>long double</code> value |
| <code>LDBL_MIN</code> | Minimum positive <code>long double</code> value |

A program similar to the following can print the values of these named constants on your system.

```
#include <iostream>
#include <cfloat>

using namespace std;

int main()
{
    cout << "Approximate number of significant digits "
          << "in a float value " << FLT_DIG << endl;
    cout << "Maximum positive float value " << FLT_MAX
          << endl;
    cout << "Minimum positive float value " << FLT_MIN
          << endl;
    cout << "Approximate number of significant digits "
          << "in a double value " << DBL_DIG << endl;
    cout << "Maximum positive double value " << DBL_MAX
          << endl;
    cout << "Minimum positive double value " << DBL_MIN
          << endl;
    cout << "Approximate number of significant digits "
          << "in a long double value " << LDBL_DIG << endl;
    cout << "Maximum positive long double value " << LDBL_MAX
          << endl;
    cout << "Minimum positive long double value " << LDBL_MIN
          << endl;

    return 0;
}
```

Header File `climits` (`limits.h`)

In Chapter 2, we listed the largest and smallest values belonging to the integral data types. We also remarked that these values are system dependent. These largest and smallest values are stored in named constants. The header file `climits` contains many such named constants. The following table lists some of these constants.

| Named Constant | Description |
|-----------------------|----------------------------------|
| <code>CHAR_BIT</code> | Number of bits in a byte |
| <code>CHAR_MAX</code> | Maximum <code>char</code> value |
| <code>CHAR_MIN</code> | Minimum <code>char</code> value |
| <code>SHRT_MAX</code> | Maximum <code>short</code> value |
| <code>SHRT_MIN</code> | Minimum <code>short</code> value |

| Named Constant | Description |
|----------------|-------------------------------------|
| INT_MAX | Maximum int value |
| INT_MIN | Minimum int value |
| LONG_MAX | Maximum long value |
| LONG_MIN | Minimum long value |
| UCHAR_MAX | Maximum unsigned char value |
| USHRT_MAX | Maximum unsigned short value |
| UINT_MAX | Maximum unsigned int value |
| ULONG_MAX | Maximum unsigned long value |

A program similar to the following can print the values of these named constants on your system.

```
#include <iostream>
#include <climits>

using namespace std;

int main()
{
    cout << "Number of bits in a byte " << CHAR_BIT << endl;
    cout << "Maximum char value " << CHAR_MAX << endl;
    cout << "Minimum char value " << CHAR_MIN << endl;
    cout << "Maximum short value " << SHRT_MAX << endl;
    cout << "Minimum short value " << SHRT_MIN << endl;
    cout << "Maximum int value " << INT_MAX << endl;
    cout << "Minimum int value " << INT_MIN << endl;
    cout << "Maximum long value " << LONG_MAX << endl;
    cout << "Minimum long value " << LONG_MIN << endl;
    cout << "Maximum unsigned char value " << UCHAR_MAX
        << endl;
    cout << "Maximum unsigned short value " << USHRT_MAX
        << endl;
    cout << "Maximum unsigned int value " << UINT_MAX << endl;
    cout << "Maximum unsigned long value " << ULONG_MAX
        << endl;

    return 0;
}
```

Header File `cmath` (`math.h`)

The following table shows various math functions.

| Function Name and Parameters | Parameter(s) Type | Function Return Value |
|------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------|
| <code>acos(x)</code> | x is a floating-point expression, $-1.0 \leq x \leq 1.0$ | Arc cosine of x , a value between 0.0 and π |
| <code>asin(x)</code> | x is a floating-point expression, $-1.0 \leq x \leq 1.0$ | Arc sine of x , a value between $-\pi/2$ and $\pi/2$ |
| <code>atan(x)</code> | x is a floating-point expression | Arc tan of x , a value between $-\pi/2$ and $\pi/2$ |
| <code>ceil(x)</code> | x is a floating-point expression | The smallest whole number $\geq x$, (“ceiling” of x) |
| <code>cos(x)</code> | x is a floating-point expression, x is measured in radians | Trigonometric cosine of the angle |
| <code>cosh(x)</code> | x is a floating-point expression | Hyperbolic cosine of x |
| <code>exp(x)</code> | x is a floating-point expression | The value e raised to the power of x ; (e = 2.718...) |
| <code>fabs(x)</code> | x is a floating-point expression | Absolute value of x |
| <code>floor(x)</code> | x is a floating-point expression | The largest whole number $\leq x$; (“floor” of x) |
| <code>log(x)</code> | x is a floating-point expression, in which $x > 0.0$ | Natural logarithm (base e) of x |
| <code>log10(x)</code> | x is a floating-point expression, in which $x > 0.0$ | Common logarithm (base 10) of x |
| <code>pow(x,y)</code> | x and y are floating-point expressions. If $x = 0.0$, y must be positive; if $x \leq 0.0$, y must be a whole number. | x raised to the power of y |
| <code>sin(x)</code> | x is a floating-point expression; x is measured in radians | Trigonometric sine of the angle |
| <code>sinh(x)</code> | x is a floating-point expression | Hyperbolic sine of x |

| Function Name and Parameters | Parameter(s) Type | Function Return Value |
|------------------------------|--------------------------------------------------------------------------|------------------------------------|
| <code>sqrt(x)</code> | x is a floating-point expression, in which $x \geq 0.0$ | Square root of x |
| <code>tan(x)</code> | x is a floating-point expression; x is measured in radians | Trigonometric tangent of the angle |
| <code>tanh(x)</code> | x is a floating-point expression | Hyperbolic tangent of x |

Header File `cstddef` (`stddef.h`)

Among others, this header file contains the definition of the following symbolic constant:
NULL: The system-dependent null pointer (usually 0)

Header File `cstring` (`string.h`)

The following table shows various string functions.

| Function Name and Parameters | Parameter(s) Type | Function Return Value |
|--------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>strcat(destStr, srcStr)</code> | <code>destStr</code> and <code>srcStr</code> are null-terminated char arrays; <code>destStr</code> must be large enough to hold the result | The base address of <code>destStr</code> is returned; <code>srcStr</code> , including the null character, is concatenated to the end of <code>destStr</code> |
| <code>strcmp(str1, str2)</code> | <code>str1</code> and <code>str2</code> are null-terminated char arrays | The returned value is as follows: <ul style="list-style-type: none"> • An int value < 0 if <code>str1 < str2</code> • An int value 0 if <code>str1 = str2</code> • An int value > 0 if <code>str1 > str2</code> |

| Function Name and Parameters | Parameter(s) Type | Function Return Value |
|--------------------------------------|-------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------|
| <code>strcpy(destStr, srcStr)</code> | <code>destStr</code> and <code>srcStr</code> are null-terminated <code>char</code> arrays | The base address of <code>destStr</code> is returned; <code>srcStr</code> is copied into <code>destStr</code> |
| <code>strlen(str)</code> | <code>str</code> is a null-terminated <code>char</code> array | An integer value ≥ 0 specifying the length of the <code>str</code> (excluding the <code>'\0'</code>) is returned |

HEADER FILE `string`

This header file—not to be confused with the header file `cstring`—supplies a programmer-defined data type named `string`. Associated with the `string` type are a data type `string::size_type` and a named constant `string::npos`. These are defined as follows:

| | |
|--------------------------------|----------------------------------------------------------|
| <code>string::size_type</code> | An unsigned integer type |
| <code>string::npos</code> | The maximum value of type <code>string::size_type</code> |

The type `string` contains several functions for string manipulation. In addition to the string functions listed in Table 8-1, the following table describes additional string functions. In this table, we assume that `strVar` is a `string` variable and `str` is a string variable, a string constant, or a character array.

| Expression | Effect |
|-------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>getline(istreamVar, strVar);</code> | <code>istreamVar</code> is an input stream variable (of type <code>istream</code> or <code>ifstream</code>). Characters until the newline character are input from <code>istreamVar</code> and stored in <code>strVar</code> . (The newline character is read but not stored into <code>strVar</code> .) The value returned by this function is usually ignored. |
| <code>strVar.append(str, n)</code> | The first <code>n</code> characters of the character array <code>str</code> are appended to <code>strVar</code> . |
| <code>strVar.c_str()</code> | The base address of a null-terminated C-string corresponding to the characters in <code>strVar</code> . |

| Expression | Effect |
|------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>strVar.capacity()</code> | Returns the size of the storage allocated for <code>strVar</code> . |
| <code>strVar.erase(pos);</code> | <p><code>pos</code> is a parameter of type <code>string::size_type</code>.</p> <p>Removes all of the characters from <code>strVar</code> starting at index <code>pos</code>.</p> |
| <code>strVar.resize(n, ch);</code> | <p>Changes the size of storage allocation for <code>strVar</code> to <code>n</code>. If <code>n</code> is less than the current storage size of <code>strVar</code>, the storage size of the string is truncated to <code>n</code>. If <code>n</code> is greater than the current storage size, the string is expanded to size <code>n</code> and the additional space is filled with copies of the character specified by the <code>char</code> variable <code>ch</code>.</p> |

This page intentionally left blank



APPENDIX G

MEMORY SIZE ON A SYSTEM AND RANDOM NUMBER GENERATOR

A program similar to the following prints the memory size of the built-in data types on your system. (The output of the program shows the size of the built-in data type on which this program was run.)

```
#include <iostream>

using namespace std;

int main()
{
    cout << "Size of char = " << sizeof(char) << endl;
    cout << "Size of int = " << sizeof(int) << endl;
    cout << "Size of short = " << sizeof(short) << endl;
    cout << "Size of unsigned int = " << sizeof(unsigned int)
        << endl;
    cout << "Size of long = " << sizeof(long) << endl;
    cout << "Size of bool = " << sizeof(bool) << endl;
    cout << "Size of float = " << sizeof(float) << endl;
    cout << "Size of double = " << sizeof(double) << endl;
    cout << "Size of long double = " << sizeof(long double)
        << endl;
    cout << "Size of unsigned short = "
        << sizeof(unsigned short) << endl;
    cout << "Size of unsigned long = "
        << sizeof(unsigned long) << endl;

    return 0;
}
```

Sample Run:

```
Size of char = 1
Size of int = 4
Size of short = 2
Size of unsigned int = 4
Size of long = 4
Size of bool = 1
Size of float = 4
Size of double = 8
Size of long double = 8
Size of unsigned short = 2
Size of unsigned long = 4
```

Random Number Generator

To generate a random number, you can use the C++ function `rand`. To use the function `rand`, the program must include the header file `cstdlib`. The header file `cstdlib` also contains the constant `RAND_MAX`. Typically, the value of `RAND_MAX` is 32767. To find the exact value of `RAND_MAX`, check your system's documentation. The function `rand` generates an integer between 0 and `RAND_MAX`. The following program illustrates how to use the function `rand`. It also prints the value of `RAND_MAX`:

```
#include <iostream>
#include <cstdlib>
#include <iomanip>

using namespace std;

int main()
{
    cout << fixed << showpoint << setprecision(5);
    cout << "The value of RAND_MAX: " << RAND_MAX << endl;
    cout << "A random number: " << rand() << endl;
    cout << "A random number between 0 and 9: "
        << rand() % 10 << endl;
    cout << "A random number between 0 and 1: "
        << static_cast<double>(rand())
            / static_cast<double>(RAND_MAX)
        << endl;

    return 0;
}
```

Sample Run:

```
The value of RAND_MAX: 32767
A random number: 41
A random number between 0 and 9: 7
A random number between 0 and 1: 0.19330
```



APPENDIX H

STANDARD TEMPLATE LIBRARY (STL)

Chapter 15 introduced templates. With the help of class templates, we developed (and used) a generic code to process lists. For example, we used the `class listType` to process a list of integers and a list of strings. In Chapters 18 and 19, we studied the three most important data structures: linked lists, stacks, and queues. In these chapters, using class templates, we developed a generic code to process linked lists. In addition, using the second principle of object-oriented programming (OOP), we developed generic codes to process unordered and ordered lists. Thus, a template is a powerful tool that promotes code reuse. This appendix discusses many important features of the STL and shows how to use the tools provided by the STL in a program.

Components of the STL

The main objective of a program is to manipulate data and generate results. This requires the ability to store data in computer memory, access a particular piece of data, and write algorithms to manipulate the data. For example, if all the data items are of the same type and we have some idea of the number of data items, we could use an array to store this data. We can then use the index to access a particular component of the array. Using a loop and the array index, we can step through the elements of the array. Algorithms, such as initializing the array, sorting, and searching, are used to manipulate the data stored in an array. On the other hand, if we do not want to be concerned with the size of the data, we can use a linked list to process the data. The STL is equipped with these and other features to effectively manipulate the data. More formally, the STL has the following three main components:

- Containers
- Iterators
- Algorithms

Containers and iterators are templated classes. Iterators are used to step through the elements of a container. Algorithms are used to manipulate data. The ensuing sections discuss each of these three components in detail.

Container Types

Containers are used to manage objects of a given type. The STL containers are divided into three categories:

- Sequence containers (also called sequential containers)
- Associative containers
- Container adapters

This appendix discusses sequence and container adapters.

Sequence Containers

Every object in a sequence container has a specific position. The three predefined sequence containers are:

- `vector`
- `deque`
- `list`

Before discussing container types in general, let us first briefly describe the sequence container `vector`. We do so because vector containers are similar to arrays and thus can be processed like arrays. Also, with the help of vector containers, we can describe several properties that are common to all containers. In fact, all containers use the same names for the common operations. Of course, there are operations that are specific to a container, which will be discussed when describing a specific container.

Sequence Container: Vectors

A vector container stores and manages its objects in a dynamic array. Because an array is a random access data structure, the elements of a vector can be accessed randomly. Item insertion at the beginning or middle of an array is time consuming, especially if the array is large. However, inserting an item at the end is quite fast.

**NOTE**

Chapter 10 briefly introduced the `class vector` and explained how to declare a vector object and manipulate the data in that object. However, to make this appendix a stand-alone section, we repeat some of the material in Chapter 10. We also provide a detailed discussion of the `class vector`.

The name of the class that implements the vector container is `vector`. (Recall that containers are class templates.) The name of the header file containing the `class vector` is `vector`. Thus, to use a vector container in a program, the program must include the following statement:

```
#include <vector>
```

Furthermore, to define an object of type `vector`, we must specify the type of the object because the `class vector` is a class template. For example, the statement:

```
vector<int> intList;
```

declares `intList` to be a vector and the component type is `int`. Similarly, the statement:

```
vector<string> stringList;
```

declares `stringList` to be a vector container and the component type is `string`.

DECLARING VECTOR OBJECTS

The `class` `vector` contains several constructors, including the default constructor. Therefore, a vector container can be declared and initialized several ways. Table H-1 describes how a vector container of a specific type can be declared and initialized.

TABLE H-1 Various Ways to Declare and Initialize a Vector Container

| Statement | Effect |
|-------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>vector<elemType> vecList;</code> | Creates the empty vector container <code>vecList</code> . (The default constructor is invoked.) |
| <code>vector<elemType> vecList (otherVecList);</code> | Creates the vector container <code>vecList</code> , and initializes <code>vecList</code> to the elements of the vector <code>otherVecList</code> . <code>vecList</code> and <code>otherVecList</code> are of the same type. |
| <code>vector<elemType> vecList (size);</code> | Creates the vector container <code>vecList</code> of size <code>size</code> . <code>vecList</code> is initialized using the default constructor. |
| <code>vector<elemType> vecList (n, elm);</code> | Creates the vector container <code>vecList</code> of size <code>n</code> . <code>vecList</code> is initialized using <code>n</code> copies of the element <code>elm</code> . |
| <code>vector<elemType> vecList (beg, end);</code> | Creates the vector container <code>vecList</code> . <code>vecList</code> is initialized to the elements in the range <code>[beg, end)</code> , that is, all the elements in the range <code>beg...end-1</code> . Both <code>beg</code> and <code>end</code> are pointers, called iterators in STL terminology. (Later in this appendix, we explain how iterators are used.) |

Now that we know how to declare a vector sequence container, let us now discuss how to manipulate the data stored in a vector container. In order to manipulate the data in a vector container, we must know the following basic operations:

- Item insertion
- Item deletion
- Stepping through the elements of a vector container

The elements in a vector container can be accessed directly by using the operations given in Table H-2. The name of the function is shown in bold.

TABLE H-2 Operations to Access the Elements of a Vector Container

| Expression | Description |
|--------------------------------|-----------------------------------------------------------------------------|
| <code>vecList.at(index)</code> | Returns the element at the position specified by index . |
| <code>vecList[index]</code> | Returns the element at the position specified by index . |
| <code>vecList.front()</code> | Returns the first element. (Does not check whether the container is empty.) |
| <code>vecList.back()</code> | Returns the last element. (Does not check whether the container is empty.) |

From Table H-2, it follows that the elements in a vector can be processed just as they can in an array; see Example H-1. (Recall that in C++, arrays start at location 0. Similarly, the first element in a vector container is at location 0.)

EXAMPLE H-1

Consider the following statement, which declares `intList` to be a vector container of size 5 and the element type is `int`.

```
vector<int> intList(5);
```

You can use a loop, such as the following, to store elements into `intList`:

```
for (int j = 0; j < 5; j++)
    intList[j] = j;
```

Similarly, you can use a `for` loop to output the elements of `intList`.

The `class` `vector` also contains member functions that can be used to find the number of elements currently in the container, the maximum number of elements that can be inserted into a container, and so on. Table H-3 describes some of these operations. The name of the function is shown in bold. (Suppose that `vecCont` is a vector container.)

TABLE H-3 Operations to Determine the Size of a Vector Container

| Expression | Description |
|----------------------------------------|---------------------------------------------------------------------------------------------------------------------------|
| <code>vecCont.capacity()</code> | Returns the maximum number of elements that can be inserted into the container <code>vecCont</code> without reallocation. |
| <code>vecCont.empty()</code> | Returns <code>true</code> if the container <code>vecCont</code> is empty, <code>false</code> otherwise. |
| <code>vecCont.size()</code> | Returns the number of elements currently in the container <code>vecCont</code> . |
| <code>vecCont.max_size()</code> | Returns the maximum number of elements that can be inserted into the container <code>vecCont</code> . |

The `class` `vector` also contains member functions that can be used to manipulate the data, as well as insert and delete items, in a vector container. Suppose that `vecList` is a container of type `vector`. Item insertion and deletion in `vecList` are accomplished using the operations given in Table H-4. These operations are implemented as member functions of the `class` `vector`, and are shown in bold. Table H-4 also shows how these operations are used.

TABLE H-4 Various Operations on a Vector Container

| Statement | Effect |
|---------------------------------------------|----------------------------------------------------------------------------------|
| <code>vecList.clear()</code> | Deletes all the elements from the container. |
| <code>vecList.erase(position)</code> | Deletes the element at the position specified by <code>position</code> . |
| <code>vecList.erase(beg, end)</code> | Deletes all the elements starting at <code>beg</code> until <code>end-1</code> . |

TABLE H-4 Various Operations on a Vector Container (continued)

| Statement | Effect |
|-------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>vecList.insert(position, elem)</code> | A copy of <code>elem</code> is inserted at the position specified by <code>position</code> . The position of the new element is returned. |
| <code>vecList.insert(position, n, elem)</code> | <code>n</code> copies of <code>elem</code> are inserted at the position specified by <code>position</code> . |
| <code>vecList.insert(position, beg, end)</code> | A copy of the elements, starting at <code>beg</code> until <code>end-1</code> , is inserted into <code>vecList</code> at the position specified by <code>position</code> . |
| <code>vecList.push_back(elem)</code> | A copy of <code>elem</code> is inserted into <code>vecList</code> at the end. |
| <code>vecList.pop_back()</code> | Deletes the last element. |
| <code>vecList.resize(num)</code> | Changes the number of elements to <code>num</code> . If <code>size()</code> increases, the default constructor creates the new elements. |
| <code>vecList.resize(num, elem)</code> | Changes the number of elements to <code>num</code> . If <code>size()</code> increases, the default constructor creates the new elements. |

NOTE

In Table H-4, the identifiers `position`, `beg`, and `end` in STL terminology are called iterators. An iterator is just like a pointer. In general, iterators are used to step through the elements of a container. In other words, with the help of an iterator, we can walk through the elements of a container and process them one at a time. Because iterators are an integral part of the STL, they are discussed in the section, “Iterators”, located later in this appendix.

Example H-1 used a `for` loop and the array subscripting operator, `[]`, to access the elements of `intList`. We declare `intList` to be a `vector` object of size 5. Does this mean that we can store only five elements in `intList`? The answer is no. You can, in fact, add more elements to `intList`. However, because when we declare `intList` we specify the size to be 5, in order to add any elements past position 4, we use the function

`push_back`. Furthermore, if you initially declare a `vector` object and do not specify its size, then to add elements to the `vector` object we use the function `push_back`. Example H-2 explains how to use the function `push_back`.

EXAMPLE H-2

The following statement declares `intList` to be a `vector` object of size 0:

```
vector<int> intList;
```

To add elements to `intList`, we can use the function `push_back` as follows:

```
intList.push_back(34);
intList.push_back(55);
```

After these statements execute, the size of `intList` is 2 and:

```
intList = {34, 55}.
```

In Example H-2, because `intList` is declared to be of size 0, we use the function `push_back` to add elements to `intList`. However, we can also use the `resize` function to increase the size of `intList` and then use the array subscripting operator. For example, suppose that `intList` is declared as in Example H-2. Then, the following statement sets the size of `intList` to 10:

```
intList.resize(10);
```

Similarly, the following statement increases the size of `intList` by 10:

```
intList.resize(intList.size() + 10);
```

However, at times, the `push_back` function is more convenient because it does not need to know the size of the vector; it simply adds the elements at the end.

Next, we describe how to declare an iterator to a vector container.

DECLARING AN ITERATOR TO A VECTOR CONTAINER

The `class` `vector` contains a `typedef` iterator, which is declared as a `public` member. An iterator to a vector container is declared using the `typedef` iterator. For example, the statement:

```
vector<int>::iterator intVecIter;
```

declares `intVecIter` to be an iterator to a vector container of type `int`.

Because `iterator` is a `typedef` defined inside the `class` `vector`, we must use the container name (which is `vector`), the container element type, and the scope resolution operator to use the `typedef` `iterator`.

The expression:

```
++intVecIter
```

advances the iterator `intVecIter` to the next element in the container, and the expression:

```
*intVecIter
```

returns the element at the current iterator position.

Note that these operations are the same as the operations on pointers, discussed in Chapter 14. Recall that when used as a unary operator, `*` is called the dereferencing operator.

We now discuss how to use an iterator to a vector container to manipulate the data stored in the vector container.

Suppose that we have the following statements:

```
vector<int>  intList;           //Line 1
vector<int>::iterator intVecIter; //Line 2
```

The statement in Line 1 declares `intList` to be a vector container, and the element type is `int`.

The statement in Line 2 declares `intVecIter` to be an iterator to a vector container whose element type is `int`.

CONTAINERS AND THE FUNCTIONS `begin` AND `end`

Every container has the member functions `begin` and `end`. The function `begin` returns the position of the first element in the container; the function `end` returns a pointer to the position after the last element in the container. Also, these functions have no parameters.

After the following statement executes:

```
intVecIter = intList.begin();
```

the iterator `intVecIter` points to the first element in the container `intList`.

The following `for` loop outputs the elements of `intList` to the standard output device:

```
for (intVecIter = intList.begin(); intVecIter != intList.end();
     ++intVecIter)
    cout << *intVecIter << " ";
```

Example H-3 shows how the function `insert` works with vector objects.

EXAMPLE H-3

Consider the following statements:

```
int intArray[7] = {1, 3, 5, 7, 9, 11, 13};    //Line 1
vector<int> vecList(intArray, intArray + 7); //Line 2
vector<int>::iterator intVecIter;           //Line 3
```

The statement in Line 2 declares and initializes the vector container `vecList`. Now consider the following statements:

```
intVecIter = vecList.begin();                //Line 4
++intVecIter;                               //Line 5
vecList.insert(intVecIter, 22);              //Line 6
```

The statement in Line 4 initializes the iterator `intVecIter` to the first element of `vecList`; the statement in Line 5 advances `intVecIter` to the second element of `vecList`. The statement in Line 6 inserts 22 at the position specified by `intVecIter`. After the statement in Line 6 executes, `vecList = {1, 22, 3, 5, 7, 9, 11, 13}`. Notice that the size of the container also increases.

The following example illustrates how to use a vector container in a program and how to process the elements in a vector container.

EXAMPLE H-4

```
#include <iostream>
#include <vector>

using namespace std;

int main()
{
    vector<int> intList;                //Line 1
    int i;                             //Line 2

    intList.push_back(13);              //Line 3
    intList.push_back(75);              //Line 4
    intList.push_back(28);              //Line 5
    intList.push_back(35);              //Line 6

    cout << "Line 7: List elements: ";  //Line 7
    for(i = 0; i < 4; i++)              //Line 8
        cout << intList[i] << " ";    //Line 9
    cout << endl;                      //Line 10
```

```

    for(i = 0; i < 4; i++)                //Line 11
        intList[i] *= 2;                  //Line 12

    cout << "Line 13: List elements: ";    //Line 13
    for(i = 0; i < 4; i++)                //Line 14
        cout << intList[i] << " ";        //Line 15
    cout << endl;                          //Line 16

    vector<int>::iterator listIt;          //Line 17

    cout << "Line 18: List elements: ";    //Line 18
    for (listIt = intList.begin();        //Line 19
        listIt != intList.end(); ++listIt)
        cout << *listIt << " ";          //Line 20
    cout << endl;                          //Line 21

    listIt = intList.begin();              //Line 22
    ++listIt;                             //Line 23
    ++listIt;                             //Line 24

    //Insert 88 at the position specified
    //by listIt
    intList.insert(listIt, 88);            //Line 25

    cout << "Line 25: List elements: ";    //Line 26
    for (listIt = intList.begin();        //Line 27
        listIt != intList.end(); ++listIt)
        cout << *listIt << " ";          //Line 28
    cout << endl;                          //Line 29

    return 0;
}

```

Sample Run:

```

Line 7: List elements: 13 75 28 35
Line 13: List elements: 26 150 56 70
Line 18: List elements: 26 150 56 70
Line 25: List elements: 26 150 88 56 70

```

The statement in Line 1 declares a vector container (or vector for short), `intList`, of type `int`. The statement in Line 2 declares `i` to be an `int` variable. The statements in Lines 3 through 6 use the operation `push_back` to insert four numbers—13, 75, 28, and 35—into `intList`. The statements in Lines 8 and 9 use the `for` loop and the array subscripting operator, `[]`, to output the elements of `intList`. In the output, see the line marked Line 7, which contains the output of Lines 7 through 10. The statements in Lines 11 and 12 use a `for` loop to double the value of each element of `intList`; the statements in Lines 14 and 15 output the elements of `intList`. In the output, see the line marked Line 13, which contains the output of Lines 13 through 16.

The statement in Line 17 declares `listIt` to be a vector iterator that processes any vector container whose elements are of type `int`. Using the iterator `listIt`, the statements in

Lines 19 and 20 output the elements of `intList`. After the statement in Line 22 executes, `listIt` points to the first element of `intList`. The statements in Lines 23 and 24 advance `listIt` twice; after these statements execute, `listIt` points to the third element of `intList`. The statement in Line 25 inserts `88` into `intList` at the position specified by the iterator `listIt`. Because `listIt` points to the component at position 2 (the third element of `intList`), `88` is inserted at position 2 in `intList`; that is, `88` becomes the third element of `intList`. The statements in Lines 27 and 28 output the modified `intList`.

Member Functions Common to All Containers

The previous section discussed vector containers. This section discusses operations that are common to all containers. For example, every container class has the default constructor, several constructors with parameters, the destructor, a function to insert an element into a container, and so on.

Recall that a class encapsulates data, and operations on that data, into a single unit. Because every container is a class, several operations are directly defined for a container, and are provided as part of the definition of the class. Also, recall that the operations to manipulate the data are implemented with the help of functions and are called member functions of the class. Table H-5 describes the member functions that are common to all containers; that is, these functions are included as members of the class template implementing the container.

Suppose `ct`, `ct1`, and `ct2` are containers of the same type. In Table H-5, the name of the function is shown in bold. This table also shows how a function is called.

TABLE H-5 Operations Common to All Containers

| Member Function | Description |
|--------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Default constructor | Initializes the object to an empty state. |
| Constructor with parameters | In addition to the default constructor, every container has constructors with parameters. We will describe these constructors when we discuss a specific container. |
| Copy constructor | Executes when an object is passed as a parameter by value, and when an object is declared and initialized using another object of the same type. |
| Destructor | Executes when the object goes out of scope. |
| <code>ct.empty()</code> | Returns <code>true</code> if container <code>ct</code> is empty, <code>false</code> otherwise. |

TABLE H-5 Operations Common to All Containers (continued)

| Member Function | Description |
|----------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>ct.size()</code> | Returns the number of elements currently in container <code>ct</code> . |
| <code>ct.max_size()</code> | Returns the maximum number of elements that can be inserted in container <code>ct</code> . |
| <code>ct1.swap(ct2)</code> | Swaps the elements of containers <code>ct1</code> and <code>ct2</code> . |
| <code>ct.begin()</code> | Returns an iterator to the first element into container <code>ct</code> . |
| <code>ct.end()</code> | Returns an iterator to the position after the last element into container <code>ct</code> . |
| <code>ct.rbegin()</code> | Reverse begin. Returns a pointer to the last element into container <code>ct</code> . This function is used to process the elements of <code>ct</code> in reverse. |
| <code>ct.rend()</code> | Reverse end. Returns a pointer to the position before the first element into container <code>ct</code> . |
| <code>ct.insert(position, elem)</code> | Inserts <code>elem</code> into container <code>ct</code> at the position specified by <code>position</code> . Note that here <code>position</code> is an iterator. |
| <code>ct.erase(beg, end)</code> | Deletes all the elements between <code>beg...end-1</code> from container <code>ct</code> . Both <code>beg</code> and <code>end</code> are iterators. |
| <code>ct.clear()</code> | Deletes all the elements from the container. After a call to this function, container <code>ct</code> is empty. |
| Operator Functions | |
| <code>ct1 = ct2;</code> | Copies the elements of <code>ct2</code> into <code>ct1</code> . After this operation, the elements in both containers are the same. |
| <code>ct1 == ct2</code> | Returns <code>true</code> if containers <code>ct1</code> and <code>ct2</code> are equal, <code>false</code> otherwise. |
| <code>ct1 != ct2</code> | Returns <code>true</code> if containers <code>ct1</code> and <code>ct2</code> are not equal, <code>false</code> otherwise. |

NOTE

Because these operations are common to all containers, when discussing a specific container, to save space, these operations will not be listed again.

Member Functions Common to Sequence Containers

The previous section described the member functions that are common to all containers. In addition to these member functions, Table H-6 describes the member functions that are common to all sequence containers, that is, containers of type **vector**, **deque**, and **list**. The name of the function is shown in bold. (Suppose that **seqCont** is a sequence container.)

TABLE H-6 Member Functions Common to All Sequence Containers

| Expression | Description |
|-------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>seqCont.insert(position, elem)</code> | A copy of elem is inserted at the position specified by the iterator position . The position of the new element is returned. |
| <code>seqCont.insert(position, n, elem)</code> | n copies of elem are inserted at the position specified by the iterator position . |
| <code>seqCont.insert(position, beg, end)</code> | A copy of the elements, starting at beg until end-1 , are inserted into seqCont at the position specified by the iterator position . Also, beg and end are iterators. |
| <code>seqCont.push_back(elem)</code> | A copy of elem is inserted into seqCont at the end. |
| <code>seqCont.pop_back()</code> | Deletes the last element. |
| <code>seqCont.erase(position)</code> | Deletes the element at the position specified by the iterator position . |
| <code>seqCont.erase(beg, end)</code> | Deletes all the elements starting at beg until end-1 . Both beg and end are iterators. |
| <code>seqCont.clear()</code> | Deletes all the elements from the container. |

TABLE H-6 Member Functions Common to All Sequence Containers (continued)

| Expression | Description |
|----------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------|
| <code>seqCont.resize(num)</code> | Changes the number of elements to <code>num</code> . If <code>size()</code> grows, the new elements are created by their default constructor. |
| <code>seqCont.resize(num, elem)</code> | Changes the number of elements to <code>num</code> . If <code>size()</code> grows, the new elements are copies of <code>elem</code> . |

copy Algorithm

Example H-4 used a `for` loop to output the elements of a vector container. The STL provides a convenient way to output the elements of a container with the help of the function `copy`. The function `copy` is provided as a part of the generic algorithm and can be used with any container type. Because we need to frequently output the elements of a container, before continuing with our discussion of containers, let us first describe this function.

The function `copy` does more than output the elements of a container. In general, the function `copy` allows us to copy the elements from one place to another. For example, to output the elements of a vector, or to copy the elements of a vector into another vector, we can use the function `copy`. The prototype of the function template `copy` is:

```
template <class inputIterator, class outputIterator>
outputItr copy(inputIterator first1, inputIterator last,
               outputIterator first2);
```

The parameter `first1` specifies the position from where to begin copying the elements, and the parameter `last` specifies the end position. The parameter `first2` specifies where to copy the elements. Therefore, the parameters `first1` and `last` specify the source, and the parameter `first2` specifies the destination.

Note that the elements of the range `first1...last-1` are copied.

The definition of the function template `copy` is contained in the header file `algorithm`. Thus, to use the function `copy`, the program must include the statement:

```
#include <algorithm>
```

The function `copy` works as follows.

Consider the following statement:

```
int intArray[] = {5, 6, 8, 3, 40, 36, 98, 29, 75};
```

This statement creates an array `intArray` of nine components. Here, `intArray[0] = 5`, `intArray[1] = 6`, and so on.

The statement:

```
vector<int> vecList(9);
```

creates an empty container of nine components of type `vector`, and the element type is `int`.

Recall that the array name, `intArray`, is, in fact, a pointer and contains the base address of the array. Therefore, `intArray` points to the first component of the array, `intArray + 1` points to the second component of the array, and so on.

Consider the statement:

```
copy(intArray, intArray + 9, vecList.begin());
```

This statement copies the elements starting at the location `intArray`—which is the first component of the array `intArray`, until `intArray + 9 - 1` (that is, `intArray + 8`), which is the last element of the array `intArray`—into the container `vecList`. (Note that here `first1` is `intArray`, `last` is `intArray + 9`, and `first2` is `vecList.begin()`.) After the previous statement executes:

```
vecList = {5, 6, 8, 3, 40, 36, 98, 29, 75}
```

Now consider the statement:

```
copy(intArray + 1, intArray + 9, intArray);
```

Here, `first1` is `intArray + 1`; that is, `first1` points to the location of the second element of the array `intArray`, and `last` is `intArray + 9`. Also, `first2` is `intArray`, that is, `first2` points to the location of the first element of the array `intArray`. Therefore, the second array element is copied into the first array component, the third array element into the second array component, and so on. After the preceding statement executes:

```
intArray[] = {6, 8, 3, 40, 36, 98, 29, 75, 75}
```

Clearly, the elements of the array `intArray` are shifted to the left by one position.

Now consider the statement:

```
copy(vecList.rbegin() + 2, vecList.rend(), vecList.rbegin());
```

Recall that the function `rbegin`, reverse begin, returns a pointer to the last element in a container, and this function is used to process the elements of a container in reverse. Therefore, `vecList.rbegin() + 2` returns a pointer to the third to the last element in the container `vecList`. The function `rend`, reverse end, returns a pointer to the position before the first element in a container. The previous statement shifts the elements of the container `vecList` to the right by two positions. After the previous statement executes, the container `vecList` is:

```
vecList = {5, 6, 5, 6, 8, 3, 40, 36, 98}
```

Example H-5 shows the effect of the preceding statements using a C++ program. Before showing Example H-5, let us next describe a special type of iterators, called **ostream iterators**, which work well with the function **copy** to copy the elements of a container to an output device.

ostream ITERATOR AND THE FUNCTION **copy**

One way to output the contents of a container is to use a **for** loop and the function **begin** to initialize the **for** loop control variable, and the function **end** to set the limit. However, the function **copy** can also be used to output the elements of a container. In this case, an iterator of type **ostream** specifies the destination. (**ostream** iterators are discussed later in this appendix.) When we create an iterator of type **ostream**, we also specify the type of element the iterator will output.

The following statement illustrates how to create an **ostream** iterator of type **int**:

```
ostream_iterator<int> screen(cout, " "); //Line A
```

This statement creates **screen** to be an **ostream** iterator, and the element type is **int**. The iterator **screen** has two arguments: the object **cout** and a space. This means that the iterator **screen** is initialized using the object **cout**, and when this iterator outputs the elements, they are separated by a space.

The statement:

```
copy(intArray, intArray + 9, screen);
```

outputs the elements of **intArray** on the screen.

Similarly, the statement:

```
copy(vecList.begin(), vecList.end(), screen);
```

outputs the elements of the container **vecList** on the screen.

We will frequently use the function **copy** to output the elements of a container by using an **ostream** iterator. Also, until we discuss **ostream** iterators in detail, we will use statements similar to the statement in Line A to create an **ostream** iterator.

Of course, we can directly specify an **ostream** iterator in the function **copy**. For example, the statement (shown previously):

```
copy(vecList.begin(), vecList.end(), screen);
```

is equivalent to the statement:

```
copy(vecList.begin(), vecList.end(),
      ostream_iterator<int>(cout, " "));
```

Finally, the statement:

```
copy(vecList.begin(), vecList.end(),
      ostream_iterator<int>(cout, ", "));
```

outputs the elements of `vecList` with a comma and space between them.

Example H-5 illustrates how to use the function `copy` and an `ostream` iterator in a program.

EXAMPLE H-5

```
#include <algorithm>
#include <vector>
#include <iterator>
#include <iostream>

using namespace std;

int main()
{
    int intArray[] = {5, 6, 8, 3, 40,
                      36, 98, 29, 75};           //Line 1

    vector<int> vecList(9);                       //Line 2

    ostream_iterator<int> screen(cout, " ");       //Line 3

    cout << "Line 4: intArray: ";                 //Line 4
    copy(intArray, intArray + 9, screen);          //Line 5
    cout << endl;                                 //Line 6

    copy(intArray, intArray + 9, vecList.begin()); //Line 7

    cout << "Line 8: vecList: ";                   //Line 8
    copy(vecList.begin(), vecList.end(), screen);  //Line 9
    cout << endl;                                 //Line 10

    copy(intArray+1, intArray + 9, intArray);      //Line 11
    cout << "Line 12: After shifting the elements "
          << "one position to the left, " << endl
          << "           intArray: ";              //Line 12
    copy(intArray, intArray + 9, screen);          //Line 13
    cout << endl;                                 //Line 14

    copy(vecList.rbegin() + 2, vecList.rend(),
          vecList.rbegin());                       //Line 15
    cout << "Line 16: After shifting the elements "
          << "down by two positions, " << endl
          << "           vecList: ";               //Line 16
```

```
        copy(vecList.begin(), vecList.end(), screen);    //Line 17
        cout << endl;                                   //Line 18

    return 0;
}
```

Sample Run:

```
Line 4: intArray: 5 6 8 3 40 36 98 29 75
Line 8: vecList: 5 6 8 3 40 36 98 29 75
Line 12: After shifting the elements one position to the left,
         intArray: 6 8 3 40 36 98 29 75 75
Line 16: After shifting the elements down by two positions,
         vecList: 5 6 5 6 8 3 40 36 98
```

Sequence Container: `deque`

This section describes the sequence container `deque`. The term **deque** stands for double-ended queue. Deque containers are implemented as dynamic arrays in such a way that the elements can be inserted at both ends. Thus, a `deque` can expand in either direction. Elements can also be inserted in the middle. Inserting elements at the beginning or the end is fast; inserting elements in the middle, however, is time consuming because the elements in the queue need to be shifted.

The name of the class defining the deque containers is `deque`. Also, the definition of the `class deque`, and the functions to implement the various operations on a `deque` object, are contained in the header file `deque`. Therefore, to use a deque container in a program, the program must include the following statement:

```
#include <deque>
```

The `class deque` contains several constructors. Thus, a `deque` object can be initialized in various ways when it is declared. Table H-7 describes various ways a `deque` object can be declared.

TABLE H-7 Various Ways to Declare a `deque` Object

| Statement | Description |
|------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>deque<elementType> deq;</code> | Creates an empty <code>deque</code> container <code>deq</code> . (The default constructor is invoked.) |
| <code>deque<elementType> deq(otherDeq);</code> | Creates the <code>deque</code> container <code>deq</code> and initializes it to the elements of <code>otherDeq</code> ; <code>deq</code> and <code>otherDeq</code> are of the same type. |

TABLE H-7 Various Ways to Declare a `deque` Object (continued)

| Statement | Description |
|------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>deque<elementType> deq(size);</code> | Creates the <code>deque</code> container <code>deq</code> of size <code>size</code> . <code>deq</code> is initialized using the default constructor. |
| <code>deque<elementType> deq(n, elm);</code> | Creates the <code>deque</code> container <code>deq</code> of size <code>n</code> . <code>deq</code> is initialized using <code>n</code> copies of the element <code>elm</code> . |
| <code>deque<elementType> deq(beg, end);</code> | Creates the <code>deque</code> container <code>deq</code> . <code>deq</code> is initialized to the elements in the range <code>[beg, end)</code> , that is, all elements in the range <code>beg...end-1</code> . Both <code>beg</code> and <code>end</code> are iterators. |

In addition to the operations that are common to all containers (see Table H-6), Table H-8 describes operations that can be used to manipulate the elements of a `deque` container. The name of the function implementing the operations is shown in bold. The statement also shows how to use a particular function. (Suppose that `deq` is a `deque` container.)

TABLE H-8 Various Operations that Can Be Performed on a `deque` Object

| Expression | Description |
|-----------------------------------|-----------------------------------------------------------------------------|
| <code>deq.assign(n, elem)</code> | Assigns <code>n</code> copies of <code>elem</code> . |
| <code>deq.assign(beg, end)</code> | Assigns all the elements in the range <code>beg...end-1</code> . |
| <code>deq.push_front(elem)</code> | Inserts <code>elem</code> at the beginning of <code>deq</code> . |
| <code>deq.pop_front()</code> | Removes the first element from <code>deq</code> . |
| <code>deq.at(index)</code> | Returns the element at the position specified by <code>index</code> . |
| <code>deq[index]</code> | Returns the element at the position specified by <code>index</code> . |
| <code>deq.front()</code> | Returns the first element. (Does not check whether the container is empty.) |
| <code>deq.back()</code> | Returns the last element. (Does not check whether the container is empty.) |

Example H-6 illustrates how to use a `deque` container in a program.

EXAMPLE H-6

```
//deque Example
#include <iostream>
#include <deque>
#include <algorithm>
#include <iterator>

using namespace std;

int main()
{
    deque<int> intDeq;                                //Line 1
    ostream_iterator<int> screen(cout, " ");          //Line 2

    intDeq.push_back(13);                              //Line 3
    intDeq.push_back(75);                              //Line 4
    intDeq.push_back(28);                              //Line 5
    intDeq.push_back(35);                              //Line 6

    cout << "Line 7: intDeq: ";                        //Line 7
    copy(intDeq.begin(), intDeq.end(), screen);        //Line 8
    cout << endl;                                       //Line 9

    intDeq.push_front(0);                              //Line 10
    intDeq.push_back(100);                             //Line 11

    cout << "Line 12: After adding two more "
        << "elements, one at the front " << endl
        << "          and one at the back, "
        << "intDeq: ";                                //Line 12
    copy(intDeq.begin(), intDeq.end(), screen);        //Line 13
    cout << endl;                                       //Line 14

    intDeq.pop_front();                                //Line 15
    intDeq.pop_front();                                //Line 16

    cout << "Line 17: After removing the first "
        << "two elements, " << endl
        << "          intDeq: ";                        //Line 17
    copy(intDeq.begin(), intDeq.end(), screen);        //Line 18
    cout << endl;                                       //Line 19

    intDeq.pop_back();                                 //Line 20
    intDeq.pop_back();                                 //Line 21

    cout << "Line 22: After removing the last "
        << "two elements, " << endl
        << "          intDeq: ";                        //Line 22
```

```

        copy(intDeq.begin(), intDeq.end(), screen);    //Line 23
        cout << endl;                                //Line 24

    return 0;
}

```

Sample Run:

```

Line 7: intDeq: 13 75 28 35
Line 12: After adding two more elements, one at the front
        and one at the back, intDeq: 0 13 75 28 35 100
Line 17: After removing the first two elements,
        intDeq: 75 28 35 100
Line 22: After removing the last two elements,
        intDeq: 75 28

```

The statement in Line 1 declares a `deque` container `intDeq` of type `int`, that is, all the elements of `intDeq` are of type `int`. The statement in Line 2 declares `screen` to be an `ostream` iterator initialized to the standard output device. The statements in Lines 3 through 6 use the `push_back` operation to insert four numbers—13, 75, 28, and 35—into `intDeq`. The statement in Line 8 outputs the elements of `intDeq`. In the output, see the line marked Line 7, which contains the output of the statements in Lines 7 through 9.

The statement in Line 10 inserts 0 at the beginning of `intDeq`; the statement in Line 11 inserts 100 at the end of `intDeq`. The statement in Line 13 outputs the modified `intDeq`.

The statements in Lines 15 and 16 use the operation `pop_front` to remove the first two elements of `intDeq`, and the statement in Line 18 outputs the modified `intDeq`. The statements in Lines 20 and 21 use the operation `pop_back` to remove the last two elements of `intDeq`, and the statement in Line 23 outputs the modified `intDeq`.

Sequence Container: `list`

This section describes the sequence container `list`. List containers are implemented as doubly linked lists. Thus, every element in a list points to its immediate predecessor and immediate successor (except the first and the last elements). Recall that a linked list is not a random access data structure, such as an array. Therefore, to access, say, the fifth element in a list, we must first traverse the first four elements.

The name of the class containing the definition of the `class list` is `list`. Also, the definition of the `class list`, and the definitions of the functions to implement the various operations on a list, are contained in the header file `list`. Therefore, to use `list` in a program, the program must include the following statement:

```
#include <list>
```

Like other container classes, the **class** `list` also contains several constructors. Thus, a `list` object can be initialized several ways when it is declared. Table H-9 shows various ways to declare and initialize a `list` object.

TABLE H-9 Various Ways to Declare a `list` Object

| Statement | Description |
|-----------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>list<elementType> listCont;</code> | Creates the empty <code>list</code> container <code>listCont</code> . (The default constructor is invoked.) |
| <code>list<elementType> listCont(otherList);</code> | Creates the <code>list</code> container <code>listCont</code> and initializes it to the elements of <code>otherList</code> . <code>listCont</code> and <code>otherList</code> are of the same type. |
| <code>list<elementType> listCont(size);</code> | Creates the <code>list</code> container <code>listCont</code> of size <code>size</code> . <code>listCont</code> is initialized using the default constructor. |
| <code>list<elementType> listCont(n, elm);</code> | Creates the <code>list</code> container <code>listCont</code> of size <code>n</code> . <code>listCont</code> is initialized using <code>n</code> copies of the element <code>elm</code> . |
| <code>list<elementType> listCont(beg, end);</code> | Creates the <code>list</code> container <code>listCont</code> . <code>listCont</code> is initialized to the elements in the range <code>[beg, end)</code> , that is, all the elements in the range <code>beg...end-1</code> . Both <code>beg</code> and <code>end</code> are iterators. |

Table H-5 described the operations that are common to all containers, and Table H-6 described the operations that are common to all sequence containers. In addition to these common operations, Table H-10 describes operations that are specific to a `list` container. The name of the function implementing the operation is shown in bold. (Suppose that `listCont`, `listCont1`, and `listCont2` are containers of type `list`.)

TABLE H-10 Various Operations Specific to a `list` Container

| Expression | Description |
|----------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>listCont.assign(n, elem)</code> | Assigns <code>n</code> copies of <code>elem</code> . |
| <code>listCont.assign(beg, end)</code> | Assigns all the elements in the range <code>beg...end-1</code> . Both <code>beg</code> and <code>end</code> are iterators. |
| <code>listCont.push_front(elem)</code> | Inserts <code>elem</code> at the beginning of <code>listCont</code> . |
| <code>listCont.pop_front()</code> | Removes the first element from <code>listCont</code> . |
| <code>listCont.front()</code> | Returns the first element. (Does not check whether the container is empty.) |
| <code>listCont.back()</code> | Returns the last element. (Does not check whether the container is empty.) |
| <code>listCont.remove(elem)</code> | Removes all the elements that are equal to <code>elem</code> . |
| <code>listCont.remove_if(oper)</code> | Removes all the elements for which <code>oper</code> is <code>true</code> . |
| <code>listCont.unique()</code> | If the consecutive elements in <code>listCont</code> have the same value, removes the duplicates. |
| <code>listCont.unique(oper)</code> | If the consecutive elements in <code>listCont</code> have the same value, removes the duplicates, for which <code>oper</code> is <code>true</code> . |
| <code>listCont.sort()</code> | The elements of <code>listCont</code> are sorted. The sort criteria is <code><</code> . |
| <code>listCont.sort(oper)</code> | The elements of <code>listCont</code> are sorted. The sort criteria is specified by <code>oper</code> . |

TABLE H-10 Various Operations Specific to a `list` Container (continued)

| Expression | Description |
|-----------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>listCont1.merge(listCont2)</code> | Suppose that the elements of <code>listCont1</code> and <code>listCont2</code> are sorted. This operation moves all the elements of <code>listCont2</code> into <code>listCont1</code> . After this operation, the elements in <code>listCont1</code> are sorted. Moreover, after this operation, <code>listCont2</code> is empty. |
| <code>listCont1.merge(listCont2, oper)</code> | Suppose that the elements of <code>listCont1</code> and <code>listCont2</code> are sorted according to the sort criteria <code>oper</code> . This operation moves all the elements of <code>listCont2</code> into <code>listCont1</code> . After this operation, the elements in <code>listCont1</code> are sorted according to the sort criteria <code>oper</code> . |
| <code>listCont.reverse()</code> | The elements of <code>listCont</code> are reversed. |

Example H-7 illustrates how to use various operations on a `list` container.

EXAMPLE H-7

//List Container Example

```
#include <iostream>
#include <list>
#include <iterator>
#include <algorithm>

using namespace std;

int main()
{
    list<int> intList1, intList2, intList3, intList4; //Line 1

    ostream_iterator<int> screen(cout, " ");          //Line 2

    intList1.push_back(23);                            //Line 3
    intList1.push_back(58);                            //Line 4
    intList1.push_back(58);                            //Line 5
    intList1.push_back(58);                            //Line 6
    intList1.push_back(36);                            //Line 7
```

```

intList1.push_back(15);           //Line 8
intList1.push_back(93);          //Line 9
intList1.push_back(98);          //Line 10
intList1.push_back(58);          //Line 11

cout << "Line 12: intList1: ";    //Line 12
copy(intList1.begin(), intList1.end(), screen); //Line 13
cout << endl;                    //Line 14

intList2 = intList1;             //Line 15

cout << "Line 16: intList2: ";    //Line 16
copy(intList2.begin(), intList2.end(), screen); //Line 17
cout << endl;                    //Line 18

intList1.unique();               //Line 19

cout << "Line 20: After removing the consecutive "
    << "duplicates," << endl
    << "          intList1: ";    //Line 20
copy(intList1.begin(), intList1.end(), screen); //Line 21
cout << endl;                    //Line 22

intList2.sort();                 //Line 23

cout << "Line 24: After sorting, intList2: "; //Line 24
copy(intList2.begin(), intList2.end(), screen); //Line 25
cout << endl;                    //Line 26

intList3.push_back(13);          //Line 27
intList3.push_back(25);          //Line 28
intList3.push_back(23);          //Line 29
intList3.push_back(198);         //Line 30
intList3.push_back(136);         //Line 31

cout << "Line 32: intList3: ";    //Line 32
copy(intList3.begin(), intList3.end(), screen); //Line 33
cout << endl;                    //Line 34

intList3.sort();                 //Line 35

cout << "Line 36: After sorting, intList3: "; //Line 36
copy(intList3.begin(), intList3.end(), screen); //Line 37
cout << endl;                    //Line 38

intList2.merge(intList3);        //Line 39

cout << "Line 40: After merging intList2 and "
    << "intList3, intList2: " << endl
    << "          ";             //Line 40

```

```

        copy(intList2.begin(), intList2.end(), screen);    //Line 41
        cout << endl;                                     //Line 42

    return 0;
}

```

Sample Run:

```

Line 12: intList1: 23 58 58 58 36 15 93 98 58
Line 16: intList2: 23 58 58 58 36 15 93 98 58
Line 20: After removing the consecutive duplicates,
        intList1: 23 58 36 15 93 98 58
Line 24: After sorting, intList2: 15 23 36 58 58 58 93 98
Line 32: intList3: 13 25 23 198 136
Line 36: After sorting, intList3: 13 23 25 136 198
Line 40: After merging intList2 and intList3, intList2:
        13 15 23 23 25 36 58 58 58 93 98 136 198

```

For the most part, the output of the preceding program is straightforward. The statements in Lines 3 through 11 insert the element numbers 23, 58, 58, 58, 36, 15, 93, 98, and 58 (in this order) into `intList1`. The statement in Line 15 copies the elements of `intList1` into `intList2`. After this statement executes, `intList1` and `intList2` are identical. The statement in Line 19 removes any consecutive occurrences of the same elements. For example, the number 58 appears consecutively three times. The operation `unique` removes two occurrences of 58. Note that this operation has no effect on the 58 that appears at the end of `intList1`.

The statement in Line 23 sorts `intList2`. The statements in Lines 27 through 31 insert 13, 25, 23, 198, and 136 into `intList3`. The statement in Line 35 sorts `intList3`, and the statement in Line 39 merges `intList2` and `intList3` into `intList2`. After the `merge` operation, `intList3` is empty. The meanings of the remaining statements are similar.

Iterators

Iterators are like pointers. In general, an iterator points to the elements of a container (sequence or associative). Thus, with the help of iterators, we can successively access each element of a container.

The two most common operations on iterators are `++` (the increment operator) and `*` (the dereferencing operator). Suppose that `cntItr` is an iterator to a container. The statement:

```
++cntItr;
```

advances `cntItr` so that it points to the next element in the container. Similarly, the statement:

```
*cntItr;
```

returns the value of the element of the container pointed to by `cntItr`.

IOStream Iterators

A useful set of iterators is stream iterators—`istream` iterators and `ostream` iterators. The next two sections describe these iterators.

`istream_iterator`

The `istream` iterator is used to input data into a program from an input stream. The `class` `istream_iterator` contains the definition of an input stream iterator. The general syntax to use an `istream` iterator is:

```
istream_iterator<Type> isIdentifier(istream&);
```

where `Type` is either a built-in type or a user-defined class type, for which an input iterator is defined. The identifier `isIdentifier` is initialized using the constructor whose argument is either an `istream` class object such as `cin`, or any publicly defined `istream` subtype, such as `ifstream`.

`ostream_iterator`

The `ostream` iterators are used to output data from a program to an output stream. These iterators were defined earlier in this appendix. We review them here for the sake of completeness.

The `class` `ostream_iterator` contains the definition of an output stream iterator. The general syntax to use an `ostream` iterator is:

```
ostream_iterator<Type> osIdentifier(ostream&);
```

or:

```
ostream_iterator<Type> osIdentifier(ostream&, char* deLimit);
```

where `Type` is either a built-in type or a user-defined class type, for which an output iterator is defined. The identifier `osIdentifier` is initialized using the constructor whose argument in either an `ostream` class object, such as `cout`, or any publicly defined `ostream` subtype, such as `ofstream`. In the second form of declaring an `ostream` iterator, using the second argument (`deLimit`) of the initializing constructor, we can specify the character separating the output.

Container Adapters

The previous sections discussed several types of containers. In addition to the containers that work in a general framework, the STL also provides containers to accommodate special situations. These containers, called **container adapters**, are adapted standard STL containers to work in a specific environment. The three container adapters are:

- Stack
- Queue
- Priority queues

The container adapters do not support any type of iterator. That is, iterators cannot be used with these types of containers. The next two sections describe the container adapters `stack` and `queue`.

STACK

Chapter 19 discussed the data structure stack in detail. Because a stack is an important data structure, the STL provides a class to implement stacks in a program. The name of the class defining a stack is `stack`, and the name of the header file containing the definition of the `class` `stack` is `stack`. Table H-11 defines various operations supported by the stack container class.

TABLE H-11 Various Operations on a `stack` Object

| Operation | Description |
|-------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>size</code> | Returns the actual number of elements in the stack. |
| <code>empty</code> | Returns <code>true</code> if the stack is empty, <code>false</code> otherwise. |
| <code>push(item)</code> | Inserts a copy of <code>item</code> into the stack. |
| <code>top</code> | Returns the top element of the stack, but does not remove the element from the stack. This operation is implemented as a value-returning function. |
| <code>pop</code> | Removes the top element of the stack. |

In addition to the operations `size`, `empty`, `push`, `top`, and `pop`, the stack container class also provides relational operators to compare two stacks. For example, the relational operator `==` can be used to determine whether two stacks are identical, and so on.

The program in Example H-8 illustrates how to use the stack container class.

EXAMPLE H-8

```
#include <iostream>
#include <stack>

using namespace std;
```

```

int main()
{
    stack<int> intStack;                                //Line 1

    intStack.push(16);                                  //Line 2
    intStack.push(8);                                   //Line 3
    intStack.push(20);                                  //Line 4
    intStack.push(3);                                   //Line 5

    cout << "Line 6: The top element of "
          << "intStack: " << intStack.top()
          << endl;                                     //Line 6

    intStack.pop();                                     //Line 7

    cout << "Line 8: After the pop operation, "
          << "the top element of intStack: "
          << intStack.top() << endl;                   //Line 8

    cout << "Line 9: intStack elements: ";             //Line 9

    while (!intStack.empty())                           //Line 10
    {
        cout << intStack.top() << " ";                 //Line 11
        intStack.pop();                                 //Line 12
    }

    cout << endl;                                       //Line 13

    return 0;
}

```

Sample Run:

```

Line 6: The top element of intStack: 3
Line 8: After the pop operation, the top element of intStack: 20
Line 9: intStack elements: 20 8 16

```

QUEUE

Chapter 19 discussed the data structure queue in detail. Because a queue is an important data structure, the STL provides a class to implement queues in a program. The name of the class defining a queue is `queue`, and the name of the header file containing the definition of the `class queue` is `queue`. Table H-12 defines various operations supported by the queue container class.

TABLE H-12 Various Operations on a `queue` Object

| Operation | Description |
|-------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>size</code> | Returns the actual number of elements in the queue. |
| <code>empty</code> | Returns <code>true</code> if the queue is empty, <code>false</code> otherwise. |
| <code>push(item)</code> | Inserts a copy of <code>item</code> into the queue. |
| <code>front</code> | Returns the next, that is, first, element in the queue, but does not remove the element from the queue. This operation is implemented as a value-returning function. |
| <code>back</code> | Returns the last element in the queue, but does not remove the element from the queue. This operation is implemented as a value-returning function. |
| <code>pop</code> | Removes the next element in the queue. |

In addition to the operations `size`, `empty`, `push`, `front`, `back`, and `pop`, the queue container class also provides relational operators to compare two queues. For example, the relational operator `==` can be used to determine whether two queues are identical, and so on.

The program in Example H-9 illustrates how to use the queue container class.

EXAMPLE H-9

```
#include <iostream>
#include <queue>

using namespace std;

int main()
{
    queue<int> intQueue;                                     //Line 1

    intQueue.push(26);                                       //Line 2
    intQueue.push(18);                                       //Line 3
    intQueue.push(50);                                       //Line 4
    intQueue.push(33);                                       //Line 5

    cout << "Line 6: The front element of "
         << "intQueue: " << intQueue.front()
         << endl;                                           //Line 6
}
```

```

cout << "Line 7: The last element of "
    << "intQueue: " << intQueue.back()
    << endl;                                     //Line 7

intQueue.pop();                                  //Line 8

cout << "Line 9: After the pop operation, "
    << "the front element of intQueue: "
    << intQueue.front() << endl;                 //Line 9

cout << "Line 10: intQueue elements: ";          //Line 10

while (!intQueue.empty())                       //Line 11
{
    cout << intQueue.front() << " ";             //Line 12
    intQueue.pop();                             //Line 13
}

cout << endl;                                    //Line 14

return 0;
}

```

Sample Run:

```

Line 6: The front element of intQueue: 26
Line 7: The last element of intQueue: 33
Line 9: After the pop operation, the front element of intQueue: 18
Line 10: intQueue elements: 18 50 33

```

Algorithms

Several operations can be defined for a container. Some of the operations are very specific to a container and, therefore, are provided as part of the container definition (that is, as member functions of the class implementing the container). However, several operations—such as **find**, **sort**, and **merge**—are common to all containers. These common operations are, therefore, provided as generic algorithms, and can be applied to all containers as well as the built-in array type. The algorithms are bound to a particular container through an iterator pair.

The generic algorithms are contained in the header file **algorithm**. The ensuing sections describe several of these algorithms and show how to use them in a program. Because algorithms are implemented with the help of functions, in these sections, the terms function and algorithm mean the same thing.

STL Algorithm Classification

In earlier sections, you applied various operations on the sequence container, such as **clear**, **sort**, **merge**, and so on. However, those algorithms were tied to a specific

container in terms of the members of a specific class. All those algorithms and a few more are also available in a more general form, called **generic algorithms**, and can be applied in a variety of situations. This section discusses some of these generic algorithms.

The STL contains algorithms that look only at the elements in a container and that move the elements of a container. It also has algorithms that can perform a specific calculation, such as finding the sum of the elements of a numeric container. The STL also contains algorithms for basic set theory operations, such as set union and intersection. You have already encountered some of the generic algorithms, such as the `copy` algorithm, which copies the elements from a given range of elements to another place, such as another container or the screen. The algorithms in the STL can be classified into the following categories:

- Nonmodifying algorithms
- Modifying algorithms
- Numeric algorithms
- STL algorithms

The next four sections describe these algorithms. Most of the generic algorithms are contained in the header file `algorithm`. Certain algorithms, such as numeric, are contained in the header file `numeric`.

NONMODIFYING ALGORITHMS

Nonmodifying algorithms do not modify the elements of the container; they only investigate the elements. Table H-13 describes the nonmodifying algorithms.

TABLE H-13 Nonmodifying Algorithms

| Nonmodifying Algorithms | | |
|----------------------------|----------------------------|--------------------------|
| <code>adjacent_find</code> | <code>find_if</code> | <code>max</code> |
| <code>binary_search</code> | <code>find_end</code> | <code>max_element</code> |
| <code>count</code> | <code>find_first_of</code> | <code>min</code> |
| <code>count_if</code> | <code>for_each</code> | <code>min_element</code> |
| <code>equal</code> | <code>includes</code> | <code>search</code> |
| <code>equal_range</code> | <code>lower_bound</code> | <code>search_n</code> |
| <code>find</code> | <code>mismatch</code> | <code>upper_bound</code> |

MODIFYING ALGORITHMS

Modifying algorithms, as the name implies, modify the elements of a container by rearranging, removing, and/or changing the values of the elements. Table H-14 describes the modifying algorithms.

TABLE H-14 Modifying Algorithms

| Modifying Algorithms | | |
|----------------------|----------------------|--------------------------|
| copy | previous_permutation | rotate_copy |
| copy_backward | random_shuffle | set_difference |
| fill | remove | set_intersection |
| fill_n | remove_copy | set_symmetric_difference |
| generate | remove_copy_if | set_union |
| generate_n | remove_if | sort |
| inplace_merge | replace | stable_partition |
| iter_swap | replace_copy | stable_sort |
| merge | replace_copy_if | swap |
| next_permutation | replace_if | swap_ranges |
| nth_element | reverse | transform |
| partial_sort | reverse_copy | unique |
| partial_sort_copy | rotate | unique_copy |
| partition | | |

Modifying algorithms that change the order of the elements, not their values, are also called **mutating algorithms**. For example, `next_permutation`, `partition`, `previous_permutation`, `random_shuffle`, `reverse`, `reverse_copy`, `rotate`, `rotate_copy`, and `stable_partition` are mutating algorithms.

NUMERIC ALGORITHMS

Numeric algorithms are designed to perform numeric calculations on the elements of a container. Table H-15 defines these algorithms.

TABLE H-15 Numeric Algorithms

| Numeric Algorithms | |
|----------------------------------|----------------------------|
| <code>accumulate</code> | <code>inner_product</code> |
| <code>adjacent_difference</code> | <code>partial_sum</code> |

The next section shows how some of these algorithms are used in a program.

STL Algorithms

The ensuing sections describe some of the STL algorithms. Each algorithm includes the function prototypes, a brief description of what the algorithm does, and a program or example showing how to use it. In the function prototypes, the parameter types indicate for which type of container the algorithm is applicable.

Functions `fill` and `fill_n`

The function `fill` is used to fill a container with elements, and the function `fill_n` is used to fill the next `n` elements. The element that is used as a filling element is passed as a parameter to these functions. Both of these functions are defined in the header file `algorithm`. The prototypes of these functions are:

```
template <class forwardItr, class Type>
void fill(forwardItr first, forwardItr last, const Type& value);

template <class forwardItr, class size, class Type>
void fill_n(forwardItr first, size n, const Type& value);
```

The first two parameters of the function `fill` are forward iterators that specify the starting and ending positions of the container; the third parameter is the filling element. The first parameter of the function `fill_n` is a forward iterator that specifies the starting position of the container; the second parameter specifies the number of elements to be filled; and the third parameter specifies the filling element. The program in Example H-10 illustrates how to use these functions.

EXAMPLE H-10

```

//STL functions fill and fill_n

#include <iostream>
#include <algorithm>
#include <iterator>
#include <vector>

using namespace std;

int main()
{
    vector<int>  vecList(8);                //Line 1
    ostream_iterator<int>  screen(cout, " "); //Line 2

    fill(vecList.begin(), vecList.end(), 2); //Line 3

    cout << "Line 4: After filling vecList "
          << "with 2's: ";                //Line 4
    copy(vecList.begin(), vecList.end(), screen); //Line 5
    cout << endl;                          //Line 6

    fill_n(vecList.begin(), 3, 5);          //Line 7

    cout << "Line 8: After filling the first "
          << "three elements with 5's: "
          << endl << "          ";        //Line 8
    copy(vecList.begin(), vecList.end(), screen); //Line 9
    cout << endl;                          //Line 10

    return 0;
}

```

Sample Run:

```

Line 4: After filling vecList with 2's: 2 2 2 2 2 2 2 2
Line 8: After filling the first three elements with 5's:
      5 5 5 2 2 2 2 2

```

The statements in Lines 1 and 2 declare `vecList` to be a sequence container of size 8, and `screen` to be an `ostream_iterator` initialized to `cout` with the delimit character space, respectively. The statement in Line 3 uses the function `fill` to fill `vecList` with 2; that is, all eight elements of `vecList` are set to 2. The statement in Line 5 outputs the elements of `vecList` using the `copy` function. The statement in Line 7 uses the function `fill_n` to store 5 in the elements of `vecList`. In the statement in Line 7, the first parameter of `fill_n` is `vecList.begin()`, which specifies the starting position of where to begin copying. The second parameter of `fill_n` is 3, which specifies the number of elements to be filled, and the third parameter, 5, specifies the

filling element. Therefore, 5 is copied into the first three elements of `vecList`. The statement in Line 9 outputs the elements of `vecList`.

Functions `find` and `find_if`

The functions `find` and `find_if` are used to find the elements in a given range. These functions are defined in the header file `algorithm`. The prototypes of the functions `find` and `find_if` are:

```
template <class inputItr, class size, class Type>
inputItr find(inputItr first, inputItr last,
              const Type& searchValue);
```

```
template <class inputItr, class unaryPredicate>
inputItr find_if(inputItr first, inputItr last, unaryPredicate op);
```

The function `find` searches the range of elements `first...last-1` for the element `searchValue`. If `searchValue` is found in the range, the function returns the position in the range where `searchValue` is found; otherwise, it returns `last`. The function `find_if` searches the range of elements `first...last-1` for the element for which `op(rangeElement)` is `true`. If an element satisfying `op(rangeElement)` `true` is found, it returns the position in the given range where such an element is found; otherwise, it returns `last`.

Example H-11 illustrates how to use the functions `find` and `find_if`.

EXAMPLE H-11

Consider the following statements:

```
char cList[10] = {'a', 'i', 'C', 'd', 'e', 'f',
                 'o', 'H', 'u', 'j'};           //Line 1

vector<char> charList(cList, cList + 10);      //Line 2

vector<char>::iterator position;               //Line 3
```

After the statement in Line 2 executes, the vector container `charList` is:

```
charList = {'a', 'i', 'C', 'd', 'e', 'f', 'o', 'H', 'u', 'j'};
```

Consider the following statement:

```
position = find(charList.begin(), charList.end(), 'd');
```

This statement searches `charList` for the first occurrence of `'d'` and returns an iterator, which is stored in `position`. Because `'d'` is the fourth character in `charList`, its position is 3. Therefore, `position` points to the element at position 3 in `charList`.

Now consider the following statement:

```
position = find_if(charList.begin(), charList.end(), isupper);
```

This statement uses the function `find_if` to find the first uppercase character in `charList`. (Note that the function `isupper` from the header file `cctype` is passed as the third parameter to the function `find_if`.) The first uppercase character in `charList` is the third element. Therefore, after this statement executes, `position` points to the third element of `charList`.

We leave it as an exercise for you to write a program that tests the functions `find` and `find_if`.

Functions `remove` and `replace`

The function `remove` is used to remove certain elements from a sequence. The function `replace` is used to replace all occurrences, in a given range, of a given element with a new value. Some of the prototypes of these functions are:

```
template <class forwardItr, class Type>
forwardItr remove(forwardItr first, forwardItr last,
                  const Type& value);

template <class forwardItr, class Type>
void replace(forwardItr first, forwardItr last,
             const Type& oldValue, const Type& newValue);
```

The function `remove` removes each occurrence of a given element in the range `first...last-1`. The element to be removed is passed as the third parameter to this function. This function returns an iterator, which points to the position after the last element copied.

The function `replace` replaces all the elements in the range `first...last-1` whose value is equal to `oldValue` with the value specified by `newValue`.

The program in Example H-12 shows how to use the functions `remove` and `replace`.

EXAMPLE H-12

```
//STL functions remove and replace
```

```
#include <iostream>
#include <cctype>
#include <algorithm>
```

```

#include <iterator>
#include <vector>

using namespace std;

int main()
{
    char cList[10] = {'A', 'a', 'A', 'B', 'A',
                     'c', 'D', 'e', 'F', 'A'};           //Line 1

    vector<char> charList1(cList, cList + 10);           //Line 2
    vector<char> charList2(cList, cList + 10);           //Line 3

    vector<char>::iterator lastElem;                     //Line 4

    ostream_iterator<char> screen(cout, " ");           //Line 5

    cout << "Line 6: Character list 1: ";               //Line 6
    copy(charList1.begin(), charList1.end(), screen);    //Line 7
    cout << endl;                                       //Line 8

    //remove
    lastElem = remove(charList1.begin(),
                     charList1.end(), 'A');             //Line 9

    cout << "Line 10: Character list 1 after "
          << "removing A: ";                             //Line 10
    copy(charList1.begin(), lastElem, screen);           //Line 11
    cout << endl;                                       //Line 12

    cout << "Line 13: Character list 2: ";               //Line 13
    copy(charList2.begin(), charList2.end(), screen);    //Line 14
    cout << endl;                                       //Line 15

    //replace
    replace(charList2.begin(), charList2.end(),
           'A', 'Z');                                   //Line 16

    cout << "Line 17: Character list 2 after "
          << "replacing A with Z: " << endl;             //Line 17
    copy(charList2.begin(), charList2.end(), screen);    //Line 18
    cout << endl;                                       //Line 19

    return 0;
}

```

Sample Run:

```

Line 6: Character list 1: A a A B A c D e F A
Line 10: Character list 1 after removing A: a B c D e F
Line 13: Character list 2: A a A B A c D e F A
Line 17: Character list 2 after replacing A with Z:
Z a Z B Z c D e F Z

```

The statements in Lines 2 and 3 create vector lists, `charList1` and `charList2`, of type `char` and initialize them using the array `cList` created in Line 1. The statement in Line 4 declares the vector iterator `lastElem`. The statement in Line 5 declares the ostream iterator `screen`. The statement in Line 6 outputs the value of `charList1`.

The statement in Line 9 uses the function `remove` to remove all the occurrences of 'A' from `charList1`. The function returns a pointer to one character past the last element of the new range, which is stored in `lastElem`. The statement in Line 11 outputs the elements in the new range.

The statement in Line 16 uses the function `replace` to replace all the occurrences of 'A' with 'Z' in `charList2`. The statement in Line 18 outputs the elements of `charList2`.

Functions `search`, `sort`, and `binary_search`

The functions `search`, `sort`, and `binary_search` are defined in the header file `algorithm`. The function `search` is used to search for elements. A prototype of the function `search` is:

```
template <class forwardItr1, class forwardItr2>
forwardItr1 search(forwardItr1 first1, forwardItr1 last1,
                  forwardItr2 first2, forwardItr2 last2);
```

Given the two ranges of elements, `first1...last1-1` and `first2...last2-1`, the function `search` searches for the first element in the range `first1...last1-1` where the range `first2...last2-1` occurs as a subrange of `first1...last1-1`.

A prototype of the function `sort` is:

```
template <class randomAccessItr>
void sort(randomAccessItr first, randomAccessItr last);
```

The function `sort` reorders the elements in the range `first...last-1` in ascending order.

A prototype of the function `binary_search` is:

```
template <class forwardItr, class Type>
bool binary_search(forwardItr first, forwardItr last,
                  const Type& searchValue);
```

This function returns `true` if `searchValue` is found in the range `first...last-1`, `false` otherwise.

Example H-13 illustrates how to use these searching and sorting functions.

EXAMPLE H-13

```

//STL functions search, sort, and binary_search

#include <iostream>
#include <algorithm>
#include <iterator>
#include <vector>

using namespace std;

int main()
{
    int intList[15] = {12, 34, 56, 34, 34,
                      78, 38, 43, 12, 25,
                      34, 56, 62, 5, 49}; //Line 1

    vector<int> vecList(intList, intList + 15); //Line 2
    int list[2] = {34, 56}; //Line 3

    vector<int>::iterator location; //Line 4

    ostream_iterator<int> screenOut(cout, " "); //Line 5

    cout << "Line 6: vecList: "; //Line 6
    copy(vecList.begin(), vecList.end(), screenOut); //Line 7
    cout << endl; //Line 8

    cout << "Line 9: list: "; //Line 9
    copy(list, list + 2, screenOut); //Line 10
    cout << endl; //Line 11

    //search
    location = search(vecList.begin(), vecList.end(),
                     list, list + 2); //Line 12

    if (location != vecList.end()) //Line 13
        cout << "Line 14: list found in vecList. "
              << "The first occurrence of \n      "
              << "    list in vecList is at position: "
              << (location - vecList.begin())
              << endl; //Line 14
    else //Line 15
        cout << "Line 16: list is not in vecList."
              << endl; //Line 16

    //sort
    sort(vecList.begin(), vecList.end()); //Line 17

    cout << "Line 18: vecList after sorting:\n"
          << "      "; //Line 18
    copy(vecList.begin(), vecList.end(), screenOut); //Line 19

```

```

    cout << endl; //Line 20

    //binary_search
    bool found; //Line 21

    found = binary_search(vecList.begin(),
                          vecList.end(), 78); //Line 22

    if (found) //Line 23
        cout << "Line 24: 43 found in vecList "
              << endl; //Line 24
    else //Line 25
        cout << "Line 26: 43 not in vecList" << endl; //Line 26

    return 0;
}

```

Sample Run:

```

Line 6: vecList: 12 34 56 34 34 78 38 43 12 25 34 56 62 5 49
Line 9: list: 34 56
Line 14: list found in vecList. The first occurrence of
        list in vecList is at position: 1
Line 18: vecList after sorting:
        5 12 12 25 34 34 34 34 38 43 49 56 56 62 78
Line 24: 43 found in vecList

```

The statement in Line 2 creates a vector, `vecList`, and initializes it using the array `intList` created in Line 1. The statement in Line 3 creates an array, `list`, of two components and also initializes `list`. The statement in Line 7 outputs `vecList`. The statement in Line 12 uses the function `search` and searches `vecList` to find the position (of the first occurrence) in `vecList` where `list` occurs as a subsequence. The statements in Lines 13 through 16 output the result of the search. See the line marked Line 14 in the output.

The statement in Line 17 uses the function `sort` to sort `vecList`. The statement in Line 19 outputs `vecList`. In the output, the line marked Line 18 contains the output of the statements in Lines 18 through 20.

The statement in Line 22 uses the function `binary_search` to search `vecList`. The statements in Lines 23 through 26 output the search result.

This page intentionally left blank



APPENDIX I ANSWERS TO ODD-NUMBERED EXERCISES

Chapter 1

1. a. false; b. false; c. true; d. false; e. false; f. false; g. false; h. true; i. true; j. false; k. true; l. false
3. Screen and printer.
5. An operating system monitors the overall activity of the computer and provides services. Some of these services include memory management, input/output activities, and storage management.
7. In machine language, the programs are written using the binary codes, whereas in high-level language, the programs are closer to the natural language. For execution, a high-level language program is translated into machine language, whereas a machine language need not be translated into any other language.
9. Because the computer cannot directly execute instructions written in a high-level language, a compiler is needed to translate a program written in high-level language into machine code.
11. Every computer directly understands its own machine language. Therefore, for the computer to execute a program written in a high-level language, the high-level language program must be translated into the computer's machine language.
13. In linking, an object program is combined with other programs in the library used in the program to create the executable code.
15. To find the weighted average of the four test scores, first you need to know each test score and its weight. Next, you multiply each test score with its weight and then add these numbers to get the average. Therefore:
 1. Get `testScore1`, `weightTestScore1`
 2. Get `testScore2`, `weightTestScore2`
 3. Get `testScore3`, `weightTestScore3`
 4. Get `testScore4`, `weightTestScore4`
 5. `weightedAverage = testScore1 * weightTestScore1 +
testScore2 * weightTestScore2 +
testScore3 * weightTestScore3 +
testScore4 * weightTestScore4;`

17. To find the price per square inch, first we need to find the area of the pizza. Then we divide the price of the pizza by the area of the pizza. Let **radius** denote the radius, **area** denote the area of the circle, and **price** denote the price of the pizza. Also, let **pricePerSquareInch** denote the price per square inch.

- a. Get **radius**
- b. $\text{area} = \pi * \text{radius} * \text{radius}$
- c. Get **price**
- d. $\text{pricePerSquareInch} = \text{price} / \text{area}$

19. To calculate the selling price of an item, we need to know the original price (the price the store pays to buy) of the item. We can then use the following formula to find the selling price.

$$\text{sellingPrice} = \text{originalPrice} + \text{originalPrice} * .60$$

The algorithm is as follows:

- a. Get **originalPrice**
- b. Calculate the **sellingPrice** using the formula:

$$\text{sellingPrice} = \text{originalPrice} + \text{originalPrice} * .60$$

The information needed to calculate the selling price is the original price and the marked-up percentage.

21. Suppose that **numOfPages** denotes the number of pages to be faxed, and **billingAmount** denotes the total charges for the pages faxed. To calculate the total charges, you need to know the number of pages faxed.

If **numOfPages** is less than or equal to 10, the billing amount is service charges + (**numOfPages** × 0.20); otherwise, billing amount is service charges + 10 × 0.20 + (**numOfPages** - 10) × 0.10. That is,

You can now write the algorithm as follows:

- a. Get **numOfPages**.
- b. Calculate billing amount using the formula:

if (**numOfPages** is less than or equal to 10)

$\text{billingAmount} = 3.00 + (\text{numOfPages} \times 0.20);$

 otherwise

$$\text{billingAmount} = 3.00 + 10 \times 0.20 + (\text{numOfPages} - 10) \times 0.10;$$

23. Suppose **averageTestScore** denotes the average test score, **highestScore** denotes the highest test score, **testScore** denotes a test score, **sum** denotes the sum of all of the test scores, **count** denotes the number of students in class, and **studentName** denotes the name of a student.

- a. First, you design an algorithm to find the average test score. To find the average test score, first you need to count the number of students in the class and add the test score of each student. You then divide the sum by count to find the average test score. The algorithm to find the average test score is as follows:
 - i. Set **sum** and **count** to 0.
 - ii. Repeat the following for each student in class.
 1. Get **testScore**
 2. Increment **count** and update the value of **sum** by adding the current test score to **sum**.
 - iii. Use the following formula to find the average test score.


```
if (count is 0)
    averageTestScore = 0;
otherwise
    averageTestScore = sum / count;
```
- b. The following algorithm determines and prints the names of all of the students whose test score is below the average test score.

Repeat the following for each student in class.

 - i. Get **studentName** and **testScore**
 - ii. **if (testScore is less than averageTestScore)**
 print studentName
- c. The following algorithm determines the highest test score.
 - i. Get first student's test score and call it **highestTestScore**.
 - ii. Repeat the following for each of the remaining students in class
 1. Get **testScore**
 2. **if (testScore is greater than highestTestScore)**
 highestTestScore = testScore;
- d. To print the names of all of the students whose test score is the same as the highest test score, compare the test score of each student with the highest test score, and if they are equal, print the name. The following algorithm accomplishes this. Repeat the following for each student in class.
 - i. Get **studentName** and **testScore**
 - ii. **if (testScore is equal to highestTestScore)**
 print studentName

You can use the solutions of the subproblems obtained in parts a through d to design the main algorithm as follows:

1. Use the algorithm in part a to find the average test score.
2. Use the algorithm in part b to print the names of all of the students whose score is below the average test score.
3. Use the algorithm in part c to find the highest test score.
4. Use the algorithm in part d to print the names of all of the students whose test score is the same as the highest test score.

Chapter 2

1. a. false; b. false; c. false; d. true; e. true; f. false; g. true; h. true; i. false; j. true; k. false
3. b, d, e
5. The identifiers `firstName` and `FirstName` are not the same. C++ is case sensitive. The first letter of `firstName` is lowercase `f`, whereas the first character of `FirstName` is uppercase `F`. So these identifiers are different.
7.
 - a. 3
 - b. Not possible. Both of the operands of the operator `%` must be integers. Because the second operand, `w`, is a floating-point value, the expression is invalid.
 - c. Not possible. Both of the operands of the operator `%` must be integers. Because the first operand, which is `y + w`, is a floating-point value, the expression is invalid.
 - d. 38.5
 - e. 1
 - f. 2
 - g. 2
 - h. 420.0
9. 7
11. a and c are valid.
13.
 - a. `32 * a + b`
 - b. `'8'`
 - c. `"Julie Nelson"`
 - d. `(b * b - 4 * a * c) / (2 * a)`
 - e. `(a + b) / c * (e * f) - g * h`
 - f. `(-b + (b * b - 4 * a * c)) / (2 * a)`
15.


```
x = 20
y = 15
z = 6
w = 11.5
t = 4.5
```
17. a. 0.50; b. 24.50; c. 37.6; d. 8.3; e. 10; f. 38.75
19. a and c are correct.
21.
 - a.

```
int num1;
int num2;
```
 - b. `cout << "Enter two numbers separated by spaces." << endl;`
 - c. `cin >> num1 >> num2;`
 - d.

```
cout << "num1 = " << num1 << "num2 = " << num2
    << "2 * num1 - num2 = " << 2 * num1 - num2 << endl;
```

23. A correct answer is:

```
#include <iostream>

using namespace std;

const char STAR = '*';
const int PRIME = 71;

int main()
{
    int count, sum;
    double x;

    int newNum;    //declare newNum

    count = 1;
    sum = count + PRIME;
    x = 25.67;    // x = 25.67;
    newNum = count * 1 + 2; //newNum = count * ONE + 2;
    sum = sum + count;    //sum + count = sum;
    x = x + sum * count; // x = x + sum * COUNT;
    cout << " count = " << count << ", sum = " << sum
        << ", PRIME = " << PRIME << endl;
    return 0;
}
```

25. An identifier must be declared before it can be used.

27. a. `x *= 2;`
 b. `x += y - 2;`
 c. `sum += num;`
 d. `z *= x + 2;`
 e. `y /= x + 5;`

- 29.
- | | a | b | c |
|-------------------------------------|----|----|-----|
| <code>a = (b++) + 3;</code> | 9 | 7 | und |
| <code>c = 2 * a + (++b);</code> | 9 | 8 | 26 |
| <code>b = 2 * (++c) - (a++);</code> | 10 | 45 | 27 |

31. (The user input is shaded.)

```
a = 25
Enter two integers : 20 15
```

```
The numbers you entered are 20 and 15
z = 45.5
Your grade is A
The value of a = 65
```

33. `#include <iostream>`
`#include <string>`

`using namespace std;`

`const double X = 13.45;`
`const int Y = 34;`
`const char BLANK = ' ';`

```

int main()
{
    string firstName, lastName;
    int num;
    double salary;

    cout << "Enter first name: ";
    cin >> firstName;
    cout << endl;

    cout << "Enter last name: ";
    cin >> lastName;
    cout << endl;

    cout << "Enter a positive integer less than 70: ";
    cin >> num;
    cout << endl;

    salary = num * X;

    cout << "Name: " << firstName << BLANK << lastName << endl;
    cout << "Wages: $" << salary << endl;
    cout << "X = " << X << endl;
    cout << "X + Y = " << X + Y << endl;

    return 0;
}

```

Chapter 3

1. a. true; b. true; c. false; d. false; e. true; f. true
3. a. $x = 37$, $y = 86$, $z = 0.56$
b. $x = 37$, $y = 32$, $z = 86.56$
c. Input failure: $z = 37.0$, $x = 86$, trying to read the . (period) into y .
5. Input failure: Trying to read **A** into y , which is an **int** variable. $x = 46$, $y = 18$, and $z = 'A'$. The values of y and z are unchanged.
7. iomanip
9. `getline(cin, name);`
11. a. `name = " Lance Grant", age = 23`
b. `name = " ", age = 23`
13. `#include <iostream>`
`#include <fstream>`

```

using namespace std;

int main()
{
    int num1, num2;
    ifstream infile;
    ostream outfile;
}

```

- ```

infile.open("input.dat");
outfile.open("output.dat");

infile >> num1 >> num2;
outfile << "Sum = " << num1 + num2 << endl;

infile.close();
outfile.close();

return 0;
}

```
15. `fstream`
  17.
    - a. Same as before.
    - b. The file contains the output produced by the program.
    - c. The file contains the output produced by the program. The old contents are erased.
    - d. The program would prepare the file and store the output in the file.
  19.
    - a. `outfile.open("travel.dat ");`
    - b. `outfile >> fixed >> showpoint >> setprecision(2);`
    - c. `outfile >> day >> " " >> distance >> " " >> speed >> endl;`
    - d. `travelTime = distance / speed;`  
`outfile >> travelTime;`
    - e. `fstream` and `iomanip`.

## Chapter 4

---

1. a. false; b. false; c. false; d. true; e. false; f. false; g. false; h. false; i. false; j. true
3. a. true; b. false; c. true; d. true; e. false
5.
  - a. `x = y: 0`
  - b. `x != z: 1`
  - c. `y == z - 3: 1`
  - d. `!(z > w): 0`
  - e. `x + y < z: 0`
7. Omit the semicolon after `else`. The correct statement is:
 

```

if (score >= 60)
 cout << "You pass." << endl;
else
 cout << "You fail." << endl;

```
9. 3 1
11.
 

```

if (sale > 20000)
 bonus = 0.10
else if (sale > 10000 && sale <= 20000)
 bonus = 0.05;
else
 bonus = 0.0;

```

13. a. The output is: `Discount = 10%`. The semicolon at the end of the `if` statement terminates the `if` statement. So the `cout` statement is not part of the `if` statement. The `cout` statement will execute regardless of whether the expression in the `if` statement evaluates to `true` or `false`.
- b. The output is: `Discount = 10%`. The semicolon at the end of the `if` statement terminates the `if` statement. So the `cout` statement is not part of the `if` statement. The `cout` statement will execute regardless of whether the expression in the `if` statement evaluates to `true` or `false`.
15. a. `(x >= y) ? z = x - y : z = y - x;`  
 b. `(hours >= 40.0) ? wages = 40 * 7.50 + 1.5 * 7.5 * (hours - 40) : wages = hours * 7.50;`  
 c. `(score >= 60) ? str = "Pass" : str = "Fail";`
17. a. 40.00  
 b. 40.00  
 c. 55.00
19. 15
21. 96
23. `#include <iostream>`

```
using namespace std;
const int SECRET = 5;

int main()
{
 int x, y, w, z;

 z = 9;

 if (z > 10)
 {
 x = 12;
 y = 5;
 w = x + y + SECRET;
 }
 else
 {
 x = 12;
 y = 4;
 w = x + y + SECRET;
 }

 cout << "w = " << w << endl;

 return 0;
}
```

## Chapter 5

---

1. a. false; b. true; c. false; d. true; e. true; f. true; g. true; h. false
3. 5
5. if `ch > 'Z'` or `ch < 'A'`
7. `Sum = 158`
9. `Sum = 158`
11. 11 18 25
13. Replace the `while` loop statement with the following:  
`while (response == 'Y' || response == 'y')`  
 Replace the `cout` statement:  
`cout << num1 << " + " << num2 << " = " << (num1 - num2)`  
`<< endl;`  
 with the following:  
`cout << num1 << " + " << num2 << " = " << (num1 + num2)`  
`<< endl;`
15. 4 3 2 1
17. 0 3 8 15 24
19. Loop control variable: `j`  
 The initialization statement: `j = 1;`  
 Loop condition: `j <= 10;`  
 Update statement: `j++`  
 The statement that updates the value of `s`: `s = s + j * (j - 1);`
21. 2 7 17 37 77 157 317
23. a. \*  
 b. infinite loop  
 c. infinite loop  
 d. \*\*\*\*  
 e. \*\*\*\*\*  
 f. \*\*\*
25. The relationship between `x` and `y` is:  $3^y = x$ .  
 Output: `x = 19683, y = 10`
27. 0 - 24  
 25 - 49  
 50 - 74  
 75 - 99  
 100 - 124  
 125 - 149  
 150 - 174  
 175 - 200

29. a. both  
 b. `do ... while`  
 c. `while`  
 d. `while`
31. In a pretest loop, the loop condition is evaluated before executing the body of the loop. In a posttest loop, the loop condition is evaluated after executing the body of the loop. A posttest loop executes at least once, whereas a pretest loop may not execute at all.
33. `int num;`  
`do`  
`{`  
     `cout << "Enter a number less than 20 or greater than 75: ";`  
     `cin >> num;`  
`}`  
`while (20 <= num && num <= 75);`
35. `int i = 0, value = 0;`  
`do`  
`{`  
     `if (i % 2 == 0 && i <= 10)`  
         `value = value + i * i;`  
     `else if (i % 2 == 0 && i > 10)`  
         `value = value + i;`  
     `else`  
         `value = value - i;`  
     `i = i + 1;`  
`}`  
`while (i <= 20);`  
  
`cout << "value = " << value << endl;`  
  
 The Output is: Value = 200
37. `cin >> number;`  
`while (number != -1)`  
`{`  
     `total = total + number;`  
     `cin >> number;`  
`}`  
`cout << endl;`  
`cout << total << endl;`
39. a.  
     `number = 1;`  
     `while (number <= 10)`  
     `{`  
         `cout << setw(3) << number;`  
         `number++;`  
     `}`

```

b. number = 1;
 do
 {
 cout << setw(3) << number;
 number++;
 }
 while (number <= 10);
41. 11 18 25
43. -1 0 3 8 15 24
45. 12 11 9 7 6 4 2 1

```

## Chapter 6

---

1. a. false; b. true; c. true; d. true; e. false
3. a. 4 b. 10.8 c. 2.5 d. 10.24 e. 15.625  
f. 5 g. 2.5 h. 9 i. 28 j. 36
5. (iii)
7. a, b, c, e, f, and g are valid. In d, the function call in the output (`cout`) statement requires one more argument.
9. a. 4; `int`  
b. 2; `double`  
c. 4; `char`  
d. The function `test` requires four actual parameters. The order of the parameters is: `int`, `char`, `double`, `int`.  
e. `cout << test(5, 'z', 7.3, 5) << endl;`  
f. `cout << two(17.5, 18.3) << endl;`  
g. `cout << static_cast<char>(static_cast<int>(three(4, 3, 'A', 17.6)) + 1) << endl;`
11. `bool isUppercaseLetter(char ch)`  

```

{
 if (isupper(ch))
 return true;
 else
 return false;
}

```
13. a. i. 125 ii. 432  
b. The function computes  $x^3$ , in which  $x$  is the argument of the function.
15. 1 4 9 16 25 36 49 64 81 100

```

17. double funcEx17(double x, double y, double z)
 {
 return (x + y) * z;
 }

```

## Chapter 7

---

1. a. true; b. false; c. true; d. false; e. true; f. false; g. false; h. false; i. true
3. a. A variable declared in the heading of a function definition is called a formal parameter. A variable or expression used in a function call is called an actual parameter.  
 b. A value parameter receives a copy of the actual parameter's data. A reference parameter receives the address of the actual parameter.  
 c. A variable declared within a function or block is called a local variable. A variable declared outside of every function definition is called a global variable.
5. 

```
void funcThreeTimes(double x)
{
 cout << fixed << showpoint << setprecision(2);
 cout << 3 * x << endl;
}
```
7. 

```
void initialize(int& x, double& y, string& str)
{
 x = 0;
 y = 0;
 str = "";
}
```
9. 5, 10, 15  
 20, 10, 15  
 25, 30, 15  
 45, 30, 60
11. 

```
#include <iostream>

using namespace std;

void func(int val1, int val2);

int main()
{
 int num1, num2;
 1 cout << "Please enter two integers." << endl;
 2 cin >> num1 >> num2;
 3 func (num1, num2);
}
```

- ```

__7__  cout << " The two integers are " << num1
      << ", " << num2 << endl;
__8__  return 0;
      }

      void func (int val1, int val2)
      {
          int val3, val4;
__4__  val3 = val1 + val2;
__5__  val4 = val1 * val2;
__6__  cout << "The sum and product are " << val3
      << " and " << val4 << endl;
      }

```
13. `void traceMe(double& x, double y, double& z)`
- ```

{
 if (x != 0)
 z = sqrt(y) / x;
 else
 {
 cout << "Enter a nonzero number: ";
 cin >> x;
 cout << endl;
 z = floor(pow(y, x));
 }
}

```
15. 10 20  
5 20
17. 11, 3  
16, 2  
19, 3  
24, 2
19. (a), (b), and (d) are correct.

## Chapter 8

---

1. a. true; b. false; c. true; d. false; e. false; f. true; g. true; h. true; i. false; j. false; k. false
3. Only a and c are valid.
5. The statement:

```
using namespace std;
```

is missing between Lines 1 and 2.

7. Either include the statement:

```
using namespace aaa;
```

before the function `main` or refer to the identifiers `x` and `y` in `main` as `aaa::x` and `aaa::y`, respectively.

9. Hello --> Jello  
 Bingo --> Ringo  
 Sunny --> Bunny
11. Going to the Amusement Park  
 14  
 10  
 musem  
 ABCDEFGHIJK  
 11  
 aBdDEFGHIJK

## Chapter 9

---

1. a. true; b. true; c. false; d. false; e. true; f. false; g. false; h. false; i. true; j. false; k. false; l. false
3. a. This declaration is correct.  
 b. The const declaration should be: `const int SIZE = 100;`  
`double list[SIZE];`  
 c. This declaration should be: `int numList[10];`  
 d. This declaration is correct.  
 e. This declaration should be: `double scores[50];`
5. 0 to 49
7. -3 -1 1 3 5  
 5 -1 8 3 -1
9. 5 6 9 19 23 37
11. If array index is less than 0 or greater than `arraySize - 1`, we say that the array index is out of bounds. C++ does not check for array indices within bound.
13. a. `double heights[10] = { 5.2, 6.3, 5.8, 4.9, 5.2, 5.7, 6.7, 7.1, 5.10, 6.0 } ;`  
 or  
`double heights[] = { 5.2, 6.3, 5.8, 4.9, 5.2, 5.7, 6.7, 7.1, 5.10, 6.0 } ;`  
 b. `int weights[7] = { 120, 125, 137, 140, 150, 180, 210 } ;`  
 or  
`int weights[] = { 120, 125, 137, 140, 150, 180, 210 } ;`  
 c. `char specialSymbols[] = { '$ ', '# ', '% ', '@ ', '& ', '! ', '^ ' } ;`  
 d. `string seasons[4] = { "fall", "winter", "spring", "summer" } ;`  
 or  
`string seasons[] = { "fall", "winter", "spring", "summer" } ;`

15. `list[0] = 8, list[1] = 9, list[2] = 15, list[3] = 12, list[4] = 80, list[5] = 0, list[6] = 0, list[7] = 0, list[8] = 0, and list[9] = 0.`
17.
  - a. Correct.
  - b. Correct.
  - c. Incorrect. The size of `score` is 50, so the call should be `tryMe(score, 50);`.
  - d. Correct.
  - e. Incorrect. The array `gpa` is of type `double`, whereas the parameter `x` of `tryMe` is of type `int`. So there will be mismatch data type error.
19.
  - 1 25000.00 750.00
  - 2 36500.00 1095.00
  - 3 85000.00 2550.00
  - 4 62500.00 1875.00
  - 5 97000.00 2910.00
21. List elements: 11 16 21 26 30
23.
  - 1 3.50 10.70 235.31
  - 2 7.20 6.50 294.05
  - 3 10.50 12.00 791.68
  - 4 9.80 10.50 646.54
  - 5 6.50 8.00 326.73
25. No.
27.
  - a. Invalid; the assignment operator is not defined for C-strings.
  - b. Invalid; the relational operators are not defined for C-strings.
  - c. Invalid; the assignment operator is not defined for C-strings.
  - d. Valid
29.
  - a. `strcpy(str1, "Sunny Day");`
  - b. `length = strlen(str1);`
  - c. `strcpy(str2, name);`
  - d. `if (strcmp(str1, str2) <= 0)`  
     `cout << str1 << endl;`  
     `else`  
     `cout << str2 << endl;`
31. `int temp[3][4] = {{ 6, 8, 12, 9},`  
     `{ 7, 5, 10, 6},`  
     `{ 4, 13, 16, 20}};`
33. a. 30; b. 5; c. 6; d. row; e. column
35. a. `beta` is initialized to 0.

- b. First row of beta: 0 1 2  
Second row of beta: 1 2 3  
Third row of beta: 2 3 4
- c. First row of beta: 0 0 0  
Second row of beta: 0 1 2  
Third row of beta: 0 2 4
- d. First row of beta: 0 2 0  
Second row of beta: 2 0 2  
Third row of beta: 0 2 0

## Chapter 10

---

1. a. false; b. true; c. false; d. false; e. false
3. a. 

```
int seqOrderedSearch(const int list[], int listLength,
 int searchItem)
{
 int loc;
 bool found = false;

 for (loc = 0; loc < listLength; loc++)
 if (list[loc] >= searchItem)
 {
 found = true;
 break;
 }

 if (found)
 if (list[loc] == searchItem)
 return loc;
 else
 return -1;
 else
 return -1;
}
```
- b. i. 5 ii. 7 iii. 8 iv. 11
5. List before the first iteration: 26, 45, 17, 65, 33, 55, 12, 18  
List after the first iteration: 26, 17, 45, 33, 55, 12, 18, 65  
List after the second iteration: 17, 26, 33, 45, 12, 18, 55, 65  
List after the third iteration: 17, 26, 33, 12, 18, 45, 55, 65  
List after the fourth iteration: 17, 26, 12, 18, 33, 45, 55, 65  
List after the fifth iteration: 17, 12, 18, 26, 33, 45, 55, 65  
List after the sixth iteration: 12, 17, 18, 26, 33, 45, 55, 65  
List after the seventh iteration: 12, 17, 18, 26, 33, 45, 55, 65
7. 3

9. 10, 12, 18, 21, 25, 28, 30, 71, 32, 58, 15
11. Bubble sort: 49,995,000; selection sort: 49,995,000; insertion sort: 25,007,499
13. 26
15. To use a **vector** object in a program, the program must include the header file **vector**.
17. 1 3 5 7 9
19.
  - a. `vector<int> secretList;`
  - b. `secretList.push_back(56);`  
`secretList.push_back(28);`  
`secretList.push_back(32);`  
`secretList.push_back(96);`  
`secretList.push_back(75);`
  - c. `for (unsigned int i = 0; i < secretList.size(); i++)`  
`cout << secretList[i] << " ";`  
  
`cout << endl;`
21.
  - a. `cout << myList.front() << " " << myList.back() << endl;`
  - b. `length = myList.size();`
  - c. `for (int i = 0; i < myList.size(); i++)`  
`cout << myList[i] << " ";`  
  
`cout << endl;`

## Chapter 11

---

1. a. false; b. false; c. true; d. true; e. true; f. true; g. false
3. `checkingAccount newAcct;`  
  
`newAcct.name = "Jason Miller";`  
`newAcct.accountNum = 17328910;`  
`newAcct.balance = 24476.38;`  
`newAcct.interestRate = 0.025;`
5. `movieType newRelease;`  
  
`newRelease.name = "Summer Vacation";`  
`newRelease.director = "Tom Blair";`  
`newRelease.producer = "Rajiv Merchant";`  
`newRelease.yearReleased = 2005;`  
`newRelease.copiesInStock = 34;`

7. a. Invalid; the member `name` of `newEmployee` is a **struct**. Specify the member names to store the value "John Smith". For example:
- ```
newEmployee.name.first = "John";
newEmployee.name.last = "Smith";
```
- b. Invalid; the member `name` of `newEmployee` is a **struct**. There are no aggregate output operations on a **struct**. A correct statement is:
- ```
cout << newEmployee.name.first << " "
 << newEmployee.name.last << endl;
```
- c. Valid
- d. Valid
- e. Invalid; `employees` is an array. There are no aggregate assignment operations on arrays.
9. `partsType inventory [100];`
11. `void` `getData` (`partsType& pType`)
- ```
{
    for (int j = 0; j < length; j++)
    {
        cin >> pType.partName;
        cin >> pType.partNum;
        cin >> pType.price;
        cin >> pType.quantitiesInStock;
    }
}
```
- ```
for (int j = 0; j < 100; j++)
 getData(inventory [j]);
```

## Chapter 12

---

1. a. false; b. false; c. true; d. false; e. false
3. a. 6; b. 2; c. 2;
- d. `void` `xClass::func()`
- ```
{
    u = 10;
    w = 15.3;
}
```
- e. `void` `xClass::print()`
- ```
{
 cout << u << " " << w << endl;
}
```

- ```

f. xClass::xClass()
{
    u = 0;
    w = 0;
}

g. x.print();
h. xClass t(20, 35.0);
5. a. int testClass::sum()
    {
        return x + y;
    }

    void testClass::print() const
    {
        cout << "x = " << x << ", y = " << y << endl;
    }

testClass::testClass()
{
    x = 0;
    y = 0;
}

testClass::testClass(int a, int b)
{
    x = a;
    y = b;
}

```
- b. One possible solution. (We assume that the name of the header file containing the definition of the `class` `testClass` is `Exercise5Ch12.h`.)
- ```

#include <iostream>
#include "Exercise5Ch12.h"

int main()
{
 testClass one;
 testClass two(4, 5);

 one.print();
 two.print();

 return 0;
}

```
7. a. `personType` student("Buddy", "Arora");  
 b. student.print();  
 c. student.setName("Susan", "Gilbert");

9. A constructor is a member of a class, and it executes automatically when a class object is instantiated and a call to the constructor is specified in the object declaration. A constructor is included in a class so that the objects are properly initialized when they are declared.
11. A destructor is a member of a class, and if it is included in a class, it executes automatically when a class object goes out of scope. Its main purpose is to deallocate the dynamic memory created by an object.
13.
  - a. `myClass::count = 0;`
  - b. `myClass.incrementCount();`
  - c. `myClass.printCount();`
  - d. `int myClass::count = 0;`

```

void myClass::setX(int a)
{
 x = a;
}

void myClass::printX() const
{
 cout << x;
}

void myClass::printCount()
{
 cout << count;
}

void myClass::incrementCount()
{
 count++;
}

myClass::myClass(int a)
{
 x = a;
}

```

- e. `myClass myObject1(5);`
- f. `myClass myObject2(7);`
- g. The statements in Lines 1 and 2 are valid.

The statement in Line 3 should be: `myClass::printCount();`.

The statement in Line 4 is invalid because the member function `printX` is not a `static` member of the class, and so cannot be called by using the name of class.

The statement in Line 5 is invalid because `count` is a `private static` member variable of the class.

- h. 5
- 2
- 2
- 3
- 14
- 3
- 3

## Chapter 13

---

1. a. true; b. true; c. true
3. Some of the member variables that can be added to the `class employeeType` are: `department`, `salary`, `employeeCategory` (such as supervisor and president), and `employeeID`. Some of the member functions are: `setInfo`, `getSalary`, `getEmployeeCategory`, and `setSalary`.
5. The private members of the object `newCylinder` are `radius` and `height`.
7. a. The statement:
 

```
class bClass public aClass
```

 should be:
 

```
class bClass: public aClass
```

 Also missing semicolon after `}`.
- b. Missing semicolon after the statement `cClass(int)`, and missing semicolon after `}`.
9. a. `yClass::yClass()`

```
{
 a = 0;
 b = 0;
}
```
- b. `xClass::xClass()`

```
{
 z = 0;
}
```
- c. `void yClass::two(int u, int v)`

```
{
 a = u;
 b = v;
}
```
11. The `protected` members of a base class can be directly accessed by the member functions of the derived class, but they cannot be directly accessed in a program that uses that class. The `public` members of a class can be directly accessed by the member functions of any derived class as well as in a program that uses that class.

13. The members `setX`, `print`, `y`, and `setY` are **protected** members in **class** `third`. The **private** member `x` of **class** `first` is hidden in **class** `third`, and it can be accessed in **class** `third` only through the **protected** and **public** members of **class** `first`.
15. Because the `memberAccessSpecifier` is not specified, it is a private inheritance. Therefore, all of the members of the **class** `first` become **private** members in **class** `fifth`.
17. a. 

```
void two::setData(int a, int b, int c)
{
 one::setData(a, b);
 z = c;
}
```

 b. 

```
void two::print() const
{
 one::print();
 cout << z << endl;
}
```
19. In base: `x = 7`  
 In derived: `x = 3, y = 8; x + y = 11`  
 \*\*\*\*7  
 ####11

## Chapter 14

---

1. a. false; b. false; c. false; d. true; e. true; f. true; g. false; h. false
3. The operator `*` is used to declare a pointer variable and to access the memory space to which a pointer variable points.
5. 

```
98 98
98 98
```
7. b and c
9. 

```
78 78
```
11. 

```
27 35
73 27
36 36
```
13. 

```
4 4 5 7 10 14 19 25 32 40
```
15. The operator **delete** deallocates the memory space to which a pointer points.
17. a. `num = new int[10];`  
 b. 

```
for (int j = 0; j < 10; j++)
 cin >> num[j];
```

  
 c. `delete [] num;`
19. In a shallow copy of data, two or more pointers point to the same memory space. In a deep copy of data, each pointer has its own copy of the data.

21. `Array p: 5 7 11 17 25`  
`Array q: 25 17 11 7 5`
23. The copy constructor makes a copy of the actual variable.
25. Classes with pointer data members should include the destructor, overload the assignment operator, and explicitly provide the copy constructor by including it in the class definition and providing its definition.
27. `ClassA x: 4`  
  
`ClassA x: 6`  
`ClassB y: 10`
29. Yes.
31. a. Because `employeeType` is an abstract class, you cannot instantiate an object of this class. Therefore, this statement is illegal.  
b. This statement is legal.  
c. This statement is legal.

## Chapter 15

---

1. a. false; b. true; c. true; d. false; e. false; f. true; g. false; h. true; i. false; j. true; k. false
3. A `friend` function is a nonmember of a class, whereas a member function is a member of a class.
5. Because the left operand of `<<` is a stream object, which is not of the type `mystery`.
7. When the class has pointer data members.
9. a. `friend strange operator+(const strange&, const strange&);`  
b. `friend bool operator==(const strange&, const strange&);`  
c. `friend strange operator++(strange&, int);`
11. In Line 2, the word `friend` before the word `bool` is missing. The correct statement is:  
  
`friend bool operator<=(mystery, mystery); //Line 2`
13. Because the leftmost operand of `<<` is not an object of the class type for which `<<` is overloaded.
15. A reference to an object of the `class istream`.
17. Suppose that a class, say `temp`, overloads the pre- and post-increment operator `++`, and `tempObj` is an object of the `class temp`. Then, the statement `++tempObj;` is compiled as `tempObj.operator++();`, and the statement `tempObj++;` is compiled as `tempObj.operator++(0);`. The dummy parameter distinguishes between the pre- and post-increment operator functions. Similar conventions for the pre- and post-decrement operators.
19. None.

21. One.
23. Answer to this question is available at the Web site accompanying this book.
25. Error in Line 4. A template instantiation can be for only a built-in type or a user-defined type. The word “**type**” between the angular brackets must be replaced either with a built-in type or a user-defined type.
27. a. 12 b. Sunny Day
29. 

```
template <class Type>
void swap(Type &x, Type &y)
{
 Type temp;
 temp = x;
 x = y;
 y = temp;
}
```

## Chapter 16

---

1. a. false; b. true; c. true; d. false
3. The program will terminate with an error message.
5. If an exception is thrown in a **try** block, the remaining statements in that **try** block are ignored. The program searches the **catch** blocks in the order that they appear after the **try** block and looks for an appropriate exception handler. If the type of thrown exception matches the parameter type in one of the **catch** blocks, the code of that **catch** block executes, and the remaining **catch** blocks after this **catch** block are ignored.
7. a. Leaving the try block.  
b. Current balance: 975  
Balance must be greater than 1000.00  
c. Current balance: -2000  
Balance must be greater than 1000.00
9. a. Entering the try block.  
Exception: Lower limit violation.  
After the catch block  
b. Entering the try block.  
Exception: 0  
After the catch block  
c. Entering the try block.  
Exiting the try block.  
After the catch block  
d. Entering the try block.  
Exception: 0  
After the catch block
11. A **throw** statement.

13. (Assume that the definition of the `class tornadoException` is in the header file `tornadoException.h`.)

```
#include <iostream>
#include "tornadoException.h"

using namespace std;

int main()
{
 int miles;

 try
 {
 cout << "Enter the miles: ";
 cin >> miles;
 cout << endl;

 if (miles < 5)
 throw tornadoException();
 else
 throw tornadoException(miles);
 }
 catch (tornadoException tE)
 {
 cout << tE.what() << endl;
 }

 return 0;
}
```

15. A function specifies the exceptions it throws in its heading using the `throw` clause.

## Chapter 17

---

1. a. true; b. true; c. false; d. false; e. false
3. The case in which the solution is defined in terms of smaller versions of itself.
5. A function that calls another function and eventually results in the original function call is said to be indirectly recursive.
7.
  - a. The statements in Lines 2 and 3.
  - b. The statements in Lines 4 and 5.
  - c. Any nonnegative integer.
  - d. It is a valid call. The value of `mystery(0)` is 0.
  - e. It is a valid call. The value of `mystery(5)` is 15.
  - f. It is an invalid call. It will result in infinite recursion.

9. a. 2    b. 7    c. 3    d. -85  
       5                6  
       8
11. a. It does not produce any output.  
       b. 5 6 7 8 9  
       c. It does not produce any output.  
       d. It does not produce any output.
13. a. 2; b. 3; c. 5; d. 21
- 15.

$$\text{multiply}(m, n) = \begin{cases} 0 & \text{if } n = 0 \\ m & \text{if } n = 1 \\ m + \text{multiply}(m, n - 1) & \text{otherwise} \end{cases}$$

The base cases are when  $n = 0$  or  $n = 1$ . The general case is specified by the option otherwise.

## Chapter 18

---

1. a. false; b. false; c. false; d. false
3. **NULL**
5. Before deletion, the link field of the third node stores the address of the fourth node. After deletion, the link field of the third node will store the address of the next node, which is the old fifth node. If there was no fifth node, then after deletion, the link field will store the value **NULL**. Therefore, after deleting the fourth node, the link field of the third node is changed. So a pointer to the third node is needed.
7. a. true; b. true; c. false; d. false; e. true
9. a. **A = A->link;**  
       b. **list = A->link->link;**  
       c. **B = B->link->link;**  
       d. **list = NULL;**  
       e. **B->link->info = 35;**  
       f. **newNode = new nodeType;**  
           **newNode->info = 10;**  
           **newNode->link = A->link;**  
           **A->link = newNode;**  
       g. **p = A->link;**  
           **A->link = p->link;**  
           **delete p;**
11. This is an invalid code. The statement **s->info = B;** is invalid because **B** is a pointer and **s->info** is an **int**.

13. 10 18 13
15. `nodeType head, p, q;`

```

head = new nodeType;
head->info = 72;
head->link = NULL;
p = new nodeType;
p->info = 43;
p->link = head;
head = p;
p = head->link;
q = new nodeType;
q->info = 8;
q->link = NULL;
p->link = q;
q = new nodeType;
q->info = 12;
q->link = p;
head->link = q;

p = head;
while (p != NULL)
{
 cout << p->info << " ";
 p = p->link;
}
cout << endl;

```

The output of this code is: 43 12 72 8

17. Item to be deleted is not in the list.  
18 38 2 15 45 25
19. Answer to this question is available at the Web site accompanying this book.
21. Answer to this question is available at the Web site accompanying this book.

## Chapter 19

---

1. The two basic operations on a stack are push, to add an element to a stack, and pop, to remove an element from a stack.
3. `x = 3`  
`y = 9`  
7  
13  
4  
7

5. a. 26; b. 45; c. 8; d. 29
7. a.  $A * B + C$   
b.  $(A + B) * (C - D)$   
c.  $(A - B - C) * D$
9. 10 20 30 40 50
11. If the stack is nonempty, the statement `stack.top();` returns the top element of the stack, and the statement `stack.pop();` removes the top element of the stack.
13. 

```
template <class elemType>
elemType second(stackType<elemType> stack)
{
 elemType temp1, temp2;

 if (stack.isEmptyStack())
 {
 cout << "Stack is empty." << endl;
 exit(0); //terminate the program
 }

 temp1 = stack.top();
 stack.pop();

 if (stack.isEmptyStack())
 {
 cout << "Stack has only one element." << endl;
 exit(0); //terminate the program
 }

 temp2 = stack.top();
 stack.push(temp1);

 return temp2;
}
```
15. Queue Element = 0  
Queue Element = 14  
Queue Element = 22  
Sorry, the queue is empty  
Sorry, the queue is empty  
Stack Element = 32  
Stack Elements: 64 28 0  
Queue Elements: 30
17. a. `queueFront = 50; queueRear = 0.`  
b. `queueFront = 51; queueRear = 99.`
19. a. `queueFront = 25; queueRear = 76.`  
b. `queueFront = 26; queueRear = 75.`
21. 51

23. 

```
template <class Type>
void reverseStack(stackType<Type> &s)
{
 linkedQueueType<Type> q;
 Type elem;

 while (!s.isEmptyStack())
 {
 elem = s.top();
 s.pop();
 q.addQueue(elem);
 }

 while (!q.isEmptyQueue())
 {
 elem = q.front();
 q.deleteQueue();
 s.push(elem);
 }
}
```
25. 

```
template <class Type>
int queueType<Type>::queueCount()
{
 return count;
}
```
27. Answer to this question is available at the Web site accompanying this book.
29. Answer to this question is available at the Web site accompanying this book.

*This page intentionally left blank*



# INDEX

**Note:** Page numbers in boldface indicate key terms.

& (ampersand), 369, 812  
\* (asterisk), 794, 796, 812  
\ (backslash), 69, 73  
, (comma), 85  
{ } (curly braces), 78, 85, 212  
" (double quotes), 458, 510, 513  
= (equal sign), 1153  
/ (forward slash), 32  
- (minus sign), 654  
( ) (parentheses), 187, 327, 801  
. (period), 129, 655  
+ (plus sign), 654  
# (pound sign), 145, 257, 880, 1154  
; (semicolon), 85, 651, 836  
[ ] (square brackets), 495  
~ (tilde), 677  
\_ (underscore), 33, 34, 86, 453

## A

abs function, 321, 325  
abstract classes  
    described, **836**  
    overview, 835–843  
abstract data types. *See* ADTs (abstract data types)  
abstraction, 678. *See also* abstract classes  
accessor functions, **664**, 665–669  
action statements, **189**  
actual parameter lists, 327, 363  
addFirst function, 381

addQueue function, 1166, 1168–1170, 1175, 1179–1182, 1197  
address of operator, **795–796**, 844–846  
addressOfX function, 845, 846  
ADTs (abstract data types)  
    described, **678**  
    linked lists and, 1037–1050, 1058–1059, 1072–1074  
    OOP and, relationship of, 757  
    overview, 678–680  
    queues and, 1165, 1167, 1185, 1188, 1192, 1196  
    structS and, 681  
    templates and, 927  
aggregate operations, **497**  
aggregation. *See* composition  
Aiken, Howard, 3  
algebra, 320  
algorithm(s)  
    arrays and, 507–510  
    control structures and, 287–288  
    described, **12**  
    generic, **1290**  
    linked lists and, 1059–1060, 1070, 1077  
    modifying, 1291  
    mutating, **1291**  
    non-modifying, 1290  
    numeric, 1292  
    problem analysis-coding-execution cycle and, 12–20  
    stacks and, 1154–1156, 1161–1165  
    STL and, 1289–1292

- algorithm header file, 1290, 1294
- ampersand (&), 369, 812
- analog signals, **6**
- anonymous data types, **442–443**
- ANSI (American National Standard Institute), 22, 76. *See also* ANSI/ISO Standard C++, 434, 530
- ANSI/ISO Standard C++, 434, 530
  - namespaces and, 452–453, 454
  - naming conventions for header files, 1244–1245
  - overview, 22
  - strings and, 49, 458, 530
- append function, 462
- Apple Computer, 3
- application programs, **6**. *See also* programs
- arguments. *See also* parameters
  - described, **125**
  - overview, 127
- arithmetic expressions, **40**
- arithmetic operators
  - described, **40**
  - overview, 39–44
- array(s). *See also* array indexes; *specific types*
  - applications of, overview of, 564–609
  - base addresses, **501**, 502–503
  - of class objects, 675–677
  - components, accessing, 488–490, 520
  - constant, as formal parameters, 498–500
  - declarations, 495–496, 507
  - described, **487**
  - finding the sum/average of, 492
  - implementation of stacks as, 1120–1138
  - in bounds, **495**
  - initialization, 491, 495–496
  - largest elements in, 492–493, 996–999
  - out of bounds, **495**
  - overview, 487–507
  - parallel arrays, **537**, 538
  - as parameters to functions, 497–498
  - partial initialization, **496**
  - passed by reference, 497–498
  - printing, 492, 525
  - processing, 491–494, 496–497
  - queues and, 1168–1174
  - reading data into, 492
  - searching, for specific items, 507–510
  - of strings, 530–531
  - StructS and, 619–624
- array index operator, 916–924
- array indexes
  - accessing array components and, 530
  - c-Strings and, 514
  - described, **488**
  - integral data type and, 506
  - out of bounds, 494–495
  - stacks and, 1122
- array subscript operator, **459**, 488
- ASCII (American Standard Code for Information Interchange)
  - characters, comparing, 179–180
  - collating sequence, 179, 180–181
  - c-Strings and, 510, 512
  - data types and, 37–38
  - described, **7**
  - functions and, 323
  - input/output (I/O) and, 120
  - overview, 7–8, 1219–1220
  - recursion and, 1007
  - type conversion and, 49
- assemblers, **9**
- assembly language, 8–9
- assert function, 223–231, 952, 955–956
- assert statement, 1046
- assert.h (cassert) header file, 1247
- assignment operator, 56, 209–211, 656–657, 820–821
  - linked lists and, 1044, 1049
  - overloading, 887–895
  - stacks and, 1129–1130, 1147–1149
- assignment statements, 489, 657
  - compound, **89–90**
  - enumeration types and, 436
  - putting data into variables with, 53–56
  - records and, 616–617
  - simple, **89–90**
  - types of, 89–97
- associativity, **43**, 56, 185
- asterisk (\*), 794, 796, 812
- at function, 462, 582
- Augusta, Ada, 2

**B**

Babbage, Charles, 2  
 back, of queues, **1165**, 1166  
 back function, 582, 1046, 1166, 1175, 1179–1182  
 backslash (`\`), 69, 73  
 bad\_alloc exception, 964, 805, 965–967  
 base addresses, **501**, 502–503  
 base case, 992  
 base classes. *See also* inheritance  
   constructors and, 734–741  
   described, **725**  
   member functions of, redefining, 727–734  
   overview, 726–627  
 begin function, 1046–1047, 1266–1267  
 binary code, **6**  
 binary digits, **6**. *See also* binary numbers  
 binary files  
   described, **1230**  
   working with, 1230–1234  
 binary numbers  
   described, **6**  
   converting, to other number systems, 1007–1014, 1225–1230  
   overview, 6–7, 1225  
 binary operators  
   described, **40**  
   overloading, 876–882  
 binary search algorithm  
   described, **576**  
   overview, 576–580  
   performance of, 580  
 binary\_search function, 1297–1299  
 bits, **6–7**  
 blanks, use of, 85, 87, 120  
 blocks  
   described, **195**  
   nested, **383**  
 bool data type, 36, 37, 188  
 bottom-up design, **20**  
 boxType class, 730–738, 739  
 break statement  
   overview, 289–291  
   switch structures and, 216, 217–220

bubble sort algorithm  
   described, **565**  
   overview, 565–569  
 bugs. *See also* debugging; errors  
   avoiding, 203–209, 221–223, 296–299  
   control structures and, 203–209, 221–223, 296–299  
   patches and, 296–299  
 Build command, **12**, 686  
 buildListBackward function, 1036–1037, 1038  
 buildListForward function, 1035–1036, 1038  
 bytes, **6–7**

**C**

cable-company program, 225–231, 343–349  
 calculatePay function, 837  
 callPrint function, 829–830, 834  
 candy-machine program, 697–710  
 case sensitivity, 34  
 cast operator, **47**  
 casting (type conversion), **47**, 48–49, 671  
 ceil function, 321  
 central processing units. *See* CPUs (central processing units)  
 change-making program, 94–97  
 char data type, 36–38, 121, 537  
   c-Strings and, 510, 511  
   enumeration types and, 438–439  
   functions and, 364  
   pointers and, 795  
   records and, 615  
   templates and, 925, 927  
 character arrays (c-Strings)  
   arrays of strings and, 530–531  
   described, **510**  
   execution time and, 516  
   operator overloading and, 918–824  
   overview, 510–537  
   reading and writing strings with, 513  
   specifying I/O files and, 516  
   string input and, 514–515  
   string output and, 515–516

- character sets, 1219–1221. *See also* ASCII (American Standard Code for Information Interchange); EBCDIC (Extended Binary Coded Decimal Interchange Code)
- characters, comparing, 179–180. *See also* character sets
- charitable-donations program, 156–161
- cin identifier, 33, 76, 119–124, 744
  - get function and, 127–128
  - ignore function and, 128–130
  - input/output (I/O) and, 118–119
- circle class, 725, 726, 835–836
- circular linked lists, **1083**, 1084
- class(es). *See also* classes (listed by name); inheritance
  - abstract, 835, **836**, 837–843
  - built-in operations on, 656
  - clients of, **663**
  - creating, 967–977
  - data abstraction and, 678–680
  - identifying, 757–758
  - linked lists and, 1037–1038
  - objects (instances), **654**
  - overview, 133, 849–722
  - precautions regarding, 674–675
  - scope, 657
  - templates, **925**, 927–935
- class diagrams, 654, 680, 689–690, 728–731, 740–741, 752, 754
  - linked lists and, 1040, 1043, 1050, 1059, 1074
  - queues and, 1186–1187, 1190, 1193
  - stacks and, 1119, 1121–1122, 1140
- class keyword, 651
- classes (listed by name). *See also* clockType class
  - boxType class, 730–738, 739
  - circle class, 725, 726, 835–836
  - customerType class, 1185–1188
  - cylinderType class, 758
  - dateType class, 751–752
  - deque class, 1276–1279
  - divisionByZero class, 969, 970–972, 974
  - doublyLinkedList class, 1074
  - dummyClass class, 675
  - ellipse class, 835–836
  - employeeType class, 837–840
  - extClockType class, 724
  - fullTimeEmployee class, 837, 840–841
  - linkedListIterator class, 1039–1041
  - linkedListType class, 1037–1044, 1048–1049, 1057–1059, 1067, 1150–1151, 1162, 1182
  - linkedQueueType class, 1181–1182
  - linkedStackType class, 1140–1141, 1147–1149
  - list class, 1279–1280
  - listType class, 680, 927–929
  - newString class, 918–824, 930, 952
  - orderedLinkedList class, 1043–1044, 1058
  - orderedListType class, 1066
  - partTimeEmployee class, 724, 740–742, 837, 841–843
  - personalInfo class, 753–755
  - personType class, 689–690, 724, 740, 742, 750–751, 837, 867–870
  - queueADT class, 1167, 1172, 1177–1178
  - queueType class, 1196
  - rectangle class, 725, 835–837
  - rectangleType class, 728–731, 734–736, 738, 874–888, 895–902
  - serverListType class, 1192–1194
  - serverType class, 1188–1191
  - shape class, 725, 835–837
  - stackADT class, 1119, 1120, 1139–1140, 1142
  - stackType class, 1120–1123, 1129–1134
  - testAddress class, 845, 846
  - unorderedLinkedList class, 1043–1044, 1049–1050, 1090, 1150–1151
  - unorderedListedListType class, 1182–1183
  - vector class, 1260–1269
  - videoListType class, 1090–1092, 1095–1097
  - videoType class, 1087–1089, 1092–1094
  - waitingCustomerQueueType class, 1196–1197
- classifying-numbers program, 281–284
- clear function, 135–136, 462, 463, 582
- clients, of classes, **663**
- clockType class, 651–652, 654–663, 696, 862–863, 902–810
  - arrays and, 676–677

- constructors and, 669–675
- data abstraction and, 678
- declaring, 667–669
- destructors and, 677–678
- executable code and, 685–690
- information hiding and, 681–685
- inheritance and, 724
- member functions and, 664–669
- clockType.h header file, 682, 685
- cmath header file, 456, 458
- code
  - detection program, 534–539
  - executable, 685–690
  - source, **10**, 77
- collating sequence, **38**
- column(s)
  - largest element in, 526
  - processing, **523**
  - sum by, 526
- comma (,), 85
- comments, 32, 87
- common
  - input, **118**
  - output, **118**
- compare function, 462
- compareThree function, 331, 332–333
- compilers, 22, 490, 686, 830. *See also*
  - compile-time errors
  - described, **9**
  - functions and, 340
  - inheritance and, 743–744
  - namespaces and, 452
- compile-time binding, **830**
- compile-time errors. *See also* errors
  - constructors and, 671, 673
  - inheritance and, 744
  - linked lists and, 1094
- complex number(s)
  - described, **911**
  - program, 911–916
- composition
  - described, **724**
  - overview, 750–755
- computer(s)
  - history of, 2–3
  - language of, 6–8
  - overview, 1–26
  - systems, elements of, 3–6
- computer programs. *See* programs
- conditional operator, **211**
- const keyword, 51, 658, 659
- constant functions, **664**
- constructor(s)
  - arrays of, 675–677
  - composition and, 754–755
  - containers and, 1280
  - conversion, **922**
  - default, **669**, 671, 674, 738, 1044, 1075, 1141
  - inheritance and, 734–741
  - invoking, 671–673
  - linked lists and, 1044, 1048, 1075
  - overview, 669–670
  - parameters and, 671–675
  - precautions regarding, 674–675
  - properties of, 669
  - queues and, 1176–1177
  - stacks and, 1128–1129, 1141, 1147
- container(s)
  - adapters, **1285**, 1286–1289
  - member functions common to, 1269–1272
  - types, 1260–1284
  - vector, 1260–1269
- continue statement, 289–291
- control structure(s). *See also* repetition
  - structures; selection structures; sequence structures
  - bugs and, 203–209, 221–223, 296–300
  - indentation and, 211–212
  - nested, 291–296
  - patches and, 296–299
  - short-circuit evaluation and, 199–200
  - terminating programs and, 223–231
- copy algorithm, 1272–76
- copy constructor, **821**, 822–828, 1048, 1129
- copy function, 1272–1276
- copyList function, 1044, 1047–1048, 1075
- copyStack function, 1128, 1146–1147
- cos function, 321
- counter-controlled while loops, **252**, 253–255

- cout identifier, 33, 76, 744
  - debugging with, 149–152
  - input/output (I/O) and, 118–119, 515
- .cpp filename extension, 682
- CPUs (central processing units), 3, **4**, 5
- cstdlib header file, 1258
- c-Strings (character arrays)
  - arrays of strings and, 530–531
  - described, **510**
  - execution time and, 516
  - operator overloading and, 918–824
  - overview, 510–537
  - reading and writing strings with, 513
  - specifying I/O files and, 516
  - string input and, 514–515
  - string output and, 515–516
- cctype.h (cctype) header file, 1248–1249
- curly braces ({}), 78, 85, 212
- customerType class, 1185–1188
- cylinders, 757–758
- cylinderType class, 758

## D

- data
  - abstraction, 678–681
  - formatted, **1230**
  - raw, **1230**
- data types. *See also specific types*
  - anonymous, **442–443**
  - control structures and, 178–179
  - described, **35**
  - functions and, 324, 326, 328
  - overview, 35–39
  - simple, **53**, 433–483, 486
  - structured, **486**
- data-comparison program, 404–414
- dateType class, 751–752
- debugging. *See also bugs; errors*
  - control structures and, 212–215, 299–300
  - cout statements and, 149–152
  - functions and, 392–394
  - input/output (I/O) and, 149–152
  - overview, 80–84
  - pseudocode and, 212–215
- decimal expressions, **44**
- decimal numbers
  - converting binary numbers to, 1007–1011, 1227–1228
  - converting, to other number systems, 1011–1014, 1225–1227
  - described, **7**
  - overview, 1225
- decision makers
  - described, **189**
  - overview, 249
- declaration statements, **78**
- decrement operators, **65**, 66–67, 808
- decToBin function, 1012–1014
- deep copy, 816, **817**, 818
- delete operator, 804, 805–807
- deleteNode function, 1044, 1049, 1052, 1058, 1065–1066, 1082–1083
- deleteQueue function, 1166, 1168–1169, 1170, 1175–1176, 1179–1182, 1197
- deque, use of the term, **1276**
- deque class, 1276–1279
- deque container, 1276–1279
- dereferencing operator, **796–801**, 1039
- derived classes. *See also inheritance*
  - constructors and, 734–741
  - default parameters and, 738
  - described, **724–725**
  - destructors and, 741–743
  - overriding functions and, 731–732
  - overview, 726–727
  - protected members in, accessing, 747–750
- destroyList function, 822, 824, 1044–1045, 1048
- destructor(s)
  - linked lists and, 1048
  - overview, 677–678
  - pointers and, 818–819
  - queues and, 1176–1177
  - stacks and, 1128–1129, 1147
  - virtual, **835**
- dice-rolling program, 336–337
- digital signals, **6**
- directly recursive, use of the term, **995**
- discardExp function, 1154, 1158
- “divide and conquer” technique, 477

- divisibility test, 287–288
- divisionByZero class, 969, 970–972, 974
- divisor, use of the term, **287**
- do keyword, 285
- do...while loops
  - exception handling and, 979
  - functions and, 337, 390
  - overview, 284–289
- documentation, overview of, 87
- doDivision function, 972, 976
- domains, **679**
- dot notation, 132, **133**
- double data type, 121, 498, 808
  - functions and, 328, 329
  - templates and, 925, 927
- double quotes ("), 458, 510, 513
- doubleFirst function, 381
- doublyLinkedList class, 1074
- draw function, 836
- driver programs, **392**, 393–394
- dummyClass class, 675
- dynamic arrays, **490**, 809–816
- dynamic variables, overview, 803, **804**, 805–807

## E

- early binding. *See* compile-time binding
- EBCDIC (Extended Binary Coded Decimal Interchange Code), 8, 37, 510, 1220–1221
- election-results program, 585–601
- ellipse class, 835–836
- employeeType class, 837–840
- empty function, 582, 462, 463, 1286, 1288
- end function, 1266–1267
- enumeration types, 35, 506
  - anonymous data types and, 442–443
  - described, **434**, 442
  - functions and, 440–442
  - input/output of, 438–440
  - loops and, 438
  - operations on, 437
  - overview, 434–444
  - two-dimensional arrays and, 521–524
- enumerators, **435**

- eof function, 263–264
- EOF-controlled while loops, **263**, 264–268, 294–295
- equal sign (=), 1153
- equality operator, 209–211
- equalTime function, 651, 652–653, 655, 659, 663, 664
- erase function, 462, 463
- errors. *See also* bugs; compile-time errors; debugging; syntax errors
  - identifiers and, 34
  - linked lists and, 1053, 1065
  - logging, 980
  - logic, 149–152, 964. *See also* errors
  - semantic, 194
  - stacks and, 1128, 1158
- escape sequences, 69–74
- evaluateExpression function, 1154–1156, 1158
- evaluateOpr function, 1154, 1156–1158
- example function, 499
- exception handling
  - bad\_alloc exception and, 964, 805, 965–967
  - C++ mechanisms of, 956–963
  - exception classes and, 963–977
  - overview, 952–989
  - within a program, 952–956
  - rethrowing exceptions, 973–977
  - stack unwinding and, 980–983
  - techniques, 978–980
  - throwing exceptions and, 957–958, 967–968, 973–977
  - try/catch blocks and, 956–965, 967, 973–977, 979–983
- .exe filename extension, 77, 78
- executable
  - code, overview of, 685–690
  - statements, **78**
- exp function, 321
- expressions
  - overview, 44–46
  - saving, 56–57
  - using the value of, 56–57
- extClockType class, 724
- extern keyword, 386
- extraction operator, 119–124, 129, 148

## F

- fabs function, 321
- fail state, **134**, 208
- Fibonacci numbers
  - described, **269**, 270–273, 279–280
  - nth, **270**, 999–1000
  - recursion and, 999–1003
- Fibonacci sequences, **270**
- FIFO (First In First Out) data structure, 1166
- file(s)
  - described, **153**
  - I/O, overview of, 152–165
  - name extensions, 77–78, 682, 1244
  - opening, **153**
  - stream variables, **153**
- fill function, 815, 1292–1294
- fill\_n function, 1292–1294
- find function, 462, 465–467, 1294–1295
- find\_if function, 1294–1295
- first, use of the term, **1024**
- fixed manipulator, 138–139, 140–141
- flag variables, **260**
- flag-controlled while loops, **259**, 260, 268
- float.h (cfloat) header file, 1249–1250
- floating-point data types, 35, **38**, 39, 44, 200–201
- floor function, 321, 322
- for keyword, 274
- for loops
  - arrays and, 493, 524, 525, 526, 810, 813
  - constructors and, 828
  - enumeration types and, 438
  - exception handling and, 966–967
  - functions and, 365, 383
  - nested, 292–293
  - operator overloading and, 893
  - overview, 273–280
  - vectors and, 585, 583
- formal parameter lists, 326, 362, **395**
- formatted data, use of the term, **1230**
- forward slash (/), 32
- friend functions, **870**, 871–873, 901
- friend keyword, 870
- front, of queues, **1165**
- front function, 582, 1046, 1077, 1166, 1174–1175, 1179–1182, 1288
- fstream header file, 745
- fullTimeEmployee class, 837, 840–841
- funcArrayAsParam function, 498
- funcExp function, 397
- function(s). *See also* functions (listed by name)
  - accessor, **664**, 665–669
  - body, **325**
  - calls, **125**, 326, 340, 363
  - classes and, 658, 659–669
  - debugging and, 392–394
  - with default parameters, 396–399
  - definition of, **325**, 362, 877, 881, 884, 896–899
  - described, **31**
  - enumeration types and, 440–442
  - flow of execution and, 340–341
  - friend, **870**, 871–873, 901
  - headers, **325**
  - identifiers and, 382–386
  - memory allocation and, 372–382
  - nesting, 382
  - overloading, **395**, 396, 756, 924, 1194
  - passing two-dimensional arrays as parameters to, 527–530
  - predefined, 320–323
  - prototypes, **331**, 332–333, 397, 398, 877, 881, 884, 896–899
  - pure virtual, 835, **836**, 837–843
  - records and, 618–619
  - return types, 812
  - signature of, **395**
  - static, 691, 696
  - stubs, **394**
  - templates, **925**, 926–927
- functions (listed by name). *See also* functions; main function
  - abs function, 321, 325
  - addFirst function, 381
  - addQueue function, 1166, 1168–1170, 1175, 1179–1182, 1197
  - addressOfX function, 845, 846
  - append function, 462
  - assert function, 223–231, 952, 955–956
  - at function, 462, 582
  - back function, 582, 1046, 1166, 1175, 1179–1182

- begin function, 1046–1047, 1266–1267
- binary\_search function, 1297–1299
- buildListBackward function, 1036–1037, 1038
- buildListForward function, 1035–1036, 1038
- calculatePay function, 837
- callPrint function, 829–830, 834
- ceil function, 321
- clear function, 135–136, 462, 463, 582
- compare function, 462
- compareThree function, 331, 332–333
- copy function, 1272–1276
- copyList function, 1044, 1047–1048, 1075
- copyStack function, 1128, 1146–1147
- cos function, 321
- decToBin function, 1012–1014
- deleteNode function, 1044, 1049, 1052, 1058, 1065–1066, 1082–1083
- deleteQueue function, 1166, 1168–1169, 1170, 1175–1176, 1179–1182, 1197
- destroyList function, 822, 824, 1044–1045, 1048
- discardExp function, 1154, 1158
- doDivision function, 972, 976
- doubleFirst function, 381
- draw function, 836
- empty function, 582, 462, 463, 1286, 1288
- end function, 1266–1267
- eof function, 263–264
- equalTime function, 651, 652–653, 655, 659, 663, 664
- erase function, 462, 463
- evaluateExpression function, 1154–1156, 1158
- evaluateOpr function, 1154, 1156–1158
- example function, 499
- exp function, 321
- fabs function, 321
- fill function, 815, 1292–1294
- fill\_n function, 1292–1294
- find function, 462, 465–467, 1294–1295
- find\_if function, 1294–1295
- floor function, 321, 322
- front function, 582, 1046, 1077, 1166, 1174–1175, 1179–1182, 1288
- funcArrayAsParam function, 498
- funcExp function, 397
- get function, 127–128, 514, 744
- getFirstName function, 868
- getLastName function, 868
- getLength function, 733
- getLine function, 515
- getNumberOfBusyServers function, 1194
- getScore function, 369–370
- getTime function, 651, 652, 653, 659
- getWaitingTime function, 1188
- getWidth function, 733
- ignore function, 128–130, 744
- incrementHours function, 651, 652, 664
- incrementMinutes function, 651, 652, 662, 664
- initializeList function, 1045, 1076
- initializeQueue function, 1166, 1171, 1174, 1179, 1181
- initializeStack function, 1118, 1123–1124
- insert function, 462, 467–468, 1063, 1079–1080
- insertFirst function, 1038, 1044, 1049, 1051, 1058, 1064–1065
- insertionSort function, 575–576
- insertLast function, 1038, 1044, 1049, 1058, 1064–1065
- isEmptyList function, 1044
- isEmptyQueue function, 1166, 1197
- isEmptyStack function, 1118, 1124, 1141–1142
- isFullQueue function, 1166, 1179
- isFullStack function, 1118, 1124, 1140–1142
- islower function, 322
- isNumPalindrome function, 338–340
- isupper function, 322
- larger function, 328–331, 332, 341–343, 925–927
- largerChar function, 396
- largerInt function, 396
- largestInRows function, 528–529
- length function, 462, 463, 464–465
- max\_size function, 582

functions (listed by name) (*Continued*)

- peek function, 130–132
- poolCapacity function, 394
- poolFillTime function, 394
- pop function, 1117–1118, 1126–1128, 1144–1146, 1286, 1288
- pop\_back function, 582
- pow function, 321–326, 456
- print function, 735, 740, 749, 831, 837, 868, 872, 1076
- printListReverse function, 1071
- printMatrix function, 528–529
- printResult function, 453, 454, 457, 1154, 1158–1161
- printStars function, 364–366
- printTime function, 651, 652, 653, 656, 659, 664
- push function, 1117–1118, 1124–1126, 1142–1144, 1150, 1286, 1288
- push\_back function, 582, 583–584
- rand function, 1258
- rbFibNum function, 999–1003
- read function, 1236
- readln function, 619
- remove function, 1295–1297
- replace function, 463, 467–468, 1295–97
- resize function, 583–584
- reversePrint function, 1069–1071
- rollDice function, 687
- runSimulation function, 1199–1200
- search function, 1044, 1058, 1077, 1297–1299
- seekg function, 1236, 1237–1241
- seekp function, 1236, 1237–1238
- selectionSort function, 571
- seqSearch function, 508–509, 621–622
- setCustomerInfo function, 1187
- setData function, 748, 749, 752, 753
- setDimension function, 733
- setLastName function, 868
- setName function, 868
- setServerBusy function, 1194
- setTime function, 651, 652, 653, 656, 659, 660, 664, 670
- size function, 463, 582, 1286, 1288
- sort function, 1297–1299

- sqrt function, 321, 322
- squareFirst function, 381
- strcmp function, 512, 513
- strlen function, 512
- substr function, 463, 469–470, 964
- sumRows function, 528–529
- swap function, 463, 470
- terminate function, 980
- test function, 392
- testCopyConst function, 828
- testTime function, 658, 659
- tolower function, 322
- top function, 1117–1118, 1126, 1286, 1288
- toupper function, 322
- updateServers function, 1195
- updateWaitingQueue function, 1196
- write function, 1236

**G**

- general case, **992**
- get function, 127–128, 514, 744
- getFirstName function, 868
- getLastName function, 868
- getLength function, 733
- getLine function, 515
- getNumberOfBusyServers function, 1194
- getScore function, 369–370
- getTime function, 651, 652, 653, 659
- getWaitingTime function, 1188
- getWidth function, 733
- grade-calculation programs, 162–165, 369–372
- grade-point average (GPA) program, 1134–1138
- grade-report program, 758–779
- .h filename extension, 682, 1244

**H**

- hardware, overview of, 4–5
- head, use of the term, **1024**
- header file(s), 76, 80, 456, 512
  - control structures and, 224
  - derived classes and, 741–743
  - described, **682**

- functions and, 321
- information hiding and, 682
- inheritance and, 742–744
- input/output (I/O) and, 118, 142, 143
- linked lists and, 1057–1058, 1066–1069
- multiple inclusions of, 735–746
- namespaces and, 452, 458
- naming conventions, 1244–1245
- overview, 1247–1255
- stacks and, 1130–1134, 1148
- templates and, 929
- vectors and, 585
- hexadecimal numbers, 1228–1230
- high-level languages, **9**
- Hollerith, Herman, 2

## I

- IBM (International Business Machines)
  - character sets and, 37
  - encoding schemes and, 8
  - history of, 2–3
- identifiers
  - described, **33**
  - functions and, 382–386
  - global, **382**
  - local, **382**
  - naming, 85–86
  - namespaces and, 452, 455
  - overview, 33–34
  - self-documenting, **86**
- IDEs (integrated development environments)
  - debugging and, 299
  - filename extensions and, 78
  - identifiers and, 34
  - indentation and, 212
  - input/output (I/O) and, 137
  - overview, 11–12
- if statements, 188–212, 952, 1013
  - comparing if...else statements with, 198–199
  - functions and, 334
  - linked lists and, 1070
  - nested, 195, **196**, 197–199
- if...else statements, 198–199
- ignore function, 128–130, 744
- implementation files
  - described, **682**
  - templates and, 929
- implicit type coercion, **47**
- #include preprocessor directive, 75, 81, 512, 744
  - functions and, 322–323
  - input/output (I/O) and, 118
  - string data type and, 458
- increment operators, **65**, 66–67, 1039
- incrementHours function, 651, 652, 664
- incrementMinutes function, 651, 652, 662, 664
- incrementSeconds, 651, 652, 653, 659, 662, 664
- indexes. *See* array indexes
- indirectly recursive, use of the term, **995**
- infinite loops, **250**
- infix notation, **1151**, 1152
- information hiding, 681–685
- inheritance
  - described, **724**
  - hierarchy, 738, 740–741
  - linked lists and, 1037
  - overview, 723–792
  - pointers and, 828–835
- initializeList function, 1045, 1076
- initializeQueue function, 1166, 1171, 1174, 1179, 1181
- initializeStack function, 1118, 1123–1124
- input. *See also* I/O (input/output)
  - devices, **5**
  - failure, **124**, 133, 134–136, 206–207
  - memory allocation and, 50–53
  - overview, 50–65
  - statement, 58–61
  - stream variables, **119**
  - streams, **118**
  - string, 514–515
- input/output (I/O). *See also* input; output
  - c-Strings and, 515–517
  - debugging and, 149–152
  - enumeration types and, 438
  - EOF-controlled while loops and, 263, 264
  - file, 152–165, 516
  - functions and, 321

input/output (*Continued*)

- inheritance and, 744–745
- overview, 1230–1244
- records and, 618, 619
- stream variables, 132–133
- string data type and, 148–152, 458

insert function, 462, 467–468, 1063, 1079–1080

insertFirst function, 1038, 1044, 1049, 1051, 1058, 1064–1065

insertion operator, 515

insertion sort algorithm, 572–576

insertSort function, 575–576

insertLast function, 1038, 1044, 1049, 1058, 1064–1065

instance variables, **663**

int data type, 36–37, 121, 333–335, 364

- arrays and, 508, 809, 810, 813, 815
- control structures and, 187–188
- exception handling and, 957, 960
- inheritance and, 749
- linked lists and, 1025, 1028, 1032
- pointers and, 794, 795, 797, 799, 808
- records and, 616, 625
- templates and, 925–927
- vector objects and, 581

int keyword, 87

integral data type, 35–36, 506

integral expressions, **44**

iomanip header file, 458

iostream header file, 321, 452, 456–455, 458, 743, 744–745

isEmptyList function, 1044

isEmptyQueue function, 1166, 1197

isEmptyStack function, 1118, 1124, 1141–1142

isFullQueue function, 1166, 1179

isFullStack function, 1118, 1124, 1140–1142

islower function, 322

isNumPalindrome function, 338–340

ISO (International Standards Organization), 22

istream member functions, **124**

isupper function, 322

iterative control structures, **1106**, 1107–1014

iterators, **1039**, 1040–1045, 1265–1266, 1284–1289

**J**

Jacquard, Joseph, 2

Jobs, Steven, 3

**K**

keys (items), **565**

keywords. *See also* keywords (listed by name)

- described, **33**
- list of, 1215

keywords (listed by name). *See also* keywords

- class keyword, 651
- const keyword, 51, 658, 659
- do keyword, 285
- extern keyword, 386
- for keyword, 274
- friend keyword, 870
- int keyword, 87
- namespace keyword, 76
- new keyword, 804
- operator keyword, 864
- return keyword, 77, 328
- static keyword, 491, 691
- struct keyword, 613
- this keyword, 865
- throw keyword, 958
- using keyword, 76, 454
- virtual keyword, 830

kilobytes (KB), **6–7**

**L**

larger function, 328–331, 332, 341–343, 925–927

largerChar function, 396

largerInt function, 396

largestInRows function, 528–529

largest-number program, 342–343

left manipulator, 146–148

length function, 462, 463, 464–465

length-conversion program, 91–94

libraries. *See also* STL (C++ Standard Template Library)

- described, **11**
- Standard C++, 458

LIFO (Last In First Out) data structure, **117**, 1120

limits.h (climits) header file, 1250–1251

linked lists. *See also* ordered linked lists; unordered linked lists

- building, 1032–1037
- circular, **1083**, 1084–1103
- containers and, 1279–1284
- copying, 1047–1048
- deleting items in, 1028, 1031–1032
- described, **1024**
- destroying, 1044–1045, 1075
- doubly, 1072–1083
- first/last elements of, 1077–1083
- initializing, 1045, 1076
- inserting items in, 1028–1031
- length of, 1045–1046, 1076
- overview, 1023–1114
- printing, 1045, 1069–1071, 1076–1077, 1161–1165
- properties of, 1025–1031
- searching, 1050–1051, 1059–1060, 1077
- stacks and, 1150–1151, 1161–1165
- traversing, 1044, 1027–1028

linkedList.h header file, 1057–1058, 1067–1069

LinkedListIterator class, 1039–1041

LinkedListType class, 1037–1044, 1048–1049, 1057–1059, 1067, 1150–1151, 1162, 1182

linkedQueueType class, 1181–1182

linkedStack.h header file, 1148

linkedStackType class, 1140–1141, 1147–1149

linkers, **11**

links, between nodes, **1024**, 1025

list class, 1279–1280

list container, 1279–1284

lists. *See also* linked lists

- described, **565**
- processing, 564–580

listType class, 680, 927–929

loaders, **11**

local declaration, **328**

logic errors, 149–152, 964. *See also* errors

logical expressions, **178**, 182–188, 443–444

logical operators, 182–188

logical values, **178**

loop(s). *See also* recursion; *specific types*

- arrays and, 491
- binary search algorithm and, 579, 580
- enumeration types and, 438
- nested, 291–296, 525, 526
- records and, 623
- selection sort algorithm and, 571

loop control variables (LCVs), **250**, 251, 256, 274

## M

machine language, **6**

main function, 31, 78, 80, 124, 324, 369, 381, 456–457, 872–873

- arrays and, 815
- constructors and, 826
- information hiding and, 682
- pointers and, 802
- virtual functions and, 843
- void functions and, 362

main memory. *See* RAM (random access memory)

make command, **686**

math.h (cmath) header file, 1252–1255

max\_size function, 582

member access operator, **133**, 655, 656, 657, 615

member functions

- binary operators as, 876
- common to containers, 1269–1272
- implementation of, 659–663
- operator functions as, 873–876, 896–898, 901–902
- redefining (overriding), 727–734

members, of classes

- accessing, 655–656
- described, **650**
- order of, 667–669
- overview, 650–651
- static, 691–696

memory. *See also* stacks

- addresses, **4**
- allocation, 50–53, 372–382

memory (*Continued*)

- cells, **4**
- data types and, 36
- leaks, **806**, 807
- overview, 4–5
- records and, 613–616
- size, 1257–1258
- menu-driven programs, 388–389
- minus sign (-), 654
- mixed expressions, **45**, 46
- mnemonics, **8–9**
- modular programming, **20**
- modules, **320**. *See also* functions
- movie-ticket-sales program, 156–161
- multidimensional arrays, 518–533. *See also* arrays
- mutator functions, **664**, 665–669
- myStack.h header file, 1130–1134

**N**

- named constants, **51**, 52, 386–390, 461
- namespace keyword, 76
- namespaces, 76, 452–458
- naming conventions, for header files, 1244–1245
- n-dimensional arrays, **532**, 533. *See also* arrays
- new keyword, 804
- new operator, 804–805, 809, 965–966
- newline escape sequence (\n), 69, 71–73, 120, 128, 295
- newString class, 918–824, 930, 952
- node(s)
  - deleting, 1031–1032, 1052–1057, 1065–1066
  - described, **1024**
  - inserting, 1029–1031, 1051–1057, 1060–1064, 1078–1080
  - retrieving the data of, 1046
  - structure of, 1038
- nonmember functions, 873–876, 898–902
- nonrecursive algorithms, 1161–1165
- null character, 510
- NULL nodes, 1026, 1028, 1033–1034, 1044
- null pointers, **803**
- null strings, **49**

- number-classification program, 399–404
- number-guessing game, 260–261

**O**

- .obj filename extension, 77–78
- object(s)
  - arrays of, 675–677
  - declaring, 654–655
  - described, **650**
  - identifying, 757–758
  - programs, **10–11**
  - reference parameters and, 648
- object-oriented design. *See* OOD (object-oriented design)
- object-oriented programming. *See* OOP (object-oriented programming)
- octal number system, conversion to, 1228–30
- one-dimensional arrays, **487**, 491–494, 498, 519, 527, 564. *See also* arrays
- OOD (object-oriented design). *See also* objects
  - abstract classes and, 835
  - basic principles of, 756
  - described, **20**
  - overview, 20–22, 650, 755–758
- OOP (object-oriented programming). *See also* objects
  - described, **21**
  - OOD and, relationship of, 756
  - overview, 755–758
- operands, **40**
- operating system software, **6**
- operations
  - data abstraction and, 679
  - described, **679**
  - identifying, 757–758
- operator(s). *See also* operator overloading; operators (listed by name)
  - arithmetic operators, 39, **40**, 41–44
  - functions, **863**, 864, 873–876, 898–902
  - precedence, 43–44, 85, 184–187, 1217–1218
- operator keyword, 864
- operator overloading
  - linked lists and, 1044, 1049
  - need for, 862–863

- overview, 863–924
- post-increment operator and, 897–901
- pre-increment operator and, 896
- restrictions, 864
- stacks and, 1129–1130, 1147–1149
- stream extraction operator and, 882–887
- stream insertion operator and, 882–887
- table, 1223
- unary operators and, 895–901
- operators (listed by name). *See also* assignment operator; operators
  - address of operator, **795–796**, 844–846
  - array index operator, 916–924
  - array subscript operator, **459**, 488
  - cast operator, **47**
  - conditional operator, **211**
  - delete operator, 804, 805–807
  - dereferencing operator, **796–801**, 1039
  - equality operator, 209–211
  - extraction operator, 119–124, 129, 148
  - insertion operator, 515
  - member access operator, **133**, 655, 656, 657, 615
  - new operator, 804–805, 809, 965–966
  - post-increment operator, 897–901
  - scope resolution operator, 386, 454, 457, **659**, 691
  - stream extraction operator, **59**, 882–887
  - stream insertion operator, 31, **68**, 882–887
- ordered linked lists. *See also* linked lists
  - deleting nodes from, 1065–1066
  - overview, 1058–1069
  - searching, 1059–1060
- orderedLinkedList class, 1043–1044, 1058
- orderedListType class, 1066
- output. *See also* I/O (input/output)
  - devices, **5**
  - formatting, 137–148
  - overview, 67–74, 117–174
  - statements, **68**
  - stream variables, **119**
  - streams, **118**
  - string, 515–516
- overflow condition, **126**
- overflow\_error exception, 964

## P

- palindrome number program, 338–340
- parallel arrays, **537**, 538
- parameter(s)
  - actual, **326**
  - arrays as, 497–498
  - constructors and, 671–675
  - default, 396–399, 738
  - formal, **325–326**, 498–500
  - linked lists and, 1048, 1070–1071
  - passing, to functions, 527–530
  - queues and, 1198
  - reference, **363**, 372–382
  - stacks and, 1155
  - value, **363**, 372–382
- parameterized stream manipulators, **148**
- parameterized types, **927**
- parentheses, 187, 327, 801
- partTimeEmployee class, 724, 740–742, 837, 841–843
- Pascal, Blaise, 2
- patches, 296–299
- PCs (personal computers), history of, 3. *See also* computers
- peek function, 130–132
- period (.), 129, 655
- personallInfo class, 753–755
- personType class, 689–690, 724, 740, 742, 750–751, 837, 867–870
- pig-latin strings, 471–475
- plus sign (+), 654
- pointer variable(s)
  - classes and, 902
  - declaring, 794–795
  - described, **794**
  - initializing, 803
  - operations on, 807–809
  - operators, 795–800
  - structS and, 800–803
- pointers
  - classes and, 800–803, 818–828
  - constant, 811
  - dangling, **807**
  - destructors and, 818–819
  - dynamic variables and, 803–807
  - functions and, 812

pointers (*Continued*)

- inheritance and, 828–835
- linked lists and, 1030–1038, 1044, 1048, 1054–1056, 1060, 1063
- operator overloading and, 865
- overview, 818–828
- shallow versus deep copy and, 816–818
- structS and, 800–803

polymorphism

- described, **756**
- parametric, 757

poolCapacity function, 394

poolFillTime function, 394

pop function, 1117–1118, 1126–1128, 1144–1146, 1286, 1288

pop\_back function, 582

postconditions, **683**

post-increment operator, 897–901

postfix expressions calculator, 1151–1161

posttest loops, **286**

pound sign (#), 145, 257, 880, 1154

pow function, 321–326, 456

precision

- described, **39**
- double, **39**
- single, **39**

preconditions, **683**

predefined functions

- described, **125**
- overview, 31
- using, 124–133

prefix (Polish) notation, **1151**

preprocessors, **10**, 75–76. *See also* #include preprocessor directive

pretest loops, **286**

print function, 735, 740, 749, 831, 837, 868, 872, 1076

printListReverse function, 1071

printMatrix function, 528–529

printResult function, 453, 454, 457, 1154, 1158–1161

printStars function, 364–366

printTime function, 651, 652, 653, 656, 659, 664

private members, 651–655, 663, 667–669, 681

- address of operator and, 844, 846
- friend functions and, 870, 871–872
- inheritance and, 725–727, 732, 734, 746–747
- linked lists and, 1043, 1044

problem analysis-coding-execution cycle, 12–20

program(s). *See also* programming;

- programming languages
- basic elements of, 28–34
- creating, overview of, 77–80
- described, **28**
- form, 84–89, 211–212
- overview, 6
- processing, overview of, 10–12
- source, **10**
- style, 84–89, 211–212
- terminating, 223–231, 978, 980

programming. *See also* programs

- described, **28**
- methodologies, 20–22
- structured, **20**

programming languages. *See also* programming

- described, **31**
- evolution of, 8–9
- overview, 1–26

prompt lines, 86

protected members, 651, 654, 870

- inheritance and, 725, 746–750
- linked lists and, 1043

prototypes, **331**, 332–333, 397, 398, 877, 881, 884, 896–899

pseudocode

- described, **212**
- linked lists and, 1070
- overview, 212–215
- stacks and, 1154, 1157

public members, 651–655, 667–669, 691, 694

- friend functions and, 870
- inheritance and, 725–727, 731–732, 746–747

push function, 1117–1118, 1124–1126, 1142–1144, 1150, 1286, 1288

push\_back function, 582, 583–584

## Q

queue(s)  
 application of, 1183–1203  
 back of, **1165**, 1166  
 described, **1165**  
 empty, 1174, 1178–1179  
 front of, **1165**  
 full, 1174, 1178–1179  
 implementation of, 1168–1174,  
 1177–1182  
 initializing, 1174, 1179  
 operations, 1166–1167  
 overview, 1165–1183  
 STL and, 1287–1289  
 queueADT class, 1167, 1172, 1177–1178  
 queueType class, 1196  
 queuing systems, **1184**, 1185

## R

RAM (random access memory), **4**, **5**. *See also* memory  
 rand function, 1258  
 RAND\_MAX value, 1258  
 random file access, 1236–1244  
 random number generators, memory size on,  
 1257–1258  
 raw data, **1230**  
 rbFibNum function, 999–1003  
 read function, 1236  
 readln function, 619  
 Rebuild command, 12, **686**  
 records. *See also* StructS  
 arrays and, 619–624  
 assignment statements and, 616–617  
 overview, 611–648  
 rectangle class, 725, 835–837  
 rectangleType class, 728–731, 734–736, 738,  
 874–888, 895–902  
 recursion  
 described, **992**  
 direct, **995**  
 indirect, **995**  
 infinite, 995–996  
 iteration and, 1006–1014  
 linked lists and, 1069–1071

overview, 991–1021  
 problem solving using, 996–1006  
 removing, 1161–1165  
 stacks and, 1161–1165  
 recursive algorithms  
 described, **993**  
 problem solving using, 996–1006  
 recursive definitions  
 described, **992**  
 overview, 992–996  
 recursive functions  
 described, **993**  
 infinite recursion and, 995–996  
 overview, 993–995  
 reference variables, as parameters, 368–372  
 relational operators, 201–203, 437–438  
 described, **178**  
 overview, 177–182  
 records and, 617–618  
 remove function, 1295–1297  
 repetition structures. *See also* loops  
 need for, 248–249  
 overview, 176–177, 247–318  
 replace function, 463, 467–468, 1295–97  
 reserved words. *See* keywords  
 resize function, 583–584  
 return keyword, 77, 328  
 return statement, 208, 324, 327–331,  
 333–335  
 return type, of functions, 326, 877  
 Reverse Polish notation, **1151**  
 reversePrint function, 1069–1071  
 right manipulator, 146–148  
 rightmost bit, **1011**  
 “rock, paper, and scissors” game, 444–452  
 rollDice function, 687  
 row(s)  
 arrays and, 523, 525  
 largest element in, 526  
 order form, **527**  
 processing, **523**  
 sum by, 525  
 runSimulation function, 1199–1200  
 run-time (late binding), **830**  
 run-together words, **86**

**S**

- sales data analysis program, 628–641
- scope resolution operator, 386, 454, 457, **659**, 691
- search function, 1044, 1058, 1077, 1297–1299
- searching. *See also* search function
  - arrays, for specific items, 507–510
  - lists, 564–565
- secondary storage, **5**
- seekg function, 1236, 1237–1241
- seekp function, 1236, 1237–1238
- selection sort algorithm, 569, 570–572
- selection structures
  - multiple, 195–199
  - one-way, 189–191
  - overview, 176–177, 188–212
  - two-way, 191–184
- selectionSort function, 571
- selectors, **215**
- semantic(s)
  - described, **85**
  - errors, 194
  - rules, **31**
- semicolon (;), 85, 651, 836
- sentinel(s), 257, 259
  - controlled while loops, **255**, 256
  - described, **255**
- seqSearch function, 508–509, 621–622
- sequence containers, 1260–1269, 1271–1272, 1276–1284
- sequence structures, 176–177
- sequential search algorithm, **507**, 508–510, 564–565, 621–622
- serverListType class, 1192–1194
- servers
  - described, **1184**
  - lists of, 1191–1195
  - queues and, 1184–1185, 1188–1191, 1198–1199
- serverType class, 1188–1191
- setCustomerInfo function, 1187
- setData function, 748, 749, 752, 753
- setDimension function, 733
- setfill manipulator, 144–146
- setLastName function, 868
- setName function, 868
- setprecision manipulator, 137–138, 140–141
- setServerBusy function, 1194
- setTime function, 651, 652, 653, 656, 659, 660, 664, 670
- setw manipulator, 142–144, 146
- shallow copy, 816, **817**, 818
- shape class, 725, 835–837
- short-circuit evaluation, **199**, 200
- showpoint manipulator, 139–142
- side effects, 386–390
- simple data types, **53**, 433–483, 486
- simulation example, 1183–1203
- single inheritance, **725**
- size function, 463, 582, 1286, 1288
- slicing problem, **834**
- software. *See also* programs
  - operating system, **6**
  - overview of, 6
- sort function, 1297–1299
- source
  - code, **10**, 77
  - file, **77**
  - program, **10**
- sqrt function, 321, 322
- square brackets ([ ]), 495
- squareFirst function, 381
- stack(s)
  - container adapters and, 1286
  - copying, 1128, 1146–1147
  - described, **1116**
  - emptying, 1124, 1141–1142
  - full, 1124, 1141–1142
  - implementation of, as arrays, 1120–1138
  - initializing, 1123–1124
  - linked implementation of, 1138–1151
  - operations, 1118–1119
  - overview, 1116–1165
  - recursion and, 1161–1165
  - top element of, returning to, 1144
- stackADT class, 1119, 1120, 1139–1140, 1142
- stackType class, 1120–1123, 1129–1134
- Standard C++
  - library, 458
  - naming conventions for header files, 1244–1245

- statement(s)
    - action, **189**
    - declaration, **78**
    - executable, **78**
    - nested, 195, **196**, 197–199, 280
    - terminators, **85**
  - static binding. *See* compile-time binding
  - static keyword, 491, 691
  - static members, of classes, 691–696
  - std:: prefix, 455
  - stddef.h (cstddef) header file, 1253
  - stepwise refinement, **20**
  - STL (C++ Standard Template Library), 585, 1259–1299
    - algorithms and, 1289–1292
    - components of, 1259–1260
    - containers and, 1260–1284
    - vectors and, 1260–1269
  - strcmp function, 512, 513
  - stream(s)
    - classes, 744–745
    - described, **118**
    - extraction operator, **59**, 882–887
    - functions, 124
    - insertion operator, 31, **68**, 882–887
    - variables, **119**, 373
  - string(s). *See also* string data type
    - arrays of, 530–531
    - comparison, 512–513
    - described, **49**
    - output, 515–516
    - pig-latin, 471–475
    - reading, 60–61, 513
    - writing, 513
  - string data type, 49–50, 76, 148–152, 180–182. *See also* strings
    - functions, list of, 462–463
    - overview, 458–470
    - templates and, 927
  - string.h (cstring) header file, 470, 512, 516, 517, 918, 1253–1255
  - strlen function, 512
  - struct(S). *See also* records
    - arrays and, 619–624
    - assignment statements and, 616–617
    - classes versus, 680–681
    - described, **612**
    - linked lists and, 1038
    - overview, 611–648
    - pointer variables and, 800–803
    - structS within, 624–627
    - syntax of, 612–613
    - variables and, 618–622
  - struct keyword, 613
  - struct members, 614–616
  - structured data types, **486**
  - structured design, **20**
  - structured programming, **20**
  - structures. *See also specific types*
    - choosing the right, 289
    - switch, **215**, 216–223
    - testing, 212–215
  - substr function, 463, 469–470, 964
  - sumRows function, 528–529
  - swap function, 463, 470
  - switch statement, 439–440
  - switch structures, **215**, 216–223
  - syntax errors, 80–84, 133, 396. *See also*
    - debugging; errors; syntax rules
    - control structures and, 215
    - fixing, 80–84
  - syntax rules, **31**, 84–85. *See also* syntax errors
  - system programs, **6**
- ## T
- tabs, 120
  - tail recursive functions, **995**
  - telephone-digit program, 257–259
  - templates, **862**, 925–935. *See also* STL (C++ Standard Template Library)
  - terminate function, 980
  - ternary operators, **211**
  - test function, 392
  - testAddress class, 845, 846
  - testCopyConst function, 828
  - testing, of control structures, 212–215
  - testTime function, 658, 659
  - text processing program, 540–547
  - this keyword, 865
  - this pointer, 865–870, 895
  - throw keyword, 958

tilde (~), 677  
 time-driven simulation, **1184**  
 tokens, **32–33**, 34  
 tolower function, 322  
 top, of stacks, **116**  
 top function, 1117–1118, 1126, 1286, 1288  
 top-down design, **20**  
 toupper function, 322, 323  
 Tower of Hanoi problem, 1003–1006  
 transaction time, **1184**, 1185, 1194–1195  
 try/catch blocks, 956–963, 964–965, 967, 973–977, 979, 980–983  
 two-dimensional arrays. *See also* arrays  
   accessing components of, 530  
   declaration of, 521, 531–532  
   described, **519**  
   dynamic, 813–815  
   enumeration types and, 521–524  
   initialization of, 521, 524–525  
   overview, 518–533  
   passing, as parameters to functions, 527–530  
   printing, 525  
   processing, 523  
 type conversion (casting), **47**, 48–49, 671  
 type name, **679**  
 typedef statement, 443

## U

UML (Unified Modeling Language), **654**. *See also* UML class diagrams  
 UML class diagrams, 654, 680, 689–690, 728–731, 740–741, 752, 754  
   linked lists and, 1040, 1043, 1050, 1059, 1074  
   queues and, 1186–1187, 1190, 1193  
   stacks and, 1119, 1121–1122, 1140  
 unary operators, **40**, 895–901  
 underflow condition, **1128**  
 underscore (\_), 33, 34, 86, 453  
 Unicode, 8  
 UNIX, 265  
 unordered linked lists. *See also* linked lists  
   header files and, 1057–1058  
   overview, 1049–1058  
   queues and, 1182–1183

  searching, 1050–1051  
   stacks and, 1150–1151  
 unorderedLinkedList class, 1043–1044, 1049–1050, 1090, 1150–1151  
 unorderedListedType class, 1182–1183  
 updateServers function, 1195  
 updateWaitingQueue function, 1196  
 user-defined functions, 324  
 using keyword, 76, 454  
 using statement, 454–455, 456

## V

value parameters, 367–368  
 value-returning function(s)  
   calls, 326  
   described, **324**  
   overview, 324–343  
   return statements and, 327–331  
 variable(s)  
   automatic, **391**, 392  
   declaring, 57–58, 442, 654–655  
   described, **52**  
   dynamic, 803, **804**, 805–807  
   enumeration types and, 436  
   external, **386**  
   functions and, 372–382  
   global, 386–390, 391  
   initialized, **53**, 57–58, 61–65  
   local, **372**  
   memory allocation and, 50–53  
   putting data into, 53–56  
   records and, 613–622  
   static, **391**, 392  
 vector class, 1260–1269  
 vector objects, declaring, 581–583  
 vector type, 580–585  
 vectors, **581**, 582–585, 1260–1269  
 video store program, 1084–1103  
 videoListType class, 1090–1092, 1095–1097  
 videoType class, 1087–1089, 1092–1094  
 virtual destructors, **835**  
 virtual functions, 828–829, **830**, 834–835  
 virtual keyword, 830  
 void functions, **324**, 362–366, 660, 677

**W**

- waitingCustomerQueueType class, 1196–1197
- walk-throughs, **56**, 65, 214, 292
- while loops
  - binary search algorithm and, 579, 580
  - counter-controlled, 252, 253–255
  - described, **249**
  - designing, 251–252
  - EOF-controlled, **263**, 264–268, 294–295
  - expressions in, 268–269
  - Fibonacci numbers and, 269, 270–273
  - flag-controlled, **259**, 260, 268
  - functions and, 366
  - nested, 293
  - overview, 249–284
  - sentinel-controlled, **255**, 256
- whitespace, 34, 120, 129, 149
- Wozniak, Stephen, 3
- write function, 1236